
	NORMAL CHECKLIST DA40NG LN-FTQ	Rev.01 15.10.2019
---	---	----------------------

BEFORE START		
1	A/C doc. / Pre-flight / Pax brief	COMPLETED
2	Pitot cover / Chocks / Control lock	RMWD
3	Rudder pedals	ADJUSTED
4	Seatbelts	CHKD / FASTENED
5	Parking brake	LCKD
6	Front canopy	POS 1 OR 2
7	Rear door	CLSD & LCKD
8	Before start flow check	COMPLETED
9	Electric master	ON
10	Engine fire on ground	BRIEFED
11	Flight controls	CHKD
12	G1000	POWERED & ACK.
13	Fuel	CHKD / SET
14	Fuel temperature	CHKD
15	Position lights	ON
16	Engine master	ON
17	Annunciations	CHKD
18	Start key	START
AFTER START		
1	Annunciations / Engine instruments	CHKD
2	RPM 710 +/-30	CHKD
3	Avionic master	ON
4	Flaps	CHKD / AS REQ
5	Pitot heat	CHKD
6	ATIS	RECEIVED
7	Stand-by instruments	CHKD
8	Altimeters	SET & CHKD
9	Clearance	RECEIVED
10	Instrument setup/Nav. aids	DONE/SET & IDENT
TAXI		
1	Brakes	CHKD
2	Flight instruments	CHKD
BEFORE TAKE-OFF		
1	Parking brake	AS REQ
2	Annunciations	CHKD
3	Engine instruments normal rang	CHKD
4	Circuit breakers	CHKD
5	Flaps	AS REQ
6	Trim	SET T/O
7	Fuel valve	NORMAL
8	Power lever	IDLE
9	ECU-test	COMPLETED
10	Voter switch A&B	CHKD / AUTO
11	Depart. brief/Take-off consid.	GIVEN/BRIEFED
12	Emergency brief	GIVEN
13	Transponder	CHKD

	NORMAL CHECKLIST DA40NG LN-FTQ	Rev.01 15.10.2019
---	---	----------------------

LINE UP		
1	Lights	AS REQ
2	Fuel pumps	ON
3	Front canopy / Windows	POS 1 / CLSD &
4	Compass / HDG bug	CHKD / SET
5	Pitot heat / Alternate air	ON / AS REQ
AFTER TAKEOFF		
1	Lights	AS REQUIRED
2	Fuel pumps	OFF / AS REQ
3	Flaps	UP
4	Cruise power	SET
5	Engine instruments	CHKD
APPROACH / BEFORE LANDING		
1	ATIS / Weather information	RECEIVED
2	Nav. aids/Approach brief	SET & IDENT/GIVEN
3	Altimeters	SET & XCHKD
4	Seat belts	CHKD / FASTENED
5	Fuel valve	NORMAL
4	Parking brake	RELEASED
5	Fuel pumps	ON
6	Lights	AS REQ
AFTER LANDING (RWY vacated)		
1	Flaps	UP
2	Pitot heat / Alternate air	OFF
3	Fuel pumps	OFF
4	Lights	AS REQ
PARKING		
1	Parking brake	AS REQ
2	Power lever	IDLE (1 MIN)
3	Transponder	7000
4	Avionic master	OFF
5	Engine master	OFF
5	Lights	OFF
7	Electric master	10 SEC – OFF
8	Interior light	OFF