CARPET INSTALLATION Checklist

Rolled Carpet

- [ ] Remove existing flooring, nails, tacks
- [ ] Repair any cracks or holes in the subfloor
- [ ] Remove doors and baseboards
- [ ] Nail tack strips to the subfloor around the edge of the room
- [ ] Tack the carpet pad to the subfloor
- [ ] Use masking tape to connect the strips of carpet padding
- [ ] Add 4–6 in. to longer wall measurement
- [ ] Measure the roll of carpet to match the longer wall
- [ ] Chalk a line on back of carpeting at this measurement
- [ ] Cut the carpet roll to the measured length
- [ ] Place the cut section of carpet in the room w/ overlap
- [ ] Stretch the carpet tight
- [ ] Hook tightened carpet to the tack strips
- [ ] Trim the extra carpeting along the base of the walls
- [ ] Reinstall the baseboards and doors

ROLLED

Angi

CARPET INSTALLATION Checklist

Self-Stick Carpet Tile

- [ ] Remove any existing carpet, flooring, nails, and tacks
- [ ] Repair any cracks or holes in the subfloor
- [ ] Remove doors and baseboards
- [ ] Use the tape measure to find the center of the room
- [ ] Dry lay 4 square tiles around the center point
- [ ] Dry-lay a line of single tiles until you reach the wall
- [ ] Adjust center point if last tile to wall must be cut +50%
- [ ] Repeat in other directions
- [ ] Install on subfloor outward from center point
- [ ] Cut tiles along the wall as needed
- [ ] Use a heavy carpet roller to ensure adhesion
- [ ] Reinstall the baseboards and doors

SELF-STICK

Angi