Typical Exterior Walls - Tod	ay's Minimum Requirements
Face Brick	0.39
Air Space	2.02
Air & Vapor Barrier	0.15
1/2" Gypsum Sheathing	0.45
Insulation	22.00
Vapor Barrier	0.15
Interior Gypsum Board	0.45
TOTAL R-VALUE	25.61
WINDOW TRIPLE PANE R-VALUE	5.00

Physical Conditions of Exterior Envelope - Windows

The windows are replacement double hung aluminum windows with double pane glazing. The windows are in good condition and should have routine maintenance to keep them operational.

Physical Conditions of Exterior Envelope - Roof

The roofing is membrane and is in good condition. No active leaks or damage was observed.

McCall Existing	Roof Condition
Rubber Membrane	0.40
3" Insulrock Insulation	7.00
Structure/Ceiling	5.00
TOTAL R-VALUE	12.40

Roof Construction - Tod	ay's Minimum Standard
Rubber/PVC	0.40
4" Polyisocyanurate	30.00
Structure/Ceiling	5.00
TOTAL R-VALUE	35.40

Interior

Finishes are well suited for school use, but are showing signs of wear in some areas; some replacement is warranted.

Interior Partitions

In general, all interior partitions appear to be in good condition. The type of partition varies throughout the building as follows:

- Painted concrete masonry units
- Painted plaster
- Painted drywall
- Painted brick

Flooring

In general, the flooring is VCT and some minor damage is occurring in multiple locations. The existing flooring consist of the following types:



Brick at exterior of building



Cafeteria

- Vinyl Composition tile (12x12)
- Wood floor at gymnasium

Wall Base

The wall base is rubber of various sizes. All base material appear to be in good condition.

Ceilings

The ceilings are a combination of 2x4 acoustical tile and plaster. They are generally in good condition although the gym ceiling is missing tiles that should be replaced. The existing ceilings consist of the following types:

- Suspended Acoustical tile
- Plaster

Doors and Frames

Doors are generally wood and many are chipped. The conditions are good. Doors have lever handle hardware that meet accessibility guidelines.

Fire Extinguishers

Fire extinguishers meet code.



School roof



Gymnasium

Tackboards and Markerboards

Tackboards and markerboards are existing throughout and appear to be in good condition. Fire code regulations do not allow for tackboards to be within 5 feet of egress doors.

Regulations

The existing facility as a whole is in compliance with the original code, however, this does not mean it meets every standard of the current code. In accordance with the current code, an existing building is presumed to have met the codes and regulations in effect at the time of its construction and is allowed to continue in its use, provided it is maintained per the original code. Current building codes are applicable to any alteration or addition or change in use of the structure in accordance with 780 CMR 34.

Code Classification 780 CMR 302.1

The occupancy of the facility is non-separated mixed use with assembly and educational uses as follows:

Classrooms, Offices E-Educational Auditorium A3-Assemble

Construction Classification

Based upon the definitions in the current code, the minimum classification of the building is as follows:

3B Noncombustible

Chapter 34: Repair, Alteration, Addition and Change of Use of Existing Buildings

A renovation project is governed by Chapter 34. This chapter is "intended to maintain or increase public safety, health, and general welfare, without requiring full compliance with the code for new construction."

- i. Building renovation For continuation of the same use groups the building shall comply with 780 CMR 3404.0.
- ii. New Building Systems Any new building system or portion thereof shall conform to 780 CMR for new construction to the fullest extent practical.
- iii. Alterations and Repairs Alternations of repairs to existing buildings, which maintain or improve the performance of the building may be made with like material, unless required otherwise under 780 CMR 3408 Structural Requirements for Existing Buildings.
- iv. Number of Means of Egress Egress for the existing facility is sufficient in accordance with the current building code.
- v. Capacity of Exits There is sufficient egress capacity to meet current codes at the doors throughout the facility.
- vi. Length of Access Travel Shall not exceed 200 feet, in building without a sprinkler system. All areas of the existing building are within 200 feet of an exit.
- vii. Exit Signs and Lights For notes on the existing system, refer to the Electrical Existing Conditions Report.
- viii. Means of Egress Lighting Refer to the Electrical Existing Conditions Report.
- ix. Height and Area Limitations Under Chapter 34, the building is in conformance with applicable height and area limitations, so long as there is no change in use. Additions may be made to the structure.
- x. Fire Protection Systems Fire protections systems must be provided for existing building that are "substantially" altered or "substantially" renovated where required for the specific use group.
- xi. Enclosure of Stairways open egress stairways are prohibited. There shall be no minimum fire resistance rating required for an existing enclosure of a stairway.
- xii. Assembly Use Groups Any alteration within an assembly use group shall comply with the code for new construction. This applies to the cafeteria, auditorium and gymnasium

- xiii. Accessibility for Persons with Disabilities Accessibility for persons with disabilities shall be provided in accordance with the regulations of the Architectural Access Board.
- xiv. Energy Provisions for Existing Buildings Alterations to components affecting energy conservation performance shall comply with 780 CMR 13 generally, and 780 CMR 1304.2 or 780 CMR 1304.5 or 780 CMR 1309 specifically. Existing components may remain.
- xv. Evaluation of Existing Building The structural engineer shall make a structural evaluation of the existing building to determine the adequacy of all structural systems that are affected by alteration or damage to be repaired.
- xvi. Existing Lateral Load Capacity (Refer to Structural Existing Conditions Report for further information) Alterations shall not be make to elements or systems contributing to the lateral lad resistance unless the altered lateral load resisting system conforms to 780 CMR 1611.0 and 1612.0; or there is no reduction in the lateral capacity to the building as a whole. Existing elements of systems may be reinforced or replaces with new elements or systems of equivalent strength and stiffness.
- xvii. Earthquake Loads (Refer to Structural Existing Conditions Report for further information) For no change in use groups, but alterations exceeding 50% of the assessed valuation of the building, the project is defined as Seismic Hazard Category 2.
- xviii. Earthquake resistance shall comply with the requirements of 780 CMR 3408.3.5
- xix. The provisions of 780 CMR 34 govern Fire Resistant Materials Fire resistance construction systems.

Interior Finishes 780 CMR 8

Interior trim and finishes altered as a part of a renovation shall conform to the requirements of 780 CMR 801. Flame spread of Interior Finishes for the E and A-3 use Groups, shall conform to Table 803.4. Existing finishes are code compliant.

The State Fire Marshall introduced regulations in 2003 restricting display of paper in egress areas. The provisions are as follows:

- i. Paper display in classrooms shall not exceed 20% of the wall area. Measurement of wall area shall include windows and doors.
- ii. Paper display in corridors shall not exceed 10% of the wall area and shall not be placed within 5 feet of an egress door. It shall be applied directly to the wall and shall not be grouped in areas bigger than 6 feet by 12 feet.

Handicap Accessibility

The building complies with Massachusetts Architectural Access Board (MAAB) regulations.

Mechanical Engineering

Overall the McCall Middle School systems are in good condition. The school was renovated in 2000. The last addition was completed in the summer of 2009. The mechanical, electrical and fire protection systems are generally working well. Systems have received normal maintenance.

2.5 | Muraco Elementary School

Landscape Architecture

Civil Architecture

Architecture

Structural Engineering

Mechanical Engineering

Electrical Engineering

Plumbing Engineering

Fire Protection

Data/Communications



Unofficial Property Record Card - Winchester, MA

General Property Data

Parcel ID 11 192 0 Prior Parcel ID -Mailing Address 33 BATES

Mailing State MA

Zip 01890

Account Number

Property Use MUNICPL tecent Sale Date 2/6/1963 Legal Reference N/A
Grantor MURACO SCHO Sale Price 0 Land Area 11.020 a

Current Property Assessment

Card 1 Value Building Value 24,099,700 Land Value 737,000 **Building Description** Building Style SCHOOL
of Living Units 1
Year Built 1960
Building Grade VERY GOOD
Building Condition Good

Finished Area (SF) 53414,5 # of 3/4 Baths 0

Foundation Type CONCRETE
Frame Type WOOD
Roof Structure FLAT
Roof Cover TAR+GRAVEL
Siding BRICK
Interior Walls DRYWALL # of Bedrooms 0 # of 1/2 Baths 6


Flooring Type CARPET
Basement Floor N/A
Heating Type FORCED H/A
Heating Fuel GAS
Air Conditioning 0% # of Bsmt Garages 0 # of Full Baths 0

Total Value 24,836,700

Legal Description

Narrative Description of Property

his property contains 11.020 acres of land mainly classified as MUNICPL with a(n) SCHOOL style building, built about 1960 , having BRICK exterior and TAR+GRAVEL roof cover, with 1 unit(e), 20 room(e), 0 bedroom(e), 0 bath(e), 6 half bath(e) **Property Images**





Disclaimer: This information is believed to be correct but is subject to change and is not warranteed.



	SPACE SUMMARY			
	Room Type	Room NFA	# of Rooms	Area Total
	CORE ACADEMIC SPACES	ROOM NEA	J# 01 ROURS	Area Total
23	3 23	21036		
36 37	Classroom Classroom	958 1210		
23	Classroom	811	1	
25	Classroom	852		
24	Classroom	1016		
38	Classroom Classroom	807 887	1	
30	Classroom	883	1	
44	Classroom	960	1	
42 43	Classroom Classroom	811 1175	1	
29	Classroom	848		
15	Classroom	827	1	
11	Classroom	827		
9 16	Classroom Classroom	785 1021		
30	Classroom	1036		
31	Classroom	786	1	
17	Classroom	791	1	
6	Kindergarten Kindergarten	1137 1433	1	
10	Kindergarten	1016		
8	Storage	159		
	SPECIAL EDUCATION			
9	9 10	2762	10	
40	ELL	442	1	
13	ОТ	447		
61 27	Sped Classroom Speech	871 445		
39	Storage	159		
12	Storage	143	1	
26	Storage	152		
41	Toilet Toilet	35 34		
14	Toilet	34		
	ART & MUSIC	1237	2	ı
60	Art	859		
49	Music	378	1	
	VOCATIONS & TECHNOLO	cv		
-	0 0	0	0	
	HEALTH & PHYSICAL EDU			
70	4 4	CATION 4317 4048		
70 71	4 4 Multi-Purpose Room Storage	4317 4048 132	1	
70 71 M-07	4 4 4 Multi-Purpose Room Storage Storage	4317 4048 132 76	1 1 1	
70 71 M-07	4 4 Multi-Purpose Room Storage	4317 4048 132	1	
70 71 M-07	4 4 4 Multi-Purpose Room Storage Storage	4317 4048 132 76	1 1 1 1 1 1	
70 71 M-07 67	4 Multi-Purpose Room Storage Storage Storage MEDIA CENTER	4317 4048 132 76 61	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	
70 71 M-07 67	4 4 Multi-Purpose Room Storage Storage Storage Storage MEDIA CENTER	4317 4048 132 76 61	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	
70 71 M-07 67	4 Multi-Purpose Room Storage Storage Storage MEDIA CENTER	4317 4048 132 76 61	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	
70 71 M-07 67	4 4 4 4 4 Multi-Purpose Room Storage Storage Storage MEDIA CENTER 1 Library 1	4317 4048 132 76 61	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	
70 71 M-07 67	4 4 4 4 Multi-Purpose Room Storage Storage Storage Storage Storage Storage Dibrary 1 1 Library 1 1 Library 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	4317 4048 1322 76 61 2361 2361	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	
70 71 M-07 67	4 4 4 4 Multi-Purpose Room Storage Storage Storage Storage 1 1 1 Library DDINING & FOOD SERVICE	4317 4048 1322 76 61 2361 2361	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	
70 71 M-07 67	4 4 4 Whiti-Purpose Room Storage Storage Storage MEDIA CENTER 1 1 1 Library DINING & FOOD SERVICE 0 0 0 0	4317 40484 132 76 61 2361 2361	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	
70 71 M-07 67	4 4 4 4 Multi-Purpose Room Storage Storage Storage MEDIA CENTER 1 1 1 Library DINING & FOOD SERVICE 0 0 0 ADMINISTRATION & GUIDA	4317 4048 1328 76 61 2361 2361	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	
70 71 M-07 67	4 4 4 4 4 Multi-Purpose Room Storage Storage Storage Storage Storage Storage 1 Library 1 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	4317 40484 132 76 61 2361 2361	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	
70 71 MH-07 67 48	4 4 4 4 4 4 Multi-Purpose Room Storage Storage Storage Storage Storage DIMPER 1 1 Library DIMING & FOOD SERVICE 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	4317 4048 4048 1323 76 61 2361 2361 0 0 NCE 2439 516	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	
70 71 M-07 67 48	4 4 4 4 Multi-Purpose Room Storage Storage Storage MEDIA CENTER 1 1 1 Library 0 DINING & FOOD SERVICE 0 0 0 ADMINISTRATION & GUIDLE 7 Administration Counciling Faculty Room	4317 40484 132 76 61 2361 2361 0 0 NCE 2439 516 413	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	
70 71 M-07 67 67 48 (52 51 50 57	4 4 4 4 4 Multi-Purpose Room Storage Storage Storage Storage MEDIA CENTER 1 1 Library DINING & FOOD SERVICE 0 0 0 4 4 MINISTRATION & GUIDA 7 7 4 Administration Counciling Faculty Room Office	4317 4048 4048 13236 61 2361 2361 0 0 NCE 2439 516 4131 477 4055	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	
70 71 M-07 67 48	4 4 4 4 Multi-Purpose Room Storage Storage Storage MEDIA CENTER 1 1 1 Library 0 DINING & FOOD SERVICE 0 0 0 ADMINISTRATION & GUIDLE 7 Administration Counciling Faculty Room	4317 40484 132 76 61 2361 2361 0 0 NCE 2439 516 413	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	
70 71 M-07 67 48	4 4 4 4 4 Multi-Purpose Room Storage Storage Storage MEDIA CENTER 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	4317 40484 40184 40184 40184 40184 40184 40184 40184 40184 405 405 405 405 405 405 405 405 405	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	
70 71 M-07 67 48	4 4 4 Wulti-Purpose Room Storage Storage Storage MEDIA CENTER 1 1 1 Library DINING & FOOD SERVICE 0 0 0 ADMINISTRATION & GUIDA 7 7 Administration Counciling Faculty Room Office Principal's Office Reception Storage	4317 40484 40184	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	
70 71 M-07 67 48	4 4 4 4 4 Multi-Purpose Room Storage Storage Storage Storage Storage Storage Storage Storage MEDIA CENTER 1 1 Library DINING & FOOD SERVICE 0 0 0 4 4 5 5 5 5 5 5 5 5 6 5 6 5 6 6 6 7 7 7 7 7	4317 40484 40184	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	
70 71 M-07 67 48 48 (1) 552 551 550 557 22A 22 4	4 4 4 4 4 4 Multi-Purpose Room Storage Storage Storage Storage Storage Storage Storage MEDIA CENTER 1 1 1 Library DINING & FOOD SERVICE 0 0 0 4 MEDICAL 0 0 0 0 4 Administration & GUIDA 7 7 7 Administration Counciling Faculty Room Office Principal's Office Reception Storage CUSTODIAL & MAINTENAN 6 CUSTODIAL & MAINTENA	4317 40484 40848 1323 76 61 2361 2361 2361 0 0 0 NCE 2439 5164 413 477 4050 200 264 164 164 ICE	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	
70 71 M-07 67 48 48 (1) 552 551 550 557 2A 44	4 4 4 4 4 Multi-Purpose Room Storage Storage Storage MEDIA CENTER 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	4317 40484 40184 4	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	
70 71 M-07 67 48 48 (1) 552 51 550 557 22A 2 4	4 4 4 4 4 Multi-Purpose Room Storage Storage Storage Storage MEDIA CENTER 1 1 1 Library DINING & FOOD SERVICE 0 0 0 ADMINISTRATION & GUIDA 7 7 Administration Counciling Faculty Room Office Principal's Office Reception Storage CUSTODIAL & MAINTENAN 6 6 Cust. Cust.	4317 40484 40184 4	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	
70 71 M-07 67 48 48 (1) 552 551 550 557 2A 44	4 4 4 4 4 Multi-Purpose Room Storage Storage Storage MEDIA CENTER 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	4317 40484 40184 4	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	
70 71 M-07 67 48 48 52 55 55 50 57 2A 44	4 4 4 4 4 4 Multi-Purpose Room Storage Storage Storage Storage MEDIA CENTER 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	4317 40484 40184 4	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	
70 71 M-07 67 48 48 52 55 55 50 57 2A 44	4 4 4 4 Multi-Purpose Room Storage Storage Storage Storage MEDIA CENTER 1 1 1 Library DINING & FOOD SERVICE 0 0 0 ADMINISTRATION & QUIDA 7 Administration Councilling Faculty Room Office Principal's Office Reception Storage CUST QUISA Cust.	4317 40484 40184 4	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	
70 71 M-07 67 48 48 52 55 55 50 57 2A 44	4 4 4 4 Multi-Purpose Room Storage Storage Storage Storage MEDIA CENTER 1 1 1 Library DINING & FOOD SERVICE 0 0 0 ADMINISTRATION & GUIDA 7 Administration Counciling Faculty Room Office Principal's Office Reception Storage CUSTODIAL & MAINTENAN 6 Cust.	4317 4048 4048 1022 76 61 61 2361 2361 0 0 0 .NCE 2439 5164 413 4777 4055 200 2644 164 ICE 1012 49 68 57 401 401 181	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	
70 71 M-07 67 48 48 (1) 52 51 552 51 550 57 2A 44 45 65 63 62	4 4 4 4 4 Multi-Purpose Room Storage Storage Storage Storage Storage Storage Storage Storage MEDIA CENTER 1 1 1 Library DINING & FOOD SERVICE 0 0 0 4 MEDICAL 0 0 0 0 4 MEDICAL 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	4317 40484 40184 4	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	
70 71 M-07 67 48 48 (1) 52 51 552 51 550 57 2A 44 45 65 63 62	Multi-Purpose Room Storage Storage Storage Storage MEDIA CENTER I	4317 40484 40188 40188 40188 40188	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	
70 71 M-07 67 48 48 (1) 52 51 552 51 550 57 2A 44 45 65 63 62	Multi-Purpose Room Storage Storage Storage Storage MEDIA CENTER Library DINING & FOOD SERVICE O ADMINISTRATION & GUIDA Administration Councilling Faculty Room Office Principal's Office Reception Storage CUSTODIAL & MAINTENAN 6 Cust. Cu	4317 4048 4018 4018 4018 4018 4018 4018 4018	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	
70 71 M-07 67 48 48 66 67 67 68 69 69 69 69 69 69 69 69 69 69 69 69 69	4 4 4 4 4 Multi-Purpose Room Storage Storage Storage Storage MEDIA CENTER 1 1 1 1 Library DINING & FOOD SERVICE 0 0 0 MEDICAL 0 0 0 ADMINISTRATION & GUIDA/7 7 Administration Counciling Faculty Room Office Principal's Office Reception Storage CUSTODIAL & MAINTENAN 6 6 Cust. Cu	4317 4048 4018 4018 4018 4018 4018 4018 4018	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	
70 71 M-07 67 448 (1) 552 51 550 550 50 50 50 60 60 60 60 60 60 60 60 60 60 60 60 60	4 4 4 4 4 4 4 Multi-Purpose Room Storage Storage Storage Storage Storage Storage Storage Storage Storage MEDIA CENTER 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	4317 40484 40848 4	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	

	SPACE SUMMAR			
	Room Type	Room NFA	# of Rooms	Area Total
	CORE ACADEMIC SPA		In or receive	priod rotal
	1	3 21036	23	
	Classroom	1729		
	Kindergarten	3586		
3	Storage	159		
	SPECIAL EDUCATION			
	4	6 2762		
10	ELL	442		
3	OT	447		
1	Sped Classroom	87		
7	Speech	445		
	Storage	454		
	Toilet	103	3	
	ART & MUSIC			
	2	2 1237	1 2	,
0	Art	2 1237		
19	Music	378		
J	iviualic	376		
	VOCATIONS & TECHN	DLOGY		
	0	ol (
	Ĭ			
	HEALTH & PHYSICAL I	EDUCATION	'	
	1	2 4317	. 4	1
70	Multi-Purpose Room	4048		
	Storage	269		3
	MEDIA CENTER			,
	1	1 2361	1	
18	Library	2361	1	
	DINING & FOOD SERV			,
	0	0 0) C	
	MEDICAL 0	ol c) (,
	0	0	,	,
	ADMINISTRATION & G	UDANCE		
	7	7 2439	7	
52	Administration	516		
51	Counciling	413		
50	Faculty Room	477		
7	Office	405		
A	Principal's Office	200		
2	Reception	264		
1	Storage	164	1	
	CUSTODIAL & MAINTE	NANCE		
	3	4 1012		
	Cust.	174		
35	Custodian	401		
3	Receiving	256		
32	Storage	181	1	
	OTHER			
	2	2 800		
8	Partnership Program	604		
37	PPP	196	1	-
	TOTAL BUILDING GRO	00 51 000 4054		
			1	1
	TOTAL BUILDING GRO	1 55416	1	

LANDSCAPE ARCHITECTURE

General

The Muraco School is located in a residential neighborhood with the back of its site bounded by the MBTA Commuter Rail embankment and the Aberjona River. The Tri-Community Bikeway that connects Woburn, Winchester and Stoneham crosses the Muraco site and connects it to Leonard Field. The wooded area across the Aberjona to the north has been removed and is currently undergoing conversion into soccer fields. The topography of the site is such that the building has three levels of access, with the main entrance door higher than the parking level and the lowest level, being the storage space for the playing field.

Vehicular Access & Circulation

There are two separate vehicular access routes to the school: Bates Road, which leads to the parking area and Tufts Road, which leads to the lower loop by the playing fields. Bates Road is the main entrance and includes a newer school sign at the beginning of the parking lot. Circulation is color-coded for parking cars (white) and student drop-off along the curb (yellow), which is marked with signs. The pavement continues to a service area and staff parking (with directional sign) on the south side of the building where the pavement ends. A former link to Irving Street is blocked off to vehicles with boulders. Pavement in the larger parking area is in reasonably good condition with some cracking. The drop-off loop has granite curbing. For service area pavement condition, see "Service Area" below.

The loop from Tufts Road is a simple one-way circulation with a spur service road that runs to the end of the lowest building level (playing field level) where athletic equipment is stored. There is little signage at this location other than an "End of Public Way" indication. The roadway pavement is worn but in reasonably good condition with granite curbing.

Parking Location, Arrangement & Quantity

The main parking lot off Bates Road is lined for 75 spaces with 1 additional handicap space. Eight of the spaces are marked "staff" in worn paint. There are no vertical HP signs. Circulation is one-way and connects with a spur to the service area with five lined parking spaces for staff and two additional handicap spaces marked "Drop-off Area". The main parking is an attractive area surrounded by wooded edges and includes curbed islands with trees and ornamental plantings. Presumably, vehicles park around the Tufts Road loop for athletic events taking place at field level, although there are no marked spaces. We estimate that 15-18 vehicles could park in this area.



School sign at the end of Bates Road



Clearly separated parking and drop-off lanes

Pedestrian Circulation

There are several pedestrian routes into the site from the surrounding neighborhoods. Bates and Tufts Road both dead-end at the school site. Bates Road has a worn but curbed asphalt sidewalk from Washington Street along its southern side; Tufts has no sidewalk so pedestrians must walk in the street. There is also a pedestrian link from the Irving Street sidewalk on the south. And the path of the Tri-Community Bikeway (under construction) provides access for walkers from the north.

Once on site, both parking/drop-off areas are ringed with asphalt sidewalks and both have pathways connecting up to the School's main door. At the north of the school, pedestrians from the Tufts loop can use the pavement that runs along the athletic storage area to walk on to the school site, but the path ends at the building corner. At the south, there is a paved path behind the service/parking area, but walkers clearly prefer to walk along the building face where they can reach the entrance door to the Annex in back. There is no exterior pedestrian connection from the south side of the school to the court/playground level to the west, approximately one floor level below. At the west side (back) of the school, circulation consists of a long concrete ramp and sloped asphalt path from two school doorways down to the basketball court level, from which one can access the play area. There are no paved connections to the fields. The asphalt pavement varies in condition but is relatively worn and cracked in most places. The ramp (discussed below under "Pedestrian Accessibility") is recently installed and in good condition.



Drop-off, parking loop at the end of Tufts Road



Service to athletic service off Tufts Road loop



Looking up from Tufts Road to Washington Street



Signage at Tufts Road loop

Pedestrian Accessibility and Code Compliance

The main doorway to the school sits at a higher elevation than either of the two parking/drop-off areas and although there is a code-compliant ramp at that entrance, access is from inside the building to the outdoor kindergarten area only. The pathways to this entrance from either parking lot are steeper than 5% so the main entrance does not meet ADA or MAAB requirements. At the Bates Road drop-off, there is a directional sign to the accessible entry door (Door #6) on the south face of the building at the service area. However, while the threshold has been made flush, the paved route to this area is in poor condition (see "Service Area" below) and the uneven surface presents a code violation. Doors #9 and #10 to the kindergarten area are accessible. However the other egress doors on this façade have steps and are not. At the back of

the school, the recently built concrete ramp (over 80 LF long) connects Door M2 to the basketball court level. This ramp appears to comply with code requirements. Also at the back of the school, pavement has been ramped up to Door #8, but the interior has stairs so this entrance is not accessible. To get access from the exterior ramp to the playground and to the fields, one must cross the basketball court. Cracks in the pavement have been repaired but it is still not an unbroken surface (see "Recreation Spaces" below) as required by code. The play areas at the back, with the exception of one climber, are connected by smooth concrete paths in good condition. The accessibility issue here, as at the kindergarten play space, is that a ramping system is needed from the edge of pavement into the variable height loose surfacing. There is no paved access to the climber by the large birch or to the adjacent playing field.

The curb cuts at the Tufts Road loop are built to code and associated with a cross-walk. The curb cuts at the Bates Road loop are asphalt and not code-compliant. The 75-space parking lot requires a minimum of 3 parking spaces, and a total of 4 are



Service to athletic courts off Tufts Road



Pedestrian/vehicular access to athletic storage next to field



Extensive crack repair at basketball court pavement



Flowering tree and garden plantings at front of school

required if we combine it with the 5 space lot by the service area. So the single space within the larger lot plus the two HP "Drop-off" spaces do not fulfill MAAB requirements. In addition, the single space does not have an associated curb cut or vertical sign.

Service Areas

The school does not have a loading dock. Deliveries and trash pick-up are serviced at the south side of the building using available doors. The asphalt pavement is heavily patched and has both smooth and uneven areas.

Courtyards / Exterior Student Gathering Spaces

While there are no courtyards per se, each playground area has an associated paved space that functions as a gathering space with seating and/or picnic tables. For further information see "Recreation Spaces" and "Site Furnishings" below. Recreational Spaces

The Muraco's recreational spaces include a Kindergarten Playground, School-age Playground, basketball court, playing fields and some older play equipment associated with the Tufts Road loop.

The age-appropriate play structures at both the "Muraco School Kindergarten Playground" (2003) and the "Muraco Community Playground" (2002) are by Playworld and in very good condition. A combination of concrete pavement edge and plastic timbers retain the loose wood chip surfacing in both locations. One exception is the raised timber edge around the independent climber, an older installation not connected to the paved circulation and seating areas which has non-accessible pea-stone surfacing. In addition to connecting the various play structures, the concrete pathways provide space for seating and picnic tables and, in the case of the kindergarten, are used for play graphics. Vinyl-coated chain link fencing in good condition partially encloses the Kindergarten play area. The basketball court is large enough for extensive pavement play and includes other play graphics. Its surface cracks have been repaired but it remains worn and uneven.

The playing field to the northwest of the school is bounded by the Aberjona River and the MBTA embankment, both fenced. Early in the playing season, some worn patches of turf were observed but the field looks well used. Passing trains are both visible and audible from this area.

The final "play area" is at the lawn adjacent to the Tufts drop-off loop where an old spring rider and swing set remain. Several other pieces of equipment are visible in the adjacent woods. This equipment is outdated and is not installed over appropriate resilient and accessible surfacing as required by code.

Site Lighting

Utility pole-mounted floodlights and cobra head fixtures illuminate the parking and drop-off loops. Doorway overhangs incorporate lighting on the building. There is no additional lighting of the pedestrian pathways and no athletic or playground lighting.

Site Furnishings

Furniture on the site includes a flagpole by the main entrance, composite timber benches and picnic tables associated with both playgrounds, and one steel trash receptacle. There are also aging concrete retaining walls at the base of the slope by the Tufts Road loop and the chain link fencing at the perimeter of the playing field and play area is very old and in poor condition. It is unclear whether the fencing along the MBTA right-of-way belongs to the school or to the MBTA. Given the proximity to the bike trail, it is surprising that there are no bike racks on the site.

Trees, Planting, and Other Vegetation

The Muraco site features mature shade trees, flowering trees, shrubs and annuals. Entry to the site along Bates Road is through a wooded "channel" and the drop-off loop rings central islands with mature pines and birch. The embankment up to the school at the end of the loop is dotted with flowering trees and the walkways up from both drop-off loops are shaded by larger trees. Massive shade trees dominate the slope behind the school. A large, spreading paper birch provides shade to the playground. The trees appear to be in good health and condition. Foundation plantings include seasonal bulbs and some evergreen shrubs at the Kindergarten façade. There are ornamental lower plantings at the parking lot drop-off loop and around the outside of the kindergarten.

Lawn condition varies depending on location. Areas by the school entrance and where pedestrians have worn paths are compacted and bare, while areas that get little foot traffic, such as the embankment at the back of the school, look healthy and green.

Finally, there is a wooded area between the Tufts Road loop and the playing field that seems to be used for storage. When leafed out, this area must become quite dense and could present a potential safety issue.

CIVIL ENGINEERING

General Site Conditions

Landscaped areas around the school have poor grass coverage and there are several unpaved paths, including the primary path to the rear of the school, throughout the site.

There are three play structure areas on site, two at the rear of the school and one for the kindergarten at the front of the school. The larger play area has some damaged plastic curbing and the smaller play area has decaying wooden curbing. The play structures themselves appear to be in good condition but further evaluation should be done by a certified playground safety inspector. The surface of the play areas was either common mulch or peastone. The pavement in the paved play area at the rear of the school is in poor condition.

There is one set of swings on the side of the school that appear to be original to the school construction with no associated safety area or resilient surfacing.

Not all of the sidewalks have curb cuts at cross walks or primary crossing areas. There are ramps at the rear and front doors for accessibility and the doorway at south side of the school is at grade.

The area behind and to the north side of the school are within the 100-year flood plain and the site has witnessed flooding in recent years. The ground floor of the building and the parking areas are not within the 100-year flood plain.

The Aberjona River runs along the north side of the site crossing through a culvert under the train track at the rear of the school. (The Town of Winchester's multi-year Flood Mitigation Program has identified this culvert as in need of widening to accommodate more water to flow through to alleviate flooding.) The northeast corner of the existing building may be within the 200-foot riverfront area associated with the Aberjona River.



Unpaved path



Decaying wood

Parking and Circulation

The main parking lot at the school is in front of the school and features a one-way counter-clockwise circulation. The main parking area appears to have been recently reconstructed and the pavement is in good condition. There are a couple of flood-type security lights in the area closest to the school. The parking area drains to a closed drainage system and there was no evidence of ponding or puddling in the main parking area.

There is one accessible parking spot in the main parking lot. The slopes in the accessible parking space do not appear to meet accessibility guidelines (less than 2% slope in any direction) and there is no curb cut to the sidewalk adjacent to the accessible parking spot.

Section 2 | Muraco Elementary School Existing Conditions

There is a small parking area (5 standard spots plus 2 striped accessible spots) on the south side of the school. The pavement in this lot is in poor condition and the slopes at the accessible parking spots do not appear to meet accessibility guidelines.

Utilities

There is a closed drainage system in the main parking area. Downspouts along the front of the school discharge to grade. The school is connected to the town sewer system but there was no evidence of an external grease-trap. The gas meter and electric transformer are located on the south side of the building adjacent to parking, the dumpster, and a secondary entrance. Both the transformer and gas meter have some bollards around them.

ARCHITECTURE

Organization

The Muraco School was built in the mid- 1960s and is approximately 50,000 square feet. The building contains classrooms, a multi-function room (cafetorium), Media Center and offices. A (2) classroom modular addition was added in 2008.

Circulation

The building is one story. There is a partial basement space at the north side of the building which contains storage spaces and access to an exterior covered play space. Access to the lower level is by stairways only.

Program and Space Issues

The Muraco School includes 22 classroom spaces of approximately 900 square feet typically. Two courtyards at the plan interior bring daylight to the corridors. Comparisons with current MSBA space standards indicate that classrooms and core academic spaces are undersized. See the chart below.

	Muraco Elementary	MSBA Standards
Classroom	910 square feet	950 square feet
Music	378 square feet	1,200 square feet
Library	2,361 square feet	2,020 square feet
Art	859 square feet	1,000 square feet
Gymnasium	0 square feet	6,000 square feet

Physical Conditions of Exterior Envelope - Walls

The building is faced with red brick in a running bond pattern, with a large roof overhang. The envelope appears to be in good condition. There are few areas on the north side where the brick has cracked and there are no expansion joints in the brick. The wood at the roof edge appears to have been recently painted and is in good condition. See the charts below.

Representative R-V	alues (1940s Walls)
12" Masonry	1.17
TOTAL R-VALUE	1.17
WINDOW DOUBLE PANE R-VALUE	0.91
	1960s: 4" exterior brick, 8" masonry

Typical Exterior Walls - Tod	ay's Minimum Requirements
Face Brick	0.39
Air Space	2.02
Air & Vapor Barrier	0.15
1/2" Gypsum Sheathing	0.45
Insulation	22.00
Vapor Barrier	0.15
Interior Gypsum Board	0.45
TOTAL R-VALUE	25.61
WINDOW TRIPLE PANE R-VALUE	5.00

Physical Conditions of Exterior Envelope - Windows

About half of the windows are replacement windows and the rest are original single glazed windows. Other than the lack of energy efficiency, the windows appear to be functioning properly.

Physical Conditions of Exterior Envelope - Roof

The roofing is membrane at all areas. Generally, the roofing appears to be in good condition. There is minor damage at the roof edge in one location. Also, there is some evidence of a roof leak that has occurred in the newer modular section of the school. The joint at the connections of the two modular sections appears to be the location of the leak. See the charts below.

Muraco Existing	Roof Construction
Rubber Membrane	0.40
2" Insulrock Insulation	5.00
2" Rigid Insulation	5.00
Structure/Ceiling	5.00
TOTAL R-VALUE	15.40

Roof Construction - Tod	ay's Minimum Standard
Rubber/PVC	0.40
4" Polyisocyanurate	30.00
Structure/Ceiling	5.00
TOTAL R-VALUE	35.40



School windows from exterior



School exterior and play area

Interior

Finishes are well suited for school use and have been well maintained. Light quality is generally good.

Interior Partitions

In general, all interior partitions appear to be in good condition. The type of partition varies throughout the building as follows:

- Exposed brick
- Painted plaster

- Painted drywall
- Glass wall windows

In a renovation, various existing plaster walls to remain could be cut open to accommodate new electrical, plumbing and technology systems. All walls should have acoustical batt insulation to improve acoustical performance.

Flooring

In general, all flooring is in good condition. Carpet covers many of the classroom spaces and appears well maintained. The type of flooring that exists is as follows:

- Asbestos containing tile (9x9)
- Vinyl Composition tile (12x12)
- Slate
- Carpeting

Wall Base

The wall base is rubber of various sizes. All base material appears to be in good condition.

Ceiling

The ceilings are 2x4 suspended acoustical tiles and are in good condition. Although some tiles show evidence of slight cupping, possibly due to moisture issues. The existing ceilings consist of the following types:

• Suspended acoustical tile

Doors and Frames

Doors are generally wood and many are chipped and damaged. The conditions are fair to good. Most if not all doors are equipped with lever handles.

Fire Extinguishers

All existing fire extinguishers appear to be operational and certified.

Tackboards and Markerboards

Tackboards and markerboards are existing throughout and appear to be in good condition. Fire code regulations do not allow for tackboards to be within 5 feet of egress doors.

Regulations

The existing facility as a whole is in compliance with the original code, however, this does not mean it meets every standard of the current code. In accordance with the current code, an existing building is presumed to have met the codes and regulations in effect at the time of its construction and is allowed to continue in its use, provided it is maintained per the original code. Current building codes are applicable to any alteration or addition or change in use of the structure in accordance with 780 CMR 34.

Code Classification 780 CMR 302.1

The occupancy of the facility is non-separated mixed use with assembly and educational uses as follows:

Construction Classification

Based upon the definitions in the current code, the minimum classification of the building is as follows:

Chapter 34: Repair, Alteration, Addition and Change of Use of Existing Buildings

A renovation project is governed by Chapter 34. This chapter is "intended to maintain or increase public safety, health, and general welfare, without requiring full compliance with the code for new construction."

- i. Building renovation For continuation of the same use groups the building shall comply with 780 CMR 3404.0.
- ii. New Building Systems Any new building system or portion thereof shall conform to 780 CMR for new construction to the fullest extent practical.
- iii. Alterations and Repairs Alternations of repairs to existing buildings, which maintain or improve the performance of the building may be made with like material, unless required otherwise under 780 CMR 3408 Structural Requirements for Existing Buildings.
- iv. Number of Means of Egress Egress for the existing facility is sufficient in accordance with the current building code.
- v. Capacity of Exits There is sufficient egress capacity to meet current codes at the doors throughout the facility.
- vi. Length of Access Travel Shall not exceed 200 feet, in building without a sprinkler system. All areas of the existing building are within 200 feet of an exit.
- vii. Exit Signs and Lights For notes on the existing system, refer to the Electrical Existing Conditions Report.
- viii. Means of Egress Lighting Refer to the Electrical Existing Conditions Report.
- ix. Height and Area Limitations Under Chapter 34, the building is in conformance with applicable height and area limitations, so long as there is no change in use. Additions may be made to the structure.
- x. Fire Protection Systems Fire protections systems must be provided for existing building that are "substantially" altered or "substantially" renovated where required for the specific use group.
- xi. Enclosure of Stairways open egress stairways are prohibited. There shall be no minimum fire resistance rating required for an existing enclosure of a stairway.
- xii. Assembly Use Groups Any alteration within an assembly use group shall comply with the code for new construction. This applies to the cafeteria, auditorium and gymnasium
- xiii. Accessibility for Persons with Disabilities Accessibility for persons with disabilities shall be provided in accordance with the regulations of the Architectural Access Board.
- xiv. Energy Provisions for Existing Buildings Alterations to components affecting energy conservation performance shall comply with 780 CMR 13 generally, and 780 CMR 1304.2 or 780 CMR 1304.5 or 780 CMR 1309 specifically. Existing components may remain.
- xv. Evaluation of Existing Building The structural engineer shall make a structural evaluation of the existing building to determine the adequacy of all structural systems that are affected by alteration or damage to be repaired.
- xvi. Existing Lateral Load Capacity (Refer to Structural Existing Conditions Report for further information) Alterations shall not be make to elements or systems contributing to the lateral lad load resistance unless the altered lateral load resisting system conforms to 780 CMR 1611.0 and 1612.0; or there is no reduction in the lateral capacity to the building as a whole. Existing elements of systems may be reinforced or replaced with new elements or systems of equivalent strength and stiffness.
- xvii. Earthquake Loads (Refer to Structural Existing Conditions Report for further information) For no change in use groups, but alterations exceeding 50% of the assessed valuation of the building, the project is defined as Seismic Hazard Category 2.
- xviii. Earthquake resistance shall comply with the requirements of 780 CMR 3408.3.5
- xix. The provisions of 780 CMR 34 govern Fire Resistant Materials Fire resistance construction systems.

Interior Finishes 780 CMR 8

Interior trim and finishes altered as a part of a renovation shall conform to the requirements of 780 CMR 801. Flame spread of Interior Finishes for the E and A-3 use Groups, shall conform to Table 803.4. Existing finishes are code compliant.

The State Fire Marshall introduced regulations in 2003 restricting display of paper in egress areas. The provisions are as follows:

- i. Paper display in classrooms shall not exceed 20% of the wall area. Measurement of wall area shall include windows and doors.
- ii. Paper display in corridors shall not exceed 10% of the wall area and shall not be placed within 5 feet of an egress door. It shall be applied directly to the wall and shall not be grouped in areas bigger than 6 feet by 12 feet.

Handicap Accessibility

The building complies with Massachusetts Architectural Access Board (MAAB) regulations.

STRUCTURAL ENGINEERING

The Muraco School was constructed in the mid 1960's, is well maintained and in generally good condition. Two modular classrooms were added on the west side of the building in 2008. The roofing on the original building appears to be in good condition, and the wood building trim recently painted. The roofing on the modulars appears to have leaks at the east edge, and at the east west seam between modular units.

The original building is a one-story building, with the roof likely framed with open web steel joists and structural steel framing. There is a one story basement level on the north side of the building. Some of the basement areas were only partially excavated. Doors open into these areas where the first floor concrete framing is visible. Interior basement areas have asbestos warnings posted on some of the columns. Access to the basement areas is restricted.

Part of the northwest basement level is open to the exterior. The brick veneer of the first floor walls is supported on a steel shelf angle, attached to the concrete floor beam. The brick masonry is showing some distress, resulting from brick growth. The corners of the north wall have moved outward about 1", resulting in some cracking of the masonry near the corners of the wall. These cracks should be repaired, and control joints cut into the wall to limit future movement.

There are also spalls in the concrete foundation wall at the north east corner caused by brick growth in the north and east walls. Joints could be cut into these walls to minimize future movement.

At the front entry there is a brick pier supporting the roof, with vertical cracks on the north and south faces. The cracks are caused by corrosion and rusting of an embedded steel column. This should be further investigated, and the column repaired if necessary.

There is a small site retaining wall at the west side of the north elevation. The wall has shifted, and the cap stone is loose. The wall should be repaired.

MECHANICAL ENGINEERING

Heating Plant

The boiler room houses three condensing boilers of which are fired with natural gas of which are approximately five years old. It has been reported that all three boilers are required to heat the building during the coldest weather of the heating season. The existing (original equipment?) cast iron sectional boilers have been abated of asbestos and remain abandoned in the boiler room. The existing breaching from these boilers has been covered, encapsulating the (presumed) asbestos insulation on these existing flue systems. The existing brick stack is being used only to chase up the new flue for the domestic hot water heater. The new HVAC boilers are Camus "DynaForce Series" (2000 MBH input) boilers and are in fine operating condition. These boilers produce hot water for heating the building. The boilers do have the ability to "condense" acids from the flue gases and are fitted with acid neutralization devices to treat the condensate prior to draining. It was observed that on a mild spring day the leaving water temperature of the system was 178 degrees F of which is not cool enough to promote condensation. It is also noted that the cooler the hot water supply temperature (generally designed for 140 degrees F) the more efficient the boilers are. It is unclear why the supply water temperature set-point was set so high on a moderate day.

Air Systems

The classrooms are predominantly served with console unit ventilators or ducted cabinet unit heaters. The unit ventilators entrain the required ventilation air using an adjacent wall louver (units located on exterior walls). The classrooms served with cabinet unit heaters receive the required ventilation air from Energy Recovery Ventilators (ERVs) located in the attic space of the building. These ERV units transfer heat from the exhaust air into the ventilation (outdoor) air prior to tempering the air to room temperature. This air is then ducted to various classrooms using centralized ductwork systems. There are several air handling units which are ducted to interior spaces such as the Administration Wing and the Media Center. All of the air handling units have been replaced approximately five years ago and are in good condition.

Piping Systems

The piping/pumping system has been replaced in its entirety approximately five years ago along with most of the HVAC equipment. The hot water piping system is used to heat the building. The primary and secondary pumps for this system are located in the boiler room. The secondary pumps are fitted with Variable Frequency Drives (VFDs) to allow for energy savings when the building does not require full hot water flow for heating (during the warmer heating season days). The piping system networks out from the boiler room through the crawlspace of the building upfeeding various heating equipment throughout the building. The existing chilled water piping system was replaced with a small piping system located in the attic space of the building serving various air handling equipment.

Air Conditioning

The building is served with a small (20 ton) chiller located on the roof. This chiller is piped to various air handling units serving interior spaces. The chiller is aircooled. The administration wing is served with a dedicated fan coil unit which includes a dedicated roof mounted aircooled condensing unit. This allows the administration wing to cool without turning on the larger chiller thus saving energy when the school administration wing is the only space occupied. A minisplit air conditioning system serves the health wing of the building. All this equipment is approximately five years old and in good operating condition.

Automatic Temperature Controls

The automatic temperature controls for the entire school have been converted to Direct Digital Controls (DDC) five years ago along with all of the HVAC renovations. The control system is a Johnson Controls Metasys platform with a computer located in the custodian's office adjacent to the boiler room. No problems have been reported with this system or HVAC controls operations in general.

ELECTRICAL ENGINEERING

Main Electric Services

The main electric service is rated 208/120V, 800A, three-phase, four-wire. The distribution equipment is primarily manufactured by General Electric. Eversource electric services appear to originate from Verizon street pole number 77/8 along Irving Street. The service route is underground from the street pole to a 150 kVA pad mount transformer (Eversource number PMH21853). The secondary service conductors are installed underground from the pad mount transformer to the main electric service located in the facility maintenance office. Based on the Eversource electric meter number 5063803 and the metering nameplate multiplier of 80, the maximum demand recorded on the date of survey is 104.8 kW.



Power line atop school



Typical lighting in classrooms

Emergency Electric Services

The school does not include an emergency generator.

Emergency lighting throughout the school appears to be provided by local battery pack luminaires. Multiple manufacturers appear to be used for these luminaires. Many exit signs also appear to include battery backup, but could not be confirmed physically for all locations.

Fire Alarm

The fire alarm system is manufactured by Standard Electric Time Company which has not manufactured fire alarms under this name since 1970. This fire alarm system is no longer listed to meet present day requirements. There is a Notifier expansion panel, Model NFW-50, to support the modular classrooms located at the rear of the school. The expansion panel is connected to the existing fire alarm panel. The fire alarm system includes full, but limited, heat detection coverage throughout the school, since no fire protection systems appears evident. Manual initiation and notification devices are installed throughout the school and at most egresses. The fire alarm appears to be connected to a Honeywell dialer assumed to signal the local fire department. There is an original remote annunciator, assumed to be out of service, as well as a newer Notifier remote annunciator located inside the front entrance across the corridor from the principal office with drill switch function. There is a red fire alarm beacon and fire alarm master box located outside the school main entrance.

Lighting and Lighting Controls

Luminaires, primarily fluorescent with a few incandescent, appear to be relatively old in most locations throughout the school. Occupancy sensors are located in many administrative and classroom areas. Gymnasium lighting is manually controlled with low-voltage devices and remote contactors. Exterior lighting appears minimal. No emergency lighting was observed at exterior of building egresses.

Clock System

There appears to be a functional central clock system used in the school. The main clock control panel, located in a storage room, appears to be relatively new and manufactured by American Time and Signal Company, AllSync Master.

Audio-Visual (AV)

Aside from the select intelligent classroom presentation boards, there is a voice communication system throughout the school. A rack receiver and Radio Shack 40 Watt amplifier located in the facility maintenance office appear to be the head end equipment.

Telephones

There was no staff to confirm operation, but telephones appear to be voice over internet protocol (VoIP). This is assumed due to the tracing of the network cabling to voice and data wall outlets.

Security

Access control is provided with the use of Keri Systems hardware and appears relatively new. Unless well hidden, security cameras were not observed. All entrances are monitored with status indicating devices. There is one access keypad observed at the side entrance door. The American Alarm keypad appears to be the operational control connected to the American Alarm panels located in the facility maintenance office.

IT Network

The main distribution frame (MDF) was located in the assistant principal office and not ventilated adequately for this type of equipment. Wireless access points (WAP) were observed and assumed to provide adequate wireless coverage to satisfy occupant needs.

General Conditions

Electrical code clearances and proximity to non-electric systems and components is not met in many locations. Storage of supplies and debris is impeding access to electrical panel boards in many locations throughout the school. There did not appear to be any sign of main electric service equipment testing.

Each accessible battery backup luminaire in the based building and the modular classrooms did not operate when test switch was activated. Spaces associated with daycare, preschool, kindergarten and early childhood education are required to include tamperproof receptacles and none were observed anywhere in the school. Receptacle safety inserts do not meet this requirement. Some sink locations include close proximity receptacles without ground-fault protection or had no receptacle provided.

Exterior egress luminaries do not appear supported with a backup source.

Fire alarm notification devices are audible horns only and include no visual indicators (strobes). Notification devices are also limited in quantity and do not cover all areas adequately. Fire alarm manual initiation devices and notification devices are not installed at ADA required elevations. No emergency lighting or exit signs were located in boiler room. There was no record of fire alarm testing observed.

A rear egress door does not include a fire alarm manual initiation device and a notification device was also not in vicinity.

PLUMBING ENGINEERING

Domestic Water System

A buried 4 inch service, assumed to be connected to the main in Bates Road, enters the Boiler Room from the east. The entry includes full-size iron gate valves and a 4 inch Municipal meter that appears to be original to the building (1966). The condition of existing iron and copper water piping is fair considering its age. Some copper piping appears to have been repaired or replaced. Insulation condition, where visible, varies with age and is showing signs of wear.

Domestic Hot Water Plant

The entire building is served by a 100 gallon, gas-fired storage heater, installed with the heating system upgrade when the buried oil tank was removed and the natural gas service installed. There is a circulator pump, an aquastat and a master mixing valve that appears to be about 20 years old. Hot water delivery at remote fixtures is fair.

Plumbing Fixtures and Fittings

Toilet Room plumbing fixtures and trim are generally in fair to good condition, accessible fixtures were not noted. Casework sinks and fittings are in fair condition; none of those viewed were accessible. Accessibility and fixture counts for students and staff require review.

Natural Gas Service

The gas service enters the Boiler Room from the meter assembly on the south wall, fed from Irving Street. A branch line directly feeds the domestic water heater and the main feeds the gas-fired boiler plant. Gas piping is in very good condition.

Sanitary, Waste and Vent Systems

The exact location of building sanitary exit(s) could not be determined by this survey. Cast iron piping, visible in the Boiler Room and crawl space, appears to be original to the building and is in fair to good condition. A sump pump and basin are buried in the northwest corner of the Boiler Room; exact piping connections could not be determined. Below casework fixture copper drainage piping is in fair condition.

Building Storm Drainage

The location of building storm exit(s) could not be determined by this survey. Visible cast iron piping is in fair to good condition. Insulation is showing signs of wear.

General Condition

The building Plumbing systems are in fair to good condition overall and, according to staff, there have been no recent major problems.

FIRE PROTECTION

There is no water-based fire protection within the building.

DATA/COMMUNICATIONS, TECHNOLOGY

The telephone system is an older WIN 440CT. The systems is wall mounted in the Service Entrance Room. There are several local older RadioShack amplifiers attached to the system, allowing it to connect to corridor and classroom speakers for general announcements. Speakers are of varying makes and manufacturers and many are not functioning. The intercom speakers in corridors and classrooms are in need of replacement. Most classrooms and offices have phones that connect to the WIN system. Clocks are of varying manufacturers. Some are newer American AllSyncplus wireless products. Intercom and telephone systems needs to be updated to newer technology. Any future project should include an upgrade of the phone system to the district standard NEC VoIP and a replacement of the intercom system.

The Gymansium/Caf has some local audio speakers. The equipment rack for the audio equipment is portable, currently located on the stage. Any future project should include local AV systems for large group gathering and instructional spaces.

Distribution of cabling is achieved with wall mounted racks and patch panels. Cabling is Category 5. A significant amount of the cabling has been run exposed. There are typically three data jacks at the teacher location, 3 for student use, one for a wireless access point. Many classrooms have wireless. Wireless APs are Aruba AP105. Many classrooms are equipment with projectors. The projectors are a combination of Epson 480i and 410W. Some classrooms are equipped with ENO Boards. Teachers are equipped with Dell laptops and port replicators and Lumens DC-170 document cameras. Any future project should include an upgrade of all cabling to the current TAI/EIA standard at the time.

There is no site or exterior video surveillance. There is an access control system and an alarm keypad at the back door of the school. The access control system is a relative new Kerisystem with multiple panels. Any future project should include an integrated security system inclusive of building and site surveillance, intrusion detection and access control.

2.6 | Mystic Elementary School

Landscape Architecture

Civil Architecture

Architecture

Structural Engineering

Mechanical Engineering

Electrical Engineering

Plumbing Engineering

Fire Protection

Data/Communications






Narrative Description of Property


This property contains 2.520 acres of land mainly classified as PSCHOOL with a(n) SCHOOL style building, built about 1930, having BRICK exterior and SLATE roof cover, with 3 unit(s), 11 room(s), 0 bedroom(s), 2 bath(s), 4 half bath(s).

Property Images



Disclaimer: This information is believed to be correct but is subject to change and is not warranteed.







		Room NFA	# of Rooms	Area Total
	CORE ACADEMIC SPACES			
15		11041	15	
	Adult Classes After School	591	1	
	Adult Classes After School	929	1	
	After School	584		
	After School	573	1	
	After School Enrichment	947	1	
	Conf. Rm.	242	1	
	Kid's Corner	695		
	Kid's Corner	932 577	1 1	
	Kid's Corner Kid's Corner	577	1	
	Kid's Corner	573	1	
	Pre-School After School	968	1	
	Pre-School After School	591	1	
_	Pre-School Enrichment	1132	1	
	Pre-School Enrichment	1126	1	
	F1e-SCHOOLEHHICHHIEH	1120	'	
	SPECIAL EDUCATION			
0		0	C C	
	ART & MUSIC			
C		O	C	
	VOCATIONS & TECHNOLO	GY		
C			C C	
	HEALTH & PHYSICAL EDU	CATION		
- 4	4	2471	4	
	Gymnasium	1732	1	
	Stage	561	1	
	Storage	93	1	
	Storage	85	1	
	MEDIA CENTER			
C	0		0	
_	DINING & FOOD SERVICE			
С	0	0	0	
0	MEDICAL 0	0	1 0	
·	0		· ·	
	ADMINISTRATION & GUIDA	NCE		
- 4		796	4	
	Director	177	1	
	Health Dept. & Teach Rm.	371	1	
	Office	209	1	
	Stor.	39	1	
	O.O.			
	CUSTODIAL & MAINTENAM	ICF		
8			8	
	Boiler Room	374	1	
	Fan Room	335		
	Janitor	82	1	
	Janitor	42	1	
	Storage	68	1	
	Storage	195	1	
	Storage	284	1	
	Utility Space	524	1	
_				
	OTHER			
	0	C	C	
	TOTAL BUILDING GROSS I	FLOOR AREA		
_	2	26638	2	
	Basement	8202	1	
	Floor 1	18436	1	

Room Type	Room NFA	# of Rooms	Area Total
CORE ACADEMIC SPACE	7 11041	15	1
A			
Adult Classes After School After School	1520	2	
After School Enrichment	947		
Conf. Rm.	242		
Kid's Corner	3358		
Pre-School After School	1559		
Pre-School Enrichment	2258		
SPECIAL EDUCATION			
	0 0	0	
ART & MUSIC	ما		1
	0 0	0	-
OCATIONS & TECHNOL	OCA		
	0 0	0	
	1	,	
HEALTH & PHYSICAL ED	UCATION	·	
	3 2471	4	
Gymnasium	1732		
Stage	561		
Storage	178	2	
MEDIA CENTER			
	0 0	0	
DINING & FOOD SERVICE	0 0	0	
	9 0	-	
MEDICAL			
	0 0	0	
		_	
ADMINISTRATION & GUID	DANCE		
	4 796		
Director	177		
lealth Dept. & Teach Rm.	371		
Office	209		
Stor.	39	1	
CUSTODIAL & MAINTENA			
Boiler Room	5 1904 374		
an Room	374		
-an Room Janitor	124		
Janitor Storage	547	3	
Jtility Space	524		
zum, opace	324	,	
OTHER	•		•
	0 0	0	
TOTAL BUILDING GROSS	FLOOR AREA		
FOTAL BUILDING GROSS Basement	2 26638 8202		

LANDSCAPE ARCHITECTURE

General

The Mystic School is located at one end of a residential block bounded on three sides by Madison Avenue, Main Street and Marshall Road. It houses the Winchester Recreation & Community Education Department, which includes pre-school and a summer K-6 program, and Kids Corner, an independent, parent-operated after school program. Both recreational space and building access for these different programs are separated on the site, which is ringed with mature shade trees.

The site is relatively flat at Main Street and slopes steeply up Madison Avenue. As a result of this change in grade, the building has three levels: the Basement level (occupied by Kids Corner), the Gym level and the Madison Avenue level (second floor).

Vehicular Access & Circulation

While cars have two access points into the site, buses delivering children are relegated to the surrounding streets. Full-size school buses for the after-school program drop off along Main Street. A van for special needs stops along Madison Avenue. Vehicular access into the site includes a large parking lot located off Marshall Road and a second parking area located off Madison Avenue. On mornings during the school year, parents drop off approximately 80 children, mostly at the Marshall Road lot. Pick-up from Kid's Corner also occurs here. The pavement at the drop-off loop is in relatively good condition with cracking in some limited areas.

There are few signs directing visitors clearly to their destination. The Marshall Road parking/drop-off area is at least visible from Main Street. There is a "Kid's Corner" sign on the chain link fence facing Main, but it can only be seen from the south-bound lane and other programs accessible at this point are not listed on the sign. The Winchester Recreation and Community Education sign on Main Street just south of Madison Avenue is visible only from the north-bound lane.

Parking Location, Arrangement, & Quantity

The Marshall Road parking lot is striped for 22 cars plus one handicapped parking space. None of the spaces have signs. Circulation is one-way with a single access point and there is plenty of extra pavement space for cars to line up to pick up or drop off students. Several vehicles do park on the lawn area up against the building, even though there was pavement space available on the day of our visit. Staff and pre-school parents use this lot. Pavement Condition is reasonably good with some areas of cracking and a few low points that hold water. Because there is no curbing, there are no curb cuts; pedestrians walk directly from the parking pavement to the pathways.

On Madison, there is both a paved parking area and a "cut-in" approximately 4 feet wide along the curb for parallel parking. Staff park along Madison in the morning and parents line up at the end of the day for pick-up. The paved area against the building is in very poor condition and mirrors the slope of the road. There are approximately 10 spaces and an additional 2 with handicap parking signs, although the pavement line work is practically illegible. Visitor parking is signed in this area.



Parking & drop-off loop at Marshall Road is one-way



Main Street signage is insufficient to direct visitors

Pedestrian Circulation

Pedestrians circulate outdoors via a combination of pathways, stairways and public sidewalks, which makes for some cumbersome routes between spaces and many non-accessible routes (see "Pedestrian Accessibility and Code Compliance" below).

Kid's Corner has its own pedestrian gates at Main Street and at the Marshall Road and Madison Avenue parking areas. Users of this program normally come and go from Main Street or Marshall Road. The concrete walkaways on this site are flat and generous, although there is some spalling to the surfaces.

Pathways to entrances facing Madison Avenue are all perpendicular to the public sidewalk and generally in poor condition due to surface irregularities or non-compliant slopes. The only other pathway on the site connects the main parking/drop-off loop to the pre-school entrance (Doors #3 & #4), and this consists of worn asphalt leading to a concrete riser and asphalt tread stair, also in worn condition. There are no paved pedestrian routes linking the play area to the basketball court or providing full access into the tot lot.



Worn condition of steps



Modern play components over wood mulch surfacing



Accessible path connects to broken pavement



Toddler play area on packed earth

Pedestrian Accessibility and Code Compliance

With the exception of the flat play space and building access at Kids' Corner on Main Street, none of the pathways or doorways around the building comply with MAAB or ADA.

The Madison Avenue sidewalk follows existing steep topography that cannot be modified to comply with ADA. There are four access points from this sidewalk to the school. At the highest elevation is the main entrance to the Recreation Department (Door #1). There is a parking space marked with an HP sign here although it does not meet code, and a curb ramp in the concrete sidewalk, also not to code. The concrete path has an excessive cross-slope and there are tree roots from a large oak heaving the concrete walkway slabs, although the doorway itself is flush. The next highest access point is the HP Auditorium door (Door #11). The pathway to this door is steeply sloped from the sidewalk, the combined asphalt and concrete pavement are in poor condition and run-off is directed across the pathway in front of the door, which can be a hazard in winter. The next highest access is to "Recreation and Community" (the gym). This entrance (Door #10) has four steps and is not accessible. And the lowest access point to the building on Madison is off the paved parking area. There is an access door with four steps (Door #8), an adjacent door signed for HP access but with a high threshold, and an egress only door leading to a curbed area with a drain (Door #7), which is also not accessible. The slopes and poor condition of the pavement in this area render it non-compliant.

While on-site circulation from the Madison Avenue side of the building to the Marshall Road side would require one to pass through the Kids' Corner area, pedestrians typically take the public sidewalk on Main Street. There is no sidewalk along Marshall Road and no paved pedestrian access to the site from this direction.

The Kids Corner pathways and pavement are level and in reasonably good condition with some spalling to the concrete surfaces. The ramp leading to the door is to code (has been tested and proven compliant according to staff). The marked HP space in the Marshall Street parking lot is close to this accessible entrance, although it is not the closest available space. It is unknown whether this entrance can be used to access the rest of the building interior.

Pedestrian circulation and doorways on the Marshall Road side of the building are all in violation of ADA and MAAB. The main entrance (Doors #3 and #4) is at the top of a long stairway reached via a steeply sloped asphalt path. The steps are old and uneven and all children in the pre-school must walk up these steps with their wooden handrails. There are no paved paths into the toddler play area by the building or connecting the larger play area to the basketball court, which is at a slightly higher elevation. Another doorway level with the main entrance (Door #2) faces the basketball court and is connected to it via another steep path and stairway.

The single accessible parking space in the main lot is sufficient to meet ADA and lacks only a vertical sign. The two parking spaces at the Madison Avenue lot are non-compliant in slope, surfacing and markings.

Service Areas

The building has no loading dock. Vehicles making deliveries typically park on Madison Avenue and bring goods through the main entrance. Deliveries to Kids Corner are made from the larger parking lot. In most cases, the trucks are smaller box trucks. Rarely is a semi used to make deliveries.

Courtyards / Exterior Student Gathering Spaces

The closest areas to "gathering spaces" are the picnic table areas in front of Kids Corner and the shade structure adjacent to the large play area. The former is in good condition with recently installed materials. The wooden shade structure incorporates seating and is installed over old asphalt pavement. With its raised "floor", it is not accessible.

Recreational Spaces

Play areas, for the younger children who use this building, are located on Main street (by Kids Corner) and on the Marshall Road side of the site.

The Kids Corner play area is a flat space divided about evenly into asphalt pavement and artificial turf. The only play "equipment" is a portable basketball hoop. Free play takes the form of pavement games, kickball and running. Both the pavement and the turf area are in good condition and the entire area is surrounded by chain link fencing and shaded by a massive tree. There is a storage shed for loose equipment in the corner.

The area adjacent to the parking lot below the main back entrance is occupied by a large play area containing fixed play structures by Gametime, two play houses, a 4-seat arch swing with handicap seat, some smaller climbing equipment, a shade structure and two storage sheds, all on a wood mulch play surface. This type of surface needs to be replenished in order to maintain accessibility compliance and can become uneven with use. There is a toddler-age area adjacent to the building with loose play components, a sandbox, picnic table and a separate storage shed, all shaded by a large flowering cherry. The surfacing here is earth, packed hard and uneven and a fence with gate separates this area from the pathway.

Adjacent to the large play area and slightly uphill is a paved court with two basketball nets, one permanent and one portable. The pavement has cracking throughout.

While the steep topography is subject to erosion, the children make use of it in their play. A run-off channel at the bottom of a roof drain was used as a raceway for tennis balls. In winter, the hill on the east side of the site is used for sledding.



Trees at front of school



Vegetation surrounding playground

Site Lighting

There are over-door façade-mounted fixtures on the Madison Avenue side of the building, over the entrance to Kids' Corner and one façade-mounted light facing the parking on Marshall Road. The remainder of site lighting comes from floods and acorn fixtures mounted on utility poles at the perimeter of Marshall Road and the basketball court.

Site Furnishings

There are limited site furnishings at the Mystic. Two picnic tables flanking the Kids' Corner entrance and two aluminum picnic tables in the larger play area are the only outdoor seating. None of the models is wheelchair accessible. There is a single trash barrel by the drop-off loop and an old, seemingly unused bike rack on the lawn by Main Street. Directional signage is post-mounted, mounted on the chain link fence or mounted on the building façade. Fencing varies in condition with interior fencing (at Kids' Corner and separating the parking from the play area) in better condition than the perimeter fence along Marshall Road. The larger play area, toddler play area and Kids' Corner all have associated storage sheds.

Trees, Planting, and Other Vegetation

A sprinkling of mature trees line the perimeter of the site. At Kids' Corner and by the playground picnic tables, they provide much-needed shade. A large shade trees grows adjacent to the main entrance path on Madison Avenue and the tot play area is shaded by a mature flowering cherry. All appear to be healthy. There are also a few younger shade trees planted more recently on the site. Rhododendrons and yews screen the utility cabinets at the corner of Marshall and Main. The only foundation plantings are along the Kids' Corner façade where mature evergreens occupy mulched beds. Lawns are in reasonably good condition where they are not adjacent to active play areas. But where children play, particularly along the slopes by the large play area, lawns are either heavily eroded or compacted bare earth.

CIVIL ENGINEERING

General Site Conditions

Grass in the play areas is in poor condition and there is significant erosion along the sloped areas of the landscaped play areas. The pavement in the paved play area is in poor condition with severe cracking and uneven settling.

There is no edging in the play structure area and the surfacing is wood mulch. The equipment appears to be in good condition but should be evaluated by a certified playground safety inspector. The small artificial grass play area at the front of the school is in fair condition but is a very hard surface.

The walks, paving and landscaping near the entrances along the Madison Avenue side of the school are generally in poor condition, with uneven/poor pavement and lack of grass coverage. The pre-school entrance is accessed via long set of stairs from the main parking lot.

The areas of the school that see less foot traffic along the rear and upper end of the Madison Avenue sides of the school are in good condition with good grass coverage and positive drainage away from the building.

The school site is not within any flood area there did not appear to be any wetland resources within 200 feet of the site.







Cracking and uneven pavement

Parking and Circulation

The main parking lot is located along the Marshall Road side of the school. Striping in the parking lot indicate a counter clockwise circulation. The one accessible space in the parking area is directly against a fence that restricts movement on that side of the space. The pavement in the main parking area is in good condition with some signs of minor puddling and cracking. There are no lights in the parking area.

Pavement conditions in the small parking area along the Madison Avenue side of the school is in poor condition. The pavement in the accessible parking spot is crumbling and the striping has worn away.

Utilities

There is a closed drainage system on site that the roof downspouts appear to tie into. The site is well drained with little evidence of puddling/drainage issues outside some puddling due to uneven pavement and one doorway along the Madison Avenue side of the school which has been protected with curbing and a trench drain. What appears to be a below grade pump-station with above grade transformer and switch-gear is located in the southwest corner of the site. The pump-station and associated equipment is not enclosed by fencing.

The building is connected to the town sewer system but there is no evidence of an external grease-trap. The gas meter is adjacent to the Main Street entrance in an area not accessible to vehicles.

ARCHITECTURE

Organization

The Mystic School was built in the 1920s and is approximately 26,000 square feet. The Building is entered from Madison Avenue and currently houses the Town's Recreation Department at the main level within existing room configurations. An after school program occupies the basement level. The basement level has a separate entry from the Main Street side. An addition was added to the original L shaped plan in the 1940s which more than doubled the size of the school.

Circulation

The building is 1 ½ storys with classroom spaces at both levels, accessed only by two stairways. The original auditorium space is on the Madison Avenue side and includes a separate non-ADA entry.

Program and Space Issues

The Mystic School serves the Town as a program space for all ages. The after school program in the basement is a separate program sponsored by parents and licensed by the Department of Early Education and Care. The Recreation Department provides programs year round to all ages, including an after school program, youth clinics, and adult programs. There are 9 classroom spaces of between 650 sf and 900 sf square feet at the upper level and there are five additional classroom spaces at the lower level. Comparisons with current MSBA space standards indicate that classrooms and core academic spaces are undersized. See the chart below.

	Mystic Elementary*	MSBA Standards
Classroom	580 square feet	950 square feet
Music	930 square feet	1,200 square feet
Library	930 square feet 2,020 square feet	
Art	695 square feet 1,000 square feet	
Gymnasium	1,732 square feet	6,000 square feet

^{*} Only if school becomes accessible

Physical Conditions of Exterior Envelope - Walls

The building is faced with red brick in a running bond pattern, with cast stone window sills and wood accent trim along the roof edge. The envelope appears to be in good condition. See the charts below.

Representative R-Values		
12" Brick	1.17	
3/8" Air Space	1.01	
1/2" Plaster	0.32	
TOTAL R-VALUE 2.50		
1920s: 12" exterior brick, plaster walls		

Typical Exterior Walls - Today's Minimum Requirements	
Face Brick	0.39
Air Space	2.02
Air & Vapor Barrier	0.15
1/2" Gypsum Sheathing	0.45
Insulation	22.00
Vapor Barrier	0.15
Interior Gypsum Board	0.45
TOTAL R-VALUE	25.61
WINDOW TRIPLE PANE R-VALUE	5.00

Physical Conditions of Exterior Envelope - Windows

About half of the windows are replacement windows and the rest are original single glazed windows. Some windows include large sections of glass block above venting units. The glass block areas of the windows tend be badly damaged with many blocks broken at the outer face. Other than the lack of energy efficiency, the windows appear to be functioning properly.

Physical Conditions of Exterior Envelope - Roof

The roofing is asphalt shingle at the sloping sections with membrane at the high flat areas. Generally, the roofing is in good condition. There are no signs of leaking. The roof edge and gutters also appear to be well maintained. See the charts below.

Mystic Existing Roof Condition		
Asphalt Shingles	0.40	
Fiberglass Insulation	13.00	
Structure/Ceiling	5.00	
TOTAL R-VALUE	12.40	

Roof Construction - Today's Minimum Standard		
Rubber/PVC	0.40	
4" Polyisocyanurate	30.00	
Structure/Ceiling	5.00	
TOTAL R-VALUE	35.40	

Interior

Finishes are well suited for school use and have been well maintained. Light quality varies throughout the building and is generally good, but could be improved.

Interior Partitions

In general, all interior partitions appear to be in good condition. The type of partition varies throughout the building as follows:

- Painted concrete masonry units
- Painted concrete masonry with glazed block wainscot or ceramic tile
- Painted plaster
- Ceramic tile

In a renovation, various masonry walls could be re-framed with steel studs and painted drywall to accommodate new electrical, plumbing and technology systems. Existing plaster walls to remain could be cut open to allow for new systems. All walls should have acoustical batt insulation to improve acoustical performance, however, the closets between the larger spaces and corridors provide additional acoustical separation.

Flooring

In general, all flooring is in fair to good condition. There are a few places where the VCT is broken and should be repaired. Carpet covers much of the classroom spaces and appears well maintained. The type of flooring that exists is as follows:


- Asbestos containing tile (9x9)
- Vinyl Composition tile (12x12)
- Ceramic tile
- Carpeting

Wall Base

The majority of the wall base is wood of various sizes, although some recent renovation work has installed vinyl base. At the glazed block walls, there is no additional base except the glazed block. All base material appears to be in good condition.



Storage area in classroom



Stairway leading to exit



Typical flooring in hallway



Typical classroom

Ceilings

In general, the ceiling types vary throughout. In some cases, the tile ceilings are secured to the plaster ceiling above. Some suspended ceilings have been installed below the original plaster ceilings. The existing ceilings consist of the following types:

- Suspended acoustical tile
- Painted plaster
- Acoustical tile adhered to plaster ceiling

Doors and Frames

Doors and frames vary in size and type both in metal and wood. The conditions are fair to good. However, most doors still have round knobs which do not meet the ADA requirements. It is recommended that all doors and hardware be replaced to meet compliance with handicapped accessibility requirements. Finish hardware should consist of levers.

Fire Extinguishers

All existing fire extinguishers appear to be operational and certified. Many fire cabinets do not meet ADA requirements. It is recommended to replace all fire extinguishers and cabinets with new ADA compliant cabinets.

Tackboards and Markerboards

All three types of boards exist in various sizes and conditions. Fire code regulations do not allow for tackboards to be within 5 feet of egress doors.

Regulations

The existing facility as a whole is in compliance with the original code, however, this does not mean it meets every standard of the current code. In accordance with the current code, an existing building is presumed to have met the codes and regulations in effect at the time of its construction and is allowed to continue in its use, provided it is maintained per the original code. Current building codes are applicable to any alteration or addition or change in use of the structure in accordance with 780 CMR 34.

Code Classification 780 CMR 302.1

The occupancy of the facility is non-separated mixed use with assembly and educational uses as follows:

Classrooms, Offices E-Educational Auditorium A3-Assemble

Construction Classification

Based upon the definitions in the current code, the minimum classification of the building is as follows:

1920s (Original) 3B Noncombustible 1940s (Addition) 3B Noncombustible

Chapter 34: Repair, Alteration, Addition and Change of Use of Existing Buildings

A renovation project is governed by Chapter 34. This chapter is "intended to maintain or increase public safety, health, and general welfare, without requiring full compliance with the code for new construction."

- i. Building renovation For continuation of the same use groups the building shall comply with 780 CMR 3404.0.
- ii. New Building Systems Any new building system or portion thereof shall conform to 780 CMR for new construction to the fullest extent practical.
- iii. Alterations and Repairs Alternations of repairs to existing buildings, which maintain or improve the performance of the building may be made with like material, unless required otherwise under 780 CMR 3408 Structural Requirements for Existing Buildings.
- iv. Number of Means of Egress Egress for the existing facility is sufficient in accordance with the current building code.

- v. Capacity of Exits There is sufficient egress capacity to meet current codes at the doors throughout the facility.
- vi. Length of Access Travel Shall not exceed 200 feet, in building without a sprinkler system. All areas of the existing building are within 200 feet of an exit.
- vii. Exit Signs and Lights For notes on the existing system, refer to the Electrical Existing Conditions Report.
- viii. Means of Egress Lighting Refer to the Electrical Existing Conditions Report.
- ix. Height and Area Limitations Under Chapter 34, the building is in conformance with applicable height and area limitations, so long as there is no change in use. Additions may be made to the structure.
- x. Fire Protection Systems Fire protections systems must be provided for existing building that are "substantially" altered or "substantially" renovated where required for the specific use group.
- xi. Enclosure of Stairways open egress stairways are prohibited. There shall be no minimum fire resistance rating required for an existing enclosure of a stairway.
- xii. Assembly Use Groups Any alteration within an assembly use group shall comply with the code for new construction. This applies to the cafeteria, auditorium and gymnasium
- xiii. Accessibility for Persons with Disabilities Accessibility for persons with disabilities shall be provided in accordance with the regulations of the Architectural Access Board.
- xiv. Energy Provisions for Existing Buildings Alterations to components affecting energy conservation performance shall comply with 780 CMR 13 generally, and 780 CMR 1304.2 or 780 CMR 1304.5 or 780 CMR 1309 specifically. Existing components may remain.
- xv. Evaluation of Existing Building The structural engineer shall make a structural evaluation of the existing building to determine the adequacy of all structural systems that are affected by alteration or damage to be repaired.
- xvi. Existing Lateral Load Capacity (Refer to Structural Existing Conditions Report for further information) Alterations shall not be make to elements or systems contributing to the lateral lad load resistance unless the altered lateral load resisting system conforms to 780 CMR 1611.0 and 1612.0; or there is no reduction in the lateral capacity to the building as a whole. Existing elements of systems may be reinforced or replaced with new elements or systems of equivalent strength and stiffness.
- xvii. Earthquake Loads (Refer to Structural Existing Conditions Report for further information) For no change in use groups, but alterations exceeding 50% of the assessed valuation of the building, the project is defined as Seismic Hazard Category 2.
- xviii. Earthquake resistance shall comply with the requirements of 780 CMR 3408.3.5
- xix. The provisions of 780 CMR 34 govern Fire Resistant Materials Fire resistance construction systems.

Interior Finishes 780 CMR 8

Interior trim and finishes altered as a part of a renovation shall conform to the requirements of 780 CMR 801. Flame spread of Interior Finishes for the E and A-3 use groups, shall conform to Table 803.4. Existing finishes are code compliant.

The State Fire Marshall introduced regulations in 2003 restricting display of paper in egress areas. The provisions are as follows:

- i. Paper display in classrooms shall not exceed 20% of the wall area. Measurement of wall area shall include windows and doors.
- ii. Paper display in corridors shall not exceed 10% of the wall area and shall not be placed within 5 feet of an egress door. It shall be applied directly to the wall and shall not be grouped in areas bigger than 6 feet by 12 feet.

Handicap Accessibility

Some improvements have been made over the years to comply with the Massachusetts Architectural Access Board (MAAB) regulations. For the most part the building is not in compliance with the accessibility code. The regulations require that any building undergoing a renovation where the costs exceed 30% of its assessed value must comply with the requirements of the MAAB. It is anticipated that renovation costs will exceed the 30% assessed value and would require the building to be brought up to full compliance with MAAB.

STRUCTURAL ENGINEERING

The Mystic School dates from the 1920's. It is essentially a one story building, with a basement, also built into the side of a hill. Entry off Madison Avenue is to the first floor. Entry off Main Street is to the ground level, basement. Exterior walls are brick masonry, likely built solid with Concrete Masonry Units. For its age, the exterior walls and building envelope appear to be in good overall condition.

Interior basement corridor bearing walls are CMU where not exposed, and glazed masonry units in the classroom areas. Interior walls on the first floor are plastered, possibly over wood studs.

The first floor construction consists of wood floor joists within the classroom areas and office areas, and a concrete slab, which might have had a terrazzo finish, but is now covered with vinyl tiles.

The most noticeable problem with the building appears to be the falling ceiling tiles, particularly where they were glued to the plaster ceiling. There are exposed metal anchors in many classroom and administration areas securing the tiles to the original plaster ceiling.

MECHANICAL ENGINEERING


Heating Plant

The boiler room is located on the lower level and is depressed lower (+/- 10 feet) thus making the boiler room double-height. A single HB Smith 14-section model 28 cast iron sectional boiler serves the building. The boiler is gas-fired and produces low pressure steam to heat the building. The boiler is of indeterminate age but appears to be over 30 years old. The boiler burner is a power flame gas-fired model of which is probably not 30 years old but appears to be approaching 20 years old. Both units are approaching the average service life expectancy. The boiler is vented into a masonry chimney along with the gas-fired domestic hot water heater of which is also located in the boiler room. The condensate receiver/ duplex pump boiler feed unit is leaking and water is pooling on the floor of the boiler room. It has been reported that the boiler is manually operated and does not use the outdoor air temperature to automatically activate the building heating plant. The combustion air fan serving the boiler room was not operating at the time of the survey, status unknown.

Air Systems

The only central air handling system serves the gym. This system was not operating at the time of the survey. This system is located above the stage area of which had recently experienced water damage in the drop ceiling. The cause of the damage was not determined by the survey crew. The gym is also served with cast iron steam radiators located around the perimeter in protective enclosures. The rest of the building is served with console unit ventilators. These units are +/- 50 years old and are past the expected average service life. The unit ventilators appear to be operable but the models present in the building are no longer being manufactured and spare parts would be increasingly more difficult to acquire. Centralized ducted exhaust systems serve the classrooms and toilets and were not operating at the time of the survey, status unknown.







Cracking and uneven pavement

Piping Systems

The steam supply and return systems are piped with insulated steel piping. This piping may be original to the building (1932) but has probably been replaced/modified during the history of the building. There were no reported leaks or issues with this piping but it should be regarded as past its average expected service life. The condensate return piping was noisy (one can hear the condensate flowing down the piping) on the lower level hallway. Cast iron steam radiators serve the building spaces of which most have protective covers of various vintages to protect against burning the occupants since most of these radiators are located within reach in the spaces.

Air Conditioning

The gym does have an air-cooled condensing unit located adjacent to the space on grade in one of the parking lots of the school. It was reported that this unit has been inoperable for approximately two years. This unit serves the air handling unit serving the space so the gym does not have an operable air conditioning system. There are a number of wall-mounted air conditioners located along the perimeter of the building serving various office spaces. Two classrooms in the after school

section of the building have been retrofitted with split-system air conditioning units (mini-splits) and these systems have been reported as operational.

Automatic Temperature Controls

The building is served by an antiquated pneumatic control system. This system is of indeterminate age and status but is probably over 40 years old and past its expected average service life. Uneven space temperature control results in various spaces using the windows to prevent the spaces from overheating in the heating season. The boiler controls are standalone and are fairly rudimentary. A combination of Barber Coleman and Robert Shaw thermostats are present in the various spaces indicative to repairs/modifications that have been performed over the years. Pneumatic control systems are antiquated and have not been installed in buildings for over 20 years.



Recently installed air conditioning unit



Mechanical closet

ELECTRICAL ENGINEERING

Main Electric Services

The main electric service is rated 208/120V, 400A, three-phase, four-wire. The distribution equipment is primarily manufactured by General Electric. Eversource electric services appear to originate from Eversource street pole number 94/2 along Madison Avenue. The service route is overhead from the street pole to a service weather head located on the school. The secondary service conductors enter through a mechanical space and down to the main electric service located in the school boiler mechanical room. Based on the Eversource electric meter number 5063809 and the metering nameplate multiplier of 40, the maximum demand recorded on the date of survey is 16.8 kW.

Emergency Electric Services

The school does not include an emergency generator.

Emergency lighting throughout the school appears to be provided by local battery pack luminaires. Multiple manufacturers appear to be used for these luminaires. Exit signs also appear to include battery backup. Site staff indicated that they are tested routinely and operate properly.

Fire Alarm

The fire alarm system is manufactured by Edwards (EST), 2400 Series, and appears to be in relatively good condition. The fire alarm system includes limited smoke detection or heat detection coverage throughout the school, since no fire protection systems appears evident. Manual initiation and notification devices are installed throughout the school and at all egresses. The fire alarm is connected to an exterior Master Box (#17) assumed to signal the local fire department. An exterior red beacon is located above the Master Box at the administrative entrance. Notification devices are audible only. There are no visual alarm devices inside the school.

Lighting and Lighting Controls

Luminaires and lighting controls appear to be updated in select locations, but overall are less efficient than current luminaire products. Occupancy sensors are located in administrative, classroom and gymnasium areas. Exterior lighting was adequate and appeared to include emergency lighting at exterior of building egresses.

Clock System

The central clock system is not operational according to site personnel feedback.

Audio-Visual (AV)

No visual systems were identified during survey. The school includes a fully operational Rauland MCX 1400 A public address system (circa ~1960) with integrated AM/FM radio and selective area and override controls. Speakers are located throughout the school, including each classroom. Each classroom appears to be equipped with local paging ability via the head end equipment.

Telephones

Based on observation of limited phones in the school, it appeared to include phones only for administrative areas in school and Kids Corner childcare area. Communication services appeared to be from Verizon and from multiple (three) poles along Madison Avenue (Poles 94/2, 94/3, 94/4). Classrooms and common areas rely on the central audio system for internal communications.

Security

Access control is provided with the use of American Alarm and Security Command keypad hardware and appears to operate properly. Security cameras manufactured by Comelit appear to be located only at the exterior of the school administration area entrance and the Kids Corner entrance. Both camera system locations appear to operate independent of each other.

Section 2 | Mystic Elementary School Existing Conditions

Perimeter school door alarm status contacts were not observed. It is assumed that motion detection devices detect intrusion(s).

IT Network

The main distribution frame (MDF) was located in an upper level storage room and not ventilated adequately for this type of equipment. Wireless access points (WAP) appeared to be located in some locations. Network cabling is installed in surface plastic raceways or in plain sight throughout the school for all network needs.

General Conditions

Panel boards are generally located in common corridors and not locked.

There did not appear to be any sign of main electric service equipment testing.

Spaces associated with daycare, preschool, kindergarten and early childhood education are required to include tamperproof receptacles and none were observed anywhere in the school.

Some sink locations include close proximity receptacles without ground-fault protection.

Receptacle quantities are inadequate throughout the school.

Gymnasium luminaire lenses appear to be supported in an unorthodox manner.

PLUMBING ENGINEERING

Domestic Water System

A buried 2 inch service, assumed to be connected to the main in Main Street, enters the boiler room through a utility tunnel from the west. The entry includes full-size iron gate valves and a 2 inch municipal meter that appears to be a replacement to the original building (1932). Access to the meter in the tunnel is through a covered and framed opening in the floor of a storage closet. The condition of existing iron and copper water piping is fair considering its age. Some copper piping appears to have been repaired or replaced. Insulation condition, where visible, varies with age and is showing signs of wear.

Domestic Hot Water Plant

The entire building is served by a 40 gallon, gas-fired storage heater, noted to have been installed around 2010. There is a circulator pump and a disconnected aquastat; a master mixing valve is not evident. Hot water delivery at remote fixtures is fair.

Plumbing Fixtures and Fittings

Toilet room plumbing fixtures and trim are generally in fair to good condition, some accessible fixtures were noted in renovated toilet rooms. Casework sinks and fittings are in fair condition; none of those viewed were accessible. The art room sink drain includes what appears to be a neutralizing basin. Accessibility and fixture counts for students and staff require review.





Restroom

Hanging urinals

Natural Gas Service

The gas service enters the boiler room through a utility tunnel from the meter assembly on the west exterior wall and fed from Main Street. A dedicated, submetered line directly feeds the domestic water heater and the main feeds the gas-fired steam boiler. Gas piping is in very good condition.

Sanitary, Waste and Vent Systems

The exact location of building sanitary exit(s) could not be determined by this survey. Cast iron piping, visible in the boiler room, custodial closets and crawl space appears to be original to the building and is in fair to good condition. An inoperable sump pump and basin are buried in the northwest corner of the boiler room; exact below-slab piping connections could not be determined. Below casework fixture copper drainage piping is in fair condition, there is some non-code-compliant PVC sink drainage piping.

Section 2 | Mystic Elementary School Existing Conditions

Building Storm Drainage

The location of building interior storm exit(s) could not be determined by this survey. Visible cast iron piping is in fair to good condition, insulation on interior storm piping was not noted. Exterior cast iron downspouts appear to be recent replacements and are in excellent condition.

General Condition

The building plumbing systems are in fair to good condition overall and, according to staff, there have been no recent major problems.

FIRE PROTECTION

There is no water-based fire protection within the building.

DATA/COMMUNICATION, TECHNOLOGY

Mystic School is not equipped with a significant amount of technology. There is a Lucent PBX being used by the Daycare provider using some of the space. The writer assumes that this system is owned by the user and not school property. There are some intercom components in a few areas which are antiquated and non-functional. Any future project should include an upgrade of the phone system to the district standard NEC VoIP and a replacement of the intercom system.

Distribution cabling is Category 5 and 3. Distribution of cabling is achieved with wall mounted racks and patch panels. A significant amount of the cabling has been run exposed. Any future project should include an upgrade of all cabling to the current TAI/EIA standard at the time.

There is no site or exterior video surveillance. There is an alarm keypad at the entrance. The alarm system is DMP Security Command Executive. Any future project should include an integrated security system inclusive of building and site surveillance, intrusion detection and access control.

2.7 | Parkhurst Elementary School

Landscape Architecture

Civil Architecture

Architecture

Structural Engineering

Mechanical Engineering

Electrical Engineering

Plumbing Engineering

Fire Protection

Data/Communications






Narrative Description of Property

This property contains 4.110 acres of land mainly classified as PSCHOOL with a(n) SCHOOL style building, built about 1950, having BRICK exterior and ASPHALT roof cover, with 1 unit(s), 14 room(s), 0 bedroom(s), 0 beth(s), 5 half bath(s)



Disclaimer; This information is believed to be correct but is subject to change and is not warranteed.





	SPACE SUMMARY		1		
	Room Type CORE ACADEMIC SPACES		# of Rooms	Area Total	
0			0		
	SPECIAL EDUCATION				
0		0	0		
	ART & MUSIC				
0		0	0		
	VOCATIONS & TECHNOLO	GV			
0		0	0		
	HEALTH & PHYSICAL EDU	CATION			
0			0		
	MEDIA CENTER				
0		0	0		
	DINING & FOOD SERVICE				
0		0	0		
	MEDICAL				
0		0	0		
	ADMINISTRATION & GUIDA	NCE			
0		0	0		
	CUSTODIAL & MAINTENAM	ICE			
0			0		
	OTHER				
58	58	27914	58		
	Corridor	311	1 1		
	Storage Toilet	805 146	1		
	Passage	306	1		
	Storage Storage	300 370	<u> </u>		
	Storage	956	1		
	Storage Toilet	794 94	<u>1</u> 1		
	Storage	601	1		
	Corridor Storage	1785 865	<u> </u>		
	Storage	948	1		
	Custodial Boiler Room	640 534	1		
	Toilet	136	1		
	Stage Gymnasium	463 3011	1		
	Storage	654	1		
	Storage Storage	603 173	<u>1</u>		
	Storage	177	1		
	Toilet Toilet	147 67	<u> </u>		
	Office	611	1		
	Storage Office	180 586	1		
	Office	651	1		
	Corridor Toilet	755 148	<u>1</u> 1		
	Office	588	1		
	Vestibule Corridor	229 1629	<u>1</u> 1		
	Toilet	87	1		
	Toilet Storage	87 127	<u>1</u> 1		
	Office	583	1		
	Storage Office	163 599	<u> </u>		
	Storage	186	1		
	Toilet Office	66 1225	<u>1</u> 1		
	Office	124	1		
	Office Office	153 121	1 1		
	Toilet	44	1		
	Toilet Toilet	145 148	1		
	Storage	178	1		
	Fan Rm	61	1		
	Office Office	593 759	1		
	Storage	177	1		
	Storage Toilet	185 153	1 1		
	Storage	73	1		
	Professional Development Professional Development	807 807	<u> </u>		
	TOTAL BUILDING GROSS I	FLOOR AREA 37653	2		
	Floor 1 Floor 1	17925 19728	1		

SPACE SUMMARY				
Room Type	Room NFA	# of Rooms	Area Tot	al
CORE ACADEMIC S		-1	-	
	0	0	0	
SPECIAL EDUCATION		-1	-	
	0	0	0	
ART & MUSIC			<u> </u>	
	0	0	0	
VOCATIONS & TECH				
	0	0	0	
HEALTH & PHYSICA				
	0	0	0	
MEDIA CENTER				
	0	0	0	
DINING & FOOD SEE				
	0	0	0	
MEDICAL				
	0	0	0	
ADMINISTRATION &				
	0	0	0	
CUSTODIAL & MAIN				
	0	0	0	
OTHER				
	12	27914	58	
Boiler Room		534	1	
Corridor		4480	4	
Custodial		640	1	
Fan Rm		61	1	
Gymnasium		3011	1	
Office		6593	12	
Passage		306	1	
Professional Develop	ment	1614	2	
Stage		463	1	
Storage		8515	20	
Toilet		1468	13	
Vestibule		229	1	
TOTAL BUILDING G	ROSS FLOOR AREA			
	2	37653	2	
Floor 1		17925	1	
Floor 1		19728	1	

LANDSCAPE ARCHITECTURE

General

The Parkhurst School is located on a steeply sloped hill within a residential neighborhood and sits adjacent to the Mount Pisgah conservation area. Mount Pisgah, also known as Andrews Hill, is the highest point in the Town of Winchester and portions of this site offer spectacular views to the Middlesex Fells and beyond.

The facility no longer functions as a school, but serves as the Central Administration building for the School Department, housing Human Resources, Special Ed, and offices of the Superintendent and Assistant Superintendent, among others. Approximately fourteen people work in the building. Professional Development classes are held after school, and Winchester School Committee meetings are held at night in the modular classrooms structure. The building recently served as a swing space while the Vinson-Owen School was being renovated. The bottom floor of the building is currently not used. A playing field and playground behind the building are used by the Recreation Department and by neighbors.

Vehicular Access & Circulation

There are two vehicular access points to the site. A drop-off loop and parking area are located off Andrews Road where circulation is one-way with separate entry and exit points. There is no signage at the entrance to the parking area but there is a sign identifying the building off Andrews Road. A steep driveway from Samoset Road leads uphill to the lower parking and service area. The sign here reads "Gym Access". There is no vehicular circulation around the building. In an emergency, an ambulance or fire truck would likely come to the Andrews Road loop.



Handicap parking at service area with pedestrian ramp to door



Drop-off at parking loop leading to modular classrooms doorway

Parking Location, Arrangement & Quantity

The main parking lot is incorporated into the one-way drop-off loop and includes 28 lined spaces and two handicap spaces, as required by MAAB. Spaces closest to the building entrance are signed for staff members or marked for handicap use. There is a marked cross-walk from the handicap spaces with a curb cut at the front path. The pavement is in reasonably good condition and the line paint is clear. A second area for parking is designated at the lower, service lot where there are two regular parking spaces and one handicap space. For larger events such as field games or night classes, cars often park along Andrews Road.

Pedestrian Circulation

Circulation into the site from the surrounding neighborhood is a challenge, due to the steep slopes. There are sidewalks on Samoset only to the intersection with Emerson Road and up Andrews Road only as far as the parking lot entrance. These are all in poor condition.

Although the lower level of the school facing Samoset Road is not currently used except for service, the service area connects to a second paved area via a narrow path around the gym. This second area once faced a series of schoolrooms and was used for outdoor exercise. The pedestrian way dead-ends at the north end of the building where slopes are too steep to fit a pathway.

Most of the pedestrian pavement is asphalt (bituminous concrete), and the drop-off loop has asphalt curbing. The walkways around the loop are in moderate to poor condition, with patching, cracks and degraded edges. This pavement extends along the west side of the building, connecting to the modular classrooms entrance and the play area where it dead-ends at the end of the modular classroom structure.

Pedestrian Accessibility & Code Compliance

The two primary entrances – the main door at the end of the building facing Andrews Street and the doorway to the modular classrooms— have both been made accessible, the first by ramping the asphalt path up to the concrete door stoop and the second, by use of a wooden ramp with steel handrails. The asphalt pavement leading from the drop-off loop to these two doorways is in variable condition. Some of it is patched and broken, and does not meet the requirements of a compliant walking surface. While Door #15, the service door, has an accessible concrete ramp, most other doorways (Doors #2-5 facing the drop-off loop, Doors #9-12 at the lower paved area, Doors #15 and 16 at the gym and service area) have at least one concrete step and high thresholds.







Abandoned lower courtyard

There are three concrete curb cuts with ADA tiles that seem to have been recently installed around the curbed drop-off loop. While these are in good condition, the asphalt pavement around the concrete is settling and this differential creates a lip that makes the surface uneven and therefore, not to code.

The steep site makes movement from one area to another difficult. There is no accessible route from the lower parking level of the site to the upper parking level or from the upper parking level to the field level. The sidewalk starting at the Andrews parking lot and looping around Samoset Road is in poor condition and must follow the steep topography. There is no sidewalk or walkway leading into the fields from Andrews Road and access from the school requires walking across lawn to a set of concrete stairs, one of several on the site. With the exception of the stair closest to the main entry, there are no handrails at any of the exterior stairs, including the stairs to the gym.

The number of accessible parking spaces is adequate for the size of the parking lot. They are located and signed correctly and are in good condition. The play area with its uneven wood mulch surfacing is inaccessible and would require either a ramp down into the loose surfacing area or resilient surfacing paths to the structures.



Lighting at modular classrooms



Worn turf



Playground



Healthy field turf contrasts with worn turf at sloping embankment

Service Areas

The service area, accessible from Samoset Road, has no loading dock. Pallets are dropped off on the pavement and supplies carried in through normal doorways. Small dumpsters are also serviced here. Trailers rarely deliver to this building. There is adequate room for vehicles to turn within the space and to drive out forward. The pavement and concrete retaining wall are in good condition.

Courtyards/Exterior Gathering Spaces

There are currently no visually appealing or truly functional outdoor gathering spaces at the site. The inaccessible, abandoned "lower courtyard" is paved with broken asphalt, but has potential as a "terrace" with great views to the Middlesex Fells if some of the adjacent vegetation is cleared and the doorways are made accessible.

On the west side of the building along the drop-off loop, there is potential to create a gathering space with access to the main building and Annex doorways, the play area and the parking lot. But this space is poorly paved and has no plantings or furnishings such as benches or other amenities. The surroundings include an unsightly, poorly-screened oil tank close to the play area.

Recreation Spaces

A playground is located behind the building, accessible by the asphalt sidewalk. Two fairly new structures by Playworld Systems offer age-appropriate play. For older children, there are overhead components and a shaded "hang-out" space; for younger children, a structure with slides, easy climbers and play panels. The surfacing is wood mulch and very uneven with no containing edge. This area is used by children from the neighborhood and by younger children whose older siblings are using the field, but it does not get much use.

There is a basketball pole nearby but the surrounding pavement is cracked and buckled.

The playing field, adjacent to and roughly four and a half feet in elevation above the playground and parking area, includes a skinned softball infield, the infield area of dirt, and backstop. The Recreation Department uses this field for softball, soccer, T-ball and archery, but it is not extensively used. Access to the field is either from along Andrews Road, a dead-end street which has no sidewalk, or via the concrete steps behind the playground. There is no pathway to these steps. The backstop is in good condition but the bench is a wooden, make-shift model. The infield was full of dead weeds on the day of our visit, but maybe had not yet been maintained for the season. It's unclear whether the right field space is adequate for league play as the edges of the field slope steeply up to the adjacent conservation land. There are several catch basins in back of the left field line along the top of the embankment. The "abandoned" pavement outside the first level of the school shows signs of having once been used for activities, primarily pavement games and tetherball. This entire area is in very poor condition and lacks code-compliant access.

Site Lighting

The main parking lot and adjacent play area are lit by floodlights mounted on utility poles. The field is un-lit. Building-mounted lights are located on the façade of the Annex structure.

Site Furnishings

There are few furnishings on this site. They are limited to the flagpole, located halfway up the slope along Andrew's Road, an identifying sign (illustrated above under "Vehicular Access"), a wooden players' bench at the softball backstop and chain link fencing along the paved service and "courtyard" spaces outside the building's first floor. There are no other benches, nor are there trash receptacles or bike racks on the site.

Trees, Planting & Other Vegetation

There are a number of impressive mature pines and shade trees along the slopes on the east side of this site, all of which are in need of pruning. While trees are dotted along the slope at the south end of the building (by the main entrance), they are clustered more heavily along the edges of the first floor paved spaces, just outside the chain link fence. Several of the larger trees are dead and at least one has already fallen over. The over-growth surrounding the trees on the slopes that face Emerson Road is badly in need of maintenance. Erosion on these steep slopes is kept in check by the dense planting, but there are half-fallen trees and other detritus (including an abandoned concrete stairway) in this area. In contrast to the east side of the building, the west side has no trees at all. With the exception of a couple of evergreen shrubs by the main doorway, there are no foundation plantings anywhere around the building.

The lawns are in variable condition with some erosion along the steeper slopes. Turf at the playing field is in reasonably good condition.

CIVIL ENGINEERING

General Site Conditions

The site is located at the top of a hill with the play fields located behind the building. The grass in the playfield area is in good condition although the grading in the field appears somewhat uneven. The play structure appears current but there is no defined edge or curbing to the play structure area and the surface is primarily a mix of stone, dirt and mulch.

There are signs of water damage along the base of the modular classrooms, possibly the result of accumulation of leaves not allowing for water to flow away from the structure. A large above-grade steel oil tank sits adjacent to the modular classrooms. The tank was behind a chain link fence but there were no bollards protecting the tank from vehicles.

There are no flood plains on the site and there does not appear to be any wetland resource areas within 200 feet of the site. The site fencing is in poor conditions and many of the large trees on the site have visible damage and appear to be in decline.

Parking and Circulation

The primary parking area is accessed off of Andrews Road with a small semi-circular drive with some striped parking along the sides. The pavement in the parking area is in good condition and there is one light in the parking lot. Portions of the rear of the site appear to have been recently repaved. Paving in the remainder of the site is in generally poor condition with extensive cracking and numerous patching. Concrete curb cuts have been installed in several locations to provide an accessible path from the parking area to the school.

Utilities

There is a closed drainage system on site that serves the rear of the school and the main parking area and includes a large sub-surface infiltration area under the parking lot. The roof drains at the rear of the school are tied into this system. Roof drains for the rest of school generally consist of downspouts discharging at grade. The school is tied into the town's sanitary sewer system and there is no external grease trap.

ARCHITECTURE

Organization

The Parkhurst School was built in the late 1940s and is approximately 25,800 square feet. The building currently houses the School Department Central Office at the main level within existing classroom configurations. It was recently upgraded with accessible hardware, signage and repainting when it was used as swing space for the Vinson Owen school project.

Circulation

The building is two levels. The main school classroom level and a basement level housing the auditorium/gym and a few classroom spaces. There is no elevator to the lower lever and the lower level is now used only for storage.

Program and Space Issues

There are 9 classroom spaces at the upper level including two classrooms in a modular addition, and three original classrooms at the lower level, of approximately 700 square feet. The two classroom, modular addition is currently used for conference rooms. Comparisons with current MSBA space standards indicate that classrooms and core academic spaces are undersized. See the chart below.

	Parkhurst Elementary*	MSBA Standards
Classroom	600 square feet	950 square feet
Music	950 square feet 1,200 square feet	
Library	1,225 square feet 2,020 square feet	
Art	950 square feet 1,000 square fee	
Gymnasium	3,011 square feet 6,000 square feet	

^{*} Only if school becomes accessible

Physical Conditions of Exterior Envelope - Walls

The building is faced with red brick with cast stone window sills and has a low slope gabled roof. The large steel window units have been modified with plywood and plaster panels used to cover original existing glass block sections. The envelope appears to be in good condition considering the age of the structure. The modular addition at the north side of the school is wrapped with vinyl siding and appears to be in good condition. See the charts below.

Representative R-Values		
12" Brick	1.17	
3/8" Air Space	1.01	
1/2" Plaster	0.32	
TOTAL R-VALUE	2.50	
1940s: 12" exterior brick, plaster walls		

Typical Exterior Walls - Today's Minimum Requirements	
Face Brick	0.39
Air Space	2.02
Air & Vapor Barrier	0.15
1/2" Gypsum Sheathing	0.45
Insulation	22.00
Vapor Barrier	0.15
Interior Gypsum Board	0.45
TOTAL R-VALUE	25.61
WINDOW TRIPLE PANE R-VALUE	5.00

Physical Conditions of Exterior Envelope - Windows

The metal windows are all original. Most of the windows are of the type that have a large glass block upper section with venting lower sections. Most of the glass block areas have been covered over, however the units in the rear of the school are not covered and many of the glass blocks are damaged. Other than the lack of energy efficiency, the windows appear to be functioning properly.

Physical Conditions of Exterior Envelope - Roof

The roofing is currently rubber membrane on a sloping surface. The roof edge has been damaged at the auditorium section. The gutter, edge and trim have been ripped open. This is something that should be addressed right away to prevent water infiltration into the building. The rubber membrane replaced asphalt shingles. The rubber does not hold snow the way asphalt does and it appears that ice dams and icicles formed on these edges during the winter are responsible for the damage at the auditorium roof edge. The copper downspouts have been replaced with PVC pipe. See the charts below.

Parkhurst Existing Roof Condition		
Asphalt Shingles	0.40	
Fiberglass Insulation	13.00	
Structure/Ceiling	5.00	
TOTAL R-VALUE	12.40	

Roof Construction - Today's Minimum Standard		
Rubber/PVC	0.40	
4" Polyisocyanurate	30.00	
Structure/Ceiling	5.00	
TOTAL R-VALUE	35.40	

Interior

Finishes are well suited for school use and are well maintained. There was a minor renovation recently when the school was used for swing space for the Vinson-Owen project. Light quality varies throughout the building and is generally good, but could be improved.

Interior Partitions

In general, all interior partitions appear to be in good condition. The partitions are plaster with some areas of drywall and all original wood trim.

In a renovation, to accommodate new electrical, plumbing and technology systems the plaster and drywall walls could be cut open. All walls should have acoustical batt insulation to improve acoustical performance.

Flooring

The floors are all covered with carpet, except in the toilet areas which are terrazzo. They are generally in good condition.

Wall Base

The majority of the wall base is wood of various sizes, although some recent renovation work has installed vinyl base. All base material appears to be in good condition.

Ceilings

The ceiling types vary, but the majority of the ceilings are 12x12 acoustical tiles secured in place with wood battens. Some spaces have plaster ceilings.

Doors and Frames

Doors and frames vary in size and type both in metal and wood. The conditions are good and all have been upgraded to lever hardware.

Fire Extinguishers

All fire extinguishers appear to be operational and certified.

Tackboards and Makerboards

All boards appear to be in good condition. Fire code regulations do not allow for tackboards to be within 5 feet of egress doors.

Regulations

The existing facility as a whole is in compliance with the original code, however, this does not mean it meets every standard of the current code. In accordance with the current code, an existing building is presumed to have met the codes and regulations in effect at the time of its construction and is allowed to continue in its use, provided it is maintained per the original code. Current building codes are applicable to any alteration or addition or change in use of the structure in accordance with 780 CMR 34.



Typical flooring in school hallways



Handicap accessibility ramp



Recently repaved parking lot



Steel oil tank adjacent to modulars



Signs of water damage along the base of the modulars



Classroom chalkboards

Code Classification 780 CMR 302.1

The occupancy of the facility is non-separated mixed use with assembly and educational uses as follows:

Classrooms, Offices E-Educational Auditorium A3-Assemble

Construction Classification

Based upon the definitions in the current code, the minimum classification of the building is as follows:

1940s (Original) 3B Noncombustible

Chapter 34: Repair, Alteration, Addition and Change of Use of Existing Buildings

A renovation project is governed by Chapter 34. This chapter is "intended to maintain or increase public safety, health, and general welfare, without requiring full compliance with the code for new construction."

- i. Building renovation For continuation of the same use groups the building shall comply with 780 CMR 3404.0.
- ii. New Building Systems Any new building system or portion thereof shall conform to 780 CMR for new construction to the fullest extent practical.
- iii. Alterations and Repairs Alternations of repairs to existing buildings, which maintain or improve the performance of the building may be made with like material, unless required otherwise under 780 CMR 3408 Structural Requirements for Existing Buildings.

- iv. Number of Means of Egress Egress for the existing facility is sufficient in accordance with the current building code.
- v. Capacity of Exits There is sufficient egress capacity to meet current codes at the doors throughout the facility.
- vi. Length of Access Travel Shall not exceed 200 feet, in building without a sprinkler system. All areas of the existing building are within 200 feet of an exit.
- vii. Exit Signs and Lights For notes on the existing system, refer to the Electrical Existing Conditions Report.
- viii. Means of Egress Lighting Refer to the Electrical Existing Conditions Report.
- ix. Height and Area Limitations Under Chapter 34, the building is in conformance with applicable height and area limitations, so long as there is no change in use. Additions may be made to the structure.
- x. Fire Protection Systems Fire protections systems must be provided for existing building that are "substantially" altered or "substantially" renovated where required for the specific use group.
- xi. Enclosure of Stairways open egress stairways are prohibited. There shall be no minimum fire resistance rating required for an existing enclosure of a stairway.
- xii. Assembly Use Groups Any alteration within an assembly use group shall comply with the code for new construction. This applies to the cafeteria, auditorium and gymnasium
- xiii. Accessibility for Persons with Disabilities Accessibility for persons with disabilities shall be provided in accordance with the regulations of the Architectural Access Board.
- xiv. Energy Provisions for Existing Buildings Alterations to components affecting energy conservation performance shall comply with 780 CMR 13 generally, and 780 CMR 1304.2 or 780 CMR 1304.5 or 780 CMR 1309 specifically. Existing components may remain.
- xv. Evaluation of Existing Building The structural engineer shall make a structural evaluation of the existing building to determine the adequacy of all structural systems that are affected by alteration or damage to be repaired.
- xvi. Existing Lateral Load Capacity (Refer to Structural Existing Conditions Report for further information) Alterations shall not be make to elements or systems contributing to the lateral lad load resistance unless the altered lateral load resisting system conforms to 780 CMR 1611.0 and 1612.0; or there is no reduction in the lateral capacity to the building as a whole. Existing elements of systems may be reinforced or replaced with new elements or systems of equivalent strength and stiffness.
- xvii. Earthquake Loads (Refer to Structural Existing Conditions Report for further information) For no change in use groups, but alterations exceeding 50% of the assessed valuation of the building, the project is defined as Seismic Hazard Category 2.
- xviii. Earthquake resistance shall comply with the requirements of 780 CMR 3408.3.5
- xix. The provisions of 780 CMR 34 govern Fire Resistant Materials Fire resistance construction systems.

Interior Finishes 780 CMR 8

Interior trim and finishes altered as a part of a renovation shall conform to the requirements of 780 CMR 801. Flame spread of Interior Finishes for the E and A-3 use Groups, shall conform to Table 803.4. Existing finishes are code compliant.

The State Fire Marshall introduced regulations in 2003 restricting display of paper in egress areas. The provisions are as follows:

- i. Paper display in classrooms shall not exceed 20% of the wall area. Measurement of wall area shall include windows and doors.
- ii. Paper display in corridors shall not exceed 10% of the wall area and shall not be placed within 5 feet of an egress door. It shall be applied directly to the wall and shall not be grouped in areas bigger than 6 feet by 12 feet.

Section 2 | Parkhurst Elementary School Existing Conditions

Handicap Accessibility

Some improvements have been made over the years to comply with the Massachusetts Architectural Access Board (MAAB) regulations. For the most part the building is not in compliance with the accessibility code. The regulations require that any building undergoing a renovation where the costs exceed 30% of its assessed value must comply with the requirements of the MAAB. It is anticipated that renovation costs will exceed the 30% assessed value and would require the building to be brought up to full compliance with MAAB.

STRUCTURAL ENGINEERING

The Parkhurst School is currently used for School Administration. The building is a one story brick building, with a gable roof, built into the side of a hill. The building reportedly dates from the 1940's. Outside grade is at the first floor level on the west and south elevations, dropping of sharply to the east. On the east side, there is a 2 story high auditorium at the basement level. The auditorium seems to be used for storage now due to accessibility issues.

The first floor is framed with 4x14 wood joists in the classroom areas, and 2x14 joists in the corridor. The floor framing appears adequate for classroom and business use. The roof is likely framed with wood rafters or trusses. Structurally, the building appears to be in good condition.

There are modular classrooms on the west side. They also appear in good condition, with some wear on the corridor floor.

The building has been re-roofed with an EPDM roof on all the gable roofs. This has created a problem on the auditorium roof where sliding snow has ripped off the gutter. This is likely to happen at other locations as well, as the smooth EPDM offers no resistance to sliding snow. The damaged roof area should be repaired to prevent damage from wind lifting the membrane.

MECHANICAL ENGINEERING

Heating Plant

The boiler room is located on the lower level and of which the boiler room is depressed lower (+/- 8 feet) thus making the boiler room double-height. A single HB Smith 10-section model 450 Mills cast iron sectional boiler serves the building. The boiler is gas-fired and produces low-pressure steam to heat the building. The boiler is of indeterminate age but appears to be over 40 years old. The boiler burner is an Industrial Combustion gas-fired model (of which had its motor replaced recently) and appears to be 20 to 30 years old. Both units are approaching, if not exceeding, the average service life expectancy. The boiler is vented into the masonry stack with fairly new breeching. We speculate that the original system was abated of asbestos and replaced. The boiler is served with a duplex condensate receiver/pump unit of indeterminate age. It has been reported that the boiler is manually operated and does not use the outdoor air temperature to automatically actuate the building heating plant. It is noted that a fairly new, above-ground double-walled fuel oil storage tank (approximately 5000 gallons) has been locate adjacent to the modular building extension. It has been reported that the system was never filled with heating oil and, since the boiler is gas-fired, its purpose for being at the site is unknown.

Air Systems

The only central air handling system serves the gym. This system was not operational at the time of the survey. This system is located in the back of the gym, elevated above the ceiling. The gym is also served with recessed cabinet unit heaters located around the perimeter. The rest of the building is served with console unit ventilators. These units are +/- 50 years old and are past the expected average service life. The Unit Ventilators appear to be operable but the models present in the building are no longer being manufactured and spare parts would be increasing more difficult to acquire. Centralized ducted exhaust systems serve the classrooms and bathrooms the roof mounted exhaust fans are objectionably noisy from both the interior and exterior of the building. A two-classroom modular building is attached to the school. These classrooms are conditioned using self-contained, exterior wall-hung gas-fired HVAC units of which are ducted in the ceiling cavity serving these spaces. The modular building extension appears to be less than 5 years old and is in good operational condition.

Piping Systems

The steam piping system is insulated steel and is routed throughout the building where a good deal of the condensate return system is located in a crawlspace off of the boiler room. This piping may be original to the building (1940's vintage) but has probably been replaced/repaired/modified during the history of the building. There were no reported leaks or issues with this piping but it should be regarded as past its average expected service life. Cast iron radiators and convectors serve the building spaces with some of the protective enclosures missing and some of these units disconnected completely.

Air Conditioning

The building perimeter has wall-mounted air conditioners in most of the spaces. These residential units include localized manual controls. The building is presently used as an administration building where the school administration offices populate the building. The modular building extension includes self-contained air conditioning units that also provide the building heat. These units include modern programmable thermostats enabling precise temperature control of these spaces. The school department IT server system appears to be located in one of the lower level spaces (former classroom) and it was not determined if the space overheats due to this equipment since no air-conditioning systems were observed serving this space.

ELECTRICAL ENGINEERING

Main Electric Services

One main electric service to the modular classroom spaces is rated 120/240V, 200A, single-phase, three-wire. The service load center for the modular classroom spaces is manufactured by Cutler-Hammer. Eversource electric services appear to originate from Eversource street pole number 345/2 along Andrews Road. The service route is overhead from the street pole to a main service mast mounted to the modular classroom structure. The second service (original) is installed underground from Eversource street pole number 345/1 along Andrews Road to the main electric service located in the lower level of the main school building. The second (original) service is rated 120/240V, 400A, single-phase, three-wire. The quantity of pole service conductors and panel board nameplates throughout the school indicate single-phase service, but the main (original) service disconnect nameplate indicates three-phase. Based on the Eversource electric meter (base building, not portable classrooms) number 5058162 and the metering nameplate multiplier of 40, the maximum demand recorded on the date of survey is 19.2 kW. The school appears to be used only for administrative purposes at the time of survey and is not employed for school functions other than the periodic school committee meetings.

Emergency Electric Services

The school does not include an emergency generator. Emergency lighting throughout the school appears to be provided by local battery pack luminaires. Multiple manufacturers appear to be used for these luminaires. Many exit signs also appear to include battery backup.



Modular classrooms



Generator for modular classrooms

Fire Alarm

The fire alarm system is manufactured by Mircom, Model FX-2000. The panel also supports the fire alarm devices and functions in the modular classrooms. The fire alarm system includes full, but limited, smoke and heat detection coverage throughout the school, since no fire protection systems appears evident. Manual initiation and notification devices are installed throughout the school and at most egresses. Individual classroom egresses do not include manual initiation devices at exterior egress doors. The fire alarm appears to be connected to a Digitize panel (#15) assumed to signal the local fire department. There is a red fire alarm beacon located outside the school main entrance.

Lighting and Lighting Controls

Luminaires, primarily fluorescent with a few incandescent, appear to be very old in most locations throughout the school. Occupancy sensors are located in many administrative and classroom areas. Gymnasium lighting is manually controlled. Exterior lighting appears minimal. No emergency lighting was observed at exterior of building egresses.

Clock System

There appears to be a functional central clock system in the school. The main clock control panel was not identified during survey.

Audio-Visual (AV)

There is no AV equipment in any classrooms or function rooms in the original school spaces. One of the portable classrooms includes three cameras and sound equipment for public cable television access to the school committee meetings.

Telephones

There was no staff to confirm type of operation, but telephones appear to be integrated services digital network (ISDN) based on observed communications circuiting and research of WIN Communications Corporation. Communications appears to be connected to Eversource street pole number 345/2 along Andrews Road for the portable classrooms and Verizon street pole number 11 along Emerson Road.

Security

Access control is provided with the use of Security Command products and hardware and appears operational based on occupant feedback. Unless well hidden, security cameras were not observed. Building entrances do not appear to include alarm status indications, but motion sensor devices are strategically located within the school. There was one access control keypad observed at the main entrance door.

IT Network

The main distribution frame (MDF) was located in the lower level, adjacent to the main (original) electric service equipment, and not ventilated adequately for this type of equipment. Wireless access points (WAP) were not observed. Other than communications network distribution, there did not appear to be any data network distribution, or limited at best.

General Conditions

Electrical code clearances and proximity to non-electric systems and components is not met in many locations. Storage of supplies and debris is impeding access to electrical panel boards in many locations throughout the school.

There did not appear to be any sign of main electric service equipment testing.

Very few battery backup luminaires in the base building and the modular classrooms operated when the test switch was activated.

Spaces associated with daycare, preschool, kindergarten and early childhood education are required to include tamper proof receptacles and none were observed anywhere in the school. Receptacle safety inserts do not meet this requirement.

Exterior egress luminaries do not appear supported with a backup source.

Many sink locations do not include a ground-fault protection receptacle. There were no receptacles at these locations.

There are inadequate quantities of convenience receptacles throughout the school.

There was no record of fire alarm testing observed.

Smoke detection appeared to be limited only to common corridor areas. Full smoke detection coverage is required for buildings with no fire protection system.

Main electric service grounding electrode conductor did not appear to be connected at the main water entrance. It appeared to be connected to local building water pipe distribution.

PLUMBING ENGINEERING

Domestic Water System

The buried 3 inch service indicated on the original design drawings (1942) was not accessible at the time of our visit. The line, assumed to be connected to the main in Emerson Road, enters the boiler room through a utility tunnel from the east. The condition of existing iron and copper water piping inside the boiler room is fair considering its age. Some copper piping appears to have been repaired or replaced. Insulation condition, where visible, varies with age and is showing signs of wear.

Domestic Hot Water Plant

The entire building is served by a 60 gallon, gas-fired storage heater with a manufacture date of May 2011. There is a circulator pump and a master mixing valve on the system. Hot water delivery at remote fixtures is adequate.

Plumbing Fixtures and Fittings

Toilet room plumbing fixtures and trim are generally in fair to good condition, accessible fixtures were noted in recently renovated toilet rooms (2011). Casework sinks and fittings are in fair condition; none of those viewed were accessible. Accessibility and fixture counts for students and staff require review.

Natural Gas Service

The gas service enters the boiler room from the meter assembly directly outside the boiler rjoom on the west exterior wall; the main appears to be in Andrews Road. The main line feeds the boiler and the domestic water heater; a 1-1/2 inch branch run on the building exterior to feed an exterior, wall unit on the temporary classrooms. Gas piping is in good condition.

Sanitary, Waste and Vent Systems

The exact location of building sanitary exit(s) could not be determined by this survey. Cast iron piping, visible in the Boiler Room and utility tunnel, appears to be original to the building and is in fair to good condition. A sump pump and basin are buried in the corner of the Boiler Room; exact below-slab piping connections could not be determined. Below casework fixture copper drainage piping is in fair condition, there is some non-code compliant PVC sink drainage piping.

Building Storm Drainage

The location of building interior storm exit(s) could not be determined by this survey. Visible cast iron piping is in fair to good condition, insulation on interior storm piping was not noted. Exterior downspouts appear to be recent replacements and are fabricated with PVC electrical conduit.

General Condition

The building plumbing systems are in fair to good condition overall and, according to staff, there have been no recent major problems.

FIRE PROTECTION

There is no water-based fire protection within the building.

DATA/COMMUNICATIONS, TECHNOLOGY

Parkhurst is currently being used as District Offices. It is equipped with a new NEC 8300 VoIP phone systems. The system is redundant to the new system at Vinson Owen Elementary School. There are IP handset at all desk locations. There is an antiquated Simplex intercom system that does not appear to be in working order. Sapling clocks are in working order but do not appear to be synchronized. Any future project should include a replacement of the intercom system.

Distribution of cabling is achieved with a free standing rack and patch panels in the basement. Cabling is Category 5 and 3. A significant amount of the cabling has been run exposed. There are typically either two or three data jacks in the general vicinity of each workspace location. Any future project should include an upgrade of all cabling to the current TAI/EIA standard at the time.

There is no site or exterior video surveillance. There is an access control system and an alarm keypad at the entrance. The alarm system is DMP Security Command Executive. Any future project should include an integrated security system inclusive of building and site surveillance, intrusion detection and access control.



WINCHESTER PUBLIC SCHOOLS

Fifteen Year Enrollment History & Five/Ten Year Projections Prepared: October 15, 2015

Census Projection Model for Kindergarten Projections

Year	К	1	2	3	4	5	6	7	8	9	10	11	12	Total	9-12	6-8	K-5
2001-02	243	285	268	277	280	280	311	270	258	230	227	229	220	3378	906	839	1633
2002-03	252	282	301	268	276	285	285	308	274	239	227	231	220	3448	917	867	1664
2003-04	274	298	286	311	266	281	282	278	308	272	233	213	222	3524	940	868	1716
2004-05	270	326	300	286	302	262	290	279	280	305	267	234	205	3606	1011	849	1746
2005-06	307	306	336	313	288	311	267	295	282	264	294	264	234	3761	1056	844	1861
2006-07	289	349	314	346	310	294	315	266	294	275	266	296	258	3872	1095	875	1902
2007-08	259	324	357	318	345	309	309	309	271	282	276	266	277	3902	1101	889	1912
2008-09	314	310	331	364	320	356	318	306	315	264	280	270	267	4015	1081	939	1995
2009-10	298	368	335	345	381	324	368	308	310	280	256	270	266	4109	1072	986	2051
2010-11	345	336	371	352	330	379	325	361	307	274	282	255	279	4196	1090	993	2113
2011-12	331	378	351	372	351	337	374	316	357	284	275	274	259	4259	1092	1047	2120
2012-13	303	352	389	342	367	352	339	378	318	330	282	278	277	4307	1167	1035	2105
2013-14	324	338	358	391	354	371	359	335	377	392	319	271	268	4357	1150	1071	2136
2014-15	318	361	342	367	398	354	373	365	335	336	282	316	275	4422	1209	1073	2140
2015-16	328	347	373	365	377	391	363	381	362	294	335	279	315	4510	1223	1106	2181

1 Year Rate	109%	103%	107%	103%	98%	103%	102%	99%	88%	100%	99%	100%
3 Year Rate	111%	102%	103%	103%	100%	102%	101%	100%	90%	98%	98%	99%
5 Year Rate	110%	103%	101%	101%	100%	101%	100%	100%	91%	98%	98%	100%
10 Year Rate	112%	103%	102%	101%	101%	102%	99%	100%	92%	99%	99%	99%
15 Year Rate	114%	103%	102%	100%	101%	102%	99%	100%	93%	99%	99%	99%


Year	К	1	2	3	4	5	6	7	8	9	10	11	12	Total	9-12	6-8	K-5
2016-17	328	363	354	385	375	376	398	366	380	324	287	328	277	4541	1216	1143	2181
2017-18	325	363	371	366	395	374	383	401	365	340	317	281	326	4606	1264	1148	2194
2018-19	325	360	371	383	375	395	380	386	400	327	332	310	279	4622	1248	1166	2208
2019-20	325	360	367	383	393	375	401	384	384	358	319	325	308	4682	1310	1169	2202
2020-21	325	360	367	379	393	392	381	405	382	344	350	313	323	4714	1330	1168	2216
2021-22	325	360	367	379	389	392	399	384	403	342	336	343	310	4730	1332	1186	2212
2022-23	325	360	367	379	389	388	399	402	383	361	334	330	340	4758	1365	1184	2209
2023-24	325	360	367	379	389	388	395	402	401	343	353	328	327	4757	1350	1198	2209
2024-25	325	360	367	379	389	388	395	398	401	359	335	346	325	4768	1365	1194	2209
2025-26	325	360	367	379	389	388	395	398	397	359	350	328	343	4780	1381	1190	2209
Average	325	360	367	379	388	386	392	393	390	346	331	323	316	4696	1316	1175	2205
Inc./Dec.	-3	13	-6	14	11	-5	29	12	28	52	-4	44	1	186	93	69	24

WINCHESTER PUBLIC SCHOOLS

Fifteen Year Enrollment History & Five/Ten Year Projections Prepared: October 15, 2015

Census Projection Model for Kindergarten Projections	nsus Pro	iection N	Andel for	Kindergarten	Projections
--	----------	-----------	-----------	--------------	-------------


	Census Projection Model for Kindergarten Projections												
Year	1	2	3	4	5	6	7	8	9	10	11	12	Avg.
2001-02													
2002-03	116%	106%	100%	100%	102%	102%	99%	101%	93%	99%	102%	96%	2.07%
2003-04	118%	101%	103%	99%	102%	99%	98%	100%	99%	97%	94%	96%	2.20%
2004-05	119%	101%	100%	97%	98%	103%	99%	101%	99%	98%	100%	96%	2.33%
2005-06	113%	103%	104%	101%	103%	102%	102%	101%	94%	96%	99%	100%	4.30%
2006-07	114%	103%	103%	99%	102%	101%	100%	100%	98%	101%	101%	98%	2.95%
2007-08	112%	102%	101%	100%	100%	105%	98%	102%	96%	100%	100%	94%	0.77%
2008-09	120%	102%	102%	101%	103%	103%	99%	102%	97%	99%	98%	100%	2.90%
2009-10	117%	108%	104%	105%	101%	103%	97%	101%	89%	97%	96%	99%	2.34%
2010-11	113%	101%	105%	96%	99%	100%	98%	100%	88%	101%	100%	103%	2.12%
2011-12	110%	104%	100%	100%	102%	99%	97%	99%	93%	100%	97%	102%	1.50%
2012-13	106%	103%	97%	99%	100%	101%	101%	101%	92%	99%	101%	101%	1.13%
2013-14	112%	102%	101%	104%	101%	102%	99%	100%	92%	97%	96%	96%	1.16%
2014-15	111%	101%	103%	102%	100%	101%	102%	100%	89%	97%	99%	101%	1.49%
2015-16	109%	103%	107%	103%	98%	103%	102%	99%	88%	100%	99%	100%	1.99%
1 Year	109%	103%	107%	103%	98%	103%	102%	99%	88%	100%	99%	100%	1.99%
3 Years	111%	102%	103%	103%	100%	102%	101%	100%	90%	98%	98%	99%	1.55%
5 Years	110%	103%	101%	101%	100%	101%	100%	100%	91%	99%	98%	100%	1.45%
10 Years	112%	103%	102%	101%	101%	102%	99%	100%	92%	99%	99%	99%	1.84%
15 Years	114%	103%	102%	100%	101%	102%	99%	100%	93%	99%	99%	99%	2.09%



	WINCHESTER PUBLIC SCHOOLS																
DISTRICT ENROLLMENT																	
Year	PK	K	1	2	3	4	5	6	7	8	9	10	11	12	SP	Oth.	Tot.
Winchester Public	5	3	1	1	1	1	2	10	2	4	4	10	10	3	6	0	63
Lincoln Elem.	0	75	64	75	71	49	76	0	0	0	0	0	0	0	0	0	410
Lynch Elem.	89	76	86	63	87	72	76	0	0	0	0	0	0	0	0	0	549
Vison-Owen	0	48	64	67	87	82	74	0	0	0	0	0	0	0	0	0	422
Muraco Elem.	0	63	58	65	68	70	80	0	0	0	0	0	0	0	0	0	404
Ambrose Elem.	0	50	69	82	77	84	78	0	0	0	0	0	0	0	0	0	440
McCall Middle	0	0	0	0	0	0	0	387	365	382	0	0	0	0	0	0	1134
Winchester High	0	0	0	0	0	0	0	0	0	0	359	297	333	277	0	0	1266
Totals	94	315	342	353	391	358	386	397	367	386	363	307	343	280	6	0	4688

PREK	Existing 5 Classrooms at 94 students (FTE = 89) Proposed 5 Classrooms at 96 students (FTE=80)
GRADES K-5	Existing 106 classrooms at 2,136 students at 110 sections Currently 110 sections - 106 classrooms = 4 classrooms needed Proposed 113 classrooms at 2,217 students at 113 sections 2,717 proposed - 2,139 existing = 78 students at 3 classrooms Grades K-5 classroom needs = 113 proposed - 106 current = 7 classrooms needed
GRADES 6-8	Existing 52 classrooms at 1,150 students Proposed 56 classrooms at 1,232 students 56 proposed classrooms - 52 existing classrooms = 4 classrooms required
GRADES 9-12	Existing 1,292 students Proposed 1,370 students *New high school designed for 1,370 students






2021-2022 School Year at 2,217 Elementary School Students


School Year	School Department	Growth with Developments School Dept. Numbers (2007)	Growth with Developments New Projected Numbers (2017)
2006	1746	-	-
2007	1861	-	-
2008	1902	-	-
2009	1912	-	-
2010	1995	-	-
2011	2051	-	-
2012	2113	-	-
2013	2120	-	-
2014	2105	-	-
2015	2136	-	-
2016	2136	-	-
2017	2181	2191	2184
2018	2194	2194	2232
2019	2204	2204	2280
2020	2216	2217	2328
2021	2212	2217	2376
2022	2209	2210	2388
2023	2209	2210	2400
2024	2209	2210	2412
2025	2209	2210	2423
2026	2209	2210	2434





Design Enrollment for Analysis 2021-2022 School Year at 1,196 Middle School Students

School Year	School Department	Growth with Developments School Dept. Numbers (2007)	Growth with Developments New Projected Numbers (2017)
2006	844	-	-
2007	875	-	-
2008	889	-	-
2009	935	-	-
2010	986	-	-
2011	993	-	-
2012	1047	-	-
2013	1035	-	-
2014	1071	-	-
2015	1073	-	-
2016	1134	-	-
2017	1143	1143	1163
2018	1148	1148	1192
2019	1166	1166	1221
2020	1169	1174	1251
2021	1168	1173	1281
2022	1186	1196	1287
2023	1184	1184	1293
2024	1198	1198	1299
2025	1194	1194	1304
2026	1190	1190	1309



Growth with Developments Growth with Developments School Department School Year School Dept. Numbers (2007) New Projected Numbers (2017) -

Flansburgh Architects

August 9, 2016

Mr. Richard Howard Town Manager 71 Mt. Vernon Street Winchester, MA 01890

RE: Proposed 40B Project at Forest Ridge

Dear Mr. Howard:

Based on the number of units outlined in the Forest Ridge Residences Site Approval application date June 2016 that includes 29 three bedroom units, 119 two bedroom units, 119 one bedroom units, and 29 zero bedroom units. We offer the following analysis:

- 1. The Forest Ridge Residences project will impact the school system with a potential increase of 118 students system wide.
- 2. 9-12 grade students: 606-8 grade students: 45K-5 grade students: 15
- 3. Assuming occupancy starting in 2025 and completion by 2027, the potential impact is as follows:
 - Three (3) additional classrooms and support spaces at the high school
 - Two (2) additional classrooms and support spaces at the middle school
 - One (1) additional classroom at Muraco School

In conclusion, the School Department will need to renovate and add on to the above referenced school to add a total of six (6) classrooms plus support spaces by the anticipated occupancy of 2025.

If you have any questions or need additional information, please feel free to contact me at 617-367-3970.

Sincerely,

Jorge M. Cruz, AIA Executive Vice President

MEMORANDUM

To: School Committee, Superintendent Evans

From: Christian Nixon & Susan Verdicchio

Subject: Revisiting Classroom Targets as means to express capacity in Master Plan

Date: 11 October 2016

cc: Jennifer Elineema, John Danizio, file

At the Master Plan Working Group meeting on September 28, questions about overall capacity came up along with interest in using some expression and understanding of capacity as a metric in evaluating various Master Plan options-- particularly given the variations in costs associated with different renovation and constructions options. While the School Committee stopped short of declaring specific student capacities at our elementary schools during redistricting in 2012, we did establish the Classroom Target concept and voted this figure for each school-- with the further understanding that multiplying this figure by twenty [20] students yields a target enrollment for a fully-occupied building. With renewed interest in some expression of capacity (or some similar concept such as *design enrollment*) and with the passage of time since the Committee's vote in 2012, the Chair and I believe it is appropriate to:

- a) Use the SC-voted Classroom Targets [for existing/remaining elementary schools depending on development options] multiplied by twenty for a "WPS Design Enrollment" figure, expressly and clearly noted as being derived from the Classroom Targets and our average K-5 class size guidelines. Further, have Flansburgh develop new/renovation options using the WPS 20 students/classroom guideline (this will drive a modest increase in classrooms, as the MSBA uses 24/room as a standard).
- b) Revisit the Classroom Targets originally voted by the Committee for all the elementary buildings and adjust as necessary. With more than three years since WPS redistricting, there have been some key program changes in primary education in Winchester, most notably the redistribution of specialized learning centers/programs to four of five elementary schools and the expansion of the co-teach/tri-teach model. It is an appropriate time to review program changes against our understanding of a "general education core classroom" and confirm our expectations. There have also been physical plant modifications, such as the fit up of lower-level shell space this past summer at Vinson-Owen.

Classroom Target Background

In August of 2012 the Committee voted to establish the following Classroom Targets (spaces intended, appropriately sized and configured for general education classrooms) for our elementary schools. For context, the number of sections in each school at the time of the vote is given as well as today's October '16 figures. Note that at 110 sections, we are two over our 108 target which means impact on some program spaces:

	Spring '12	<u>Target</u>	<u>Today</u>
Ambrose Elementary School	25 sections	23 (460)	23 (440)
Lincoln Elementary School	23 sections	21 (420)	22 (410)
Lynch Elementary School	19 sections	22 (440)	24 (460)
Muraco Elementary School	24 sections	21 (420)	20 (404)
Vinson-Owen Elementary School	15 sections	<u>21 (420)</u>	<u>21 (422)</u>
	106 sections	108 (2160)	110 (2136 actual)

Supporting the 2012 Committee discussion and vote was the WPS Elementary Schools Space Summary for 2013-14 (v2.1), attached for reference. Committee members may recall that spaces "taken" for general education classrooms were identified for recapture post-redistricting. For instance, Ambrose was using its Music Room as a general ed classroom and Lincoln was doing the same, in addition to using its Computer Lab. While redistricting helped to relieve some of these pressure points the Committee acknowledged at the time that shifts in philosophy over instructional spaces and instructional methods would require a periodic reevaluation of space program, including specialty/support spaces.

Elementary Space Today

With the help of Mr. Danizio and the elementary principals, this week we reviewed key changes in space utilization. Major changes are summarized below, but drive a series of questions for School Committee discussion and possible action (see page 5):

Ambrose

Originally housing 25 sections in the spring of 2012, including the Music Room and a Special Education resource room, Ambrose was able to recapture these spaces post-redistricting and is operating at 23 sections-- the Classroom Target voted by the Committee. The target assumed four (4) Kindergarten classroom and 19 grade 1-5 rooms. Principal Leigh Petrowski noted this week that the building is "on target" only because of the three (3) Kindergarten sections this year, which accommodates twenty grade 1-5 classrooms. When asked what moves must be considered next year if we register four K sections, Ms. Petrowski identified both the Music Room and the Computer Lab. While she is reluctant to see the Computer Lab go-- noting the frequency of use among K-2 students-- she is more concerned about a return to Music on a Cart. She notes that Ambrose is full

right now with no additional space available. For Ambrose-- and the other four schools-- a transition to All Day Kingergarten [ADK] and a potential 8% increase in K enrollment may well be a tipping point in K-room space needs.

Specialized Learning Center- Ambrose houses the Cognitive Program SLC which has grown each year it has been housed at Ambrose (beginning post-redistricting). It is important for the School Committee to note that while we originally dedicated a 600sf space for this program (see 8/12 Space Summary for 2013-14), the growth in enrollment has dictated a second space be made available for these students-- in this case the 160sf PT/OT Room has been repurposed. With continued growth in this SLC, it appears that there is no expansion space and therefore specialty program such as the Computer Lab and/or Music Room are vulnerable.

Lincoln

Originally housing 23 sections in the spring of 2012, including the Music Room, Computer Lab and a basement-level resource room, Lincoln recaptured some space-- but not all-- after redistricting. Today Lincoln houses 22 sections. After some discussion in 2012, the Committee voted Lincoln's Classroom Target at 21 rather than 20. It is important to recall that Lincoln has twenty general ed classrooms (4 K + 16 grades 1-5) but-- as noted in the 2007 Master Plan-- the Music Room has been used as a grade 1-5 classroom for some time due to space needs. At the time of redistricting, it was felt by Administration that this use was 'acceptable' given the adjacent Auditorium space which is used for music instruction. The Computer Lab was moved into the Lincoln Library, a condition that exists today and is readily accepted as a good fit. Today Lincoln Elementary uses both the Music Room and Computer Lab as general ed classrooms. Only the basement-level resource room is still being used for its intended purpose.

Music Room- With a revised Master Plan in the works, it is appropriate for the Committee to reconsider the future of the Music Room at Lincoln. Mr. Schindelman has noted that this space is specifically configured for music instruction: at nearly 1000sf, it is larger than a general ed classroom and has risers built into the space. Principal Kelly Clough acknowledges some of the difficulties inherent in using the auditorium for instructional space and would welcome the Music Room back in the future.

Computer Lab- Although the space has been in use as a general ed classroom space for at least the the last five years, Ms. Clough is reluctant to formally reclassify this as such. While there is agreement that the traditional role of the lab is going the way of the dinosaur, she is hopeful for an alternative use such as a Maker Space or similar STEM-supportive program.

Lynch

Originally housing 19 sections in 2012, available classroom space at Lynch was expanded with the Central Office move to Parkhurst. The School Committee voted an increase of three rooms for a Classroom Target of 22. As the Committee is aware, there has been significant enrollment growth post-redistricting and today Lynch is running 24 sections (4 K + 20 grades 1-5). Enrollment growth has been accommodated through repurposing a Pre-K room on the main level (with trickle-down program impact downstairs though it has been well-accommodated), a large SPED Resource Room (over 700sf) and the Computer Lab (over 1000sf).

Specialized Learning Center- Lynch houses the Autism Spectrum Program, which is housed in multiple spaces. It is important for the Committee to understand that-- at 24 sections-- Lynch is exhausted of space and has repurposed (or 'lost') key program space that had Committee support in 2012, including the Computer Lab.

Muraco

Originally housing 24 sections in the spring of 2012-- including the Computer Lab (divided in half for two smaller classrooms) and the 820sf Reading Room-- Muraco recaptured some of this space with a Classroom Target of 21 post-redistricting. Today Muraco houses 20 sections (3 K + 17 grades 1-5), however this does not mean that spaces are left unused or unassigned. As you will see below, Muraco is actually now full-- similar to Ambrose-- without space for an additional section with impacting specialists space.

Specialized Learning Center- Muraco houses the Behavioral/Partnership program which was originally located at Ambrose. At the time of redistricting, the Superintendent made clear the intent to distribute the four SLC's to Ambrose, Lynch, Muraco and V-O. While specific accommodation was made for these programs at Lynch and V-O in the form of two classrooms, Muraco did not have any such space designated (perhaps due to the limited enrollment). In the years since redistricting the Partnership Program at Muraco has taken the former Music Room (now relocated to a general ed classroom) and shares an additional general education classroom space.

Therefore, while Muraco is housing only 20 sections today there are no additional available classrooms. It is worth noting that while the Committee chose not to include in the Classroom Target the two spaces created by dividing the Computer Lab (never used due to rising enrollment), one of these spaces is in use today as a 5th grade classroom.

Vinson-Owen

V-O is an easy summary! Originally housing 15 sections at Parkhurst during construction, the School Committee voted a Classroom Target of 21 for the new building (3 K + 18 grades 1-5) and this is exactly how the school operates today.

Specialized Learning Center- V-O houses the LBLD program which has just seen an expansion in program space. The school was designed with two SPED/LBLD classroom spaces (900sf) and these have been in use. The program has expanded, however, and Grant Smith reports that the specialist room included in this summer's shell space fit-up project is now used for 4th graders in the LBLD program. *Note- even though we planned two classrooms for this program as recently as 2012, it has expanded.* The three new classrooms are not permanently assigned, though there is interest in creating a Maker Space in one. When asked about accommodating future enrollment growth that may take these new spaces, Mr. Smith notes an interest in the potential to transition the Computer Lab (2nd floor) to a STEM/Maker Space-type program.

Key Questions for School Committee and Administration

Specialized Learning Centers

If the the SLCs continue to grow in enrollment (as we would hope), what space needs can we/should we reasonably predict? How does this/should this impact our 2012 voted Classroom Targets? If V-O and Lynch were planned to house SLCs with at least two classroom spaces (and these were therefore not included in the Classroom Target figures) should Muraco and Ambrose Classroom Targets not be revisited?

Computer Lab/Maker Space

Understanding that in 2012 the School Committee chose not to absorb Computer Lab space as general ed classrooms, should we revisit the Classroom Target for Lincoln? Given the space shortage at Lynch and the taking of the Computer Lab, what is the future utilization of the three new classrooms at Vinson-Owen and what are Administration's thoughts on the location of SLCs?

Music Room

With dedicated Music Rooms in our other four elementary schools should Lincoln's Classroom Target be revisited to recapture this space?

Vinson-Owen Construction

Given all the above, what number of the three new classrooms-- if any-- should be added to V-O's Classroom Target?

Action Item

After discussion over the the questions above, it is recommended that the School Committee revise and re-vote adjusted Classroom Targets for our Master Plan team's use in expressing "WPS Design Enrollment".



ES-5A Lynch Elementary - 540 Enrollment: Renovation/A	Addition
PROGRAM	
Core Academic	25,000
Special Education	6,040
Art & Music	5,000
Health & Physical Education	6,300
Media Center	3,280
Dining & Food Service	7,870
Medical	610
Administration & Guidance	2,445
Custodial & Maintenance	2,180
SUBTOTAL NSF	58,725 NSF
GROSSING FACTOR	1.46
TOTAL GSF	85,455 GSF

ES-5B Lynch Elementary - 540 Enrollment: New Cor	nstruction
PROGRAM	
Core Academic	25,000
Special Education	6,040
Art & Music	5,000
Health & Physical Education	6,300
Media Center	3,280
Dining & Food Service	7,870
Medical	610
Administration & Guidance	2,445
Custodial & Maintenance	2,180
SUBTOTAL NSF	58,725 NSF
GROSSING FACTOR	1.46
TOTAL GSF	85,455 GSF

ES-5D Lynch Elementary - 540 Enrollment + 90 PreK: New Construction **PROGRAM** Core Academic 26,900 **Special Education** 7,550 5,000 Art & Music **Health & Physical Education** 6,300 Media Center 3,505 **Dining & Food Service** 8,320 Medical 610 Administration & Guidance 2,165 **Custodial & Maintenance** 2,230 63,030 NSF **SUBTOTAL NSF GROSSING FACTOR** 1.45 **TOTAL GSF** 81,350 GSF

ES-6A: Muraco Elementary - 520 Enrollment: Renovation/Addition			
PROGRAM			
Core Academic	20,000		
Special Education	5,540		
Art & Music	2,575		
Health & Physical Education	6,300		
Media Center	2,740		
Dining & Food Service	6,780		
Medical	510		
Administration & Guidance	2,325		
Custodial & Maintenance	2,060		
SUBTOTAL NSF	48,830 NSF		
GROSSING FACTOR	1.52		
TOTAL GSF	74,215 GSF		

ES-6A: Muraco Elementary - 460 Enrollment: New Construction				
PROGRAM				
Core Academic	20,000			
Special Education	5,540			
Art & Music	2,575			
Health & Physical Education	6,300			
Media Center	2,740			
Dining & Food Service	6,778			
Medical	510			
Administration & Guidance	2,325			
Custodial & Maintenance	2,060			
SUBTOTAL NSF	48,828 NSF			
GROSSING FACTOR	1.52			
TOTAL GSF	74,213 GSF			

ES-6A: Muraco Elementary - 520 Enrollment: New Construction				
PROGRAM				
Core Academic	22,850			
Special Education	6,040			
Art & Music	3,725			
Health & Physical Education	6,300			
Media Center	3,010			
Dining & Food Service	7,325			
Medical	610			
Administration & Guidance	2,325			
Custodial & Maintenance	2,120			
SUBTOTAL NSF	52,365 NSF			
GROSSING FACTOR	1.48			
TOTAL GSF	80,225 GSF			


ES-6A: Vinson-Owen Elementary - 580 Enrollment: New Addition

E3-0A. VIIIson-Owen Elementary - 380 Emolinent. New Addition
PROGRAM
Core Academic
Special Education
Art & Music
Health & Physical Education
Media Center
Dining & Food Service
Medical
Administration & Guidance
Custodial & Maintenance
SUBTOTAL NSF
GROSSING FACTOR
TOTAL GSF



Presentation 1 - June 16, 2016

6/17/16 6/17/16














Explorer Elementary











1

2





6/17/16





6/17/16

















4

3

198

6/17/16 6/17/16















Project-**Based Learning** ... the ONLY way to teach 21st century and independent learning skills







6



5





6/17/16





6/17/16

















7 8

199

6/17/16 6/17/16

























9

10

6/17/16





6/17/16



















12

11 12

11

6/17/16

























14

6/17/16

13

6/17/16

13 14

























16

15 16

6/17/16

























18

17 18

17

6/17/16 6/17/16

























19 20

19

Caleb Dustin Hunking K-8

22

22

6/17/16 6/17/16













21

21

6/17/16 6/17/16



















23

23 24

6/17/16 6/17/16



























6/17/16 6/17/16

























6/17/16 6/17/16



























29 30

6/17/16 6/17/16

























31 32

31

205

6/17/16 6/17/16























34

33 34

33

6/17/16 6/17/16





















Dearborn 6-12 Early College STEM Academy



35 36

35

6/17/16 6/17/16





















Presentation 2 - September 28, 2016



FLANSBURGH

1

10-Year Projected Enrollments



Design Enrollment for Analysis 2021 - 2022 School Year @ 1196 / 6-8 Students

3

ES-1 Muraco Elementary - 484 enrollment - K-5: Modular Classroom

PROGRAM	GRADES K-5 (New)
Core Academic	20,950
Special Education	5,540
Art & Music	2,575
Health & Physical Education	6,300
Media Center	2,850
Dining & Food Service	6,995
Medical	510
Administration & Guidance	2,350
Custodial & Maintenance	2,085
Subtotal NSF	50,155 NSF
Grossing Factor	1.53
Total GSF	76,730 GSF

5

FLANSBURGH

10-Year Projected Enrollments




Design Enrollment for Analysis 2021 - 2022 School Year @ 2217 / K-5 Students

2

PreK - 5 Options for 2021 - 2022 School Year								
Current Enrollment: 2021-2022 Enrollment: Enrollment Increase:	2,140 Students 2,217 Students +77 Students							
	Option ES-1 Three Modular Classrooms	Option ES-2 Move PK ← K to Parkhurst, Renovation/ Addition	Option ES-3 Move PreK & K to Parkhurst, New Construction	Option ES-4 Muraco/Lynch Combined School	Option ES-5 Muraco/Lynch Renovations/ Addition	Option ES-6 Muraco/Lynch New Construction		
Ambrose	No change	Two classrooms available	Two classrooms available	No change	No change	No change		
Lincoln	No change	Four classrooms available	Four classrooms available	No change	No change	No change		
Lynch	Add two modular classrooms	Four classrooms available	Nine classrooms available	Closed for develop- ment	Renovation/addi- tion for 624 stu- dents	New construction for 624 students		
Muraco	Add one modular classroom	Three classrooms available	Three classrooms available	New school for 1,030 students	Renovation/ addition for 484 students	New construction for 484 students		
Vinson-Owen	No change	Three classrooms available	Three classrooms available	No change	No change	No change		
Parkhurst	No change	Renovation/ addition for 411 students	New construction for 411 students	No change	No change	No change		
Project Budget	\$2,663,000	\$27,235,000	\$28,105,353	\$74,902,000	\$76,000,000	\$85,678,000		

4



 $[\]ensuremath{^{\star}}$ When Vinson Owen is at capacity the overflow of students move to Lynch & Muraco.




ES-1 Lynch Elementary - 624 enrollment - PK-5 : Modular Classroom

PROGRAM	GRADES K-5
Core Academic	26,900
Special Education	7,550
Art & Music	5,000
Health & Physical Education	6,300
Media Center	3,480
Dining & Food Service	8,270
Medical	610
Administration & Guidance	2,610
Custodial & Maintenance	2,225
Subtotal NSF	62,940 NSF
Grossing Factor	1.44
Total GSF	90,480 GSF

 $\mbox{\ensuremath{^{\star}}}$ When Vinson Owen is at capacity the overflow of students move to Lynch & Muraco.

FLANSBURGH **Lynch Elementary School** 8




7



ES-2 Parkhurst Elementary - 411 enrollment : Renovation / Addition

9


PROGRAM	GRADES PreK-K
Core Academic	17,850
Special Education	4,350
Art & Music	2,575
Health & Physical Education	6,300
Media Center	2,520
Dining & Food Service	6,335
Medical	510
Administration & Guidance	2,125
Custodial & Maintenance	2,010
Subtotal NSF	44,755 NSF
Grossing Factor	1.53
Total GSF	68,660 GSF




10

FLANSBURGH Parkhurst Elementary School


> 11 12





13

ES-3 Parkhurst Elementary - 411 enrollment : New Construction



PROGRAM	GRADES PreK-K
Core Academic	17,850
Special Education	4,350
Art & Music	2,575
Health & Physical Education	6,300
Media Center	2,520
Dining & Food Service	6,335
Medical	510
Administration & Guidance	2,125
Custodial & Maintenance	2,010
Subtotal NSF	44,755 NSF
Grossing Factor	1.53
Total GSF	68,660 GSF

14

Parkhurst Elementary School Winchester, MA

FLANSBURGH

NEW SCHOOL BE ANDREWS RD

Site Plan

Poption ES-3


Poption

15



16

17 18




ES-4 Muraco / Lynch Elementary - 1030 enrollment : New Construction K-5

PROGRAM	GRADES K-5 *
Core Academic	44,750
Special Education	11,070
Art & Music	7,575
Health & Physical Education	6,300
Media Center	5,305
Dining & Food Service	11,956
Medical	810
Administration & Guidance	3,165
Custodial & Maintenance	2,630
Subtotal NSF	93,561 NSF
Grossing Factor	1.60
Total GSF	149,350 GSF


Lynch / Muraco Elementary School Winchester, MA

FLANSBURGH






21 22



23




24

ES-5 Muraco / Lynch Elementary - K-5: Renovation / Addition

	Muraco Renovation/Addition		Lynch Renovation/Addition	
PROGRAM	RENOVATION	ADDITION	RENOVATION	ADDITION
Core Academic	14,210	7,430	20,905	4,635
Special Education	2,390	925	5,305	1,020
Art & Music	2,630		5,035	
Health & Physical Education		6,290	7,040	
Media Center	3,065		3,400	
Dining & Food Service		7,045	7,085	
Medical	570		625	
Administration & Guidance	975	2,160		2,040
Custodial & Maintenance		2,300		3,550
Subtotal NSF	23,840 NSF	26,150 NSF	54,700 NSF	11,240 NSF
Grossing Factor		1.51		1.51
Total GSF	41,115 SF	35,615 SF 76,730 GSF	79,745 SF	11,030 SF 90,775 GSF

^{*} Parkhurst utilized for Muraco and Lynch students during phased construction.




Option ES-5
Muraco Elementary School
Muraco El



Option ES-5
Lynch Elementary School
Windlester, Massachusetis

FLANSBURGH

27



28

29 30

FI ANSRURGH




ES-6 Muraco/Lynch Elementary - PK-5 : New Construction Muraco New Construction Lynch New Construction

NEW* 20,950 5,540 2,575	NEW* 26,900 7,550
5,540	·
· ·	7.550
2 575	.,
2,313	5,000
6,300	6,300
2,848	3,450
6,996	8,270
510	610
2,349	2,610
2,084	2,225
50,152 NSF	62,940 NSF
1.53	1.44
	90,480 GSF
	6,996 510 2,349 2,084 50,152 NSF


Muraco/Lynch Elementary School Winchester, MA

FLANSBURGH



33

Option ES-6 Nuraco Elementary School Vinchester, Massachusetts





Second Floor Plan FLANSBURGH



34

^{*} Based on MSBA Space Summary.
** Parkhurst utilized for Muraco & Lynch students during construction.





37
6-8 Options for 2021 - 2022 School Year

Option MS-2 New Addition Option MS-1 Youth Center Renovation Option MS-3 Add elevator and renovated Youth Center (four Add a four permanent classroom addition Twelve classrooms available Twelve classrooms available Twelve classrooms available McCall Middle No change No change No change No change Ambrose No change No change No change No change Closed for development No change No change No change New school for 1,430 students

38

MS-1 McCall Middle School - 1,105 enrollment - Youth Center Renovation


PROGRAM	GRADES 6-8 (EXISTING)
Core Academic	29,140
Special Education	5,795
Art & Music	6,875
Vocations & Technology	5,450
Health & Physical Education	12,905
Media Center	4,500
Dining & Food Service	8,235
Medical	520
Administration & Guidance	2,290
Custodial & Maintenance	6,340
Subtotal NSF	73,905 NSF
Grossing Factor	1.85
Total GSF	136,955 GSF

McCall Middle School

Winchester, MA

FLANSBURGH

39





40




MS-2 McCall Middle School - 1,105 enrollment - New Addition


PROGRAM			GRADES 6-8 (EXISTING)
Core Academic			28,630
Special Education			5,795
Art & Music			6,875
Vocations & Technology			5,450
Health & Physical Education			12,905
Media Center			4,500
Dining & Food Service			8,235
Medical			520
Administration & Guidance			2,290
Custodial & Maintenance			6,340
Subtotal NSF			73,905 NSF
Grossing Factor			1.85
Total GSF	132,280 SF EXISTING	4,675 SF ADDITION	136,955 GSF

McCall Middle School Winchester, MA FLANSBURGH

43 44



45



46

BASE ALMMAN_LISERS

WHO A CORPER

WHO AL CORPER

WH

Section 5 | Presentations & Meeting Notes

MS-3 Parkhurst 6th Grade Academy - 400 Enrollment

PROGRAM	6 th GRADE ACADEMY
Core Academic	18,920
Special Education	4,530
Art & Music	3,050
Activity	8,400
Discovery	2,680
Dining & Food Service	6,835
Medical	510
Administration & Guidance	2,750
Custodial & Maintenance	1,875
Subtotal NSF	49,550 NSF
Grossing Factor	1.53
Total GSF	76,000 GSF

FLANSBURGH

Parkhurst Elementary School

FLANSBURGH

Site Plan

FLANSBURGH

49

50

 $\mbox{MS-4}$ - \mbox{Muraco} / $\mbox{Lincoln}$ Elementary - 884 enrollment - New Construction

PROGRAM	GRADES K-5 *
Core Academic	37,850
Special Education	9,060
Art & Music	6,300
Health & Physical Education	6,300
Media Center	4,650
Dining & Food Service	10,630
Medical	710
Administration & Guidance	3,010
Custodial & Maintenance	2,485
Subtotal NSF	81,000 NSF
Grossing Factor	1.58
Total GSF	128,180 GSF

^{*} Based on MSBA Space Summary.

51


Muraco Elementary School

Winchester, MA

FLANSBURGH

FLANSBURGH

53



52

54

216

FLANSBURGH

^{**} Parkhurst utilized for Muraco & Lincoln students during construction.

MS-4a Muraco/Lynch/Lincoln Elementary - 1430 enrollment: New Construction

PROGRAM	PreK-5
Core Academic	61,650
Special Education	15,600
Art & Music	10,150
Health & Physical Education	6,300
Media Center	7,105
Dining & Food Service	15,589
Medical	910
Administration & Guidance	3,985
Custodial & Maintenance	3,030
Subtotal NSF	124,319 NSF
Grossing Factor	1.67
Total GSF	207,350 GSF

^{*} Based on MSBA Space Summary

Option MS-4n Munico Elementary School Winchester, Massachusetts


56

Muraco Elementary School

Option MS-4a Muraco Elementary School Vinchester, Massachusetts Winchester, MA

FLANSBURGH





57 58






60

Option MS-4a Muraco Elementary School Winchester, Massachusetts

^{**} Parkhurst utilized for Muraco, Lynch, & Lincoln students during construction.

Presentation 3 - October 19, 2016



FLANSBURGH

1

10-Year Projected Enrollments



Design Enrollment for Analysis 2021 - 2022 School Year @ 1196 / 6-8 Students

3

Current Enrollment: 2021-2022 Enrollment: Enrollment Increase:							
	Option ES-1 Three Modular Classrooms	Option ES-2 Move PK & K to Parkhurst, Renovation∕ Addition	Option ES-3 Move PreK & K to Parkhurst, New Construction	Option ES-4 Muraco/Lynch Combined School (1,000 Students)	Option ES-5 Muraco/Lynch Renovations/ Addition (1,000 Students)	Option ES-6 Muraco/Lynch New Construction (1,000 Students)	
Ambrose	No change	Two classrooms available	Two classrooms available	No change	No change	No change	
Current Enrollment	439	388	388	439	439	439	
WPS Design Enrollment	460	460	460	460	460	460	
# Classrooms	23	23	23	23	23	23	
Lincoln	No change	Four classrooms available	Four classrooms available	No change	No change	No change	
Current Enrollment	402	330	330	402	402	402	
WPS Design Enrollment	440	440	440	440	440	440	
# Classrooms	22	22	22	22	22	22	
Lynch w/ PreK	Add two modular classrooms	Nine classrooms available	Nine classrooms available	Closed for development	Renovation/addition for 560 students	New construction for 560 students	
Current Enrollment	521	370	370	0	521	521	
WPS Design Enrollment	560	440	440	0	560	560	
# Classrooms	29	27	27	0	29	29	
Muraco	Add one modular classroom	Three classrooms available	Three classrooms available	New school for 1,000 students	Renovation/addition for 440 students	New construction for 440 students	
Current Enrollment	387	329	329	908	387	387	
WPS Design Enrollment	440	420	420	1000	440	440	
# Classrooms	22	21	21	51	22	22	
Vinson-Owen	No change	Three classrooms available	Three classrooms available	No change	No change	No change	
Current Enrollment	421	372	372	421	421	421	
WPS Design Enrollment	420	420	420	420	420	420	
# Classrooms	21	21	21	21	21	21	
Parkhurst	No change	Renovation/addition for 420 students	New construction for 420 students	No change	No change	No change	
Current Enrollment	0	381	381	0	0	0	
WPS Design Enrollment	0	420	420	0	0	0	
# Classrooms	0	22	22	0	0	0	
Project Budget	\$2,663,000	\$27,235,000	\$28,105,353	\$74,902,000	\$76,000,000	\$85,678,00	

5

10-Year Projected Enrollments





Design Enrollment for Analysis 2021 - 2022 School Year @ 2217 / K-5 Students


2

	6-8 Ор	TIONS FOR 2021 - 2022	SCHOOL YEAR	
Current Enrollment: 2021-2022 Enrollment: Enrollment Increase:	1,105 Students 1,196 Students +91 Students			
	Option MS-1 Youth Center Renovation	Option MS-2 New Addition	Option MS-3 6th Grade at Parkhurst	Option MS-4 6th Grade to Lincoln
McCall Middle	Add elevator and renovated Youth Center (four classrooms)	Add a six permanent classroom addition & renovated Youth Center (Innovation Space)	Twelve classrooms available	Twelve classrooms available
Current Enrollment	1,132	1,132	745	745
WPS Design Enrollment	1,232	1,276	1,122	1,122
# Classrooms	56	58	51	51
Ambrose	No change	No change	No change	No change
Current Enrollment	439	439	439	439
WPS Design Enrollment	460	460	460	460
# Classrooms	23	23	23	23
Lincoln	No change	No change	No change	Sixth Grade moves in
Current Enrollment	402	402	402	252
WPS Design Enrollment	440	440	440	440
# Classrooms	22	22	22	22
Lynch with PreK	No change	No change	No change	No change
Current Enrollment	521	521	521	521
WPS Design Enrollment	560	560	560	560
# Classrooms	27	27	27	27
Muraco	No change	No change	No change	New school for 926 Lincoln, Muraco, 8 future students
Current Enrollment	387	387	387	789
WPS Design Enrollment	420	420	420	926
# Classrooms	21	21	21	46
Vinson-Owen	No change	No change	No change	No change
WPS Design Enrollment	421	421	421	421
Max. Enrollment	420	420	420	420
# Classrooms	21	21	21	21
Parkhurst	No change	No change	New construction for 374 students	No change
Current Enrollment	0	0	362	0
WPS Design Enrollment	0	0	374	0
# Classrooms	0	0	17	0
Project Budget	\$2,574,000	\$6,586,000	\$28,106,000	\$63,618.40


4








7 8



9


n ES-5 Elementary School ester, Massachusetts



10

OPTION ES-5
ADDITION 13
MAJOR RENOVATION 70
TOTAL AREA 83
STORIES
CLASSROOMS
WPS DESIGN ENFOLLMENT
PROJECT BUDGET \$76.0

PARENT DROP, GET
PARENT DROP, GE




11 12


FLANSB







13 14






15 16





ENROLLMENT OPTIONS REVIEW

Presentation 4 - November 21, 2016



The Visioning Process

Larger Community



Winchester Public Schools | Winchester, MA

FLANSBURGH

2

4

6

FLANSBURGH

1

Focus on 21st Century Skills

• The six R's and the four C's

- Proactive, life long, continuous learning
- Critical thinking
- Communication
- Collaboration Creativity
- Citizenship
- · Academic mindset



ENROLLMENT OPTIONS REVIEW

Focus on Learning

- · High-performance work environments
- · Varied and collaborative
- · Flexible and agile

Winchester Public Schools | Winchester, MA











Winchester Public Schools | Winchester, MA

FLANSBURGH

ENROLLMENT OPTIONS REVIEW

21st Century Design Patterns





Winchester Public Schools | Winchester, MA



3

Indoor / Outdoor Learning



5





Streetscapes
Displays
Informal Gathering Areas

Guiding Principles & Priorities

- Understanding of district's current initiatives
- · Analysis of opportunities and goals
- Translation of goals into architectural priorities







Winchester Public Schools | Winchester, MA

FLANSBURGH

FLANSBURGH

ENROLLMENT OPTIONS REVIEW

Current Enrollment: 2021-2022 Enrollment: Enrollment Increase:	6-8 OP 1,105 Students 1,196 Students +91 Students	TIONS FOR 2021 - 2022	School Year	
	Option MS-1 Youth Center Renovation	Option MS-2 New Addition	Option MS-3 6th Grade at Parkhurst	Option MS-4 6th Grade to Lincoln
McCall Middle	Add elevator and renovated Youth Center (four classrooms)	Add a six permanent classroom addition & renovated Youth Center (Innovation Space)	Twelve classrooms available	Twelve classrooms available
Current Enrollment	1,132	1,132	745	745
WPS Design Enrollment	1,232	1,276	1,122	1,122
# Classrooms	56	58	51	51
Ambrose	No change	No change	No change	No change
Current Enrollment	439	439	439	439
WPS Design Enrollment	460	460	460	460
# Classrooms	23	23	23	23
Lincoln	No change	No change	No change	Sixth Grade moves in
Current Enrollment	402	402	402	252
WPS Design Enrollment	440	440	440	440
# Classrooms	22	22	22	22
Lynch with PreK	No change	No change	No change	No change
Current Enrollment	521	521	521	521
WPS Design Enrollment	560	560	560	560
# Classrooms	27	27	27	27
Muraco	No change	No change	No change	New school for 926 Lincoln, Muraco, & futus students
Current Enrollment	387	387	387	789
WPS Design Enrollment	420	420	420	926
# Classrooms	21	21	21	46
Vinson-Owen	No change	No change	No change	No change
WPS Design Enrollment	421	421	421	421
Max. Enrollment	420	420	420	420
# Classrooms	21	21	21	21
Parkhurst	No change	No change	New construction for 374 students	No change
Current Enrollment	0	0	362	0
WPS Design Enrollment	0	0	374	0
# Classrooms	0	0	17	0
Project Budget	\$2,574,000	\$6,586,000	\$28,106,000	\$63,618,4
Winchester Public Scho	ols Winchester, MA			FLANSBURG

														2.11	OLLINE	11 01 1101	45 112 412
Winchester Public Schools																	
	DISTRICT ENROLLMENT																
Year	PK	K	1	2	3	4	5	6	7	8	9	10	11	12	SP	Other	Total
WINCHESTER PUBLIC	5	3	1	1	1	1	2	10	2	4	4	10	10	3	6	0	63
LINCOLN ELEMENTARY	0	75	64	75	71	49	76	0	0	0	0	0	0	0	0	0	410
LYNCH ELEMENTARY	89	76	86	63	87	72	76	0	0	0	0	0	0	0	0	0	549
Vison-Owen	0	48	64	67	87	82	74	0	0	0	0	0	0	0	0	0	422
MURACO ELEMENTARY	0	63	58	65	68	70	80	0	0	0	0	0	0	0	0	0	404
Ambrose Elementary	0	50	69	82	77	84	78	0	0	0	0	0	0	0	0	0	440
McCall Middle School	0	0	0	0	0	0	0	387	365	382	0	0	0	0	0	0	1134
WINCHESTER HIGH SCHOOL	0	0	0	0	0	0	0	0	0	0	359	297	333	277	0	0	1266
Totals	9.4	315	342	353	391	358	386	397	367	386	363	307	343	280	6	0	4688

7

Option ES-1

Winchester Public Schools | Winchester, MA

FLANSBURGH

ENROLLMENT OPTIONS REVIEW

Pre-Kindergarten

8

Existing 5 Classrooms at 94 students (FTE = 89) Proposed 5 Classrooms at 96 students (FTE=80)

nchester Public Schools | Winchester, MA FLANSBURGH

ENROLLMENT OPTIONS REVIEW

Winchester Public Schools | Winchester, MA

FLANSBURGH

ENROLL MENT OPTIONS REVIEW

GRADES 6-8

10

GRADES K-5

9

Existing 106 classrooms at 2,139 students at 110 sections Currently 110 sections - 106 classrooms = 4 classrooms needed Proposed 113 classrooms at 2,217 students at 113 sections 2,717 proposed - 2,139 existing = 78 students at 3 classrooms Grades K-5 classroom needs = 113 proposed - 106 current = 7 classrooms needed

Existing 52 classrooms at 1,150 students Proposed 56 classrooms at 1,232 students 56 proposed classrooms - 52 existing classrooms = 4 classrooms required

Winchester Public Schools | Winchester, MA FLANSBURGH 11

Winchester Public Schools | Winchester, MA FLANSBURGH

FLANSBURGH

GRADES 9-12

Existing 1,292 students Proposed 1,370 students *New high school designed for 1,370 students

Winchester Public Schools | Winchester, MA

EXTENT OF RENOVATED AREA

BASEMENT LEVEL PLAN


Winchester Public Schools | Winchester, MA

2021-2022 Enrollment: <u>1.196 Students</u> Enrollment Increase: +91 Students		
	Option MS-1 Youth Center Renovation Phase I	Option MS-2 New Addition Phase II
McCall Middle	Add elevator and renovated Youth Center (four classrooms)	Add a six permanent classroom addition
Current Enrollment	1,132	1,132
WPS Design Enrollment	1,232	1,276
# Classrooms	56	58
Ambrose	No change	No change
Current Enrollment	439	439
WPS Design Enrollment	460	460
# Classrooms	23	23
Lincoln	No change	No change
Current Enrollment	402	402
WPS Design Enrollment	440	440
# Classrooms	22	22
Lynch with PreK	No change	No change
Current Enrollment	521	521
WPS Design Enrollment	560	560
# Classrooms	27	27
Muraco	No change	No change
Current Enrollment	387	387
WPS Design Enrollment	420	420
# Classrooms	21	21
Vinson-Owen	No change	No change
WPS Design Enrollment	421	421
Max. Enrollment	420	420
# Classrooms	21	21
Parkhurst	No change	No change
Current Enrollment	0	0
WPS Design Enrollment	0	0
# Classrooms	0	0

FLANSBURGH


14

13



Option MS-1 (Classrooms Only) McCall Middle School Winchester, Massachusetts FLANSBURGH

FLANSBURGH Winchester Public Schools | Winchester, MA 15




Option MS-1 (Classrooms with Existing Lockers to Remain) McCall Middle School Winchester, Massachusetts **FLANSBURGH**

FLANSBURGH Winchester Public Schools | Winchester, MA

ENROLLMENT OPTIONS REVIEW

16 ENROLLMENT OPTIONS REVIEW



2021-2022 Enrollment: Enrollment Increase:	2.217 Students +78 Students Pre-					
	Option ES-2 Grade Shift PK & K to Parkhurst, Renovation/ Addition	Option ES-3 Grade Shift PreK & K to Parkhurst, New Construction	Option ES-2AGrade Shift 5th to Parkhurst, Renovation/ Addition	Option ES-3A Grade Shift 5th to Parkhurst, New Construction	Option ES-5 Muraco/Lynch Renovations/ Addition	Option ES-6 Muraco/Lynch New Construction
Ambrose	Three classrooms available	Three classrooms available	Three classrooms available	Three classrooms available	No change	No change
Current Enrollment	390	390	362	362	440	440
WPS Design Enrollment	460	460	460	460	460	460
# Classrooms	23	23	23	23	23	23
Lincoln	Four classrooms available	Four classrooms available	Four classrooms available	Four classrooms available	No change	No change
Current Enrollment	335	335	334	334	410	410
WPS Design Enrollment	440	440	440	440	440	440
# Classrooms	21	21	21	21	21	21
Lynch w/ PreK	Nine classrooms available	Nine classrooms available	Nine classrooms available	Nine classrooms available	Renovation/addition for 580 students (PK-5)	New construction for 580 students (PK-5)
Current Enrollment	384	384	473	473	549	549
WPS Design Enrollment	540	540	540	540	580	580
# Classrooms	27	27	27	27	29	29
Muraco	Three classrooms available	Three classrooms available	Three classrooms available	Three classrooms available	Renovation/addition for 460 students (K-5)	New construction for 460 students (K-5)
Current Enrollment	341	341	324	324	404	404
WPS Design Enrollment	420	420	420	420	460	460
# Classrooms	21	21	21	21	23	23
Vinson-Owen	Three classrooms available	Three classrooms available	Three classrooms available	Three classrooms available	No change	No change
Current Enrollment	374	374	384	384	422	422
WPS Design Enrollment	480	480	480	480	480	480
# Classrooms	24	24	24	24	24	24
Parkhurst	Renovation/addition for 420 students (PK-5)	New construction for 420 students (PK-K)	Renovation/addition for 420 students (PK-5)	New construction for 420 students (PK-K)	No change	No change
Current Enrollment	409	409	386	386	0	0
WPS Design Enrollment	420	420	400	400	0	0
# Classrooms	22	22	20	20	0	0
Project Budget	\$ 27,235,000	\$ 28,105,353	\$ 27,235,000	\$ 28,105,353	\$ 41,125,000 (Lynch) \$ 34,875,000 (Muraco)	


17 18

Winchester Public Schools | Winchester, MA

FLANSBURGH

223

FLANSBURGH



Cotton ES-3
Performe ES-3
Perf

20

19

Winchester Public Schools | Winchester, MA

FLANSBURGH

OPTION ES-5

NATION RESOURCE

STAFF PARKING

OPTION ES-5

NATION RESOURCE

PROJECT BUDGET

SILE Plan

Option ES-5

Lynch Elementary School

Windowsky, Massachusetts

FLANSBURGH

PITON ES-5
MAJOR RENOVATION 40,000 SE
ADOITION 34,219 SF
ISTORIES
OPTION ES-5
MAJOR RENOVATION ATTENTION ES-5
MAJOR RENOVATION ES-5

21

Winchester Public Schools | Winchester, MA

FLANSBURGH

ENROLLMENT OPTIONS REVIEW

Winchester Public Schools | Winchester, MA

FLANSBURGH

PROJECT BUDGET

NEW SCHOOL
85.455 SF

RAAREN

NEW SCHOOL
85.455 SF

RAAREN

RAME

RA



22

23 24

FLANSBURGH

Presentation 5 - November 28, 2016



WINCHESTER PUBLIC SCHOOLS FACILITIES MASTER PLAN

Winchester Public Schools | Winchester, MA

FLANSBURGH

1

What is a Master Plan?

The Facilities Master Plan is a vision for the support, expansion, consolidation, or transformation of district facilities that provides flexibility to accommodate changes in enrollment, educational goals and programming.

Definition

Winchester Public Schools | Winchester, MA

FLANSBURGH

2

A Master Plan DOES:

- \bullet align with WPS educational programming and planning.
- plan for growth (enrollment, staff, and physical plants).
- plan for best use of facilities & lands (fields).
- develop short- and long-term recommendations.
- develop preliminary cost, phasing and scheduling options.
- meet local planning and MSBA guidelines.
- assist in procurement of funds

A Master Plan DOES NOT:

- Does not define a financial plan for implementation.
- Does not design new buildings or additions.
- Does not directly fund implementation or construction.

FLANSBURGH Winchester Public Schools | Winchester, MA

Winchester Public Schools | Winchester, MA

FLANSBURGH

3

Why now? ...it's out of date - 2007 SHORT TERM (5-year) MASTER PLAN · Ambrose & Muraco modulars · McCall E-Wing addition Winchester High School LONG TERM (10-year) Vinson-Owen reconstruction · Muraco renovation & addition · Lynch renovation

Why now? We're also out of space

4

3.5% K-5 Enrollment Growth (post-redistricting Fall 2012)

2012-13: 2105 2013-14: 2136

2014-15: 2140

2015-16: 2179 = 74 more K-5 students

197 more K-12 students



FLANSBURGH Winchester Public Schools | Winchester, MA Winchester Public Schools | Winchester, MA FLANSBURGH



Process & Timeline




FLANSBURGH Winchester Public Schools | Winchester, MA FLANSBURGH

8

7


The Visioning Process

Winchester Public Schools | Winchester, MA



Focus on 21st Century Skills

- The six R's and the four C's
- Proactive, life long, continuous learning
- · Critical thinking
- Communication
- Collaboration
- Creativity
- Citizenship
- Academic mindset



Winchester Public Schools | Winchester, MA FLANSBURGH

Winchester Public Schools | Winchester, MA FLANSBURGH

9


Focus on Learning

- High-performance work environments
- Varied and collaborative
- Flexible and agile

inchester Public Schools | Winchester, MA



21st Century Design Patterns



FLANSBURGH Winchester Public Schools | Winchester, MA

McCall Middle School

The McCall Middle School is exhausted of space today, with the library now partitioned to provide two instructional spaces

The Schedule Committee (CBA) may find efficiencies in space

Early Options

McCall Middle School

- Repurpose WYC space below gymnasium
- multi-story addition behind library wing
- 6th Grade Academy relocated to Lincoln
- 6th Grade Academy relocated to Parkhurst

- 4 classrooms

Note: multi-story McCall addition includes potential for two additional specialized

Early Options

Winchester Public Schools | Winchester, MA FLANSBURGH

Winchester Public Schools | Winchester, MA

FI ANSBURGH

13

14

Elementary Schools

- Modular Classroom Additions (multiple)
- PK & K to Renovated or New Parkhurst
- New or Renovated/Expanded Muraco & Lynch
- Combination School (Lynch + Muraco)
- Combination School (Lynch, Muraco, Lincoln)

7 classrooms

420 students

1000 students (M & L)

1460 students

Early Options

Working Group - Scrubs the options

REPRESENTATION

- · School Committee (2)
- Superintendent
- WPS Dir of FInanceTown Manager
- · EFPBC (2)
- Finance Committee (2)
- Dept of Public Works (2)
- · Engineering & Planning

Winchester Public Schools | Winchester, MA FLANSBURGH

Winchester Public Schools | Winchester, MA

FLANSBURGH

15

16

School Committee VOTE - Nov 3rd

McCall Middle School

Pursue a 2-phase project: 1. Reconfigured WYC space and 2. 2-story library wing addition

6th Grade Academy no longer under consideration.





Phase 1 - Article 10 / Motion 3

Preferred Options

School Committee VOTE - Nov 3rd

McCall Middle School

Pursue a 2-phase project:

1. Reconfigured WYC space and 2. 2-story library wing addition

2. 2-Story library Wing addition

6th Grade Academy no longer under consideration.

PK & Elementary Students

Pursue separate development of new or renovated Muraco & Lynch. Consider Parkhurst "Grade-Shift" option.

Modulars & Combination School no longer under consideration.

Preferred Options

Windhester Public Schools | Windhester, MA

17 18

227

FLANSBURGH

2021 - 2022 5-YEAR K-5 ENROLLMENT CLASS SECTIONS SCHOOL YEAR 2016-201 2.136 actua 110 actua 106 avaliable 4 classroom

2021 - 2022 5-YEAR 6-8 ENROLLMENT

	Enrollment	Classrooms	Shortfall
School Year 2016-2017	1,150 actual	52 avaliable	0 classrooms
SCHOOL YEAR 2021-2022	1,196 proposed	56 required	56-52 = 4 classrooms

Winchester Public Schools | Winchester, MA FLANSBURGH


19

SHORT TERM & MID TERM OPTIONS FOR GRADES 6-8 Current Enrollment: 1,150 Students 2021-2022 Enrollment: 1,196 Students Enrollment Increase: +46 Students							
	PHASE I Youth Center Renovation 3-4 Classrooms	PHASE II New Addition Up to 6 Classrooms					
McCall Middle	Add elevator and renovated Youth Center	Newclassroom addition					
Current Enrollment	1,150	1,150					
WPS Design Enrollment	1,196	1,196					
# Classrooms	55-56	Up to 6 classrooms					
Project Bu	get \$ 2,500,000 - \$3,000,000	\$4,200,000 - \$4,800,000					

Winchester Public Schools | Winchester, MA

20

McCall Middle School - Classroom Reconfiguration - Option A



Phase I - Option A McCall Middle School Winchester, Massachusetts FLANSBURGH

Winchester Public Schools | Winchester, MA FLANSBURGH

22


 $\underline{\text{McCall Middle School - Classroom Reconfiguration - } \textbf{Option C}}$

21

McCall Middle School - Tech/Makerspace and Classroom Reconfiguration - Option B

Winchester Public Schools | Winchester, MA

Winchester Public Schools | Winchester, MA



23

FLANSBURGH

LOWER LEVEL PLAN

EXTENT OF RENOVATED AREA

PROJECT SUMMARY: The lower level area, currently utilized for the "Youth Center Program", will be reconfigured to accommodate four classrooms and a new elevator. Classrooms will have natural light with views to the exterior. A new elevator will connect the lower level to the first floor in the area adjacent to the existing egress static. Displaced Team Rooms, supporting field activities, requires study.

FLANSBURGH

EXTENSIVE RENOVATION
Lower Level Area: 5,500 square feet
First Floor Area: 300 square feet

McCall

Phase I - Option C McCall Middle School Winchester, Massachuse FLANSBURGH

Winchester Public Schools | Winchester, MA


EXTENT OF RENOVATED AREA

FLANSBURGH

FLANSBURGH

24

FLANSBURGH



Vinchester Public Schools | Winchester, MA FLANSBURG

25

DEMOUSH EXISTING
DEMOUS

PARKING SERVICE STATE OF SITE PLANSBURCH

PARKING SHOOL BE STATE SHOOL

26


Winchester Public Schools | Winchester, MA FLANSBURGH

27

Winchester Public Schools | Winchester, MA FLANSBURGH

28


Winchester Public Schools | Winchester, MA



30

29

FLANSBURGH



Current Enrollment: 2,136 Students 2021-2022 Enrollment: 2,217 Students 2011-2022 Enrollment +81 Students	PREK	- 5 Options for 2021 - 2022 School	YEAR
		Option ES-6A Muraco Renovations/Addition, PreK - 5	Option ES-6B Muraco New Construction, PreK - 5
Ambrose		No change	No change
Current Enrollment		440	440
WPS Design Enrollment		460	460
# Classrooms		23	23
Lincoln		No change	No change
Current Enrollment		410	410
WPS Design Enrollment		440	440
# Classrooms		21	21
Lynch w/ PreK		No change	No change
Current Enrollment		549	549
WPS Design Enrollment		540	540
# Classrooms		27	27
Muraco		Renovation/addition for 460 students (PK-5)	New construction for 460 students (PK-5)
Current Enrollment		404	404
WPS Design Enrollment		540	540
# Classrooms		28	28
Vison-Owen		No change	No change
Current Enrollment		422	422
WPS Design Enrollment		480	480
# Classrooms		24	24
Parkhurst		No change	No change
Current Enrollment		0	0
WPS Design Enrollment		0	0
# Classrooms		0	0
	Project Budget	\$ 34,000,000 - \$ 36,000,000	\$ 43,000,000 - \$ 45,000,

31

PES-6A

| Control Es-4A | Cont

Coption ES-68

Muraco Elementary School
Winchester, Massachusetts

Coption FS-68

32

Winchester Public Schools | Winchester, MA FLANSBURGH

33

Winchester Public Schools | Winchester, MA

Winchester Public Schools | Winchester, MA



Question & Comments

Winchester Public Schools | Winchester, MA FLANSBURGH

35

FLANSBURGH

FLANSBURGH

Presentation 6 - January 11, 2017



2021 - 2022 5-YEAR 6-8 ENROLLMENT ENROLLMENT School Year 2016-2017 SCHOOL YEAR 2021-2022 1,196 proposed 56 required 56-50 = 6 classroom

WINCHESTER PUBLIC SCHOOLS

FACILITIES MASTER PLAN

Winchester, Massachusetts | January 11, 2017

Winchester Public Schools | Winchester, MA FLANSBURGH 1

2021 - 2022 5-Year K-5 Enrollment						
	Enrollment	CLASS SECTIONS	Classrooms	Shortfall		
SCHOOL YEAR 2016-2017	2,136 actual	110 actual	106 avaliable	4 classrooms		
SCHOOL YEAR 2021-2022	2,217 proposed	113 required	113 required	113-106 = 7 classrooms		

Winchester Public Schools | Winchester, MA FLANSBURGH


2

Current Enrollment: 1,150 Students 2021-2022 Enrollment: 1,196 Students Enrollment Increase: +46 Students	HORT TERM & MID TERM OPTIONS FOR GRA	DES 6-8
	PHASE I Lower Level Renovation 3-4 Classrooms	PHASE II New Addition Up to 6 Classrooms
McCall Middle	Add elevator and renovated Youth Center	Newclassroom addition
Current Enrollment	1,150	1,150
WPS Design Enrollment	1,196	1,196
# Classrooms	55-56	Up to 6 classrooms

FLANSBURGH Winchester Public Schools | Winchester, MA Winchester Public Schools | Winchester, MA

3

McCall Middle School - Classroom Reconfiguration - Option A



Phase I - Option A McCall Middle School Winchester, Massachusetts FLANSBURGH

Winchester Public Schools | Winchester, MA

FLANSBURGH

LOWER LEVEL PLAN

FLANSBURGH

FLANSBURGH

5

FLANSBURGH

231

Winchester Public Schools | Winchester, MA

McCall Middle School - Tech/Makerspace and Classroom Reconfiguration - Option B

4






The lower level area, currently utilized for the "Youth Center Program", will be reconfigured to accommodate the Technology/CAD and Makerspace program. Team Rooms will remain to support field activities. The current Tech

PROJECT SUMMARY:

McCall Mid KEYPLAN



A new building addition will be located on the west side of the existing school. The new addition will accommodate two classrooms per floor on the lower and first floors. The library will have addition support with two new resource rooms on the second floor.

Areas by Floor Lower Level Area: 2,400 square feet First Floor Area: 2,400 square feet Second Floor Area: 2,400 square feet First Floor Area: 2,400 square feet First

McCall Middle School - Building Addition

Winchester Public Schools | Winchester, MA FLANSBURGH

Winchester Public Schools | Winchester, MA


Winchester Public Schools | Winchester, MA

FLANSBURGH

FLANSBURGH

7

McCall Middle School - Teacher's Workroom & Cafeteria Expansion



Phase II - Option A
McCall Middle School
Winchester, Massachusetts

8

Windhester Public Schools | Windhester, MA FLANSBURGH

DESCRIPTION BS.

SO, SIGN ST.

Winchester Public Schools | Winchester, MA FLANSBURGH

PARKING 100 SPACES AREA MAIN ENTERT OF BOLLARDS SCHOOL BOLLARDS SHOULD BE STATED AREA MAIN ENTERT OF BOLLARDS SCHOOL BOLLARDS

10

Winchester Public Schools | Winchester, MA FLANSBURGH

11 12

arrent Enrollment: 2,136 Students 21-2022 Enrollment: 2,217 Students vrollment Increase: +81 Students	- 5 Options for 2021 - 2022 School	
	Option ES-5A Lynch Renovations/ Addition, PreK - K	Option ES-5B Lynch New Construction, PreK - K
Ambrose	No change	No change
Current Enrollment	440	440
WPS Design Enrollment	460	460
# Classrooms	23	23
Lincoln	No change	No change
Current Enrollment	410	410
WPS Design Enrollment	440	440
# Classrooms	21	21
Lynch w/ PreK	Renovation/addition for 580 students (PK-5)	New construction for 580 students (PK-5)
Current Enrollment	549	549
WPS Design Enrollment	580	580
# Classrooms	29	29
Muraco	No change	No change
Current Enrollment	404	404
WPS Design Enrollment	420	420
# Classrooms	21	21
Vinson-Owen	No change	No change
Current Enrollment	422	422
WPS Design Enrollment	480	480
# Classrooms	24	24
Parkhurst	No change	No change
Current Enrollment	0	0
WPS Design Enrollment	0	0
# Classrooms	0	0

PANONE BOLLAND BOLLAND

Winchester Public Schools | Winchester, MA

FLANSBURGH

13

Winchester Public Schools | Winchester, MA

Winchester Public Schools | Winchester, MA

Winchester Public Schools | Winchester, MA

FLANSBURGH

FLANSBURGH

CETON ES-38

SERVICE
REMOVABLE
BOLLANGES

SERVICE
REAL PRINCIPIED IN RESOLUTION

SERVICE
REAL PRINCIPIED IN RESOLUTION

PLAY AREA

OPTION ES-38

SERVICE
REMOVABLE
BOLLANGES

SERVICE
REAL PRINCIPIED IN RESOLUTION

OPTION ES-38

Lynch Elementary School

REMOVABLE
REMOVABLE
BOLLANGES

SERVICE
REMOVABLE
BOLLANGES
BOLLANGE

14

Current Enrollment: 2,136 Students 2021-2022 Enrollment: 2,217 Students Enrollment Increase: +81 Students	PreK	- 5 Options for 2021 - 2022 School	Year
		Option ES-6A Muraco Renovations/Addition, PreK - 5	Option ES-6B Muraco New Construction, PreK - 5
Ambrose		No change	No change
Current Enrollment		440	440
WPS Design Enrollment		460	460
# Classrooms		23	23
Lincoln		No change	No change
Current Enrollment		410	410
WPS Design Enrollment		440	440
# Classrooms		21	21
Lynch w/ PreK		No change	No change
Current Enrollment		549	549
WPS Design Enrollment		540	540
# Classrooms		27	27
Muraco		Renovation/addition for 460 students (PK-5)	New construction for 460 students (PK-5)
Current Enrollment		404	404
WPS Design Enrollment		540	540
# Classrooms		28	28
Vinson-Owen		No change	No change
Current Enrollment		422	422
WPS Design Enrollment		480	480
# Classrooms		24	24
Parkhurst		No change	No change
Current Enrollment		0	0
WPS Design Enrollment		0	0
# Classrooms		0	0
Proje	ect Budget	\$ 34,000,000 - \$ 36,000,000	\$ 43,000,000 - \$ 45,000,000

Winchester Public Schools | Wincheste

FLANSBURGH

15

Corron Es-da

Site Pan

Corron Es-da

Muraco Elementary School

Murchaster, Massachusets

FLANSBURGH

Corron Es-da

Muraco Elementary School

Murchaster, Massachusets

16



FLANSBURGH

Windhester Public Schools | Winchester, MA FLANSBURGH




PreK - 5 (Carrent Eurollment: 2,136 Students 2021-2022 Eurollment: 2,217 Students Eurollment Increase: 481 Students	ient: <u>2.217 Students</u>	
	Option ES-7 Mystic Renovations/Addition, Grade Shift	
Cost of Construction	\$19,600,000 to \$20,580,000	
Construction Contingency	\$196,000 to \$205,000	
Soft Cost	\$5,939,000 to \$6,235,000	
Probable Cost Range	\$25,735,000 to \$27,020,000	

Winchester Public Schools | Winchester, MA

Winchester Public Schools | Winchester, MA FLANSBURGH


19

Winchester District Office		
Space	Square Footage	
Vestibule	80-s.f.	
Men's	60-s.f.	
Women's	60-s.f.	
Waiting	60-s.f.	
Office	125-s.f.	
Office	300-s.f.	
Office	300-s.f.	
Office	300-s.f.	
Break Room	80-s.f.	
Reception	450-s.f.	
Administration	250-s.f.	
Corridor	300-s.f.	
Storage	500-s.f.	
Mail/Copy	300-s.f.	
Conference Room	350-s.f.	
TOTAL	4,140-s.f.	



Winchester Public Schools | Winchester, MA FLANSBURGH

Winchester Public Schools | Winchester, MA FLANSBURGH






Winchester Public Schools | Winchester, MA FLANSBURGH

Winchester Public Schools | Winchester, MA FLANSBURGH


23 24

FLANSBURGH

FLANSBURGH



25



26

Winchester Public Schools | Winchester Public Schools | Winchester Public Schools | Winchester Public Schools | Winchester, MA

Presentation 7 - March 16, 2017



WINCHESTER PUBLIC SCHOOLS

FACILITIES MASTER PLAN Winchester, Massachusetts | March 16, 2017

Winchester Public Schools FLANS DURGH

1

Winchester Public Schools 6-8 Design Enrollment Options


McCall Middle School

Winchester Public Schools FLANSBURGH

2

IGN ENROLLMENT OPTIONS WINCHESTER PUBLIC SCHOOLS

McCall Middle School - Classroom Reconfiguration and Elevator Addition




Phase I - Option A
McCall Middle School
Winchester, Massachusetts

FLANSBURGH


3

Winchester Public Schools 6-8 Design Enrollment Options



5


McCall Middle School - Specialists Space & Workroom with adiacent Storage



Prase i McCall Middle School FLANSBURGH
Winchester, Massachusetts

4

6-8 DESIGN ENROLLMENT OPTIONS WINCHESTER PUBLIC SCHOOLS



WINCHESTER PUBLIC SCHOOLS

6-8 Design Enrollment Options

Grades 6-8 Options for 2021 - 2022 School Year		
Current Enrollment:	1,150 Students	
2021-2022 Enrollment:	1.196 Students	
Enrollment Increase:	+46 Students	
		Phase II
		McCall Middle School New Classroom Addition
	Cost of Construction	\$1,950,000 to \$2,100,000
	Construction Contingency	\$195,000 to \$210,000
	Soft Cost	\$643,000 to \$693,000
	Probable Cost Range	\$2,788,000 to \$3,003,000


6-8 Design Enrollment Options

WINCHESTER PUBLIC SCHOOLS

McCall Middle School - Cafeteria Expansion Option 1

8

McCall Middle School - Cafeteria Expansion Option 3



The first floor plan expands the cafeteria into an adjacent classroom.

PROJECT SUMMARY:



Phase II McCall Middle School Winchester, Massachuse

FLANSBURGH

7

WINCHESTER PUBLIC SCHOOLS

6-8 Design Enrollment Options

6-8 Design Enrollment Options

WINCHESTER PUBLIC SCHOOLS

McCall Middle School - Cafeteria Expansion

Option 2



PROJECT SUMMARY:

The first floor plan expands the cafeteria into two adjacent classrooms, eliminatin one and reducing the Nutrition class by half.



KEYPLAN

FLANSBURGH

Phase II McCall Middle School

The first floor plan expands the cafeteria onto the exterior terrace.

FIRST FLOOR PLAN

FLANSBURGH


9

WINCHESTER PUBLIC SCHOOLS

Phase II McCall Middle School Winchester, Massachuse

6-8 DESIGN ENROLLMENT OPTIONS

WINCHESTER PUBLIC SCHOOLS



PROJECT SUMMARY: A new building addition will be located on the west side of the existing school. The new addition will accommodate two team rooms and tollet rooms on the lower floor and two classorooms on the first floor. The library will have the support of two new resource rooms on the second floor.

10









BASEMENT LEVEL PLAN Phase IIA McCall Middle School Winchester, Massachusetts

FLANSBURGH


GRADES 6-8 OPTIONS FOR 2021 - 2022 SCHOOL YEAR

Current Enrollment: 1,150 Students		
2021-2022 Enrollment: 1,196 Students		
Enrollment Increase: +46 Students		
PHASE II McCall Middle School Cafeteria Expansion		
Option 1		
Cost of Construction	\$130,000 to \$143,000	
Construction Contingency	\$13,000 to \$14,300	
Soft Cost	\$43,000 to \$47,00	
Probable Cost Range	\$186,000 to \$204,000	
Option 2		
Cost of Construction	\$343,000 to \$377,000	
Construction Contingency	\$34,300 to \$37,700	
Soft Cost	\$113,200 to \$124,500	
Probable Cost Range	\$490,500 to \$539,200	
Option 3		
Cost of Construction	\$1,134,300 to \$1,248,000	
Construction Contingency	\$113,400 to \$124,800	
Soft Cost	\$374,300 to \$411,800	
Probable Cost Range	\$1,622,000 to \$1,784,600	

11

WINCHESTER PUBLIC SCHOOLS 6-8 DESIGN ENROLLMENT OPTIONS

McCall Middle School - Classroom Reconfiguration and Elevator Addition



Grades PreK-5

Winchester Public Schools FLANSBURGK

14

Phase IA
McCall Middle School
Winchester, Messachusetts
FLANSBURGH

13

DEMOLIPHENSTRY

ADDITION

NEW ASCIDION
3,160 SP


CAR D_{ROB-OFF}

PARKING
10 SPACES

SILE PIgn

S-5 DESIGN ENROLLMENT OPTIONS

REMOVABLE



15


WINCHESTER PUBLIC SCHOOLS

PREK-5 DESIGN ENROLLMENT OPTIONS

FLANSBURGH

PREK-5 DESIGN ENROLLMENT OPTIONS

Winchester Public Schools






16

WINCHESTER PUBLIC SCHOOLS

PREK-5 DESIGN ENROLLMENT OPTIONS



PreK-5 Design Enrollment Options Winchester Public Schools

PreK - 5 Options for 2021 - 2022 School Year			
Current Enrollment: 2021-2022 Enrollment: Enrollment Increase:	2,136 Students 2.217 Students +81 Students		
		Option ES-2: Grade Shift Parkhurst, Renovation/Addition	Option ES-3: Grade Shift Parkhurst, New Construction
Cost o	f Construction	\$25,000,000 to \$26,250,000	\$26,700,000 to \$28,000,0
Constructio	n Contingency	\$25,000,000 to \$26,250,000	\$26,700,000 to \$28,000,0
	Soft Cost	\$8,250,000 to \$8,670,000	\$8,800,000 to \$9,240,01
Probal	ble Cost Range	\$35,750,000 to \$37,570,000	\$38,170,000 to \$40,000,0
		Option ES-5C: New Lynch with Old Lynch Occupied	Option ES-6B: New Muraco with Old Lynch Occupied
Cost o	f Construction	\$34,658,000 to \$38,124,000	\$30,326,000 to \$33,359,0
Constructio	n Contingency	\$3,466,000 to \$3,812,000	\$3,033,000 to \$3,366,0
	Soft Cost	\$10,397,000 to \$11,437,000	\$9,098,000 to \$10,008,0
Proba	ble Cost Range	\$48,521,000 to \$53,373,000	\$442,457,000 to \$46,703,0


.

WINCHESTER PUBLIC SCHOOLS

PREK-3 DESIGN ENROLLMENT OPTIONS

SPACE SUMMARY LEGEND

Order Mandrial States



FLANSBURGH

20

PROCE ANAMARY LEGEND

GORE ANAMARY LEGEND

HECAL ROUGHTON

HAS THE PROBLECK EXCACATON

HOMO AS FOOD SERVICE

HOMO AS FOOD SERVICE

HOMO AS FOOD SERVICE

HOMO AS FOOD SERVICE

HOMO AS TO COMERCE

HOMO AS TO COME AS MANTENANCE

Third Floor Plan

Third Floor Addition
Vinson-Owen Elementary School
Winchester, Massachusetts

FLANSBURGH

22

21


District Office

DISTRICT OFFICE RELOCATION OPTIONS


PREK-5 DESIGN ENROLLMENT OPTIONS

WINCHESTER PUBLIC SCHOOLS

WINCHESTER PUBLIC SCHOOLS



Section 5 | Presentations & Meeting Notes




26

25

WINCHESTER PUBLIC SCHOOLS

DISTRICT OFFICE RELOCATION OPTIONS




DISTRICT OFFICE RELOCATION OPTIONS

DISTRICT OFFICE RELOCATION OPTIONS

WINCHESTER PUBLIC SCHOOLS


WINCHESTER PUBLIC SCHOOLS



28

27

DISTRICT OFFICE KELOCATION OPTIONS



DISTRICT OFFICE RELOCATION OPTIONS

WINCHESTER PUBLIC SCHOOLS

	WPS-1	WPS-2
Cost of Construction	\$1,821,000 to \$2,003,000	\$1,691,000 to \$1,8
Construction Contingency	\$182,000 to \$200,000	\$169,000 to \$1
Soft Cost	\$601,000 to \$661,000	\$558,000 to \$6
Probable Cost Range *Does not include phasing cost	\$2,604,000 to \$2,864,000	\$2,418,000 to \$2,6
	WPS-3	WPS-4
Cost of Construction	\$1,664,000 to \$1,830,000	\$1,691,000 to \$1,8
Construction Contingency	\$166,000 to \$183,000	\$169,000 to \$1
Soft Cost	\$549,000 to \$604,000	\$558,000 to \$6
Probable Cost Range *Does not include phasing cost	\$2,604,000 to \$2,864,000	\$2,418,000 to \$2,6
	WPS-5	WPS-6
Cost of Construction	\$1,004,000 to \$1,104,000	\$1,990,000 to \$2,
Construction Contingency	\$100,000 to \$140,000	\$199,00 to \$2
Soft Cost	\$331,000 to \$364,000	\$657,000 to \$7
Probable Cost Range *Does not include phasing cost	\$1,335,000 to \$1,578,000	\$2,846,000 to \$3,1

29 30

WINCHESTER PUBLIC SCHOOLS

ENROLLMENT IMPACTS

ENROLLMENT IMPACTS			
Impacting Factor	Student Impacted		
Cambridge Street Development	160 Students		
New Impacts on Enrollment	Student Impacted		
2016 Single Family Housing Bedroom Increase	40 Students		
Holton Street Development	120 Students		
Total Combined Impacts	320 Students		
Other Potential Impacts (If Developed)	Units		
Forest Ridge	(300 Units, on hold)		
Krafts	(12 Single Family Houses + 20 Townhouses)		
Main Street North	(40 Units)		
Highland Avenue	(40 Units)		
Mahoney's	(40 Units)		
Waterfield Street	(40 Units)		
2017 - 2026 Single Family Housing Bedroom Increase	TBD		

Presentation 8 - March 30, 2017



McCall Middle School

Winchester Public Schools FLANSBURGK

Winchester Public Schools Facilities Master Plan

Winchester, Massachusetts | March 16, 2017


Winchester Public Schools FLANSBURGH

1

Winchester Public Schools 6-8 Design Enrollment Options

WINCHESTER PUBLIC SCHOOLS

McCall Middle School - Classroom Reconfiguration and Elevator Addition






3

WINCHESTER PUBLIC SCHOOLS



2



Phase I
McCall Middle School
FLANSBURGH
Winchester, Massachusetts

4

6-8 Design Enrollment Options

6-8 DESIGN ENROLLMENT OPTIONS


\$536,000 to \$563,000

WINCHESTER PUBLIC SCHOOLS



5

Soft Co:



6

WINCHESTER PUBLIC SCHOOLS 6-8 DESIGN ENROLLMENT OPTIONS 6-8 DESIGN ENROLLMENT OPTIONS WINCHESTER PUBLIC SCHOOLS McCall Middle School - Team Room & Toilets at Playing Field GRADES 6-8 OPTIONS FOR 2021 - 2022 SCHOOL YEAR EXTENT OF -RENOVATED AREA PROJECT SUMMARY: The lower level area, currently utilized for Building Storage, will be reconfigured to accommodate new Team Rooms and toilets rooms with access to the adjacent playing field. PHASE II McCall Middle School New Classroom Addition Cost of Construct \$2,788,000 to \$3,003,000 MINOR RENOVATION
Lower Level Area: 1,770 square feet
Total Area: 1,770 square feet Cost of Construct Construction Continge \$55,300 to \$60,830 \$774,200 to \$851,620 McCall Middle School KEYPLAN BASEMENT LEVEL PLAN FLANSBURGH 7 8 WINCHESTER PUBLIC SCHOOLS 6-8 Design Enrollment Options 6-8 Design Enrollment Options WINCHESTER PUBLIC SCHOOLS McCall Middle School - Cafeteria Expansion McCall Middle School - Cafeteria Expansion Option 1 PROJECT SUMMARY: The first floor plan expands the cafe EXTENT OF RENOVATED AREA MAJOR RENOVATION

Total Area: 2,400 square fee FIRST FLOOR PLAN KEYPLAN Phase II McCall Middle School Winchester, Massachuse Phase II McCall Middle School FLANSBURGH FLANSBURGH 9 10 6-8 DESIGN ENROLLMENT OPTIONS WINCHESTER PUBLIC SCHOOLS McCall Middle School - Cafeteria Expansion GRADES 6-8 OPTIONS FOR 2021 - 2022 SCHOOL YEAR PROJECT SUMMARY: The first floor plan expands the cafeteria onto the exterior terrace. Cost of Construction \$13,000 to \$14,300 Cost of Construction \$34,300 to \$37,700 \$490,500 to \$539,200


11 12

FLANSBURGH

FIRST FLOOR PLAN

Option 3

Cost of Construction



FLANSBURGH

Grades PreK-5

Winchester Public Schools

FLANSBURGH

15 WINCHESTER PUBLIC SCHOOLS FLANSBURGH

16 PREK-5 DESIGN ENROLLMENT OPTIONS WINCHESTER PUBLIC SCHOOLS ES-5C Site Plan FLANSBURGH

17 18 FLANSBURGH

WINCHESTER PUBLIC SCHOOLS

PLANSBURGH

Option ES-SC - Phase III
Lynch Elementary School
Winchester, Messachusetts

FLANSBURGH

Cypton ES-RB andray School
Minchaster, Massachusetts

FLANSBURG

20

19

WINCHESTER PUBLIC SCHOOLS

WINCHESTER PUBLIC SCHOOLS

PREK-5 DESIGN ENROLLMENT OPTION

PREK-5 DESIGN ENROLLMENT OPTIONS

PreK-5 Design Enrollment Options

PreK - 5 Options for 2021 - 2022 School Year

	Option ES-2: Grade Shift Parkhurst, Renovation/Addition	Option ES-3: Grade Shift Parkhurst, New Construction
Cost of Construction	\$25,000,000 to \$26,250,000	\$26,700,000 to \$28,000,000
Construction Contingency	\$25,000,000 to \$26,250,000	\$26,700,000 to \$28,000,000
Soft Cost	\$8,250,000 to \$8,670,000	\$8,800,000 to \$9,240,000
Probable Cost Range	\$35,750,000 to \$37,570,000	\$38,170,000 to \$40,000,000
	Option ES-5C: New Lynch with Old Lynch Occupied	Option ES-6B: New Muraco with Old Lynch Occupied
Cost of Construction	Option ES-5C: New Lynch with Old Lynch Occupied \$34,658,000 to \$38,124,000	Option ES-6B: New Muraco with Old Lynch Occupied \$30,326,000 to \$33,359,000
Cost of Construction Construction Contingency		
· · · · · · · · · · · · · · · · · · ·	\$34,658,000 to \$38,124,000	\$30,326,000 to \$33,359,000


22

FLANSBURGH


District Office

21

Winchester Public Schools FLANSBURGH



Section 5 | Presentations & Meeting Notes



Cyclion WPS-3

Cyclion WPS-3

Sylo Plan

Windesder, Massachuseds

FANSBURGH

26

WINCHESTER PUBLIC SCHOOLS

WINCHESTER PUBLIC SCHOOLS

FLANSBURGH

25

WINCHESTER PUBLIC SCHOOLS DISTRICT OFFICE RELOCATION OPTIONS

WPS-4

Option WP

DISTRICT OFFICE RELOCATION OPTIONS

DISTRICT OFFICE RELOCATION OPTIONS

DISTRICT OFFICE RELOCATION OPTIONS

MADISON AVE

MARSHALL RO

Site Plan

27

DISTRICT OFFICE RELOCATION OPTIONS

AMBROSE
ELEMENTARY
SCHOOL

AMBROSE
ELEMENTARY
SCHOOL

AMBROSE
ELEMENTARY
SCHOOL

RICHARD

AMBROSE
ELEMENTARY
SCHOOL

RICHARD

RIC

Winchester Public Schools

District Office Relocation		
	WPS-1	WPS-2
Cost of Construction	\$1,821,000 to \$2,003,000	\$1,691,000 to \$1,
Construction Contingency	\$182,000 to \$200,000	\$169,000 to \$
Soft Cost	\$601,000 to \$661,000	\$558,000 to \$6
Probable Cost Range *Does not include phasing cost	\$2,604,000 to \$2,864,000	\$2,418,000 to \$2,0
	WPS-3	WPS-4
Cost of Construction	\$1,664,000 to \$1,830,000	\$1,691,000 to \$1,
Construction Contingency	\$166,000 to \$183,000	\$169,000 to \$
Soft Cost	\$549,000 to \$604,000	\$558,000 to \$6
Probable Cost Range *Does not include phasing cost	\$2,604,000 to \$2,864,000	\$2,418,000 to \$2,6
	WPS-5	WPS-6
Cost of Construction	\$1,004,000 to \$1,104,000	\$1,990,000 to \$2
Construction Contingency	\$100,000 to \$140,000	\$199,00 to \$
Soft Cost	\$331,000 to \$364,000	\$657,000 to \$
Probable Cost Range *Does not include phasing cost	\$1,335,000 to \$1,578,000	\$2,846,000 to \$3,

28

29 30

WINCHESTER PUBLIC SCHOOLS

ENROLLMENT IMPACTS

Enrollment Impacts		
Impacting Factor	Student Impacted	
Cambridge Street Development	160 Students	
New Impacts on Enrollment	Student Impacted	
2016 Single Family Housing Bedroom Increase	40 Students	
Holton Street Development	120 Students	
Total Combined Impacts	320 Students	
Other Potential Impacts (If Developed)	Units	
Forest Ridge	(300 Units, on hold)	
Krafts	(12 Single Family Houses + 20 Townhouses)	
Main Street North	(40 Units)	
Highland Avenue	(40 Units)	
Mahoney's	(40 Units)	
Waterfield Street	(40 Units)	
2017 - 2026 Single Family Housing Bedroom Increase	TBD	

Presentation 9 - May 16, 2017



K-5 Design Options

K-5 Design Options


Winchester Public Schools Facilities Master Plan

Winchester, Massachusetts | May 16, 2017

Winchester Public Schools FLANSBURGH


1

K-5 Design Options



3

OPTION ES-6C - Muraco Elementary School




5

Winchester Public Schools FLANSBURGH


2

OPTION ES-5D - Lynch Elementary School



4

OPTION ES-8 - Vinson-Owen Elementary School








FLANSBURGH Winchester Public Schools 7

FLANSBURGH Winchester Public Schools

8

6-8 Design Options

McCall MIDDLE SCHOOL - Phase I



FLANSBURGH




McCall MIDDLE SCHOOL - Phase I

EXTENT OF -RENOVATED AREA

Classrooms Required:

PROJECT SUMMARY: The lower level area, currently utilized for Building Storage, will be reconfigured to accommodate a new Specialists Space & Workroom with adjacent Storage



Winchester Public Schools FLANSBURGH

10



9


Based on Enrollment Numbers Current Enrollment: 2026-2027 Enrollment:

Winchester Public Schools

Winchester Public Schools

McCall MIDDLE SCHOOL - Phase II


BASEMENT LEVEL PLAN



Winchester Public Schools

FLANSBURGH

FLANSBURGH



Meeting Notes - June 16, 2016

Winchester Public Schools



Educational Working Group

Master Planning Workshop Notes June 16, 2016

Priority Goals for Master Planning

The following list of priority goals for the Winchester Public School's Master Planning effort was recorded during the participant introduction section of the June 16, 2016 Master Planning Workshop, with each participant offering one or more priority goals. The 12-person group included administrativ leadership from WPS and school principals.



Priorities for the Master Plannina

- Being able to provide facilities that match
- Collaborative and adequate space windows

 - o Hearing impaired students o Furniture
- Facilities match models that we have o One floor elementary schools are desirable
- Student centered real world stations -
- Project Based Learning (PBL)- we do it well in early childhood - FLEX design patterns

- SAFETY
- o Embedded within the school
- o Integrate senior citizens / community
- Social emotional health
- Authentic learning
- Continue to inspire teachers to be the best they can be
- Students learning all the time
 - o Flex workspace
- o Collaboration multi-age classrooms
- o Quiet spaces



1

Winchester Public Schools



Visioning Workshop One Notes June 16, 2016

SCOG Analysis

The following SCOG Analysis of WPS's current strengths, challenges, opportunities and goals with regard to its academic programs and facilities was recorded during the June 16, 2016 Master Planning Workshop. The 12-person group included administrative leadership from WPS and school principals.



STRENGTHS

- Proactive and not reactive Focus on getting the biggest bang for the
- All elementary schools have perception of
- All elementary schools have perception or equity
 Neighborhood schools walker
 Engaged parents (also a challenge)
 Great kids they want to be at school
 Great kids they want to be at school
 Great background/enrichment
 esperiences outside of school
 Pride in schools
 Educators / teachers committed
 Talented / caring
 Community support
 Teacher Autonomy

- - Teacher Autonomy
 (also a challenge)

- Generous ED Foundation
 - o Tech funding
- o Past Successes (also a challenge) Spawn risk-taking ional Development - Opportunities

- Professional Development Opportunities
 Space to bring people together
 Leadership team always looking at big and small picture
 Relocation companies sending families/kids to Winchester
 Growing international diversity
 Strong investment demand (olso a challenge)
 Older students working with younger students and seniors
 Spanish classes

CHALLENGES

- Going from really good to great
- No urgency
 Rooms with no ventilation / windows
 Tension between transitional families and
- town folks
 - Plays out in many ways
 - High cost of real estate (purchasing) vs. investing in the community
- Historical funding of buildings but not
- programming (overrides)
 o Funding places not people
 Decision making based on aesthetics not
 quality programming learning mismatch
 Perception is important (testing) makes
- changing practice harder Maintaining focus on essential vs. "outer
- newvistadesign Envisioning 21st Century Schools | Flansburgh Architects

Priority Goals for Master Planning (continued)

- · Differentiated Programming
 - o Find programs that work for you
- Permeable
- Access to professionals
- Continuous learning
 Cost effective value added
- o Space & Time scheduling movement
- Classrooms & Spaces
- De-escalation rooms
- Hubs
 - Consider distributed dining
 - Collaboration spaces
 - o Data room

- Consider differentiated clusters of spaces
- Maximize older school spaces
 - o Thinking outside of the box
 - Green space sustainability
 Invite more ways for kids to be active
- · School as community resource
 - o Encourage community use

newvistadesign Envisioning 21st Century Schools | Flansburgh Architects

2

- Teacher autonomy reluctance to collaborate
- reacher auconator or innovate

 Stress that families and students feel

 Staff members stressed and

 Trived
- engagement in some schools
- Sharp reduction in family and community
- How to better prioritize investments and

OPPORTUNITIES AND GOALS

- How to meld /work with Rec Department to offer in-house before and after school
- programming New HS renovation

- New HS renovation

 o Learning commons

 o Maker space

 Cross grade / school interactions

 o After school programs that students
 can get involved in before and after school
- Lynch / Muraco Elementary Schools
- Uynch / Muraco Elementary Schools
 Within walking distance of HS
 Geography lends itself to being more engaged
 World Languages non Western
 Put more resources into special needs programs and students
 More efficiency space / resources
- Lots of talent in district
 - Use most effectively
 - Making sure all are included Break down walls (co-teaching)

disciplinary incidents - but still there)

- goals

 o Bring varied (floating) organizations together to prioritize

 o Create a more cohesive community
- · Extraordinarily strong programming Library / Media

 - Art / Music / Tech

- Better prioritize investments and goals
 Bring varied (floating) organizations
- together to prioritize Create a more cohesive community
- Capture resources of collective community
- for benefit of entire town Identify shared spaces as community
- resources

 o Provide access to community groups
 in thoughtful ways

 bildbood huilding?
- Extended day programming Before school too
- Minimally adult supervised play

 o Promote autonomy

newvistadesign Envisioning 21th Century Schools | Flansburgh Architects

4

Winchester Public Schools



Visioning Workshop One Notes | June 16 2016

21st Century Learning Goals

The following comments about "21st Century Learning Goals" for Winchester Public School students were recorded at the June 16, 2016 workshop. Participants expressed the desire to take the time to step back and look at their district vision and mission. The skills and learning goals that rose to the top as being of most importance to Winchester Public Schools are

• Empathy and Humility

Coalition of Essential Schools

Social Emotional Development

o Ruler Program out of Yale

Resiliency

Adaptability

- All starts with adults giving up control
- o Look at how we live it
- Start with adults









Shelving / recyclables One stop shop (Discovery Museum in Acton)

Within library / media How do we schedule librarians Fab Lab at

5

ELEMENTARY

MAKER SPACES

INNOVATION LAB

Heavy/light Clean / dirty

CNC /CAD

LIBRARY / MEDIA Opportunities on elementary level Multi-purpose

- Books dispersed Maker space / tech
- K-2 Library?
 3-5 Library?
 Gen resource materials
- Media specialists are key Heart of school
- Movable stacks

DISTRIBUTED DINING

- Smaller scale
 Since don't cook on site can look at distributing dining / food

INDOOR/OUTDOOR CONNECTIONS

- Natural light Different learning environment Caveat: provide some shelter
- Avoid large expanses of paving
 Connect to nature /
 Commitment to walking, biking, green space
- (paths, trans/access)
- Winchester trail
- WIFFY (ED Foundation) gardens

- How much do we really need? Many students don't use them - more digital
- Most kids have digital devices Flexible storage
 In MS - use them for backpacks
- Charging stations

- In Learning Commons Classrooms
- At elementary its about storage boxes /



newvistadesign Envisioning 21th Century Schools Flansburgh Architects

Winchester Public Schools



Visioning Workshop One Notes June 16, 2016

21st Century Design Patterns

The following set of priority "21st Century Design Patterns" for the Winchester Public Schools Master Planning process was recorded during the June 16, 2016 Master Planning Workshop. The 12-person group included administrative leadership from WPS and school principals.

- Concierge Hotel Welcoming
- "Double buzz"
- "Double buzz"
 Secure but welcoming
 Avoid "blind" entrances

Distributed services / adults

- Kids seeking out private spaces and supervised
 Does every kid need to have a desk

- Co-teaching
 Tri-teach model working as a model -
- some flexible walls
- Flexibility allows changes in ED model

- Teacher resource / meeting
- Teacher resource ,
 Free up classroom









6

Winchester Public Schools



Visioning Workshop One

Notes June 16, 2016

Guiding Design Principles

Guiding Design Principles offer a framework of educational and facility related priorities that prove invaluable in helping stakeholders and design team members to set design goals and focus their work

The following set of priority Guiding Design Principles for the Winchester Public Schools Master Planning process was recorded during the June 16, 2016 Master Planning Workshop. The 12-person group included administrative leadership from WPS and school principals.

1. Adaptable and Flexible

2. Community Resource

o Community Access

3. Inquiry-Based Learning

- o Authentic Learning
- o Interdisciplinary Space o Empowering Independent
 - Learners

4. Professional & Collaborative

5. Personalized & Differentiated

- o Small School Feel,
 - Large School Setting
- o Collaborative Not Competitive
- o Comfortable and Inviting

newvistadesign Envisioning 21st Century Schools Flansburgh Architects

7

Winchester Public Schools



Educational Working Group

Visioning Workshop

June 16, 2016

Agenda

EXPECTED OUTCOMES: By the end of the session we will have begun to...

- Share Priority Goals for Winchester Public School's master planning process
- Discuss 21st century teaching and learning and identify 21st Century Learning Goals and initiatives for Winchester Public Schools
- Assess Winchester Public School's **Strengths, Challenges, Opportunities, and Goals** with regard to the development of its academic programs and school facilities
- Explore and prioritize a range of architectural **Design Patterns** that will best support 21st century teaching and Explore an prioritize a rating to architectural usage Patterns into win uses support 2. Century te learning within Minchester Public Schools

 Create a set of Guiding Principles and priorities for Winchester Public School's master planning process Articulate Blue Sky felesa for the master planning effort

 Discuss Next Steps for master planning

Time	Activity	Purpose
8:30 - 9:15	Workshop Goals and Introductions Workshop overview Introductions Priority Goals for the master planning process	Introduce participants, and clarify agenda and desired outcomes for this workshop. Share some of our priority goals for the master planning process.
9:15-10:15	Self Control Cabrolined Location Control	Ideals and discussion of helf-

	Workshop overview Introductions Priority Goals for the master planning process	introduce participants, and clarify agenda and desired outcomes for this workshop. Share some of our priority goals for the master planning process.
9:15-10:15	21" Century Schools and Learning Goals Interactive Presentation: 21" Century Teaching and Learning Videos and discussion Prioritization of 21" Century Learning Goals	identify and discuss elements of 21" century teaching and learning as connected to Winchester Public School's approach to its educational programming.
10:15-10:30	BREAK	



newvistadesign Envisioning 21th Century Schools Flansburgh Architects

9 I Page

newvistadesign Envisioning 21st Century Schools Flansburgh Architects

10 | Page

9

Exploring Learning Goals for the 21st Century

The following learning goals listings represent the attempts of a variety of thoughtful and successful schools, school networks, and educational organizations to identify the learning goals and skills that are most important for preparing today's students for success in life, work and post-secondary study. As you look through them, think about which 21st century learning goals you find most meaningful for your students and why.

Taxonomy

- Knowledge
 Comprehension
 Application
 Analysis
 Synthesis
 Evaluation

Partnership for 21st Century Skills



NCREL - North Central Regional Education Laboratory

- Digital Age Literacy
 Basic, scientific, economic and technological

- Inventive Thinking

 Adaptability and managing complexity

 Self-direction

 Curiosity, creativity, and risk taking

 ligher-order thinking and sound reason

- Teaming, collaboration and interpersonal Self-direction Personal, social, and civic responsibility Interactive communication

- High Productivity
 Prioritizing, planning and managing for results
 Effective use of real world tools
 Ability to produce relevant, high-quality products



New Tech Network

Coalition of Essential Schools Habits of Mind Technology Literacy

- iecnnology Literacy
 Citizenship and Ethics
 Critical Thinking
 Career Preparation
 Collaboration
 Written Communication
 Oral Communication
 Curricular Literacy
- Perspective Analysis
 Imagination
 Empathy
 Communication
 Commitment


11 I Page

- - Committee
 Humility
 Joy
- National Association for Independent Schools Analytical and creative thinking and problem solving
 Complex communication - oral and written
 Leadership and teamwork
 Digital and quantitative literacy
 Global perspective literacy
 Adaptability, including a relative literacy
 Integrity and ethical decision making

Wagner: Seven 21st Century Skills

wagner: seven ZIST Century sk Critical Thinking and problem solving Collaboration and leadership A glitty and adaptability Initiative and entrepreneurship Effective written and oral communicat Assessing and analyzing information Curiosity and imagination





10

Exploring Learning Goals for the 21st Century

The following learning goals listings represent the attempts of a variety of thoughtful and successful schools, school networks, and educational organizations to identify the learning goals and skills that are most important for preparing today's students for success in life, work and post-secondary study. As you look through them, think about which 21st century learning goals you find most meaningful for your students and why.

The MET Technical School

- Ine ME I lecnnical School

 Communication

 How do I take in and express ideas?

 Empirical Reasoning

 How do I prove it?

 Personal Qualities

 What do I bring to this process?

 Quantitative Reasoning

 How do I measure, or represent it?

 Social Resoning
- Social Reasoning
 What are other peoples perspectives on this?

- The primacy of self-discovery
 The having of wonderful ideas
 The responsibility for learning
 Empathy and caring
 Success and failure
 Collaboration and competition
 Diversity and inclusion
 The natural world
 Selftuda on effections

- Solitude and reflection
 Service and compassion

Deeper Learning Network/

EL Schools

- EL SCHOOLS

 Mastery of Core Academic Content
 Critical Thinking and Problem Solving
 Collaboration
 Effective Communication
 Self-Directed Learning
 An "Academic Mindset"

21st Century Employability and College Prep Skills (CTE)

- Work in teams
 Ask good questions
 Consider multiple perspectives in the workplace
 Ask how things are connected
 Take big picture views



Digital competence
 Learning to learn
 Social and civic competences
 Sense of initiative and entrepreneurship
 Cultural awareness and expression

Key Competencies for Lifelong Learning

Communication in the mother tongue
Communication in foreign languages
Mathematical competence
Basic competences in science and technology

European Reference Framework

- The Four Pillars of Education UNESCO (1996)
- Learning to know
 Learning to do
- Learning to live together
 Learning to be

Pink: Skills for Whole

Brain Thinking

- 5 Minds
- DesignStorySymphonyEmpathyPlay

Howard Gardner Disciplined Mind Synthesizing Mind Creative Mind Respectful Mind Ethical Mind



12 | Page

Meeting Notes - August 9, 2016

FLANSBURGH

Meeting Notes

DATE: August 9, 2016 Winchester Public Schools Facilities Master Plan PROJECT NO: 1603.00 Town of Winchester Superintendent of Schools Town of Winchester School Committee Town of Winchester Director of Finance Town of Winchester EFPBC Chair Town of Winchester Special Projects Engineer Flansburgh Architects Flansburgh Architects Flansburgh Architects Judy Evans Chris Nixon John Danzio Bob Deering Maraget White Kent Kovacs Jorge Cruz Vince Dubé PRESENT DISTRIBUTION: All attendees

- The Forest Ridge project in not included in the projected enrollment numbers.
- Potential 3 classrooms at the high school, 2 at the middle school and 1 at Muraco.
- It would be 2025 before the new additional students would be enrolling.
- Various options of PK-5 based on projected enrollments were reviewed.
- Muraco site would be considered for a new school site.
- The pre-schools often identify special needs students early on in the educational process.
 It is difficult and expensive to run a Pre-K program for towns due to teacher's salaries.
 CN noted 11% 13% special needs in population does town need more space to allow more students to attend rather than provide other arrangements?
- Computer Lab spaces can this be future "found" space to be used for something else? Potentially for innovation space in elementary school? No computer labs currently in elementary schools.
- FAI will do a graphic for each option then do a cost estimate for each.
- Specialty spaces in performing arts, language, etc. innovations, science rooms
- JE Lincoln School potential for a second middle school or as a 6th grade academy.
- CN Parkhurst could be swing space without the elevator for a short term new project option as was done for Vinson Owens School.
- Vinson Owens currently has 3 extra classrooms, plus a potential room in the computer lab.

Flansburgh Architects 77 N. Washington Street Boston, MA 02114 T. 617-367-3970 F. 617-720-7873 flansburgh.com

1

FLANSBURGH

- One option is to replace Muraco and Lynch or renovate one significantly or combined into 1 new school on one of the sites. Will need to show this on the study.
- 6,7 and 8 grade middle school will require possibly using the Lincoln School.
- More intense need for space is at the middle school level, not at the PK-5 level.
- Will need another workshop in September (mid-September)
- Price up options for the workshop meeting
- November 7th is the town meeting
- Need a draft study by Mid –October.

Flansburgh Architects 77 N. Washington Street Boston, MA 02114 T. 617-367-3970 F. 617-720-7873 flansburgh.com

Meeting Notes - September 28, 2016

FLANSBURGH

Meeting Notes

DATE: September 28, 2016 - Parkhurst School

PROJECT NO: 1603.00

PRESENT:

Town of Winchester DPW Facilities
Town of Winchester Superintendent of Schools
Town of Winchester School Committee
Town of Winchester School Committee
Town of Winchester Assistant Superintendent
Town of Winchester School Committee
Town of Winchester School Committee
Town of Winchester EFPSC
Town of Winchester EFPSC
Town of Winchester Finance Committee Vice Chair
Town of Winchester Finance Committee Chair
Flansburgh Architects
Flansburgh Architects
Flansburgh Architects Pete Lawson
Judy Evans
Chris Nixon
Jennifer Elineema
John Danzio
Susan Verdicchio
Susan Verdicchio
Shelly Walsh
Jessica Lohnes
Samantha Allison
Roger Michelson
Jorge Cruz
Kent Kovacs
Vincent Dubé

The members wanted to know how many classrooms are in each school

The student populations are as follows:

443 students 410 students 460 students + 89 Pre-K 404 students 413 students 2,130 students

What is the capacity of each school, based on number of classrooms each classroom at the Winchester preferred of 20 students per classroom and the MSBA 24 students per classroom.

If new total becomes 2,200 students how many classrooms will this require.

The value of a larger school is that the specialty teachers can be hired full time rather than using part time teachers.

Look at adding a link between the McCall center classroom bar corridor connecting to the youth center floor to reduce adding a new elevator cost.

Remove Option MS-4a since the 1430 size school is unrealistic for Winchester. The HS is only 1200 students.

Flansburgh Architects 77 N. Washington Street Boston, MA 02114 T. 617-367-3970 F. 617-720-7873 flansburgh.com

1

FLANSBURGH

Add a new Option MS-2a which combines the Youth Center Renovation (4 classroom) and the new classroom addition (4 classrooms) plus add a third floor to the addition at the library level and add either 2 new classrooms and include a large team space. A total of 10 new gross classrooms, but only 8 net classrooms.

Better to plan for a few extra classrooms on any addition or new school.

Include or clarify the escalation used for the estimates. Currently 1 yr.

There will be a similar larger meeting on October 19 at maybe 6:30 or 7 pm at the High School media center.

Flansburgh Architects 77 N. Washington Street Boston, MA 02114 T. 617-367-3970 F. 617-720-7873 flansburgh.com

Meeting Notes - November 28, 2016

LIMMODRIKAL

Meeting Notes

DATE: November 28, 2016 PROJECT Winchester Public Schools Facilities Master Plan PROJECT NO: 1603.00

The following meeting notes summarize the minutes of the Community Update held November 28, 2016 at Winchester High School: Winchester School Committee Presentation:

- Winchester School Committee always has a comprehensive Master Plan in place instead of updating each Winchester scnoor, utminuses and school need at a time o Last Master Plan completed by Flansburgh in 2007

 Master Plans support the educational program and school mission and evaluate the existing school facilities
- Plan for growth
 Reference point for procurement of funds
- Minchester should ideally update their Master Plan every ten years
 Winchester should ideally update their Master Plan every ten years
 Since the last Master Plan study, Vinson-Owen and Winchester High School have been updated with new
- Since the last Master Priest young "Institute Winchester's enrollment grew by more than 30%.

 The District considers certain spaces in elementary schools (i.e., music, reading, media, etc.) essential important to maintain these spaces for the students to grow creatively.

 Between January and February of 2017, Winchester expects to make a recommendation for options o In the Spring of 2017, the final Facilities Report should be ready.

- o in the Spring of 2017, the final Facilities Report should be ready

 "Schools in not just a space to educate students," Superintendent Judy Evans

 o Schools need to meet the challenge of 21" century

 a Each building should reflect the vision of the particular school and community

 o 21" century schools not focused on content but traits (i.e. critical thinking, communication, etc.)

 to Leadership Team recommends fieldable spaces, spaces that fit into the environment,
 indoor/outdoor learning, integrated technology, displays of students' artwork (display encourages
 student support), woold file elementary schools to meet these standards in the next true years

- Flansburgh Architects Presentation:

 McCall Middle School:

 Incollment growth at the elementary level effects middle school's ability to absorb the increase in population

 General classrooms are in spaces that are not ideal for learning

 3 to 6 additional classes are anticipated to satisfy enrollment

 The increase student population may effect other spaces as well

sburgh Architects 77 N. Washington Street Boston, MA 02114 T. 617-367-3970 F. 617-720-7873 flansburgh.com

1

FLANSBURGH

- supportive of what ever direction the School Building Committee makes, but we must remember what an asset the Youth Program is to the community

 "If the Youth Center goes to the high school, what will the protect on security be for weekend events?"

 O The current high school is designed to accommodate community events and programs like the Youth Center after school hours and the accessibility and security can be updated to reflect that O The Youth Center is not poing away, McCall does not have extra space to appropriately fit the program's needs, all spaces available should be considered for academic purposed first

 "How would we pay for these options?"

 O "These are major capital projects" —Chris Nilson; District would need to submit SOIs to the MSBA to get some help with funding

 Prek going to Muraco means that space at Lynch would be free for general education programs and other uses

 "I like the welcoming feel at Lynch. We don't want to lose the look and feel of the school. There is heavy
- programs and other uses

 "I like the welcoming feat a Lynch. We don't want to lose the look and feel of the school. There is heavy community participation at Lynch, the other schools have a Black box feel, and it's hard to navigate the pick-up/drop-off route at these other schools as well" Winchester resident
 "What are your houghts on accommodations for future development other than Cambridge Street?"

 Forest Ridge, is they vars out and was not factored in to the current enrollment
 of int of forest Ridge, something else will contribute to enrollment growth in the future and will be
 reviewed at that time
 "Prex and k in one school [Parkhurst]. The location does not seem like the greatest choice because of it's
 location, "it's not a centrally located."

 School Building Committee: Redistricting is something that was done when Vinson-Owen was
 completed, it is something we can look into if we settle on this option

 "Why not move to another school like Mystics".
- - - Competed, it is sometimely ear indow into it we seate on this uption

 "Why not move to another school like Mystic?"

 More central and eay to get to

 "Where would the tenants renting the space at the school go?" (Kid Connections, Rec.
 Center could be relocated)

 It is an idea we're exploring for this project; the available land at Parkhurst site

 - for PreK K accommodates this grade population

 We are evaluating including PreK K grades at Mystic and will advise the
- "Is there any way of approaching the MSBA to get the appropriate funding for one of these projects?"
 Completion of Ten Year Master Plan a good start
 MSBA Guidelines: Enrollment Increase will need to be reviewed

- MSBA Guidelines: Enrollment increase will need to be reviewed
 Opportunities to work with MSBA on a future project
 The Lynch option seems to cut through traffic on the main road and disrupts traffic flow"
 The Lynch option seems to cut through traffic on the main road and disrupts traffic flow"
 The intention here is not to have a cut through but allow for separation of buss and car traffic while also providing full fire apparatus
 Nine classrooms seems like a lot of classrooms for Lynch"
 The Lynch School community has twenty-seven (27) classrooms for PreK 5 students and the enrollment increase would require twenty-nine (29) total

 "What about the fields behind lynch?"

 What about the fields behind lynch?"

 What about the fields behind lynch?"

- Classroom options have two phases: the first focuses on utilizing the lower level after school program area while the second phase recommends adding to the library wing of the existing school building

 - m are a while the second phase recommends adding to the library wing of the existing school of the plant of t top level classrooms can be accessed from the library.

K-5 Options

- The increased enrollment at the K-5 grade level will impact the 110 class sections approved by the The increased enrollment at the N3 grade level with inlight Life 12 LO2as Sections applied by the District. There are currently 0106 classrooms available giving the District a four (4) classroom deficient. Overlaying the increased enrollment figures on the current class sections would suggest 113 class sections needed. This will result in a total need of seven (7) classrooms in the K-5

 - lass sections needed. This will result in a total need of seven (7) classrooms in the K-5 tory of spaces.

 Options ES-2 and ES-3: Create a grade shift school that could accommodate increased enrollment to free up classrooms at the existing elementary schools. The existing Parkhurst School could be renovated an added on to or replaced with a new facility. This would allow for a school of up to twenty-two (22) classrooms would could accommodate any grade size in the near future.

 lynch School Options ES-58. The Lynch School could absorb the increased enrollment from the proposed Cambridge Street Development by adding two general classrooms to the existing twenty-seven (27) classrooms for a total of twenty-nine (29) classrooms for PreK-5 students. The school can be renovated and added on to to accommodate ane propulation of 500 students. The site is also large enough to construct a new school on the same shite while the existing school remains occupied.
 Muraco-Chiol Options ES-64 and ES-68. The Muraco School can be redesigned to accommodate the increased enrollment. The PreK program can be moved from Lynch to accommodate the increased enrollment. The PreK program can be moved from Lynch to accommodate the increased enrollment in the precipitation of the sense of twenty-eight (28). The existing school can be reconfigured with renovations and additions to meet the need of twenty-eight (28) classrooms for a population of 460 students. A new school on this site would require the demolition of the existing school.

Community Questions about McCall Middle School:

- "Which is the leading option?"

 Shool Building Committee is still considering all options
 The least expensive option is the renovation to the Youth Center
 The addition to the Center Wing addresses current need of two classrooms as well as two
- classrooms for additional enrichment programs "What are your considerations for the Youth Center?"

 - Space at high school is being considered for a possible relocation
 Youth Center Director stated leadership skills are being learned at the Youth Center; they are

Flansburgh Architects 77 N. Washington Street Boston, MA 02114 T. 617-367-3970 F. 617-720-7873 flansburgh.com

MEMORANDUM

To: Board of Selectmen

From: Christian Nixon, School Committee Vice Chair

Subject: Statements of Interest for the Lynch & Muraco Elementary Schools

Date: 31 March 2017

cc: School Committee, Dr. Evans, Mr. Howard, EFPBC, CPC, Working Group, Ms. White

Informed substantially by our on-going *Facilities Master Plan* update project and with a deadline of April 7th for application, the School Committee voted last night to submit two Statements of Interest [SOIs] to the Massachusetts School Building Authority [MSBA] for the renovation or reconstruction of the Lynch and Muraco Elementary Schools. The key eligible criteria cited (as noted in the MSBA-required motion language voted by the SC and before you for action on Monday) are: existing overcrowding, future enrollment growth/further overcrowding and the condition/age of existing facilities. Our vote last night (and the vote of the Board of Selectmen) is a requirement for submission/consideration by the MSBA. It is important to note that in submitting an SOI we are not approving or submitting a project, but-- rather-requesting the MSBA partner with us to explore our options in a Feasibility Study. As you will note in the motion language, this submission does not obligate the Town, district or MSBA in any way.

This memo briefly summarizes our current enrollment/space shortage as well as our 5-year and 10-year projections (I have included grades 6-8 for your information, as well).

As much of the Board is aware, the 2007 Master Plan called for the renovation/reconstruction and expansion of the Muraco and Lynch Elementary Schools. Based on our work to date on the new Master Plan, the Working Group concurs with the 2007 recommendation and last night the School Committee took the first of two steps required to apply to partner with the MSBA in exploring solutions to our physical plant and enrollment challenges. As the second step, we ask for your support and vote on the SOIs for these two schools. We expect some response from MSBA by the fall. It is important to underscore that voting an SOI is not the submission of a building plan, building site or even building size, but-- rather-- simply a request for partnership with MSBA to evaluate the district's needs and opportunities, including the opportunity for substantial state funding through reimbursement in a major capital project. Submitting the SOIs in no way obligates the District, Town or the MSBA to any costs.

Enrollment/ Growth Background 2003-2012

During the MSBA Feasibility Study stage of Winchester's Vinson-Owen Elementary School in 2010, the district struggled to keep up with extraordinary enrollment growth of over 25% in a decade that saw statewide enrollment fall by 3% [2003-2012]. Winchester was one of a handful of districts seeing such double-digit growth which-- in no small part-- contributed to the MSBA's decision to partner with the Town again on the renovation and expansion of Winchester High School while we were still in the construction of the Vinson-Owen school. (The 3-phase WHS project is on budget and on schedule for fall 2017 completion).

The Vinson-Owen project (opened fall 2013) did much more than replace an aged, deteriorating and inaccessible 1950s physical plant—it increased the number of general education core classrooms on the site from 15 to 21. The move of WPS Central Office Administration from the Lynch Elementary School to

Parkhurst (the former Vinson-Owen swing space) freed up an additional three classrooms at Lynch for a total net increase of nine (9) elementary classrooms in the district.

In the fall of 2012 and in concert with the pending opening of the new and larger Vinson-Owen school, the Winchester School Committee voted to redistrict the Town's five (5) elementary districts or boundaries to 'rebalance' enrollment with the district's five elementary schools and their associated capacities or 'classroom targets' as defined by the the School Committee. The classroom target for each of the five schools was understood to exclude spaces which had been taken to accommodate enrollment growth over the decade including music classrooms, art classrooms, computer labs, libraries, specialist workspaces, etc.

The Redistricting Advisory Committee [RAC] which developed the map ultimately recommended by the Superintendent and voted by the School Committee noted three key priorities:

- a) equitably distribute students across town to meet capacity,
- b) reclaim specialist space equitably at every building, and
- c) anticipate and plan for future enrollment dynamics.

The RAC further noted, "Any recommended plan must further the district's goal of providing the best physical learning environment possible by <u>uniform and equitable utilization of facilities</u>..." and secondwith an understanding of the means by which increased enrollment has been addressed-- "[Protect or provide] specialist space such as art, music, technology, and library".

Simultaneous with the vote on a new elementary district map effective fall 2013, the School Committee also established the following "Classroom Targets" (spaces intended, appropriately sized and configured for general education classrooms) at the district's elementary schools. This figure represented the maximum number of classrooms to be occupied without taking away other instructional spaces (Music, Art, Specialist Space, Computer Lab, Library, etc.):

Fall 2012 vote by School Committee establishing maximum classroom targets per school building

Ambrose Elementary: 23 gen ed classrooms
Lincoln Elementary: 21 gen ed classrooms
Lynch Elementary: 22 gen ed classrooms
Muraco Elementary: 21 gen ed classrooms
Vinson-Owen Elementary: 21 gen ed classrooms

Total classroom 'capacity': 108 classrooms [total rooms available without sacrificing other space/s]

2013 to present day 2016-17 school year

Since the School Committee's restricting vote in the fall of 2012 and the opening of the new Vinson-Owen school in the fall of 2013, Winchester's elementary schools are once again exhausted of space for two primary reasons: enrollment growth and the success of our Specialized Learning Centers

Enrollment Growth

In the four years from FY13 (redistricting vote) to FY17 (present), Winchester's K-12 enrollment is up 5.2% from 4,396 to 4,623 students. Enrollment growth at the elementary level has been a more modest 2.3% from 2,105 to 2,135 students; however, this rate of growth has been met with a net reduction in instructional spaces, due in part to the success of the WPS' Specialized Learning Center programs.

Specialized Learning Centers [SLCs]

Recognizing nearly a decade ago that our out-of-district [OOD] placements rate was increasing, with significant budgetary consequences, and with a desire shared by the district and families to educate students in-district to the greatest degree possible, the Winchester Public Schools developed so-called Specialized Learning Centers at two (2) of our five elementary schools. By the fall of 2012 when the School Committee voted the new elementary district map, the Superintendent had further established two additional SLCs. These centers are equipped and staffed (with specific staff expertise and training) to educate students with specific needs and have proven successful -- with significant growth in student enrollment and requisite space needs:

Partnership Program	[behavioral program]	at Muraco Elementary School
Spectrum Program	[Autism Spectrum]	at Lynch Elementary School
LBLD Program	[language based LD]	at Vinson-Owen School
Cognitive Program	[cognition focused]	at Ambrose Elementary School

In 2012, the Spectrum Program at Lynch was limited to one classroom and has since expanded to two. The Cognitive Program at Ambrose has similarly expanded from one small space to two larger spaces today. The LBLD Program at Vinson-Owen has grown significantly and now requires three instructional spaces and at Muraco, the Partnership Program which was 'designated' to be based at the school in the fall of 2013 with an unknown-- but presumed small-- enrollment has now grown to require 1.5 classrooms, including the school's original Music Room.

The School Committee, administration and community all see the growth of these district-based programs as a strong success. The consequence is that spaces have once again been 'taken' to accommodate the students. In October of 2016, the School Committee revisited the 'Classroom Targets' last voted in the fall of 2012. Backing out the space/s required for the SLCs as well as seeking to recapture the Music Instruction Room at Lincoln Elementary School, the targets were revised as follows.

	SC vote - Fall 2012	SC vote - Fall 2017
Ambrose Elementary:	23 gen ed classrooms	22 gen ed classrooms recommended
Lincoln Elementary:	21 gen ed classrooms	20 gen ed classrooms recommended
Lynch Elementary:	22 gen ed classrooms	21 gen ed classrooms recommended
Muraco Elementary:	21 gen ed classrooms	19 gen ed classrooms recommended
Vinson-Owen Elementary:	21 gen ed classrooms	24 gen ed classrooms recommended
Total gen ed 'capacity':	108 classrooms	106 classrooms target VOTED 10/2017

Although the district completed the construction of 'shell space' at the lower level of Vinson-Owen in 2016, providing an additional three (3) classrooms [note V-O's classroom target number increased from 21 to 24, above], the School Committee has determined that the district reasonably has 106 K-5 general education classrooms available. This year we are running, 110 sections of K-5 and are therefore four (4) classrooms short. It is the projected 5-year and 10-year growth that has the School Committee especially concerned for the sustainability of our educational space.

The Coming Wave-- Five year and Ten year K-6 Enrollment Projections

With our early concern in the fall over the potential for a large-scale 40B project off of Forest Circle in the Muraco District [Forest Ridge] diminished by understandings that the project was facing significant hurdles in the regulatory/approval process, we collectively breathed a sigh of relief-- until word came in

January of another potential large scale 40B on the Muraco-Lynch line [Holton Street]. The Working Group agreed to pause and reevaluate our enrollment projection methodology to ensure that we were capturing the full potential of land development across the town -- and with it, students.

With the meaningful insight and help of the Town Manager, Town Planner, Town Engineer and the Chair & Vice Chair of the Board of Selectmen, our Working Group and Flansburgh have identified a number of land development projects which we feel are likely to be completed in the 5-year and 10-year timeframe (see 5-year 2021/22 and 10-year 2026/27 growth charts, provided). Each of these development opportunities had to pass a series of questions to be counted:

- 1. "Is is possible that this area/parcel could be developed for housing?" [Y/N]
- 2. "If Yes, is it probable that the development will occur" [Y/N]
- 3. "If Yes, is it more probable than not that the development will occur in the next 5/10 years?"
- 4. "If Yes, what is the zoning and/or scale of development reasonably expected?"

With these answers in hand, Flansburgh has updated our 5-year and 10-year K-6 enrollment as shown in your attachments (in detail) and summarized below:

	5-year 2021-22 [FY22]	<u>10-year 2026-27 [FY27]</u>
K-5:	+240 students (11.2%)	+58 students (13.9% cumulative to year 10)
6-8:	+147 students (12.9%)	+28 students (15.4% cumulative to year 10)

To accommodate this rate of enrollment growth, the Master Plan Working Group and Flansburgh have determined a need for 19 additional K-5 classrooms (4 today, 12 by the 2021-22 school year and 3 by the 2026-27 school year) [see attachments for more detail as to drivers of projected enrollment growth]

Physical Plant Condition & Capital Project Needs

The third priority recognized by the MSBA as an eligible SOI criteria is the state/age of a school's physical plant and needed capital projects. A summary of the key anticipated capital projects for both Lynch and Muraco are summarized, below. These costs come from our *Capital Improvement Program* summary sheets which are reviewed by the Capital Planning Committee [CPC] each summer for recommendation to the Town Manager and Town Meeting.

Lynch Elementary School Capital Projects	estimate	work year
Replacement of Heating & Domestic Hot Water piping systems:	\$555,000*	FY18
Replacement of Boiler Equipment w/ mod high-efficiency units:	\$800,000	TBD
Design & Specs for Window Replacement	\$150,000	FY18
Selected flooring/carpet replacement in classroom areas	\$100,000	FY19
Window replacement (existing single pane/steel frame)	\$3.4M	FY20
Replace Gym Flooring	\$350,000	FY21
Replace aging master clock/bell system	\$35,000	FY22
_		
*Heat/DHW orig est \$300K. Actual SD & cost estimate = \$555K.	\$5.39M	over 4 years

Like the Heating/DHW and Boiler project noted above, the other key capital projects at Lynch are being carried on the School Committee's multi-year Capital Planning Worksheet. As the BOS and Management are well-aware, the costs carried for these projects-- as well as other Town department projects-- are informed best guesses with input from our VFA database and contemporary market understandings. Given the limitations of the Building and Capital Stabilization Funds, the practice of the Capital Planning

Committee [CPC] for some years now has been to vote priorities for an early Schematic Design package, yielding a more detailed understanding of scope and cost. This has been a helpful change in practice and-- generally speaking-- we tend to find that the cost to complete the project is higher than originally anticipated in the earliest planning phases (3-4 years out). An example of this is the Lynch Elementary School's Heating/DHW replacement project. Originally estimated at \$300K, the recently completed design study pegs the work at \$555,000-- an 85% increase over our earliest estimates. One component of this is ambiguity is the true complexity of the required work (only known once fully investigated) and another is our [CPC's] cost escalation practices which may not track true market conditions.

Why does this matter? Simply put, while the \$1.36M cost to replace Lynch's Heating/DHW and boilers is a much more realistic figure (for bidding this year), the remaining projects are most likely similarly underestimated and/or under-escalated. It should also be noted that the 'plan' to carry out expensive projects at Lynch each consecutive year is ambitious given the pressing capital needs of DPW, WPD, WFD and other Town departments. It therefore suggested that the \$4M+ worth of capital projects beyond the Heating/DHW/Boiler work is likely in the \$5.25M to \$6.75M range when stretched over a more "practical" six to seven years yielding a total anticipated Lynch Capital Projects burden of \$6,600,000 to \$8,100,000.

Muraco Elementary School Capital Projects	estimate	work year
Replacement of Fire Alarm System:	\$165,000*	FY18
Design & Specs for window replacement:	\$140,000	FY18
Window Replacement Project - Phase II (classrooms)	\$200,000	FY18
Design & Specs for replacement of electrical system:	\$100,000	FY18
Replacement of rusting classroom sink cabinets	\$100,000	FY18
Replacement of flooring/carpet:	\$300,000	FY19
Window Replacement Project - Phase III (clerestory,courtyard)	\$225,000	FY19
Replace Electrical System:	\$500,000	FY19
Design & Specs for Heat/DHW replacement:	\$37,500	FY20
Replacement of Heat/DHW system:	\$212,500	FY21
Design & Specs Roof Replacement:	\$225,000	FY21
Roof Replacement:	\$1.28M	FY22
Gym Addition + 3 Classrooms	\$3.34M	FY21
	\$6.825M	over 4 years

Given that the only Muraco project actually designed with a detailed cost estimate is the Fire Alarm replacement project (\$165K), it is fair to project the actual cost of Muraco's capital needs at between \$8.8M and \$10.2M. Noting that this includes the Gymnasium addition (as carried in the Capital Improvement Program, we can pull this expansion project out for a more apples-to-apples comparison against Lynch's capital needs and costs, yielding a current projection of \$3.5M (over an unrealistic four years) or a more probable \$4.5M to \$5.2M.

On behalf of the School Committee and WPS Administration, Ms. Verdicchio, Dr. Evans, Mr. Danizio and I look forward to discussing this with you Monday evening. We appreciate your support of our SOIs for the Muraco and Lynch schools to follow our Master Plan guidance, keep pace with significant enrollment growth and provide the facilities & resources necessary to support our students.

CN/cn

FLANSBURGH

WINCHESTER BUILD OUTS

3.30.17

K-5 CLASSROOMS 10 YR. BUILD OUT

19 CLASSROOMS REQUIRED (15 FOR ENROLLMENT GROWTH + 4 FOR FY 17 SHORTAGE)

CLASSROOM TARGETS BASED ON SCHOOL COMMITTEE MEMO DATED 10/11/16

TARGET CLASSROOM/ENROLLMENTS (PRESENT DAY)

AMBROSE	22 (440)
LINCOLN	20 (400)
LYNCH	21 (420)
MURACO	19 (380)
VINSON OWEN	24 (480)
TARGET	106 (2120

CURRENT 110 SECTIONS – 106 CLASSROOMS AVAILABLE = 4 CLASSROOMS SHORT 106 X 20 STUDENTS = 2120 PROPOSED 125 X 20 STUDENTS = 2500 2500 -2120 = 380 STUDENTS

SPLIT 380 STUDENTS TO LYNCH, MURACO AND VINSON OWEN (VO LARGEST)

AMBROSE	22 (440)
LINCOLN	20 (400)
LYNCH	27 (540)
MURACO	27 (540)

VINSON OWEN 29 (580) W/ 5 CLASSROOM ADDITION

SPLIT 380 STUDENTS TO LYNCH, MURACO AND VINSON OWEN (VO AND LYNCH LARGEST)

AMBROSE	22 (440)
LINCOLN	20 (400)
LYNCH	28 (560)
MURACO	27 (540)

VINSON OWEN 28 (560) W/ 4 CLASSROOM ADDITION

SPLIT 380 STUDENTS TO LYNCH & MURACO (LYNCH LARGEST)

AMBROSE	22 (440)
LINCOLN	20 (400)
LYNCH	30 (600)
MURACO	29 (580)
VINSON OWEN	24 (480)

^{*}PRE-SCHOOL EITHER AT LYNCH OR MURACO DEPENDING ON WHICH IS BUILT FIRST

Meeting Notes - May 16, 2017

Flansburgh Architects

Meeting Notes

Winchester Public Schools

Winchester Master Plan - 1603.00

PRESENT:

Judy Evans – Superintendent, Winchester Public Schools Chris Nixon – Winchester School Committee Meg White – Winchester Engineering and Planning Vincent Dubé – Flansburgh Architects Jorge Cruz – Flansburgh Architects

DISTRIBUTION: Attendees

Presentation of Master Plan Study status to Town Board Members.

Current Master Plan needs some updating

Focus for vision for 10-15 -25 years out from now

Need flexible spaces to provide multiuse options.

Spaces designed using visioning sessions, and space planning using MSBA templates MSBA templates are used so the new school spaces meet the guidelines for potential reimbursement if MSBA funds the school.

There are 40b projects that are likely to be built. All likely projects are being considered in the study enrollment projections, not just permitted projects.

In 5-years the Cambridge Street project plus Holten Street, Kraft, Forest Street and North Main Street development is all likely to occur.

In 10-years Waterfield Street, Highland Ave more Kraft and more North Main Street development is likely to occur

McCall needs 8 classrooms which can be built from the Youth Center in the basement (3 CRs) and five more in a new addition off the library. Where will the Youth Center students go? Possibly the high school can accommodate since most students using it are older anyway. Can class sizes be increased to 25 versus 22.

Flansburgh Associates, Inc. 77 North Washington Street Boston, MA 02114-1910 617.367,3970 www.faiarchitects.com

1

Flansburgh Architects

The high school is designed for 1370 students. Current enrollment this year is 1268 which is a 102-student float. Anticipate +85 student increase mext year, but a potential for 218 student increase within five years, plus 28 additional students by year 10. There are 110 of these students already enrolled in the system.

At the high school level, the total enrollments can be more easily accommodate due to scheduling of classes and room availability. It's more about fitting the students to the spaces. Only 80 -85% occupancy at any time.

In 20 years, the methods of teaching at high schools is likely to change with more flexible times at the school and more time in the community doing work/study or online learning, etc. Class sizes average about 18 – 19 students (some classes are larger) which could grow as well. HS is not like the lower grades which is a 1:1 ration of classrooms to student numbers.

Comfortable that the additional 244 students in 10 years at the high school level can be easily accommodated without an addition.

[Modify the blue background on slides to make it easier to read from a distance.]

Mystic School is in a good location in town, why not renovate this school. The site is well located, but small, and fitting a new school or significant renovation/addition would be very limited.

24 sessions at Lynch now, but Lincoln could not grow to that size due to a tight bounded site.

A 600-student school is better for efficiency with staff. Schools at 400 - 450 often have part-time specialists (gym teacher, nurse, etc.), but 600 student school can afford the bring this staff on full-time. It is harder to keep part-time staff since they typically want full-time positions.

Priority for school department is to replace Lynch and Muraco

MSBA will require the town to hold title to a property to consider the location for a school option.

School department policy is to place students where space is available

Holten Street development is considering 300-330 units, with 10% of units being affordable to meet the town's Housing Plan. (and state requirement). 50 units per year progress towards the Housing Production Plan is the goal. 10% of total units in town to be affordable.

Can 40b development provide financial assistance to town for school. Sometimes the developer will provide a donation to the town to spend as they wish.

Impact fees can't be assessed.

Flansburgh Associates, Inc. 77 North Washington Street Boston, MA 02114-1910 617.367.3970 www.faiarchitects.com

Flansburgh Architects

The McCall cafeteria needs to be expanded to accommodate the increased enrollment. It is already undersized for the current enrollment. Elementary School options include:

Lynch: Muraco: V.O.: expanded to Ambrose: expanded to Lincoln:

What is the value of not using the MSBA? Net cost: Self-fund for smaller projects but partner with MSBA for large projects (new school or major renovations).

Lynch built in 1960. Muraco in 1966

Analysis of the town facilities needs requests (VFA database) suggest a potential for \$32.5 million R&R (removal and replacement) over 10 years at Lynch with \$6.6 million to \$8.1 million within 6-8 years. At Muraco the numbers are slightly less but still significant - \$22.7 million in 10 years and \$4.5 million - \$52.2 million within 6-8 years.

The PFA estimates tend to be inflated for the 10-year period, so be careful when suggesting those as values to Town Meeting requests

Lynch roof was replaced 4 years ago

Muraco roof may need to be replaced within 5 years.

V.O. has two options for expansion: at the lower level and roof, V.O. currently at 420 students, plus three classrooms at lower level (+60) increases to 480 students and 5 classrooms on roof floor increases another 100 students for a potential enrollment of 580 students at V.O.

Ambrose school modular are currently 10-years old and eventually will need to be replaced. An addition at the end of the modular wing offers a potential for 6 classrooms (minus the two modular classrooms) nets 4 classrooms. (+40 students).

Central Offices are short term at Parkhurst. Options being considered are new buildouts at a new Lynch or Muraco or at the Carriage House at Ambrose.

Analysis of renting space for the Central Offices over a 20-year period suggests that the costs approximate renovating the Carriage House costs. (using 4 (5-yr) lease periods at 2.8% bond costs will require only 18 additional months of renting to equal the estimate for renovating the Carriage House) this analysis does not include buildout of raw rental space or renovating other rental space if available.

Renovating the Carriage House frees up Parkhurst to be sold. (?)

Flansburgh Associates, Inc. 77 North Washington Street Boston, MA 02114-1910 617.367.3970 www.faiarchitects.com

Flansburgh Architects

V.O. could use modular for additional classrooms. Third floor classrooms are too hot now. Plan would be to include AIC for the rooftop addition. Lincoln is the only school now with AIC throughout.

New schools will be designed with A/C or likely displacement which is a "lite" version of A/C.

New schools are likely to be used 12 months of the year. Most are now with summer programs

Can't fund large projects through the school stabilization fund. Tried once with the school modular upgrades several years ago and still hasn't recovered yet. Taxes already increasing 5% - 6% per year which is hurting the elderly home owner.

Will a new school increase enrollment through attractiveness? Potential 20% increase from a new school. However, be careful since future events could slow enrollment due to interest rate increases, slows housing starts, slow approval process for development, slow economy, etc.

Need to include these options in Master Plan study

Parkhurst can be used for any spike in enrollment if necessary

Include a potential for future growth in new school options.

Use Gant Chart to show sequence of proposed improvements Community presentation on May 22

Flansburgh Associates, Inc. 77 North Washington Street Boston, MA 02114-1910 617.367.3970 www.faiarchitects.com

3

Meeting Notes - May 22, 2017

Flansburgh Architects

Meeting Notes

Winchester Public Schools

PROJECT NO: Winchester Master Plan - 1603.00

Judy Evans – Superintendent, Winchester Public Schools Chris Nixon – Winchester School Committee Meg White – Winchester Engineering and Planning Vincent Dubé – Flansburgh Architects Jorge Cruz – Flansburgh Architects PRESENT:

DISTRIBUTION: Attendees

Presentation of Master Plan Study status to Community. (see meeting notes from 5/16/17)

Enrollment for the middle school

 $3\ yr$ to $5\ yr$ typical developments includes 200 additional K-12 students, with 74 at the elementary school level.

Vinson Owen currently 24 classrooms after recent 3 classroom addition.

2-story school as well as a 3-story option.

State (MSBA) does not reimburse Central Office or swing space

10% 8th graders go to private or vocational schools - it's not 100% go on to Winchester High

From 2003 - 2012, while the state lost (-) 3 1/2% population, Winchester saw a 27% growth.

Questions from Audience:

What is the plan for Mystic School? Response: Mystic was looked at, but the site is constricted.

Lynch and Muraco R&R show \$12 - \$13 million. Response: No, that amount has not been spent on those schools. \$160,000 for the Muraco fire alarm will be spent to update it.

Flansburgh Associates, Inc. 77 North Washington Street Boston, MA 02114-1910 617.367,3970 www.faiarchitects.com

1

Flansburgh Architects

The trend is that schools (mostly in other states) are being regionalized to centralize administration to larger districts. (reduces administrative costs). In Winchester over the last 20 years the EFPBC has been diligent at watching every dollar is spent wisely on projects.

At McCall, there is unit ventilator work that needs attention immediately. Will this work be part of the new classroom project? Response: This work is not currently in the project.

Could the road between McCall and Lincoln be closed to provide more useable space at the site? Response: This has been suggested before, but the issue is that the road is a state road and cannot be easily closed. This must be approved by the state.

If McCall has two phases proposed, wouldn't it be more efficient to do both t the same time? Also, why only build 5 classrooms at V.O. instead of the full potential of 7 classrooms? At VO the addition was to not maximize space, but to respect the exterior wall envelope and create a more aesthetic addition.

Flansburgh Architects

Lynch and Muraco are priorities – has there been thoughts to phase Muraco or build on Leonard Field? What other sites are being considered? Response: A new school can only be built on property owned by town. Options did not presume to build on land other than land owned by the school. At Lynch the field belong to the school the Muraco site is limited.

During an MSBA project, the MSBA will require options on various sites to find the most cost effective location.

How was enrollment distributed? Response: The new students were distributed by percentages. The state allows the district to redistribute students if it has new residential developments.

Preschool programs are eligible for reimbursement from the state which is why a new pre-K would be included in either a new Lynch or Muraco option. A preschool expansion is not anticipated. The preschool is not a business for the town. 105 students have been identified by age 3 as requiring special needs. These programs need special spaces such as OT/PT and ST.

Lincoln School projections suggest the enrollment will go down next year, but it has been steady

During a renovation students would typically be dispersed to other schools, but the Winchester schools are at or above capacity. Would an increase in class size be needed to avoid procuring swing space? Class size recommendation set by the state at 24.

V.O. rooftop expansion not a priority as high as the new Lynch or new Muraco, with Lynch as

Cost estimates include 3% inflation for one year but also a 10% contingency which could cover an additional 3years of inflation. Estimates would reflect building four years out for a 2021

The presentation was well received. Mystic School is a small site. The potential for expansion was reviewed as far back as the 1994 Master Plan and it was rejected then as well. It was preferred to have one on each side of Rts. 3

Was there thought to using Lynch as swing space if a new Lynch built first? Response: Yes. It was considered. It might be that the Lynch kids would not get to use the new school if the Muraco kids move in first.


How have the financial costs been considered? Is there a risk of funding not being available due to potential changes at the federal level? It is not expected that the funding would not be there due to federal changes since the MSBA gets funding from state sales tax. The school's budget might be affect by federal changes, but even so, Winchester has historically been a low taker of state funds.

Flansburgh Associates, Inc. 77 North Washington Street Boston, MA 02114-1910 617.367.3970 www.faiarchitects.com

A copy of all presentations and meeting notes will be provided with an electronic version of this report.

Section 6 | Appendix

Cost Estimates



PM&C LLC 20 Downer Avenue, Suite 1c Hingham, MA 02043

(T) 781-740-8007

(F) 781-740-1012

Feasibility Design Estimate

Winchester Schools RENOVATIONS + ADDITIONS

Winchester, MA

Prepared for:

Flansburgh Architects

September 26, 2016



Winchester Schools RENOVATIONS + ADDITIONS Winchester, MA

26-Sep-16

Feasibility Design Estimate

MAIN CONSTRUCTION COST SUMMARY

	Construction Start	Gross Floor Area	\$/sf	Estimated Construction Cost
ADDITION TO LYNCH ELEMEN	TARY SCHOO	L		
RENOVATE EXISTING SCHOOL				Not Required
ADDITION		1,505	\$358.83	\$540,040
SITEWORK				\$50,000
SUB-TOTAL	Jun-17	1,505	\$392.05	\$590,040
ESCALATION TO START - (assumed 4% PA)	5.3%			\$31,272
DESIGN AND PRICING CONTINGENCY	12%			\$70,805
SUB-TOTAL		1,505	\$459.88	\$692,117
GENERAL CONDITIONS				\$69,212
BONDS	1.00%			\$6,921
INSURANCE	2.00%			\$13,842
PERMIT				NIC
OVERHEAD AND FEE	5.00%			\$34,606
OWNER CONTINGENCY				By Owner
TOTAL OF ALL CONSTRUCTION	Jun-17	1,505	\$542.66	\$816,698



Winchester Schools RENOVATIONS + ADDITIONS Winchester, MA

26-Sep-16

Feasibility Design Estimate

ADDITION and MAJOR RENOVATION TO LYNCH ELEMENTARY SCHOOL

RENOVATE EXISTING SCHOOL		79,745	\$220.00	\$17,543,900
HAZMAT REMOVALS		79,745	\$15.00	\$1,196,175
ADDITION		11,030	\$252.65	\$2,786,721
SITEWORK - (10% of building costs)				\$2,033,062
SUB-TOTAL	Jun-17	90,775	\$259.54	\$23,559,858
ESCALATION TO START - (assumed 4% PA)	5.3%			\$1,248,672
DESIGN AND PRICING CONTINGENCY	12%			\$2,827,183
SUB-TOTAL		90,775	\$304.44	\$27,635,713
GENERAL CONDITIONS				\$2,210,857
BONDS	1.00%			\$276,357
INSURANCE	2.00%			\$552,714
PERMIT				NIC
OVERHEAD AND FEE	3.00%			\$829,071
OWNER CONTINGENCY				By Owner
TOTAL OF ALL CONSTRUCTION	Jun-17	90,775	\$347.06	\$31,504,712



RENOVATIONS + ADDITIONS
Winchester, MA

Feasibility Design Estimate

NEW LYNCH ELEMENTARY SCHOOL

TOTAL OF ALL CONSTRUCTION	Jun-17	90,480	\$408.39	\$36,951,492
OWNER CONTINGENCY				By Owner
OVERHEAD AND FEE	3.00%			\$972,408
PERMIT				NIC
INSURANCE	2.00%			\$648,272
BONDS	1.00%			\$324,136
GENERAL CONDITIONS				\$2,593,087
SUB-TOTAL		90,480	\$358.24	\$32,413,589
DESIGN AND PRICING CONTINGENCY	12%			\$3,315,968
ESCALATION TO START - (assumed 4% PA)	5.3%			\$1,464,553
SUB-TOTAL	Jun-17	90,480	\$305.41	\$27,633,068
SITEWORK - (10% of building costs)				\$2,388,688
NEW SCHOOL		90,480	\$256.00	\$23,162,880
HAZMAT REMOVALS		90,500	\$15.00	\$1,357,500
DEMOLISH EXISTING SCHOOL		90,500	\$8.00	\$724,000



RENOVATIONS + ADDITIONS

26-Sep-16

Winchester, MA

Feasibility Design Estimate

MODULAR ADDITION + MINOR RENOVATION TO VINSON-OWEN ELEMENTARY SCHOOL

SITEWORK - (Connections and Resurface Play Area) \$180,000 SUB-TOTAL Jun-17 3,210 \$225.83 \$724,901 ESCALATION TO START - (assumed 4% PA) 5.3% \$38,420 DESIGN AND PRICING CONTINGENCY 12% \$86,988 SUB-TOTAL 3,210 \$264.89 \$850,309 GENERAL CONDITIONS \$85,03 BONDS 1.00% \$8,503 INSURANCE 2.00% \$17,006 PERMIT NIC OVERHEAD AND FEE 5.00% \$42,515 OWNER CONTINGENCY By Owner	RENOVATE EXISTING SCHOOL		950	\$97.79	\$92,901
SUB-TOTAL Jun-17 3,210 \$225.83 \$724,901 ESCALATION TO START - (assumed 4% PA) 5.3% \$38,420 DESIGN AND PRICING CONTINGENCY 12% \$86,988 SUB-TOTAL 3,210 \$264.89 \$850,309 GENERAL CONDITIONS \$85,03 \$85,03 BONDS 1.00% \$8,503 INSURANCE 2.00% \$17,006 PERMIT NIC \$42,515 OWNER CONTINGENCY By Owner	MODULAR ADDITION		2,260	\$200.00	\$452,000
ESCALATION TO START - (assumed 4% PA) 5.3% \$38,420 DESIGN AND PRICING CONTINGENCY 12% \$86,988 SUB-TOTAL 3,210 \$264.89 \$850,309 GENERAL CONDITIONS \$85,03 BONDS 1.00% \$8,503 INSURANCE 2.00% \$17,006 PERMIT NIC \$42,515 OWNER CONTINGENCY By Owner	SITEWORK - (Connections and Resurface Play Area)				\$180,000
DESIGN AND PRICING CONTINGENCY 12% \$86,988 SUB-TOTAL 3,210 \$264.89 \$850,309 GENERAL CONDITIONS \$85,03 \$85,03 BONDS 1.00% \$8,503 INSURANCE 2.00% \$17,006 PERMIT NIC OVERHEAD AND FEE 5.00% \$42,515 OWNER CONTINGENCY By Owner	SUB-TOTAL	Jun-17	3,210	\$225.83	\$724,901
SUB-TOTAL 3,210 \$264.89 \$850,309 GENERAL CONDITIONS \$85,03 BONDS 1.00% \$8,503 INSURANCE 2.00% \$17,006 PERMIT NIC OVERHEAD AND FEE 5.00% \$42,515 OWNER CONTINGENCY By Owner	ESCALATION TO START - (assumed 4% PA)	5.3%			\$38,420
GENERAL CONDITIONS \$85,03 BONDS 1.00% \$8,503 INSURANCE 2.00% \$17,006 PERMIT NIC OVERHEAD AND FEE 5.00% \$42,515 OWNER CONTINGENCY By Owner	DESIGN AND PRICING CONTINGENCY	12%			\$86,988
BONDS 1.00% \$8,503 INSURANCE 2.00% \$17,006 PERMIT NIC OVERHEAD AND FEE 5.00% \$42,515 OWNER CONTINGENCY By Owner	SUB-TOTAL		3,210	\$264.89	\$850,309
INSURANCE 2.00% \$17,006 PERMIT NIC OVERHEAD AND FEE 5.00% \$42,515 OWNER CONTINGENCY By Owner	GENERAL CONDITIONS				\$85,031
PERMIT OVERHEAD AND FEE 5.00% \$42,515 OWNER CONTINGENCY By Owner	BONDS	1.00%			\$8,503
OVERHEAD AND FEE 5.00% \$42,515 OWNER CONTINGENCY By Owner Continue Continu	INSURANCE	2.00%			\$17,006
OWNER CONTINGENCY By Owner	PERMIT				NIC
	OVERHEAD AND FEE	5.00%			\$42,515
TOTAL OF ALL CONSTRUCTION Jun-17 3,210 \$312.57 \$1,003,364	OWNER CONTINGENCY				By Owner
	TOTAL OF ALL CONSTRUCTION	Jun-17	3,210	\$312.57	\$1,003,364



Winchester Schools RENOVATIONS + ADDITIONS Winchester, MA

26-Sep-16

Feasibility Design Estimate

ADDITION and MAJOR RENOVATION TO MURACO ELEMENTARY SCHOOL

RENOVATE EXISTING SCHOOL		40,000	\$220.00	\$8,800,000
HAZMAT REMOVALS		90,500	\$15.00	\$1,357,500
PARTIAL DEMO TO EXISTING SCHOOL		20,600	\$10.00	\$206,000
LOWER LEVEL ADDITION		15,015	\$238.03	\$3,574,068
FRONT ADDITION		20,600	\$297.14	\$6,121,043
SITEWORK - (minor work)				\$100,000
SUB-TOTAL	Jun-17	75,615	\$266.60	\$20,158,611
ESCALATION TO START - (assumed 4% PA)	5.3%			\$1,068,406
DESIGN AND PRICING CONTINGENCY	12%			\$2,419,033
SUB-TOTAL		75,615	\$312.72	\$23,646,050
GENERAL CONDITIONS BONDS INSURANCE PERMIT	1.00% 2.00%			\$1,891,684 \$236,461 \$472,921 NIC
OVERHEAD AND FEE	3.00%			\$709,382
OWNER CONTINGENCY				By Owner
TOTAL OF ALL CONSTRUCTION	Jun-17	75,615	\$356.50	\$26,956,498



RENOVATIONS + ADDITIONS

Winchester, MA

26-Sep-16

Feasibility Design Estimate

NEW MURACO ELEMENTARY SCHOOL - ES 2

DEMOLISH EXISTING SCHOOL		55,415	\$8.00	\$443,320
HAZMAT REMOVALS		55,415	\$15.00	\$831,225
NEW SCHOOL		76,730	\$256.54	\$19,684,309
SITEWORK - (Allowance of 10% of Building)				\$1,968,431
SUB-TOTAL	Jun-17	76,730	\$282.19	\$21,652,740
ESCALATION TO START - (assumed 4% PA)	5.3%			\$1,147,595
DESIGN AND PRICING CONTINGENCY	12%			\$2,598,329
SUB-TOTAL		76,730	\$331.01	\$25,398,664
GENERAL CONDITIONS				\$2,031,893
BONDS	1.00%			\$253,987
INSURANCE	2.00%			\$507,973
PERMIT				NIC
OVERHEAD AND FEE	3.00%			\$761,960
OWNER CONTINGENCY				By Owner
TOTAL OF ALL CONSTRUCTION	Jun-17	76,730	\$377.36	\$28,954,477



RENOVATIONS + ADDITIONS

Winchester, MA

Feasibility Design Estimate

NEW MURACO ELEMENTARY SCHOOL - ES 4a

TOTAL OF ALL CONSTRUCTION	Jun-17	149,350	\$381.76	\$57,016,454
OWNER CONTINGENCY				By Owner
OVERHEAD AND FEE	3.00%			\$1,500,433
PERMIT				NIC
INSURANCE	2.00%			\$1,000,289
BONDS	1.00%			\$500,144
GENERAL CONDITIONS				\$4,001,155
SUB-TOTAL		149,350	\$334.88	\$50,014,433
DESIGN AND PRICING CONTINGENCY	12%			\$5,116,566
ESCALATION TO START - (assumed 4% PA)	5.3%			\$2,259,817
SUB-TOTAL	Jun-17	149,350	\$285.49	\$42,638,050
SITEWORK - (Allowance of 10% of Building)				\$3,760,319
NEW SCHOOL		149,350	\$251.78	\$37,603,186
HAZMAT REMOVALS		55,415	\$15.00	\$831,225
DEMOLISH EXISTING SCHOOL		55,415	\$8.00	\$443,320



RENOVATIONS + ADDITIONS

Winchester, MA

Feasibility Design Estimate

NEW MURACO ELEMENTARY SCHOOL - ES 4

DEMOLISH EXISTING SCHOOL		55,415	\$8.00	\$443,320
HAZMAT REMOVALS		55,415	\$15.00	\$831,225
NEW SCHOOL		207,350	\$245.16	\$50,834,825
SITEWORK - (Allowance of 10% of Building)				\$5,083,483
SUB-TOTAL	Jun-17	207,350	\$269.68	\$55,918,308
ESCALATION TO START - (assumed 4% PA)	5.3%			\$2,963,670
DESIGN AND PRICING CONTINGENCY	12%			\$6,710,197
SUB-TOTAL		207,350	\$316.34	\$65,592,175
GENERAL CONDITIONS				\$5,247,374
BONDS	1.00%			\$655,922
INSURANCE	2.00%			\$1,311,844
PERMIT				NIC
PERIVITI				NIC
OVERHEAD AND FEE	3.00%			\$1,967,765
	3.00%			



Winchester Schools RENOVATIONS + ADDITIONS

26-Sep-16

Winchester, MA

Feasibility Design Estimate

MODULAR ADDITION TO MURACO ELEMENTARY SCHOOL

RENOVATE EXISTING SCHOOL				Not Required
MODULAR ADDITION		1,215	\$200.00	\$243,000
SITEWORK - (Connections and Site modifications)				\$57,000
SUB-TOTAL	Jun-17	1,215	\$246.91	\$300,000
ESCALATION TO START - (assumed 4% PA)	5.3%			\$15,900
DESIGN AND PRICING CONTINGENCY	12%			\$36,000
SUB-TOTAL		1,215	\$289.63	\$351,900
GENERAL CONDITIONS				\$35,190
BONDS	1.00%			\$3,519
INSURANCE	2.00%			\$7,038
PERMIT				NIC
OVERHEAD AND FEE	5.00%			\$17,595
OWNER CONTINGENCY				By Owner
TOTAL OF ALL CONSTRUCTION	Jun-17	1,215	\$341.76	\$415,242



RENOVATIONS + ADDITIONS 26-Sep-16

Winchester, MA

Feasibility Design Estimate

MINOR RENOVATION + ADDITIONS TO McCALL MIDDLE SCHOOL

RENOVATE EXISTING SCHOOL		5,600	\$142.28	\$796,766
ADDITION		4,675	\$285.01	\$1,332,427
SITEWORK				\$100,000
SUB-TOTAL	Jun-17	10,275	\$216.95	\$2,229,193
ESCALATION TO START - (assumed 4% PA)	5.3%			\$118,147
DESIGN AND PRICING CONTINGENCY	12%			\$267,503
SUB-TOTAL		10,275	\$254.49	\$2,614,843
GENERAL CONDITIONS				\$261,484
BONDS	1.00%			\$26,148
INSURANCE	2.00%			\$52,297
PERMIT				NIC
OVERHEAD AND FEE	5.00%			\$130,742
OWNER CONTINGENCY				By Owner
TOTAL OF ALL CONSTRUCTION	Jun-17	10,275	\$300.29	\$3,085,514



RENOVATIONS + ADDITIONS
Winchester, MA

Feasibility Design Estimate

NEW PARKHURST ELEMENTARY SCHOOL - ES6

DEMOLISH EXISTING SCHOOL		37,650	\$8.00	\$301,200
HAZMAT REMOVALS		37,650	\$15.00	\$564,750
NEW SCHOOL		57,413	\$256.00	\$14,697,728
SITEWORK - (Allowance of 10% of Building)				\$1,469,773
SUB-TOTAL	Jun-17	57,413	\$281.60	\$16,167,501
ESCALATION TO START - (assumed 4% PA)	5.3%			\$856,878
DESIGN AND PRICING CONTINGENCY	12%			\$1,940,100
SUB-TOTAL		57,413	\$330.32	\$18,964,479
GENERAL CONDITIONS				\$1,517,158
BONDS	1.00%			\$189,645
INSURANCE	2.00%			\$379,290
PERMIT				NIC
OVERHEAD AND FEE	3.00%			\$568,934
OWNER CONTINGENCY				By Owner
TOTAL OF ALL CONSTRUCTION	Jun-17	57,413	\$376.56	\$21,619,506



RENOVATIONS + ADDITIONS

Winchester, MA

Feasibility Design Estimate

ADDITION and MAJOR RENOVATION TO PARKHURST ELEMENTARY SCHOOL

RENOVATE EXISTING SCHOOL		35,560	\$220.00	\$7,823,200
PARTIAL DEMO EXISTING SCHOOL		2,090	\$10.00	\$20,900
ADDITION		21,500	\$273.81	\$5,886,888
HAZMAT REMOVALS		37,650	\$15.00	\$564,750
SITEWORK - (Allowance of 10% of Building)				\$1,371,009
SUB-TOTAL	Jun-17	57,060	\$274.57	\$15,666,747
ESCALATION TO START - (assumed 4% PA)	5.3%			\$830,338
DESIGN AND PRICING CONTINGENCY	12%			\$1,880,010
SUB-TOTAL		57,060	\$322.07	\$18,377,095
GENERAL CONDITIONS				\$1,470,168
BONDS	1.00%			\$183,771
INSURANCE	2.00%			\$367,542
PERMIT				NIC
OVERHEAD AND FEE	3.00%			\$551,313
OWNER CONTINGENCY				By Owner
TOTAL OF ALL CONSTRUCTION	Jun-17	57,060	\$367.16	\$20,949,889

26-Sep-16



Winchester Schools RENOVATIONS + ADDITIONS Winchester, MA

26-Sep-16

Feasibility Design Estimate

This Feasibility Design cost estimate was produced from preliminary drawings prepared by Flansburgh Architects Inc. and their design team dated September 16, 2016. Design and engineering changes occurring subsequent to the issue of these documents have not been incorporated in this estimate.

This estimate includes all direct construction costs, general contractor's overhead, fee and design contingency. Cost escalation assumes start dates indicated.

Bidding conditions are expected to be public bidding under Chapter 149 of the Massachusetts General Laws to pre-qualified general contractors, and pre-qualified sub-contractors, open specifications for materials and manufactures.

The estimate is based on prevailing wage rates for construction in this market and represents a reasonable opinion of cost. It is not a prediction of the successful bid from a contractor as bids will vary due to fluctuating market conditions, errors and omissions, proprietary specifications, lack or surplus of bidders, perception of risk, etc. Consequently the estimate is expected to fall within the range of bids from a number of competitive contractors or subcontractors, however we do not warrant that bids or negotiated prices will not vary from the final construction cost estimate.

ITEMS NOT CONSIDERED IN THIS ESTIMATE

Items not included in this estimate are:

Land acquisition, feasibility, and financing costs
All professional fees and insurance
Site or existing conditions surveys investigations costs, including to determine subsoil conditions
All Furnishings, Fixtures and Equipment
Items identified in the design as Not In Contract (NIC)
Items identified in the design as by others
Owner supplied and/or installed items as indicated in the estimate
Utility company back charges, including work required off-site
Work to City streets and sidewalks, (except as noted in this estimate)
Construction contingency



Winchester Schools RENOVATIONS + ADDITIONS

Winchester, MA

Feasibility Design Estimate GFA 1,505

		CONSTRUCTION COST SUMMARY								
ADDITI	BUILDING ON TO LY		SUB-TOTAL	TOTAL	\$/SF	%				
A10		DATIONS	070.440							
	A1010	Standard Foundations	\$76,418							
	A1020	Special Foundations	\$0		004.00	40.00/				
	A1030	Lowest Floor Construction	\$20,889	\$97,307	\$64.66	18.0%				
A20	BASEM	ENT CONSTRUCTION								
	A2010	Basement Excavation	\$0							
	A2020	Basement Walls	\$0	\$0	\$0.00	0.0%				
B10	SUPER	STRUCTURE								
DIO	B1010	Upper Floor Construction	\$0							
	B1020	Roof Construction	\$48,535	\$48,535	\$32.25	9.0%				
B20		IOR CLOSURE								
	B2010	Exterior Walls	\$78,357							
	B2020	Windows	\$68,074		****	00.00/				
	B2030	Exterior Doors	\$16,520	\$162,951	\$108.27	30.2%				
B30	ROOFI	NG								
	B3010	Roof Coverings	\$46,967							
	B3020	Roof Openings	\$0	\$46,967	\$31.21	8.7%				
C10	INTERI	OR CONSTRUCTION								
	C1010	Partitions	\$17,544							
	C1020	Interior Doors	\$10,900							
	C1030	Specialties/Millwork	\$8,608	\$37,052	\$24.62	6.9%				
C20	STAIRO	SACEC								
C20	C2010	Stair Construction	\$0							
	C2020	Stair Finishes	\$0 \$0	\$0	\$0.00	0.0%				
C30		OR FINISHES	***							
	C3010	Wall Finishes	\$10,743							
	C3020	Floor Finishes	\$12,040		****	~ 0 0/				
	C3030	Ceiling Finishes	\$9,030	\$31,813	\$21.14	5.9%				
D10	CONVE	YING SYSTEMS								
	D1010	Elevator	\$0	\$0	\$0.00	0.0%				
D20	PLUME	BING								
_	D20	Plumbing	\$5,000	\$5,000	\$3.32	0.9%				

26-Sep-16



Winchester, MA

Feasibility Design Estimate GFA 1,505

		CONSTRUCTION	COST SUMMA	NRY		
	BUILDING		SUB-TOTAL	TOTAL	\$/SF	%
ADDITIC	ON TO LY	NCH ES				
D3o	HVAC					
	D30	HVAC	\$48,160	\$48,160	\$32.00	8.9%
D40	FIRE P	ROTECTION				
	D40	Fire Protection	\$6,773	\$6,773	\$4.50	1.3%
D50	ELECT	RICAL				
	D5010	Complete System	\$30,100	\$30,100	\$20.00	5.6%
E10	EQUIP	MENT				
	E10	Equipment	\$0	\$0	\$0.00	0.0%
E20	FURNIS	SHINGS				
	E2010	Fixed Furnishings	\$15,382			
	E2020	Movable Furnishings	NIC	\$15,382	\$10.22	2.8%
F10	SPECIA	AL CONSTRUCTION				
	F10	Special Construction	\$0	\$0	\$0.00	0.0%
F20	HAZMA	AT REMOVALS				
	F2010	Building Elements Demolition	\$10,000			
	F2020	Hazardous Components Abatement	\$0	\$10,000	\$6.64	1.9%
TOT	AL DIDE	CT COST (Trade Costs)		\$540,040	\$358.83	100.0%



56

Mesh reinforcing 15% lap

Winchester Schools RENOVATIONS + ADDITIONS Winchester, MA

Feasibility Design Estimate GFA 1,505

26-Sep-16

CSI				UNIT	EST'D	SUB	TOTAL
CODE	DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST

ADDITION TO LYNCH ES

GROSS	FLOOR AREA CALCULATION					
	First Floor			1,505		
	TOTAL GROSS FLOOR AREA (GFA)				1,505 sf	
A10	FOUNDATIONS					
A1010	STANDARD FOUNDATIONS Strip footings - 2'-0" x 1'-0"					
	Excavation	143	cy	20.00	2,860	
	Store on site for reuse	143	cy	14.00	2,002	
	Backfill with existing fill	133	cy	16.00	2,128	
	Remove surplus fill off site	10	cy	25.00	250	
	Formwork	258	sf	12.00	3,096	
	Re-bar, 10#/lf	1,290	lbs	1.20	1,548	
	Concrete material; 3,000 psi	10	cy	125.00	1,250	
	Placing concrete	10	cy	55.00	550	
	Foundation walls at exterior - 14" thick					
	Formwork	1,032	sf	14.00	14,448	
	Re-bar, 4.5#/sf	2,322	lbs	1.20	2,786	
	Concrete material; 4,000 psi	23	сy	135.00	3,105	
	Placing concrete	23	cy	65.00	1,495	
	Dampproofing foundation wall and footing	-3 77 4	sf	1.90	NIC	
	Insulation to foundation walls; 2" thick	516	sf	2.50	1,290	
	Form shelf	129	lf	8.00	1,032	
	Column footings, typical, 5' x 5' x 2'-0"	-=7		2.20	2,002	
	Excavation	86	CV	20.00	1,720	
	Store on site for reuse	86	cy	14.00	1,720	
	Store on site for reuse Backfill with new fill	86 68	cy	14.00	1,204	
			cy		360	
	Remove surplus fill off site	18	cy	20.00		
	Formwork	360	sf	11.00	3,960	
	Re-bar	5,040	lbs	1.20	6,048	
	Concrete material; 3,000 psi	18	cy	125.00	2,250	
	Placing concrete	18	cy	55.00	990	
	Set anchor bolts grout plates	9	ea	150.00	1,350	
	<u>Interior pilasters</u>					
	Formwork	264	sf	11.00	2,904	
	Re-bar	1,620	lbs	1.20	1,944	
	Concrete material; 3,000 psi	5	cy	125.00	625	
	Placing concrete	5	cy	55.00	275	
	Foundations against existing building	77	lf	180.00	13,860	
	SUBTOTAL					76,418
A < = - :	CRECIAL EQUIND ATTIONS					
A1020	SPECIAL FOUNDATIONS No Work in this section					
	SUBTOTAL					
	SODIOTAL					
A1030	LOWEST FLOOR CONSTRUCTION					
	New Slab on grade, 5" thick					
	Structural gravel fill, 8"	3 7	cy	30.00	1,110	
	Base course, 8" gravel	3 7	cy	40.00	1,480	
	Rigid insulation	1,505	sf	2.25	3,386	
	Vapor barrier	1,505	sf	1.00	1,505	
	M 1 1 C 1 170/1		c	0.00	1.005	

1,731

0.80

1,385



58

60

69 70

71

72 73 74

75

76

77 78

79

81

83

84

85

87

89

90

91

93

94

95

97

98 99 100

RENOVATIONS + ADDITIONS Winchester, MA

Feasibility Design Estimate GFA 1,505

SI CODE	DESCRIPTION	QTY	UNIT	UNIT COST	EST'D COST	SUB TOTAL	TOTAL COST
DDITION	TO LYNCH ES						
	Concrete - 5" thick	25	cy	125.00	3,125		
	Placing concrete	25	cy	45.00	1,125		
	Finishing and curing concrete	1,505	sf	4.00	6,020		
	Control joints - saw cut	1,505	sf	0.50	753		
	<u>Miscellaneous</u>						
	Dewatering	1	ea	1,000.00	1,000		
	SUBTOTAL					20,889	

26-Sep-16

A20 BASEMENT CONSTRUCTION

A2010 BASEMENT EXCAVATION

No items in this section

SUBTOTAL

A2020 BASEMENT WALLS

No items in this section

SUBTOTAL

TOTAL - BASEMENT CONSTRUCTION

B10	SUPERSTRUCTURE
-----	----------------

B1010 FLOOR CONSTRUCTION

No Work in this section

SUBTOTAL

B1020 ROOF CONSTRUCTION

Roof Structure - Steel:

Steel beams/Joists; 13#/SF 10 tns 3,800.00 38,000

Roof Structure

1-1/2" Metal floor Deck @ roof 1,505 sf 3.00 4,515

Miscellaneous

NIC Roof screen framing - allow

6,020 Fire proofing to columns, beams and deck 4.00 1,505 sf

SUBTOTAL 48,535

13 lbs/sf

10

tns

TOTAL - SUPERSTRUCTURE

\$48,535

EXTERIOR CLOSURE

L		1			
B2010	EXTERIOR WALLS; 60% solid/40% glass Interior skin	1,084	sf		
	6" metal stud backup	1,084	sf	7.50	8,130
	Batt insulation in stud	1,084	sf	2.25	2,439
	2 1/2" Rigid Insulation	1,084	sf	3.00	3,252
	Air barrier	1,084	sf	6.00	6,504
	Air barrier/flashing at windows	238	lf	7.00	1,666
	Gypsum Sheathing	1,084	sf	2.75	2,981
	Drywall lining to interior face of stud backup	1,084	sf	3.00	3,252
	Exterior skin				



Feasibility Design Estimate GFA 1,505

CSI CODE	DESCRIPTION	QTY	UNIT	UNIT COST	EST'D COST	SUB TOTAL	TOTAL COST
	N TO LYNCH ES	, , , , , , , , , , , , , , , , , , ,			7,77		7777
2	Brick veneer; 75% of exterior wall	813	sf	35.00	28,455		
3	Metal panels; 25% of exterior wall	271	sf	60.00	16,260		
4	<u>Miscellaneous</u>						
15	Staging to exterior wall	1,806	sf	3.00	5,418		
16	SUBTOTAL					78,357	
17 18 B2 0	020 WINDOWS	722	sf				
19	Premium for sunscreen and light shelf elements	1	ls		NIC		
20	Windows/storefront	722	sf	90.00	64,980		
21	Backer rod & double sealant	238	lf	9.00	2,142		
22	Wood blocking at openings	238	lf	4.00	952		
23	SUBTOTAL					68,074	
24 25 R9	TWEEDLOD DOODS						
B20	O30 EXTERIOR DOORS Glazed entrance doors including frame and hardware;	2	pr	8,000.00	16,000		
	double door at corridor exit	-	Pι	0,000.00	10,000		
27	Packer red & double content		1£	0.00	200		
28	Backer rod & double sealant	40	lf lf	9.00	360 160		
29	Wood blocking at openings SUBTOTAL	40	11	4.00	160	16,520	
30	SUDIOTAL					10,320	
31	TOTAL - EXTERIOR CLOSURE						\$162,951
32 33							
34 B	o ROOFING	1					
35]					
B36 B37	D10 ROOF COVERINGS Flat roofing						
38	PVC roof membrane fully adhered	1,505	sf	14.00	21,070		
39	Insulation	1,505	sf	7.00	10,535		
10	1/2" dens-deck protection board	1,505	sf	2.00	3,010		
11	Reinforced vapor barrier	1,505	sf	1.50	2,258		
12	Rough blocking	824	lf	6.00	4,944		
13	Miscellaneous Roofing						
14	Roof screens - allow				NIC		
15	Roof fascia/cornice	206	lf	25.00	5,150		
16	SUBTOTAL					46,967	
17 18 Ro 4	020 ROOF OPENINGS						
19	Skylights, allow				NIC		
50	Roof hatch				NIC		
51	SUBTOTAL					-	
52							
53	TOTAL - ROOFING						\$46,967
54							
56 C 1	o INTERIOR CONSTRUCTION]					
57	P.I. DIETER CATO	•					
⁵⁸ C10	O10 PARTITIONS CWR furred wall at existing exterior wall	600	°t.	19.00	11 100		
30	GWB furred wall at existing exterior wall Corridors; GWB with 2 lyrs corridor side	930	sf ef	12.00 15.55	11,160 4,665		
31	Ç .	300	sf ef	0.50	4,665		
32	Sealants & caulking at partitions Rough blocking to partitions	300	sf lf	3.00	69		
33	Rough blocking to partitions Glazed partitions/borrowed lights - allowance	23	ls	1,500.00	1,500		
34	SUBTOTAL	1	15	1,300.00	1,500	17,544	
35	SODIOIAL					17,344	
	20 INTERIOR DOORS				_		
37	Corridor glazed doors Classroom door with sidelight	1	pr	8,000.00 2,900.00	8,000 2,900		
38		1	ea				



Feasibility Design Estimate GFA 1,505

SI ODE	DESCRIPTION DESCRIPTION	QTY	UNIT	UNIT COST	EST'D COST	SUB TOTAL	TOTA
DDITION TO	O LYNCH ES					10,900	
	SUBTOTAL					10,900	
C1030	SPECIALTIES / MILLWORK						
	Marker boards/tackboards in classroom	128	sf	24.00	3,072		
	Room Signs	1	ea	150.00	150		
	Lockers				Not Required		
	Expansion joints	1	ls	2,000.00	2,000		
	Miscellaneous metals throughout building	1,505	sf	1.25	1,881		
	Miscellaneous sealants throughout building	1,505	sf	1.00	1,505		
	SUBTOTAL	,,,				8,608	
	TOTAL - INTERIOR CONSTRUCTION						фо
	TOTAL - INTERIOR CONSTRUCTION						\$3
C20	STAIRCASES						
C2010	STAIR CONSTRUCTION						
02010	No Work in this section						
	SUBTOTAL					-	
_							
C2020	STAIR FINISHES No Work in this section						
	SUBTOTAL					-	
	TOTAL - STAIRCASES						
Сзо	INTERIOR FINISHES	\neg					
C3010	WALL FINISHES Paint to GWB	1,530	sf	1.50	2,295		
	Ceramic Tile to corridor	352	sf	24.00	8,448		
	SUBTOTAL	33-	51	21.00	0,110	10,743	
						,	
C3020	FLOOR FINISHES						
	Resilient floor finishes	1,505	sf	8.00	12,040		
	SUBTOTAL					12,040	
Сзозо	CEILING FINISHES						
	Allowance for ceiling finishes; 2 x 2 ACT	1,505	sf	6.00	9,030		
	SUBTOTAL					9,030	
	TOTAL - INTERIOR FINISHES						\$3
D10	CONVEYING SYSTEMS						
D1010	ELEVATOR						
	No Work in this section						
	SUBTOTAL						
	TOTAL - CONVEYING SYSTEMS						
D20	PLUMBING						
D20	PLUMBING, GENERALLY	_					
D20	New sink in classrooms	1	loc	5,000.00	5,000		
	SUBTOTAL					5,000	
	TOTAL - PLUMBING						\$
							Ψ,



233 234 235

236

237 238

239 240 241

242 243

244

245

246 247

248 249 250

251 252

253

254

255 256 257

258 259 260

261 262

263

264

265 266

267 268

271

272

273

274

275

276 277

278

279

280 281

282 283 284

285 286

287

288

289 290

291 292 293

294 295 RENOVATIONS + ADDITIONS Winchester, MA

Feasibility Design Estimate GFA 1.505

CSI				UNIT	EST'D	SUB	TOTAL
CODE	DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST
ADDI'	TION TO LYNCH ES				·		
	D30 HVAC, GENERALLY						

HVAC complete system 32.00 48,160 1,505 gsf

SUBTOTAL 48,160

TOTAL - HVAC \$48,160

4.50

6,773

6.773

26-Sep-16

FIRE PROTECTION D40

D40 FIRE PROTECTION, GENERALLY Sprinkler system 1,505

gsf SUBTOTAL

TOTAL - FIRE PROTECTION \$6,773

ELECTRICAL D₅o

D5010 COMPLETE ELECTRICAL SYSTEM

20.00 30,100 Electrical system; complete 1,505 gsf

SUBTOTAL 30,100

TOTAL - ELECTRICAL \$30,100

E10 **EQUIPMENT**

EQUIPMENT, GENERALLY

AV Equipment (including Smartboards, Projectors, FF+E

LED monitors, Digital information displays etc.) **SUBTOTAL**

TOTAL - EQUIPMENT

E20 **FURNISHINGS**

FIXED FURNISHINGS E2010

Entry mats & frames - recessed with carpet/rubber 45.00 2,250

Manual operated roller shades 722 sf 6.00 4,332 ls 8,800.00 8,800

Counters, base cabinets, tall storage in classrooms and other rooms

SUBTOTAL 15,382

E2020 MOVABLE FURNISHINGS

All movable furnishings to be provided and installed by owner

SUBTOTAL NIC

TOTAL - FURNISHINGS \$15,382

SPECIAL CONSTRUCTION F10

F10 SPECIAL CONSTRUCTION

No Work in this section

SUBTOTAL

TOTAL - SPECIAL CONSTRUCTION

F20 SELECTIVE BUILDING DEMOLITION

F2010 BUILDING ELEMENTS DEMOLITION



303

Winchester Schools RENOVATIONS + ADDITIONS Winchester, MA

Feasibility Design Estimate

CSI				UNIT	EST'D	SUB	TOTAL
CODE	DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST
100	TOUT TO THE STATE OF THE						

26-Sep-16

1,505

\$10,000

GFA

ADDITION TO LYNCH ES

10,000.00 10,000 Create openings to existing façade for new 1 loc connections

297 SUBTOTAL 10,000

298

F2020 HAZARDOUS COMPONENTS ABATEMENT
None Included 300

TOTAL - SELECTIVE BUILDING DEMOLITION

301 SUBTOTAL 302



Winchester, MA

Feasibility Design Estimate GFA 11,030

	מוווו מוווים		ON COST SUMMA		¢/CF	0/
DITIC	BUILDING ON TO LA	YNCH ES3	SUB-TOTAL	TOTAL	\$/SF	%
A10		OATIONS	6100.005			
	A1010 A1020	Standard Foundations	\$183,965 \$0			
	A1020 A1030	Special Foundations Lowest Floor Construction	\$0 \$146,271	¢000 006	\$29.94	11.9%
	A1030	Lowest Floor Construction	\$140,271	\$330,236	329.94	11.97
A20	BASEM	ENT CONSTRUCTION				
	A2010	Basement Excavation	\$0			
	A2020	Basement Walls	\$0	\$0	\$0.00	0.09
B10	SUPER	STRUCTURE				
	B1010	Upper Floor Construction	\$0			
	B1020	Roof Construction	\$350,810	\$350,810	\$31.81	12.69
B20	EXTER	IOR CLOSURE				
	B2010	Exterior Walls	\$227,120			
	B2020	Windows	\$197,443			
	B2030	Exterior Doors	\$16,520	\$441,083	\$39.99	15.89
В30	ROOFI	NG				
	B3010	Roof Coverings	\$288,561			
	B3020	Roof Openings	\$0	\$288,561	\$26.16	10.49
В	INTER	OR CONSTRUCTION				
	C1010	Partitions	\$180,191			
	C1020	Interior Doors	\$37,000			
	C1030	Specialties/Millwork	\$85,511	\$302,702	\$27.44	10.99
C20	STAIR	CASES				
	C2010	Stair Construction	\$0			
	C2020	Stair Finishes	\$0	\$0	\$0.00	0.09
С30	INTER	OR FINISHES				
-	C3010	Wall Finishes	\$70,740			
	C3020	Floor Finishes	\$88,240			
	C3030	Ceiling Finishes	\$66,180	\$225,160	\$20.41	8.19
D10	CONVE	CYING SYSTEMS				
	D1010	Elevator	\$0	\$0	\$0.00	0.09
D20	PLUME	BING				
	D20	Plumbing	\$132,360	\$132,360	\$12.00	4.79



Feasibility Design Estimate GFA 11,030

		CONSTRUCTION	COST SUMM	ARY		
	BUILDING		SUB-TOTAL	TOTAL	\$/SF	%
DDITIC	ON TO LY	NCH ES3				
D30	HVAC					
	D30	HVAC	\$352,960	\$352,960	\$32.00	12.7%
D40	FIRE P	ROTECTION				
	D40	Fire Protection	\$49,635	\$49,635	\$4.50	1.8%
D50	ELECT	RICAL				
	D5010	Complete System	\$220,600	\$220,600	\$20.00	7.9%
E10	EQUIP	MENT				
	E10	Equipment	\$0	\$0	\$0.00	0.0%
E20	FURNIS	SHINGS				
	E2010	Fixed Furnishings	\$67,614			
	E2020	Movable Furnishings	NIC	\$67,614	\$6.13	2.4%
F10	SPECIA	AL CONSTRUCTION				
	F10	Special Construction	\$0	\$0	\$0.00	0.0%
F20	HAZMA	AT REMOVALS				
	F2010	Building Elements Demolition	\$25,000			
	F2020	Hazardous Components Abatement	\$0	\$25,000	\$2.27	0.9%
TOTA	AL DIREC	CT COST (Trade Costs)		\$2,786,721	\$252.65	100.0%



56

Mesh reinforcing 15% lap

Feasibility Design Estimate GFA 11,030

26-Sep-16

CSI				UNIT	EST'D	SUB	TOTAL
CODE	DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST

ADDITION TO LYNCH ES3

.11ON IC	J LINCH ESS					
GROSS	FLOOR AREA CALCULATION					
	First Floo	r		11,030		
	TOTAL GROSS FLOOR AREA (GFA)				11.000 cf	
	TOTAL GROSS FLOOR AREA (GFA)				11,030 sf	
A10	FOUNDATIONS	٦				
	STANDARD FOUNDATIONS Strip footings - 2'-0" x 1'-0"	-				
	Excavation	416	cy	20.00	8,320	
	Store on site for reuse	416	cy	14.00	5,824	
	Backfill with existing fill	387	cy	16.00	6,192	
	Remove surplus fill off site	29		25.00	725	
	Formwork	748	cy sf	12.00	8,976	
	Re-bar, 10#/lf	3,740	lbs	1.20	4,488	
	Concrete material; 3,000 psi	3,740		125.00	3,625	
	Placing concrete		cy	55.00	1,595	
	Foundation walls at exterior - 14" thick	29	cy	55.00	1,595	
	Formwork	2,992	sf	14.00	41,888	
	Re-bar, 4.5#/sf		lbs	1.20	8,078	
	Concrete material; 4,000 psi	6,732 68		135.00	9,180	
	Placing concrete	68	cy	65.00	9,180 4,420	
	<u>v</u>		cy sf	1.90	4,420 NIC	
	Dampproofing foundation wall and footing Insulation to foundation walls; 2" thick	2,244	si sf	2.50	3,740	
	Form shelf	1,496	si lf	2.50 8.00	3,740 2,992	
	Column footings, typical, 5' x 5' x 2'-0"	374	11	6.00	۷,99۲	
	Excavation	100	CV	20.00	3 800	
		190	cy	20.00	3,800	
	Store on site for reuse	190	cy	14.00	2,660	
	Backfill with new fill	151	cy	16.00	2,416	
	Remove surplus fill off site	39	cy	20.00	780	
	Formwork	800	sf	11.00	8,800	
	Re-bar	11,200	lbs	1.20	13,440	
	Concrete material; 3,000 psi	39	cy	125.00	4,875	
	Placing concrete	39	cy	55.00	2,145	
	Set anchor bolts grout plates	20	ea	150.00	3,000	
	Interior pilasters	2.5	C	14.00	0.440	
	Formwork	586	sf	11.00	6,446	
	Re-bar	3,600	lbs	1.20	4,320	
	Concrete material; 3,000 psi	10	cy	125.00	1,250	
	Placing concrete	10	cy	55.00	550	
	Foundations against existing building	108	lf	180.00	19,440	
	SUBTOTAL					183,965
A1020	SPECIAL FOUNDATIONS					
	No Work in this section					
	SUBTOTAL					
A = = = =	LOWEST ELOOP CONSTRUCTOR					
A1030	LOWEST FLOOR CONSTRUCTION New Slab on grade, 5" thick					
	=	050	CV	30.00	8,160	
	Structural gravel fill, 8"	272	cy			
	Base course, 8" gravel	272	cy	40.00	10,880	
	Rigid insulation	11,030	sf	2.25	24,818	
	Vapor barrier	11,030	sf	1.00	11,030	
	NA In In Committee of 150/ In	(0-	- C	0.00	10 140	

12,685

sf

0.80

10,148



RENOVATIONS + ADDITIONS

Winchester, MA

58

60

69 70

71

72 73 74

75

76

77 78

79

81

83

85

87

89

90

91

93

94

95

97

98 99 100

Feasibility Design Estimate GFA 11,030

SI	P.EGGPVPETOV	0,000		UNIT	EST'D	SUB	TOTAL
DDITION	DESCRIPTION N TO LYNCH ES3	QTY	UNIT	COST	COST	TOTAL	COST
DDIIIO	· ·						
	Concrete - 5" thick	180	cy	125.00	22,500		
	Placing concrete	180	cy	45.00	8,100		
	Finishing and curing concrete	11,030	sf	4.00	44,120		
	Control joints - saw cut	11,030	sf	0.50	5,515		
	<u>Miscellaneous</u>						
	Dewatering	1	ea	1,000.00	1,000		
	SUBTOTAL					146,271	
	TOTAL - FOUNDATIONS						\$330,2

26-Sep-16

A20 BASEMENT CONSTRUCTION

A2010 BASEMENT EXCAVATION

No items in this section

SUBTOTAL

A2020 BASEMENT WALLS

No items in this section

SUBTOTAL

TOTAL - BASEMENT CONSTRUCTION

SUPERSTRUCTURE B10

B1010 FLOOR CONSTRUCTION

No Work in this section

SUBTOTAL

B1020 ROOF CONSTRUCTION

Roof Structure - Steel:

Steel beams/Joists; 13#/SF tns 3,800.00 273,600

Roof Structure

1-1/2" Metal floor Deck @ roof 11,030 sf 3.00 33,090

Miscellaneous

NIC Roof screen framing - allow

Fire proofing to columns, beams and deck 4.00 44,120 11,030 sf

SUBTOTAL 350,810

13 lbs/sf

72

tns

TOTAL - SUPERSTRUCTURE \$350,810

B20 EXTERIOR CLOSURE

B2010	EXTERIOR WALLS; 60% solid/40% glass Interior skin	3,142	sf		
	6" metal stud backup	3,142	sf	7.50	23,565
	Batt insulation in stud	3,142	sf	2.25	7,070
	2 1/2" Rigid Insulation	3,142	sf	3.00	9,426
	Air barrier	3,142	sf	6.00	18,852
	Air barrier/flashing at windows	691	lf	7.00	4,837
	Gypsum Sheathing	3,142	sf	2.75	8,641
	Drywall lining to interior face of stud backup	3,142	sf	3.00	9,426
	Exterior skin				



Feasibility Design Estimate GFA 11,030

Feasibility Desi	gn Estimate					GFA	11,0
CSI CODE	DESCRIPTION	QTY	UNIT	UNIT COST	EST'D COST	SUB TOTAL	TOTAL COST
ADDITION T	O LYNCH ES3						
	Brick veneer; 75% of exterior wall	2,357	sf	35.00	82,495		
	Metal panels; 25% of exterior wall	785	sf	60.00	47,100		
	<u>Miscellaneous</u>						
	Staging to exterior wall	5,236	sf	3.00	15,708		
	SUBTOTAL					227,120	
	WINDOWS		C				
В2020	> WINDOWS Premium for sunscreen and light shelf elements	2,094	sf ls		NIC		
	Windows/storefront	1	sf	90.00	188,460		
	Backer rod & double sealant	2,094	lf	9.00	6,219		
		691					
	Wood blocking at openings	691	lf	4.00	2,764	107.440	
	SUBTOTAL					197,443	
B2030	EXTERIOR DOORS						
	Glazed entrance doors including frame and hardware; double door at corridor exit	2	pr	8,000.00	16,000		
	Backer rod & double sealant	40	lf	9.00	360		
	Wood blocking at openings	40	lf	4.00	160		
	SUBTOTAL					16,520	
Г	TOTAL EVTEDIOD OLOCUPE						 -
	TOTAL - EXTERIOR CLOSURE						\$441,0
Взо	ROOFING						
D	POOL GOVERNIGG						
В3010	ROOF COVERINGS Flat roofing						
	PVC roof membrane fully adhered	11,030	sf	14.00	154,420		
	Insulation	11,030	sf	7.00	77,210		
	1/2" dens-deck protection board	11,030	sf	2.00	22,060		
	Reinforced vapor barrier	11,030	sf	1.50	16,545		
	Rough blocking	1,496	lf	6.00	8,976		
	Miscellaneous Roofing	-,47		0.00	2,010		
	Roof screens - allow				NIC		
	Roof fascia/cornice	374	lf	25.00	9,350		
	SUBTOTAL	3/4		20.00	3,330	288,561	
	552.5 Hill					200,001	
B3020	ROOF OPENINGS						
	Skylights, allow				NIC		
	Roof hatch				NIC		
	SUBTOTAL					-	
Г	TOTAL BOOKING						\$200
	TOTAL - ROOFING						\$288,5
C10	INTERIOR CONSTRUCTION						
Canan							
C1010	PARTITIONS GWB furred wall at existing exterior wall	1,500	sf	12.00	18,000		
	Corridors; GWB with 2 lyrs corridor side	9,870	sf	15.55	153,479		
	Sealants & caulking at partitions	9,870	sf	0.50	4,935		
	Rough blocking to partitions		lf	3.00	4,933 2,277		
	Glazed partitions/borrowed lights - allowance	759 1	ls	1,500.00	1,500		
	SUBTOTAL	1	13	1,500.00	1,300	190 101	
	SUDTUTAL					180,191	
C1020	INTERIOR DOORS						
C1020	INTERIOR DOORS Corridor glazed doors Classroom door with sidelight	1	pr	8,000.00 2,900.00	8,000 29,000		



Winchester, MA

SI	n Estimate			UNIT	EST'D	GFA SUB	TOTAL
ODE DOITION TO	DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST
IDDITION TO	SUBTOTAL					37,000	
	SOBIOTAL					37,000	
C1030	SPECIALTIES / MILLWORK						
	Marker boards/tackboards in classroom	768	sf	24.00	18,432		
	Toilet partitions and accessories	11,030	gfa	0.75	8,273		
	Room Signs	11,030	gfa	0.25	2,758		
	Wood paneling/benches/display cases etc.	11,030	gfa	1.50	16,545		
	Lockers	11,030	sf	1.15	12,685		
	Expansion joints	1	ls	2,000.00	2,000		
	Miscellaneous scalants throughout building	11,030	sf	1.25 1.00	13,788 11,030		
	Miscellaneous sealants throughout building SUBTOTAL	11,030	sf	1.00	11,030	85,511	
						65,511	
	TOTAL - INTERIOR CONSTRUCTION						\$302,
C20	STAIRCASES						
C2010	STAIR CONSTRUCTION						
	No Work in this section						
	SUBTOTAL					-	
C2020	STAIR FINISHES						
	No Work in this section						
	SUBTOTAL					-	
	TOTAL - STAIRCASES						
<u> </u>							
Сзо	INTERIOR FINISHES	\neg					
C3010	WALL FINISHES Paint to GWB	21,240	sf	1.50	31,860		
	Ceramic Tile to corridor	1,620	sf	24.00	38,880		
	SUBTOTAL	,				70,740	
C3020	FLOOR FINISHES Resilient floor finishes	11 000	c.f	8.00	88,240		
	SUBTOTAL	11,030	sf	8.00	86,240	88,240	
						00,240	
С3030	CEILING FINISHES Allowance for ceiling finishes; 2 x 2 ACT	11 000	sf	6.00	66,180		
	SUBTOTAL	11,030	31	0.00	00,100	66,180	
						,	
	TOTAL - INTERIOR FINISHES						\$225,
D10	CONVEYING SYSTEMS						
D1010	ELEVATOR						
	No Work in this section						
	SUBTOTAL					-	
	TOTAL - CONVEYING SYSTEMS						
D20	PLUMBING						
D20	PLUMBING, GENERALLY						
	New sink in classrooms	11,030	sf	12.00	132,360	,	
	SUBTOTAL					132,360	
	TOTAL - PLUMBING						\$132,3



Winchester, MA

232 233 234

235 236

237

238

240

241 242 243

244 245

246

247

248 249

250 251 252

253 254

256

257 258 259

260 261 262

263 264

265

266

267

270 271

272 273

274

275

276

277

278

280

281

282 283

284 285 286

287 288

289

290

291 292

293 294 295 Feasibility Design Estimate GFA 11,030

CSI				UNIT	EST'D	SUB	TOTAL
CODE	DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST

ADDITION TO LYNCH ES3

D30 HVAC

D30 HVAC, GENERALLY

HVAC complete system **11,030** gsf 32.00 352,960

SUBTOTAL 352,960

TOTAL - HVAC \$352,960

26-Sep-16

D40 FIRE PROTECTION

D40 FIRE PROTECTION, GENERALLY

Sprinkler system **11,030** gsf 4.50 49,635

SUBTOTAL 49,635

TOTAL - FIRE PROTECTION \$49,635

D50 ELECTRICAL

D5010 COMPLETE ELECTRICAL SYSTEM

Electrical system; complete **11,030** gsf 20.00 220,600

SUBTOTAL 220,600

TOTAL - ELECTRICAL \$220,600

E10 EQUIPMENT

E10 EQUIPMENT, GENERALLY

AV Equipment (including Smartboards, Projectors, $$\operatorname{FF}+\operatorname{E}$$

LED monitors, Digital information displays etc.)

SUBTOTAL

TOTAL - EQUIPMENT

E20 FURNISHINGS

E2010 FIXED FURNISHINGS

Entry mats & frames - recessed with carpet/rubber 50 sf 45.00 2,250 strips

Manual operated roller shades **2,094** sf 6.00 12,564

Counters, base cabinets, tall storage in classrooms **6** rms 8,800.00 52,800

and other rooms

SUBTOTAL 67,614

E2020 MOVABLE FURNISHINGS

All movable furnishings to be provided and installed

by owner

SUBTOTAL

TOTAL - FURNISHINGS \$67,614

F10 SPECIAL CONSTRUCTION

F10 SPECIAL CONSTRUCTION

No Work in this section

SUBTOTAL

TOTAL - SPECIAL CONSTRUCTION

F20 SELECTIVE BUILDING DEMOLITION



305

Winchester Schools RENOVATIONS + ADDITIONS Winchester, MA

TOTAL - SELECTIVE BUILDING DEMOLITION

Feasibility Design Estimate GFA 11,030

26-Sep-16

\$25,000

CSI				UNIT	EST'D	SUB	TOTAL			
CODE	DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST			

ADDITION TO LYNCH ES3 297 F2010 BUILDING ELEMENTS DEMOLITION 298 Create openings to existing façade for new loc 25,000.00 25,000 connections 299 SUBTOTAL 25,000 300 301 F2020 HAZARDOUS COMPONENTS ABATEMENT 302 None Included SUBTOTAL 304



Feasibility Design Estimate

Winchester, MA

		CONSTRUCTION				
FNOVA	BUILDING TION TO	O EXISTING VINSON-OWENS ES	SUB-TOTAL	TOTAL	\$/SF	%
A10		OATIONS				
AIU	A1010	Standard Foundations	\$0			
	A1020	Special Foundations	\$0			
	A1030	Lowest Floor Construction	\$0	\$0	\$0.00	0.0%
B10	SUPER	STRUCTURE				
	B1010	Upper Floor Construction	\$0			
	B1020	Roof Construction	\$0	\$0	\$0.00	0.0%
B20	EXTER	IOR CLOSURE				
	B2010	Exterior Walls	\$0			
	B2020	Windows/Curtainwall	\$0			
	B2030	Exterior Doors	\$0	\$0	\$0.00	0.0%
Взо	ROOFI	NG				
	B3010	Roof Coverings	\$0			
	B3020	Roof Openings	\$0	\$0	\$0.00	0.0%
C10	INTER	IOR CONSTRUCTION				
	C1010	Partitions	\$16,576			
	C1020	Interior Doors	\$10,900			
	C1030	Specialties/Millwork	\$625	\$28,101	\$29.58	30.2%
C20	STAIR	CASES				
	C2010	Stair Construction	\$0			
	C2020	Stair Finishes	\$0	\$0	\$0.00	0.0%
С30	INTERI	IOR FINISHES				
	C3010	Wall Finishes	\$3,400			
	C3020	Floor Finishes	\$9,500			
	C3030	Ceiling Finishes	\$5,750	\$18,650	\$19.63	20.1%
D10	CONVE	EYING SYSTEMS				
	D1010	Elevator	\$0	\$0	\$0.00	0.09
D20	PLUME	BING				
	D20	Plumbing	\$0	\$0	\$0.00	0.0%
D30	HVAC					
	D30	HVAC	\$14,250	\$14,250	\$15.00	15.39
D40		ROTECTION				
	D40	Fire Protection	\$1,900	\$1,900	\$2.00	2.0%
D50	ELECT					
	D5010	Electrical Systems	\$14,250	\$14,250	\$15.00	15.3%
E10	EQUIP	MENT				

26-Sep-16

950

GFA



26-Sep-16

Feasibility Design Estimate GFA 950

	BUILDING	SYSTEM	SUB-TOTAL	TOTAL	\$/SF	%
ENOVA	ATION TO	EXISTING VINSON-OWENS ES				
	E10	Equipment	\$0	\$0	\$0.00	0.0%
E20	FURNIS	SHINGS				
	E2010	Fixed Furnishings	\$0			
	E2020	Movable Furnishings	NIC	\$0	\$0.00	0.0%
F10	SPECIA	L CONSTRUCTION				
	F10	Special Construction	\$0	\$0	\$0.00	0.0%
F20	SELECT	TIVE BUILDING DEMOLITION				
	F2010	Building Elements Demolition	\$15,750			
	F2020	Hazardous Components Abatement	\$0	\$15,750	\$16.58	17.0%
TOTA	AL DIREC	CT COST (Trade Costs)		\$92,901	\$97.79	100.0%



Winchester, MA

10

12

14 15

16

17

18 19

20 21 22

23 24

25

26

27

28

30

31 32

33 34 35

36 37

38

39

41

43

45

46

47

48

50 51 52

53 54

55

56

57 58

59

60

61 62

63 64 Feasibility Design Estimate GFA 950

				UNIT	EST'D	SUB	TOTAL	ı
	DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST	

RENOVATION TO EXISTING VINSON-OWENS ES

TOTAL RENOVATED AREA (GFA) 950 GSF

26-Sep-16

A10 FOUNDATIONS

A1010 STANDARD FOUNDATIONS

No work in this section SUBTOTAL

A1020 SPECIAL FOUNDATIONS

No work in this section

SUBTOTAL

A1030 LOWEST FLOOR CONSTRUCTION

No work in this section

SUBTOTAL

TOTAL - FOUNDATIONS

B10 SUPERSTRUCTURE

B1010 FLOOR CONSTRUCTION

No work in this section SUBTOTAL

B1020 ROOF CONSTRUCTIONNo work in this section

SUBTOTAL

TOTAL - SUPERSTRUCTURE

B20 EXTERIOR CLOSURE

B2010 EXTERIOR WALLS

No work assumed to existing exterior

SUBTOTAL

B2020 WINDOWS/CURTAINWALL

No work assumed to existing exterior

SUBTOTAL

B2030 EXTERIOR DOORS

No work assumed to existing exterior

SUBTOTAL

TOTAL - EXTERIOR CLOSURE

B30 ROOFING

B3010 ROOF COVERINGS

No work assumed to existing exterior

SUBTOTAL

B3020 ROOF OPENINGS

No work in this section

SUBTOTAL

TOTAL - ROOFING

Winchester Schools Feasibility 9.26.16 Page 33 PMC - Project Management Cost



Winchester, MA

Feasibility Design Estimate GFA 950

26-Sep-16

\$28,101

				UNIT	EST'D	SUB	TOTAL
	DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST
OVATION	TO EXISTING VINSON-OWENS ES				•		
C10	INTERIOR CONSTRUCTION						
C1010	PARTITIONS						
	New walls	1,036	sf	16.00	16,576		
	SUBTOTAL					16,576	
C1020	INTERIOR DOORS						
	Corridor glazed doors	1	pr	8,000.00	8,000		
	Classroom door with sidelight	1	ea	2,900.00	2,900		
	SUBTOTAL					10,900	
C1030	SPECIALTIES / MILLWORK						
	Room Signs	1	loc	150.00	150		
	Miscellaneous sealants throughout building	950	sf	0.50	475		
	SUBTOTAL					625	

C20	STAIRCASES
-----	------------

C2010 STAIR CONSTRUCTION

No work in this section $\label{eq:subtotal} SUBTOTAL$

C2020 STAIR FINISHES

No work in this section $\label{eq:SUBTOTAL} SUBTOTAL$

TOTAL - STAIRCASES

TOTAL - INTERIOR CONSTRUCTION

C30 INTERIOR FINISHE	\boldsymbol{S}
----------------------	------------------

C3010	WALL FINISHES					
	Paint to walls etc.	950	sf	2.00	1,900	
	Patch existing walls	1	ls	1,500.00	1,500	
	SUBTOTAL					3,400
Casas	ELOOR EINIGHEG					
C3020	FLOOR FINISHES					
	New resilient flooring	950	sf	8.00	7,600	
	Floor prep	950	sf	2.00	1,900	
	SUBTOTAL					9,500
Сзозо	CEILING FINISHES					
	ACT, 2x2	950	sf	5.00	4,750	
	Patch existing flooring	1	ls	1,000.00	1,000	
	SUBTOTAL					5,750

TOTAL - INTERIOR FINISHES \$18,650

D10 CONVEYING SYSTEMS

No work in this section SUBTOTAL

TOTAL - CONVEYING SYSTEMS

D20 PLUMBING



Winchester, MA

126 127

128

129

130 131

132 133 134

135 136

137

138

139

140

141 142 143

144 145

146

147

148 149

150 151 152

153 154

155

156

157 158

159 160 161

162 163

164

165

166 167

168 169 170

171 172

173

174

175 176

177

178

179 180

182 183

184 185

186

Feasibility Design Estimate GFA 950

			UNIT	ESTD	SUB	TOTAL	Ĺ
DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST	İ

RENOVATION TO EXISTING VINSON-OWENS ES

D20 PLUMBING, GENERALLY

No work in this section SUBTOTAL

TOTAL - PLUMBING

D30 HVAC

D30 HVAC, GENERALLY

HVAC modifications **950** sf 15.00 14,250

SUBTOTAL 14,250

TOTAL - HVAC \$14,250

26-Sep-16

D40 FIRE PROTECTION

D40 FIRE PROTECTION, GENERALLY

Sprinkler system modifications **950** sf 2.00 1,900

SUBTOTAL 1,900

TOTAL - FIRE PROTECTION \$1,900

D50 ELECTRICAL

D5010 COMPLETE ELECTRICAL SYSTEMS

Lighting, power and Tele/Data modifications **950** sf 15.00 14,250

SUBTOTAL 14,250

TOTAL - ELECTRICAL \$14,250

E10 EQUIPMENT

E10 EQUIPMENT, GENERALLY

No work in this section

SUBTOTAL -

TOTAL - EQUIPMENT

E20 FURNISHINGS

E2010 FIXED FURNISHINGS

No work in this section
SUBTOTAL -

E2020 MOVABLE FURNISHINGS

All movable furnishings to be provided and installed

by owner.

SUBTOTAL NIC

TOTAL - FURNISHINGS

F10 SPECIAL CONSTRUCTION

F10 SPECIAL CONSTRUCTION

No items in this section SUBTOTAL.

565161.



Winchester, MA

193 194

195

196

197

198

199

200

201 202

203

204

205 206 Feasibility Design Estimate GFA 950

				UNIT	EST'D	SUB	TOTAL
	DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST

RENOVATION TO EXISTING VINSON-OWENS ES

TOTAL - SPECIAL CONSTRUCTION

26-Sep-16

F20 SELECTIVE BUILDING DEMOLITION

F2010 BUILDING ELEMENTS DEMOLITION

Remove existing GWB walls ls 1,000.00 1,000 1 Remove floor finishes 950 sf 2.00 1,900 Remove ceilings 950 $\mathbf{s}\mathbf{f}$ 1.00 950 Form opening in exterior wall for connection to 10,000.00 ls 10,000 modular addition $Miscellaneous\ demo/protection$ gfa 2.00 1,900 950

SUBTOTAL 15,750

F2020 HAZARDOUS COMPONENTS ABATEMENT

None Included SUBTOTAL

TOTAL - SELECTIVE BUILDING DEMOLITION \$15,750

Winchester Schools Feasibility 9.26.16 Page 36 PMC - Project Management Cost



26-Sep-16

Feasibility Design Estimate GFA 5,600

		CONSTRUCT	TON COST SUMMA	RY		
RENOVA	BUILDING	S SYSTEM O EXISTING McCALL MS	SUB-TOTAL	TOTAL	\$/SF	%
A10		DATIONS				
Alu	A1010	Standard Foundations	\$30,000			
	A1020	Special Foundations	\$0			
	A1030	Lowest Floor Construction	\$10,000	\$40,000	\$7.14	5.0%
B10	SUPER	STRUCTURE				
	B1010	Upper Floor Construction	\$15,000			
	B1020	Roof Construction	\$0	\$15,000	\$2.68	1.9%
B20	EXTER	IOR CLOSURE				
	B2010	Exterior Walls	\$10,000			
	B2020	Windows/Curtainwall	\$0			
	B2030	Exterior Doors	\$0	\$10,000	\$1.79	1.3%
В30	ROOFI	NG				
	B3010	Roof Coverings	\$0			
	B3020	Roof Openings	\$0	\$0	\$0.00	0.0%
C10	INTER	IOR CONSTRUCTION				
	C1010	Partitions	\$96,016			
	C1020	Interior Doors	\$11,600			
	C1030	Specialties/Millwork	\$2,950	\$110,566	\$19.74	13.9%
C20	STAIR	CASES				
	C2010	Stair Construction	\$0			
	C2020	Stair Finishes	\$0	\$0	\$0.00	0.0%
Сзо	INTER	IOR FINISHES				
	C3010	Wall Finishes	\$21,800			
	C3020	Floor Finishes	\$56,000			
	C3030	Ceiling Finishes	\$31,000	\$108,800	\$19.43	13.7%
D10	CONVE	EYING SYSTEMS				
	D1010	Elevator	\$100,000	\$100,000	\$17.86	12.6%
D20	PLUMI	BING				
	D20	Plumbing	\$0	\$0	\$0.00	0.0%
D30	HVAC					
	D30	HVAC	\$179,200	\$179,200	\$32.00	22.5%
D40	FIRE P	ROTECTION				
	D40	Fire Protection	\$11,200	\$11,200	\$2.00	1.4%
D50	ELECT	RICAL				
	D5010	Electrical Systems	\$132,000	\$132,000	\$23.57	16.6%
E10	EQUIP	MENT				



26-Sep-16

Feasibility Design Estimate GFA 5,600

	BUILDING	SYSTEM	SUB-TOTAL	TOTAL	\$/SF	%
ENOVA	ATION TO	D EXISTING McCALL MS				
	E10	Equipment	\$0	\$0	\$0.00	0.0%
E20	FURNIS	SHINGS				
	E2010	Fixed Furnishings	\$35,200			
	E2020	Movable Furnishings	NIC	\$35,200	\$6.29	4.4%
F10	SPECIA	L CONSTRUCTION				
	F10	Special Construction	\$0	\$0	\$0.00	0.0%
F20	SELECT	TIVE BUILDING DEMOLITION				
	F2010	Building Elements Demolition	\$54,800			
	F2020	Hazardous Components Abatement	\$0	\$54,800	\$9.79	6.9%
TOTA	AL DIREC	CT COST (Trade Costs)		\$796,766	\$142.28	100.0%



Winchester, MA

11

12

13

14

16

17

18 19

20 21 22

23 24

25

26

27 28

29 30 31

32 33 34

35 36

37

38

39 40

41

42

43 44

45

46

47 48

50 51

52 53

54

55

57

60 61

62

Feasibility Design Estimate GFA 5,600

26-Sep-16

				UNIT	EST'D	SUB	TOTAL	ı
	DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST	

RENOVATION TO EXISTING McCALL MS

TOTAL RENOVATED AREA (GFA) 5,600 GSF

A10 FOUNDATIONS

A1010 STANDARD FOUNDATIONS

New elevator pit **1** loc 30,000.00 30,000

SUBTOTAL 30,000

A1020 SPECIAL FOUNDATIONS

No work in this section

SUBTOTAL

A1030 LOWEST FLOOR CONSTRUCTION

Patch existing slab **1** loc 10,000.00 10,000

SUBTOTAL 10,000

TOTAL - FOUNDATIONS \$40,000

B10 SUPERSTRUCTURE

B1010 FLOOR CONSTRUCTION

Create floor opening for new elevator ${f 1} \quad loc \quad 15,000.00 \quad 15,000$

SUBTOTAL 15,000

B1020 ROOF CONSTRUCTION

SUBTOTAL -

TOTAL - SUPERSTRUCTURE \$15,000

B20 EXTERIOR CLOSURE

B2010 EXTERIOR WALLS

New elevator vent **1** ls 10,000.00 10,000

SUBTOTAL 10,000

B2020 WINDOWS/CURTAINWALL

No work assumed to existing exterior

SUBTOTAL -

B2030 EXTERIOR DOORS

No work assumed to existing exterior

SUBTOTAL

TOTAL - EXTERIOR CLOSURE \$10,000

B30 ROOFING

B3010 ROOF COVERINGS

No work assumed to existing exterior

SUBTOTAL

B3020 ROOF OPENINGS

No work in this section

SUBTOTAL -

TOTAL - ROOFING



Winchester, MA

1		1		UNIT	EST'D	SUB	TOTAL
	DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST
OVATIO	N TO EXISTING McCALL MS				1		
C10	INTERIOR CONSTRUCTION						
	D. D. D. D. C.	<u> </u>					
C1010	PARTITIONS New elevator shaft assumed CMU	1,120	sf	30.00	33,600		
	New walls	3,276	sf	16.00	52,416		
	Patch existing walls	3,2/0	ls	10,000.00	10,000		
	SUBTOTAL	1	15	10,000.00	10,000	96,016	
	SODIOTAL					30,010	
C1020	INTERIOR DOORS						
	Classroom door with sidelight	4	ea	2,900.00	11,600		
	SUBTOTAL					11,600	
C1030	SPECIALTIES / MILLWORK						
0-	Room Signs	1	loc	150.00	150		
	Miscellaneous sealants throughout building	5,600	sf	0.50	2,800		
	SUBTOTAL					2,950	
	TOTAL - INTERIOR CONSTRUCTION						011
	TOTAL - INTERIOR CONSTRUCTION						\$110
		_					
C20	STAIRCASES						
C2010	STAIR CONSTRUCTION						
	No work in this section						
	SUBTOTAL					-	
Canan	STAIR FINISHES						
C2020	No work in this section						
	SUBTOTAL					-	
	TOTAL - STAIRCASES						
Сзо	INTERIOR FINISHES						
Cento	WALL FINISHES						
C3010	Paint to walls etc.	5,600	gsf	3.00	16,800		
	Patch existing walls	1		5,000.00	5,000		
	SUBTOTAL	_	15	0,000.00	0,000	21,800	
						,	
C3020	FLOOR FINISHES		. c	0.00	44.000		
	New resilient flooring	5,600	sf	8.00	44,800		
	Floor prep	5,600	sf	2.00	11,200		
			sf	2.00	11,200	56,000	
C3030	Floor prep		sf	2.00	11,200	56,000	
C3030	Floor prep SUBTOTAL		sf sf	5.00	11,200 28,000	56,000	
C3030	Floor prep SUBTOTAL CEILING FINISHES	5,600				56,000	
C3 03 0	Floor prep SUBTOTAL CEILING FINISHES ACT, 2x2	5,600	sf	5.00	28,000	56,000 31,000	
C3030	Floor prep SUBTOTAL CEILING FINISHES ACT, 2x2 Patch existing flooring	5,600	sf	5.00	28,000		\$108
C3030	Floor prep SUBTOTAL CEILING FINISHES ACT, 2x2 Patch existing flooring SUBTOTAL	5,600	sf	5.00	28,000		\$108
C3030	Floor prep SUBTOTAL CEILING FINISHES ACT, 2x2 Patch existing flooring SUBTOTAL	5,600	sf	5.00	28,000		\$108
	Floor prep SUBTOTAL CEILING FINISHES ACT, 2x2 Patch existing flooring SUBTOTAL TOTAL - INTERIOR FINISHES CONVEYING SYSTEMS	5,600 5,600 1	sf ls	5.00 3,000.00	28,000 3,000		\$108
	Floor prep SUBTOTAL CEILING FINISHES ACT, 2x2 Patch existing flooring SUBTOTAL TOTAL - INTERIOR FINISHES	5,600	sf	5.00	28,000		\$108



Winchester, MA

125

126 127

128

129

130 131

132 133 134

135 136

137

138

139

140

141 142 143

144 145

146

147

148

149

150 151 152

153 154

155

157

158 159

160 161 162

163 164

165

166 167

169 170 171

172 173

174

175

176 177

178

179

180

181

182 183 184 Feasibility Design Estimate GFA 5,600

			UNIT	EST'D	SUB	TOTAL
DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST

RENOVATION TO EXISTING McCALL MS

D20 PLUMBING

D20 PLUMBING, GENERALLY

No work in this section SUBTOTAL

TOTAL - PLUMBING

D30 HVAC

D30 HVAC, GENERALLY

HVAC modifications **5,600** sf 32.00 179,200

SUBTOTAL 179,200

TOTAL - HVAC \$179,200

26-Sep-16

D40 FIRE PROTECTION

D40 FIRE PROTECTION, GENERALLY

Sprinkler system modifications **5,600** sf 2.00 11,200

SUBTOTAL 11,200

TOTAL - FIRE PROTECTION \$11,200

D50 ELECTRICAL

D5010 COMPLETE ELECTRICAL SYSTEMS

Feeders to elevator 1 ls 20,000.00 20,000

Lighting, power and Tele/Data modifications **5,600** sf 20.00 112,000

SUBTOTAL 132,000

TOTAL - ELECTRICAL \$132,000

E10 EQUIPMENT

E10 EQUIPMENT, GENERALLY

No work in this section

SUBTOTAL -

TOTAL - EQUIPMENT

E20 FURNISHINGS

E2010 FIXED FURNISHINGS

Counters, base cabinets, tall storage in classrooms and 4 rms 8,800.00 35,200

other rooms

SUBTOTAL 35,200

E2020 MOVABLE FURNISHINGS

All movable furnishings to be provided and installed

by owner

SUBTOTAL

TOTAL - FURNISHINGS \$35,200

F10 SPECIAL CONSTRUCTION



F20

Winchester, MA

GFA Feasibility Design Estimate 5,600

			UNIT	EST'D	SUB	TOTAL	l
DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST	l

RENOVATION TO EXISTING McCALL MS

185 186 187

SPECIAL CONSTRUCTION

No items in this section SUBTOTAL

189

190

188

191 192

193

194 195

196 197 198

199 200

201 202 203

204 205 206

TOTAL - SPECIAL CONSTRUCTION

SELECTIVE BUILDING DEMOLITION

F2010 BUILDING ELEMENTS DEMOLITION

Gut demolition Form openings in slab/structure for elevator $\,$ Miscellaneous demo/protection

5,600 5,600

loc gfa

2

 \mathbf{sf}

5,000.00 2.00

6.00

10,000 11,200

33,600

54,800

PMC - Project Management Cost

F2020 HAZARDOUS COMPONENTS ABATEMENT

None Included SUBTOTAL

SUBTOTAL

TOTAL - SELECTIVE BUILDING DEMOLITION

\$54,800



Winchester, MA

Feasibility Design Estimate GFA 4,675

\$29.19	%
\$29.19	
\$29.19	
\$29.19	
\$29.19	
\$29.19	
	10.2%
\$0.00	0.0%
34.09	12.0%
\$90.95	31.9%
\$13.94	4.9%
\$22.70	8.0%
\$0.00	0.0%
\$18.48	6.5%
\$0.00	0.0%
\$4.28	1.5%
	\$34.09 \$90.95 \$13.94 \$22.70 \$0.00



Feasibility Design Estimate GFA 4,675

		CONSTRUCTION	COST SUMMA	ARY		
	BUILDING		SUB-TOTAL	TOTAL	\$/SF	%
DDITIC	ON TO M	cCALL MS				
D30	HVAC					
	D30	HVAC	\$149,600	\$149,600	\$32.00	11.2%
D40	FIRE P	ROTECTION				
	D40	Fire Protection	\$21,038	\$21,038	\$4.50	1.6%
D50	ELECT	RICAL				
	D5010	Complete System	\$93,500	\$93,500	\$20.00	7.0%
E10	EQUIP	MENT				
	E10	Equipment	\$0	\$0	\$0.00	0.0%
E20	FURNI	SHINGS				
	E2010	Fixed Furnishings	\$49,546			
	E2020	Movable Furnishings	NIC	\$49,546	\$10.60	3.7%
F10	SPECIA	AL CONSTRUCTION				
	F10	Special Construction	\$0	\$0	\$0.00	0.0%
F20	HAZMA	AT REMOVALS				
	F2010	Building Elements Demolition	\$20,000			
	F2020	Hazardous Components Abatement	\$0	\$20,000	\$4.28	1.5%
TOTA	AL DIRE	CT COST (Trade Costs)		\$1,332,427	\$285.01	100.0%



25

26 26

27

27

28

28

SUBTOTAL

A1030 LOWEST FLOOR CONSTRUCTION

New Slab on grade, 5" thick

Structural gravel fill, 8"

Base course, 8" gravel

Rigid insulation

Vapor barrier

Feasibility Design Estimate GFA 4,675

26-Sep-16

	QTY	UNIT	COST	COST	TOTAL	COS
ON						
Basement			2,315			
First Floor			2,360			
1115(1150)			2,000			
REA (GFA)				4,675	sf	
IS						
	258	CV	20.00	5,160		
	258 258	cy	14.00	3,612		
		cy	16.00	3,696		
	231	cy	25.00	675		
	27	cy sf	12.00	4,176		
	348	lbs	1.20	2,088		
	1,740		125.00	3,375		
	27	cy	55.00	1,485		
4" thick	2 7	cy	33.00	1,465		
4 tilick	1 = 10	sf	14.00	24,360		
	1,740	lbs	1.20	4,698		
	3,915		135.00	5,265		
	39	cy	65.00	2,535		
and fasting	39	cy				
and footing	870	sf	8.00	6,960		
2" thick	696	sf	2.50	1,740		
01.011	174	lf	8.00	1,392		
<u>x 2'-0"</u>	6 -		90.00	1.040		
	_					
	-	·				
	_					
	7	ea	150.00	1,050		
		C	11.00	0.055		
	_					
	4	cy				
	4	cy				
uilding	77	lf	180.00	13,860		
					104,324	
	uilding	67 67 53 14 280 3,920 14 14 7 205 1,260 4	67 cy 67 cy 53 cy 14 cy 280 sf 3,920 lbs 14 cy 7 ea 205 sf 1,260 lbs 4 cy 4 cy	67 cy 20.00 67 cy 14.00 53 cy 16.00 14 cy 20.00 280 sf 11.00 3,920 lbs 1.20 14 cy 125.00 14 cy 55.00 7 ea 150.00 205 sf 11.00 1,260 lbs 1.20 4 cy 125.00 4 cy 55.00 4 cy 55.00	67 cy 20.00 1,340 67 cy 14.00 938 53 cy 16.00 848 14 cy 20.00 280 280 sf 11.00 3,080 3,920 lbs 1.20 4,704 14 cy 125.00 1,750 14 cy 55.00 770 7 ea 150.00 1,050 205 sf 11.00 2,255 1,260 lbs 1.20 1,512 4 cy 125.00 500 4 cy 55.00 220	67 cy 20.00 1,340 67 cy 14.00 938 53 cy 16.00 848 14 cy 20.00 280 280 sf 11.00 3,080 3,920 lbs 1.20 4,704 14 cy 125.00 1,750 14 cy 55.00 770 7 ea 150.00 1,050 205 sf 11.00 2,255 1,260 lbs 1.20 1,512 4 cy 125.00 500 4 cy 55.00 220

58

58

2,360

2,360

cy

cy

sf

 $\mathbf{s}\mathbf{f}$

30.00

40.00

2.25

1.00

1,740

2,320

5,310

2,360



RENOVATIONS + ADDITIONS Winchester, MA

Feasibility Design Estimate GFA 4,675

CSI CODE	DESCRIPTION	QTY	UNIT	UNIT COST	EST'D COST	SUB TOTAL	TOTAL COST
ADDITIO	DDITION TO McCALL MS			-			
	Mesh reinforcing 15% lap	2,714	sf	0.80	2,171		
	Concrete - 5" thick	39	cy	125.00	4,875		
	Placing concrete	39	cy	45.00	1,755		
	Finishing and curing concrete	2,360	sf	4.00	9,440		
	Control joints - saw cut	2,360	sf	0.50	1,180		
	<u>Miscellaneous</u>						
	Dewatering	1	ea	1,000.00	1,000		
	SUBTOTAL					32,151	

TOTAL - FOUNDATIONS \$136,475

26-Sep-16

BASEMENT CONSTRUCTION A20

A2010 BASEMENT EXCAVATION

SUBTOTAL

A2020 BASEMENT WALLS

SUBTOTAL

TOTAL - BASEMENT CONSTRUCTION

B10	SUPERSTRUCTURE						
		13	lbs/sf				
B1010	FLOOR CONSTRUCTION	30	tns				
	Floor Structure - Steel:						
	Steel beams and columns; 13 lbs per SF	15	tns	3,500.00	52,500		
	Shear studs	463	ea	2.50	1,158		
	Floor Structure						
	3" 18 Ga. Metal galvanized floor Deck	2,315	sf	4.00	9,260		
	WWF reinforcement	2,662	sf	0.85	2,263		
	Concrete Fill to metal deck; 6-1/2" thick; Light Weight	43	cy	160.00	6,880		
	Place and finish concrete	2,315	sf	2.00	4,630		
	Rebar to decks	695	lbs	1.00	695		
	Miscellaneous						
	Fireproofing to columns and beams	2,315	sf	3.00	6,945		
	Fire stopping floors	1	ls	1,500.00	1,500		
	SUBTOTAL					85,831	
B1020	ROOF CONSTRUCTION						
	Roof Structure - Steel:						
	Steel beams/Joists; 13#/SF	15	tns	3,800.00	57,000		
	Roof Structure						
	1-1/2" Metal floor Deck @ roof	2,360	sf	3.00	7,080		
	Miscellaneous						
	Roof screen framing - allow				NIC		
	Fire proofing to columns, beams and deck	2,360	sf	4.00	9,440		
	SUBTOTAL					73,520	

B20	EXTERIOR CLOSURE
D20	EATERIOR CLOSURE

B2010 EXTERIOR WALLS; 60% solid/40% glass

sf 3,024



Feasibility Design Estimate GFA 4,675

26-Sep-16

DE	DESCRIPTION	QTY	UNIT	UNIT COST	EST'D COST	SUB TOTAL	TO CO
	O McCALL MS			1	1		
	<u>Interior skin</u>						
	6" metal stud backup	3,024	sf	7.50	22,680		
	Batt insulation in stud	3,024	sf	2.25	6,804		
	2 1/2" Rigid Insulation	3,024	sf	3.00	9,072		
	Air barrier	3,024	sf	6.00	18,144		
	Air barrier/flashing at windows	665	lf	7.00	4,655		
	Gypsum Sheathing	3,024	sf	2.75	8,316		
	Drywall lining to interior face of stud backup	3,024	sf	3.00	9,072		
	Exterior skin	3,0=4	51	0.00	0,072		
	Brick veneer; 75% of exterior wall	2,268	sf	35.00	79,380		
	Metal panels; 25% of exterior wall	756	sf	60.00	45,360		
	Miscellaneous	750	51	00.00	45,500		
		5 040	of.	2.00	15 120		
	Staging to exterior wall	5,040	sf	3.00	15,120	010 000	
	SUBTOTAL					218,603	
B2020	o WINDOWS	2,016	sf				
	Premium for sunscreen and light shelf elements	1	ls		NIC		
	Windows/storefront	2,016	sf	90.00	181,440		
	Backer rod & double sealant	665	lf	9.00	5,985		
	Wood blocking at openings	665	lf	4.00	2,660		
	SUBTOTAL	ŭ			,	190,085	
						200,000	
B203	EXTERIOR DOORS						
	Glazed entrance doors including frame and hardware; double door at corridor exit	2	pr	8,000.00	16,000		
	Backer rod & double sealant	40	lf	9.00	360		
	Wood blocking at openings	40	lf	4.00	160		
	SUBTOTAL					16,520	
	TOTAL EXPENSES OF OCCUPA						
	TOTAL - EXTERIOR CLOSURE						\$4
Pag	ROOFING						
B30							
В3010	Proof COVERINGS Flat roofing						
	PVC roof membrane fully adhered	2,360	sf	14.00	33,040		
	Insulation	2,360	sf	7.00	16,520		
	1/2" dens-deck protection board	2,360	sf	2.00	4,720		
	Reinforced vapor barrier	2,360	sf	1.50	3,540		
	Rough blocking	600	lf	6.00	3,600		
	Miscellaneous Roofing						
	Roof screens - allow				NIC		
	Roof fascia/cornice	150	lf	25.00	3,750		
	SUBTOTAL	ŭ				65,170	
Paga	O ROOF OPENINGS						
ь3020	Skylights, allow				NIC		
	Roof hatch				NIC		
					INIC		
	SURTOTAL					-	
	SUBTOTAL						

C10 INTERIOR CONSTRUCTION

C1010 PARTITIONS

84

84



 26-Sep-16

	n Estimate	•			nomir '	GFA	
	DESCRIPTION	QTY	UNIT	UNIT COST	EST'D COST	SUB TOTAL	TOTA COST
ITION TO	O McCALL MS			<u>.</u>			
	GWB furred wall at existing exterior wall	1,860	sf	12.00	22,320		
	Corridors; GWB with 2 lyrs corridor side	1,800	sf	15.55	27,990		
	Sealants & caulking at partitions	1,800	sf	0.50	900		
	Rough blocking to partitions	138	lf	3.00	414		
	Glazed partitions/borrowed lights - allowance	1	ls	1,500.00	1,500		
	SUBTOTAL					53,124	
C1020	INTERIOR DOORS						
	Corridor glazed doors	2	pr	8,000.00	16,000		
	Classroom door with sidelight	4	ea	2,900.00	11,600		
	SUBTOTAL					27,600	
C1030	SPECIALTIES / MILLWORK						
	Marker boards/tackboards in classroom	512	sf	24.00	12,288		
	Room Signs	4	ea	150.00	600		
	Lockers			1	Not Required		
	Expansion joints	1	ls	2,000.00	2,000		
	Miscellaneous metals throughout building	4,675	sf	1.25	5,844		
	Miscellaneous sealants throughout building	4,675	sf	1.00	4,675		
	SUBTOTAL					25,407	
	TOTAL - INTERIOR CONSTRUCTION						\$10
	10112 111211011 00110111011						Ψ20
C20	STAIRCASES	\neg					
020	STARCAGES						
C2010	STAIR CONSTRUCTION						
	No Work in this section						
	SUBTOTAL					-	
C2020	STAIR FINISHES						
	No Work in this section						
	SUBTOTAL					-	
	TOTAL - STAIRCASES						
Сзо	INTERIOR FINISHES						
C3010	WALL FINISHES						
	Paint to GWB	5,460	sf	1.50	8,190		
				94.00	12,768		
	Ceramic Tile to corridor	532	sf	24.00	12,700		
	Ceramic Tile to corridor SUBTOTAL	532	sf	24.00	12,700	20,958	
C3020		532	sf	24.00	12,700	20,958	
C3020	SUBTOTAL	532 4,675	sf sf	8.00	37,400	20,958	
C3 02 0	SUBTOTAL FLOOR FINISHES					20,958 37,400	
	SUBTOTAL FLOOR FINISHES Resilient floor finishes						
	SUBTOTAL FLOOR FINISHES Resilient floor finishes SUBTOTAL						
	SUBTOTAL FLOOR FINISHES Resilient floor finishes SUBTOTAL CEILING FINISHES	4,675	sf	8.00	37,400		
	SUBTOTAL FLOOR FINISHES Resilient floor finishes SUBTOTAL CEILING FINISHES Allowance for ceiling finishes; 2 x 2 ACT	4,675	sf	8.00	37,400	37,400	\$86

TOTAL - CONVEYING SYSTEMS

No Work in this section

D1010 ELEVATOR

SUBTOTAL



117 117

118 118

119

119

120 120

121 121 122

122 123

123

124

124 125

125 126 126

127 127

128

128

129 129

130 131

131 132

132

133

133 134 134

135 135 136

136 137

137

138

139

139 140 140

141 141

142

142

143

143

144 144

145

145

146 146

147 147

RENOVATIONS + ADDITIONS

Winchester, MA

UNIT EST'D SUB TOTAL UNIT

26-Sep-16

Feasibility Design Estimate GFA 4.675 CODE DESCRIPTION COST TOTAL COST ADDITION TO McCALL MS D20 PLUMBING D20 PLUMBING, GENERALLY New sink in classrooms 5,000.00 20,000 loc SUBTOTAL. 20,000 TOTAL - PLUMBING \$20,000 D30 HVAC HVAC, GENERALLY D30 HVAC complete system 32.00 149,600 4,675 gsf SUBTOTAL 149,600 TOTAL - HVAC \$149,600 D40 FIRE PROTECTION D40 FIRE PROTECTION, GENERALLY Sprinkler system 4.50 21,038 4,675 gsf **SUBTOTAL** 21,038 TOTAL - FIRE PROTECTION \$21,038 D50 ELECTRICAL D5010 COMPLETE ELECTRICAL SYSTEM

> Electrical system; complete 20.00 93,500 4,675 gsf

SUBTOTAL 93,500

TOTAL - ELECTRICAL \$93,500

EQUIPMENT E10

EQUIPMENT, GENERALLY E10

FF+E AV Equipment (including Smartboards, Projectors,

LED monitors, Digital information displays etc.)

SUBTOTAL

TOTAL - EQUIPMENT

FURNISHINGS

FIXED FURNISHINGS

Entry mats & frames - recessed with carpet/rubber 45.00 2,250 50 sf

strips

E20

E2010

Manual operated roller shades 6.00 12,096 2,016 sf 35,200

Counters, base cabinets, tall storage in classrooms 8,800.00 4 rms and other rooms

SUBTOTAL 49,546

E2020 MOVABLE FURNISHINGS

All movable furnishings to be provided and installed

by owner

SUBTOTAL NIC

TOTAL - FURNISHINGS \$49,546



148

148 149

149

150

151

151 152 152

153 153

154

154

155 155

156

157

158 159

Winchester Schools RENOVATIONS + ADDITIONS Winchester, MA

Feasibility Design Estimate

CSI				UNIT	EST'D	SUB	TOTAL
CODE	DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST

ADDITION TO McCALL MS SPECIAL CONSTRUCTION F10 F10 SPECIAL CONSTRUCTION No Work in this section SUBTOTAL TOTAL - SPECIAL CONSTRUCTION F20 SELECTIVE BUILDING DEMOLITION F2010 BUILDING ELEMENTS DEMOLITION 20,000 Create openings to existing façade for new 10,000.00 2 loc connections SUBTOTAL 20,000 F2020 HAZARDOUS COMPONENTS ABATEMENT

SUBTOTAL TOTAL - SELECTIVE BUILDING DEMOLITION

None Included

\$20,000

26-Sep-16

4,675

GFA



Feasibility Design Estimate GFA 15,015

			ON COST SUMMA			
LOWED	BUILDING	ADDITION TO MURACO ES	SUB-TOTAL	TOTAL	\$/SF	%
A10		DATIONS	0005.005			
	A1010	Standard Foundations	\$265,285			
	A1020	Special Foundations	\$0	4.60.506	001.17	10 10/
	A1030	Lowest Floor Construction	\$202,801	\$468,086	\$31.17	13.1%
A20	BASEM	IENT CONSTRUCTION				
	A2010	Basement Excavation	\$0			
	A2020	Basement Walls	\$0	\$0	\$0.00	0.0%
B10	SUPER	STRUCTURE				
210	B1010	Upper Floor Construction	\$0			
	B1020	Roof Construction	\$477,505	\$477,505	\$31.80	13.4%
B20	EVTED	IOR CLOSURE				
D20	B2010	Exterior Walls	\$230,748			
	B2020	Windows	\$200,646			
	B2030	Exterior Doors	\$16,520	\$447,914	\$29.83	12.5%
	Bacco	Exterior Boots	Ų10,0 <i>2</i> 0	¥ 44 /,9 24	Ψ20.00	12.070
B30	ROOFI	NG				
	B3010	Roof Coverings	\$377,962			
	B3020	Roof Openings	\$0	\$377,962	\$25.17	10.6%
C10	INTER	IOR CONSTRUCTION				
	C1010	Partitions	\$212,145			
	C1020	Interior Doors	\$47,900			
	C1030	Specialties/Millwork	\$98,097	\$358,142	\$23.85	10.0%
C20	STAIR	CASES				
	C2010	Stair Construction	\$0			
	C2020	Stair Finishes	\$0	\$0	\$0.00	0.0%
С30	INTER	IOR FINISHES				
2,33	C3010	Wall Finishes	\$91,503			
	C3020	Floor Finishes	\$120,120			
	C3030	Ceiling Finishes	\$90,090	\$301,713	\$20.09	8.4%
D10	CONVE	YING SYSTEMS				
210	D1010	Elevator	\$0	\$0	\$0.00	0.0%
	21010	210.400	Ų.	ΨΟ	\$5.00	0.070
D20	PLUME					
	D20	Plumbing	\$180,180	\$180,180	\$12.00	5.0%



Feasibility Design Estimate GFA 15,015

	BUILDING	CONSTRUCTION SYSTEM	SUB-TOTAL	TOTAL	\$/SF	%
WER I		DDITION TO MURACO ES	SOD TOTAL	TOTAL	φ/51	70
Doo	HVAC					
D30	D30	HVAC	\$480,480	\$480,480	\$32.00	13.4%
Die	EIDE D	DOMEC/MAN				
D40		ROTECTION	*****	4.5	*	4.00/
	D40	Fire Protection	\$67,568	\$67,568	\$4.50	1.9%
D50	ELECTI	RICAL				
	D5010	Complete System	\$300,300	\$300,300	\$20.00	8.4%
E10	EQUIP	MENT				
	E10	Equipment	\$0	\$0	\$0.00	0.0%
E20	FURNIS	SHINGS				
	E2010	Fixed Furnishings	\$94,218			
	E2020	Movable Furnishings	NIC	\$94,218	\$6.27	2.6%
F10	SPECIA	L CONSTRUCTION				
-	F10	Special Construction	\$0	\$0	\$0.00	0.0%
F20	HAZMA	AT REMOVALS				
	F2010	Building Elements Demolition	\$20,000			
	F2020	Hazardous Components Abatement	\$0	\$20,000	\$1.33	0.6%
TOTA	L DIREC	CT COST (Trade Costs)		\$3,574,068	\$238.03	100.0%



Feasibility Design Estimate GFA 15,015

26-Sep-16

CS	SI				UNIT	EST'D	SUB	TOTAL
CO	ODE	DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST

LOWER LEVEL ADDITION TO MURACO ES

GROSS FLOOR AREA CALCULATION

First Floor 15,015

	First F	1001		15,015		
	TOTAL GROSS FLOOR AREA (GFA)				15,015 sf	
A10	FOUNDATIONS					
A1010	STANDARD FOUNDATIONS Strip footings - 2'-0" x 1'-0"					
	Excavation	422	cy	20.00	8,440	
	Store on site for reuse	422	cy	14.00	5,908	
	Backfill with existing fill	392	cy	16.00	6,272	
	Remove surplus fill off site	30	cy	25.00	750	
	Formwork	760	sf	12.00	9,120	
	Re-bar, 10#/lf	3,800	lbs	1.20	4,560	
	Concrete material; 3,000 psi	30	cy	125.00	3,750	
	Placing concrete	30	cy	55.00	1,650	
	Foundation walls at exterior - 14" thick					
	Formwork	3,040	sf	14.00	42,560	
	Re-bar, 4.5#/sf	6,840	lbs	1.20	8,208	
	Concrete material; 4,000 psi	69	cy	135.00	9,315	
	Placing concrete	69	cy	65.00	4,485	
	Dampproofing foundation wall and footing	2,280	sf	1.90	NIC	
	Insulation to foundation walls; 2" thick	1,520	sf	2.50	3,800	
	Form shelf	380	lf	8.00	3,040	
	Column footings, typical, 5' x 5' x 2'-0"					
	Excavation	352	cy	20.00	7,040	
	Store on site for reuse	352	cy	14.00	4,928	
	Backfill with new fill	280	cy	16.00	4,480	
	Remove surplus fill off site	72	cy	20.00	1,440	
	Formwork	1,480	sf	11.00	16,280	
	Re-bar	20,720	lbs	1.20	24,864	
	Concrete material; 3,000 psi	72	cy	125.00	9,000	
	Placing concrete	72	cy	55.00	3,960	
	Set anchor bolts grout plates	3 7	ea	150.00	5,550	
	<u>Interior pilasters</u>					
	Formwork	1,083	sf	11.00	11,913	
	Re-bar	6,660	lbs	1.20	7,992	
	Concrete material; 3,000 psi	19	cy	125.00	2,375	
	Placing concrete	19	cy	55.00	1,045	
	Foundations against existing building	292	lf	180.00	52,560	
	SUBTOTAL					265,285
A1020	SPECIAL FOUNDATIONS No Work in this section					
	NO WORK IN this section SUBTOTAL					
A1030	LOWEST FLOOR CONSTRUCTION					
	New Slab on grade, 5" thick					
	Structural gravel fill, 8"	371	cy	30.00	11,130	
	Base course, 8" gravel	371	cy	40.00	14,840	
	Rigid insulation	15,015	sf	2.25	33,784	
	Vapor barrier	15,015	sf	1.00	15,015	
	Mesh reinforcing 15% lap	17,267	sf	0.80	13,814	



ibility Desig			, ,	HAIFF	ECT'D	GFA	TOTAL
3	DESCRIPTION	QTY	UNIT	UNIT COST	EST'D COST	SUB TOTAL	TOTAL COST
VER LEVI	EL ADDITION TO MURACO ES						
	Concrete - 5" thick	245	cy	125.00	30,625		
	Placing concrete	245	cy	45.00	11,025		
	Finishing and curing concrete	15,015	sf	4.00	60,060		
	Control joints - saw cut	15,015	sf	0.50	7,508		
	<u>Miscellaneous</u>						
	Dewatering	1	ea	5,000.00	5,000		
	SUBTOTAL					202,801	
	TOTAL - FOUNDATIONS						\$468,
							,
A20	BASEMENT CONSTRUCTION	7					
A2010	BASEMENT EXCAVATION						
	No items in this section						
	SUBTOTAL					-	
A2020	BASEMENT WALLS						
	No items in this section						
	SUBTOTAL					-	
	TOTAL - BASEMENT CONSTRUCTION						
B10	SUPERSTRUCTURE						
		13	lbs/sf				
B1010	FLOOR CONSTRUCTION	98	tns				
	No Work in this section SUBTOTAL					-	
B1020	ROOF CONSTRUCTION						
	Roof Structure - Steel:						
	Steel beams/Joists; 13#/SF	98	tns	3,800.00	372,400		
	Roof Structure			,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	,		
	1-1/2" Metal floor Deck @ roof	15,015	sf	3.00	45,045		
	Miscellaneous	-0,~-0		2.00	,5 10		
	Roof screen framing - allow				NIC		
	Fire proofing to columns, beams and deck	15,015	sf	4.00	60,060		
	SUBTOTAL	10,010	31	1.00	00,000	477,505	
	5521011IL					411,000	
	TOTAL - SUPERSTRUCTURE						\$477,
B20	EXTERIOR CLOSURE						
		_	•				
В2010	EXTERIOR WALLS; 60% solid/40% glass Interior skin	3,192	sf				
	6" metal stud backup	3,192	sf	7.50	23,940		
	Batt insulation in stud	3,192	sf	2.25	7,182		
	2 1/2" Rigid Insulation	3,192	sf	3.00	9,576		
	Air barrier	3,192	sf	6.00	19,152		
	Air barrier/flashing at windows	702	lf	7.00	4,914		
	Gypsum Sheathing	3,192	sf	2.75	8,778		
	Drywall lining to interior face of stud backup	3,192	sf	3.00	9,576		
	Exterior skin						



CSI

Feasibility Design Estimate GFA 15,015

EST'D

SUB

UNIT

26-Sep-16

TOTAL

	CODE CODE	DESCRIPTION	QTY	UNIT	COST	COST COST	TOTAL	COST
	LOWER LEVE	L ADDITION TO MURACO ES						
2		Brick veneer; 75% of exterior wall	2,394	sf	35.00	83,790		
3		Metal panels; 25% of exterior wall	798	sf	60.00	47,880		
4		Miscellaneous						
5		Staging to exterior wall	5,320	sf	3.00	15,960		
6		SUBTOTAL					230,748	
7								
18	B2020	WINDOWS	2,128	sf		NIC		
20		Premium for sunscreen and light shelf elements	1	ls	00.00	NIC		
21		Windows/storefront	2,128	sf	90.00	191,520		
22		Backer rod & double sealant	702	lf	9.00	6,318		
23		Wood blocking at openings	702	lf	4.00	2,808	000.040	
24		SUBTOTAL					200,646	
25	B2030	EXTERIOR DOORS						
26		Glazed entrance doors including frame and hardware; double door at corridor exit	2	pr	8,000.00	16,000		
27		Backer rod & double sealant	40	lf	9.00	360		
8		Wood blocking at openings	40	lf	4.00	160		
9		SUBTOTAL					16,520	
0		TOTAL - EXTERIOR CLOSURE						\$447.01
2		TOTAL - EXTERIOR CLOSURE						\$447,91
3								
4	Взо	ROOFING						
5 6	Rooto	ROOF COVERINGS						
7	B3010	Flat roofing						
8		PVC roof membrane fully adhered	15,015	sf	14.00	210,210		
89		Insulation	15,015	sf	7.00	105,105		
10		1/2" dens-deck protection board	15,015	sf	2.00	30,030		
11		Reinforced vapor barrier	15,015	sf	1.50	22,523		
12		Rough blocking	824	lf	6.00	4,944		
13		Miscellaneous Roofing						
14		Roof screens - allow				NIC		
5		Roof fascia/cornice	206	lf	25.00	5,150		
6		SUBTOTAL					377,962	
7								
9	B3020	ROOF OPENINGS				NIC		
i9 i0		Skylights, allow				NIC		
51		Roof hatch				NIC		
2		SUBTOTAL					-	
3		TOTAL - ROOFING						\$377,96
4								
5 6	Can	INTERIOR CONSTRUCTION						
7	C10	INTERIOR CONSTRUCTION						
8	C1010	PARTITIONS						
59		GWB furred wall at existing exterior wall	4,380	sf	12.00	52,560		
30		Interior partitions	9,495	sf	15.55	147,647		
		Sealants & caulking at partitions	9,495	sf	0.50	4,748		
31		Rough blocking to partitions	730	lf	3.00	2,190		
				_	F 000 00	F 000		
32		Glazed partitions/borrowed lights - allowance	1	ls	5,000.00	5,000		
31 32 33 34		Glazed partitions/borrowed lights - allowance SUBTOTAL	1	ls	5,000.00	5,000	212,145	
33 34 35	Cross	SUBTOTAL	1	ls	5,000.00	5,000	212,145	
32 33	C1020		1	ls pr	5,000.00 8,000.00	16,000	212,145	



Feasibility Design Estimate GFA 15,015

r	in Estimate			UNIT	EST'D	SUB	TOTAL
DE WERLEVE	DESCRIPTION EL ADDITION TO MURACO ES	QTY	UNIT	COST	COST	TOTAL	COST
, WEIGHT	SUBTOTAL					47,900	
	SOBIOTAL					47,500	
C1030	SPECIALTIES / MILLWORK						
	Marker boards/tackboards in classroom	1,152	sf	24.00	27,648		
	Toilet partitions and accessories	2	rms	9,000.00	18,000		
	Room Signs	11	ea	150.00	1,650		
	Lockers				Not Required		
	Expansion joints	1	ls	2,000.00	2,000		
	Lockers	15,015	sf	1.00	15,015		
	Miscellaneous metals throughout building	15,015	sf	1.25	18,769		
	Miscellaneous sealants throughout building	15,015	sf	1.00	15,015		
	SUBTOTAL					98,097	
	TOTAL - INTERIOR CONSTRUCTION	_					\$358,1
C20	STAIRCASES						
		_					
C2010	STAIR CONSTRUCTION						
	No Work in this section SUBTOTAL					_	
	SOBIOTAL					_	
C2020	STAIR FINISHES						
	No Work in this section SUBTOTAL					_	
	SOBIOTAL						
	TOTAL - STAIRCASES						
<i>C</i> 30	INTERIOR FINISHES						
C3010	WALL FINISHES						
-0	Paint to GWB	23,370	sf	1.50	35,055		
	Ceramic Tile to corridor	2,352	sf	24.00	56,448		
	SUBTOTAL					91,503	
Canan	FLOOR FINISHES						
03020	Resilient floor finishes	15,015	sf	8.00	120,120		
	SUBTOTAL					120,120	
Casas	CEH INC EINICHES						
C3030	CEILING FINISHES Allowance for ceiling finishes; 2 x 2 ACT	15,015	sf	6.00	90,090		
	SUBTOTAL	5 /- 3			-,	90,090	
	TOTAL INTERIOR ENVIOLES						d
	TOTAL - INTERIOR FINISHES						\$301,7
Dia	CONTIEVING CVCTEMC	\neg					
D10	CONVEYING SYSTEMS						
D1010	ELEVATOR						
	No Work in this section SUBTOTAL					_	
	TOTAL - CONVEYING SYSTEMS						
		_					
D20	PLUMBING						
D20	PLUMBING, GENERALLY			10.00	100 100		
	Plumbing allowance SUBTOTAL	15,015	gsf	12.00	180,180	180,180	
	SODIOTAL					100,180	



RENOVATIONS + ADDITIONS

Winchester, MA

230 231 232

233 234

235

236

237 238

239 240 241

242

243

244

245

246 247

248 249 250

251 252

254

255 257

258 259 260

261 262

263

264

265

268 269

270 271

272

273

274

275

276 277

278

279

280 281

282 283 284

285 286

287

288

289 290

291 292 293 Feasibility Design Estimate GFA 15.015

CSI				UNIT	EST'D	SUB	TOTAL
CODE	DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST

LOWER LEVEL ADDITION TO MURACO ES

D30 HVAC

HVAC, GENERALLY

HVAC complete system 15,015 32.00 480,480

SUBTOTAL 480,480

TOTAL - HVAC \$480,480

26-Sep-16

FIRE PROTECTION D40

FIRE PROTECTION, GENERALLY **D40**

4.50 67 568 Sprinkler system 15,015 gsf

SUBTOTAL 67,568

TOTAL - FIRE PROTECTION \$67,568

D50 ELECTRICAL

D5010 COMPLETE ELECTRICAL SYSTEM

Electrical system; complete 15,015 gsf 20.00 300.300

SUBTOTAL 300.300

TOTAL - ELECTRICAL \$300,300

EQUIPMENT E10

EQUIPMENT, GENERALLY

FF+EAV Equipment (including Smartboards, Projectors,

LED monitors, Digital information displays etc.)

SUBTOTAL

TOTAL - EQUIPMENT

FURNISHINGS E20

E2010 FIXED FURNISHINGS

Entry mats & frames - recessed with carpet/rubber 50 sf 45.00 2,250

strips

Manual operated roller shades 2,128 sf 6.00 12.768 8,800.00 79,200

Counters, base cabinets, tall storage in classrooms and other rooms

SUBTOTAL 94,218

9

E2020 MOVABLE FURNISHINGS

All movable furnishings to be provided and installed

by owner

SUBTOTAL NIC

TOTAL - FURNISHINGS \$94,218

rms

SPECIAL CONSTRUCTION F10

F10 SPECIAL CONSTRUCTION

No Work in this section

SUBTOTAL

TOTAL - SPECIAL CONSTRUCTION

F20 SELECTIVE BUILDING DEMOLITION



Feasibility Design Estimate

Winchester, MA

CSI				UNIT	EST'D	SUB	TOTAL
CODE	DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST

26-Sep-16

15,015

GFA

	CODE	DESCRIPTION	QIY	UNII	COST	COSI	IOIAL	COST
	LOWER LEVE	EL ADDITION TO MURACO ES						
294 295	Facto	BUILDING ELEMENTS DEMOLITION						
200	F2010	BUILDING ELEMENTS DEMOLITION						
296		Create openings to existing façade for new connections	2	loc	10,000.00	20,000		
297		SUBTOTAL					20.000	
298		565161.12					20,000	
299	F2020	HAZARDOUS COMPONENTS ABATEMENT						
300		None Included						
301		SUBTOTAL						
302								
303	TO	TAL - SELECTIVE BUILDING DEMOLITION						\$20,000



Winchester Schools RENOVATIONS + ADDITIONS

Winchester, MA

Feasibility Design Estimate GFA 20,600

		CONSTRUCTI	ON COST SUMM	ARY		
EDONE	BUILDING		SUB-TOTAL	TOTAL	\$/SF	%
FRONT		N TO MURACO ES				
A10		DATIONS				
	A1010	Standard Foundations	\$316,729			
	A1020	Special Foundations	\$0			
	A1030	Lowest Floor Construction	\$276,352	\$593,081	\$28.79	9.7%
A20	BASEM	IENT CONSTRUCTION				
	A2010	Basement Excavation	\$0			
	A2020	Basement Walls	\$0	\$0	\$0.00	0.0%
B10	SUPER	STRUCTURE				
	B1010	Upper Floor Construction	\$0			
	B1020	Roof Construction	\$653,400	\$653,400	\$31.72	10.7%
B20	EXTER	IOR CLOSURE				
	B2010	Exterior Walls	\$620,671			
	B2020	Windows	\$539,717			
	B2030	Exterior Doors	\$16,520	\$1,176,908	\$57.13	19.2%
В30	ROOFI	NG				
· ·	B3010	Roof Coverings	\$528,073			
	B3020	Roof Openings	\$0	\$528,073	\$25.63	8.6%
C10	INTER	IOR CONSTRUCTION				
	C1010	Partitions	\$264,272			
	C1020	Interior Doors	\$103,000			
	C1030	Specialties/Millwork	\$164,740	\$532,012	\$25.83	8.7%
C20	STAIR	CASES				
	C2010	Stair Construction	\$0			
	C2020	Stair Finishes	\$0	\$0	\$0.00	0.0%
С30	INTER	IOR FINISHES				
-0-	C3010	Wall Finishes	\$92,700			
	C3020	Floor Finishes	\$247,200			
	C3030	Ceiling Finishes	\$123,600	\$463,500	\$22.50	7.6%
D10	CONVE	EYING SYSTEMS				
-	D1010	Elevator	\$0	\$0	\$0.00	0.0%
D20	PLUME	BING				
	D20	Plumbing	\$247,200	\$247,200	\$12.00	4.0%



Feasibility Design Estimate GFA 20,600

		CONSTRUCTION	COST SUMMA	ARY		
	BUILDING		SUB-TOTAL	TOTAL	\$/SF	%
RONT A	DDITIO	N TO MURACO ES				
D30	HVAC					
	D30	HVAC	\$782,800	\$782,800	\$38.00	12.8%
D40	FIRE P	ROTECTION				
	D40	Fire Protection	\$92,700	\$92,700	\$4.50	1.5%
D50	ELECTI	RICAL				
	D5010	Complete System	\$700,400	\$700,400	\$34.00	11.4%
E10	EQUIP	MENT				
	E10	Equipment	\$137,100	\$137,100	\$6.66	2.2%
E20	FURNIS	SHINGS				
	E2010	Fixed Furnishings	\$118,994			
	E2020	Movable Furnishings	NIC	\$118,994	\$5.78	1.9%
F10	SPECIA	L CONSTRUCTION				
	F10	Special Construction	\$0	\$0	\$0.00	0.0%
F20	HAZMA	AT REMOVALS				
	F2010	Building Elements Demolition	\$94,875			
	F2020	Hazardous Components Abatement	\$0	\$94,875	\$4.61	1.5%
TOTA	I DIDE	CT COST (Trade Costs)		\$6,121,043	\$297.14	100.0%



55

56

Vapor barrier

Mesh reinforcing 15% lap

Feasibility Design Estimate GFA 20,600

26-Sep-16

CSI				UNIT	EST'D	SUB	TOTAL
CODE	DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST

FRONT ADDITION TO MURACO ES

GROSS FLOOR AREA CALCULATION

	First Floo			20,600		
	TOTAL GROSS FLOOR AREA (GFA)				20,600 sf	
A10	FOUNDATIONS	7				
A1010	STANDARD FOUNDATIONS Strip footings - 2'-0" x 1'-0"	-				
	Excavation	520	CV	20.00	10,600	
	Store on site for reuse	530 530	cy	14.00	7,420	
	Backfill with existing fill		cy	16.00	7,420	
	Remove surplus fill off site	493	cy	25.00	925	
	Formwork	37	cy sf	12.00	11,448	
	Re-bar, 10#/lf	954	lbs	1.20	5,724	
	Concrete material; 3,000 psi	4,770		125.00	4,625	
	•	37	cy	55.00	2,035	
	Placing concrete Foundation walls at exterior - 14" thick	37	cy	JJ.UU	۵,033	
	Formwork	3,816	sf	14.00	53,424	
	Re-bar, 4.5#/sf	8,586	lbs	1.20	10,303	
	Concrete material; 4,000 psi	87		135.00	11,745	
	Placing concrete	8 ₇	cy	65.00	5,655	
	<u>v</u>	2,862	cy sf	1.90	NIC	
	Dampproofing foundation wall and footing Insulation to foundation walls; 2" thick	1,908	sf	2.50	4,770	
	Form shelf		lf	8.00	3,816	
	Column footings, typical, 5' x 5' x 2'-0"	477	11	8.00	3,810	
	Excavation	4=6	077	20.00	9,120	
		456	cy			
	Store on site for reuse	456	cy	14.00	6,384	
	Backfill with new fill	363	cy	16.00	5,808	
	Remove surplus fill off site	93	cy	20.00	1,860	
	Formwork	1,920	sf	11.00	21,120	
	Re-bar	26,880	lbs	1.20	32,256	
	Concrete material; 3,000 psi	93	cy	125.00	11,625	
	Placing concrete	93	cy	55.00	5,115	
	Set anchor bolts grout plates	48	ea	150.00	7,200	
	Interior pilasters	,	~£	11.00	15 455	
	Formwork	1,405	sf	11.00	15,455	
	Re-bar	8,640	lbs	1.20	10,368	
	Concrete material; 3,000 psi	25	cy	125.00	3,125	
	Placing concrete	25	cy	55.00	1,375	
	Foundations against existing building	253	lf	180.00	45,540	010 700
	SUBTOTAL					316,729
A1020	SPECIAL FOUNDATIONS					
	No Work in this section					
	SUBTOTAL					
A1020	LOWEST FLOOR CONSTRUCTION					
111030	New Slab on grade, 5" thick					
	Structural gravel fill, 8"	509	cy	30.00	15,270	
	Base course, 8" gravel	509	cy	40.00	20,360	
	Rigid insulation	20,600	sf	2.25	46,350	
		_0,000	31	w.wJ	10,000	

20,600

23,690

 $\mathbf{s}\mathbf{f}$

sf

1.00

0.80

20,600

18,952



RENOVATIONS + ADDITIONS

Winchester, MA

58

60

70

72

73 74

75

76

77 78

79

81

83

85

87

89

90

91

93

94

95

97

98 99 100

101 102

103

104

105

106

107

108

109

110

111

Feasibility Design Estimate GFA 20,600

SI CODE	DESCRIPTION	QTY	UNIT	UNIT COST	EST'D COST	SUB TOTAL	TOTAL COST
RONT A	DDITION TO MURACO ES	<u></u>	•				
	Concrete - 5" thick	336	cy	125.00	42,000		
	Placing concrete	336	cy	45.00	15,120		
	Finishing and curing concrete	20,600	sf	4.00	82,400		
	Control joints - saw cut	20,600	sf	0.50	10,300		
	Miscellaneous						
	Dewatering	1	ea	5,000.00	5,000		
	SUBTOTAL					276,352	
	TOTAL - FOUNDATIONS						\$593,0

26-Sep-16

A20 BASEMENT CONSTRUCTION

A2010 BASEMENT EXCAVATION

No items in this section

SUBTOTAL

A2020 BASEMENT WALLS

No items in this section

SUBTOTAL

TOTAL - BASEMENT CONSTRUCTION

SUPERSTRUCTURE B10

B1010 FLOOR CONSTRUCTION

No Work in this section

SUBTOTAL

B1020 ROOF CONSTRUCTION

Roof Structure - Steel:

Steel beams/Joists; 13#/SF tns 3,800.00 509,200 134

Roof Structure

1-1/2" Metal floor Deck @ roof 20,600 sf 3.00 61,800

Miscellaneous

Exterior skin

Roof screen framing - allow NIC

Fire proofing to columns, beams and deck 4.00 82.400 20,600 sf

SUBTOTAL 653,400

13

134

lbs/sf

tns

TOTAL - SUPERSTRUCTURE \$653,400

EXTERIOR CLOSURE B20

B2010 EXTERIOR WALLS; 60% solid/40% glass 8,586 sf Interior skin 6" metal stud backup 8,586 7.50 64,395 sf 2.25 Batt insulation in stud 8,586 sf 19,319 2 1/2" Rigid Insulation 8,586 3.00 25,758 sf Air barrier 8,586 sf 6.00 51,516 Air barrier/flashing at windows 1,889 lf 7.00 13,223 Gypsum Sheathing 8,586 sf 2.75 23,612 Drywall lining to interior face of stud backup 8,586 sf 3.00 25,758

Winchester Schools Feasibility 9.26.16 Page 62 PMC - Project Management Cost



CSI

Feasibility Design Estimate GFA 20,600

UNIT

EST'D

SUB

26-Sep-16

TOTAL

CSI CODE	DESCRIPTION	QTY	UNIT	UNIT COST	EST'D COST	SUB TOTAL	TOTAL COST
	TION TO MURACO ES					<u>'</u>	
	Brick veneer; 75% of exterior wall	6,440	sf	35.00	225,400		
	Metal panels; 25% of exterior wall	2,146	sf	60.00	128,760		
	Miscellaneous						
	Staging to exterior wall	14,310	sf	3.00	42,930		
	SUBTOTAL					620,671	
B2020	WINDOWS	5,724	sf				
	Premium for sunscreen and light shelf elements	1	ls		NIC		
	Windows/storefront	5,724	sf	90.00	515,160		
	Backer rod & double sealant	1,889	lf	9.00	17,001		
	Wood blocking at openings	1,889	lf	4.00	7,556		
	SUBTOTAL					539,717	
Ranan	EXTERIOR DOORS						
D2030	Glazed entrance doors including frame and hardware; double door at corridor exit	2	pr	8,000.00	16,000		
	Backer rod & double sealant	40	lf	9.00	360		
	Wood blocking at openings	40	lf	4.00	160		
	SUBTOTAL	79		1.00	100	16,520	
						20,000	
	TOTAL - EXTERIOR CLOSURE						\$1,176,9
Взо	ROOFING						
D 30	ROOTEN						
B3010	ROOF COVERINGS Flat roofing						
	PVC roof membrane fully adhered	20,600	sf	14.00	288,400		
	Insulation	20,600	sf	7.00	144,200		
	1/2" dens-deck protection board	20,600	sf	2.00	41,200		
	Reinforced vapor barrier	20,600	sf	1.50	30,900		
	Rough blocking	1,908	lf	6.00	11,448		
	Miscellaneous Roofing						
	Roof screens - allow				NIC		
	Roof fascia/cornice	477	lf	25.00	11,925		
	SUBTOTAL					528,073	
Danas	DOOF OBENINGS						
В3020	ROOF OPENINGS Skylights, allow				NIC		
	Roof hatch				NIC		
	SUBTOTAL				NIC	_	
	SOLIOIAL					-	
	TOTAL - ROOFING						\$528,0
C10	INTERIOR CONSTRUCTION						
213							
C1010	PARTITIONS						
	Interior partitions	15,925	sf	15.55	247,634		
	Sealants & caulking at partitions	15,925	sf	0.50	7,963		
	Rough blocking to partitions	1,225	lf	3.00	3,675		
	Glazed partitions/borrowed lights - allowance	1	ls	5,000.00	5,000		
	SUBTOTAL					264,272	
C1020	INTERIOR DOORS						
01020	Doors, frames and hardware	20,600	sf	5.00	103,000		
	SUBTOTAL					103,000	



Feasibility Design Estimate GFA 20,600

	DESCRIPTION	QTY	UNIT	UNIT COST	EST'D COST	SUB TOTAL	TOTA COS
	TION TO MURACO ES						
C1030	SPECIALTIES / MILLWORK						
	Marker boards/tackboards in classroom	20,600	gfa	1.15	23,690		
	Toilet partitions and accessories	20,600	gfa	0.75	15,450		
	Room Signs	20,600	gfa	0.25	5,150		
	Wood paneling/benches/display cases etc.	20,600	gfa	1.50	30,900		
	Lockers	20,600	sf	1.00	20,600		
	Expansion joints	1	ls	2,000.00	2,000		
	Lockers	20,600	sf	1.00	20,600		
	Miscellaneous metals throughout building	20,600	sf	1.25	25,750		
	Miscellaneous sealants throughout building	20,600	sf	1.00	20,600		
	SUBTOTAL					164,740	
	TOTAL - INTERIOR CONSTRUCTION						\$53
C20	STAIRCASES						
C2010	STAIR CONSTRUCTION						
	No Work in this section						
	SUBTOTAL					-	
C2020	STAIR FINISHES						
	No Work in this section						
	SUBTOTAL					-	
	TOTAL - STAIRCASES						
Сзо	INTERIOR FINISHES						
Cooto	WALL FINISHES						
03010	Wall finishes	20,600	gfa	4.50	92,700		
	SUBTOTAL		Ü			92,700	
C3020	FLOOR FINISHES	_		40.00	0.47.000		
	Floor finishes	20,600	sf	12.00	247,200	0.47.000	
	SUBTOTAL					247,200	
C3030	CEILING FINISHES						
	Ceiling finishes	20,600	sf	6.00	123,600		
	SUBTOTAL					123,600	
	TOTAL - INTERIOR FINISHES						\$46
D10	CONVEYING SYSTEMS						
D1010	ELEVATOR	_					
21010	No Work in this section						
	SUBTOTAL					-	
	TOTAL - CONVEYING SYSTEMS						
D20	PLUMBING						
D20	PLUMBING, GENERALLY	_					
D20	Plumbing allowance	20,600	gsf	12.00	247,200		
	SUBTOTAL					247,200	
	TOTAL - PLUMBING						
1	IOIAL - FLUMDING						\$24



291

292

F10

SPECIAL CONSTRUCTION

Feasibility Design Estimate GFA 20,600

	CSI					UNIT	EST'D	SUB	TOTAL
	FRON	T ADDI	TION TO MURACO ES	QTY	UNIT	COST	COST	TOTAL	COST
232		D30	HVAC						
233				1					
234		D30	HVAC, GENERALLY	00 600	ggf	38.00	792 900		
236			HVAC complete system SUBTOTAL	20,600	gsf	38.00	782,800	782,800	
237			SOBIOTAL					702,000	
238			TOTAL - HVAC						\$782,800
239 240									
241		D40	FIRE PROTECTION						
242 243		D40	FIRE PROTECTION, GENERALLY						
244		240	Sprinkler system	20,600	gsf	4.50	92,700		
245			SUBTOTAL					92,700	
246 247	i		TOTAL - FIRE PROTECTION						ф
			TOTAL - FIRE PROTECTION						\$92,700
248 249									
250 251		D50	ELECTRICAL]					
252		D5010	COMPLETE ELECTRICAL SYSTEM						
253		Ü	Electrical system; complete	20,600	gsf	34.00	700,400		
254			SUBTOTAL		J			700,400	
255 256									
257			TOTAL - ELECTRICAL						\$700,400
258	ļ								., ,
259 260	ı		TO LUDWING TO	7					
261		E10	EQUIPMENT						
262		E10	EQUIPMENT, GENERALLY						
263	11500		Gym wall pads	1	ls	10,000.00	10,000		
264	11500		Basketball backstops; swing up; electric operated	2	ea	9,800.00	19,600		
265	11500		Gymnasium dividing net; electrically operated	1	loc	45,000.00	45,000		
266	11500		Volleyball net and standards	1	ea	2,000.00	2,000		
267 268	11500 11500		Telescoping bleachers	1	ls	25,000.00	25,000		
269	11970		Cubicle curtain & track at nurse area	1	loc	500.00	500		
270	11970		Platform curtains, rigging and controls	1	ls	35,000.00	35,000		
210			AV Equipment (including Smartboards, Projectors, LED monitors, Digital information displays etc.)				FF+E		
271			SUBTOTAL					137,100	
272									
273 274			TOTAL - EQUIPMENT						\$137,100
275									
276 277		E20	FURNISHINGS]					
278		E2010	FIXED FURNISHINGS						
279			Entry mats & frames - recessed with carpet/rubber strips	50	sf	45.00	2,250		
280			Manual operated roller shades	5,724	sf	6.00	34,344		
281			Counters, base cabinets, tall storage in classrooms and other rooms	20,600	gfa	4.00	82,400		
282			SUBTOTAL					118,994	
283 284		E2020	MOVABLE FURNISHINGS						
285		12020	All movable furnishings to be provided and installed by owner						
286			SUBTOTAL					NIC	
287 288	ĺ		TOTAL - FURNISHINGS						\$118,994
289	ļ								,,,,,
290				-					



305 306

307

308

309 310 Winchester Schools RENOVATIONS + ADDITIONS Winchester, MA

Winchester, MA

 Feasibility Design Estimate
 GFA
 20,600

 CSI
 UNIT
 EST'D
 SUB
 TOTAL

26-Sep-16

CODE		DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST
FRON	T ADDI	TION TO MURACO ES			•		•	
	F10	SPECIAL CONSTRUCTION						
		No Work in this section SUBTOTAL						
		TOTAL - SPECIAL CONSTRUCTION						
			1					
	F20	SELECTIVE BUILDING DEMOLITION						
	F2010	BUILDING ELEMENTS DEMOLITION						
		Demolish existing exterior wall	6,325	sf	15.00	94,875		
		SUBTOTAL					94,875	

F2020 HAZARDOUS COMPONENTS ABATEMENT None Included

SUBTOTAL

TOTAL - SELECTIVE BUILDING DEMOLITION \$94,875



Winchester Schools RENOVATIONS + ADDITIONS

Winchester, MA

Feasibility Design Estimate GFA 76,730

		CONSTRUCTI	ON COST SUMM	ARY		
	BUILDING		SUB-TOTAL	TOTAL	\$/SF	%
NEW SC		Γ MURACO ES 2				
A10		DATIONS				
	A1010	Standard Foundations	\$614,098			
	A1020	Special Foundations	\$0			
	A1030	Lowest Floor Construction	\$729,491	\$1,343,589	\$17.51	6.8%
A20	BASEM	IENT CONSTRUCTION				
	A2010	Basement Excavation	\$0			
	A2020	Basement Walls	\$0	\$0	\$0.00	0.0%
B10	SUPER	STRUCTURE				
	B1010	Upper Floor Construction	\$1,050,175			
	B1020	Roof Construction	\$1,570,812	\$2,620,987	\$34.16	13.3%
B20	EXTER	IOR CLOSURE				
	B2010	Exterior Walls	\$1,527,916			
	B2020	Windows	\$1,276,504			
	B2030	Exterior Doors	\$43,040	\$2,847,460	\$37.11	14.5%
В30	ROOFI	NG				
230	B3010	Roof Coverings	\$1,298,906			
	B3020	Roof Openings	\$5,000	\$1,303,906	\$16.99	6.6%
C10	INTER	IOR CONSTRUCTION				
010	C1010	Partitions	\$1,534,600			
	C1020	Interior Doors	\$383,650			
	C1030	Specialties/Millwork	\$529,439	\$2,447,689	\$31.90	12.4%
C20	STAIR	CASES				
C _ C	C2010	Stair Construction	\$78,000			
	C2020	Stair Finishes	\$20,550	\$98,550	\$1.28	0.5%
C30	INTER	IOR FINISHES				
2,00	C3010	Wall Finishes	\$345,285			
	C3020	Floor Finishes	\$537,110			
	C3030	Ceiling Finishes	\$460,380	\$1,342,775	\$17.50	6.8%
D10	CONVE	YING SYSTEMS				
	D1010	Elevator	\$100,000	\$100,000	\$1.30	0.5%
D20	PLUME	RING				
<i>D2</i> 0	D20	Plumbing	\$920,760	\$920,760	\$12.00	4.7%



Feasibility Design Estimate GFA 76,730

		CONSTRUCTION				
	BUILDING		SUB-TOTAL	TOTAL	\$/SF	%
W SCI	HOOL AT	T MURACO ES 2				
D30	HVAC					
	D30	HVAC	\$2,915,740	\$2,915,740	\$38.00	14.8%
D40	FIRE PI	ROTECTION				
	D40	Fire Protection	\$345,285	\$345,285	\$4.50	1.8%
D50	ELECTI	RICAL				
	D5010	Complete System	\$2,608,820	\$2,608,820	\$34.00	13.3%
E10	EQUIP	MENT				
	E10 Equipment		\$396,100	\$396,100	\$5.16	2.0%
E20	FURNIS	SHINGS				
	E2010	Fixed Furnishings	\$392,648			
	E2020	Movable Furnishings	NIC	\$392,648	\$5.12	2.0%
F10	SPECIA	L CONSTRUCTION				
	F10	Special Construction	\$0	\$0	\$0.00	0.0%
F20	HAZMA	AT REMOVALS				
	F2010	Building Elements Demolition	\$0			
	F2020	Hazardous Components Abatement	\$0	\$0	\$0.00	0.0%
TOTA	I DIDE	CT COST (Trade Costs)		\$19,684,309	\$256.54	100.0%



Vapor barrier

Mesh reinforcing 15% lap

Winchester Schools RENOVATIONS + ADDITIONS Winchester, MA

Feasibility Design Estimate GFA 76,730

26-Sep-16

CSI				UNIT	EST'D	SUB	TOTAL
CODE	DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST
NEW	SCHOOL AT MURACO ES o						

I DDE	DESCRIPTION	QTY	UNIT	UNIT COST	EST'D COST	SUB TOTAL	TOTAI COST
	L AT MURACO ES 2	QII	UNII	031	cosi	IOIAL	
GROSS	FLOOR AREA CALCULATION]					
	First Floor			48,916			
	Second Floor			27,814			
	Second Floor			27,014			
	TOTAL GROSS FLOOR AREA (GFA)				76,730	sf	
A10	FOUNDATIONS	1					
		•					
A1010	STANDARD FOUNDATIONS Strip footings - 2'-0" x 1'-0"						
	Excavation	1,329	сy	20.00	26,580		
	Store on site for reuse	1,329	сy	14.00	18,606		
	Backfill with existing fill	1,236	сy	16.00	19,776		
	Remove surplus fill off site	93	су	25.00	2,325		
	Formwork	2,392	sf	12.00	28,704		
	Re-bar, 10#/lf	11,960	lbs	1.20	14,352		
	Concrete material; 3,000 psi	93	cy	125.00	11,625		
	Placing concrete	93	cy	55.00	5,115		
	Foundation walls at exterior - 14" thick						
	Formwork	9,568	sf	14.00	133,952		
	Re-bar, 4.5#/sf	21,528	lbs	1.20	25,834		
	Concrete material; 4,000 psi	218	cy	135.00	29,430		
	Placing concrete	218	cy	65.00	14,170		
	Dampproofing foundation wall and footing	7,176	sf	1.90	NIC		
	Insulation to foundation walls; 2" thick	4,784	sf	2.50	11,960		
	Form shelf	1,196	lf	8.00	9,568		
	Column footings, typical, 6' x 6' x 2'-0"						
	Excavation	998	cy	20.00	19,960		
	Store on site for reuse	998	cy	14.00	13,972		
	Backfill with new fill	760	cy	16.00	12,160		
	Remove surplus fill off site	238	cy	20.00	4,760		
	Formwork	4,080	sf	11.00	44,880		
	Re-bar	47,600	lbs	1.20	57,120		
	Concrete material; 3,000 psi	238	cy	125.00	29,750		
	Placing concrete	238	cy	55.00	13,090		
	Set anchor bolts grout plates	85	ea	150.00	12,750		
	<u>Interior pilasters</u> Formwork	0.490	2.0	11.00	97 970		
	Re-bar	2,489	sf	11.00 1.20	27,379		
		15,300	lbs	125.00	18,360 5,500		
	Concrete material; 3,000 psi Placing concrete	44	cy	55.00	2,420		
	SUBTOTAL	44	cy	33.00	۵,420	614,098	
	SOPIOTIL					014,000	
A1020	SPECIAL FOUNDATIONS						
	No Work in this section						
	SUBTOTAL						
A1030	LOWEST FLOOR CONSTRUCTION						
	New Slab on grade, 5" thick						
	Structural gravel fill, 8"	1,208	cy	30.00	36,240		
	Base course, 8" gravel	1,208	cy	40.00	48,320		
	Rigid insulation	48,916	sf	2.25	110,061		
	37 1 .	-0	C	1.00	40.010		

48,916

56,253

sf

sf

1.00

0.80

48,916

45,002



Winchester Schools RENOVATIONS + ADDITIONS Winchester, MA

Feasibility Design Estimate GFA 76,730

CSI CODE	DESCRIPTION	QTY	UNIT	UNIT COST	EST'D COST	SUB TOTAL	TOTAL COST
NEW SCH	HOOL AT MURACO ES 2						
	Concrete - 5" thick	799	cy	125.00	99,875		
	Placing concrete	799	cy	45.00	35,955		
	Finishing and curing concrete	48,916	sf	4.00	195,664		
	Control joints - saw cut	48,916	sf	0.50	24,458		
	<u>Miscellaneous</u>						
	Backfill existing foundations/basement	1	ea	50,000.00	50,000		
	Elevator pit	1	ea	30,000.00	30,000		
	Dewatering	1	ea	5,000.00	5,000		
	SUBTOTAL					729,491	

TOTAL - FOUNDATIONS \$1,343,589

26-Sep-16

A20 BASEMENT CONSTRUCTION

A2010 BASEMENT EXCAVATION

No items in this section

SUBTOTAL -

A2020 BASEMENT WALLS

No items in this section

SUBTOTAL -

TOTAL - BASEMENT CONSTRUCTION

B10	SUPERSTRUCTURE	7				
Бю	SCIERSIRCCICRE	8	lbs/sf			
B1010	FLOOR CONSTRUCTION	318	tns			
	Floor Structure - Steel:					
	Steel beams and columns; 13/SF	181	tns	3,500.00	633,500	
	Shear studs	5,563	ea	2.50	13,908	
	Floor Structure					
	2" Metal floor Deck	27,814	sf	4.20	116,819	
	WWF reinforcement	31,986	sf	0.80	25,589	
	Concrete Fill to metal deck; 5" normal weight	443	сy	125.00	55,375	
	Place and finish concrete	27,814	sf	2.00	55,628	
	Misc. perimeter angles	1,196	lf	25.00	29,900	
	<u>Miscellaneous</u>					
	Barrier one at slab	443	cy	65.00	28,795	
	Fire proofing to columns and beams	27,814	sf	2.90	80,661	
	Fire stopping floors	2	flrs	5,000.00	10,000	
	SUBTOTAL					1,050,175
B1020	ROOF CONSTRUCTION					
	Roof Structure - Steel:					
	Steel beams/Joists; 13#/SF	318	tns	3,800.00	1,208,400	
	Roof Structure					
	1-1/2" Metal floor Deck @ roof	48,916	sf	3.00	146,748	
	<u>Miscellaneous</u>					
	Roof screen framing - allow	1	ls	20,000.00	20,000	
	Fire proofing to columns, beams and deck	48,916	sf	4.00	195,664	
	SUBTOTAL					1,570,812



Winchester Schools RENOVATIONS + ADDITIONS Winchester, MA

Feasibility Design Estimate GFA 76,730

26-Sep-16

CSI				UNIT	EST'D	SUB	TOTAL
CODE	DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST
NEW	SCHOOL AT MURACO ES 2						

110 TOTAL - SUPERSTRUCTURE \$2,620,987 111 112 113 EXTERIOR CLOSURE B20 114 B2010 EXTERIOR WALLS; 60% solid/40% glass 115 20,306 sf 116 Interior skin 117 6" metal stud backup 7.50 152,295 20,306 sf 118 Batt insulation in stud 20,306 sf 2.25 45,689 119 2 1/2" Rigid Insulation 3.00 60,918 20,306 sf 120 Air barrier 20,306 sf 6.00 121,836 121 7.00 Air barrier/flashing at windows 4,468 lf 31,276 122 Gypsum Sheathing 20,306 sf 2.75 55,842 123 Drywall lining to interior face of stud backup 20,306 sf 3.00 60,918 124 Exterior skin 125 35.00 533,050 Brick veneer; 75% of exterior wall sf 15,230 126 Metal panels; 25% of exterior wall 60.00 304,560 5,076 sf 127 Miscellaneous 128 60,000.00 Roof screens - allow ls 60,000 129 101,532 Staging to exterior wall 33,844 sf 3.00 130 SUBTOTAL 1,527,916 131 132 B2020 WINDOWS 13,538 sf 133 Premium for sunscreen and light shelf elements ls NIC 134 Windows/storefront 13,538 sf 90.00 1,218,420 135 Backer rod & double sealant 4,468 lf 9.00 40,212 136 Wood blocking at openings 4,468 lf 4.00 17,872 137 SUBTOTAL 1,276,504 138 139 **B2030 EXTERIOR DOORS** 140 Glazed entrance doors including frame and hardware; 8,000.00 32,000 pr double door at corridor exit 141 Other doors 10,000.00 10,000 1 ls 142 Backer rod & double sealant lf 9.00 720 80 143 Wood blocking at openings lf 4.00 320 80 144 SUBTOTAL 43,040 145 146 TOTAL - EXTERIOR CLOSURE \$2,847,460 147 148 149 150 151 152

B30	ROOFING]				
B3010	ROOF COVERINGS Flat roofing					
	PVC roof membrane fully adhered	48,916	sf	14.00	684,824	
	Insulation	48,916	sf	7.00	342,412	
	1/2" dens-deck protection board	48,916	sf	2.00	97,832	
	Reinforced vapor barrier	48,916	sf	1.50	73,374	
	Rough blocking	4,784	lf	6.00	28,704	
	Miscellaneous Roofing					
	Roof screens - allow				NIC	
	Roof fascia/cornice	1,196	lf	60.00	71,760	
	SUBTOTAL					1,298,906
B3020	ROOF OPENINGS					
	Skylights, allow				NIC	
	Roof hatch	1	ea	5,000.00	5,000	



Feasibility Design Estimate GFA 76,730

26-Sep-16

_			n Estimate					GFA	70,730
	CSI CODE		DESCRIPTION	QTY	UNIT	UNIT COST	EST'D COST	SUB TOTAL	TOTAL COST
	NEW	SCHOOL	L AT MURACO ES 2						
66			SUBTOTAL					5,000	
167 168			TOTAL - ROOFING						\$1,303,906
69									
70 71		C10	INTERIOR CONSTRUCTION	٦					
72		CIO	INTERIOR CONSTRUCTION						
73		C1010	PARTITIONS						
74			Allowance for interior walls/glazed partitions etc.	76,730	gfa	20.00	1,534,600	4.504.000	
75 76			SUBTOTAL					1,534,600	
77		C1020	INTERIOR DOORS						
78			Interior doors, frames and hardware	76,730	gfa	5.00	383,650		
79 80			SUBTOTAL					383,650	
81		C1030	SPECIALTIES / MILLWORK						
82			Marker boards/tackboards in classroom	76,730	gfa	1.15	88,240		
83			Toilet partitions and accessories	76,730	gfa	0.75	57,548		
84			Room Signs	76,730	gfa	0.25	19,183		
85			Wood paneling/benches/display cases etc.	76,730	gfa	1.50	115,095		
86			Lockers	76,730	sf	1.00	76,730		
87			Miscellaneous metals throughout building	76,730	sf	1.25	95,913		
88			Miscellaneous sealants throughout building	76,730	sf	1.00	76,730		
89			SUBTOTAL					529,439	
90 91			TOTAL - INTERIOR CONSTRUCTION						\$2,447,689
92			TOTAL INTERIOR CONSTRUCTION						Ψ=,44/,009
93 94		Coo	CTAIDCACEC	7					
95		C20	STAIRCASES						
96		C2010	STAIR CONSTRUCTION						
97	55100		Metal pan stair; egress stair	3	flt	24,000.00	72,000		
98	33000		Concrete fill to stairs	3	flt	2,000.00	6,000		
99			SUBTOTAL					78,000	
00 01		C2020	STAIR FINISHES						
02	90009	02020	High performance coating to stairs including all railings etc.	3	flt	3,000.00	9,000		
03	90006		Rubber tile at stairs - landings	330	sf	12.00	3,960		
:04	90006		Rubber tile at stairs - treads & risers	345	lft	22.00	7,590		
:05			SUBTOTAL					20,550	
:06 :07			TOTAL - STAIRCASES						\$98,550
08									.,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,
:09 :10		Coo	INTERIOR FINISHES	7					
11		<i>C</i> 30	INTERIOR FINISHES						
12		С3010	WALL FINISHES	-6	.6	4.50	045.005		
14			Wall finishes SUBTOTAL	76,730	gfa	4.50	345,285	245 205	
:15			SUBTUTAL					345,285	
216		C3020	FLOOR FINISHES						
17			Floor finishes	76,730	sf	7.00	537,110		
18			SUBTOTAL					537,110	
20		C3030	CEILING FINISHES						
21			Ceiling finishes	76,730	sf	6.00	460,380		
222			SUBTOTAL					460,380	
223 224			TOTAL - INTERIOR FINISHES						\$1,342,775
25		L							, ,54-,7/3



288

10999

cafeteria

Feasibility Design Estimate GFA 76,730

26-Sep-16

CSI					UNIT	EST'D	SUB	TOTAL
NEW	SCHOO	DESCRIPTION L AT MURACO ES 2	QTY	UNIT	COST	COST	TOTAL	COST
11211	D10	CONVEYING SYSTEMS	\neg					
93000	D1010	ELEVATOR Passenger elevator; 2 stop, 3500 lbs	1	ea	100,000.00	100,000		
		SUBTOTAL	1	ea	100,000.00	100,000	100,000	
		SUBTUTAL					100,000	
		TOTAL - CONVEYING SYSTEMS						\$100,00
	D20	PLUMBING						
	D20	PLUMBING, GENERALLY						
	220	Plumbing allowance	76,730	gsf	12.00	920,760		
		SUBTOTAL					920,760	
		TOTAL - PLUMBING						\$000 5 6
		TOTAL - I LUMBING						\$920,76
	Dag	INVAC	_					
	D30	HVAC	_					
	D30	HVAC, GENERALLY						
		HVAC complete system	76,730	gsf	38.00	2,915,740		
		SUBTOTAL					2,915,740	
		TOTAL - HVAC						\$2,915,74
	D40	FIRE PROTECTION						
	D40	FIRE PROTECTION, GENERALLY						
	<i>D</i> 40	Sprinkler system	76,730	gsf	4.50	345,285		
		SUBTOTAL					345,285	
		TOTAL - FIRE PROTECTION						#0.4 = 00
		TOTAL - TIKE PROTECTION						\$345,28
	D50	ELECTRICAL						
	D5010	COMPLETE ELECTRICAL SYSTEM						
	Ü	Electrical system; complete	76,730	gsf	34.00	2,608,820		
		SUBTOTAL		_			2,608,820	
		TOTAL - ELECTRICAL						\$2,608,82
	E10	EQUIPMENT						
	E10	EQUIPMENT, GENERALLY						
11500	LIO	Gym wall pads	1	ls	10,000.00	10,000		
11500		Basketball backstops; swing up; electric operated	2	ea	9,800.00	19,600		
11500		Gymnasium dividing net; electrically operated	1	loc	45,000.00	45,000		
11500		Volleyball net and standards	1	ea	2,000.00	2,000		
11500		Telescoping bleachers	1	ls	25,000.00	25,000		
11500		Cubicle curtain & track at nurse area	1	loc	500.00	500		
11970		Platform curtains, rigging and controls	1	ls	35,000.00	35,000		
		AV Equipment at Café/Gym/ Learning				F,F&E		
11400		Food Service equipment	1	ls	225,000.00	225,000		
11500		Allowance for loading dock equipment	1	ls	10,000.00	10,000		
11400		Refrigerator/Freezer	1	ea	1,000.00	1,000		
11400		Kiln	1	ea	3,000.00	3,000		

Electrically operated projection screens in gym &

2 loc 10,000.00

20,000



RENOVATIONS + ADDITIONS

Feasibility Design Estimate

Winchester, MA

290

291 292

293 295

296 297

298

300

301

302 303

304

305

306 307

308 309 310

311 312

313

314

315 316

317 318 319

321

322

323 324

325

326

327 328

UNIT EST'D SUB TOTAL CODE DESCRIPTION QTY UNIT TOTAL

NEW SCHOOL AT MURACO ES 2

AV Equipment (including Smartboards, Projectors, LED monitors, Digital information displays etc.)

SUBTOTAL

TOTAL - EQUIPMENT \$396,100

26-Sep-16

76.730

GFA

396,100

FF+E

E20 FURNISHINGS

E2010 FIXED FURNISHINGS

Entry mats & frames - recessed with carpet/rubber 100 45.00 4,500 strips Manual operated roller shades 6.00 81,228 13,538 sf Counters, base cabinets, tall storage in classrooms 4.00 306,920 76,730 gfa

and other rooms

SUBTOTAL 392,648

E2020 MOVABLE FURNISHINGS

All movable furnishings to be provided and installed

by owner

SUBTOTAL NIC

TOTAL - FURNISHINGS \$392,648

SPECIAL CONSTRUCTION F10

SPECIAL CONSTRUCTION F10

No Work in this section

SUBTOTAL

TOTAL - SPECIAL CONSTRUCTION

F20 SELECTIVE BUILDING DEMOLITION

F2010 BUILDING ELEMENTS DEMOLITION

SUBTOTAL

F2020 HAZARDOUS COMPONENTS ABATEMENT

None Included

SUBTOTAL

TOTAL - SELECTIVE BUILDING DEMOLITION



Winchester Schools RENOVATIONS + ADDITIONS

Winchester, MA

Feasibility Design Estimate GFA 149,350

		CONSTRUCT	ION COST SUMM	ARY		
NIEWAY CO	BUILDING		SUB-TOTAL	TOTAL	\$/SF	%
		Г MURACO ES 4a				
A10		DATIONS				
	A1010	Standard Foundations	\$925,558			
	A1020	Special Foundations	\$0			
	A1030	Lowest Floor Construction	\$1,333,747	\$2,259,305	\$15.13	6.0%
A20	BASEM	IENT CONSTRUCTION				
	A2010	Basement Excavation	\$0			
	A2020	Basement Walls	\$0	\$0	\$0.00	0.0%
В10	SUPER	STRUCTURE				
	B1010	Upper Floor Construction	\$2,040,410			
	B1020	Roof Construction	\$3,044,239	\$5,084,649	\$34.05	13.5%
B20	EXTER	IOR CLOSURE				
	B2010	Exterior Walls	\$3,020,741			
	B2020	Windows	\$2,539,707			
	B2030	Exterior Doors	\$64,560	\$5,625,008	\$37.66	15.0%
В30	ROOFI	NG				
-0-	B3010	Roof Coverings	\$2,484,997			
	B3020	Roof Openings	\$5,000	\$2,489,997	\$16.67	6.6%
C10	INTER	IOR CONSTRUCTION				
	C1010	Partitions	\$2,987,000			
	C1020	Interior Doors	\$746,750			
	C1030	Specialties/Millwork	\$1,030,517	\$4,764,267	\$31.90	12.7%
C20	STAIR	CASES				
	C2010	Stair Construction	\$130,000			
	C2020	Stair Finishes	\$34,250	\$164,250	\$1.10	0.4%
С30	INTER	IOR FINISHES				
- 0 -	C3010	Wall Finishes	\$672,075			
	C3020	Floor Finishes	\$1,045,450			
	C3030	Ceiling Finishes	\$896,100	\$2,613,625	\$17.50	7.0%
D10	CONVE	YING SYSTEMS				
	D1010	Elevator	\$100,000	\$100,000	\$0.67	0.3%
D20	PLUME	BING				
2=0	D20	Plumbing	\$1,792,200	\$1,792,200	\$12.00	4.8%



Feasibility Design Estimate GFA 149,350

		CONSTRUCTION				
	BUILDING		SUB-TOTAL	TOTAL	\$/SF	%
W SCI	HOOL AT	「MURACO ES 4a				
D30	HVAC					
	D30	HVAC	\$5,675,300	\$5,675,300	\$38.00	15.1%
D40	FIRE PI	ROTECTION				
	D40	Fire Protection	\$672,075	\$672,075	\$4.50	1.8%
D50	ELECTI	RICAL				
	D5010	Complete System	\$5,077,900	\$5,077,900	\$34.00	13.5%
E10	EQUIP	MENT				
	E10	Equipment	\$521,100	\$521,100	\$3.49	1.4%
E20	FURNIS	SHINGS				
	E2010	Fixed Furnishings	\$763,510			
	E2020	Movable Furnishings	NIC	\$763,510	\$5.11	2.0%
F10	SPECIA	L CONSTRUCTION				
	F10	Special Construction	\$0	\$0	\$0.00	0.0%
F20	HAZMA	AT REMOVALS				
	F2010	Building Elements Demolition	\$0			
	F2020	Hazardous Components Abatement	\$0	\$0	\$0.00	0.0%
		CT COST (Trade Costs)		\$37,603,186	\$251.78	100.0%



52

53

54

55

Feasibility Design Estimate GFA 149,350

26-Sep-16

CODE	DESCRIPTION	OTY	UNIT	COST	COST	TOTAL	COST
	DISCRIPTION	VII.	01111	cosi	CODI	TOTAL	COSI

	DESCRIPTION	QTY	UNIT	UNIT COST	EST'D COST	SUB TOTAL	TOTAL COST
SCHOOL	L AT MURACO ES 4a						
GROSS	FLOOR AREA CALCULATION]					
	First Floor			94,777			
	Second Floor			54,573			
	TOTAL GROSS FLOOR AREA (GFA)				140.050	ef	
	TOTAL GROSS FLOOR AREA (GFA)				149,350	sf	
A10	FOUNDATIONS]					
A1010	STANDARD FOUNDATIONS Strip footings - 2'-0" x 1'-0"						
	Excavation	2,156	cy	20.00	43,120		
	Store on site for reuse	2,156	cy	14.00	30,184		
	Backfill with existing fill	2,005	cy	16.00	32,080		
	Remove surplus fill off site	151	cy	25.00	3,775		
	Formwork	3,880	sf	12.00	46,560		
	Re-bar, 10#/lf	19,400	lbs	1.20	23,280		
	Concrete material; 3,000 psi	151	cy	125.00	18,875		
	Placing concrete	151	cy	55.00	8,305		
	Foundation walls at exterior - 14" thick						
	Formwork	15,520	sf	14.00	217,280		
	Re-bar, 4.5#/sf	34,920	lbs	1.20	41,904		
	Concrete material; 4,000 psi	353	cy	135.00	47,655		
	Placing concrete	353	cy	65.00	22,945		
	Dampproofing foundation wall and footing	11,640	sf	1.90	NIC		
	Insulation to foundation walls; 2" thick	7,760	sf	2.50	19,400		
	Form shelf	1,940	lf	8.00	15,520		
	Column footings, typical, 6' x 6' x 2'-0"	,,					
	Excavation	1,350	сy	20.00	27,000		
	Store on site for reuse	1,350	су	14.00	18,900		
	Backfill with new fill	1,028	сy	16.00	16,448		
	Remove surplus fill off site	322	су	20.00	6,440		
	Formwork	5,520	sf	11.00	60,720		
	Re-bar	64,400	lbs	1.20	77,280		
	Concrete material; 3,000 psi	322	су	125.00	40,250		
	Placing concrete	322	cy	55.00	17,710		
	Set anchor bolts grout plates	115	ea	150.00	17,250		
	Interior pilasters	9					
	Formwork	3,367	sf	11.00	37,037		
	Re-bar	20,700	lbs	1.20	24,840		
	Concrete material; 3,000 psi	60	су	125.00	7,500		
	Placing concrete	60	сy	55.00	3,300		
	SUBTOTAL		J			925,558	
A1020	SPECIAL FOUNDATIONS						
	No Work in this section SUBTOTAL						
A1030	LOWEST FLOOR CONSTRUCTION						
	New Slab on grade, 5" thick						
	G			00.00	70.000		

2,341

2,341

94,777

94,777

108,994

cy

cy

sf

sf

sf

30.00

40.00

2.25

1.00

0.80

70,230

93,640

213,248

94,777

87,195

Structural gravel fill, 8"

Base course, 8" gravel

Mesh reinforcing 15% lap

Rigid insulation

Vapor barrier



Feasibility Design Estimate GFA 149,350

CSI				UNIT	EST'D	SUB	TOTAL
CODE	DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST
NEW S	SCHOOL AT MURACO ES 4a						
	Concrete - 5" thick	1,548	cy	125.00	193,500		
	Placing concrete	1,548	cy	45.00	69,660		
	Finishing and curing concrete	94,777	sf	4.00	379,108		
	Control joints - saw cut	94,777	sf	0.50	47,389		
	<u>Miscellaneous</u>						
	Backfill existing foundations/basement	1	ea	50,000.00	50,000		
	Elevator pit	1	ea	30,000.00	30,000		
	Dewatering	1	ea	5,000.00	5,000		
	SUBTOTAL					1,333,747	

TOTAL - FOUNDATIONS \$2,259,305

26-Sep-16

A20 BASEMENT CONSTRUCTION

A2010 BASEMENT EXCAVATION

No items in this section

SUBTOTAL

A2020 BASEMENT WALLS

No items in this section

SUBTOTAL

TOTAL - BASEMENT CONSTRUCTION

В10	SUPERSTRUCTURE	1				
		8	lbs/sf			
B1010	FLOOR CONSTRUCTION	616	tns			
	Floor Structure - Steel:					
	Steel beams and columns; 13/SF	355	tns	3,500.00	1,242,500	
	Shear studs	10,915	ea	2.50	27,288	
	Floor Structure					
	2" Metal floor Deck	54,573	sf	4.20	229,207	
	WWF reinforcement	62,759	sf	0.80	50,207	
	Concrete Fill to metal deck; 5" normal weight	870	cy	125.00	108,750	
	Place and finish concrete	54,573	sf	2.00	109,146	
	Misc. perimeter angles	1,940	lf	25.00	48,500	
	Miscellaneous					
	Barrier one at slab	870	cy	65.00	56,550	
	Fire proofing to columns and beams	54,573	sf	2.90	158,262	
	Fire stopping floors	2	flrs	5,000.00	10,000	
	SUBTOTAL					2,040,410
B1020	ROOF CONSTRUCTION					
21020	Roof Structure - Steel:					
	Steel beams/Joists; 13#/SF	616	tns	3,800.00	2,340,800	
	Roof Structure			·	, ,	
	1-1/2" Metal floor Deck @ roof	94,777	sf	3.00	284,331	
	<u>Miscellaneous</u>					
	Roof screen framing - allow	1	ls	40,000.00	40,000	
	Fire proofing to columns, beams and deck	94,777	sf	4.00	379,108	
	SUBTOTAL					3,044,239



Winchester Schools RENOVATIONS + ADDITIONS Winchester, MA

Feasibility Design Estimate GFA 149,350

26-Sep-16

CSI				UNIT	EST'D	SUB	TOTAL
CODE	DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST

NEW SCHOOL AT MURACO ES 4a 110 TOTAL - SUPERSTRUCTURE \$5,084,649 111 112 113 EXTERIOR CLOSURE B20 114 B2010 EXTERIOR WALLS; 60% solid/40% glass 115 40,403 sf 116 Interior skin 117 6" metal stud backup 7.50 303,023 sf 40,403 118 Batt insulation in stud 40,403 sf 2.25 90,907 119 2 1/2" Rigid Insulation 3.00 121,209 sf 40,403 120 Air barrier 40,403 sf 6.00 242,418 121 Air barrier/flashing at windows 8,889 lf 7.00 62,223 122 Gypsum Sheathing 40,403 sf 2.75 111,108 123 121,209 Drywall lining to interior face of stud backup 3.00 40,403 sf 124 Exterior skin 125 1,060,570 Brick veneer; 75% of exterior wall 35.00 sf 30,302 126 Metal panels; 25% of exterior wall 60.00 606,060 10,101 sf 127 Miscellaneous 128 100,000.00 100,000 Roof screens - allow ls 129 67,338 202,014 Staging to exterior wall sf 3.00 130 SUBTOTAL 3,020,741 131 132 B2020 WINDOWS 26,935 sf 133 Premium for sunscreen and light shelf elements ls NIC 134 Windows/storefront sf 90.00 2,424,150 26,935 135 Backer rod & double sealant 8,889 lf 9.00 80,001 136 Wood blocking at openings 8,889 lf 4.00 35,556 137 SUBTOTAL 2,539,707 138 139 **B2030 EXTERIOR DOORS** 140 Glazed entrance doors including frame and hardware; 8,000.00 48,000 pr double door at corridor exit 141 Other doors 15,000.00 15,000 1 ls 142 Backer rod & double sealant lf 9.00 1,080 120 143 Wood blocking at openings lf 4.00 120 480 144 SUBTOTAL 64,560 145 146 TOTAL - EXTERIOR CLOSURE \$5,625,008 147

Взо	ROOFING	7				
<i>B</i> 30	ROOFING	_				
B3010	ROOF COVERINGS Flat roofing					
	PVC roof membrane fully adhered	94,777	sf	14.00	1,326,878	
	Insulation	94,777	sf	7.00	663,439	
	1/2" dens-deck protection board	94,777	sf	2.00	189,554	
	Reinforced vapor barrier	94,777	sf	1.50	142,166	
	Rough blocking	7,760	lf	6.00	46,560	
	Miscellaneous Roofing					
	Roof screens - allow				NIC	
	Roof fascia/cornice	1,940	lf	60.00	116,400	
	SUBTOTAL					2,484,997
B3020	ROOF OPENINGS					
	Skylights, allow				NIC	
	Roof hatch	1	ea	5,000.00	5,000	
		1	ea	5,000.00		



Feasibility Design Estimate GFA 149,350

26-Sep-16

_		int, Desig	n Estimate					GFA	149,330
(CSI CODE		DESCRIPTION	QTY	UNIT	UNIT COST	EST'D COST	SUB TOTAL	TOTAL COST
	NEW	SCHOO	L AT MURACO ES 4a						
166 167			SUBTOTAL					5,000	
168			TOTAL - ROOFING						\$2,489,997
69									
70 71		C10	INTERIOR CONSTRUCTION	\neg					
72		C10	INTERIOR CONSTRUCTION						
73		C1010	PARTITIONS						
74			Allowance for interior walls/glazed partitions etc.	149,350	gfa	20.00	2,987,000		
75 76			SUBTOTAL					2,987,000	
177		C1020	INTERIOR DOORS						
78			Interior doors, frames and hardware	149,350	gfa	5.00	746,750		
79			SUBTOTAL					746,750	
80 81		C1030	SPECIALTIES / MILLWORK						
82			Marker boards/tackboards in classroom	149,350	gfa	1.15	171,753		
83			Toilet partitions and accessories		_	0.75	112,013		
84			Room Signs	149,350 149,350	gfa gfa	0.75	37,338		
85			Wood paneling/benches/display cases etc.	149,350	gfa	1.50	224,025		
86			Lockers	149,350	sf	1.00	149,350		
87			Miscellaneous metals throughout building	149,350	sf	1.25	186,688		
88			Miscellaneous sealants throughout building	149,350	sf	1.00	149,350		
89			SUBTOTAL	,				1,030,517	
90			TOTAL INTERIOR CONCERNICATION						.
91 92			TOTAL - INTERIOR CONSTRUCTION						\$4,764,267
93				_					
94		C20	STAIRCASES						
95 96		C2010	STAIR CONSTRUCTION						
97 5	55100		Metal pan stair; egress stair	5	flt	24,000.00	120,000		
98 3	33000		Concrete fill to stairs	5	flt	2,000.00	10,000		
99			SUBTOTAL					130,000	
:00 :01		Canan	OTAID FINIGHES						
	90009	C2020	STAIR FINISHES High performance coating to stairs including all railings etc.	5	flt	3,000.00	15,000		
203 9	90006		Rubber tile at stairs - landings	550	sf	12.00	6,600		
204 9	90006		Rubber tile at stairs - treads & risers	575	lft	22.00	12,650		
205			SUBTOTAL					34,250	
206 207			TOTAL CTAIDCAGES						0164.0==
208			TOTAL - STAIRCASES						\$164,250
209				_					
210 211		Сзо	INTERIOR FINISHES						
212		C3010	WALL FINISHES						
213			Wall finishes	149,350	gfa	4.50	672,075		
14			SUBTOTAL					672,075	
215 216		Canan	FLOOR FINISHES						
:17		0,020	Floor finishes	149,350	sf	7.00	1,045,450		
218			SUBTOTAL					1,045,450	
19		0	CENTING EINHOUSE						
20		C3030	CEILING FINISHES Ceiling finishes	149,350	sf	6.00	896,100		
222			SUBTOTAL	-4 3,330	91	0.00	550,100	896,100	
223									
224			TOTAL - INTERIOR FINISHES						\$2,613,625
25									



285

286

287

288

11500

11400

11400

10999

Allowance for loading dock equipment

Electrically operated projection screens in gym &

Refrigerator/Freezer

Kiln

cafeteria

Feasibility Design Estimate GFA 149,350

26-Sep-16

CSI	·	,			HAIFT	ECTIN I	CIIP	TOTAL
CODE	COLLOC	DESCRIPTION LATERAL PAGE 15	QTY	UNIT	UNIT COST	EST'D COST	SUB TOTAL	TOTAL COST
NEW		L AT MURACO ES 4a	_					
	D10	CONVEYING SYSTEMS						
	D1010	ELEVATOR						
93000		Passenger elevator; 2 stop, 3500 lbs	1	ea	100,000.00	100,000		
		SUBTOTAL					100,000	
		TOTAL - CONVEYING SYSTEMS						\$100,00
	l .							
	D20	PLUMBING						
	D20	PLUMBING, GENERALLY Plumbing allowance	149,350	gsf	12.00	1,792,200		
		SUBTOTAL	17700	8		, ,	1,792,200	
		TOTAL - PLUMBING						\$1,792,20
	D30	HVAC						
	D30	HVAC, GENERALLY						
		HVAC complete system	149,350	gsf	38.00	5,675,300		
		SUBTOTAL					5,675,300	
		TOTAL - HVAC						\$5,675,30
		555002 550005						+0,-70,0
	D40	FIRE PROTECTION						
	D40	FIRE PROTECTION, GENERALLY Sprinkler system	149,350	gsf	4.50	672,075		
		SUBTOTAL	149,330	831	4.00	072,073	672,075	
							,,,,,,	
		TOTAL - FIRE PROTECTION						\$672,0
	D50	ELECTRICAL						
	D5010	COMPLETE ELECTRICAL SYSTEM						
	2,010	Electrical system; complete	149,350	gsf	34.00	5,077,900		
		SUBTOTAL	12700	O			5,077,900	
		TOTAL - ELECTRICAL						\$5,077,90
	L							
	E10	EQUIPMENT	\neg					
	LIU							
11500	E10	EQUIPMENT, GENERALLY		,	10.000.00	10.000		
11500		Gym wall pads	1	ls	10,000.00	10,000		
11500		Basketball backstops; swing up; electric operated	2	ea	9,800.00	19,600		
11500		Gymnasium dividing net; electrically operated	1	loc	45,000.00	45,000		
11500		Volleyball net and standards Telescoping bleachers	1	ea ls	2,000.00 25,000.00	2,000 25,000		
11500		Cubicle curtain & track at nurse area	1	loc	500.00	500		
11970		Platform curtains, rigging and controls	1	ls	35,000.00	35,000		
		AV Equipment at Café/Gym/ Learning	1	13	55,000.00	55,000 F,F&E		
11400		Food Service equipment	1	ls	350,000.00	350,000		
11500		All C. I. I. I. I. I.		13	10.000.00	10,000		

ls

ea

ea

1

1

1

2

10,000.00

1,000.00

3,000.00

10,000.00

10,000

1,000

3,000

20,000



RENOVATIONS + ADDITIONS

Winchester, MA

290

291 292

293 295

296 297

298

300

301

302 303

304

305

306 307

308 309 310

311 312

313

314

315 316

317 318 319

321

322

323 324

325

326

327 328 Feasibility Design Estimate GFA 149,350

CODE DESCRIPTION QTY UNIT COST COST TOTAL COST	CSI				UNIT	EST'D	SUB	TOTAL
	CODE	DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST

NEW SCHOOL AT MURACO ES 4a

SUBTOTAL

AV Equipment (including Smartboards, Projectors, LED monitors, Digital information displays etc.)

FF+E

TOTAL - EQUIPMENT \$521,100

E20 FURNISHINGS

E2010 FIXED FURNISHINGS

Entry mats & frames - recessed with carpet/rubber 100 45.00 4,500 strips Manual operated roller shades 6.00 161,610 26,935 sf Counters, base cabinets, tall storage in classrooms 4.00 597,400 149,350 gfa

and other rooms

SUBTOTAL 763,510

E2020 MOVABLE FURNISHINGS

All movable furnishings to be provided and installed

by owner

SUBTOTAL NIC

TOTAL - FURNISHINGS \$763,510

SPECIAL CONSTRUCTION F10

SPECIAL CONSTRUCTION F10

No Work in this section

SUBTOTAL

TOTAL - SPECIAL CONSTRUCTION

F20 SELECTIVE BUILDING DEMOLITION

F2010 BUILDING ELEMENTS DEMOLITION

SUBTOTAL

F2020 HAZARDOUS COMPONENTS ABATEMENT

None Included

SUBTOTAL

TOTAL - SELECTIVE BUILDING DEMOLITION

26-Sep-16

521,100



Feasibility Design Estimate GFA 207,350

	BUILDING	CONSTRUCTI	SUB-TOTAL	TOTAL	\$/SF	%
w sc		Γ MURACO ES 4	SUB-TOTAL	IOIAL	ֆ/SF	%
		OATIONS				
A10	A1010	Standard Foundations	\$024 626			
	A1010 A1020	Special Foundations	\$934,626 \$0			
	A1020	Lowest Floor Construction	\$992,753	\$1 00 7 0 7 0	\$9.30	3.89
	A1030	Lowest Floor Construction	\$99£,733	\$1,927,379	39.30	3.07
A20	BASEM	ENT CONSTRUCTION				
	A2010	Basement Excavation	\$0			
	A2020	Basement Walls	\$0	\$0	\$0.00	0.0
B10	SUPER	STRUCTURE				
	B1010	Upper Floor Construction	\$5,094,514			
	B1020	Roof Construction	\$2,244,700	\$7,339,214	\$35.40	14.49
B20	EXTER	IOR CLOSURE				
	B2010	Exterior Walls	\$4,810,328			
	B2020	Windows	\$4,052,399			
	B2030	Exterior Doors	\$64,560	\$8,927,287	\$43.05	17.6
Взо	ROOFI	NG				
0	B3010	Roof Coverings	\$1,851,010			
	B3020	Roof Openings	\$5,000	\$1,856,010	\$8.95	3.79
C10	INTERI	OR CONSTRUCTION				
	C1010	Partitions	\$4,147,000			
	C1020	Interior Doors	\$1,036,750			
	C1030	Specialties/Millwork	\$1,430,717	\$6,614,467	\$31.90	13.0
C20	STAIRO	CASES				
	C2010	Stair Construction	\$260,000			
	C2020	Stair Finishes	\$68,500	\$328,500	\$1.58	0.6°
Сзо	INTERI	OR FINISHES				
-	C3010	Wall Finishes	\$933,075			
	C3020	Floor Finishes	\$1,451,450			
	C3030	Ceiling Finishes	\$1,244,100	\$3,628,625	\$17.50	7.19
D10	CONVE	YING SYSTEMS				
	D1010	Elevator	\$200,000	\$200,000	\$0.96	0.4°
D20	PLUME	BING				
	D20	Plumbing	\$2,488,200	\$2,488,200	\$12.00	4.9°



Feasibility Design Estimate GFA 207,350

		CONSTRUCTION	I COST SUMM	$AR\overline{Y}$		
	BUILDING		SUB-TOTAL	TOTAL	\$/SF	%
EW SCI	HOOL AT	T MURACO ES 4				
D30	HVAC					
	D30	HVAC	\$7,879,300	\$7,879,300	\$38.00	15.5%
D40	FIRE P	ROTECTION				
	D40	Fire Protection	\$933,075	\$933,075	\$4.50	1.8%
D ₅ o	ELECTI	RICAL				
	D5010	Complete System	\$7,049,900	\$7,049,900	\$34.00	13.9%
E10	EQUIP	MENT				
	E10	Equipment	\$571,100	\$571,100	\$2.75	1.1%
E20	FURNIS	SHINGS				
	E2010	Fixed Furnishings	\$1,091,768			
	E2020	Movable Furnishings	NIC	\$1,091,768	\$5.27	2.1%
F10	SPECIA	L CONSTRUCTION				
	F10	Special Construction	\$0	\$0	\$0.00	0.0%
F20	HAZMA	AT REMOVALS				
	F2010	Building Elements Demolition	\$0			
	F2020	Hazardous Components Abatement	\$0	\$0	\$0.00	0.0%
TOTA	I. DIRFO	CT COST (Trade Costs)		\$50,834,825	\$245.16	100.0%



DESCRIPTION

CSI CODE

Feasibility Design Estimate GFA 207,350

UNIT

QTY

UNIT COST

EST'D

COST

26-Sep-16

TOTAL COST

SUB TOTAL

SCHOOL								
	L AT MURACO ES 4							
GROSS	FLOOR AREA CALCULATION							
	First Floor			68,900				
	Second Floor			51,932				
	Third Floor			43,259				
	Fourth Floor			43,259				
	1 data 1 iooi			10,200				
	TOTAL GROSS FLOOR AREA (GFA)				207,350	sf		
A10	FOUNDATIONS							
A1010	STANDARD FOUNDATIONS Strip footings - 2'-0" x 1'-0"							
	Excavation	2,156	cy	20.00	43,120			
	Store on site for reuse	2,156	cy	14.00	30,184			
	Backfill with existing fill	2,005		16.00	32,080			
	Remove surplus fill off site	151		25.00	3,775			
	Formwork	3,880	-	12.00	46,560			
	Re-bar, 10#/lf	19,400		1.20	23,280			
	Concrete material; 3,000 psi	151		125.00	18,875			
	Placing concrete	151	-	55.00	8,305			
	Foundation walls at exterior - 14" thick	-0-	-7		2,220			
	Formwork	15,520	sf	14.00	217,280			
	Re-bar, 4.5#/sf	34,920		1.20	41,904			
	Concrete material; 4,000 psi	353		135.00	47,655			
	Placing concrete	353		65.00	22,945			
	Dampproofing foundation wall and footing	11,640	-	1.90	NIC			
	Insulation to foundation walls; 2" thick	7,760		2.50	19,400			
	Form shelf	1,940		8.00	15,520			
	Column footings, typical, 6' x 6' x 2'-0"	<i>,,</i> •			•			
	Excavation	1,385	cy	20.00	27,700			
	Store on site for reuse	1,385	-	14.00	19,390			
	Backfill with new fill	1,055	-	16.00	16,880			
	Remove surplus fill off site	330	=	20.00	6,600			
	Formwork	5,664	-	11.00	62,304			
	Re-bar	66,080		1.20	79,296			
	Concrete material; 3,000 psi	330		125.00	41,250			
	Placing concrete	330	=	55.00	18,150			
	Set anchor bolts grout plates	118	=	150.00	17,700			
	Interior pilasters							
	Formwork	3,455	sf	11.00	38,005			
	Re-bar	21,240		1.20	25,488			
	Concrete material; 3,000 psi	61	cy	125.00	7,625			
	Placing concrete	61		55.00	3,355			
	SUBTOTAL		-			934	,626	
A1020	SPECIAL FOUNDATIONS							
	No Work in this section							
	SUBTOTAL							
A1030	LOWEST FLOOR CONSTRUCTION							
	New Slab on grade, 5" thick							
	Structural gravel fill, 8"	1,702	cy	30.00	51,060			
	Base course, 8" gravel	1,702	cy	40.00	68,080			
	Rigid insulation	68,900	sf	2.25	155,025			



Feasibility Design Estimate GFA 207,350

CSI COD	E DESCRIPTION	QTY	UNIT	UNIT COST	EST'D COST	SUB TOTAL	TOTAL COST
	W SCHOOL AT MURACO ES 4	ŲH	UNII	COSI	cosi	IOIAL	cosi
	Vapor barrier	68,900	sf	1.00	68,900		
	Mesh reinforcing 15% lap	79,235	sf	0.80	63,388		
	Concrete - 5" thick	1,125	cy	125.00	140,625		
	Placing concrete	1,125	cy	45.00	50,625		
	Finishing and curing concrete	68,900	sf	4.00	275,600		
	Control joints - saw cut	68,900	sf	0.50	34,450		
	<u>Miscellaneous</u>						
	Backfill existing foundations/basement	1	ea	50,000.00	50,000		
	Elevator pit	1	ea	30,000.00	30,000		
	Dewatering	1	ea	5,000.00	5,000		
	SUBTOTAL					992,753	

TOTAL - FOUNDATIONS \$1,927,379

26-Sep-16

A20 BASEMENT CONSTRUCTION

A2010 BASEMENT EXCAVATION

No items in this section

SUBTOTAL

A2020 BASEMENT WALLS

No items in this section

SUBTOTAL

TOTAL - BASEMENT CONSTRUCTION

B10	SUPERSTRUCTURE					
		4	lbs/sf			
B1010	FLOOR CONSTRUCTION	448	tns			
	Floor Structure - Steel:					
	Steel beams and columns; 13/SF	900	tns	3,500.00	3,150,000	
	Shear studs	27,690	ea	2.50	69,225	
	Floor Structure					
	2" Metal floor Deck	138,450	sf	4.20	581,490	
	WWF reinforcement	159,218	sf	0.80	127,374	
	Concrete Fill to metal deck; 5" normal weight	2,208	cy	125.00	276,000	
	Place and finish concrete	138,450	sf	2.00	276,900	
	Misc. perimeter angles	1,940	lf	25.00	48,500	
	Miscellaneous					
	Barrier one at slab	2,208	cy	65.00	143,520	
	Fire proofing to columns and beams	138,450	sf	2.90	401,505	
	Fire stopping floors	4	flrs	5,000.00	20,000	
	SUBTOTAL					5,094,514
B1020	ROOF CONSTRUCTION					
	Roof Structure - Steel:					
	Steel beams/Joists; 13#/SF	448	tns	3,800.00	1,702,400	
	Roof Structure					
	1-1/2" Metal floor Deck @ roof	68,900	sf	3.00	206,700	
	Miscellaneous					
	Roof screen framing - allow	1	ls	60,000.00	60,000	
	Fire proofing to columns, beams and deck	68,900	sf	4.00	275,600	



148 149

163

Feasibility Design Estimate GFA 207,350

26-Sep-16

CSI				UNIT	EST'D	SUB	TOTAL
CODE	DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST
NEW	SCHOOL AT MURACO ES 4						

SUBTOTAL 2,244,700

	SUBTUTAL					2,244,700	
	TOTAL - SUPERSTRUCTURE						\$7,3
B20	EXTERIOR CLOSURE						
B2010	EXTERIOR WALLS; 60% solid/40% glass Interior skin	64,467	sf				
	6" metal stud backup	64,467	sf	7.50	483,503		
	Batt insulation in stud	64,467	sf	2.25	145,051		
	2 1/2" Rigid Insulation	64,467	sf	3.00	193,401		
	Air barrier	64,467	sf	6.00	386,802		
	Air barrier/flashing at windows	14,183	lf	7.00	99,281		
	Gypsum Sheathing	64,467	sf	2.75	177,284		
	Drywall lining to interior face of stud backup	64,467	sf	3.00	193,401		
	Exterior skin						
	Brick veneer; 75% of exterior wall	48,350	sf	35.00	1,692,250		
	Metal panels; 25% of exterior wall	16,117	sf	60.00	967,020		
	Miscellaneous						
	Roof screens - allow	1	ls	150,000.00	150,000		
	Staging to exterior wall	107,445	sf	3.00	322,335		
	SUBTOTAL					4,810,328	
B2020	WINDOWS	42,978	sf		NIC		
	Premium for sunscreen and light shelf elements	1	ls	00.00	NIC		
	Windows/storefront	42,978	sf	90.00	3,868,020		
	Backer rod & double sealant	14,183	lf	9.00	127,647		
	Wood blocking at openings	14,183	lf	4.00	56,732	4 0 7 0 0 0 0	
	SUBTOTAL					4,052,399	
B2030	EXTERIOR DOORS						
	Glazed entrance doors including frame and hardware; double door at corridor exit $$	6	pr	8,000.00	48,000		
	Other doors	1	ls	15,000.00	15,000		
	Backer rod & double sealant	120	lf	9.00	1,080		
	Wood blocking at openings	120	lf	4.00	480		
	SUBTOTAL					64,560	
	TOTAL - EXTERIOR CLOSURE						\$8,0

<i>B</i> 30	ROOFING					
В3010	ROOF COVERINGS Flat roofing					
	PVC roof membrane fully adhered	68,900	sf	14.00	964,600	
	Insulation	68,900	sf	7.00	482,300	
	1/2" dens-deck protection board	68,900	sf	2.00	137,800	
	Reinforced vapor barrier	68,900	sf	1.50	103,350	
	Rough blocking	7,760	lf	6.00	46,560	
	Miscellaneous Roofing					
	Roof screens - allow				NIC	
	Roof fascia/cornice	1,940	lf	60.00	116,400	
	SUBTOTAL					1,851,010
Ranan	ROOF OPENINGS					



Feasibility Design Estimate GFA 207,350

	CSI					UNIT	EST'D	SUB	TOTAL
	CODE	SCHOOL	DESCRIPTION LAT MURACO ES 4	QTY	UNIT	COST	COST	TOTAL	COST
10.4	NEW	SCHOOL	•						
164			Skylights, allow				NIC		
165			Roof hatch	1	ea	5,000.00	5,000		
166			SUBTOTAL					5,000	
167									
168			TOTAL - ROOFING						\$1,856,010
169 170									
171		C10	INTERIOR CONSTRUCTION						
172									
173		C1010	PARTITIONS						
174			Allowance for interior walls/glazed partitions etc.	207,350	gfa	20.00	4,147,000		
175			SUBTOTAL					4,147,000	
176 177									
178		C1020	INTERIOR DOORS Interior doors, frames and hardware	207,350	gfa	5.00	1,036,750		
179			SUBTOTAL	20/,330	gra	3.00	1,030,730	1,036,750	
180			SOBIOTAL					1,030,730	
181		C1030	SPECIALTIES / MILLWORK						
182			Marker boards/tackboards in classroom	207,350	gfa	1.15	238,453		
183					_				
184			Toilet partitions and accessories	207,350	gfa	0.75	155,513		
			Room Signs	207,350	gfa	0.25	51,838		
185			Wood paneling/benches/display cases etc.	207,350	gfa	1.50	311,025		
186			Lockers	207,350	sf	1.00	207,350		
187			Miscellaneous metals throughout building	207,350	sf	1.25	259,188		
188			Miscellaneous sealants throughout building	207,350	sf	1.00	207,350		
189			SUBTOTAL					1,430,717	
190 191			TOTAL INTERPLOP CONCERNICATION						46.66-
192			TOTAL - INTERIOR CONSTRUCTION						\$6,614,467
193									
194		C20	STAIRCASES						
195									
196		C2010	STAIR CONSTRUCTION						
197	55100		Metal pan stair; egress stair	10	flt	24,000.00	240,000		
198	33000		Concrete fill to stairs	10	flt	2,000.00	20,000		
199			SUBTOTAL					260,000	
200		_							
201	90009	C2020	STAIR FINISHES High performance coating to stairs including all	10	flt	3,000.00	30,000		
			railings etc.	10	110	3,000.00	30,000		
203	90006		Rubber tile at stairs - landings	1,100	sf	12.00	13,200		
204	90006		Rubber tile at stairs - treads & risers	1,150	lft	22.00	25,300		
205			SUBTOTAL	1,130	III.	22.00	23,300	68,500	
206			SOBIOTAL					08,300	
207			TOTAL - STAIRCASES						\$328,500
208									
209				İ					
210 211		Сзо	INTERIOR FINISHES						
212		C3010	WALL FINISHES						
213		Ü	Wall finishes	207,350	gfa	4.50	933,075		
214			SUBTOTAL					933,075	
215									
216		C3020	FLOOR FINISHES						
217			Floor finishes	207,350	sf	7.00	1,451,450		
218			SUBTOTAL					1,451,450	
219 220		Causu	CEILING FINISHES						
221		-J0J0	Ceiling finishes	207,350	sf	6.00	1,244,100		
222			SUBTOTAL					1,244,100	
223									



AV Equipment at Café/Gym/ Learning

Allowance for loading dock equipment

Food Service equipment

Refrigerator/Freezer

Kiln

	inty Desig	n Estimate	1	1		namin .	GFA	207,:
CSI CODE		DESCRIPTION	QTY	UNIT	UNIT COST	EST'D COST	SUB TOTAL	TOTAL COST
NEW	SCHOO	L AT MURACO ES 4						
		TOTAL - INTERIOR FINISHES						\$3,628,6
_								
	D10	CONVEYING SYSTEMS						
	D1010	ELEVATOR						
93000		Passenger elevator; 4 stop, 3500 lbs	1	ea	200,000.00	200,000		
		SUBTOTAL					200,000	
		TOTAL - CONVEYING SYSTEMS						\$200,0
•								
[D20	PLUMBING						
	D20	PLUMBING, GENERALLY						
	D20	Plumbing allowance	207,350	gsf	12.00	2,488,200		
		SUBTOTAL					2,488,200	
Ī		TOTAL - PLUMBING						\$2,488,2
		TOTAL-T LONDING						Ψ2,400,2
ſ	D30	HVAC						
Į	DJU	IIVAC						
	D30	HVAC, GENERALLY			22.22	g 0g0 000		
		HVAC complete system SUBTOTAL	207,350	gsf	38.00	7,879,300	7,879,300	
_		SUBTUTAL					7,679,300	
		TOTAL - HVAC						\$7,879,3
[D40	FIRE PROTECTION						
	D40	FIRE PROTECTION, GENERALLY						
		Sprinkler system	207,350	gsf	4.50	933,075		
		SUBTOTAL					933,075	
		TOTAL - FIRE PROTECTION						\$933,0
Ĺ								
Ī	D50	ELECTRICAL						
-	D=010	COMPLETE ELECTRICAL SYSTEM	<u>.</u>					
	2,010	Electrical system; complete	207,350	gsf	34.00	7,049,900		
		SUBTOTAL	_0/,550	851	01.00	1,010,000	7,049,900	
		SOBTOTIE:					7,010,000	
[TOTAL - ELECTRICAL						\$7,049,9
ļ	I							
ſ	E10	EQUIPMENT						
L								
11500	E10	EQUIPMENT, GENERALLY Gym wall pads	1	ls	10,000.00	10,000		
11500		Basketball backstops; swing up; electric operated	2	ea	9,800.00	19,600		
11500		Gymnasium dividing net; electrically operated	1	loc	45,000.00	45,000		
11500		Volleyball net and standards	1	ea	2,000.00	2,000		
11500		Telescoping bleachers	1	ls	25,000.00	25,000		
11500		Cubicle curtain & track at nurse area	1	loc	500.00	500		
11970		Platform curtains, rigging and controls	1	ls	35,000.00	35,000		

26-Sep-16

F,F&E

400,000

10,000

1,000

3,000

400,000.00

10,000.00

1,000.00

3,000.00

ls

ls

ea



Feasibility Design Estimate GFA 207,350

CSI CODE		DESCRIPTION	QTY	UNIT	UNIT COST	EST'D COST	SUB TOTAL	TOTAL COST
	снооі	L AT MURACO ES 4	ŲII	UNII	COSI	COSI	IOIAL	COST
0999		Electrically operated projection screens in gym & cafeteria	2	loc	10,000.00	20,000		
		AV Equipment (including Smartboards, Projectors, LED monitors, Digital information displays etc.)				FF+E		
		SUBTOTAL					571,100	
		TOTAL - EQUIPMENT						\$571,10
	E20	FURNISHINGS]					
	E2010	FIXED FURNISHINGS Entry mats & frames - recessed with carpet/rubber	100	sf	45.00	4,500		
		strips		- C	0.00	057.000		
		Manual operated roller shades	42,978	sf	6.00	257,868		
		Counters, base cabinets, tall storage in classrooms and other rooms	207,350	gfa	4.00	829,400		
		SUBTOTAL					1,091,768	
	E2020	MOVABLE FURNISHINGS All movable furnishings to be provided and installed by owner						
		SUBTOTAL					NIC	
		TOTAL - FURNISHINGS						\$1,091,7
L								
	F10	SPECIAL CONSTRUCTION						
	F10	SPECIAL CONSTRUCTION						
		No Work in this section						
		SUBTOTAL						
Γ		TOTAL - SPECIAL CONSTRUCTION						
L								
	F20	SELECTIVE BUILDING DEMOLITION						
	F2010	BUILDING ELEMENTS DEMOLITION						
		SUBTOTAL					-	
	F2020	HAZARDOUS COMPONENTS ABATEMENT None Included						
		SUBTOTAL						
		TAL - SELECTIVE BUILDING DEMOLITION						



Winchester Schools RENOVATIONS + ADDITIONS

Winchester, MA

Feasibility Design Estimate GFA 21,500

		CONSTRUCTI	ON COST SUMM	ARY		
A DDITI	BUILDING		SUB-TOTAL	TOTAL	\$/SF	%
		ARKHURSRT ES 5				
A10		DATIONS				
	A1010	Standard Foundations	\$208,066			
	A1020	Special Foundations	\$0			
	A1030	Lowest Floor Construction	\$226,743	\$434,809	\$20.22	7.4%
A20	BASEM	IENT CONSTRUCTION				
	A2010	Basement Excavation	\$0			
	A2020	Basement Walls	\$0	\$0	\$0.00	0.0%
B10	SUPER	STRUCTURE				
	B1010	Upper Floor Construction	\$411,180			
	B1020	Roof Construction	\$361,250	\$772,430	\$35.93	13.1%
B20	EXTER	IOR CLOSURE				
D =0	B2010	Exterior Walls	\$593,341			
	B2020	Windows	\$463,719			
	B2030	Exterior Doors	\$43,040	\$1,100,100	\$51.17	18.7%
В30	ROOFI	NG				
D 30	B3010	Roof Coverings	\$298,991			
	B3020	Roof Openings	\$5,000	\$303,991	\$14.14	5.2%
C10	INTER	IOR CONSTRUCTION				
CIO	C1010	Partitions	\$430,000			
	C1020	Interior Doors	\$107,500			
	C1020	Specialties/Millwork	\$148,350	\$685,850	\$31.90	11.7%
C20	STAIR	CACEC				
020	C2010	Stair Construction	\$52,000			
	C2020	Stair Finishes	\$13,700	\$65,700	\$3.06	1.1%
С30	INTED	IOR FINISHES				
C30	C3010	Wall Finishes	\$96,750			
	C3020	Floor Finishes	\$150,500			
	C3030	Ceiling Finishes	\$129,000	\$376,250	\$17.50	6.4%
	C3030	Cennig I misnes	\$123,000	Ψ3/0,230	\$17.50	0.470
D10	CONVE	EYING SYSTEMS				
	D1010	Elevator	\$100,000	\$100,000	\$4.65	1.7%
D20	PLUMI	BING				
	D20	Plumbing	\$258,000	\$258,000	\$12.00	4.4%



Winchester Schools RENOVATIONS + ADDITIONS

Winchester, MA

Feasibility Design Estimate GFA 21,500

		CONSTRUCTION	COST SUMM	ARY		
	BUILDING		SUB-TOTAL	TOTAL	\$/SF	%
ADDITIC	ON AT PA	ARKHURSRT ES 5				
D30	HVAC					
	D30	HVAC	\$817,000	\$817,000	\$38.00	13.9%
D40	FIRE P	ROTECTION				
	D40	Fire Protection	\$96,750	\$96,750	\$4.50	1.6%
D50	ELECT	RICAL				
	D5010	Complete System	\$731,000	\$731,000	\$34.00	12.4%
E10	EQUIP	MENT				
	E10	Equipment	\$0	\$0	\$0.00	0.0%
E20	FURNIS	SHINGS				
	E2010	Fixed Furnishings	\$120,008			
	E2020	Movable Furnishings	NIC	\$120,008	\$5.58	2.0%
F10	SPECIA	AL CONSTRUCTION				
	F10	Special Construction	\$0	\$0	\$0.00	0.0%
F20	HAZMA	AT REMOVALS				
	F2010	Building Elements Demolition	\$25,000			
	F2020	Hazardous Components Abatement	\$0	\$25,000	\$1.16	0.4%
TOTA	AL DIREC	CT COST (Trade Costs)		\$5,886,888	\$273.81	100.0%



Feasibility Design Estimate GFA 21,500

26-Sep-16

CSI				UNIT	EST'D	SUB	TOTAL
CODE	DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST
ADDI	TION AT DADIVILIDODT EC -						

ADDITION AT PARKHURSRT ES 5

GROSS FLOOR AREA CALCULATION First Floor 10,750 Second Floor 10,750

	TOTAL GROSS FLOOR AREA (GFA)			·	21,500 sf	
A10	FOUNDATIONS					
A1010	STANDARD FOUNDATIONS Strip footings - 2'-0" x 1'-0"					
	Excavation	471	cy	20.00	9,420	
	Store on site for reuse	471	cy	14.00	6,594	
	Backfill with existing fill	438	сy	16.00	7,008	
	Remove surplus fill off site	33	cy	25.00	825	
	Formwork	848	sf	12.00	10,176	
	Re-bar, 10#/lf	4,240	lbs	1.20	5,088	
	Concrete material; 3,000 psi	33	cy	125.00	4,125	
	Placing concrete	33	су	55.00	1,815	
	Foundation walls at exterior - 14" thick	00	J		•	
	Formwork	3,392	sf	14.00	47,488	
	Re-bar, 4.5#/sf	7,632	lbs	1.20	9,158	
	Concrete material; 4,000 psi	7,° 3-	су	135.00	10,395	
	Placing concrete	77	cy	65.00	5,005	
	Dampproofing foundation wall and footing	2,544	sf	1.90	NIC	
	Insulation to foundation walls; 2" thick	1,696	sf	2.50	4,240	
	Form shelf	424	lf	8.00	3,392	
	Column footings, typical, 6' x 6' x 2'-0"				5,555	
	Excavation	317	су	20.00	6,340	
	Store on site for reuse	317	cy	14.00	4,438	
	Backfill with new fill	241	cy	16.00	3,856	
	Remove surplus fill off site	76	cy	20.00	1,520	
	Formwork	1,296	sf	11.00	14,256	
	Re-bar	15,120	lbs	1.20	18,144	
	Concrete material; 3,000 psi	76	су	125.00	9,500	
	Placing concrete	76	cy	55.00	4,180	
	Set anchor bolts grout plates	27	ea	150.00	4,050	
	Interior pilasters	-/	cu	100.00	1,000	
	Formwork	791	sf	11.00	8,701	
	Re-bar	4,860	lbs	1.20	5,832	
	Concrete material; 3,000 psi	4,000	су	125.00	1,750	
	Placing concrete	14	cy	55.00	770	
	SUBTOTAL	14	~J	00.00		208,066
						200,000
A1020	SPECIAL FOUNDATIONS					
	No Work in this section					
	SUBTOTAL					
A1030	LOWEST FLOOR CONSTRUCTION					
-	New Slab on grade, 5" thick					
	Structural gravel fill, 8"	266	cy	30.00	7,980	
	Base course, 8" gravel	266	су	40.00	10,640	
	Rigid insulation	10,750	sf	2.25	24,188	
	Vapor barrier	10,750	sf	1.00	10,750	
	Mesh reinforcing 15% lap	,, -	sf	0.80	9,890	



Feasibility Design Estimate GFA 21,500

CSI				UNIT	EST'D	SUB	TOTAL
CODE	DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST
ADDI	FION AT PARKHURSRT ES 5						
	Concrete - 5" thick	176	cy	125.00	22,000		
	Placing concrete	176	cy	45.00	7,920		
	Finishing and curing concrete	10,750	sf	4.00	43,000		
	Control joints - saw cut	10,750	sf	0.50	5,375		
	<u>Miscellaneous</u>						
	Backfill existing foundations/basement	1	ea	50,000.00	50,000		
	Elevator pit	1	ea	30,000.00	30,000		
	Dewatering	1	ea	5,000.00	5,000		
	SUBTOTAL					226,743	

TOTAL - FOUNDATIONS \$434,809

26-Sep-16

A20 BASEMENT CONSTRUCTION

A2010 BASEMENT EXCAVATION

No items in this section

SUBTOTAL

A2020 BASEMENT WALLS

No items in this section

SUBTOTAL

TOTAL - BASEMENT CONSTRUCTION

B10	SUPERSTRUCTURE					
		7	lbs/sf			
B1010	FLOOR CONSTRUCTION	70	tns			
	Floor Structure - Steel:					
	Steel beams and columns; 13/SF	70	tns	3,500.00	245,000	
	Shear studs	2,150	ea	2.50	5,375	
	Floor Structure					
	2" Metal floor Deck	10,750	sf	4.20	45,150	
	WWF reinforcement	12,363	sf	0.80	9,890	
	Concrete Fill to metal deck; 5" normal weight	171	cy	125.00	21,375	
	Place and finish concrete	10,750	sf	2.00	21,500	
	Misc. perimeter angles	424	lf	25.00	10,600	
	<u>Miscellaneous</u>					
	Barrier one at slab	171	cy	65.00	11,115	
	Fire proofing to columns and beams	10,750	sf	2.90	31,175	
	Fire stopping floors	2	flrs	5,000.00	10,000	
	SUBTOTAL					411,180
B1020	ROOF CONSTRUCTION					
	Roof Structure - Steel:					
	Steel beams/Joists; 13#/SF	70	tns	3,800.00	266,000	
	Roof Structure					
	1-1/2" Metal floor Deck @ roof	10,750	sf	3.00	32,250	
	<u>Miscellaneous</u>					
	Roof screen framing - allow	1	ls	20,000.00	20,000	
	Fire proofing to columns, beams and deck	10,750	sf	4.00	43,000	
	SUBTOTAL					361,250



79

Winchester Schools RENOVATIONS + ADDITIONS Winchester, MA

Feasibility Design Estimate GFA 21,500

26-Sep-16

							_
CSI				UNIT	EST'D	SUB	TOTAL
CODE	DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST
ADDI'	TION AT PARKHURSRT ES 5						

TOTAL - SUPERSTRUCTURE \$772,430 57 57 58 EXTERIOR CLOSURE B20 B2010 EXTERIOR WALLS; 60% solid/40% glass 7,378 sf 59 Interior skin 60 6" metal stud backup 7.50 55,335 sf 7,378 60 Batt insulation in stud 7,378 sf 2.25 16,601 61 2 1/2" Rigid Insulation 3.00 22,134 sf 7,378 61 Air barrier 7,378 sf 6.00 44,268 62 7.00 Air barrier/flashing at windows lf 11,361 1,623 62 Gypsum Sheathing 7,378 sf 2.75 20,290 63 7,378 Drywall lining to interior face of stud backup sf 3.00 22,134 63 Exterior skin 64 Brick veneer; 75% of exterior wall 35.00 193,690 sf 5,534 64 Metal panels; 25% of exterior wall 60.00 110,640 1,844 sf 65 Miscellaneous 65 60,000.00 Roof screens - allow ls 60,000 66 3.00 36,888 Staging to exterior wall 12,296 sf 66 SUBTOTAL 593,341 67 67 B2020 WINDOWS 4,918 sf 68 Premium for sunscreen and light shelf elements ls NIC 68 Windows/storefront 4,918 sf 90.00 442,620 69 Backer rod & double sealant 1,623 lf 9.00 14,607 69 Wood blocking at openings lf 4.00 6,492 1,623 70 SUBTOTAL 463,719 70 71 **B2030 EXTERIOR DOORS** 71 Glazed entrance doors including frame and hardware; 8,000.00 32,000 pr double door at corridor exit 10,000.00 Other doors 10,000 1 ls 72 Backer rod & double sealant lf 9.00 720 80 73 Wood blocking at openings lf 4.00 320 80 73 SUBTOTAL 43,040 74 74 TOTAL - EXTERIOR CLOSURE \$1,100,100 75 75 76 76

Взо	ROOFING					
B3010	ROOF COVERINGS Flat roofing					
	PVC roof membrane fully adhered	10,750	sf	14.00	150,500	
	Insulation	10,750	sf	7.00	75,250	
	1/2" dens-deck protection board	10,750	sf	2.00	21,500	
	Reinforced vapor barrier	10,750	sf	1.50	16,125	
	Rough blocking	1,696	lf	6.00	10,176	
	Miscellaneous Roofing					
	Roof screens - allow				NIC	
	Roof fascia/cornice	424	lf	60.00	25,440	
	SUBTOTAL					298,991
B3020	ROOF OPENINGS					
	Skylights, allow				NIC	
	Roof hatch	1	ea	5,000.00	5,000	



Feasibility Design Estimate GFA 21,500

26-Sep-16

	mty Desig	n Estimate					GFA	21,300
CSI CODE		DESCRIPTION	QTY	UNIT	UNIT COST	EST'D COST	SUB TOTAL	TOTAL COST
ADD	ITION AT	Γ PARKHURSRT ES 5						
		SUBTOTAL					5,000	
		TOTAL - ROOFING						\$303,991
	C10	INTERIOR CONSTRUCTION	٦					
	CIO	TVIENOR CONSTRUCTION						
	C1010	PARTITIONS						
		Allowance for interior walls/glazed partitions etc.	21,500	gfa	20.00	430,000	400.000	
		SUBTOTAL					430,000	
	C1020	INTERIOR DOORS						
		Interior doors, frames and hardware	21,500	gfa	5.00	107,500	107.500	
		SUBTOTAL					107,500	
	C1030	SPECIALTIES / MILLWORK						
		Marker boards/tackboards in classroom	21,500	gfa	1.15	24,725		
		Toilet partitions and accessories	21,500	gfa	0.75	16,125		
		Room Signs	21,500	gfa	0.25	5,375		
		Wood paneling/benches/display cases etc.	21,500	gfa	1.50	32,250		
		Lockers	21,500	sf	1.00	21,500		
		Miscellaneous metals throughout building	21,500	sf	1.25	26,875		
		Miscellaneous sealants throughout building	21,500	sf	1.00	21,500		
		SUBTOTAL					148,350	
		TOTAL - INTERIOR CONSTRUCTION						\$685,850
	1							
	C20	STAIRCASES	7					
55100	C2010	STAIR CONSTRUCTION		a.	04.000.00	40.000		
33000		Metal pan stair; egress stair Concrete fill to stairs	2	flt flt	24,000.00 2,000.00	48,000 4,000		
00000		SUBTOTAL	2	ш	2,000.00	4,000	52,000	
		SOBIOTAL					32,000	
90009	C2020	STAIR FINISHES High performance coating to stairs including all		ti+	2 000 00	6 000		
00000		railings etc.	2	flt	3,000.00	6,000		
90006		Rubber tile at stairs - landings	220	sf	12.00	2,640		
90006		Rubber tile at stairs - treads & risers	230	lft	22.00	5,060		
		SUBTOTAL					13,700	
		TOTAL - STAIRCASES						\$65,700
								1 - 077 -
	Coo	INTEDIOD EINICHEC	٦					
	Сзо	INTERIOR FINISHES						
	C3010	WALL FINISHES				00 770		
		Wall finishes SUBTOTAL	21,500	gfa	4.50	96,750	96,750	
		SUBTOTAL					90,730	
	C3020	FLOOR FINISHES						
		Floor finishes	21,500	sf	7.00	150,500		
		OI IDEOMAI					150,500	
		SUBTOTAL						
	C3030	CEILING FINISHES						
	С3030		21,500	sf	6.00	129,000		
	Сзозо	CEILING FINISHES	21,500	sf	6.00	129,000	129,000	



146

E2020 MOVABLE FURNISHINGS

Feasibility Design Estimate GFA 21,500

Feasibi	lity Desig	n Estimate					GFA	21,5
CSI CODE		DESCRIPTION	QTY	UNIT	UNIT COST	EST'D COST	SUB TOTAL	TOTAL COST
ADDI	ΓΙΟΝ ΑΤ	PARKHURSRT ES 5						
	D10	CONVEYING SYSTEMS						
	D1010	ELEVATOR						
93000		Passenger elevator; 2 stop, 3500 lbs	1	ea	100,000.00	100,000		
		SUBTOTAL					100,000	
Г		TOTAL - CONVEYING SYSTEMS						\$100,00
L								
Г	D20	PLUMBING	7					
_	D20	PLUMBING, GENERALLY	_					
	D20	Plumbing allowance	21,500	gsf	12.00	258,000		
		SUBTOTAL		J			258,000	
Г		MOTAL DIVINDING						
L		TOTAL - PLUMBING						\$258,0
Г	Dao	HVAC	7					
L	D30	HVAC	_					
	D30	HVAC, GENERALLY						
		HVAC complete system	21,500	gsf	38.00	817,000	047.000	
		SUBTOTAL					817,000	
		TOTAL - HVAC						\$817,0
	D40	FIRE PROTECTION						
	D40	FIRE PROTECTION, GENERALLY						
	•	Sprinkler system	21,500	gsf	4.50	96,750		
		SUBTOTAL					96,750	
		TOTAL - FIRE PROTECTION						\$96,7
г	D	DI POTENCIA I	7					
L	D ₅ o	ELECTRICAL						
	D5010	COMPLETE ELECTRICAL SYSTEM						
		Electrical system; complete	21,500	gsf	34.00	731,000		
		SUBTOTAL					731,000	
F								
		TOTAL - ELECTRICAL						\$731,0
г			7					
Ĺ	E10	EQUIPMENT	_					
	E10	EQUIPMENT, GENERALLY						
		AV Equipment (including Smartboards, Projectors, LED monitors, Digital information displays etc.)				FF+E		
		SUBTOTAL					_	
		502.511H						
		TOTAL - EQUIPMENT						
	E20	FURNISHINGS						
	E2010	FIXED FURNISHINGS						
		Entry mats & frames - recessed with carpet/rubber	100	sf	45.00	4,500		
		strips	-	c		20		
		Manual operated roller shades	4,918	sf	6.00	29,508		
		Counters, base cabinets, tall storage in classrooms and other rooms	21,500	gfa	4.00	86,000		
		SUBTOTAL					120,008	
							•	
	H 0000	MOVARI E ELIDNICHINGS						



147

148

148

149 150

150 151

151

152

153

153 154 154

155 155

156

157

158

159

160 161 Winchester Schools RENOVATIONS + ADDITIONS Winchester, MA

Feasibility Design Estimate

Winchester, MA

CS	SI				UNIT	EST'D	SUB	TOTAL
CO	ODE	DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST

ADDITION AT PARKHURSRT ES 5

All movable furnishings to be provided and installed by owner

SUBTOTAL

TOTAL - FURNISHINGS \$120,008

26-Sep-16

21,500

GFA

F10 SPECIAL CONSTRUCTION

F10 SPECIAL CONSTRUCTION
No Work in this section
SUBTOTAL

TOTAL - SPECIAL CONSTRUCTION

F20 SELECTIVE BUILDING DEMOLITION

F2010 BUILDING ELEMENTS DEMOLITION

Create openings to existing façade for new 1 loc 25,000.00 25,000


connections

156 SUBTOTAL 25,000

F2020 HAZARDOUS COMPONENTS ABATEMENT

None Included SUBTOTAL

TOTAL - SELECTIVE BUILDING DEMOLITION \$25,000



Feasibility Design Estimate

Winchester Schools CAFETERIA + DISTRICT OFFICE EXPANSION

Winchester, MA

PM&C LLC 20 Downer Avenue, Suite 1c Hingham, MA 02043 (T) 781-740-8007 (F) 781-740-1012 Prepared for:

Flansburgh Architects

February 7, 2017



Winchester Schools CAFETERIA + DISTRICT OFFICE EXPANSION

Winchester, MA

Feasibility Design Estimate

07-Feb-17

MAIN CONSTRUCTION COST SUMMARY

	Construction Start	Gross Floor Area	\$/sf	Estimated Construction Cost
RENOVATION TO McCALL MS -	CAFETERIA C	PTION 1		
CAFETERIA EXPANSION		1,100	\$76.63	\$84,298
SUB-TOTAL	Jun-18	1,100	\$76.63	\$84,298
ESCALATION TO START - (assumed 4% PA)	5.7%			\$4,805
DESIGN AND PRICING CONTINGENCY	15%			\$12,645
SUB-TOTAL		1,100	\$92.50	\$101,748
GENERAL CONDITIONS				\$15,262
BONDS	1.00%			\$1,017
INSURANCE	2.00%			\$2,035
PERMIT				NIC
OVERHEAD AND FEE	10.00%			\$10,175
OWNER CONTINGENCY				By Owner
TOTAL OF ALL CONSTRUCTION	Jun-18	1,100	\$118.40	\$130,237



07-Feb-17

Feasibility Design Estimate

MAIN CONSTRUCTION COST SUMMARY

	Construction Start	Gross Floor Area	\$/sf	Estimated Construction Cost
RENOVATION TO McCALL MS -	· CAFETERIA C	PTION 2		
CAFETERIA EXPANSION		2,400	\$92.36	\$221,660
SUB-TOTAL	Jun-18	2,400	\$92.36	\$221,660
ESCALATION TO START - (assumed 4% PA)	5.7%			\$12,635
DESIGN AND PRICING CONTINGENCY	15%			\$33,249
SUB-TOTAL		2,400	\$111.48	\$267,544
GENERAL CONDITIONS				\$40,132
BONDS	1.00%			\$2,675
INSURANCE	2.00%			\$5,351
PERMIT				NIC
OVERHEAD AND FEE	10.00%			\$26,754
OWNER CONTINGENCY				By Owner
TOTAL OF ALL CONSTRUCTION	Jun-18	2,400	\$142.69	\$342,456



Winchester Schools

CAFETERIA + DISTRICT OFFICE EXPANSION

07-Feb-17

Winchester, MA

Feasibility Design Estimate

ADDITION AT CAFETERIA - OPTION ${\bf 3}$

ADDITION		1,525	\$517.84	\$789,704
SUB-TOTAL	Jun-18	1,525	\$517.84	\$789,704
ESCALATION TO START - (assumed 4% PA)	5.7%			\$45,013
DESIGN AND PRICING CONTINGENCY	15%			\$118,456
SUB-TOTAL		1,525	\$625.03	\$953,173
GENERAL CONDITIONS				\$76,254
BONDS	1.00%			\$9,532
INSURANCE	2.00%			\$19,063
PERMIT				NIC
OVERHEAD AND FEE	8.00%			\$76,254
OWNER CONTINGENCY				By Owner
TOTAL OF ALL CONSTRUCTION	Jun-18	1,525	\$743.79	\$1,134,276
NEW TEACHERS WORKROOM WORKROOM RENOVATION		1,250	\$37.90	\$47,370
		,		,
SUB-TOTAL	Jun-18	1,250	\$37.90	\$47,370
ESCALATION TO START - (assumed 4% PA)	5.7%			\$2,700
DESIGN AND PRICING CONTINGENCY	15%			\$7,106
SUB-TOTAL		1,250	\$45.74	\$57,176
GENERAL CONDITIONS				\$11,435
BONDS	1.00%			\$572
INSURANCE	2.00%			\$1,144
PERMIT				NIC
OVERHEAD AND FEE	15.00%			\$8,576
OWNER CONTINGENCY				By Owner
TOTAL OF ALL CONSTRUCTION	Jun-18	1,250	\$63.12	\$78,903



07-Feb-17

Feasibility Design Estimate

MAIN CONSTRUCTION COST SUMMARY

	Construction Start	Gross Floor Area	\$/sf	Estimated Construction Cost
DISTRICT OFFICE ADDITION T	O LYNCH OPT	ION WPS-	1	
DISTRICT OFFICE ADDITION		4,900	\$281.81	\$1,380,878
SUB-TOTAL	Jun-18	4,900	\$281.81	\$1,380,878
ESCALATION TO START - (assumed 4% PA)	5.7%			\$78,710
DESIGN AND PRICING CONTINGENCY	10%			\$138,088
SUB-TOTAL		4,900	\$326.06	\$1,597,676
GENERAL CONDITIONS				\$127,814
BONDS	1.00%			\$15,977
INSURANCE	2.00%			\$31,954
PERMIT				NIC
OVERHEAD AND FEE	3.00%			\$47,930
OWNER CONTINGENCY				By Owner
TOTAL OF ALL CONSTRUCTION	Jun-18	4,900	\$371.70	\$1,821,351



Winchester Schools CAFETERIA + DISTRICT OFFICE EXPANSION

CAPETERIA + DISTRICT OFFICE EXTANSION

Winchester, MA

Feasibility Design Estimate

MAIN CONSTRUCTION COST SUMMARY

	Construction Start	Gross Floor Area	\$/sf	Estimated Construction Cost
DISTRICT OFFICE ADDITION T	O NEW LYNCI	H OPTION	WPS-2	
DISTRICT OFFICE ADDITION		4,900	\$261.63	\$1,281,982
SUB-TOTAL	Jun-18	4,900	\$261.63	\$1,281,982
ESCALATION TO START - (assumed 4% PA)	5.7%			\$73,073
DESIGN AND PRICING CONTINGENCY	10%			\$128,198
SUB-TOTAL		4,900	\$302.70	\$1,483,253
GENERAL CONDITIONS				\$118,660
BONDS	1.00%			\$14,833
INSURANCE	2.00%			\$29,665
PERMIT				NIC
OVERHEAD AND FEE	3.00%			\$44,498
OWNER CONTINGENCY				By Owner
TOTAL OF ALL CONSTRUCTION	Jun-18	4,900	\$345.08	\$1,690,909

07-Feb-17



Winchester Schools

CAFETERIA + DISTRICT OFFICE EXPANSION

Winchester, MA

Feasibility Design Estimate

MAIN CONSTRUCTION COST SUMMARY

	Construction Start	Gross Floor Area	\$/sf	Estimated Construction Cost
DISTRICT OFFICE ADDITION T	O NEW LYNCI	H OPTION	WPS-3	
DISTRICT OFFICE ADDITION		4,900	\$257.55	\$1,261,982
SUB-TOTAL	Jun-18	4,900	\$257.55	\$1,261,982
ESCALATION TO START - (assumed 4% PA)	5.7%			\$71,933
DESIGN AND PRICING CONTINGENCY	10%			\$126,198
SUB-TOTAL		4,900	\$297.98	\$1,460,113
GENERAL CONDITIONS				\$116,809
BONDS	1.00%			\$14,601
INSURANCE	2.00%			\$29,202
PERMIT				NIC
OVERHEAD AND FEE	3.00%			\$43,803
OWNER CONTINGENCY				By Owner
TOTAL OF ALL CONSTRUCTION	Jun-18	4,900	\$339.70	\$1,664,528

07-Feb-17



07-Feb-17

Feasibility Design Estimate

MAIN CONSTRUCTION COST SUMMARY

	Construction Start	Gross Floor Area	\$/sf	Estimated Construction Cost
DISTRICT OFFICE ADDITION T	O NEW LYNCI	H OPTION	WPS-4	
DISTRICT OFFICE ADDITION		4,900	\$261.63	\$1,281,982
SUB-TOTAL	Jun-18	4,900	\$261.63	\$1,281,982
ESCALATION TO START - (assumed 4% PA)	5.7%			\$73,073
DESIGN AND PRICING CONTINGENCY	10%			\$128,198
SUB-TOTAL		4,900	\$302.70	\$1,483,253
GENERAL CONDITIONS				\$118,660
BONDS	1.00%			\$14,833
INSURANCE	2.00%			\$29,665
PERMIT				NIC
OVERHEAD AND FEE	3.00%			\$44,498
OWNER CONTINGENCY				By Owner
TOTAL OF ALL CONSTRUCTION	Jun-18	4,900	\$345.08	\$1,690,909



07-Feb-17

Feasibility Design Estimate

MAIN CONSTRUCTION COST SUMMARY

	Construction Start	Gross Floor Area	\$/sf	Estimated Construction Cost
DISTRICT OFFICE RENOVATION 5	N TO MYSTIC	ES OPTION	N WPS-	
DISTRICT OFFICE RENOVATION		4,900	\$150.05	\$735,225
SUB-TOTAL	Jun-18	4,900	\$150.05	\$735,225
ESCALATION TO START - (assumed 4% PA)	5.7%			\$41,908
DESIGN AND PRICING CONTINGENCY	10%			\$73,523
SUB-TOTAL		4,900	\$173.60	\$850,656
GENERAL CONDITIONS				\$85,066
BONDS	1.00%			\$8,507
INSURANCE	2.00%			\$17,013
PERMIT				NIC
OVERHEAD AND FEE	5.00%			\$42,533
OWNER CONTINGENCY				By Owner
TOTAL OF ALL CONSTRUCTION	Jun-18	4,900	\$204.85	\$1,003,775



07-Feb-17

Feasibility Design Estimate

This Feasibility Design cost estimate was produced from preliminary drawings prepared by Flansburgh Architects Inc. and their design team dated February 2, 2017. Design and engineering changes occurring subsequent to the issue of these documents have not been incorporated in this estimate.

This estimate includes all direct construction costs, general contractor's overhead, fee and design contingency. Cost escalation assumes start dates indicated.

Bidding conditions are expected to be public bidding under Chapter 149 of the Massachusetts General Laws to pre-qualified general contractors, and pre-qualified sub-contractors, open specifications for materials and manufactures.

The estimate is based on prevailing wage rates for construction in this market and represents a reasonable opinion of cost. It is not a prediction of the successful bid from a contractor as bids will vary due to fluctuating market conditions, errors and omissions, proprietary specifications, lack or surplus of bidders, perception of risk, etc. Consequently the estimate is expected to fall within the range of bids from a number of competitive contractors or subcontractors, however we do not warrant that bids or negotiated prices will not vary from the final construction cost estimate.

ITEMS NOT CONSIDERED IN THIS ESTIMATE

Items not included in this estimate are:

Land acquisition, feasibility, and financing costs

All professional fees and insurance

Site or existing conditions surveys investigations costs, including to determine

subsoil conditions

All Furnishings, Fixtures and Equipment

Items identified in the design as Not In Contract (NIC)

Items identified in the design as by others

Owner supplied and/or installed items as indicated in the estimate

Utility company back charges, including work required off-site

Work to City streets and sidewalks, (except as noted in this estimate)

Construction contingency



Feasibility Design Estimate GFA 1,100

Feasibility	Design Es	timate			GFA	1,100	
			ION COST SUMMA				
	BUILDING		SUB-TOTAL	TOTAL	\$/SF	%	
		O McCALL MS - CAFETERIA OPTION	N 1				
A10	FOUNI A1010	OATIONS Standard Foundations	\$0				
	A1010	Special Foundations	\$0 \$0				
	A1020	Lowest Floor Construction	\$2,750	\$2,750	\$2.50	3.3%	
B10	SUPER	STRUCTURE					
	B1010	Upper Floor Construction	\$0				
	B1020	Roof Construction	\$0	\$0	\$0.00	0.0%	
B20	EXTER	IOR CLOSURE					
	B2010	Exterior Walls	\$0				
	B2020	Windows/Curtainwall	\$0				
	B2030	Exterior Doors	\$0	\$0	\$0.00	0.0%	
Взо	ROOFI	NG					
	B3010	Roof Coverings	\$0				
	B3020	Roof Openings	\$0	\$0	\$0.00	0.0%	
C10	INTER	IOR CONSTRUCTION					
	C1010	Partitions	\$6,648				
	C1020	Interior Doors	\$0				
	C1030	Specialties/Millwork	\$700	\$7,348	\$6.68	8.7%	
C20	STAIR	CASES					
	C2010	Stair Construction	\$0				
	C2020	Stair Finishes	\$0	\$0	\$0.00	0.0%	
С30	INTER	IOR FINISHES					
	C3010	Wall Finishes	\$5,300				
	C3020	Floor Finishes	\$13,000				
	C3030	Ceiling Finishes	\$10,200	\$28,500	\$25.91	33.8%	
D10	CONVE	YING SYSTEMS					
	D1010	Elevator	\$0	\$0	\$0.00	0.0%	
D20	PLUMI	BING					
	D20	Plumbing	\$0	\$0	\$0.00	0.0%	
D30	HVAC						
	D30	HVAC	\$11,000	\$11,000	\$10.00	13.0%	
D40		ROTECTION					
	D40	Fire Protection	\$2,200	\$2,200	\$2.00	2.6%	

07-Feb-17



07-Feb-17

Feasibility Design Estimate GFA 1,100

	BUILDING	SYSTEM	SUB-TOTAL	TOTAL	\$/SF	%
NOVA	TION TO	O McCALL MS - CAFETERIA OPTION 1				
D50	ELECTI	RICAL				
	D5010	Electrical Systems	\$16,500	\$16,500	\$15.00	19.6%
E10	EQUIP	MENT				
	E10	Equipment	\$0	\$0	\$0.00	0.0%
E20	FURNIS	SHINGS				
	E2010	Fixed Furnishings	\$0			
	E2020	Movable Furnishings	NIC	\$0	\$0.00	0.0%
F10	SPECIA	L CONSTRUCTION				
	F10	Special Construction	\$0	\$0	\$0.00	0.0%
F20	SELECT	TIVE BUILDING DEMOLITION				
	F2010	Building Elements Demolition	\$16,000			
	F2020	Hazardous Components Abatement	\$0	\$16,000	\$14.55	19.0%
TOTA	AL DIREC	CT COST (Trade Costs)		\$84,298	\$76.63	100.0%



CAFETERIA + DISTRICT OFFICE EXPANSION

Winchester, MA

10 11

12

17

18 19

20 21 22

23

26

27 28

29

30 31

32 33

38 39 40

41

42

43

47 48

49 50 51

52 53

54

Feasibility Design Estimate GFA 1,100

				UNIT	EST'D	SUB	TOTAL	ı
	DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST	l

RENOVATION TO McCALL MS - CAFETERIA OPTION 1

TOTAL RENOVATED AREA (GFA) 1,100 GSF

A10 FOUNDATIONS

A1010 STANDARD FOUNDATIONS

No work in this section

SUBTOTAL

A1020 SPECIAL FOUNDATIONS

No work in this section $% \left(1\right) =\left(1\right) \left(

SUBTOTAL

A1030 LOWEST FLOOR CONSTRUCTION

Patch existing slab **1,100** sf 2.50 2,750

SUBTOTAL 2,750

TOTAL - FOUNDATIONS

B10 SUPERSTRUCTURE

B1010 FLOOR CONSTRUCTION

No work in this section

SUBTOTAL

B1020 ROOF CONSTRUCTION

SUBTOTAL -

TOTAL - SUPERSTRUCTURE

B20 EXTERIOR CLOSURE

B2010 EXTERIOR WALLS

No work assumed to existing exterior

SUBTOTAL

B2020 WINDOWS/CURTAINWALL

No work assumed to existing exterior

SUBTOTAL

B2030 EXTERIOR DOORS

No work assumed to existing exterior

SUBTOTAL

TOTAL - EXTERIOR CLOSURE

B30 ROOFING

B3010 ROOF COVERINGS

No work assumed to existing exterior

SUBTOTAL

\$2,750



CAFETERIA + DISTRICT OFFICE EXPANSION

Winchester, MA

56 57

58

59

60 61

62 63 64

65 66

69

70 71

72

73

77

79 80

81 82 83

84

86

87

89

90

91

92 93

94 95 96

97 98

99

100

101

102 103

104

105

106

108

Feasibility Design Estimate GFA 1,100

				UNIT	EST'D	SUB	TOTAL	ı
	DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST	l

RENOVATION TO McCALL MS - CAFETERIA OPTION 1

B3020 ROOF OPENINGS

No work in this section

SUBTOTAL

TOTAL - ROOFING

C10 INTERIOR CONSTRUCTION

C1010 PARTITIONS

Patch existing walls **1,716** sf 3.00 5,148

 $\label{eq:localization} \text{Infill door opening; single door} \qquad \qquad \qquad \textbf{1} \qquad \text{loc} \qquad \qquad 1{,}500.00 \qquad \qquad 1{,}500$

SUBTOTAL 6,648

C1020 INTERIOR DOORS

No work in this section

SUBTOTAL

C1030 SPECIALTIES / MILLWORK

Room Signs **1** loc 150.00 150

Miscellaneous sealants **1,100** sf 0.50 550

SUBTOTAL 700

TOTAL - INTERIOR CONSTRUCTION

C20 STAIRCASES

C2010 STAIR CONSTRUCTION

No work in this section $% \left\{ \left\{ \left\{ \left\{ \right\} \right\} \right\} \right\} =\left\{ \left\{ \left\{ \left\{ \left\{ \right\} \right\} \right\} \right\} \right\}$

SUBTOTAL -

C2020 STAIR FINISHES

No work in this section

SUBTOTAL

TOTAL - STAIRCASES

C30 INTERIOR FINISHES

C3010 WALL FINISHES

 Paint to walls etc.
 1,100
 gsf
 3.00
 3,300

 Patch/paint existing walls
 1
 ls
 2,000.00
 2,000

SUBTOTAL

C3020 FLOOR FINISHES

 New resilient flooring
 1,100
 sf
 8.00
 8,800

 Patch existing floor at removed walls
 100
 lf
 20.00
 2,000

 Floor prep
 1,100
 sf
 2.00
 2,200

SUBTOTAL 13,000

5,300

\$7,348



CAFETERIA + DISTRICT OFFICE EXPANSION

Winchester, MA

Feasibility Design Estimate GFA 1,100

ibility Desig	n Estimate					GFA	1,10
				UNIT	EST'D	SUB	TOTAL
	DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST
	TO McCALL MS - CAFETERIA OPTION 1 CEILING FINISHES						
C3030	ACT, 2x2	1,100	sf	7.00	7,700		
	Patch existing floor at removed walls	100	lf	25.00	2,500		
	SUBTOTAL				,	10,200	
	TOTAL - INTERIOR FINISHES						\$28,50
D10	CONVEYING SYSTEMS	\neg					
<i>D</i> 10	CONVENTIONS						
	No work in this section SUBTOTAL					-	
	TOTAL - CONVEYING SYSTEMS						
D20	PLUMBING						
D20	PLUMBING, GENERALLY						
	No work in this section						
	SUBTOTAL					-	
	TOTAL - PLUMBING						
D30	HVAC						
D30	HVAC, GENERALLY						
-0-	HVAC modifications	1,100	sf	10.00	11,000		
	SUBTOTAL					11,000	
	TOTAL - HVAC						\$11,00
D40	FIRE PROTECTION						
D40	FIRE PROTECTION, GENERALLY						
-4-	Sprinkler system modifications	1,100	sf	2.00	2,200		
	SUBTOTAL					2,200	
	TOTAL - FIRE PROTECTION						\$2,20
D50	ELECTRICAL						
Denic	COMPLETE ELECTRICAL SYSTEMS						
D2010	Lighting, power and Tele/Data modifications	1,100	sf	15.00	16,500		
	SUBTOTAL	-,0			-,	16 500	
	SUDIUIAL					16,500	

E10 EQUIPMENT

E10 EQUIPMENT, GENERALLY

TOTAL - ELECTRICAL

\$16,500



CAFETERIA + DISTRICT OFFICE EXPANSION

Winchester, MA

164

165

166 167

168 169 170

171

172 173

174

175 176

177

178

179 180

181 182 183

184 185

186

187

188 189

190 191 192

193 194

195

196

197

199

203

204 205

206

Feasibility Design Estimate GFA 1,100

				UNIT	EST'D	SUB	TOTAL	
	DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST	

RENOVATION TO McCALL MS - CAFETERIA OPTION 1

No work in this section SUBTOTAL

TOTAL - EQUIPMENT

E20 FURNISHINGS

E2010 FIXED FURNISHINGS

No work in this section

SUBTOTAL

E2020 MOVABLE FURNISHINGS

All movable furnishings to be provided and installed

by owner SUBTOTAL

NIC

TOTAL - FURNISHINGS

F10 SPECIAL CONSTRUCTION

F10 SPECIAL CONSTRUCTION

No items in this section

SUBTOTAL

TOTAL - SPECIAL CONSTRUCTION

F20 SELECTIVE BUILDING DEMOLITION

F2010 BUILDING ELEMENTS DEMOLITION

Gut demolition; finishes and casework 6.00 6,600 1,100 \mathbf{sf} Create opening in bearing wall ls 3,000.00 3,000 Remove walls 1,400 sf 3.00 4,200 Miscellaneous demo/protection 2.00 2,200 gfa 1,100

SUBTOTAL 16,000

F2020 HAZARDOUS COMPONENTS ABATEMENT

None Included SUBTOTAL

TOTAL - SELECTIVE BUILDING DEMOLITION

\$16,000



Feasibility Design Estimate GFA 2,400

1 cusibility	Design E	, in the second			GI.I	2,100
			ON COST SUMMA			
DENION	BUILDING		SUB-TOTAL	TOTAL	\$/SF	%
		O McCALL MS - CAFETERIA OPTION 2	1			
A10	A1010	OATIONS Standard Foundations	\$0			
	A1020	Special Foundations	\$0			
	A1030	Lowest Floor Construction	\$6,000	\$6,000	\$2.50	2.7%
	711000	Lowest 1 1001 Constitution	\$0,000	ψ0,000	φ2.00	2.170
B10	SUPER	STRUCTURE				
	B1010	Upper Floor Construction	\$24,000			
	B1020	Roof Construction	\$0	\$24,000	\$10.00	10.8%
D	EX/DED	NOD CLOCUPE				
B20	B2010	CIOR CLOSURE	\$0			
	B2020	Exterior Walls Windows/Curtainwall	\$0 \$0			
	B2020	Exterior Doors	\$0 \$0		\$0.00	0.0%
	DZUSU	Exterior Doors	\$0	\$0	\$0.00	0.0%
Взо	ROOFI	NG				
	B3010	Roof Coverings	\$0			
	B3020	Roof Openings	\$0	\$0	\$0.00	0.0%
C10	INTER	IOR CONSTRUCTION				
CIO	C1010	Partitions	\$19,600			
	C1020	Interior Doors	\$0			
	C1030	Specialties/Millwork	\$1,350	\$20,950	\$8.73	9.5%
_						
C20	STAIR		0.0			
	C2010	Stair Construction	\$0			
	C2020	Stair Finishes	\$0	\$0	\$0.00	0.0%
Сзо	INTER	IOR FINISHES				
	C3010	Wall Finishes	\$11,200			
	C3020	Floor Finishes	\$28,100			
	C3030	Ceiling Finishes	\$19,300	\$58,600	\$24.42	26.4%
D10	CONVE	EYING SYSTEMS				
DIO	D1010	Elevator	\$0	\$0	\$0.00	0.0%
			, ,	**	, , , ,	
D20	PLUMI					
	D20	Plumbing	\$0	\$0	\$0.00	0.0%
D30	HVAC					
	D30	HVAC	\$24,000	\$24,000	\$10.00	10.8%
D40	FIRE P	ROTECTION				
540	D40	Fire Protection	\$4,800	\$4,800	\$2.00	2.2%
			- 1,000	T-17,000	÷ 70 0	

07-Feb-17



07-Feb-17

Feasibility Design Estimate GFA 2,400

	BUILDING	SYSTEM	SUB-TOTAL	TOTAL	\$/SF	%
ENOVA	TION TO	O McCALL MS - CAFETERIA OPTION 2				
D50	ELECT	RICAL				
	D5010	Electrical Systems	\$36,000	\$36,000	\$15.00	16.2%
E10	EQUIP	MENT				
	E10	Equipment	\$0	\$0	\$0.00	0.0%
E20	FURNIS	SHINGS				
	E2010	Fixed Furnishings	\$0			
	E2020	Movable Furnishings	NIC	\$0	\$0.00	0.0%
F10	SPECIA	L CONSTRUCTION				
	F10	Special Construction	\$0	\$0	\$0.00	0.0%
F20	SELEC	TIVE BUILDING DEMOLITION				
	F2010	Building Elements Demolition	\$47,310			
	F2020	Hazardous Components Abatement	\$0	\$47,310	\$19.71	21.3%
TOTA	L DIRE	CT COST (Trade Costs)		\$221,660	\$92.36	100.0%



CAFETERIA + DISTRICT OFFICE EXPANSION

Winchester, MA

18 19

20

25

26

27 28

34

35 36

37

38

39 40

46

47 48

49 50 51

52 53

55

Feasibility Design Estimate GFA 2,400

				UNIT	EST'D	SUB	TOTAL
	DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST

RENOVATION TO McCALL MS - CAFETERIA OPTION 2

TOTAL RENOVATED AREA (GFA) 2,400 GSF

A10 FOUNDATIONS

A1010 STANDARD FOUNDATIONS

No work in this section

SUBTOTAL

A1020 SPECIAL FOUNDATIONS

No work in this section $% \left(1\right) =\left(1\right) \left(

SUBTOTAL

A1030 LOWEST FLOOR CONSTRUCTION

Patch existing slab **2,400** sf 2.50 6,000

SUBTOTAL 6,000

TOTAL - FOUNDATIONS \$6,000

B10 SUPERSTRUCTURE

B1010 FLOOR CONSTRUCTION

Infill floor structure at removed stair **800** sf 30.00 24,000

SUBTOTAL 24,000

B1020 ROOF CONSTRUCTION

SUBTOTAL -

TOTAL - SUPERSTRUCTURE \$24,000

B20 EXTERIOR CLOSURE

B2010 EXTERIOR WALLS

No work assumed to existing exterior

SUBTOTAL

B2020 WINDOWS/CURTAINWALL

No work assumed to existing exterior

SUBTOTAL

B2030 EXTERIOR DOORS

No work assumed to existing exterior

SUBTOTAL

TOTAL - EXTERIOR CLOSURE

B30 ROOFING

B3010 ROOF COVERINGS

No work assumed to existing exterior

SUBTOTAL



CAFETERIA + DISTRICT OFFICE EXPANSION

Winchester, MA

56 57

58

59

60

67

68

69

70 71

74

75 76

77

78

79 80

82

84

86

87

88

90

91

92 93

94 95 96

97 98

99

100

101

102 103

104

105

107

108

Feasibility Design Estimate GFA 2,400

				UNIT	EST'D	SUB	TOTAL	ı
	DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST	l

RENOVATION TO McCALL MS - CAFETERIA OPTION 2

B3020 ROOF OPENINGS

No work in this section

SUBTOTAL

TOTAL - ROOFING

C10 INTERIOR CONSTRUCTION

C1010 PARTITIONS

 Patch existing walls
 3,024
 sf
 3.00
 9,072

New partition **658** sf 16.00 10,528

SUBTOTAL 19,600

C1020 INTERIOR DOORS

No work in this section

SUBTOTAL -

C1030 SPECIALTIES / MILLWORK

Room Signs 1 loc 150.00 150

Miccellaneous scalants 2 100 of 0.50 1200

Miscellaneous sealants **2,400** sf 0.50 1,200

SUBTOTAL 1,350

TOTAL - INTERIOR CONSTRUCTION

C2010 STAIR CONSTRUCTION

STAIRCASES

C20

No work in this section

SUBTOTAL -

C2020 STAIR FINISHES

No work in this section

SUBTOTAL

TOTAL - STAIRCASES

C30 INTERIOR FINISHES

C3010 WALL FINISHES

 Paint to walls etc.
 2,400
 gsf
 3.00
 7,200

 Patch/paint existing walls
 1
 ls
 4,000.00
 4,000

SUBTOTAL 11,200

C3020 FLOOR FINISHES

 New resilient flooring
 2,400
 sf
 8.00
 19,200

 Patch existing floor at removed walls
 205
 lf
 20.00
 4,100

 Floor prep
 2,400
 sf
 2.00
 4,800

SUBTOTAL 28,100

\$20,950



CAFETERIA + DISTRICT OFFICE EXPANSION

Winchester, MA

Feasibility Design Estimate GFA 2,400

	DESCRIPTION	OTV	UNIT	UNIT COST	EST'D COST	SUB TOTAL	TOTAL
NOVATION	DESCRIPTION	QTY	UNIT	CUST	CUST	IUIAL	COST
	N TO McCALL MS - CAFETERIA OPTION 2						
C3030	CEILING FINISHES ACT, 2x2	2,400	sf	7.00	16,800		
	Patch existing floor at removed walls	100	lf	25.00	2,500		
	SUBTOTAL	100	11	23.00	2,300	10.200	
	SUBTOTAL					19,300	
	TOTAL - INTERIOR FINISHES						\$58,6
D10	CONVEYING SYSTEMS						
	No work in this section						
	SUBTOTAL					_	
	Septemb						
	TOTAL - CONVEYING SYSTEMS						
D20	PLUMBING						
D20	PLUMBING, GENERALLY						
	No work in this section						
	SUBTOTAL					-	
	TOTAL - PLUMBING						
	TOTAL - I LUMBING						
D30	HVAC	7					
230	TV/IC						
D3o	HVAC, GENERALLY						
	HVAC modifications	2,400	sf	10.00	24,000		
	SUBTOTAL					24,000	
	TOTAL - HVAC						\$24,0
D40	FIRE PROTECTION	7					
Des	EIDE BROTECTION CENERALLY	_					
D40	FIRE PROTECTION, GENERALLY Sprinkler system modifications	2,400	sf	2.00	4,800		
	SUBTOTAL	_,400	31	۵.00	4,000	4,800	
	552.511E					1,000	
	TOTAL - FIRE PROTECTION						\$4,8
D50	ELECTRICAL						
l		_					
D5010	COMPLETE ELECTRICAL SYSTEMS		_				
	Lighting, power and Tele/Data modifications	2,400	sf	15.00	36,000		
	SUBTOTAL					36,000	
							_
1	TOTAL - ELECTRICAL						\$36,0

E10 EQUIPMENT

160 161

162 163

E10 EQUIPMENT, GENERALLY



CAFETERIA + DISTRICT OFFICE EXPANSION

Winchester, MA

164

165

166 167

170

171 172

173

174

175 176

177

178

179 180

181 182 183

184 185

186

187

188 189

190 191 192

196

196

197

199

200 201

202

203

204 205

206

Feasibility Design Estimate GFA 2,400

				UNIT	EST'D	SUB	TOTAL
	DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST

RENOVATION TO McCALL MS - CAFETERIA OPTION 2

No work in this section SUBTOTAL

TOTAL - EQUIPMENT

E20 FURNISHINGS

E2010 FIXED FURNISHINGS

No work in this section

SUBTOTAL

E2020 MOVABLE FURNISHINGS

All movable furnishings to be provided and installed

by owner

SUBTOTAL

TOTAL - FURNISHINGS

F10 SPECIAL CONSTRUCTION

F10 SPECIAL CONSTRUCTION

No items in this section

SUBTOTAL

TOTAL - SPECIAL CONSTRUCTION

F20 SELECTIVE BUILDING DEMOLITION

F2010 BUILDING ELEMENTS DEMOLITION

14,400 Gut demolition; finishes and casework 6.00 2,400 sf Create opening in bearing wall ls 4,500.00 4,500 Remove walls 2,870 sf 3.00 8,610 Remove stair flight and patch/new finishes 15.000.00 15.000 ls Miscellaneous demo/protection 2,400 gfa 2.00 4,800

SUBTOTAL 47,310

F2020 HAZARDOUS COMPONENTS ABATEMENT

None Included SUBTOTAL

TOTAL - SELECTIVE BUILDING DEMOLITION

\$47,310



Feasibility Design Estimate

Winchester Schools CAFETERIA + DISTRICT OFFICE EXPANSION Winchester, MA

relegia MA

		CONSTRUCTI	ON COST SUMMA	ARY		
	BUILDING		SUB-TOTAL	TOTAL	\$/SF	%
DITIO		AFETERIA - OPTION 3				
A10		DATIONS				
	A1010	Standard Foundations	\$184,721			
	A1020	Special Foundations	\$54,250			
	A1030	Lowest Floor Construction	\$56,272	\$295,243	\$193.60	37.4%
A20	BASEM	IENT CONSTRUCTION				
	A2010	Basement Excavation	\$0			
	A2020	Basement Walls	\$0	\$0	\$0.00	0.0%
B10	SUPER	STRUCTURE				
	B1010	Upper Floor Construction	\$0			
	B1020	Roof Construction	\$55,675	\$55,675	\$36.51	7.1%
B20	EXTER	IOR CLOSURE				
	B2010	Exterior Walls	\$0			
	B2020	Windows	\$181,213			
	B2030	Exterior Doors	\$0	\$181,213	\$118.83	22.9%
В30	ROOFI	NG				
0 -	B3010	Roof Coverings	\$34,933			
	B3020	Roof Openings	\$0	\$34,933	\$22.91	4.4%
C10	INTERI	IOR CONSTRUCTION				
	C1010	Partitions	\$0			
	C1020	Interior Doors	\$0			
	C1030	Specialties/Millwork	\$3,431	\$3,431	\$2.25	0.4%
C20	STAIRO	CASES				
	C2010	Stair Construction	\$0			
	C2020	Stair Finishes	\$0	\$0	\$0.00	0.0%
С30	INTERI	IOR FINISHES				
-00	C3010	Wall Finishes	\$6,863			
	C3020	Floor Finishes	\$13,725			
	C3030	Ceiling Finishes	\$10,675	\$31,263	\$20.50	4.0%
D10	CONVE	YING SYSTEMS				
	D1010	Elevator	\$0	\$0	\$0.00	0.0%
D20	PLUME	BING				
	D20	Plumbing	\$7,625	\$7,625	\$5.00	1.0%

07-Feb-17

1,525

GFA



Feasibility Design Estimate

Winchester Schools CAFETERIA + DISTRICT OFFICE EXPANSION Winchester, MA

ETERIA + DISTRICT OFFICE EXPANSION

		CONSTRUCTION	COST SUMMA	ARY		
	HVAC D30 HVAC \$68,6 FIRE PROTECTION D40 Fire Protection \$6,8 ELECTRICAL D5010 Complete System \$38,1 EQUIPMENT E10 Equipment FURNISHINGS E2010 Fixed Furnishings \$8,7 E2020 Movable Furnishings \$8,7 E2020 Movable Furnishings \$8,7 E2020 Movable Furnishings \$8,7 E2020 Movable Furnishings \$8,7 E2020 Movable Furnishings \$8,7 E2020 Movable Furnishings \$8,7 E2020 Movable Furnishings \$8,7 E2020 Movable Furnishings \$8,7 E2020 Movable Furnishings \$8,7 E2020 Movable Furnishings \$8,7 E2020 Movable Furnishings \$8,7 E2020 Movable Furnishings \$8,7 E2020 Movable Furnishings \$8,7 E2020 Movable Furnishings \$8,7 E2020 Movable Furnishings \$8,7 E2020 Movable Furnishings \$8,7 E2020 Movable Furnishings \$8,7 E2020 Movable Furnishings \$8,7		SUB-TOTAL	TOTAL	\$/SF	%
DITIO	ON AT CA	AFETERIA - OPTION 3				
D30	HVAC					
	D30	HVAC	\$68,625	\$68,625	\$45.00	8.7%
D40	FIRE P	ROTECTION				
	D40	Fire Protection	\$6,863	\$6,863	\$4.50	0.9%
D50	ELECT	RICAL				
	D5010	Complete System	\$38,125	\$38,125	\$25.00	4.8%
E10	EQUIP	MENT				
	E10	Equipment	\$0	\$0	\$0.00	0.0%
E20	FURNIS	SHINGS				
	E2010	Fixed Furnishings	\$8,748			
	E2020	Movable Furnishings	NIC	\$8,748	\$5.74	1.1%
F10	SPECIA	AL CONSTRUCTION				
	F10	Special Construction	\$0	\$0	\$0.00	0.0%
F20	HAZMA	AT REMOVALS				
	F2010	Building Elements Demolition	\$57,960			
	F2020	Hazardous Components Abatement	\$0	\$57,960	\$38.01	7.3%
TOT	I DIDE	CT COST (Trada Costs)		\$789,704	\$517.84	100.0%

07-Feb-17

1,525

GFA



3

Feasibility Design Estimate

Winchester Schools CAFETERIA + DISTRICT OFFICE EXPANSION Winchester $M\Delta$

Winchester, MA

CSI				UNIT	EST'D	SUB	TOTAL
CODE	DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST

ADDITION AT CAFETERIA - OPTION ${\bf 3}$

GROSS FLOOR AREA CALCULATION

First Floor 1,525

	TOTAL GROSS FLOOR AREA (GFA)				1,525 sf	
A10	FOUNDATIONS					
A1010	STANDARD FOUNDATIONS Strip footings - 8'-0" x 1'-6"					
	Excavation	178	cy	35.00	6,230	
	Store on site for reuse	178	cy	14.00	2,492	
	Backfill with existing fill	141	cy	16.00	2,256	
	Remove surplus fill off site	37	cy	25.00	925	
	Formwork	240	sf	12.00	2,880	
	Re-bar	4,440	lbs	1.20	5,328	
	Concrete material; 3,000 psi	3 7	cy	125.00	4,625	
	Placing concrete	3 7	cy	55.00	2,035	
	Foundation walls at exterior - 14" thick					
	Formwork	3,200	sf	16.00	51,200	
	Re-bar, 4.5#/sf	7,200	lbs	1.20	8,640	
	Concrete material; 4,000 psi	73	cy	135.00	9,855	
	Placing concrete	73	cy	65.00	4,745	
	Waterproofing foundation wall and footing	1,600	sf	7.00	11,200	
	Insulation to foundation walls; 2" thick	320	sf	2.50	800	
	Form shelf	80	lf	8.00	640	
	Column footings, typical, 6' x 6' x 2'-0"					
	Excavation	94	cy	20.00	1,880	
	Store on site for reuse	94	cy	14.00	1,316	
	Backfill with new fill	72	cy	16.00	1,152	
	Remove surplus fill off site	22	cy	20.00	440	
	Formwork	384	sf	11.00	4,224	
	Re-bar	4,480	lbs	1.20	5,376	
	Concrete material; 3,000 psi	22	cy	125.00	2,750	
	Placing concrete	22	cy	55.00	1,210	
	Set anchor bolts grout plates	8	ea	150.00	1,200	
	Interior pilasters					
	Formwork	234	sf	11.00	2,574	
	Re-bar	1,440	lbs	1.20	1,728	
	Concrete material; 3,000 psi	4	cy	125.00	500	
	Placing concrete	4	cy	55.00	220	
	Work around existing utilities	1	ls	10,000.00	10,000	
	Foundations against face of existing building	33	lf	1,100.00	36,300	
	SUBTOTAL					184,721
A1020	SPECIAL FOUNDATIONS					

07-Feb-17

1,525

GFA



07-Feb-17

	DECCRIPTION	OTT	T TATE	UNIT	EST'D	SUB	TOTAL
CODE	DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST
ADDITION A	T CAFETERIA - OPTION 3					T 4 0 T O	
	SUBTOTAL					54,250	
A1030	LOWEST FLOOR CONSTRUCTION						
	New Slab on grade, 5" thick						
	Structural gravel fill	960	cy	30.00	28,800		
	Rigid insulation	1,525	sf	2.25	3,431		
	Vapor barrier	1,525	sf	1.00	1,525		
	Mesh reinforcing 15% lap	1,754	sf	0.80	1,403		
	Concrete - 5" thick	25	cy	125.00	3,125		
	Placing concrete	25	cy	45.00	1,125		
	Finishing and curing concrete	1,525	sf	4.00	6,100		
	Control joints - saw cut	1,525	sf	0.50	763		
	<u>Miscellaneous</u>						
	Dewatering	1	ea	10,000.00	10,000		
	SUBTOTAL					56,272	
	TOTAL - FOUNDATIONS						\$295,2
A20	BASEMENT CONSTRUCTION	\neg					
7120	ZISZNZVI CONSTRUCTION						
A2010	BASEMENT EXCAVATION						
	No items in this section						
	SUBTOTAL					-	
A2020	BASEMENT WALLS						
	No items in this section						
	SUBTOTAL					-	
	TOTAL - BASEMENT CONSTRUCTION						
В10	SUPERSTRUCTURE						
Pagas	FLOOR CONSTRUCTION						
P1010	No items in this section						
	SUBTOTAL					_	
	SOBTOTAL						
B1020	ROOF CONSTRUCTION						
	Roof Structure - Steel:						
	Steel beams/Joists; 13#/SF	10	tns	4,500.00	45,000		
	Roof Structure						
	1-1/2" Metal floor Deck @ roof	1,525	sf	3.00	4,575		
	<u>Miscellaneous</u>	•					
	Fire proofing to columns, beams and deck	1,525	sf	4.00	6,100		
	SUBTOTAL					55,675	

98



103

104

105

106 107

108

109

110

111 112

113

114

115 116

121 122

123

124

125

126

127

128

129

130

131 132

133

134

135 136

137 138 139

140 141

142

143

144 145

146

147

148 149

150

151

Feasibility Design Estimate

Winchester Schools CAFETERIA + DISTRICT OFFICE EXPANSION Winchester, MA

CSI				UNIT	EST'D	SUB	TOTAL
CODE	DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST

ADDITION	AT CAFETERIA	- OPTION o

B20	EXTERIOR CLOSURE

B2010 EXTERIOR WALLS

No items in this section

SUBTOTAL

B2020 WINDOWS

Curtainwall 120.00 174,960 1,458 sf Backer rod & double sealant lf 9.00 4,329 481 Wood blocking at openings 481 lf 4.00 1,924

SUBTOTAL 181,213

B2030 EXTERIOR DOORS

No items in this section

SUBTOTAL

TOTAL - EXTERIOR CLOSURE

\$181,213

B30	ROOFING	

B3010 ROOF COVERINGS

Flat roofing

PVC roof membrane fully adhered 8.00 12,200 1,525 sf Insulation 7.00 10,675 1,525 sf 1/2" dens-deck protection board 2.00 sf 3,050 1,525 Reinforced vapor barrier 1,525 sf 1.50 2,288 Rough blocking lf 6.00 1,920 320 Miscellaneous Roofing

Roof fascia/cornice 60.00 80 lf 4,800 SUBTOTAL

B3020 ROOF OPENINGS

Skylights, allow NIC

SUBTOTAL

TOTAL - ROOFING \$34,933

INTERIOR CONSTRUCTION C10

C1010 PARTITIONS

No items in this section

SUBTOTAL

C1020 INTERIOR DOORS

No items in this section

SUBTOTAL

C1030 SPECIALTIES / MILLWORK

Miscellaneous metals throughout building 1.25 1.906 1,525 sf Miscellaneous sealants throughout building 1.00 1,525 sf 1,525

34,933

07-Feb-17

1,525

GFA



153 154

155 156 157

158 159

160

161

162 163

164

165

166 167

168 169 170

171

172 173

174

175 176

177

178

179

180 181

182

183

184

185 186 187

188 189

190

191

192 193

194 195 196

197

199

200

201 202

203 204 205

206 207

208

Winchester Schools
CAFETERIA + DISTRICT OFFICE EXPANSION
Winchester, MA

CAFETERIA + DISTRICT OFFICE EXPANSION
Winchester, MA

Feasibility Design Estimate				GFA	1,525
CSI		UNIT	EST'D	SUB	TOTAL

CODE DESCRIPTION QTY UNIT COST COST TOTAL COST	CSI				UNIT	EST'D	SUB	TOTAL
	CODE	DESCRIPTION	OTV	UNIT	COST	COST	TOTAL	COST

ADDITION AT CAFETERIA - OPTION 3

SUBTOTAL 3,431

TOTAL - INTERIOR CONSTRUCTION \$3,431

C20 STAIRCASES

C2010 STAIR CONSTRUCTION

No items in this section

SUBTOTAL -

C2020 STAIR FINISHES

No items in this section

SUBTOTAL -

TOTAL - STAIRCASES

C30 INTERIOR FINISHES

C3010 WALL FINISHES

 Wall finishes
 1,525
 gfa
 4.50
 6,863

 SUBTOTAL
 6,863

C3020 FLOOR FINISHES

Floor finishes **1,525** sf 9.00 13,725

SUBTOTAL 13,725

C3030 CEILING FINISHES

Ceiling finishes **1,525** sf 7.00 10,675

SUBTOTAL 10,675

TOTAL - INTERIOR FINISHES \$31,263

D10 CONVEYING SYSTEMS

D1010 ELEVATOR

No items in this section

SUBTOTAL -

TOTAL - CONVEYING SYSTEMS

D20 PLUMBING

D20 PLUMBING, GENERALLY

Plumbing allowance **1,525** gsf 5.00 7,625

SUBTOTAL 7,625

TOTAL - PLUMBING \$7,625

D30 HVAC

D30 HVAC, GENERALLY

HVAC complete system **1,525** gsf 45.00 68,625



210 211

212 213 214

215 216

217

218

219 220

221 222 223

224 225

226

227

228 229 230

231 232 233

234 235

238

243 244

245

246

247 248

249

250

251 252

253 254 255

256 257

258

259

260 261

263 264

265

Feasibility Design Estimate

Winchester Schools
CAFETERIA + DISTRICT OFFICE EXPANSION
Winchester, MA

Winchester, MA

CSI				UNIT	EST'D	SUB	TOTAL
CODE	DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST

ADDITION AT CAFETERIA - OPTION 3

SUBTOTAL 68,625

TOTAL - HVAC \$68,625

D40 FIRE PROTECTION

D40 FIRE PROTECTION, GENERALLY

Sprinkler system **1,525** gsf 4.50 6,863

SUBTOTAL 6,863

TOTAL - FIRE PROTECTION \$6,863

D50 ELECTRICAL

D5010 COMPLETE ELECTRICAL SYSTEM

Electrical system; complete **1,525** gsf 25.00 38,125

SUBTOTAL 38,125

TOTAL - ELECTRICAL \$38,125

E10 EQUIPMENT

E10 EQUIPMENT, GENERALLY

AV Equipment (including Smartboards, Projectors, FF+E LED monitors, Digital information displays etc.)

SUBTOTAL

SUBIOTAL

TOTAL - EQUIPMENT

E20 FURNISHINGS

E2010 FIXED FURNISHINGS

Manual operated roller shades 1,458 sf 6.00 8,748

SUBTOTAL 8,748

E2020 MOVABLE FURNISHINGS

All movable furnishings to be provided and installed

by owner

SUBTOTAL

TOTAL - FURNISHINGS \$8,748

F10 SPECIAL CONSTRUCTION

F10 SPECIAL CONSTRUCTION

No Work in this section

SUBTOTAL

TOTAL - SPECIAL CONSTRUCTION

F20 SELECTIVE BUILDING DEMOLITION

07-Feb-17

1,525

GFA



Feasibility Design Estimate

Winchester Schools CAFETERIA + DISTRICT OFFICE EXPANSION Winchester, MA

TOTAL - SELECTIVE BUILDING DEMOLITION

Winchester, MA

CS	21		I		UNIT	EST'D	SUB	TOTAL
	ODE	DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST
Al	DDITION AT	CAFETERIA - OPTION 3	•				1	
266	F2010	BUILDING ELEMENTS DEMOLITION						
267		Create openings to existing façade for new connections	864	sf	15.00	12,960		
268		Demolish existing patio and steps	1	ls	20,000.00	20,000		
269		Relocate existing utilities	1	ls	15,000.00	15,000		
270		Restore/new landscaping	1	ls	10,000.00	10,000		
271		SUBTOTAL					57,960	
272								
273	F2020	HAZARDOUS COMPONENTS ABATEMENT						
274		None Included						
275		SUBTOTAL						
276								

07-Feb-17

1,525

\$57,960

GFA



Winchester Schools 07-Feb-17

CAFETERIA + DISTRICT OFFICE EXPANSION

Winchester, MA

Feasibility Design Estimate GFA 1,250

				UNIT	EST'D	SUB	TOTAL	
	DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST	

RENOVATION TO McCALL MS - TEACHERS ROOM

TOTAL RENOVATED AREA (GFA)				1,250 GS	F	
INTERIOR CONSTRUCTION						
PARTITIONS						
New walls at storage area	403	sf	15.00	6,045		
SUBTOTAL					6,045	
INTERIOR DOORS						
New single door	1	ea	1,800.00	1,800		
SUBTOTAL					1,800	
SPECIALTIES / MILLWORK						
Room Signs	1	loc	150.00	150		
Miscellaneous sealants	1,250	sf	0.50	625		
SUBTOTAL					775	
TOTAL - INTERIOR CONSTRUCTION						\$8,62
INTERIOR FINISHES	\neg					
	INTERIOR CONSTRUCTION PARTITIONS New walls at storage area SUBTOTAL INTERIOR DOORS New single door SUBTOTAL SPECIALTIES / MILLWORK Room Signs Miscellaneous sealants SUBTOTAL TOTAL - INTERIOR CONSTRUCTION	INTERIOR CONSTRUCTION PARTITIONS New walls at storage area 403 SUBTOTAL INTERIOR DOORS New single door 1 SUBTOTAL SPECIALTIES / MILLWORK Room Signs 1 Miscellaneous sealants 1,250 SUBTOTAL TOTAL - INTERIOR CONSTRUCTION	INTERIOR CONSTRUCTION PARTITIONS New walls at storage area 403 sf SUBTOTAL INTERIOR DOORS New single door 1 ea SUBTOTAL SPECIALTIES / MILLWORK Room Signs 1 loc Miscellaneous sealants 1,250 sf SUBTOTAL TOTAL - INTERIOR CONSTRUCTION	INTERIOR CONSTRUCTION PARTITIONS New walls at storage area 403 sf 15.00 SUBTOTAL INTERIOR DOORS New single door 1 ea 1,800.00 SUBTOTAL SPECIALTIES / MILLWORK Room Signs 1 loc 150.00 Miscellaneous sealants 1,250 sf 0.50 SUBTOTAL TOTAL - INTERIOR CONSTRUCTION	INTERIOR CONSTRUCTION	INTERIOR CONSTRUCTION

C3010	WALL FINISHES Paint to walls etc. SUBTOTAL	1,250	gsf	3.00	3,750	3,750
C3020	FLOOR FINISHES					
	New resilient flooring	1,250	sf	8.00	10,000	
	Floor prep	1,250	sf	2.00	2,500	
	SUBTOTAL					12,500
C3030	CEILING FINISHES					
	No items in this section					

TOTAL INTERIOR FINICIPO		
TOTAL - INTERIOR FINISHES \$16,25	AL - INTERIOR FINISHES	\$16,250

Dog HVAC	

D3o	HVAC, GENERALLY	
	No items in this section	
	SUBTOTAL	-

TOTAL -	HVAC	

D40	FIRE PROTECTION]			
D40	FIRE PROTECTION, GENERALLY Sprinkler system modifications	1,250	sf	2.00	2,500

SUBTOTAL 2,500

SUBTOTAL



Winchester Schools 07-Feb-17

CAFETERIA + DISTRICT OFFICE EXPANSION

Winchester, MA

55 56

57 58 59

60 61

62

63

64 65

67 68

69 70

71

73 74

75

76

77

78 79 80

86

91

92

93

92

Feasibility Design Estimate GFA 1,250

			UNIT	EST'D	SUB	TOTAL
DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST

RENOVATION TO McCALL MS - TEACHERS ROOM

TOTAL - FIRE PROTECTION \$2,500

D50 ELECTRICAL

D5010 COMPLETE ELECTRICAL SYSTEMS

Lighting, power and Tele/Data modifications 1,250 sf 15.00 18,750

SUBTOTAL 18,750

TOTAL - ELECTRICAL \$18,750

E20 FURNISHINGS

E2010 FIXED FURNISHINGS

No work in this section

SUBTOTAL -

E2020 MOVABLE FURNISHINGS

All movable furnishings to be provided and installed

by owner

SUBTOTAL

TOTAL - FURNISHINGS

F20 SELECTIVE BUILDING DEMOLITION

F2010 BUILDING ELEMENTS DEMOLITION

 Gut demolition; floor finishes
 1,250
 sf
 1.00
 1,250

SUBTOTAL 1,250

F2020 HAZARDOUS COMPONENTS ABATEMENT

None Included SUBTOTAL

TOTAL - SELECTIVE BUILDING DEMOLITION

TOTAL - TEACHERS ROOM \$47,370

Winchester Schools Cafeteria + District Office Expansions 2.7.17

\$1,250



Feasibility Design Estimate

Winchester Schools
CAFETERIA + DISTRICT OFFICE EXPANSION
Winchester MA

Winchester, MA

	BUILDING	SYSTEM	ON COST SUMMA SUB-TOTAL	TOTAL	\$/SF	%
STRIC	T OFFIC	CE ADDITION TO LYNCH OPTION	WPS-1		.,	
A10	FOUND	DATIONS				
	A1010	Standard Foundations	\$148,669			
	A1020	Special Foundations	\$0			
	A1030	Lowest Floor Construction	\$65,553	\$214,222	\$43.72	15.5%
A20	BASEM	IENT CONSTRUCTION				
	A2010	Basement Excavation	\$0			
	A2020	Basement Walls	\$0	\$0	\$0.00	0.0%
B10	SUPER	STRUCTURE				
	B1010	Upper Floor Construction	\$0			
	B1020	Roof Construction	\$144,500	\$144,500	\$29.49	10.5%
B20	EXTER	IOR CLOSURE				
	B2010	Exterior Walls	\$133,595			
	B2020	Windows	\$110,011			
	B2030	Exterior Doors	\$16,520	\$260,126	\$53.09	18.89
В30	ROOFI	NG				
	B3010	Roof Coverings	\$106,330			
	B3020	Roof Openings	\$0	\$106,330	\$21.70	7.79
C10	INTERI	IOR CONSTRUCTION				
	C1010	Partitions	\$139,838			
	C1020	Interior Doors	\$66,000			
	C1030	Specialties/Millwork	\$20,297	\$226,135	\$46.15	16.49
C20	STAIR	CASES				
	C2010	Stair Construction	\$0			
	C2020	Stair Finishes	\$0	\$0	\$0.00	0.0%
С30	INTERI	IOR FINISHES				
	C3010	Wall Finishes	\$29,646			
	C3020	Floor Finishes	\$32,437			
	C3030	Ceiling Finishes	\$23,540	\$85,623	\$17.47	6.29
D10	CONVE	YING SYSTEMS				
	D1010	Elevator	\$0	\$0	\$0.00	0.09
D20	PLUME	BING				
	D20	Plumbing	\$30,000	\$30,000	\$6.12	2.29

07-Feb-17

4,900

GFA



07-Feb-17

Feasibility Design Estimate GFA 4,900

	DITTI DING				ø/CE	%
STRIC				TOTAL	<i>\$/δΓ</i>	70
D30	HVAC					
	D30	HVAC	\$137,200	\$137,200	\$28.00	9.9%
DISTRICT OFFICE ADDITION TO LYNCH OPTION WPS-1 D30 HVAC \$137,200 \$137,200 \$28.00 D40 FIRE PROTECTION \$19,600 \$19,600 \$4.00 D50 ELECTRICAL \$107,800 \$107,800 \$22.00 E10 EQUIPMENT \$0 <th< td=""><td></td></th<>						
	D40	Fire Protection	\$19,600	\$19,600	\$4.00	1.4%
D50	ELECTI	RICAL				
	D5010	Complete System	\$107,800	\$107,800	\$22.00	7.8%
E10	EQUIP	MENT				
	E10	Equipment	\$0	\$0	\$0.00	0.0%
E20	FURNIS	SHINGS				
	E2010	Fixed Furnishings	\$24,342			
	E2020	Movable Furnishings	NIC	\$24,342	\$4.97	1.8%
F10 S	SPECIA	L CONSTRUCTION				
	F10	Special Construction	\$0	\$0	\$0.00	0.0%
D50 H H H H H H H H H H H H H H H H H H H	HAZMA	AT REMOVALS				
	F2010	Building Elements Demolition	\$25,000			
	F2020	Hazardous Components Abatement	\$0	\$25,000	\$5.10	1.8%
				h0- 0 0	4.0.0	0/



3

Feasibility Design Estimate GFA 4,900

CSI				UNIT	EST'D	SUB	TOTAL
CODE	DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST

DISTRICT OFFICE ADDITION TO LYNCH OPTION WPS-1

		AREA			

First Floor 4,900

	FIISUF	1001		4,900		
	TOTAL GROSS FLOOR AREA (GFA)				4,900 sf	
A10	FOUNDATIONS					
A1010	STANDARD FOUNDATIONS Strip footings - 2'-0" x 1'-0"					
	Excavation	244	cy	20.00	4,880	
	Store on site for reuse	244	cy	14.00	3,416	
	Backfill with existing fill	227	cy	16.00	3,632	
	Remove surplus fill off site	17	cy	25.00	425	
	Formwork	440	sf	12.00	5,280	
	Re-bar, 10#/lf	2,200	lbs	1.20	2,640	
	Concrete material; 3,000 psi	17	cy	125.00	2,125	
	Placing concrete	17	cy	55.00	935	
	Foundation walls at exterior - 14" thick					
	Formwork	1,760	sf	14.00	24,640	
	Re-bar, 4.5#/sf	3,960	lbs	1.20	4,752	
	Concrete material; 4,000 psi	40	cy	135.00	5,400	
	Placing concrete	40	cy	65.00	2,600	
	Dampproofing foundation wall and footing	1,320	sf	1.90	NIC	
	Insulation to foundation walls; 2" thick	880	sf	2.50	2,200	
	Form shelf	220	lf	8.00	1,760	
	Column footings, typical, 5' x 5' x 2'-0"					
	Excavation	285	сy	20.00	5,700	
	Store on site for reuse	285	сy	14.00	3,990	
	Backfill with new fill	227	сy	16.00	3,632	
	Remove surplus fill off site	58	cy	20.00	1,160	
	Formwork	1,200	sf	11.00	13,200	
	Re-bar	8,120	lbs	1.20	9,744	
	Concrete material; 3,000 psi	58	су	125.00	7,250	
	Placing concrete	58	cy	55.00	3,190	
	Set anchor bolts grout plates	30	ea	150.00	4,500	
	Interior pilasters	J			•	
	Formwork	878	sf	11.00	9,658	
	Re-bar	5,400	lbs	1.20	6,480	
	Concrete material; 3,000 psi	16	су	125.00	2,000	
	Placing concrete	16	cy	55.00	880	
	Foundations against existing building	70	lf	180.00	12,600	
	SUBTOTAL	,3		3.00	,000	148,669
						,000
A1020	SPECIAL FOUNDATIONS					
	No Work in this section					

SUBTOTAL

48

49 50

A1030 LOWEST FLOOR CONSTRUCTION



Feasibility Design Estimate GFA 4,900

SI		Discontinuo	O.TTV		UNIT	EST'D	SUB	TOTAL
ODE		DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST
DISTE	RICT OF	FICE ADDITION TO LYNCH OPTION WPS-1						
		New Slab on grade, 5" thick						
		Structural gravel fill, 8"	121	cy	30.00	3,630		
		Base course, 8" gravel	121	cy	40.00	4,840		
		Rigid insulation	4,900	sf	2.25	11,025		
		Vapor barrier	4,900	sf	1.00	4,900		
		Mesh reinforcing 15% lap	5,635	sf	0.80	4,508		
		Concrete - 5" thick	80	cy	125.00	10,000		
		Placing concrete	80	cy	45.00	3,600		
		Finishing and curing concrete	4,900	sf	4.00	19,600		
		Control joints - saw cut	4,900	sf	0.50	2,450		
		Miscellaneous						
		Dewatering	1	ea	1,000.00	1,000		
		SUBTOTAL					65,553	
		TOTAL - FOUNDATIONS						\$214
ı								
	A20	BASEMENT CONSTRUCTION						
	10010	DACEMENTE EXCAVATION						
	A2010	BASEMENT EXCAVATION No items in this section						
		SUBTOTAL					_	
		SOBIOTAL						
	A2020	BASEMENT WALLS						
		No items in this section						
		SUBTOTAL					-	
		TOTAL - BASEMENT CONSTRUCTION						
	B10	SUPERSTRUCTURE						
-			12	lbs/sf				
	B1010	FLOOR CONSTRUCTION	29	tns				
		No Work in this section						
		SUBTOTAL					-	
	P1000	ROOF CONSTRUCTION						
	Б1020	Roof Structure - Steel:						
		Steel beams/Joists; 12#/SF	90	tne	3,800.00	110 200		
		Roof Structure	29	tns	3,800.00	110,200		
				C	0.00	14.700		
		1-1/2" Metal floor Deck @ roof	4,900	sf	3.00	14,700		
		Miscellaneous Description of the state of t						
		Roof screen framing - allow		•		NIC		
		Fire proofing to columns, beams and deck	4,900	sf	4.00	19,600		
		SUBTOTAL					144,500	



Feasibility Design Estimate GFA 4,900

CSI				UNIT	EST'D	SUB	TOTAL
CODE	DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST

DISTRICT OFFICE ADDITION TO LYNCH OPTION WPS-1

Dooro	EVTEDIOD WALLS, 60% solid/40% gloss	1,848	sf				
D2010	EXTERIOR WALLS; 60% solid/40% glass Interior skin	1,040	SI				
	6" metal stud backup	1,848	sf	7.50	13,860		
	Batt insulation in stud	1,848	sf	2.25	4,158		
	2 1/2" Rigid Insulation	1,848	sf	3.00	5,544		
	Air barrier	1,848	sf	6.00	11,088		
	Air barrier/flashing at windows	407	lf	7.00	2,849		
	Gypsum Sheathing	1,848	sf	2.75	5,082		
	Drywall lining to interior face of stud backup	1,848	sf	3.00	5,544		
	Exterior skin						
	Brick veneer; 75% of exterior wall	1,386	sf	35.00	48,510		
	Metal panels; 25% of exterior wall	462	sf	60.00	27,720		
	<u>Miscellaneous</u>						
	Staging to exterior wall	3,080	sf	3.00	9,240		
	SUBTOTAL					133,595	
B2020	WINDOWS	1,232	sf				
	Premium for sunscreen and light shelf elements	1	ls		NIC		
	Windows/storefront	1,232	sf	85.00	104,720		
	Backer rod & double sealant	407	lf	9.00	3,663		
	Wood blocking at openings	407	lf	4.00	1,628		
	SUBTOTAL					110,011	
B2030	EXTERIOR DOORS						
	Glazed entrance doors including frame and hardware; double door at corridor exit	2	pr	8,000.00	16,000		
	Backer rod & double sealant	40	lf	9.00	360		
	Wood blocking at openings	40	lf	4.00	160		
	SUBTOTAL					16,520	

TOTAL - EXTERIC	R CLOSURE	\$260,126

Взо	ROOFING					
B3010	ROOF COVERINGS Flat roofing					
	PVC roof membrane fully adhered	4,900	sf	9.00	44,100	
	Insulation	4,900	sf	7.00	34,300	
	1/2" dens-deck protection board	4,900	sf	2.00	9,800	
	Reinforced vapor barrier	4,900	sf	1.50	7,350	
	Rough blocking	880	lf	6.00	5,280	
	Miscellaneous Roofing					
	Roof screens - allow				NIC	
	Roof fascia/cornice	220	lf	25.00	5,500	
	SUBTOTAL					106,330



Winchester Schools CAFETERIA + DISTRICT OFFICE EXPANSION

Winchester, MA

148 149

150

151

152 153

154 155 156

157 158

159

160

161

162

163

164

165

166 167

168

169

170

171 172

173

174

175

176

177

178

179 180

181 182 183

184

185 186

187

188 189

190

191

192 193

194 195 196

197 198

199

200

Feasibility Design Estimate	GFA	4,900

CSI				UNIT	EST'D	SUB	TOTAL
CODE	DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST

DISTRICT OFFICE ADDITION TO LYNCH OPTION WPS-1

B3020	ROOF	OPENINGS
-------	------	-----------------

NIC Skylights, allow Roof hatch NIC

SUBTOTAL

TOTAL - ROOFING \$106,330

12.00

12.600

sf

C10 INTERIOR CONSTRUCTION

GWB furred wall at existing exterior wall

C1010 PARTITIONS

Corridors; GWB with 2 lyrs corridor side 4,860 sf 15.55 75,573 General Walls; GWB with 1 lyrs each side 13.75 46,613 3,390 sf Sealants & caulking at partitions 4,860 sf 0.50 2,430 Rough blocking to partitions lf 3.00 1,122 374 Glazed partitions/borrowed lights - allowance ls 1,500.00 1,500

SUBTOTAL 139,838

1,050

C1020 INTERIOR DOORS

8,000 Corridor glazed doors pr 8,000.00 Single door with sidelight 2,900.00 58,000 20 ea

SUBTOTAL 66,000

C1030 SPECIALTIES / MILLWORK

Marker boards/tackboards in conference room 128 sf 24.00 3,072 Toilet partitions and accessories 2,000.00 4,000 2 rooms Room Signs 20 loc 110.00 2,200 Miscellaneous metals throughout building sf 1.25 6,125 4,900 Miscellaneous sealants throughout building 1.00 4,900 4,900 sf

SUBTOTAL 20,297

TOTAL - INTERIOR CONSTRUCTION \$226,135

C20 **STAIRCASES**

C2010 STAIR CONSTRUCTION

No Work in this section

SUBTOTAL

C2020 STAIR FINISHES

No Work in this section

SUBTOTAL

TOTAL - STAIRCASES

INTERIOR FINISHES Сзо

C3010 WALL FINISHES

Paint to GWB 1.00 17,550 17,550 sf Ceramic Tile to toilets 24.00 12,096 504 sf



Feasibility Design Estimate GFA 4,900

	inty Design	n Estimate					GFA	4,8
SSI SODE		DESCRIPTION	QTY	UNIT	UNIT COST	EST'D COST	SUB TOTAL	TOTAL COST
DISTE	RICT OF	FICE ADDITION TO LYNCH OPTION WPS-1						
		SUBTOTAL					29,646	
	C3020	FLOOR FINISHES						
		Carpet floor finishes	2,675	sf	5.00	13,375		
		Resilient floor	1,913	sf	6.50	12,435		
		Ceramic Tile to toilets	120	sf	25.00	3,000		
		Rubber base	1,319	lf	2.75	3,627		
		SUBTOTAL					32,437	
	C3030	CEILING FINISHES						
	-0-0-	Allowance for ceiling finishes; 2 x 2 ACT	4,708	sf	5.00	23,540		
		SUBTOTAL					23,540	
Ī		TOTAL - INTERIOR FINISHES						\$85,6
L								
ſ	D10	CONVEYING SYSTEMS						
L								
	D1010	ELEVATOR No Work in this section						
		SUBTOTAL					_	
r								
		TOTAL - CONVEYING SYSTEMS						
Г								
Ĺ	D20	PLUMBING						
	D20	PLUMBING, GENERALLY New fixtures	6	fxt	5,000.00	30,000		
		SUBTOTAL					30,000	
Γ		TOTAL - PLUMBING						#20.0
		IOIAL - PLUMBING						\$30,0
Γ	Dag	HVAC						
Ĺ	D30	IIVAC						
	D30	HVAC, GENERALLY						
		HVAC complete system	4,900	gsf	28.00	137,200		
		SUBTOTAL					137,200	
		TOTAL - HVAC						\$137,2
[D40	FIRE PROTECTION						
	D40	FIRE PROTECTION, GENERALLY						
	-	Sprinkler system	4,900	gsf	4.00	19,600		
		SUBTOTAL					19,600	
		TOTAL - FIRE PROTECTION						\$19,6
	D50	ELECTRICAL						
	D5010	COMPLETE ELECTRICAL SYSTEM						

SUBTOTAL

Electrical system; complete

256

257

258

4,900

gsf

22.00

107,800

107,800



264 265

266

267

268 269

270 271 272

273 274

275

276

277

278

279 280

281

282

283 284

285 286 287

288 289

290

291

292 293

294 295 296

297 298

299

300

301 302

303

304

305 306

Winchester Schools CAFETERIA + DISTRICT OFFICE EXPANSION

Winchester, MA

Feas	bility Design Estimate					GFA	4,900
CSI				UNIT	EST'D	SUB	TOTAL
CODI	DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST

DISTRICT OFFICE	ADDITION TO LYNCH	OPTION WPS-1

TOTAL - ELECTRICAL	\$107,800
	\$107,80

EQUIPMENT E10

E10 **EQUIPMENT, GENERALLY**

> AV Equipment (including Smartboards, Projectors, LED monitors, Digital information displays etc.)

SUBTOTAL

TOTAL - EQUIPMENT

E20 **FURNISHINGS**

E2010 FIXED FURNISHINGS

Entry mats & frames - recessed with carpet/rubber 45.00 2,250 sf 50 strips Manual operated roller shades 6.00 7,392 1,232 sf Miscellaneous casework 4,900 gsf 3.00 14,700

SUBTOTAL 24,342

E2020 MOVABLE FURNISHINGS

All movable furnishings to be provided and installed

by owner

SUBTOTAL NIC

TOTAL - FURNISHINGS \$24,342

FF+E

SPECIAL CONSTRUCTION F10

SPECIAL CONSTRUCTION F10

No Work in this section

SUBTOTAL

TOTAL - SPECIAL CONSTRUCTION

SELECTIVE BUILDING DEMOLITION F20

F2010 BUILDING ELEMENTS DEMOLITION

Create openings to existing façade for new 25,000.00 25,000 loc

connections

SUBTOTAL 25,000

F2020 HAZARDOUS COMPONENTS ABATEMENT

None Included SUBTOTAL

TOTAL - SELECTIVE BUILDING DEMOLITION

\$25,000

07-Feb-17



Feasibility Design Estimate

Winchester Schools
CAFETERIA + DISTRICT OFFICE EXPANSION
Winchester MA

Winchester, MA

	BUILDING		ON COST SUMMA SUB-TOTAL	TOTAL	\$/SF	%			
TRIC		E ADDITION TO NEW LYNCH OP	TION WPS-2	TOTAL	φ/31	/0			
A10		OATIONS							
1110	A1010	Standard Foundations	\$136,069						
	A1020	Special Foundations	\$0						
	A1030	Lowest Floor Construction	\$65,553	\$201,622	\$41.15	15.7			
A20	BACEM	ENT CONSTRUCTION							
A20	A2010	Basement Excavation	\$0						
	A2010	Basement Walls	\$0 \$0	¢.	\$0.00	0.0			
	AZUZU	basement wans	\$0	\$0	\$0.00	0.0			
B10		STRUCTURE							
	B1010	Upper Floor Construction	\$0						
	B1020	Roof Construction	\$135,800	\$135,800	\$27.71	10.69			
B20	EXTER	IOR CLOSURE							
	B2010	Exterior Walls	\$92,308						
	B2020	Windows	\$75,988						
	B2030	Exterior Doors	\$16,520	\$184,816	\$37.72	14.4			
B30	ROOFING								
-0-	B3010	Roof Coverings	\$106,330						
	B3020	Roof Openings	\$0	\$106,330	\$21.70	8.3			
C10	INTERI	OR CONSTRUCTION							
CIO	C1010	Partitions	\$139,838						
	C1020	Interior Doors	\$66,000						
	C1020	Specialties/Millwork	\$20,297	\$226,135	\$46.15	17.6			
C20	STAIRO	PACEC							
C20	C2010	Stair Construction	\$0						
	C2010	Stair Finishes	\$0 \$0	\$0	\$0.00	0.0			
~									
C30		OR FINISHES	+00.010						
	C3010	Wall Finishes	\$29,646						
	C3020	Floor Finishes	\$32,437						
	C3030	Ceiling Finishes	\$23,540	\$85,623	\$17.47	6.7			
D10		YING SYSTEMS							
	D1010	Elevator	\$0	\$0	\$0.00	0.0			
D20	PLUME	BING							

07-Feb-17

4,900

GFA



Feasibility Design Estimate GFA 4,900

		CONSTRUCTION	COST SUMM	ARY		
	BUILDING		SUB-TOTAL	TOTAL	\$/SF	%
DISTRIC		E ADDITION TO NEW LYNCH OPTIO	N WPS-2			
D30	HVAC					
	D30	HVAC	\$137,200	\$137,200	\$28.00	10.7%
D40	FIRE P	ROTECTION				
	D40	Fire Protection	\$19,600	\$19,600	\$4.00	1.5%
D50	ELECT	RICAL				
	D5010	Complete System	\$107,800	\$107,800	\$22.00	8.4%
E10	EQUIP	MENT				
	E10	Equipment	\$0	\$0	\$0.00	0.0%
E20	FURNI	SHINGS				
	E2010	Fixed Furnishings	\$22,056			
	E2020	Movable Furnishings	NIC	\$22,056	\$4.50	1.7%
F10	SPECIA	AL CONSTRUCTION				
	F10	Special Construction	\$0	\$0	\$0.00	0.0%
F20	HAZMA	AT REMOVALS				
	F2010	Building Elements Demolition	\$25,000			
	F2020	Hazardous Components Abatement	\$0	\$25,000	\$5.10	2.0%
TOTA	AL DIRE	CT COST (Trade Costs)		\$1,281,982	\$261.63	100.0%



Feasibility Design Estimate

Winchester Schools CAFETERIA + DISTRICT OFFICE EXPANSION Winchester, MA

CSI				UNIT	EST'D	SUB	TOTAL
CODE	DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST

DISTRICT OFFICE ADDITION TO NEW LYNCH OPTION WPS-2

		CALCUL	

		First Floor			4,900		
	TOTAL GROSS FLOOR AREA (GFA)					4,900 sf	
A10	FOUNDATIONS						
	STANDARD FOUNDATIONS Strip footings - 2'-0" x 1'-0"						
	Excavation	2	244	cy	20.00	4,880	
	Store on site for reuse	2	244	сy	14.00	3,416	
	Backfill with existing fill	:	227	сy	16.00	3,632	
	Remove surplus fill off site		17	сy	25.00	425	
	Formwork	4	40	sf	12.00	5,280	
	Re-bar, 10#/lf	2,2	00	lbs	1.20	2,640	
	Concrete material; 3,000 psi		17	сy	125.00	2,125	
	Placing concrete		17	сy	55.00	935	
	Foundation walls at exterior - 14" thick						
	Formwork	1,7	760	sf	14.00	24,640	
	Re-bar, 4.5#/sf	3,9	60	lbs	1.20	4,752	
	Concrete material; 4,000 psi		40	cy	135.00	5,400	
	Placing concrete		40	cy	65.00	2,600	
	Dampproofing foundation wall and footing	1,3	20	sf	1.90	NIC	
	Insulation to foundation walls; 2" thick	8	80	sf	2.50	2,200	
	Form shelf	2	220	lf	8.00	1,760	
	Column footings, typical, 5' x 5' x 2'-0"						
	Excavation	2	285	cy	20.00	5,700	
	Store on site for reuse	2	285	сy	14.00	3,990	
	Backfill with new fill	:	227	сy	16.00	3,632	
	Remove surplus fill off site		58	cy	20.00	1,160	
	Formwork	1,2	200	sf	11.00	13,200	
	Re-bar	8,1	120	lbs	1.20	9,744	
	Concrete material; 3,000 psi		58	cy	125.00	7,250	
	Placing concrete		58	cy	55.00	3,190	
	Set anchor bolts grout plates		30	ea	150.00	4,500	
	<u>Interior pilasters</u>						
	Formwork	8	3 78	sf	11.00	9,658	
	Re-bar	5,4	00	lbs	1.20	6,480	
	Concrete material; 3,000 psi		16	cy	125.00	2,000	
	Placing concrete		16	cy	55.00	880	
	SUBTOTAL						136,069
A1000	SPECIAL FOUNDATIONS						
A1020	No Work in this section						
	SUBTOTAL						

A1030 LOWEST FLOOR CONSTRUCTION

New Slab on grade, 5" thick

49 50 07-Feb-17

4,900

GFA



67 68

70

71

72 73

74

75

76 77

78

81 82

83

84

85 86 87

88

89 90

91

92

93

95 96

97 98

Winchester Schools CAFETERIA + DISTRICT OFFICE EXPANSION Winchester, MA

07-Feb-17

Feasibility 1	Design Estimate					GFA	4,900
CODE CODE	DESCRIPTION	QTY	UNIT	UNIT COST	EST'D COST	SUB TOTAL	TOTAL COST
DISTRIC	FOFFICE ADDITION TO NEW LYNCH OPTI	ON WPS-2		"		1	
	Structural gravel fill, 8"	121	cy	30.00	3,630		
	Base course, 8" gravel	121	cy	40.00	4,840		
	Rigid insulation	4,900	sf	2.25	11,025		
	Vapor barrier	4,900	sf	1.00	4,900		
	Mesh reinforcing 15% lap	5,635	sf	0.80	4,508		
	Concrete - 5" thick	80	cy	125.00	10,000		
	Placing concrete	80	сy	45.00	3,600		
	Finishing and curing concrete	4,900	sf	4.00	19,600		
	Control joints - saw cut	4,900	sf	0.50	2,450		
	<u>Miscellaneous</u>						
	Dewatering	1	ea	1,000.00	1,000		
	SUBTOTAL					65,553	
	TOTAL - FOUNDATIONS						\$201,622
A	20 BASEMENT CONSTRUCTION						

A2010 BASEMENT EXCAVATION

No items in this section

SUBTOTAL

A2020 BASEMENT WALLS

No items in this section

SUBTOTAL

TOTAL - BASEMENT CONSTRUCTION

B10	SUPERSTRUCTURE	
B1010	FLOOR CONSTRUCTION	

No Work in this section

SUBTOTAL

B1020	ROOF CONSTRUCTION

Roof Structure - Steel:
Steel beams/Joists; 12#/SF
Roof Structure
1-1/2" Metal floor Deck @ roof

Miscellaneous Roof screen framing - allow

SUBTOTAL

12	lbs/sf
12	105/ 51

29 tns

3,500.00 101,500 tns 29

4,900 sf 3.00 14,700

NIC 4,900 4.00 19,600

135,800

TOTAL - SUPERSTRUCTURE

Fire proofing to columns, beams and deck

\$135,800



Fea	ibility Design Estimate					GFA	4,900
CSI				UNIT	EST'D	SUB	TOTAL
coi	DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST

DISTRICT OF	FICE ADDITION TO NEW LYNCH OPTION WPS-2	2					
B20	EXTERIOR CLOSURE						
B2010	EXTERIOR WALLS; 60% solid/40% glass Interior skin	1,277	sf				
	6" metal stud backup	1,277	sf	7.50	9,578		
	Batt insulation in stud	1,277	sf	2.25	2,873		
	2 1/2" Rigid Insulation	1,277	sf	3.00	3,831		
	Air barrier	1,277	sf	6.00	7,662		
	Air barrier/flashing at windows	281	lf	7.00	1,967		
	Gypsum Sheathing	1,277	sf	2.75	3,512		
	Drywall lining to interior face of stud backup	1,277	sf	3.00	3,831		
	Exterior skin	, , ,			r		
	Brick veneer; 75% of exterior wall	958	sf	35.00	33,530		
	Metal panels; 25% of exterior wall	319	sf	60.00	19,140		
	Miscellaneous	U- 9		20.00	-0,110		
	Staging to exterior wall	2,128	sf	3.00	6,384		
	SUBTOTAL	, -			-,	92,308	
						,,,,,,	
B2020	WINDOWS	851	sf				
	Premium for sunscreen and light shelf elements	1	ls		NIC		
	Windows/storefront	851	sf	85.00	72,335		
	Backer rod & double sealant	281	lf	9.00	2,529		
	Wood blocking at openings	281	lf	4.00	1,124		
	SUBTOTAL					75,988	
B2030	EXTERIOR DOORS						
	Glazed entrance doors including frame and hardware; double door at corridor exit	2	pr	8,000.00	16,000		
	Backer rod & double sealant	40	lf	9.00	360		
	Wood blocking at openings	40	lf	4.00	160		
	SUBTOTAL					16,520	
	TOTAL - EXTERIOR CLOSURE						\$184
<u> </u>							· · ·
Взо	ROOFING						
B3010	ROOF COVERINGS Flat roofing						
	PVC roof membrane fully adhered	4,900	sf	9.00	44,100		
	Insulation	4,900	sf	7.00	34,300		
	1/2" dens-deck protection board	4,900	sf	2.00	9,800		
	Reinforced vapor barrier	4,900	sf	1.50	7,350		
	Rough blocking	880	lf	6.00	5,280		
	Miscellaneous Roofing	000		0.00	5,230		
	Roof screens - allow				NIC		
	Roof fascia/cornice	220	lf	25.00	5,500		
	SUBTOTAL	-20	11	£J.UU	3,300	106,330	
	SUBTOTAL					100,330	



GFA 4,900 Feasibility Design Estimate

CSI CODE		DESCRIPTION	QTY	UNIT	UNIT COST	EST'D COST	SUB TOTAL	TOTAL
				0	0001	0051	101112	
DISTR	ICT OF	FICE ADDITION TO NEW LYNCH OPTION WP	S-2			NIC		
		Skylights, allow				NIC		
		Roof hatch				NIC		
		SUBTOTAL					-	
		TOTAL - ROOFING						\$106
_								
	C10	INTERIOR CONSTRUCTION						
	C1010	PARTITIONS						
		GWB furred wall at existing exterior wall	1,050	sf	12.00	12,600		
		Corridors; GWB with 2 lyrs corridor side	4,860	sf	15.55	75,573		
		General Walls; GWB with 1 lyrs each side	3,390	sf	13.75	46,613		
		Sealants & caulking at partitions	4,860	sf	0.50	2,430		
		Rough blocking to partitions	374	lf	3.00	1,122		
		Glazed partitions/borrowed lights - allowance	1	ls	1,500.00	1,500		
		SUBTOTAL					139,838	
	C1020	INTERIOR DOORS						
	01020	Corridor glazed doors	1	pr	8,000.00	8,000		
		Single door with sidelight	20	ea	2,900.00	58,000		
		SUBTOTAL					66,000	
	C1020	SPECIALTIES / MILLWORK						
	01030	Marker boards/tackboards in conference room	128	sf	24.00	3,072		
		Toilet partitions and accessories	2	rooms	2,000.00	4,000		
		Room Signs	20	loc	110.00	2,200		
		Miscellaneous metals throughout building	4,900	sf	1.25	6,125		
		Miscellaneous sealants throughout building	4,900	sf	1.00	4,900		
		SUBTOTAL					20,297	
_		TOTAL - INTERIOR CONSTRUCTION						\$226

C20	STAIRCASES

C2010 STAIR CONSTRUCTION

No Work in this section

SUBTOTAL

185

186

187 188

189

190 191 192

197 198

199

200

C2020 STAIR FINISHES

No Work in this section

SUBTOTAL

TOTAL - STAIRCASES

С30	INTERIOR FINISHES

C3010 WALL FINISHES

Paint to GWB 1.00 17,550 17,550 \mathbf{sf} Ceramic Tile to toilets 504 sf 24.00 12,096

SUBTOTAL 29,646 07-Feb-17



nchester Schools 07-Feb-17

Feasibility Design Estimate GFA							4,900
CSI				UNIT	EST'D	SUB	TOTAL
CODE	DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST

I					UNIT	EST'D	SUB	TOTAL
DE		DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST
ISTR	RICT OF	FICE ADDITION TO NEW LYNCH OPTION W	PS-2	•			•	
	C3020	FLOOR FINISHES						
		Carpet floor finishes	2,675	sf	5.00	13,375		
		Resilient floor	1,913	sf	6.50	12,435		
		Ceramic Tile to toilets	120	sf	25.00	3,000		
		Rubber base	1,319	lf	2.75	3,627		
		SUBTOTAL					32,437	
	Canan	CEILING FINISHES						
	C3030	Allowance for ceiling finishes; 2 x 2 ACT	4,708	sf	5.00	23,540		
		SUBTOTAL	4,,,00	51	0.00	20,010	23,540	
							,	
		TOTAL - INTERIOR FINISHES						\$85
-								
Γ	D10	CONVEYING SYSTEMS						
<u> </u>	D	ELENATOR						
	D1010	ELEVATOR No Work in this section						
		SUBTOTAL					-	
Г								
		TOTAL - CONVEYING SYSTEMS						
_								
	D20	PLUMBING						
	D20	PLUMBING, GENERALLY						
		New fixtures	6	fxt	5,000.00	30,000		
		SUBTOTAL					30,000	
Γ		TOTAL - PLUMBING						\$30
L								
Г	D30	HVAC						
L								
	D30	HVAC, GENERALLY		r	00.00	107.000		
		HVAC complete system SUBTOTAL	4,900	gsf	28.00	137,200	137,200	
							137,200	
		TOTAL - HVAC						\$137
	D40	FIRE PROTECTION						
	D40	FIRE PROTECTION, GENERALLY						
	•	Sprinkler system	4,900	gsf	4.00	19,600		
		SUBTOTAL					19,600	
Г		TOTAL - FIRE PROTECTION						\$19
L		TOTAL TRUITMENT						Ψ19
Г	Dec	EI ECTRICAI	_					
L	D ₅ o	ELECTRICAL						
	D5010	COMPLETE ELECTRICAL SYSTEM						
		Electrical system; complete	4,900	gsf	22.00	107,800		
		ar inmoment						

SUBTOTAL

256

257 258 107,800



263 264

265

267

272 273

274

275

276

277

279

280

281

282 283

285 286

287 288

289

291 292

293 294 295

296 297

298

299

300 301

302

303

304

305

Feasibility Design Estimate

Winchester Schools CAFETERIA + DISTRICT OFFICE EXPANSION Winchester, MA

CSI				UNIT	EST'D	SUB	TOTAL
CODE	DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST

DISTRICT OFFICE ADDITION TO NEW LYNCH OPTION WPS-2

TOTAL - ELECTRICAL	\$107,800
--------------------	-----------

EQUIPMENT E10

EQUIPMENT, GENERALLY E10

AV Equipment (including Smartboards, Projectors, LED monitors, Digital information displays etc.)

SUBTOTAL

TOTAL - EQUIPMENT

FURNISHINGS E20

E2010 FIXED FURNISHINGS

> Entry mats & frames - recessed with carpet/rubber **50** sf 45.00 strips Manual operated roller shades 851 6.00 sf

Miscellaneous casework 3.00 14,700 4,900 gsf SUBTOTAL

E2020 MOVABLE FURNISHINGS

All movable furnishings to be provided and installed

by owner

SUBTOTAL NIC

TOTAL - FURNISHINGS \$22,056

SPECIAL CONSTRUCTION F10

SPECIAL CONSTRUCTION

No Work in this section

SUBTOTAL

TOTAL - SPECIAL CONSTRUCTION

SELECTIVE BUILDING DEMOLITION F20

F2010 BUILDING ELEMENTS DEMOLITION

Create openings to existing façade for new loc 25,000.00 25,000

connections

SUBTOTAL 25.000

F2020 HAZARDOUS COMPONENTS ABATEMENT

None Included

SUBTOTAL

TOTAL - SELECTIVE BUILDING DEMOLITION

\$25,000

07-Feb-17

4 900

GFA

FF+E

2,250

5,106

22,056



Feasibility Design Estimate

Winchester Schools
CAFETERIA + DISTRICT OFFICE EXPANSION
Winchester MA

Winchester, MA

CONSTRUCTION COST SUMMARY BUILDING SYSTEM SUB-TOTAL TOTAL \$/SF DISTRICT OFFICE RENOVATION TO MYSTIC ES OPTION WPS-5 A10 **FOUNDATIONS** \$0 A1010 **Standard Foundations** \$0 A1020 Special Foundations A1030 \$19,600 2.7% **Lowest Floor Construction** \$19,600 \$4.00 **BASEMENT CONSTRUCTION** A20 A2010 **Basement Excavation** \$0 A2020 **Basement Walls** \$0 \$0.00 0.0% **\$0 B10 SUPERSTRUCTURE** B1010 **Upper Floor Construction** \$0 B1020 **Roof Construction** \$0 **\$0** \$0.00 0.0% **B20 EXTERIOR CLOSURE** B2010 **Exterior Walls** \$53,760 B2020 Windows \$0 B2030 **Exterior Doors** \$14.34 9.6% \$16,520 \$70,280 **B30 ROOFING** B3010 \$0 **Roof Coverings** B3020 **Roof Openings** \$0 **\$0** \$0.00 0.0% C10 INTERIOR CONSTRUCTION C1010 **Partitions** \$114,825 C1020 Interior Doors \$66,000 C1030 \$20,297 Specialties/Millwork \$201,122 \$41.05 27.4% **STAIRCASES C20** C2010 Stair Construction \$0 C2020 Stair Finishes \$0 **\$0** \$0.00 0.0% **INTERIOR FINISHES** C30 C3010 Wall Finishes \$27,696 C3020 Floor Finishes \$32,437 C3030 Ceiling Finishes \$23,540 \$83,673 \$17.08 11.4% **CONVEYING SYSTEMS** D10 D1010 Elevator \$0 \$0.00 0.0% **\$0 D20 PLUMBING** D20 \$30,000 \$30,000 \$6.12 4.1% Plumbing

07-Feb-17

4,900

GFA



07-Feb-17

Feasibility Design Estimate GFA 4,900

		CONSTRUCTION	COST SUMMA	ARY		
	BUILDING	SYSTEM	SUB-TOTAL	TOTAL	\$/SF	%
DISTRIC	T OFFIC	E RENOVATION TO MYSTIC ES OPT	ION WPS-5			
D30	HVAC					
	D30	HVAC	\$137,200	\$137,200	\$28.00	18.7%
D40	FIRE P	ROTECTION				
	D40	Fire Protection	\$19,600	\$19,600	\$4.00	2.7%
D50	ELECT	RICAL				
	D5010	Complete System	\$107,800	\$107,800	\$22.00	14.7%
E10	EQUIP	MENT				
	E10	Equipment	\$0	\$0	\$0.00	0.0%
E20	FURNIS	SHINGS				
	E2010	Fixed Furnishings	\$16,950			
	E2020	Movable Furnishings	NIC	\$16,950	\$3.46	2.3%
F10	SPECIA	AL CONSTRUCTION				
	F10	Special Construction	\$0	\$0	\$0.00	0.0%
F20	HAZMA	AT REMOVALS				
	F2010	Building Elements Demolition	\$49,000			
	F2020	Hazardous Components Abatement	\$0	\$49,000	\$10.00	6.7%
TOT	AL DIDE	CT COCT (Tuada Casta)		ф т от 00-	¢1=0.0=	100.0%
1017	AL DIKE	CT COST (Trade Costs)		<i>\$735,225</i>	\$150.05	100.0%



Winchester Schools

CAFETERIA + DISTRICT OFFICE EXPANSION

Winchester, MA

15

18

21

22 23

29

31

33

35 36

38

44

47

48 49 50

52

53

Feasibility Design Estimate GFA 4 900

CSI				UNIT	EST'D	SUB	TOTAL
CODE	DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST

DISTRICT OFFICE RENOVATION TO MYSTIC ES OPTION WPS-5

GROSS FLOOR AREA CALCULATION

First Floor 4,900

TOTAL GROSS FLOOR AREA (GFA) 4,900 sf

A10 FOUNDATIONS

A1010 STANDARD FOUNDATIONS

SUBTOTAL

A1020 SPECIAL FOUNDATIONS

No Work in this section

SUBTOTAL

A1030 LOWEST FLOOR CONSTRUCTION

Patch existing slab 4.00 19,600 4,900

SUBTOTAL 19,600

TOTAL - FOUNDATIONS \$19,600

BASEMENT CONSTRUCTION A20

A2010 BASEMENT EXCAVATION

No items in this section

SUBTOTAL

A2020 BASEMENT WALLS

No items in this section

SUBTOTAL

TOTAL - BASEMENT CONSTRUCTION

B10 SUPERSTRUCTURE

B1010 FLOOR CONSTRUCTION

No Work in this section

SUBTOTAL

B1020 ROOF CONSTRUCTION

No Work in this section

SUBTOTAL

TOTAL - SUPERSTRUCTURE

B20 EXTERIOR CLOSURE

B2010 EXTERIOR WALLS

Interior skin



Feasibility Design Estimate GFA 4,900

CSI CODE		DESCRIPTION	QTY	UNIT	UNIT COST	EST'D COST	SUB TOTAL	TOTAL COST
DIST	RICT OF	FICE RENOVATION TO MYSTIC ES OPTION WPS	5-5			l		
		Insulate inside face of perimeter wall; includes furring and GWB	4,480	sf	12.00	53,760		
		Exterior skin						
		Assumed no work to existing exterior closure						
		SUBTOTAL					53,760	
	B2020	WINDOWS						
		Assumed no work to existing windows						
		SUBTOTAL					-	
	B2030	EXTERIOR DOORS						
	Ū	Glazed entrance doors including frame and hardware; double door at corridor exit	2	pr	8,000.00	16,000		
		Backer rod & double sealant	40	lf	9.00	360		
		Wood blocking at openings	40	lf	4.00	160		
		SUBTOTAL					16,520	
ſ		TOTAL - EXTERIOR CLOSURE						\$70,2
Į		TOTAL EXTENSION CHOSENE						Ψ/0,2
[Взо	ROOFING						
	B3010	ROOF COVERINGS Assumed no work to existing roof						
		SUBTOTAL					-	
	B3020	ROOF OPENINGS						
		Skylights, allow				NIC		
		Roof hatch				NIC		
		SUBTOTAL					-	
		TOTAL - ROOFING						
[C10	INTERIOR CONSTRUCTION						
<u>l</u>	Ctoto	DADTITIONS						
	C1010	PARTITIONS Corridors; GWB with 2 lyrs corridor side	2,400	sf	15.55	37,320		
		General Walls; GWB with 1 lyrs each side	5,400	sf	13.75	74,250		
		Sealants & caulking at partitions	2,400	sf	0.50	1,200		
		Rough blocking to partitions	185	lf	3.00	555		
		Glazed partitions/borrowed lights - allowance	1	ls	1,500.00	1,500		
		SUBTOTAL				,	114,825	
	0.5.	INTERIOR DOORS						
	C1020	INTERIOR DOORS Corridor glazed doors	1	pr	8,000.00	8,000		
		Single door with sidelight	20	ea	2,900.00	58,000		
		SUBTOTAL SUBTOTAL	_3		,. 50.00	30,000	66,000	
	C	ODDOLAT MAKE (MAKAMANA)						
	C1030	SPECIALTIES / MILLWORK Marker boards/tackboards in conference room	128	sf	24.00	3,072		
		Toilet partitions and accessories	2	rooms	2,000.00	4,000		



Winchester Schools CAFETERIA + DISTRICT OFFICE EXPANSION

	n Estimate					GFA	
I DDE	DESCRIPTION	QTY	UNIT	UNIT COST	EST'D COST	SUB TOTAL	COS
ISTRICT OF	FICE RENOVATION TO MYSTIC ES OPTION	WPS-5			•		
	Room Signs	20	loc	110.00	2,200		
	Miscellaneous metals throughout building	4,900	sf	1.25	6,125		
	Miscellaneous sealants throughout building	4,900	sf	1.00	4,900		
	SUBTOTAL					20,297	
	TOTAL - INTERIOR CONSTRUCTION						\$20
C20	STAIRCASES						
C2010	STAIR CONSTRUCTION						
	No Work in this section						
	SUBTOTAL					-	
C2020	STAIR FINISHES						
	No Work in this section SUBTOTAL					_	
	TOTAL - STAIRCASES						
Сзо	INTERIOR FINISHES						
С3010	WALL FINISHES Paint to GWB	15,600	sf	1.00	15,600		
	Ceramic Tile to toilets	504	sf	24.00	12,096		
	SUBTOTAL					27,696	
Canan	FLOOR FINISHES						
03020	Carpet floor finishes	2,675	sf	5.00	13,375		
	Resilient floor	1,913	sf	6.50	12,435		
	Ceramic Tile to toilets	1,913	sf	25.00	3,000		
	Rubber base		lf				
	SUBTOTAL	1,319	11	2.75	3,627	32,437	
	SUBTOTAL					32,437	
С3030	CEILING FINISHES	. =00	0	7.00	99.740		
	Allowance for ceiling finishes; 2 x 2 ACT	4,708	sf	5.00	23,540	99.540	
	SUBTOTAL					23,540	
	TOTAL - INTERIOR FINISHES						\$8
D10	CONVEYING SYSTEMS	\neg					
D1010	ELEVATOR No Work in this section						
	SUBTOTAL					-	
	TOTAL - CONVEYING SYSTEMS						
D20	PLUMBING						

New fixtures

SUBTOTAL

158

159

5,000.00

fxt

30,000

30,000



165 166

167

168

170

171 172 173

174 175

176

177

178 179

180 181 182

183 184

185

186

187 188 189

190 191 192

193 194

195

196

197 198

199 200 201

202 203

204

205

206

207 208

209

210

211

212

213 214 215

Winchester Schools CAFETERIA + DISTRICT OFFICE EXPANSION Winchester, MA

Feasibility Design Estimate GFA 4 900

CSI	I				UNIT	EST'D	SUB	TOTAL
CO.	DE	DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST

DISTRICT OFFICE RENOVATION TO MYSTIC ES OPTION WPS-5

TOTAL - PLUMBING	\$30,000

D30 HVAC

HVAC, GENERALLY D30

> 28.00 137,200 HVAC complete system 4,900 gsf

SUBTOTAL 137,200

TOTAL - HVAC \$137,200

D40 FIRE PROTECTION

FIRE PROTECTION, GENERALLY **D40**

Sprinkler system 4.00 19,600 4,900 gsf

SUBTOTAL 19,600

TOTAL - FIRE PROTECTION \$19,600

D50 ELECTRICAL

D5010 COMPLETE ELECTRICAL SYSTEM

Electrical system; complete 22.00 107,800 gsf 4,900

SUBTOTAL 107,800

TOTAL - ELECTRICAL \$107,800

EQUIPMENT E10

EQUIPMENT, GENERALLY E10

> AV Equipment (including Smartboards, Projectors, FF+E

LED monitors, Digital information displays etc.)

SUBTOTAL

TOTAL - EQUIPMENT

FURNISHINGS E20

Entry mats & frames - recessed with carpet/rubber 45.00 2,250 50 sf

strips 14,700 Miscellaneous casework 3.00 4,900 gsf

SUBTOTAL 16,950

E2020 MOVABLE FURNISHINGS

E2010 FIXED FURNISHINGS

All movable furnishings to be provided and installed

by owner

SUBTOTAL NIC

TOTAL - FURNISHINGS \$16,950

F10 SPECIAL CONSTRUCTION



Winchester Schools CAFETERIA + DISTRICT OFFICE EXPANSION

07-Feb-17

Winchester, MA	Winc	hester,	MA
----------------	------	---------	----

Feasibility Design Estimate				GFA	4,900
CSI		UNIT	EST'D	SUB	TOTAL

CSI				UNIT	EST'D	SUB	TOTAL
CODE	DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST

DISTRICT OFFICE RENOVATION TO MYSTIC ES OPTION WPS-5

F10	SPECIAL CONSTRUCTION
	No Work in this section
	SUBTOTAL.


TOTAL - SPECIAL CONSTRUCTION	

F2010 BUILDING ELEMENTS DEMOLITION				
Gut demolition of existing space	4,900	gsf	10.00	49,000

SUBTOTAL	49.00	00

HAZARDOUS COMPONENTS ABATEMENT None Included	
SUBTOTAL	

SUBTOTAL	
TOTAL - SELECTIVE BUILDING DEMOLITION	\$49,000



Feasibility Design Estimate

Winchester Schools CAFETERIA + DISTRICT OFFICE EXPANSION

Winchester, MA

PM&C LLC 20 Downer Avenue, Suite 1c Hingham, MA 02043 (T) 781-740-8007 (F) 781-740-1012 Prepared for:

Flansburgh Architects

February 14, 2017



14-Feb-17

Feasibility Design Estimate

MAIN CONSTRUCTION COST SUMMARY

	Construction Start	Gross Floor Area	\$/sf	Estimated Construction Cost
RENOVATION TO McCALL MS -	CAFETERIA C	PTION 1		
CAFETERIA EXPANSION		1,100	\$76.63	\$84,298
SUB-TOTAL	Jun-18	1,100	\$76.63	\$84,298
ESCALATION TO START - (assumed 4% PA)	5.7%			\$4,805
DESIGN AND PRICING CONTINGENCY	15%			\$12,645
SUB-TOTAL		1,100	\$92.50	\$101,748
GENERAL CONDITIONS				\$15,262
BONDS	1.00%			\$1,017
INSURANCE	2.00%			\$2,035
PERMIT				NIC
OVERHEAD AND FEE	10.00%			\$10,175
OWNER CONTINGENCY				By Owner
TOTAL OF ALL CONSTRUCTION	Jun-18	1,100	\$118.40	\$130,237



14-Feb-17

Feasibility Design Estimate

MAIN CONSTRUCTION COST SUMMARY

	Construction Start	Gross Floor Area	\$/sf	Estimated Construction Cost
RENOVATION TO McCALL MS -	· CAFETERIA (OPTION 2		
CAFETERIA EXPANSION		2,400	\$92.36	\$221,660
SUB-TOTAL	Jun-18	2,400	\$92.36	\$221,660
ESCALATION TO START - (assumed 4% PA)	5.7%			\$12,635
DESIGN AND PRICING CONTINGENCY	15%			\$33,249
SUB-TOTAL		2,400	\$111.48	\$267,544
GENERAL CONDITIONS				\$40,132
BONDS	1.00%			\$2,675
INSURANCE	2.00%			\$5,351
PERMIT				NIC
OVERHEAD AND FEE	10.00%			\$26,754
OWNER CONTINGENCY				By Owner
TOTAL OF ALL CONSTRUCTION	Jun-18	2,400	\$142.69	\$342,456



Winchester Schools

 ${\sf CAFETERIA+DISTRICT\ OFFICE\ EXPANSION}$

Winchester, MA

Feasibility Design Estimate

ADDITION AT CAFETERIA - OPTION ${\bf 3}$

SUB-TOTAL Jun-18 1,525 \$517.84 \$789.704	ADDITION		1,525	\$517.84	\$789,704
DESIGN AND PRICING CONTINGENCY 15% \$118,456 SUB-TOTAL 1,525 \$825.03 \$953,173 GENERAL CONDITIONS \$76,254 \$96,524 BONDS 1.00% \$95,322 INSURANCE 2.00% \$19,063 PERMIT NIC OVERHEAD AND FEE 8.00% \$76,254 OWNER CONTINGENCY By Owner TOTAL OF ALL CONSTRUCTION Jun-18 1,525 \$743.79 \$1,134,276 NEW TEACHERS WORKROOM Jun-18 1,250 \$37.90 \$47,370 SUB-TOTAL Jun-18 1,250 \$37.90 \$47,370 ESCALATION TO START - (assumed 4% PA) 5.7% \$2,700 DESIGN AND PRICING CONTINGENCY 15% \$7,106 SUB-TOTAL 1,250 \$45.74 \$57,176 GENERAL CONDITIONS \$11,435 \$572 INSURANCE 2,00% \$1,144 PERMIT NIC \$8,576 OWNER CONTINGENCY 5,00% \$8,576 OWNER CONTINGENCY By Owner <td>SUB-TOTAL</td> <td>Jun-18</td> <td>1,525</td> <td>\$517.84</td> <td>\$789,704</td>	SUB-TOTAL	Jun-18	1,525	\$517.84	\$789,704
SUB-TOTAL 1,525 \$625.03 \$953,173 GENERAL CONDITIONS \$76,254 \$9,532 INSURANCE 2,00% \$19,063 PERMIT NIC OVERHEAD AND FEE 8.00% \$76,254 OWNER CONTINGENCY By Owner TOTAL OF ALL CONSTRUCTION Jun-18 1,525 \$743.79 \$1,134,276 NEW TEACHERS WORKROOM 1,250 \$37.90 \$47,370 SUB-TOTAL Jun-18 1,250 \$37.90 \$47,370 ESCALATION TO START - (assumed 4% PA) 5.7% \$2,700 DESIGN AND PRICING CONTINGENCY 15% \$7,106 SUB-TOTAL 1,250 \$45.74 \$57,176 GENERAL CONDITIONS \$11,435 \$572 INSURANCE 2.00% \$1,144 PERMIT NIC \$1,144 OWER CONTINGENCY \$8,576 \$8,576 OWNER CONTINGENCY By Owner	ESCALATION TO START - (assumed 4% PA)	5.7%			\$45,013
GENERAL CONDITIONS \$76,254 BONDS 1.00% \$9,532 INSURANCE 2.00% \$19,063 PERMIT NIC OVERHEAD AND FEE 8.00% \$76,254 OWNER CONTINGENCY By Owner TOTAL OF ALL CONSTRUCTION Jun-18 1,525 \$743.79 \$1,134,276 NEW TEACHERS WORKROOM 1,250 \$37.90 \$47,370 SUB-TOTAL Jun-18 1,250 \$37.90 \$47,370 ESCALATION TO START - (assumed 4% PA) 5.7% \$2,700 DESIGN AND PRICING CONTINGENCY 15% \$7,106 SUB-TOTAL 1,250 \$45.74 \$57,176 GENERAL CONDITIONS \$11,435 \$502 BONDS 1.00% \$572 INURANCE 2.00% \$1,144 PERMIT NIC OVERHEAD AND FEE 15.00% \$8,576 OWNER CONTINGENCY By Owner	DESIGN AND PRICING CONTINGENCY	15%			\$118,456
BONDS	SUB-TOTAL		1,525	\$625.03	\$953,173
INSURANCE 2.00% S19,063 NIC	GENERAL CONDITIONS				\$76,254
PERMIT NIC OVERHEAD AND FEE 8.00% \$76,254 OWNER CONTINGENCY By Owner TOTAL OF ALL CONSTRUCTION Jun-18 1,525 \$743.79 \$1,134,276 NEW TEACHERS WORKROOM WORKROOM RENOVATION 1,250 \$37.90 \$47,370 SUB-TOTAL Jun-18 1,250 \$37.90 \$47,370 ESCALATION TO START - (assumed 4% PA) 5.7% \$2,700 DESIGN AND PRICING CONTINGENCY 15% \$7,106 SUB-TOTAL 1,250 \$45.74 \$57,176 GENERAL CONDITIONS \$11,435 \$572 BONDS 1,00% \$572 INSURANCE 2,00% \$1,144 PERMIT NIC OVERHEAD AND FEE 15.00% \$8,576 OWNER CONTINGENCY By Owner	BONDS	1.00%			\$9,532
OVERHEAD AND FEE 8.00% \$76,254 OWNER CONTINGENCY By Owner TOTAL OF ALL CONSTRUCTION Jun-18 1,525 \$743.79 \$1,134,276 NEW TEACHERS WORKROOM WORKROOM RENOVATION 1,250 \$37.90 \$47,370 SUB-TOTAL Jun-18 1,250 \$37.90 \$47,370 ESCALATION TO START - (assumed 4% PA) 5.7% \$2,700 DESIGN AND PRICING CONTINGENCY 15% \$7,106 SUB-TOTAL 1,250 \$45.74 \$57,176 GENERAL CONDITIONS \$11,435 \$572 BONDS 1.00% \$572 INSURANCE 2.00% \$1,144 PERMIT NIC OVERHEAD AND FEE 15.00% \$8,576 OWNER CONTINGENCY By Owner		2.00%			
OWNER CONTINGENCY By Owner TOTAL OF ALL CONSTRUCTION Jun-18 1,525 \$743.79 \$1,134,276 NEW TEACHERS WORKROOM WORKROOM RENOVATION 1,250 \$37.90 \$47,370 SUB-TOTAL Jun-18 1,250 \$37.90 \$47,370 ESCALATION TO START - (assumed 4% PA) 5.7% \$2,700 DESIGN AND PRICING CONTINGENCY 15% \$7,106 SUB-TOTAL 1,250 \$45.74 \$57,176 GENERAL CONDITIONS \$11,435 \$572 INSURANCE 2.00% \$1,144 PERMIT NIC \$8,576 OWNER CONTINGENCY By Owner	PERMIT				NIC
NEW TEACHERS WORKROOM Jun-18 1,525 \$743.79 \$1,134,276 WORKROOM RENOVATION 1,250 \$37.90 \$47,370 SUB-TOTAL Jun-18 1,250 \$37.90 \$47,370 ESCALATION TO START - (assumed 4% PA) 5.7% \$2,700 DESIGN AND PRICING CONTINGENCY 15% \$7,106 SUB-TOTAL 1,250 \$45.74 \$57,176 GENERAL CONDITIONS \$11,435 \$572 INSURANCE 2,00% \$1,144 PERMIT NIC \$8,576 OWNER CONTINGENCY By Owner	OVERHEAD AND FEE	8.00%			\$76,254
NEW TEACHERS WORKROOM WORKROOM RENOVATION 1,250 \$37.90 \$47,370 SUB-TOTAL Jun-18 1,250 \$37.90 \$47,370 ESCALATION TO START - (assumed 4% PA) 5.7% \$2,700 DESIGN AND PRICING CONTINGENCY 15% \$7,106 SUB-TOTAL 1,250 \$45.74 \$57,176 GENERAL CONDITIONS \$11,435 BONDS 1,00% \$572 INSURANCE 2,00% \$1,144 PERMIT NIC OVERHEAD AND FEE 15.00% \$8,576 OWNER CONTINGENCY By Owner	OWNER CONTINGENCY				By Owner
WORKROOM RENOVATION 1,250 \$37.90 \$47,370 SUB-TOTAL Jun-18 1,250 \$37.90 \$47,370 ESCALATION TO START - (assumed 4% PA) 5.7% \$2,700 DESIGN AND PRICING CONTINGENCY 15% \$7,106 SUB-TOTAL 1,250 \$45.74 \$57,176 GENERAL CONDITIONS \$11,435 \$572 \$572 INSURANCE 2.00% \$1,144 PERMIT NIC OVERHEAD AND FEE 15.00% \$8,576 OWNER CONTINGENCY By Owner	TOTAL OF ALL CONSTRUCTION	Jun-18	1,525	\$743.79	\$1,134,276
ESCALATION TO START - (assumed 4% PA) 5.7% \$2,700 DESIGN AND PRICING CONTINGENCY 15% \$7,106 SUB-TOTAL 1,250 \$45.74 \$57,176 GENERAL CONDITIONS \$11,435 BONDS 1.00% \$572 INSURANCE 2.00% \$1,144 PERMIT NIC OVERHEAD AND FEE 15.00% \$8,576 OWNER CONTINGENCY By Owner			1,250	\$37.90	\$47,370
DESIGN AND PRICING CONTINGENCY 15% \$7,106 SUB-TOTAL 1,250 \$45.74 \$57,176 GENERAL CONDITIONS \$11,435 BONDS 1.00% \$572 INSURANCE 2.00% \$1,144 PERMIT NIC OVERHEAD AND FEE 15.00% \$8,576 OWNER CONTINGENCY By Owner	SUB-TOTAL	Jun-18	1,250	\$37.90	\$47,370
SUB-TOTAL 1,250 \$45.74 \$57,176 GENERAL CONDITIONS \$11,435 BONDS 1.00% \$572 INSURANCE 2.00% \$1,144 PERMIT NIC OVERHEAD AND FEE 15.00% \$8,576 OWNER CONTINGENCY By Owner	ESCALATION TO START - (assumed 4% PA)	5.7%			\$2,700
GENERAL CONDITIONS \$11,435 BONDS 1.00% \$572 INSURANCE 2.00% \$1,144 PERMIT NIC OVERHEAD AND FEE 15.00% \$8,576 OWNER CONTINGENCY By Owner	DESIGN AND PRICING CONTINGENCY	15%			\$7,106
BONDS 1.00% \$572 INSURANCE 2.00% \$1,144 PERMIT NIC OVERHEAD AND FEE 15.00% \$8,576 OWNER CONTINGENCY By Owner	SUB-TOTAL		1,250	\$45.74	\$57,176
INSURANCE 2.00% \$1,144 PERMIT NIC OVERHEAD AND FEE 15.00% \$8,576 OWNER CONTINGENCY By Owner	GENERAL CONDITIONS				\$11,435
PERMIT NIC OVERHEAD AND FEE 15.00% \$8,576 OWNER CONTINGENCY By Owner	BONDS	1.00%			\$572
OVERHEAD AND FEE 15.00% \$8,576 OWNER CONTINGENCY By Owner	INSURANCE	2.00%			\$1,144
OWNER CONTINGENCY By Owner	PERMIT				NIC
	OVERHEAD AND FEE	15.00%			\$8,576
TOTAL OF ALL CONSTRUCTION Jun-18 1,250 \$63.12 \$78,903	OWNER CONTINGENCY				By Owner
	TOTAL OF ALL CONSTRUCTION	Jun-18	1,250	\$63.12	\$78,903



14-Feb-17

Feasibility Design Estimate

MAIN CONSTRUCTION COST SUMMARY

	Construction Start	Gross Floor Area	\$/sf	Estimated Construction Cost
DISTRICT OFFICE ADDITION T	O LYNCH OPT	ION WPS	-1	
DISTRICT OFFICE ADDITION		4,900	\$281.81	\$1,380,878
SUB-TOTAL	Jun-18	4,900	\$281.81	\$1,380,878
ESCALATION TO START - (assumed 4% PA)	5.7%			\$78,710
DESIGN AND PRICING CONTINGENCY	10%			\$138,088
SUB-TOTAL		4,900	\$326.06	\$1,597,676
GENERAL CONDITIONS				\$127,814
BONDS	1.00%			\$15,977
INSURANCE	2.00%			\$31,954
PERMIT				NIC
OVERHEAD AND FEE	3.00%			\$47,930
OWNER CONTINGENCY				By Owner
TOTAL OF ALL CONSTRUCTION	Jun-18	4,900	\$371.70	\$1,821,351



14-Feb-17

Feasibility Design Estimate

MAIN CONSTRUCTION COST SUMMARY

	Construction Start	Gross Floor Area	\$/sf	Estimated Construction Cost
DISTRICT OFFICE ADDITION T	O NEW LYNCI	H OPTION	WPS-2	
DISTRICT OFFICE ADDITION		4,900	\$261.63	\$1,281,982
SUB-TOTAL	Jun-18	4,900	\$261.63	\$1,281,982
ESCALATION TO START - (assumed 4% PA)	5.7%			\$73,073
DESIGN AND PRICING CONTINGENCY	10%			\$128,198
SUB-TOTAL		4,900	\$302.70	\$1,483,253
GENERAL CONDITIONS				\$118,660
BONDS	1.00%			\$14,833
INSURANCE	2.00%			\$29,665
PERMIT				NIC
OVERHEAD AND FEE	3.00%			\$44,498
OWNER CONTINGENCY				By Owner
TOTAL OF ALL CONSTRUCTION	Jun-18	4,900	\$345.08	\$1,690,909



14-Feb-17

Feasibility Design Estimate

	Construction Start	Gross Floor Area	\$/sf	Estimated Construction Cost
DISTRICT OFFICE ADDITION TO	O NEW LYNCI	H OPTION V	WPS-3	
DISTRICT OFFICE ADDITION		4,900	\$257.55	\$1,261,982
SUB-TOTAL	Jun-18	4,900	\$257.55	\$1,261,982
ESCALATION TO START - (assumed 4% PA)	5.7%			\$71,933
DESIGN AND PRICING CONTINGENCY	10%			\$126,198
SUB-TOTAL		4,900	\$297.98	\$1,460,113
GENERAL CONDITIONS				\$116,809
BONDS	1.00%			\$14,601
INSURANCE	2.00%			\$29,202
PERMIT				NIC
OVERHEAD AND FEE	3.00%			\$43,803
OWNER CONTINGENCY				By Owner
TOTAL OF ALL CONSTRUCTION	Jun-18	4,900	\$339.70	\$1,664,528



14-Feb-17

Feasibility Design Estimate

	Construction Start	Gross Floor Area	\$/sf	Estimated Construction Cost
DISTRICT OFFICE ADDITION T	O NEW LYNCI	H OPTION	WPS-4	
DISTRICT OFFICE ADDITION		4,900	\$261.63	\$1,281,982
SUB-TOTAL	Jun-18	4,900	\$261.63	\$1,281,982
ESCALATION TO START - (assumed 4% PA)	5.7%			\$73,073
DESIGN AND PRICING CONTINGENCY	10%			\$128,198
SUB-TOTAL		4,900	\$302.70	\$1,483,253
GENERAL CONDITIONS				\$118,660
BONDS	1.00%			\$14,833
INSURANCE	2.00%			\$29,665
PERMIT				NIC
OVERHEAD AND FEE	3.00%			\$44,498
OWNER CONTINGENCY				By Owner
TOTAL OF ALL CONSTRUCTION	Jun-18	4,900	\$345.08	\$1,690,909



14-Feb-17

Feasibility Design Estimate

	Construction Start	Gross Floor Area	\$/sf	Estimated Construction Cost
DISTRICT OFFICE RENOVATION 5	N TO MYSTIC	ES OPTION	N WPS-	
DISTRICT OFFICE RENOVATION		4,900	\$150.05	\$735,225
SUB-TOTAL	Jun-18	4,900	\$150.05	\$735,225
ESCALATION TO START - (assumed 4% PA)	5.7%			\$41,908
DESIGN AND PRICING CONTINGENCY	10%			\$73,523
SUB-TOTAL		4,900	\$173.60	\$850,656
GENERAL CONDITIONS				\$85,066
BONDS	1.00%			\$8,507
INSURANCE	2.00%			\$17,013
PERMIT				NIC
OVERHEAD AND FEE	5.00%			\$42,533
OWNER CONTINGENCY				By Owner
TOTAL OF ALL CONSTRUCTION	Jun-18	4,900	\$204.85	\$1,003,775



14-Feb-17

Feasibility Design Estimate

	Construction Start	Gross Floor Area	\$/sf	Estimated Construction Cost
DISTRICT OFFICE RENOVATIO OPTION WPS-6	N AT CARRIA	GE HOUSE		
DISTRICT OFFICE RENOVATION		5,151	\$269.38	\$1,387,598
SITEWORK ALLOWANCE				\$69,380
SUB-TOTAL	Jun-18	5,151	\$282.85	\$1,456,978
ESCALATION TO START - (assumed 4% PA)	5.7%			\$83,048
DESIGN AND PRICING CONTINGENCY	10%			\$145,698
SUB-TOTAL		5,151	\$327.26	\$1,685,724
GENERAL CONDITIONS				\$168,572
BONDS	1.00%			\$16,857
INSURANCE	2.00%			\$33,714
PERMIT				NIC
OVERHEAD AND FEE	5.00%			\$84,286
OWNER CONTINGENCY				By Owner
TOTAL OF ALL CONSTRUCTION	Jun-18	5,151	\$386.17	\$1,989,153



14-Feb-17

Feasibility Design Estimate

This Feasibility Design cost estimate was produced from preliminary drawings prepared by Flansburgh Architects Inc. and their design team dated February 2, 2017. Design and engineering changes occurring subsequent to the issue of these documents have not been incorporated in this estimate.

This estimate includes all direct construction costs, general contractor's overhead, fee and design contingency. Cost escalation assumes start dates indicated.

Bidding conditions are expected to be public bidding under Chapter 149 of the Massachusetts General Laws to pre-qualified general contractors, and pre-qualified sub-contractors, open specifications for materials and manufactures.

The estimate is based on prevailing wage rates for construction in this market and represents a reasonable opinion of cost. It is not a prediction of the successful bid from a contractor as bids will vary due to fluctuating market conditions, errors and omissions, proprietary specifications, lack or surplus of bidders, perception of risk, etc. Consequently the estimate is expected to fall within the range of bids from a number of competitive contractors or subcontractors, however we do not warrant that bids or negotiated prices will not vary from the final construction cost estimate.

ITEMS NOT CONSIDERED IN THIS ESTIMATE

Items not included in this estimate are:

Land acquisition, feasibility, and financing costs

All professional fees and insurance

Site or existing conditions surveys investigations costs, including to determine

subsoil conditions

All Furnishings, Fixtures and Equipment

Items identified in the design as Not In Contract (NIC)

Items identified in the design as by others

Owner supplied and/or installed items as indicated in the estimate

Utility company back charges, including work required off-site

Work to City streets and sidewalks, (except as noted in this estimate)

Construction contingency



Feasibility Design Estimate GFA 1,100

	BUILDING	CONSTRUCTION	N COST SUMMA SUB-TOTAL	RY TOTAL	\$/SF	%
PENOVA		O McCALL MS - CAFETERIA OPTION 1	SUB-TOTAL	TOTAL	φ/51	70
A10		OATIONS				
1110	A1010	Standard Foundations	\$0			
	A1020	Special Foundations	\$0			
	A1030	Lowest Floor Construction	\$2,750	\$2,750	\$2.50	3.3%
B10	SUPER	STRUCTURE				
	B1010	Upper Floor Construction	\$0			
	B1020	Roof Construction	\$0	\$0	\$0.00	0.0%
B20	EXTER	IOR CLOSURE				
	B2010	Exterior Walls	\$0			
	B2020	Windows/Curtainwall	\$0			
	B2030	Exterior Doors	\$0	\$0	\$0.00	0.0%
В30	ROOFI	NG				
	B3010	Roof Coverings	\$0			
	B3020	Roof Openings	\$0	\$0	\$0.00	0.0%
C10	INTER	IOR CONSTRUCTION				
	C1010	Partitions	\$6,648			
	C1020	Interior Doors	\$0			
	C1030	Specialties/Millwork	\$700	\$7,348	\$6.68	8.7%
C20	STAIR	CASES				
	C2010	Stair Construction	\$0			
	C2020	Stair Finishes	\$0	\$0	\$0.00	0.0%
С30	INTER	IOR FINISHES				
	C3010	Wall Finishes	\$5,300			
	C3020	Floor Finishes	\$13,000			
	C3030	Ceiling Finishes	\$10,200	\$28,500	\$25.91	33.8%
D10	CONVE	YING SYSTEMS				
	D1010	Elevator	\$0	\$0	\$0.00	0.0%
D20	PLUMI	BING				
	D20	Plumbing	\$0	\$0	\$0.00	0.0%
D30	HVAC					
	D30	HVAC	\$11,000	\$11,000	\$10.00	13.0%
D40	FIRE P	ROTECTION				
	D40	Fire Protection	\$2,200	\$2,200	\$2.00	2.6%



14-Feb-17

Feasibility Design Estimate GFA 1,100

	BUILDING	SYSTEM	$SUB ext{-}TOTAL$	TOTAL	\$/SF	%
ENOVA	ATION TO	O McCALL MS - CAFETERIA OPTION 1				
D50	ELECTRICAL					
	D5010	Electrical Systems	\$16,500	\$16,500	\$15.00	19.6%
E10	EQUIP	MENT				
	E10	Equipment	\$0	\$0	\$0.00	0.0%
E20	FURNIS	SHINGS				
	E2010	Fixed Furnishings	\$0			
	E2020	Movable Furnishings	NIC	\$0	\$0.00	0.0%
F10	SPECIA	AL CONSTRUCTION				
	F10	Special Construction	\$0	\$0	\$0.00	0.0%
F20	SELEC	TIVE BUILDING DEMOLITION				
	F2010	Building Elements Demolition	\$16,000			
	F2020	Hazardous Components Abatement	\$0	\$16,000	\$14.55	19.0%
TOTA	AL DIRE	CT COST (Trade Costs)		\$84,298	\$76.63	100.0%



CAFETERIA + DISTRICT OFFICE EXPANSION

Winchester, MA

10 11

12

17

18 19

20 21 22

23

26

27 28

29

30 31

32 33

38 39 40

41

42

43

47 48

49 50 51

52 53

54

Feasibility Design Estimate GFA 1,100

				UNIT	ESTD	SUB	TOTAL	l
	DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST	l

RENOVATION TO McCALL MS - CAFETERIA OPTION 1

TOTAL RENOVATED AREA (GFA) 1,100 GSF

A10 FOUNDATIONS

A1010 STANDARD FOUNDATIONS

No work in this section

SUBTOTAL

A1020 SPECIAL FOUNDATIONS

No work in this section $% \left(1\right) =\left(1\right) \left(

SUBTOTAL

A1030 LOWEST FLOOR CONSTRUCTION

Patch existing slab **1,100** sf 2.50 2,750

SUBTOTAL 2,750

TOTAL - FOUNDATIONS

B1010 FLOOR CONSTRUCTION

B10 SUPERSTRUCTURE

No work in this section

SUBTOTAL

B1020 ROOF CONSTRUCTION

SUBTOTAL -

TOTAL - SUPERSTRUCTURE

B20 EXTERIOR CLOSURE

B2010 EXTERIOR WALLS

No work assumed to existing exterior

SUBTOTAL

B2020 WINDOWS/CURTAINWALL

No work assumed to existing exterior

SUBTOTAL

B2030 EXTERIOR DOORS

No work assumed to existing exterior

SUBTOTAL

TOTAL - EXTERIOR CLOSURE

B30 ROOFING

B3010 ROOF COVERINGS

No work assumed to existing exterior

SUBTOTAL

\$2,750



14-Feb-17 Winchester Schools

CAFETERIA + DISTRICT OFFICE EXPANSION

Winchester, MA

56 57

58

59

60 61

62 63 64

65 66

69

70 71

72

73

77

79 80

81 82 83

84

86

87

89

90

91

92 93

94 95 96

97 98

99

100

101

102 103

104

105

106

108

Feasibility Design Estimate GFA 1,100

				UNIT	EST'D	SUB	TOTAL	ı
	DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST	l

RENOVATION TO McCALL MS - CAFETERIA OPTION 1

B3020 ROOF OPENINGS

No work in this section

SUBTOTAL

TOTAL - ROOFING

C10 INTERIOR CONSTRUCTION

C1010 PARTITIONS

3.00 5,148 Patch existing walls 1,716 $\mathbf{s}\mathbf{f}$

Infill door opening; single door 1,500.00 1,500 loc

SUBTOTAL 6,648

C1020 INTERIOR DOORS

No work in this section

SUBTOTAL

C1030 SPECIALTIES / MILLWORK

Room Signs 150.00 150 loc

Miscellaneous sealants sf 0.50 550 1,100 SUBTOTAL

700

TOTAL - INTERIOR CONSTRUCTION

STAIRCASES C20

> C2010 STAIR CONSTRUCTION No work in this section

SUBTOTAL

C2020 STAIR FINISHES

No work in this section

SUBTOTAL

TOTAL - STAIRCASES

INTERIOR FINISHES Сзо

C3010 WALL FINISHES

Paint to walls etc. 1,100 gsf 3.00 3,300 Patch/paint existing walls ls 2,000.00 2,000

SUBTOTAL

C3020 FLOOR FINISHES

8.00 8,800 New resilient flooring sf 1,100 Patch existing floor at removed walls lf 20.00 2,000 100 2.00 Floor prep 1,100 sf 2,200

SUBTOTAL 13,000

5,300

\$7,348



Winchester Schools

CAFETERIA + DISTRICT OFFICE EXPANSION

Winchester, MA

 Feasibility Design Estimate GFA 1,100

				UNIT	EST'D	SUB	TOTAL
	DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST
RENO	VATION TO McCALL MS - CAFETERIA OPTION 1						
	C3030 CEILING FINISHES						
	ACT, 2x2	1,100	sf	7.00	7,700		
	Patch existing floor at removed walls	100	lf	25.00	2,500		
	SUBTOTAL					10,200	
	TOTAL - INTERIOR FINISHES						\$28,500

D10 CONVEYING SYSTEMS

No work in this section SUBTOTAL

TOTAL - CONVEYING SYSTEMS

D20 PLUMBING

D20 PLUMBING, GENERALLY

No work in this section SUBTOTAL

TOTAL - PLUMBING

D30 HVAC

D30 HVAC, GENERALLY

HVAC modifications **1,100** sf 10.00 11,000

SUBTOTAL 11,000

TOTAL - HVAC \$11,000

D40 FIRE PROTECTION

D40 FIRE PROTECTION, GENERALLY

Sprinkler system modifications **1,100** sf 2.00 2,200

SUBTOTAL 2,200

TOTAL - FIRE PROTECTION \$2,200

D50 ELECTRICAL

D5010 COMPLETE ELECTRICAL SYSTEMS

Lighting, power and Tele/Data modifications **1,100** sf 15.00 16,500

SUBTOTAL 16,500

TOTAL - ELECTRICAL \$16,500

E10 EQUIPMENT

E10 EQUIPMENT, GENERALLY



CAFETERIA + DISTRICT OFFICE EXPANSION

Winchester, MA

164

165

166 167

168 169 170

171

172 173

174

175 176

177

178

179 180

181 182 183

184 185

186

187

188 189

190 191 192

193 194

195

196

197

199

203

204 205

206

Feasibility Design Estimate GFA 1,100

				UNIT	EST'D	SUB	TOTAL	ı
	DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST	

RENOVATION TO McCALL MS - CAFETERIA OPTION 1

No work in this section SUBTOTAL

TOTAL - EQUIPMENT

E20 FURNISHINGS

E2010 FIXED FURNISHINGS

No work in this section

SUBTOTAL

E2020 MOVABLE FURNISHINGS

All movable furnishings to be provided and installed

by owner SUBTOTAL

NIC

TOTAL - FURNISHINGS

F10 SPECIAL CONSTRUCTION

F10 SPECIAL CONSTRUCTION

No items in this section

SUBTOTAL

TOTAL - SPECIAL CONSTRUCTION

F20 SELECTIVE BUILDING DEMOLITION

F2010 BUILDING ELEMENTS DEMOLITION

Gut demolition; finishes and casework 6.00 6,600 1,100 \mathbf{sf} Create opening in bearing wall ls 3,000.00 3,000 Remove walls 1,400 sf 3.00 4,200 Miscellaneous demo/protection 2.00 2,200 gfa 1,100

SUBTOTAL 16,000

F2020 HAZARDOUS COMPONENTS ABATEMENT

None Included SUBTOTAL

TOTAL - SELECTIVE BUILDING DEMOLITION

\$16,000



Feasibility Design Estimate

Winchester Schools CAFETERIA + DISTRICT OFFICE EXPANSION Winchester, MA

Winchester, MA

		CONSTRUCTIO	ON COST SUMMA	RY		
	BUILDING		SUB-TOTAL	TOTAL	\$/SF	%
		O McCALL MS - CAFETERIA OPTION 2	2			
A10	A1010	OATIONS Standard Foundations	\$0			
	A1020	Special Foundations	\$0 \$0			
	A1030	Lowest Floor Construction	\$6,000	\$6,000	\$2.50	2.7%
В10	SUPER	STRUCTURE				
	B1010	Upper Floor Construction	\$24,000			
	B1020	Roof Construction	\$0	\$24,000	\$10.00	10.8%
B20	EXTER	IOR CLOSURE				
	B2010	Exterior Walls	\$0			
	B2020	Windows/Curtainwall	\$0			
	B2030	Exterior Doors	\$0	\$0	\$0.00	0.0%
В30	ROOFI	NG				
	B3010	Roof Coverings	\$0			
	B3020	Roof Openings	\$0	\$0	\$0.00	0.0%
C10	INTER	IOR CONSTRUCTION				
	C1010	Partitions	\$19,600			
	C1020	Interior Doors	\$0			
	C1030	Specialties/Millwork	\$1,350	\$20,950	\$8.73	9.5%
C20	STAIR	CASES				
	C2010	Stair Construction	\$0			
	C2020	Stair Finishes	\$0	\$0	\$0.00	0.0%
С30	INTER	IOR FINISHES				
	C3010	Wall Finishes	\$11,200			
	C3020	Floor Finishes	\$28,100			
	C3030	Ceiling Finishes	\$19,300	\$58,600	\$24.42	26.4%
D10		YING SYSTEMS				
	D1010	Elevator	\$0	\$0	\$0.00	0.0%
D20						
	D20	Plumbing	\$0	\$0	\$0.00	0.0%
D30						
	D30	HVAC	\$24,000	\$24,000	\$10.00	10.8%
D40		ROTECTION				
	D40	Fire Protection	\$4,800	\$4,800	\$2.00	2.2%

14-Feb-17

2,400



Feasibility Design Estimate GFA 2,400

	BUILDING	SYSTEM	SUB-TOTAL	TOTAL	\$/SF	%
NOVA	ATION TO	O McCALL MS - CAFETERIA OPTION 2				
D50	ELECT	RICAL				
	D5010	Electrical Systems	\$36,000	\$36,000	\$15.00	16.2%
E10	EQUIP	MENT				
	E10	Equipment	\$0	\$0	\$0.00	0.0%
E20	FURNIS	SHINGS				
	E2010	Fixed Furnishings	\$0			
	E2020	Movable Furnishings	NIC	\$0	\$0.00	0.0%
F10	SPECIA	AL CONSTRUCTION				
	F10	Special Construction	\$0	\$0	\$0.00	0.0%
F20	SELEC	FIVE BUILDING DEMOLITION				
	F2010	Building Elements Demolition	\$47,310			
	F2020	Hazardous Components Abatement	\$0	\$47,310	\$19.71	21.3%
TOTA	AL DIREC	CT COST (Trade Costs)		\$221,660	\$92.36	100.0%



Winchester Schools

CAFETERIA + DISTRICT OFFICE EXPANSION

Winchester, MA

18 19

20

25

26

27 28

34

35 36

37

38

39 40

41

46

47 48

49 50 51

52 53

55

Feasibility Design Estimate GFA 2,400

				UNIT	EST'D	SUB	TOTAL	
	DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST	

RENOVATION TO McCALL MS - CAFETERIA OPTION 2

TOTAL RENOVATED AREA (GFA) 2,400 GSF

A10 FOUNDATIONS

A1010 STANDARD FOUNDATIONS

No work in this section

SUBTOTAL

A1020 SPECIAL FOUNDATIONS

No work in this section $% \left\{ \left\{ 1\right\} \right\} =\left\{ 1\right\} =\left\{ 1$

SUBTOTAL

A1030 LOWEST FLOOR CONSTRUCTION

Patch existing slab **2,400** sf 2.50 6,000

SUBTOTAL 6,000

TOTAL - FOUNDATIONS \$6,000

B10 SUPERSTRUCTURE

B1010 FLOOR CONSTRUCTION

Infill floor structure at removed stair **800** sf 30.00 24,000

SUBTOTAL 24,000

B1020 ROOF CONSTRUCTION

SUBTOTAL -

TOTAL - SUPERSTRUCTURE \$24,000

B20 EXTERIOR CLOSURE

B2010 EXTERIOR WALLS

No work assumed to existing exterior

SUBTOTAL

B2020 WINDOWS/CURTAINWALL

No work assumed to existing exterior

SUBTOTAL

B2030 EXTERIOR DOORS

No work assumed to existing exterior

SUBTOTAL

TOTAL - EXTERIOR CLOSURE

B30 ROOFING

B3010 ROOF COVERINGS

No work assumed to existing exterior

SUBTOTAL



CAFETERIA + DISTRICT OFFICE EXPANSION

Winchester, MA

56 57

58

59

60

67

68

69

70 71

74

75 76

77

78

79 80

82 83

84

86

87

88

90

91

92 93

94 95 96

97 98

99

100

101

102 103

104

105

107

108

Feasibility Design Estimate GFA 2,400

				UNIT	EST'D	SUB	TOTAL	ı
	DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST	

RENOVATION TO McCALL MS - CAFETERIA OPTION 2

B3020 ROOF OPENINGS

No work in this section SUBTOTAL

TOTAL - ROOFING

C10 INTERIOR CONSTRUCTION

C1010 PARTITIONS

 Patch existing walls
 3,024
 sf
 3.00
 9,072

 New partition
 658
 sf
 16.00
 10,528

SUBTOTAL 19,600

C1020 INTERIOR DOORS

No work in this section $% \left(1\right) =\left(1\right) \left(

SUBTOTAL -

C1030 SPECIALTIES / MILLWORK

 Room Signs
 1
 loc
 150.00
 150

 Miscellaneous sealants
 2,400
 sf
 0.50
 1,200

SUBTOTAL 1,350

TOTAL - INTERIOR CONSTRUCTION

C20 STAIRCASES

C2010 STAIR CONSTRUCTION

No work in this section

SUBTOTAL -

C2020 STAIR FINISHES

No work in this section $% \left\{ \left\{ 1\right\} \right\} =\left\{ 1\right\} =\left\{ 1$

SUBTOTAL -

TOTAL - STAIRCASES

C30 INTERIOR FINISHES

C3010 WALL FINISHES

 Paint to walls etc.
 2,400
 gsf
 3.00
 7,200

 Patch/paint existing walls
 1
 ls
 4,000.00
 4,000

SUBTOTAL 11,200

C3020 FLOOR FINISHES

 New resilient flooring
 2,400
 sf
 8.00
 19,200

 Patch existing floor at removed walls
 205
 lf
 20.00
 4,100

 Floor prep
 2,400
 sf
 2.00
 4,800

SUBTOTAL 28,100

\$20,950



CAFETERIA + DISTRICT OFFICE EXPANSION

Winchester, MA

Feasibility Design Estimate	GFA	2,400
-----------------------------	-----	-------

	DESCRIPTION	QTY	UNIT	UNIT COST	EST'D COST	SUB TOTAL	TOTAL
JOVATIO	N TO McCALL MS - CAFETERIA OPTION 2	Q11	Civii	COST	COST	TOTAL	
	CEILING FINISHES						
	ACT, 2x2	2,400	sf	7.00	16,800		
	Patch existing floor at removed walls	100	lf	25.00	2,500		
	SUBTOTAL					19,300	
	TOTAL - INTERIOR FINISHES						\$58,6
D10	CONVEYING SYSTEMS	\neg					
Dio	CONVERNOSISTEMS	_					
	No work in this section						
	SUBTOTAL					-	
	TOTAL - CONVEYING SYSTEMS						
		_					
D20	PLUMBING						
D20	PLUMBING, GENERALLY						
	No work in this section						
	SUBTOTAL					-	
	TOTAL - PLUMBING						
D30	HVAC						
D30	HVAC, GENERALLY						
	HVAC modifications	2,400	sf	10.00	24,000		
	SUBTOTAL					24,000	
	TOTAL - HVAC						\$24,0
D40	FIRE PROTECTION						
D40	FIRE PROTECTION, GENERALLY						
	Sprinkler system modifications	2,400	sf	2.00	4,800		
	SUBTOTAL					4,800	
	TOTAL - FIRE PROTECTION						\$4,8
D50	ELECTRICAL						
D5010	COMPLETE ELECTRICAL SYSTEMS						
9	Lighting, power and Tele/Data modifications	2,400	sf	15.00	36,000		
	SUBTOTAL					36,000	
	TOTAL ELECTRICAL						b -7 -
	TOTAL - ELECTRICAL						\$36,0

E10 EQUIPMENT, GENERALLY

E10

EQUIPMENT

161

162 163



CAFETERIA + DISTRICT OFFICE EXPANSION

Winchester, MA

164

165

166 167

170

171 172

173

174

175 176

177

178

179 180

181 182 183

184 185

186

187

188 189

190 191 192

196

196

197

199

200 201

202

203

204 205

206

Feasibility Design Estimate GFA 2,400

			UNIT	EST'D	SUB	TOTAL
DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST

RENOVATION TO McCALL MS - CAFETERIA OPTION 2

No work in this section SUBTOTAL

TOTAL - EQUIPMENT

E20 FURNISHINGS

E2010 FIXED FURNISHINGS

No work in this section

SUBTOTAL

E2020 MOVABLE FURNISHINGS

All movable furnishings to be provided and installed

by owner

SUBTOTAL

TOTAL - FURNISHINGS

F10 SPECIAL CONSTRUCTION

F10 SPECIAL CONSTRUCTION

No items in this section

SUBTOTAL

TOTAL - SPECIAL CONSTRUCTION

F20 SELECTIVE BUILDING DEMOLITION

F2010 BUILDING ELEMENTS DEMOLITION

14,400 Gut demolition; finishes and casework 6.00 2,400 sf Create opening in bearing wall ls 4,500.00 4,500 Remove walls 2,870 sf 3.00 8,610 Remove stair flight and patch/new finishes 15.000.00 15.000 ls Miscellaneous demo/protection 2,400 gfa 2.00 4,800

SUBTOTAL 47,310

F2020 HAZARDOUS COMPONENTS ABATEMENT

None Included SUBTOTAL

TOTAL - SELECTIVE BUILDING DEMOLITION

\$47,310



Feasibility Design Estimate

Winchester Schools CAFETERIA + DISTRICT OFFICE EXPANSION Winchester, MA

CAFETERIA + DISTRICT OFFICE EXPANSION

CONSTRUCTION COST SUMMARY BUILDING SYSTEM SUB-TOTAL TOTAL \$/SF **ADDITION AT CAFETERIA - OPTION 3** A10 **FOUNDATIONS** A1010 Standard Foundations \$184,721 A1020 Special Foundations \$54,250 A1030 **Lowest Floor Construction** \$56,272 \$295,243 \$193.60 37.4% BASEMENT CONSTRUCTION A20 A2010 **Basement Excavation** \$0 A2020 **Basement Walls** \$0 \$0.00 0.0% **\$0 B10 SUPERSTRUCTURE** B1010 **Upper Floor Construction** \$0 B1020 **Roof Construction** \$55.675 \$55,675 \$36.51 7.1% **B20 EXTERIOR CLOSURE** B2010 **Exterior Walls** \$0 B2020 Windows \$181,213 B2030 **Exterior Doors** \$0 22.9% \$181,213 \$118.83 **B30 ROOFING** B3010 \$34.933 **Roof Coverings** B3020 **Roof Openings** \$0 \$22.91 4.4% \$34,933 C10 INTERIOR CONSTRUCTION C1010 **Partitions** \$0 C1020 Interior Doors \$0 Specialties/Millwork C1030 \$3,431 \$2.25 \$3,431 0.4% **STAIRCASES C20** C2010 Stair Construction \$0 C2020 Stair Finishes \$0 **\$0** \$0.00 0.0% **INTERIOR FINISHES** C30 C3010 Wall Finishes \$6.863 C3020 Floor Finishes \$13,725 C3030 Ceiling Finishes \$10,675 \$31,263 \$20.50 4.0% D10 **CONVEYING SYSTEMS** D1010 Elevator \$0 \$0.00 0.0% **\$0 D20 PLUMBING** D20 \$7,625 \$5.00 1.0% Plumbing \$7,625

14-Feb-17

1,525



Feasibility Design Estimate GFA 1,525

	BUILDING	SYSTEM	SUB-TOTAL	TOTAL	\$/SF	%
DITIO	ON AT CA	AFETERIA - OPTION 3				
D30	HVAC					
	D30	HVAC	\$68,625	\$68,625	\$45.00	8.7%
D40	FIRE P	ROTECTION				
	D40	Fire Protection	\$6,863	\$6,863	\$4.50	0.9%
D50	ELECT	RICAL				
	D5010	Complete System	\$38,125	\$38,125	\$25.00	4.8%
E10	EQUIP	MENT				
	E10	Equipment	\$0	\$0	\$0.00	0.0%
E20	FURNIS	SHINGS				
	E2010	Fixed Furnishings	\$8,748			
	E2020	Movable Furnishings	NIC	\$8,748	\$5.74	1.1%
F10	SPECIA	AL CONSTRUCTION				
	F10	Special Construction	\$0	\$0	\$0.00	0.0%
F20	HAZMA	AT REMOVALS				
	F2010	Building Elements Demolition	\$57,960			
	F2020	Hazardous Components Abatement	\$0	\$57,960	\$38.01	7.3%
		CT COST (Trade Costs)		\$789,704	\$517.84	100.0%



14-Feb-17

Winc	nester,	MA	

Feasibility Design Estimate

CSI				UNIT	EST'D	SUB	TOTAL
CODE	DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST

GROSS FLOOR AREA CALCULATION

First Floor 1,525

	TOTAL GROSS FLOOR AREA (GFA)				1,525 sf	
A10	FOUNDATIONS					
A1010	STANDARD FOUNDATIONS Strip footings - 8'-0" x 1'-6"					
	Excavation	178	cy	35.00	6,230	
	Store on site for reuse	178	cy	14.00	2,492	
	Backfill with existing fill	141	cy	16.00	2,256	
	Remove surplus fill off site	37	cy	25.00	925	
	Formwork	240	sf	12.00	2,880	
	Re-bar	4,440	lbs	1.20	5,328	
	Concrete material; 3,000 psi	37	cy	125.00	4,625	
	Placing concrete	37	cy	55.00	2,035	
	Foundation walls at exterior - 14" thick					
	Formwork	3,200	sf	16.00	51,200	
	Re-bar, 4.5#/sf	7,200	lbs	1.20	8,640	
	Concrete material; 4,000 psi	73	cy	135.00	9,855	
	Placing concrete	73	cy	65.00	4,745	
	Waterproofing foundation wall and footing	1,600	sf	7.00	11,200	
	Insulation to foundation walls; 2" thick	320	sf	2.50	800	
	Form shelf	80	lf	8.00	640	
	Column footings, typical, 6' x 6' x 2'-0"					
	Excavation	94	cy	20.00	1,880	
	Store on site for reuse	94	cy	14.00	1,316	
	Backfill with new fill	72	cy	16.00	1,152	
	Remove surplus fill off site	22	cy	20.00	440	
	Formwork	384	sf	11.00	4,224	
	Re-bar	4,480	lbs	1.20	5,376	
	Concrete material; 3,000 psi	22	cy	125.00	2,750	
	Placing concrete	22	cy	55.00	1,210	
	Set anchor bolts grout plates	8	ea	150.00	1,200	
	<u>Interior pilasters</u>					
	Formwork	234	sf	11.00	2,574	
	Re-bar	1,440	lbs	1.20	1,728	
	Concrete material; 3,000 psi	4	cy	125.00	500	
	Placing concrete	4	cy	55.00	220	
	Work around existing utilities	1	ls	10,000.00	10,000	
	Foundations against face of existing building	33	lf	1,100.00	36,300	
	SUBTOTAL					184,721
A1000	SPECIAL FOUNDATIONS					
A1020	Sheeting and shoring allowance	1,085	sf	50.00	54,250	
	Successing and shoring allowance	1,005	51	30.00	J4,2JU	

GFA

1,525



Feasibility Design Estimate

Winchester Schools CAFETERIA + DISTRICT OFFICE EXPANSION Winchester, MA

Winchester, MA

SI ODE	DESCRIPTION	QTY	UNIT	UNIT COST	EST'D COST	SUB TOTAL	TOTAL COST
DDITION	AT CAFETERIA - OPTION 3	1	1				
	SUBTOTAL					54,250	
A102	O LOWEST FLOOR CONSTRUCTION						
11100	New Slab on grade, 5" thick						
	Structural gravel fill	960	cy	30.00	28,800		
	Rigid insulation	1,525	sf	2.25	3,431		
	Vapor barrier	1,525	sf	1.00	1,525		
	Mesh reinforcing 15% lap	1,754	sf	0.80	1,403		
	Concrete - 5" thick	25	су	125.00	3,125		
	Placing concrete	25	cy	45.00	1,125		
	Finishing and curing concrete	1,525	sf	4.00	6,100		
	Control joints - saw cut	1,525	sf	0.50	763		
	Miscellaneous	-,5-5					
	Dewatering	1	ea	10,000.00	10,000		
	SUBTOTAL	-		-,	,0	56,272	
						/	
	TOTAL - FOUNDATIONS						\$295,
A20	D BASEMENT CONSTRUCTION						
AZO	BASEMENT CONSTRUCTION						
A201	O BASEMENT EXCAVATION						
	No items in this section						
	SUBTOTAL					-	
A202	20 BASEMENT WALLS						
	No items in this section						
	SUBTOTAL					-	
	TOTAL - BASEMENT CONSTRUCTION						
B10	SUPERSTRUCTURE						
210							
B101	o FLOOR CONSTRUCTION						
	No items in this section						
	SUBTOTAL					-	
B102	o ROOF CONSTRUCTION						
	Roof Structure - Steel:						
	Steel beams/Joists; 13#/SF	10	tns	4,500.00	45,000		
	Roof Structure						
	1-1/2" Metal floor Deck @ roof	1,525	sf	3.00	4,575		
	Miscellaneous	,5 0					
	Fire proofing to columns, beams and deck	1,525	sf	4.00	6,100		
	SUBTOTAL	,5 0				55,675	
	TOTAL CUDEDCEDUCTUDE						Φ==
	TOTAL - SUPERSTRUCTURE						\$55 ,

98

14-Feb-17

1,525



103

104

105

106 107

108

109

110

111 112

113

114

115

116

117 118 119

120 121

122

123

124

125

126

127

128

129

130

131 132

133

134

135 136

137 138 139

140 141

142

143

144 145

146

147

148 149

150

151

Feasibility Design Estimate	GFA	1,525
-----------------------------	-----	-------

CSI				UNIT	EST'D	SUB	TOTAL
CODE	DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST

ADDITION AT CAFETERIA - OPTION 3

B2010 EXTERIOR WALLS

No items in this section

SUBTOTAL

B2020 WINDOWS

Curtainwall 120.00 174,960 1,458 sf Backer rod & double sealant lf 481 9.00 4,329 Wood blocking at openings 481 lf 4.00 1,924

SUBTOTAL 181,213

B2030 EXTERIOR DOORS

No items in this section

SUBTOTAL

TOTAL - EXTERIOR CLOSURE

\$181,213

14-Feb-17

Взо ROOFING

ROOF COVERINGS B3010

Flat roofing

PVC roof membrane fully adhered 8.00 12,200 1,525 sf Insulation 7.00 10,675 1,525 sf 2.00 1/2" dens-deck protection board sf 3,050 1,525 Reinforced vapor barrier 1,525 sf 1.50 2,288 Rough blocking lf 6.00 1,920 320 Miscellaneous Roofing Roof fascia/cornice 60.00 80 lf 4,800

SUBTOTAL 34,933

B3020 ROOF OPENINGS

Skylights, allow NIC

SUBTOTAL

TOTAL - ROOFING \$34,933

INTERIOR CONSTRUCTION C10

C1010 PARTITIONS

No items in this section

SUBTOTAL

C1020 INTERIOR DOORS

No items in this section

SUBTOTAL

C1030 SPECIALTIES / MILLWORK

Miscellaneous metals throughout building 1.25 1.906 1,525 sf Miscellaneous sealants throughout building 1.00 1,525 sf 1,525



153 154

155 156 157

158 159

160

161

162 163

164

165

166 167

168 169 170

171

172 173

174

175 176

177

178

179

180 181

182

183 184

185 186 187

188 189

190

191

192 193

194 195 196

197

199

200

201 202

203 204 205

206 207

208

Winchester Schools CAFETERIA + DISTRICT OFFICE EXPANSION Winchester, MA

Feasibility Design Estimate GFA 1.525

CSI				UNIT	EST'D	SUB	TOTAL	ı
CODE	DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST	ı

ADDITION AT CAFETERIA - OPTION 3

SUBTOTAL 3.431

TOTAL - INTERIOR CONSTRUCTION \$3,431

STAIRCASES C20

C2010 STAIR CONSTRUCTION

No items in this section

SUBTOTAL

C2020 STAIR FINISHES

No items in this section

SUBTOTAL

TOTAL - STAIRCASES

INTERIOR FINISHES Сзо

C3010 WALL FINISHES

1,525 SUBTOTAL 6,863

gfa

4.50

6,863

C3020 FLOOR FINISHES

Wall finishes

Floor finishes 9.00 13,725 1,525 sf

SUBTOTAL 13,725

C3030 CEILING FINISHES

Ceiling finishes 7.00 10,675 1,525 sf

SUBTOTAL 10,675

TOTAL - INTERIOR FINISHES \$31,263

D10 CONVEYING SYSTEMS

D1010 ELEVATOR

No items in this section

SUBTOTAL

TOTAL - CONVEYING SYSTEMS

D20 **PLUMBING**

D20 PLUMBING, GENERALLY

Plumbing allowance 5.00 7,625 1,525 gsf

SUBTOTAL 7,625

TOTAL - PLUMBING \$7,625

D30 HVAC

HVAC, GENERALLY D30

HVAC complete system gsf 45.00 68,625 1,525



210 211

212 213 214

215 216

217

218

219 220

221 222 223

224 225

226

227

228 229 230

231 232 233

234 235

238

243 244

245

246

247 248

249

250

251 252

253 254 255

256 257

258

259

260 261

263 264

265

Feasibility Design Estimate

Winchester Schools CAFETERIA + DISTRICT OFFICE EXPANSION Winchester, MA

CAPELEKIA + DISTRICT OFFICE EXPANSION
Winchester MA

CSI				UNIT	EST'D	SUB	TOTAL
CODE	DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST

ADDITION AT CAFETERIA - OPTION ${\bf 3}$

SUBTOTAL 68,625

TOTAL - HVAC \$68,625

D40 FIRE PROTECTION

D40 FIRE PROTECTION, GENERALLY

Sprinkler system **1,525** gsf 4.50 6,863

SUBTOTAL 6,863

TOTAL - FIRE PROTECTION \$6,863

D50 ELECTRICAL

D5010 COMPLETE ELECTRICAL SYSTEM

Electrical system; complete **1,525** gsf 25.00 38,125

SUBTOTAL 38,125

TOTAL - ELECTRICAL \$38,125

E10 EQUIPMENT

E10 EQUIPMENT, GENERALLY

AV Equipment (including Smartboards, Projectors, FF+E LED monitors, Digital information displays etc.)

SUBTOTAL

TOTAL - EQUIPMENT

E20 FURNISHINGS

E2010 FIXED FURNISHINGS

Manual operated roller shades 1,458 sf 6.00 8,748

SUBTOTAL 8,748

E2020 MOVABLE FURNISHINGS

All movable furnishings to be provided and installed

by owner

SUBTOTAL

TOTAL - FURNISHINGS \$8,748

F10 SPECIAL CONSTRUCTION

F10 SPECIAL CONSTRUCTION

No Work in this section

SUBTOTAL

TOTAL - SPECIAL CONSTRUCTION

F20 SELECTIVE BUILDING DEMOLITION

14-Feb-17

1,525



Feasibility Design Estimate

Winchester Schools CAFETERIA + DISTRICT OFFICE EXPANSION Winchester, MA

TOTAL - SELECTIVE BUILDING DEMOLITION

Winchester, MA

CSI					UNIT	EST'D	SUB	TOTAL
CODE	E	DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST
ADD	DITION AT	CAFETERIA - OPTION 3						
266	F2010	BUILDING ELEMENTS DEMOLITION						
267		Create openings to existing façade for new connections	864	sf	15.00	12,960		
68		Demolish existing patio and steps	1	ls	20,000.00	20,000		
269		Relocate existing utilities	1	ls	15,000.00	15,000		
70		Restore/new landscaping	1	ls	10,000.00	10,000		
71		SUBTOTAL					57,960	
72								
73 74	F2020	HAZARDOUS COMPONENTS ABATEMENT None Included						
75 76		SUBTOTAL						

14-Feb-17

1,525

\$57,960



Winchester Schools

CAFETERIA + DISTRICT OFFICE EXPANSION

Winchester, MA

Feasibility Design Estimate	GFA	1,250

			UNIT	EST'D	SUB	TOTAL
DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST

RENOVATION TO McCALL MS - TEACHERS ROOM

	TOTAL RENOVATED AREA (GFA)				1,250 GS	SF	
C10	INTERIOR CONSTRUCTION						
C1010	PARTITIONS						
	New walls at storage area	403	sf	15.00	6,045		
	SUBTOTAL					6,045	
C1020	INTERIOR DOORS						
	New single door	1	ea	1,800.00	1,800		
	SUBTOTAL					1,800	
	SPECIALTIES / MILLWORK						
	Room Signs	1	loc	150.00	150		
	Miscellaneous sealants	1,250	sf	0.50	625		
	SUBTOTAL					775	
	TOTAL - INTERIOR CONSTRUCTION						\$8,62
	INTERIOR FINISHES WALL FINISHES						
	Paint to walls etc.	1,250	gsf	3.00	3,750		
	SUBTOTAL					3,750	
	FLOOR FINISHES						
	New resilient flooring	1,250	sf	8.00	10,000		
	Floor prep	1,250	sf	2.00	2,500		
	SUBTOTAL					12,500	
С3030	CEILING FINISHES						
	No items in this section						
	SUBTOTAL					-	
	TOTAL - INTERIOR FINISHES						\$16,25
D30	HVAC						
_							
D30	HVAC, GENERALLY						

No items in this section SUBTOTAL

TOTAL - HVAC

FIRE PROTECTION D40

D40 FIRE PROTECTION, GENERALLY

Sprinkler system modifications 1,250 2.00 2,500 SUBTOTAL

2,500



CAFETERIA + DISTRICT OFFICE EXPANSION

Winchester, MA

55 56

57 58 59

60 61

62

63

64 65

67 68

69 70

71

73 74

75

76

77

78 79 80

86

91

92

93

92

Feasibility Design Estimate GFA 1,250

			UNIT	EST'D	SUB	TOTAL
DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST

RENOVATION TO McCALL MS - TEACHERS ROOM

TOTAL - FIRE PROTECTION \$2,500

D50 ELECTRICAL

D5010 COMPLETE ELECTRICAL SYSTEMS

Lighting, power and Tele/Data modifications 1,250 sf 15.00 18,750

SUBTOTAL 18,750

TOTAL - ELECTRICAL \$18,750

E20 FURNISHINGS

E2010 FIXED FURNISHINGS

No work in this section

SUBTOTAL -

E2020 MOVABLE FURNISHINGS

All movable furnishings to be provided and installed

by owner

SUBTOTAL

TOTAL - FURNISHINGS

F20 SELECTIVE BUILDING DEMOLITION

F2010 BUILDING ELEMENTS DEMOLITION

Gut demolition; floor finishes **1,250** sf 1.00 1,250

SUBTOTAL 1,250

F2020 HAZARDOUS COMPONENTS ABATEMENT

None Included SUBTOTAL

TOTAL - SELECTIVE BUILDING DEMOLITION \$1,250

TOTAL - TEACHERS ROOM \$47,370



CAFETERIA + DISTRICT OFFICE EXPANSION

Feasibility Design Estimate GFA 4,900 CONSTRUCTION COST SUMMARY BUILDING SYSTEM SUB-TOTAL TOTAL \$/SF DISTRICT OFFICE ADDITION TO LYNCH OPTION WPS-1 A10 **FOUNDATIONS** Standard Foundations \$148,669 A1010 A1020 Special Foundations \$0 A1030 **Lowest Floor Construction** \$65,553 \$214,222 \$43.72 15.5% BASEMENT CONSTRUCTION A20 A2010 **Basement Excavation** \$0 A2020 **Basement Walls** \$0 \$0.00 0.0% **\$0 B10 SUPERSTRUCTURE** B1010 **Upper Floor Construction** \$0 B1020 **Roof Construction** \$144,500 \$29.49 10.5% \$144,500 **B20 EXTERIOR CLOSURE** B2010 **Exterior Walls** \$133,595 B2020 Windows \$110,011 B2030 **Exterior Doors** \$16,520 \$53.09 18.8% \$260,126 **ROOFING B30** B3010 \$106.330 **Roof Coverings** B3020 **Roof Openings** \$0 \$106,330 \$21.70 7.7% C10 INTERIOR CONSTRUCTION C1010 **Partitions** \$139,838 C1020 Interior Doors \$66,000 C1030 \$20,297 Specialties/Millwork \$226,135 \$46.15 16.4% **STAIRCASES C20** C2010 Stair Construction \$0 C2020 Stair Finishes \$0 **\$0** \$0.00 0.0% **INTERIOR FINISHES** C30 C3010 Wall Finishes \$29,646 C3020 Floor Finishes \$32,437 C3030 Ceiling Finishes \$23,540 \$85,623 \$17.47 6.2% **CONVEYING SYSTEMS** D10 D1010 Elevator \$0 \$0.00 0.0% **\$0 D20 PLUMBING** D20 \$30,000 \$6.12 2.2% Plumbing \$30,000



Feasibility Design Estimate

Winchester Schools
CAFETERIA + DISTRICT OFFICE EXPANSION
Winchester MA

Winchester, MA

		CONSTRUCTION	COST SUMM	ARY		
	BUILDING		SUB-TOTAL	TOTAL	\$/SF	%
STRIC	T OFFIC	E ADDITION TO LYNCH OPTION WPS	S-1			
D30	HVAC					
	D30	HVAC	\$137,200	\$137,200	\$28.00	9.9%
D40	FIRE P	ROTECTION				
	D40	Fire Protection	\$19,600	\$19,600	\$4.00	1.4%
D50	ELECT	RICAL				
	D5010	Complete System	\$107,800	\$107,800	\$22.00	7.8%
E10	EQUIP	MENT				
	E10	Equipment	\$0	\$0	\$0.00	0.0%
E20	FURNIS	SHINGS				
	E2010	Fixed Furnishings	\$24,342			
	E2020	Movable Furnishings	NIC	\$24,342	\$4.97	1.8%
F10	SPECIA	AL CONSTRUCTION				
	F10	Special Construction	\$0	\$0	\$0.00	0.0%
F20	HAZMA	AT REMOVALS				
	F2010	Building Elements Demolition	\$25,000			
	F2020	Hazardous Components Abatement	\$0	\$25,000	\$5.10	1.8%
<i></i>	I DIDE	CT COST (Trade Costs)		\$1,380,878	\$281.81	100.0%

14-Feb-17

4,900



3

Feasibility Design Estimate GFA 4,900

CSI				UNIT	EST'D	SUB	TOTAL
CODE	DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST

DISTRICT OFFICE ADDITION TO LYNCH OPTION WPS-1

GROSS I		

First Floor 4,900

	TOTAL GROSS FLOOR AREA (GFA)				4,900 sf	
A10	FOUNDATIONS					
A1010	STANDARD FOUNDATIONS Strip footings - 2'-0" x 1'-0"					
	Excavation	244	cy	20.00	4,880	
	Store on site for reuse	244	cy	14.00	3,416	
	Backfill with existing fill	227	cy	16.00	3,632	
	Remove surplus fill off site	17	cy	25.00	425	
	Formwork	440	sf	12.00	5,280	
	Re-bar, 10#/lf	2,200	lbs	1.20	2,640	
	Concrete material; 3,000 psi	17	cy	125.00	2,125	
	Placing concrete	17	cy	55.00	935	
	Foundation walls at exterior - 14" thick					
	Formwork	1,760	sf	14.00	24,640	
	Re-bar, 4.5#/sf	3,960	lbs	1.20	4,752	
	Concrete material; 4,000 psi	40	cy	135.00	5,400	
	Placing concrete	40	cy	65.00	2,600	
	Dampproofing foundation wall and footing	1,320	sf	1.90	NIC	
	Insulation to foundation walls; 2" thick	880	sf	2.50	2,200	
	Form shelf	220	lf	8.00	1,760	
	Column footings, typical, 5' x 5' x 2'-0"					
	Excavation	285	cy	20.00	5,700	
	Store on site for reuse	285	cy	14.00	3,990	
	Backfill with new fill	227	cy	16.00	3,632	
	Remove surplus fill off site	58	cy	20.00	1,160	
	Formwork	1,200	sf	11.00	13,200	
	Re-bar	8,120	lbs	1.20	9,744	
	Concrete material; 3,000 psi	58	cy	125.00	7,250	
	Placing concrete	58	cy	55.00	3,190	
	Set anchor bolts grout plates	30	ea	150.00	4,500	
	Interior pilasters					
	Formwork	878	sf	11.00	9,658	
	Re-bar	5,400	lbs	1.20	6,480	
	Concrete material; 3,000 psi	16	cy	125.00	2,000	
	Placing concrete	16	сy	55.00	880	
	Foundations against existing building	70	lf	180.00	12,600	
	SUBTOTAL					148,669
A1020	SPECIAL FOUNDATIONS					

48

49 50



14-Feb-17

ODE	DESCRIPTION	QTY	UNIT	UNIT COST	EST'D COST	SUB TOTAL	TOTAL COST
DISTRICT	OFFICE ADDITION TO LYNCH OPTION WPS-1			<u>'</u>	"	<u> </u>	
	New Slab on grade, 5" thick						
	Structural gravel fill, 8"	121	cy	30.00	3,630		
	Base course, 8" gravel	121	cy	40.00	4,840		
	Rigid insulation	4,900	sf	2.25	11,025		
	Vapor barrier	4,900	sf	1.00	4,900		
	Mesh reinforcing 15% lap	5,635	sf	0.80	4,508		
	Concrete - 5" thick	80	cy	125.00	10,000		
	Placing concrete	80	cy	45.00	3,600		
	Finishing and curing concrete	4,900	sf	4.00	19,600		
	Control joints - saw cut		sf	0.50	2,450		
		4,900	51	0.30	2,430		
	<u>Miscellaneous</u>			1 000 00	1.000		
	Dewatering	1	ea	1,000.00	1,000	05 550	
	SUBTOTAL					65,553	
	TOTAL - FOUNDATIONS						\$214
A2	o BASEMENT CONSTRUCTION						
100	010 BASEMENT EXCAVATION						
A20	No items in this section						
	SUBTOTAL						
	SOBIOTAL					-	
A20	20 BASEMENT WALLS						
	No items in this section						
	SUBTOTAL					-	
	TOTAL - BASEMENT CONSTRUCTION						
B1	o SUPERSTRUCTURE						
		12	lbs/sf				
B10	010 FLOOR CONSTRUCTION	29	tns				
	No Work in this section						
	SUBTOTAL					-	
B10	20 ROOF CONSTRUCTION						
	Roof Structure - Steel:						
	Steel beams/Joists; 12#/SF	29	tns	3,800.00	110,200		
	Roof Structure			-,			
	1-1/2" Metal floor Deck @ roof	4,900	sf	3.00	14,700		
	Miscellaneous	4,900	31	3.00	14,700		
	Roof screen framing - allow				NIC		
		4.000	°t.	4.00			
	Fire proofing to columns, beams and deck SUBTOTAL	4,900	sf	4.00	19,600	144,500	
_							
	TOTAL - SUPERSTRUCTURE						\$144

98



Feasibility Design Estimate

Winchester Schools
CAFETERIA + DISTRICT OFFICE EXPANSION
Winchester, MA

Winchester, MA

CSI				UNIT	EST'D	SUB	TOTAL
CODE	DESCRIPTION	OTY	UNIT	COST	COST	TOTAL	COST

DISTRICT OFFICE	' ADDITION TO	IVNCH	ODTION W/DC-1

IOR WALLS; 60% solid/40% glass skin stud backup dation in stud igid Insulation er er/flashing at windows Sheathing lining to interior face of stud backup skin	1,848 1,848 1,848 1,848 407 1,848	sf sf sf sf sf	7.50 2.25 3.00 6.00	13,860 4,158 5,544		
ulation in stud igid Insulation er er/flashing at windows Sheathing lining to interior face of stud backup	1,848 1,848 1,848 407 1,848	sf sf sf lf	2.25 3.00	4,158		
igid Insulation er er/flashing at windows Sheathing lining to interior face of stud backup	1,848 1,848 407 1,848	sf sf lf	3.00	•		
er er/flashing at windows Sheathing lining to interior face of stud backup	1,848 407 1,848	sf lf		5,544		
er/flashing at windows Sheathing lining to interior face of stud backup	407 1,848	lf	6.00			
Sheathing lining to interior face of stud backup	1,848			11,088		
lining to interior face of stud backup	, •	_	7.00	2,849		
0	1.848	sf	2.75	5,082		
<u>skin</u>	-,	sf	3.00	5,544		
neer; 75% of exterior wall	1,386	sf	35.00	48,510		
nels; 25% of exterior wall	462	sf	60.00	27,720		
neous						
to exterior wall	3,080	sf	3.00	9,240		
TAL					133,595	
ows	1,232	sf				
n for sunscreen and light shelf elements	1	ls		NIC		
s/storefront	1,232	sf	85.00	104,720		
od & double sealant	407	lf	9.00	3,663		
ocking at openings	407	lf	4.00	1,628		
TAL					110,011	
IOR DOORS						
ntrance doors including frame and hardware; loor at corridor exit	2	pr	8,000.00	16,000		
	40	lf	9.00	360		
od & double sealant	40	lf	4.00	160		
od & double sealant ocking at openings					16,520	
	& double sealant king at openings L	king at openings 40	king at openings 40 lf	king at openings 40 lf 4.00	king at openings 40 lf 4.00 160	king at openings 40 lf 4.00 160

Взо	ROOFING				
B3010	ROOF COVERINGS Flat roofing				
	PVC roof membrane fully adhered	4,900	sf	9.00	44,100
	Insulation	4,900	sf	7.00	34,300
	1/2" dens-deck protection board	4,900	sf	2.00	9,800

Reinforced vapor barrier 4,900 sf 1.50 7,350

Rough blocking 880 lf 6.00 5,280

 Miscellaneous Roofing
 NIC

 Roof screens - allow
 220
 lf
 25.00
 5,500

SUBTOTAL 106,330

14-Feb-17

4,900



Feasibility Design Estimate GFA 4,900

CSI CODE		DESCRIPTION	OTV	UNIT	UNIT COST	EST'D COST	SUB TOTAL	TOTAL COST
ODE		DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST
DISTE		FICE ADDITION TO LYNCH OPTION WPS-1						
	B3020	ROOF OPENINGS						
		Skylights, allow				NIC		
		Roof hatch				NIC		
		SUBTOTAL					-	
		TOTAL - ROOFING						\$106,
	C10	INTERIOR CONSTRUCTION						
	C1010	PARTITIONS						
		GWB furred wall at existing exterior wall	1,050	sf	12.00	12,600		
		Corridors; GWB with 2 lyrs corridor side	4,860	sf	15.55	75,573		
		General Walls; GWB with 1 lyrs each side	3,390	sf	13.75	46,613		
		Sealants & caulking at partitions	4,860	sf	0.50	2,430		
		Rough blocking to partitions	374	lf	3.00	1,122		
		Glazed partitions/borrowed lights - allowance	3/4	ls	1,500.00	1,500		
		SUBTOTAL	•	13	1,000.00	1,000	139,838	
	C1020	INTERIOR DOORS						
		Corridor glazed doors	1	pr	8,000.00	8,000		
		Single door with sidelight	20	ea	2,900.00	58,000		
		SUBTOTAL					66,000	
	C1030	SPECIALTIES / MILLWORK						
		Marker boards/tackboards in conference room	128	sf	24.00	3,072		
		Toilet partitions and accessories	2	rooms	2,000.00	4,000		
		Room Signs	20	loc	110.00	2,200		
		Miscellaneous metals throughout building	4,900	sf	1.25	6,125		
		Miscellaneous sealants throughout building	4,900	sf	1.00	4,900		
		SUBTOTAL					20,297	
		TOTAL - INTERIOR CONSTRUCTION						\$226
Ī	C20	STAIRCASES						
_	C2010	STAIR CONSTRUCTION	_					
		No Work in this section						
		SUBTOTAL					-	
	C2020	STAIR FINISHES						
		No Work in this section						
		SUBTOTAL					-	
		TOTAL - STAIRCASES						
_			_					
[Сзо	INTERIOR FINISHES						

C3010 WALL FINISHES

Paint to GWB

Ceramic Tile to toilets

197 198

199

200

17,550

504

 \mathbf{sf}

sf

1.00

24.00

17,550

12,096



202 203

204

205

206

207

208

209

210 211

212

213

214

215 216 217

218 219

220

221

222 223

224 225 226

227 228

229

230

231 232

233 234 235

236 237

239

241

249 250

257

258

Winchester Schools CAFETERIA + DISTRICT OFFICE EXPANSION Winchester, MA

14-Feb-17

CSI				UNIT	EST'D	SUB	TOTAL
CODE	DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST

Feasibility Design Estimate GFA 4 900 DISTRICT OFFICE ADDITION TO LYNCH OPTION WPS-1 SUBTOTAL 29,646 C3020 FLOOR FINISHES 5.00 13,375 Carpet floor finishes 2,675 sf Resilient floor sf 6.50 12,435 1,913 Ceramic Tile to toilets 25.00 3,000 120 sf Rubber base lf 2.75 3,627 1,319 SUBTOTAL 32,437 C3030 CEILING FINISHES Allowance for ceiling finishes; 2 x 2 ACT 4,708 5.00 23,540 sf SUBTOTAL 23,540 **TOTAL - INTERIOR FINISHES** \$85,623 D10 CONVEYING SYSTEMS ELEVATOR D1010 No Work in this section SUBTOTAL TOTAL - CONVEYING SYSTEMS PLUMBING D20 **D20** PLUMBING, GENERALLY fxt 5,000.00 30,000 New fixtures 6 SUBTOTAL 30,000 TOTAL - PLUMBING \$30,000 D30 HVAC **HVAC, GENERALLY D30** 28.00 137,200 HVAC complete system 4,900 gsf SUBTOTAL 137,200

TOTAL - HVAC \$137,200

D	40 FIRE PROTECTION					
D	40 FIRE PROTECTION, GENERALLY Sprinkler system	4,900	gsf	4.00	19,600	
	SUBTOTAL		J			19,600

TOTAL - FIRE PROTECTION \$19,600

D50 ELECTRICAL				
D5010 COMPLETE ELECTRICAL ST	STEM			
Electrical system; complete	4,900	gsf	22.00	107,800

SUBTOTAL 107,800



261 262 263

265

266

267

268 269

270 271 272

273 274

275

276

277

278

279 280

281

282

283 284

285 286 287

288 289

290

291

292 293

294 295 296

297 298

299

300

301 302

303

304

305 306

Winchester Schools CAFETERIA + DISTRICT OFFICE EXPANSION Winchester, MA

Feasibility Design Estimate GFA 4 900

CSI				UNIT	EST'D	SUB	TOTAL
CODE	DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST

DISTRICT OFFICE ADDITION TO LYNCH OPTION WPS-1

TOTAL - ELECTRICAL \$107,800

EQUIPMENT E10

E10 **EQUIPMENT, GENERALLY**

> AV Equipment (including Smartboards, Projectors, LED monitors, Digital information displays etc.) SUBTOTAL

FF+E

TOTAL - EQUIPMENT

E20 **FURNISHINGS**

E2010 FIXED FURNISHINGS

Entry mats & frames - recessed with carpet/rubber 45.00 2,250 sf 50 strips Manual operated roller shades 6.00 7,392 1,232 sf Miscellaneous casework 3.00 14,700

4,900 gsf

SUBTOTAL 24,342

E2020 MOVABLE FURNISHINGS

All movable furnishings to be provided and installed by owner

SUBTOTAL NIC

TOTAL - FURNISHINGS \$24,342

SPECIAL CONSTRUCTION F10

SPECIAL CONSTRUCTION F10

No Work in this section

SUBTOTAL

TOTAL - SPECIAL CONSTRUCTION

SELECTIVE BUILDING DEMOLITION F20

F2010 BUILDING ELEMENTS DEMOLITION

Create openings to existing façade for new 25,000.00 25,000 loc

connections

SUBTOTAL 25,000

F2020 HAZARDOUS COMPONENTS ABATEMENT

None Included SUBTOTAL

TOTAL - SELECTIVE BUILDING DEMOLITION

\$25,000



Feasibility Design Estimate

Winchester Schools
CAFETERIA + DISTRICT OFFICE EXPANSION
Winchester MA

Winchester, MA

CONSTRUCTION COST SUMMARY BUILDING SYSTEM SUB-TOTAL TOTAL \$/SF DISTRICT OFFICE ADDITION TO NEW LYNCH OPTION WPS-2 A10 **FOUNDATIONS** \$136,069 A1010 Standard Foundations A1020 Special Foundations \$0 A1030 **Lowest Floor Construction** \$65,553 \$201,622 \$41.15 15.7% BASEMENT CONSTRUCTION A20 A2010 **Basement Excavation** \$0 A2020 **Basement Walls** \$0 \$0.00 0.0% **\$0 B10 SUPERSTRUCTURE** B1010 **Upper Floor Construction** \$0 B1020 **Roof Construction** \$135,800 \$135,800 S27.71 10.6% **B20 EXTERIOR CLOSURE** B2010 **Exterior Walls** \$92,308 B2020 \$75,988 Windows B2030 **Exterior Doors** \$37.72 \$16,520 \$184,816 14.4% **ROOFING B30** B3010 \$106.330 **Roof Coverings** B3020 **Roof Openings** \$0 \$106,330 \$21.70 8.3% C10 INTERIOR CONSTRUCTION C1010 **Partitions** \$139,838 C1020 Interior Doors \$66,000 C1030 \$20,297 Specialties/Millwork \$226,135 \$46.15 17.6% **STAIRCASES C20** C2010 Stair Construction \$0 C2020 Stair Finishes \$0 **\$0** \$0.00 0.0% **INTERIOR FINISHES** C30 C3010 Wall Finishes \$29,646 C3020 Floor Finishes \$32,437 C3030 Ceiling Finishes \$23,540 \$85,623 \$17.47 6.7% **CONVEYING SYSTEMS** D10 D1010 Elevator \$0 \$0.00 0.0% **\$0 D20 PLUMBING** D20 \$30,000 \$6.12 2.3% Plumbing \$30,000

14-Feb-17

4,900



Feasibility Design Estimate

Winchester Schools
CAFETERIA + DISTRICT OFFICE EXPANSION
Winchester, MA

Winchester, MA

		CONSTRUCTION	COST SUMM	ARY		
	BUILDING		SUB-TOTAL	TOTAL	\$/SF	%
DISTRIC D30	T OFFIC	E ADDITION TO NEW LYNCH OPTIO	N WPS-2			
<i>D</i> 30	D30	HVAC	\$137,200	\$137,200	\$28.00	10.7%
D40	FIRE P	ROTECTION				
	D40	Fire Protection	\$19,600	\$19,600	\$4.00	1.5%
D50	ELECT	RICAL				
	D5010	Complete System	\$107,800	\$107,800	\$22.00	8.4%
E10	EQUIP	MENT				
	E10	Equipment	\$0	\$0	\$0.00	0.0%
E20	FURNI	SHINGS				
	E2010	Fixed Furnishings	\$22,056			
	E2020	Movable Furnishings	NIC	\$22,056	\$4.50	1.7%
F10	SPECIA	AL CONSTRUCTION				
	F10	Special Construction	\$0	\$0	\$0.00	0.0%
F20		AT REMOVALS				
	F2010	Building Elements Demolition	\$25,000			
	F2020	Hazardous Components Abatement	\$0	\$25,000	\$5.10	2.0%
TOTA	AL DIRE	CT COST (Trade Costs)		\$1,281,982	\$261.63	100.0%

14-Feb-17

4,900



Winchester Schools CAFETERIA + DISTRICT OFFICE EXPANSION Winchester MA

14-Feb-17

Winchester,	MA
-------------	----

3

Feasibility Design Estimate

CSI				UNIT	EST'D	SUB	TOTAL
CODE	DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST

DISTRICT OFFICE ADDITION TO NEW LYNCH OPTION WPS-2

GROSS FLOOR AREA CALCULATION	
	GROSS FLOOR AREA CALCULATION

First Floor 4 900

	First	t Floor			4,900		
	TOTAL GROSS FLOOR AREA (GFA)					4,900 sf	•
A10	FOUNDATIONS						
A1010	STANDARD FOUNDATIONS						
	Strip footings - 2'-0" x 1'-0"						
	Excavation	24	4	cy	20.00	4,880	
	Store on site for reuse	24	4	cy	14.00	3,416	
	Backfill with existing fill	22	27	cy	16.00	3,632	
	Remove surplus fill off site	1	17	cy	25.00	425	
	Formwork	44	0	sf	12.00	5,280	
	Re-bar, 10#/lf	2,20	0	lbs	1.20	2,640	
	Concrete material; 3,000 psi	1	17	cy	125.00	2,125	
	Placing concrete	1	17	cy	55.00	935	
	Foundation walls at exterior - 14" thick						
	Formwork	1,76	0	sf	14.00	24,640	
	Re-bar, 4.5#/sf	3,96	o	lbs	1.20	4,752	
	Concrete material; 4,000 psi	4	0	cy	135.00	5,400	
	Placing concrete	4	0	cy	65.00	2,600	
	Dampproofing foundation wall and footing	1,32	0	sf	1.90	NIC	
	Insulation to foundation walls; 2" thick	88	o	sf	2.50	2,200	
	Form shelf	22	0	lf	8.00	1,760	
	Column footings, typical, 5' x 5' x 2'-0"						
	Excavation	28	5	cy	20.00	5,700	
	Store on site for reuse	28	5	cy	14.00	3,990	
	Backfill with new fill	22	27	cy	16.00	3,632	
	Remove surplus fill off site	5	8	cy	20.00	1,160	
	Formwork	1,20	o	sf	11.00	13,200	
	Re-bar	8,12	0	lbs	1.20	9,744	
	Concrete material; 3,000 psi	5	8	cy	125.00	7,250	
	Placing concrete	5	8	cy	55.00	3,190	
	Set anchor bolts grout plates	3	0	ea	150.00	4,500	
	Interior pilasters						
	Formwork	87	8	sf	11.00	9,658	
	Re-bar	5,40	0	lbs	1.20	6,480	
	Concrete material; 3,000 psi	1	6	cy	125.00	2,000	
	Placing concrete	1	6	cy	55.00	880	
	SUBTOTAL						136,069
A1020	SPECIAL FOUNDATIONS						
	No Work in this section						
	SUBTOTAL						

49

50

A1030 LOWEST FLOOR CONSTRUCTION

New Slab on grade, 5" thick

GFA

4,900



67 68

70

71

72 73

75

76 77

78

80 81

82

83

84

85

88

89

90

91

92

93

95 96

Winchester Schools CAFETERIA + DISTRICT OFFICE EXPANSION Winchester, MA

14-Feb-17

Feasibili	GFA	4,90					
CSI CODE	DESCRIPTION	QTY	UNIT	UNIT COST	EST'D COST	SUB TOTAL	TOTAL COST
CODE	DESCRIT HON	Ų11	CIVII	C031	C031	TOTAL	
DISTRI	ICT OFFICE ADDITION TO NEW LYNCH OPTIC	ON WPS-2					
	Structural gravel fill, 8"	121	cy	30.00	3,630		
	Base course, 8" gravel	121	cy	40.00	4,840		
	Rigid insulation	4,900	sf	2.25	11,025		
	Vapor barrier	4,900	sf	1.00	4,900		
	Mesh reinforcing 15% lap	5,635	sf	0.80	4,508		
	Concrete - 5" thick	80	cy	125.00	10,000		
	Placing concrete	80	cy	45.00	3,600		
	Finishing and curing concrete	4,900	sf	4.00	19,600		
	Control joints - saw cut	4,900	sf	0.50	2,450		
	<u>Miscellaneous</u>						
	Dewatering	1	ea	1,000.00	1,000		
	SUBTOTAL					65,553	
-							
	TOTAL - FOUNDATIONS						\$201,62

A20	BASEMENT CONSTRUCTION

A2010 BASEMENT EXCAVATION

No items in this section

SUBTOTAL

A2020 BASEMENT WALLS

No items in this section

SUBTOTAL

TOTAL - BASEMENT CONSTRUCTION

B10	SUPERSTRUCTURE	

B1010 FLOOR CONSTRUCTION

No Work in this section

SUBTOTAL

B1020 ROOF CONSTRUCTION

Roof Structure - Steel:

Steel beams/Joists; 12#/SF 3,500.00 101,500 tns 29

Roof Structure

4,900 1-1/2" Metal floor Deck @ roof sf 3.00 14,700

Miscellaneous

Roof screen framing - allow NIC

Fire proofing to columns, beams and deck 4,900 4.00 19,600

SUBTOTAL 135,800

12

29

lbs/sf

tns

TOTAL - SUPERSTRUCTURE

\$135,800



Winchester Schools CAFETERIA + DISTRICT OFFICE EXPANSION

Winchester, MA	
----------------	--

Feasibility Design Estimate

UNIT SUB TOTAL CODE DESCRIPTION UNIT COST costTOTAL \mathbf{cost}

B20	EXTERIOR CLOSURE						
B2010	EXTERIOR WALLS; 60% solid/40% glass Interior skin	1,277	sf				
	6" metal stud backup	1,277	sf	7.50	9,578		
	Batt insulation in stud	1,277	sf	2.25	2,873		
	2 1/2" Rigid Insulation	1,277	sf	3.00	3,831		
	Air barrier	1,277	sf	6.00	7,662		
	Air barrier/flashing at windows	281	lf	7.00	1,967		
	Gypsum Sheathing	1,277	sf	2.75	3,512		
	Drywall lining to interior face of stud backup	1,277	sf	3.00	3,831		
	Exterior skin						
	Brick veneer; 75% of exterior wall	958	sf	35.00	33,530		
	Metal panels; 25% of exterior wall	319	sf	60.00	19,140		
	Miscellaneous						
	Staging to exterior wall	2,128	sf	3.00	6,384		
	SUBTOTAL	,				92,308	
B2020	WINDOWS	851	sf				
	Premium for sunscreen and light shelf elements	1	ls		NIC		
	Windows/storefront	851	sf	85.00	72,335		
	Backer rod & double sealant	281	lf	9.00	2,529		
	Wood blocking at openings	281	lf	4.00	1,124		
	SUBTOTAL					75,988	
B2030	EXTERIOR DOORS						
Ū	Glazed entrance doors including frame and hardware; double door at corridor exit	2	pr	8,000.00	16,000		
	Backer rod & double sealant	40	lf	9.00	360		
	Wood blocking at openings	40	lf	4.00	160		
	SUBTOTAL					16,520	
	TOTAL - EXTERIOR CLOSURE						
<i>B</i> 30	ROOFING						
B3010	ROOF COVERINGS Flat roofing						
	PVC roof membrane fully adhered	4,900	sf	9.00	44,100		

B30	KUUFING					
B3010	ROOF COVERINGS Flat roofing					
	PVC roof membrane fully adhered	4,900	sf	9.00	44,100	
	Insulation	4,900	sf	7.00	34,300	
	1/2" dens-deck protection board	4,900	sf	2.00	9,800	
	Reinforced vapor barrier	4,900	sf	1.50	7,350	
	Rough blocking	880	lf	6.00	5,280	
	Miscellaneous Roofing					
	Roof screens - allow				NIC	
	Roof fascia/cornice	220	lf	25.00	5,500	
	SUBTOTAL					106,330

B3020 ROOF OPENINGS

146 147

14-Feb-17

4,900



Winchester Schools CAFETERIA + DISTRICT OFFICE EXPANSION Winchester, MA

Feasibility Design Estimate GFA

CSI				UNIT	EST'D	SUB	TOTAL			
CODE	DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST			
DICTE	DISTRICT OFFICE ADDITION TO NEW LYNCH OPTION WPS-2									

Skylights, allow NIC
Roof hatch NIC
SUBTOTAL

TOTAL - ROOFING \$106,330

C10	INTERIOR CONSTRUCTION						
C1010	PARTITIONS						
	GWB furred wall at existing exterior wall	1,050	sf	12.00	12,600		
	Corridors; GWB with 2 lyrs corridor side	4,860	sf	15.55	75,573		
	General Walls; GWB with 1 lyrs each side	3,390	sf	13.75	46,613		
	Sealants & caulking at partitions	4,860	sf	0.50	2,430		
	Rough blocking to partitions	374	lf	3.00	1,122		
	Glazed partitions/borrowed lights - allowance	1	ls	1,500.00	1,500		
	SUBTOTAL					139,838	
C1020	INTERIOR DOORS						
	Corridor glazed doors	1	pr	8,000.00	8,000		
	Single door with sidelight	20	ea	2,900.00	58,000		
	SUBTOTAL					66,000	
C1030	SPECIALTIES / MILLWORK						
	Marker boards/tackboards in conference room	128	sf	24.00	3,072		
	Toilet partitions and accessories	2	rooms	2,000.00	4,000		
	Room Signs	20	loc	110.00	2,200		
	Miscellaneous metals throughout building	4,900	sf	1.25	6,125		
	Miscellaneous sealants throughout building	4,900	sf	1.00	4,900		
	SUBTOTAL					20,297	

TOTAL - INTERIOR CONSTRUCTION	\$226,135
-------------------------------	-----------

C20	STAIRCASES
-----	------------

C2010 STAIR CONSTRUCTION

No Work in this section

SUBTOTAL

C2020 STAIR FINISHES

No Work in this section

SUBTOTAL -

TOTAL - STAIRCASES

<i>C</i> 30	INTERIOR FINISHES					
C3010	WALL FINISHES					
	Paint to GWB	17,550	sf	1.00	17,550	
	Ceramic Tile to toilets	504	sf	24.00	12,096	
	SUBTOTAL					29,646

14-Feb-17

4,900



Winchester Schools CAFETERIA + DISTRICT OFFICE EXPANSION Winchester, MA

SI SODE		DESCRIPTION	QTY	UNIT	UNIT COST	EST'D COST	SUB TOTAL	TOTAL
DISTI	RICT OF	FICE ADDITION TO NEW LYNCH OPTION V	WPS-2	1	LL	I	L_	
	C3020	FLOOR FINISHES						
	-0	Carpet floor finishes	2,675	sf	5.00	13,375		
		Resilient floor	1,913	sf	6.50	12,435		
		Ceramic Tile to toilets	120	sf	25.00	3,000		
		Rubber base	1,319	lf	2.75	3,627		
		SUBTOTAL					32,437	
	C3030	CEILING FINISHES						
		Allowance for ceiling finishes; 2 x 2 ACT	4,708	sf	5.00	23,540		
		SUBTOTAL					23,540	
		TOTAL - INTERIOR FINISHES						\$85
l								
[D10	CONVEYING SYSTEMS						
	D1010	ELEVATOR						
		No Work in this section						
		SUBTOTAL					-	
		TOTAL - CONVEYING SYSTEMS						
	D20	PLUMBING						
	D20	PLUMBING, GENERALLY						
		New fixtures	6	fxt	5,000.00	30,000		
		SUBTOTAL					30,000	
		TOTAL - PLUMBING						\$30
[D30	HVAC						
L								
	D30	HVAC, GENERALLY	4.000	ara f	28.00	137,200		
		HVAC complete system SUBTOTAL	4,900	gsf	28.00	137,200	137,200	
ı	i						107,200	
		TOTAL - HVAC						\$137
[D40	FIRE PROTECTION						
	D40	FIRE PROTECTION, GENERALLY						
	-	Sprinkler system	4,900	gsf	4.00	19,600		
		SUBTOTAL					19,600	
		TOTAL - FIRE PROTECTION						\$19
ļ	D50	ELECTRICAL						
	D5010	COMPLETE ELECTRICAL SYSTEM						
		Electrical system; complete	4,900	gsf	22.00	107,800		
		SUBTOTAL					107,800	

258

14-Feb-17



263 264

265

267

272 273

274

275

276

277

279

280

281

282 283

285 286

287 288

289

291

293 294 295

296 297

298

299

300 301

302

303

304

305

Feasibility Design Estimate

Winchester Schools CAFETERIA + DISTRICT OFFICE EXPANSION Winchester, MA

Winchester, MA

CSI				UNIT	EST'D	SUB	TOTAL
CODE	DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST

DISTRICT OFFICE ADDITION TO NEW LYNCH OPTION WPS-2

TOTAL - ELECTRICAL	\$107,800

E10 EQUIPMENT

E10 EQUIPMENT, GENERALLY

AV Equipment (including Smartboards, Projectors, LED monitors, Digital information displays etc.)

SUBTOTAL

TOTAL - EQUIPMENT

E20 FURNISHINGS

E2010 FIXED FURNISHINGS

Entry mats & frames - recessed with carpet/rubber **50** sf 45.00 2,250 strips Manual operated roller shades 851 6.00 5,106 sf Miscellaneous casework 3.00 14,700 4,900 gsf

SUBTOTAL

E2020 MOVABLE FURNISHINGS

All movable furnishings to be provided and installed

by owner

SUBTOTAL

TOTAL - FURNISHINGS

\$22,056

FF+E

F10 SPECIAL CONSTRUCTION

F10 SPECIAL CONSTRUCTION

No Work in this section

SUBTOTAL

TOTAL - SPECIAL CONSTRUCTION

F20 SELECTIVE BUILDING DEMOLITION

F2010 BUILDING ELEMENTS DEMOLITION

Create openings to existing façade for new 1 loc 25,000.00 25,000

connections

SUBTOTAL 25,000

F2020 HAZARDOUS COMPONENTS ABATEMENT

None Included

SUBTOTAL

TOTAL - SELECTIVE BUILDING DEMOLITION

\$25,000

14-Feb-17

4 900

GFA

22,056



Feasibility Design Estimate

Winchester Schools CAFETERIA + DISTRICT OFFICE EXPANSION

Winchester, MA

CONSTRUCTION COST SUMMARY BUILDING SYSTEM SUB-TOTAL TOTAL \$/SF DISTRICT OFFICE RENOVATION TO MYSTIC ES OPTION WPS-5 A10 **FOUNDATIONS** \$0 A1010 Standard Foundations A1020 Special Foundations \$0 A1030 **Lowest Floor Construction** \$19,600 2.7% \$19,600 \$4.00 **BASEMENT CONSTRUCTION** A20 A2010 **Basement Excavation** \$0 A2020 **Basement Walls** \$0 \$0.00 0.0% **\$0 B10 SUPERSTRUCTURE** B1010 **Upper Floor Construction** \$0 B1020 **Roof Construction** \$0 **\$0** \$0.00 0.0% **B20 EXTERIOR CLOSURE** B2010 **Exterior Walls** \$53,760 B2020 Windows \$0 B2030 **Exterior Doors** \$14.34 9.6% \$16,520 \$70,280 **B30 ROOFING** B3010 \$0 **Roof Coverings** B3020 **Roof Openings** \$0 **\$0** \$0.00 0.0% C10 INTERIOR CONSTRUCTION C1010 **Partitions** \$114,825 C1020 Interior Doors \$66,000 C1030 Specialties/Millwork \$20,297 \$201,122 \$41.05 27.4% **STAIRCASES C20** C2010 Stair Construction \$0 C2020 Stair Finishes \$0 **\$0** \$0.00 0.0% **INTERIOR FINISHES** C30 C3010 Wall Finishes \$27,696 C3020 Floor Finishes \$32,437 C3030 Ceiling Finishes \$23,540 \$83,673 \$17.08 11.4% D10 **CONVEYING SYSTEMS** D1010 Elevator \$0 \$0.00 0.0% **\$0 D20 PLUMBING** D20 \$30,000 \$30,000 \$6.12 4.1% Plumbing

14-Feb-17

4,900



Feasibility Design Estimate

Winchester Schools
CAFETERIA + DISTRICT OFFICE EXPANSION
Winchester MA

Winchester, MA

	BUILDING	CONSTRUCTION SYSTEM	SUB-TOTAL	TOTAL	\$/SF	%
STRIC		E RENOVATION TO MYSTIC ES OPTI		-	7,7 -	
D30	HVAC					
	D30	HVAC	\$137,200	\$137,200	\$28.00	18.7%
D40	FIRE P	ROTECTION				
	D40	Fire Protection	\$19,600	\$19,600	\$4.00	2.7%
D50	ELECT	RICAL				
	D5010	Complete System	\$107,800	\$107,800	\$22.00	14.7%
E10	EQUIP	MENT				
	E10	Equipment	\$0	\$0	\$0.00	0.0%
E20	FURNI	SHINGS				
	E2010	Fixed Furnishings	\$16,950			
	E2020	Movable Furnishings	NIC	\$16,950	\$3.46	2.3%
F10	SPECIA	AL CONSTRUCTION				
	F10	Special Construction	\$0	\$0	\$0.00	0.0%
F20	HAZMA	AT REMOVALS				
	F2010	Building Elements Demolition	\$49,000			
	F2020	Hazardous Components Abatement	\$0	\$49,000	\$10.00	6.7%
TOTA	II DIDE	CT COST (Trade Costs)		\$735,225	\$150.05	100.0%

14-Feb-17

4,900



Winchester Schools CAFETERIA + DISTRICT OFFICE EXPANSION

Winchester, MA

15

18

21

22 23

29

31

33

35 36

38

41

44

47

48 49 50

52

53

Feasibility Design Estimate	GFA	4,900

CSI				UNIT	EST'D	SUB	TOTAL
CODE	DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST

DISTRICT OFFICE RENOVATION TO MYSTIC ES OPTION WPS-5

GROSS FLOOR AREA CALCULATION

First Floor 4,900

TOTAL GROSS FLOOR AREA (GFA) 4,900 sf

A10 FOUNDATIONS

A1010 STANDARD FOUNDATIONS

SUBTOTAL

A1020 SPECIAL FOUNDATIONS

No Work in this section

SUBTOTAL

A1030 LOWEST FLOOR CONSTRUCTION

Patch existing slab 4.00 19,600 4,900

SUBTOTAL 19,600

TOTAL - FOUNDATIONS \$19,600

BASEMENT CONSTRUCTION A20

A2010 BASEMENT EXCAVATION

No items in this section

SUBTOTAL

A2020 BASEMENT WALLS

No items in this section

SUBTOTAL

TOTAL - BASEMENT CONSTRUCTION

В10 SUPERSTRUCTURE

B1010 FLOOR CONSTRUCTION

No Work in this section

SUBTOTAL

B1020 ROOF CONSTRUCTION

No Work in this section

SUBTOTAL

TOTAL - SUPERSTRUCTURE

B20 **EXTERIOR CLOSURE**

B2010 EXTERIOR WALLS

Interior skin

14-Feb-17



Winchester Schools CAFETERIA + DISTRICT OFFICE EXPANSION Winchester, MA

Feasibility Design Estimate GFA 4,900

CSI CODE	DESCRIPTION	QTY	UNIT	UNIT COST	EST'D COST	SUB TOTAL	TOTAL COST
	OFFICE RENOVATION TO MYSTIC ES OPTION W						
DISTRICT	Insulate inside face of perimeter wall; includes furrin	-	sf	12.00	53,760		
	and GWB	5 1 ,1			55,.55		
	Exterior skin						
	Assumed no work to existing exterior closure						
	SUBTOTAL					53,760	
B20	020 WINDOWS						
	Assumed no work to existing windows						
	SUBTOTAL					-	
B20	ogo EXTERIOR DOORS						
D- (Glazed entrance doors including frame and hardware	e; 2	pr	8,000.00	16,000		
	double door at corridor exit		-				
	Backer rod & double sealant	40	lf	9.00	360		
	Wood blocking at openings	40	lf	4.00	160		
	SUBTOTAL					16,520	
	TOTAL - EXTERIOR CLOSURE						\$70,
B3	o ROOFING						
Roy	010 ROOF COVERINGS	_					
ъ	Assumed no work to existing roof						
	SUBTOTAL					-	
Por	020 ROOF OPENINGS						
Бус	Skylights, allow				NIC		
	Roof hatch				NIC		
	SUBTOTAL					_	
	TOTAL - ROOFING						
	TOTAL - ROOFING						
Cı	O INTERIOR CONSTRUCTION	٦					
Car	010 PARTITIONS	_					
CIO	Corridors; GWB with 2 lyrs corridor side	2,400	sf	15.55	37,320		
	General Walls; GWB with 1 lyrs each side	5,400	sf	13.75	74,250		
	Sealants & caulking at partitions	2,400	sf	0.50	1,200		
	Rough blocking to partitions	185	lf	3.00	555		
	Glazed partitions/borrowed lights - allowance	1	ls	1,500.00	1,500		
	SUBTOTAL	-	-	,	,	114,825	
•							
C10	220 INTERIOR DOORS Corridor glazed doors	1	pr	8,000.00	8,000		
	Single door with sidelight	20	ea	2,900.00	58,000		
	SUBTOTAL	_3		, = = = 1.00	,000	66,000	
	annar (*						
C10	30 SPECIALTIES / MILLWORK		•	64.00	0.070		
C10	Marker boards/tackboards in conference room Toilet partitions and accessories	128	sf	24.00	3,072 4,000		

14-Feb-17



113 114

115

116

117

118 119

120

121 122

129

130

131 132

133

135

136

137

138 139

140

141

142 143

144 145 146

147 148

149

150

151 152

153 154 155

156 157

158

159

Feasibility Design Estimate

Winchester Schools CAFETERIA + DISTRICT OFFICE EXPANSION Winchester, MA

Winchester, MA

CSI CODE	DESCRIPTION	QTY	UNIT	UNIT COST	EST'D COST	SUB TOTAL	TOTAL COST
DISTI	RICT OFFICE RENOVATION TO MYSTIC ES OPTION W	PS-5					
	Room Signs	20	loc	110.00	2,200		
	Miscellaneous metals throughout building	4,900	sf	1.25	6,125		
	Miscellaneous sealants throughout building	4,900	sf	1.00	4,900		
	SUBTOTAL					20,297	
î	TOTAL - INTERIOR CONSTRUCTION						\$201 122

C20 STAIRCASES

C2010 STAIR CONSTRUCTION

No Work in this section

SUBTOTAL

C2020 STAIR FINISHES

No Work in this section

SUBTOTAL

TOTAL - STAIRCASES

Сзо	INTERIOR FINISHES	
C3010	WALL FINISHES	
	Paint to GWB	15,600
	Ceramic Tile to toilets	504
	SUBTOTAL	
	SUBTOTAL	

C3020 FLOOR FINISHES 5.00 13,375 Carpet floor finishes 2,675 sf Resilient floor 12,435 1,913 sf 6.50 Ceramic Tile to toilets 25.00 3,000 sf 120

 Rubber base
 1,319
 lf
 2.75
 3,627

 SUBTOTAL

C3030 CEILING FINISHES

Allowages for coiling finishes: 2 x 2 ACT

Allowance for ceiling finishes; 2 x 2 ACT $$4,\!708$$ sf 5.00 23,540 SUBTOTAL

TOTAL - INTERIOR FINISHES \$83,673

sf

sf

D10 CONVEYING SYSTEMS

D1010 ELEVATOR

No Work in this section

SUBTOTAL

TOTAL - CONVEYING SYSTEMS

D20 PLUMBING

D20 PLUMBING, GENERALLY

New fixtures SUBTOTAL **6** fxt 5,000.00 30,000

1.00

24.00

15,600

12,096

27,696

32,437

23,540

Winchester Schools Cafeteria + District Office Expansions 2.14.17

Page 54

PMC - Project Management Cost

30.000

14-Feb-17

4,900



Feasibility Design Estimate

Winchester Schools CAFETERIA + DISTRICT OFFICE EXPANSION Winchester, MA

Winchester, MA

CSI				UNIT	EST'D	SUB	TOTAL
cor	DE DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST

DISTRICT OFFICE RENOVATION TO MYSTIC ES OPTION WPS-5

	TOTAL - PLUMBING						4
D30	HVAC						
Dag	INVAC CENEDALLY						
D30	HVAC, GENERALLY HVAC complete system	4,900	gsf	28.00	137,200		
	SUBTOTAL	4,900	851	20.00	101,200	137,200	
	TOTAL - HVAC						•
D40	FIRE PROTECTION						
D40							
D40	FIRE PROTECTION, GENERALLY Sprinkler system	4,900	gsf	4.00	19,600		
	SUBTOTAL	4,900	gsi	4.00	13,000	19,600	
						10,000	
	TOTAL - FIRE PROTECTION						
D50	ELECTRICAL						
	COMPLETE ELECTRICAL SYSTEM						
-0	Electrical system; complete	4,900	gsf	22.00	107,800		
	SUBTOTAL	•//	J			107,800	
	TOTAL - ELECTRICAL						
E10	EQUIPMENT						
E10	EQUIPMENT, GENERALLY						
	AV Equipment (including Smartboards, Projectors, LED monitors, Digital information displays etc.)				FF+E		
	SUBTOTAL					-	
	TOTAL - EQUIPMENT						
E20	FURNISHINGS						
E2010	FIXED FURNISHINGS Entry mats & frames - recessed with carpet/rubber strips	50	sf	45.00	2,250		
	Miscellaneous casework	4,900	gsf	3.00	14,700		
	SUBTOTAL		-			16,950	
E2020	MOVABLE FURNISHINGS All movable furnishings to be provided and installed by owner						
	SUBTOTAL					NIC	
	TOTAL - FURNISHINGS						

F10 SPECIAL CONSTRUCTION

214 215 14-Feb-17

4,900



216 217

223 224

225 226

227

228

229 230

231

232

233 234 Feasibility Design Estimate

Winchester Schools
CAFETERIA + DISTRICT OFFICE EXPANSION
Winchester MA

Winchester, MA

CSI				UNIT	EST'D	SUB	TOTAL
CODE	DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST

DISTRICT OFFICE RENOVATION TO MYSTIC ES OPTION WPS-5

217	F10	SPECIAL CONSTRUCTION
218		No Work in this section
219		SUBTOTAL
220		
221		TOTAL - SPECIAL CONSTRUCTION
222		

F20 SELECTIVE BUILDING DEMOLITION

F2010 BUILDING ELEMENTS DEMOLITION

Gut demolition of existing space 4,900 gsf 10.00 49,000

SUBTOTAL 49,000

F2020 HAZARDOUS COMPONENTS ABATEMENT

None Included
SUBTOTAL

TOTAL - SELECTIVE BUILDING DEMOLITION

14-Feb-17

4,900

\$49,000



Feasibility Design Estimate

Winchester Schools CAFETERIA + DISTRICT OFFICE EXPANSION Winchester, MA

WILLIESTET, MA

	BUILDING		ON COST SUMMA SUB-TOTAL	TOTAL	\$/SF	%
TRIC		E RENOVATION AT CARRIAGE H	OUSE OPTION WPS-6	TOTAL	ъ̄/SF	70
		DATIONS				
A10	A1010	Standard Foundations	\$30,000			
	A1010 A1020	Special Foundations	\$30,000			
	A1020	Lowest Floor Construction	\$16,420	¢46 490	\$9.01	3.39
	AIUSU	Lowest Floor Construction	\$10,420	\$46,420	39.01	3.37
A20	BASEM	ENT CONSTRUCTION				
	A2010	Basement Excavation	\$0			
	A2020	Basement Walls	\$0	\$0	\$0.00	0.09
B10	SUPER	STRUCTURE				
	B1010	Upper Floor Construction	\$15,170			
	B1020	Roof Construction	\$10,000	\$25,170	\$4.89	1.89
B20	FYTFD	IOR CLOSURE				
D20	B2010	Exterior Walls	\$133,995			
	B2020	Windows	\$209,728			
	B2030	Exterior Doors	\$16,520	\$360,243	\$69.94	26.09
	D≈000	Exterior Boors	ψ10,5£0	Ψ300,243	Q00.01	20.07
Взо	ROOFI	NG				
	B3010	Roof Coverings	\$77,611			
	B3020	Roof Openings	\$0	\$77,611	\$15.07	5.69
C10	INTERI	OR CONSTRUCTION				
	C1010	Partitions	\$136,067			
	C1020	Interior Doors	\$98,700			
	C1030	Specialties/Millwork	\$21,192	\$255,959	\$49.69	18.49
C20	STAIRO	CASES				
	C2010	Stair Construction	\$60,000			
	C2020	Stair Finishes	\$8,000	\$68,000	\$13.20	4.9%
Сзо	INTERI	OR FINISHES				
٠,٠	C3010	Wall Finishes	\$30,599			
	C3020	Floor Finishes	\$31,771			
	C3030	Ceiling Finishes	\$23,750	\$86,120	\$16.72	6.29
D10	CONVE	YING SYSTEMS				
210	D1010	Elevator	\$90,000	\$90,000	\$17.47	6.5%
	PLUME	PINC				
D20						

14-Feb-17

5,151



Winchester Schools CAFETERIA + DISTRICT OFFICE EXPANSION

Winchester, MA

Feasibility Design Estimate GFA 5,151

		CONSTRUCTION	COST SUMM	ARY		
- TOWN TO	BUILDING		SUB-TOTAL	TOTAL	\$/SF	%
DISTRIC	T OFFIC	E RENOVATION AT CARRIAGE HOUS	SE OPTION WPS-6	•		
D30	HVAC					
	D30	HVAC	\$144,228	\$144,228	\$28.00	10.4%
D40	FIRE P	ROTECTION				
	D40	Fire Protection	\$20,604	\$20,604	\$4.00	1.5%
D50	ELECT	RICAL				
	D5010	Complete System	\$113,322	\$113,322	\$22.00	8.2%
E10	EQUIP	MENT				
	E10	Equipment	\$0	\$0	\$0.00	0.0%
E20	FURNIS	SHINGS				
	E2010	Fixed Furnishings	\$28,713			
	E2020	Movable Furnishings	NIC	\$28,713	\$5.57	2.1%
F10	SPECIA	AL CONSTRUCTION				
	F10	Special Construction	\$0	\$0	\$0.00	0.0%
F20	HAZMA	AT REMOVALS				
	F2010	Building Elements Demolition	\$41,208			
	F2020	Hazardous Components Abatement	\$0	\$41,208	\$8.00	3.0%
TOT	L DIRE	OT OOST (T I. C)		φ	<i>ф</i> 2(2.50)	100.00/
1017	AL DIKE	CT COST (Trade Costs)		<i>\$1,387,598</i>	\$269.38	100.0%

14-Feb-17



10

12

16

18

20 21

22

23

26

28 29

30

33

35

36 37

39 40

42

43

44

45

48

49

50 51 **Feasibility Design Estimate**

Winchester Schools CAFETERIA + DISTRICT OFFICE EXPANSION Winchester, MA

AFETERIA + DISTRICT OFFICE EXPANSION
Windowston, MA

CSI				UNIT	EST'D	SUB	TOTAL
CODE	DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST

DISTRICT OFFICE RENOVATION AT CARRIAGE HOUSE OPTION WPS-6

GROSS FLOOR AREA CALCULATION

 Basement
 350

 First Floor
 3,284

 Second Floor
 1,517

TOTAL GROSS FLOOR AREA (GFA)

5,151 sf

14-Feb-17

5,151

GFA

A10 FOUNDATIONS

A1010 STANDARD FOUNDATIONS

New elevator pit **1** ea 30,000.00 30,000

SUBTOTAL 30,000

A1020 SPECIAL FOUNDATIONS

No Work in this section

SUBTOTAL

A1030 LOWEST FLOOR CONSTRUCTION

Patch/repair existing slab **3,284** sf 5.00 16,420

SUBTOTAL 16,420

TOTAL - FOUNDATIONS \$46,420

A20 BASEMENT CONSTRUCTION

A2010 BASEMENT EXCAVATION

No items in this section

SUBTOTAL -

A2020 BASEMENT WALLS

No items in this section

SUBTOTAL -

TOTAL - BASEMENT CONSTRUCTION

B10 SUPERSTRUCTURE

B1010 FLOOR CONSTRUCTION

Patch/repair existing floor **1,517** sf 10.00 15,170

SUBTOTAL 15,170

B1020 ROOF CONSTRUCTION

Miscellaneous

New override for elevator PH **1** ls 10,000.00 10,000

SUBTOTAL 10,000

TOTAL - SUPERSTRUCTURE \$25,170



Winchester Schools CAFETERIA + DISTRICT OFFICE EXPANSION Winchester, MA

Feasibility Design Estimate	GFA	5,151
-----------------------------	-----	-------

CSI				UNIT	EST'D	SUB	TOTAL
CODE	DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST

DISTRICT OFFICE RENOVATION AT CARRIAGE HOUSE OPTION WPS-6

D	EXTERNOR MALL C == 0/ 1/1/0/ 1	0 -	c				
B2010	EXTERIOR WALLS; 70% solid/30% glass Interior skin: insulate perimeter	4,283	sf				
	Stud furring	4,283	sf	6.00	25,698		
	2 1/2" Rigid Insulation	4,283	sf	3.00	12,849		
	Drywall lining to interior face of stud backup	4,283	sf	3.00	12,849		
	Exterior skin						
	Repair and paint existing siding	4,283	sf	15.00	64,245		
	Miscellaneous						
	Staging to exterior wall	6,118	sf	3.00	18,354		
	SUBTOTAL					133,995	
B2020	WINDOWS	1,835	sf				
	Replace existing windows	1,835	sf	110.00	201,850		
	Backer rod & double sealant	606	lf	9.00	5,454		
	Wood blocking at openings	606	lf	4.00	2,424		
	SUBTOTAL					209,728	
B2030	EXTERIOR DOORS						
	Glazed entrance doors including frame and hardware; double door	2	pr	8,000.00	16,000		
	Backer rod & double sealant	40	lf	9.00	360		
	Wood blocking at openings	40	lf	4.00	160		
	SUBTOTAL					16,520	

TOTAL - EXTERIOR CLOSURE	\$360,243

Взо	ROOFING]				
B3010	ROOF COVERINGS Flat roofing					
	PVC roof membrane fully adhered	3,284	sf	9.00	29,556	
	Insulation	3,284	sf	7.00	22,988	
	1/2" dens-deck protection board	3,284	sf	2.00	6,568	
	Reinforced vapor barrier	3,284	sf	1.50	4,926	
	Rough blocking	1,108	lf	6.00	6,648	
	Miscellaneous Roofing					
	Roof screens - allow				NIC	
	Roof fascia/cornice	277	lf	25.00	6,925	
	SUBTOTAL					77,611
B3020	ROOF OPENINGS					
	Skylights, allow				NIC	
	Roof hatch				NIC	
	SUBTOTAL					-

TOTAL - ROOFING

\$77,611

14-Feb-17



102

Feasibility Design Estimate

Winchester Schools CAFETERIA + DISTRICT OFFICE EXPANSION Winchester, MA

Winchester, MA

CSI				UNIT	EST'D	SUB	TOTAL
CODE	DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST

DISTRICT OFFICE RENOVATION AT CARRIAGE HOUSE OPTION WPS-6

C10	INTERIOR CONSTRUCTION						
C1010	PARTITIONS						
	Corridors; GWB with 2 lyrs corridor side	4,560	sf	15.55	70,908		
	General Walls; GWB with 1 lyrs each side	2,550	sf	13.75	35,063		
	CMU elevator walls	780	sf	30.00	23,400		
	Sealants & caulking at partitions	7,110	sf	0.50	3,555		
	Rough blocking to partitions	547	lf	3.00	1,641		
	Glazed partitions/borrowed lights - allowance	1	ls	1,500.00	1,500		
	SUBTOTAL					136,067	
C1020	INTERIOR DOORS						
	Corridor glazed doors	4	pr	8,000.00	32,000		
	Single door with sidelight	23	ea	2,900.00	66,700		
	SUBTOTAL					98,700	
C1030	SPECIALTIES / MILLWORK						
	Marker boards/tackboards in conference room	128	sf	24.00	3,072		
	Toilet partitions and accessories	2	rooms	2,000.00	4,000		
	Room Signs	23	loc	110.00	2,530		
	Miscellaneous metals throughout building	5,151	sf	1.25	6,439		
	Miscellaneous sealants throughout building	5,151	sf	1.00	5,151		
	SUBTOTAL					21,192	
	TOTAL - INTERIOR CONSTRUCTION						\$
C20	STAIRCASES						
Caasa	CTAID CONCEDITORION						
C2010	STAIR CONSTRUCTION New staircase; complete	2	flt	30,000.00	60,000		
	SUBTOTAL	_	110	30,000.00	00,000	60,000	
	SOBIOTAL					00,000	
C2020	STAIR FINISHES		a.	4.000.00	0.000		
	New staircase finishes	2	flt	4,000.00	8,000	0.000	
	SUBTOTAL					8,000	
	TOTAL - STAIRCASES						\$
Сзо	INTERIOR FINISHES						
C3010	WALL FINISHES						
	Paint to GWB	18,503	sf	1.00	18,503		
	Ceramic Tile to toilets	504	sf	24.00	12,096		
	SUBTOTAL					30,599	
_	FLOOR FINISHES						
C3020				7 00	17 000		
C3020	Carpet floor finishes	3,440	sf	5.00	17,200		
C3020	Carpet floor finishes Resilient floor	3,440 1,178	sf sf	5.00 6.50	7,657		

14-Feb-17

5,151



Winchester Schools CAFETERIA + DISTRICT OFFICE EXPANSION Winchester, MA

Feasibility Design Estimate GFA 5,151

CODE	DESCRIPTION	QTY	UNIT	UNIT COST	EST'D COST	SUB TOTAL	TOTAL COST
DISTRICT	OFFICE RENOVATION AT CARRIAGE HOUSE	OPTION WPS-6	<u> </u>	I.	l		
	Rubber base	1,314	lf	2.75	3,614		
	SUBTOTAL	<i>,</i> .			ŕ	31,771	
						,,,,	
C3	O30 CEILING FINISHES		- C	r 00	99.750		
	Allowance for ceiling finishes; 2 x 2 ACT SUBTOTAL	4,750	sf	5.00	23,750	23,750	
	SUBTUTAL					23,730	
	TOTAL - INTERIOR FINISHES						\$86,
D	10 CONVEYING SYSTEMS						
D1	010 ELEVATOR						
	New two stop elevator	1	ls	90,000.00	90,000		
	SUBTOTAL					90,000	
	TOTAL - CONVEYING SYSTEMS						\$90,0
<u> </u>							
D	20 PLUMBING						
D	20 PLUMBING, GENERALLY						
	New fixtures	6	fxt	5,000.00	30,000		
	SUBTOTAL					30,000	
	TOTAL - PLUMBING						\$30,0
D	30 HVAC						
D	HVAC, GENERALLY HVAC complete system	E 151	gsf	28.00	144,228		
	SUBTOTAL	5,151	gsi	28.00	144,220	144,228	
						111,220	
	TOTAL - HVAC						\$144,
D.	40 FIRE PROTECTION						
D	40 FIRE PROTECTION, GENERALLY						
L	Sprinkler system	5,151	gsf	4.00	20,604		
	SUBTOTAL					20,604	
	TOTAL - FIRE PROTECTION						\$20,0
<u> </u>							
D_{i}	50 ELECTRICAL						
D5	010 COMPLETE ELECTRICAL SYSTEM						
	Electrical system; complete	5,151	gsf	22.00	113,322		
	SUBTOTAL					113,322	
	TOTAL - ELECTRICAL						\$113,
	TOTAL ELECTRICAL						φ113,
177	10 FOURDMENT						
E	to EQUIPMENT						

E10 EQUIPMENT, GENERALLY

212 213 14-Feb-17



Feasibility Design Estimate

E20

F10

F20

Winchester Schools CAFETERIA + DISTRICT OFFICE EXPANSION

Winchester, MA

CSI				UNIT	EST'D	SUB	TOTAL
CODE	DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST

DISTRICT OFFICE RENOVATION AT CARRIAGE HOUSE OPTION WPS-6

AV Equipment (including Smartboards, Projectors, LED monitors, Digital information displays etc.) SUBTOTAL

FF+E

215 216 217

214

218

223

224 225

230 231 232

233

238

252

253 254

247

F2020 HAZARDOUS COMPONENTS ABATEMENT None Included

SUBTOTAL

TOTAL - EQUIPMENT

FURNISHINGS FIXED FURNISHINGS E2010

Entry mats & frames - recessed with carpet/rubber

Manual operated roller shades Miscellaneous casework SUBTOTAL

1,835

5,151 gsf

50

sf

sf

3.00

45.00

6.00

15,453

2,250

11,010

28,713

NIC

E2020 MOVABLE FURNISHINGS

All movable furnishings to be provided and installed by owner

SUBTOTAL

TOTAL - FURNISHINGS

SPECIAL CONSTRUCTION F10 No Work in this section

SPECIAL CONSTRUCTION

SUBTOTAL

TOTAL - SPECIAL CONSTRUCTION

F2010 BUILDING ELEMENTS DEMOLITION Gut demolition

SELECTIVE BUILDING DEMOLITION

SUBTOTAL

5,151

gsf

8.00

41,208

41,208


TOTAL - SELECTIVE BUILDING DEMOLITION

\$41,208

\$28,713

14-Feb-17

5,151



Feasibility Design Estimate

Winchester Schools NEW MURACO + LYNCH COMBINED

Winchester, MA

PM&C LLC

20 Downer Avenue, Suite 1c Hingham, MA 02043

(T) 781-740-8007

(F) 781-740-1012

Prepared for:

Flansburgh Architects

March 1, 2017



01-Mar-17

Feasibility Design Estimate

MAIN CONSTRUCTION COST SUMMARY

	Construction Start	Gross Floor Area	\$/sf	Estimated Construction Cost
OPTION ES-5C - NEW LYNCH ELE	MENTARY S	SCHOOL		
DEMOLISH EXISTING SCHOOL		79,745	\$8.00	\$637,960
HAZMAT REMOVALS		79,745	\$15.00	\$1,196,175
NEW SCHOOL		85,455	\$242.66	\$20,736,632
SITEWORK				\$2,828,458
SUB-TOTAL	Mar-18	85,455	\$297.22	\$25,399,225
ESCALATION TO START - (assumed 3% PA)	6.0%			\$1,523,954
DESIGN AND PRICING CONTINGENCY	12%			\$3,047,907
SUB-TOTAL		85,455	\$350.72	\$29,971,086
GENERAL CONDITIONS				\$2,397,687
BONDS	1.00%			\$299,711
INSURANCE	2.00%			\$599,422
PERMIT				NIC
OVERHEAD AND FEE	3.00%			\$899,133
OWNER CONTINGENCY				By Owner
TOTAL OF ALL CONSTRUCTION	Mar-18	85,455	\$399.82	\$34,167,039



01-Mar-17

Feasibility Design Estimate

MAIN CONSTRUCTION COST SUMMARY

	Construction Start	Gross Floor Area	\$/sf	Estimated Construction Cost
OPTION ES-5C - NEW MURACO I	ELEMENTAR	Y SCHOOL		
DEMOLISH EXISTING SCHOOL		55,415	\$8.00	\$443,320
HAZMAT REMOVALS		55,415	\$15.00	\$831,225
NEW SCHOOL		74,215	\$258.09	\$19,154,294
SITEWORK - (Allowance of 12% of Building)				\$2,298,515
SUB-TOTAL	Mar-20	74,215	\$289.06	\$21,452,809
ESCALATION TO START - (assumed 4% PA)	12.0%			\$2,574,337
DESIGN AND PRICING CONTINGENCY	12%			\$2,574,337
SUB-TOTAL		74,215	\$358.44	\$26,601,483
GENERAL CONDITIONS				\$2,128,119
BONDS	1.00%			\$266,015
INSURANCE	2.00%			\$532,030
PERMIT				NIC
OVERHEAD AND FEE	3.00%			\$798,044
OWNER CONTINGENCY				By Owner
TOTAL OF ALL CONSTRUCTION	Mar-20	74,215	\$408.62	\$30,325,691



01-Mar-17

Feasibility Design Estimate

This Feasibility Design cost estimate was produced from preliminary drawings prepared by Flansburgh Architects Inc. and their design team dated February 28, 2017. Design and engineering changes occurring subsequent to the issue of these documents have not been incorporated in this estimate.

This estimate includes all direct construction costs, general contractor's overhead, fee and design contingency. Cost escalation assumes start dates indicated.

Bidding conditions are expected to be public bidding under Chapter 149 of the Massachusetts General Laws to pre-qualified general contractors, and pre-qualified sub-contractors, open specifications for materials and manufactures.

The estimate is based on prevailing wage rates for construction in this market and represents a reasonable opinion of cost. It is not a prediction of the successful bid from a contractor as bids will vary due to fluctuating market conditions, errors and omissions, proprietary specifications, lack or surplus of bidders, perception of risk, etc. Consequently the estimate is expected to fall within the range of bids from a number of competitive contractors or subcontractors, however we do not warrant that bids or negotiated prices will not vary from the final construction cost estimate.

ITEMS NOT CONSIDERED IN THIS ESTIMATE

Items not included in this estimate are:

Land acquisition, feasibility, and financing costs All professional fees and insurance Site or existing conditions surveys investigations costs, including to determine

subsoil conditions
All Furnishings, Fixtures and Equipment
Items identified in the design as Not In Contract (NIC)

Items identified in the design as by others

Owner supplied and/or installed items as indicated in the estimate

Utility company back charges, including work required off-site

Work to City streets and sidewalks, (except as noted in this estimate)

Construction contingency



Winchester Schools NEW MURACO + LYNCH COMBINED

Winchester, MA

Feasibility Design Estimate GFA 74,215

	BUILDING		ON COST SUMM. SUB-TOTAL	AKY TOTAL	\$/SF	%
WSC		Γ MURACO ES 5C	SUB-101AL	IOIAL	⊅/SF	70
A10		DATIONS				
1110	A1010	Standard Foundations	\$614,098			
	A1020	Special Foundations	\$0			
	A1030	Lowest Floor Construction	\$696,377	\$1,310,475	\$17.66	6.89
A20	BASEM	ENT CONSTRUCTION				
	A2010	Basement Excavation	\$0			
	A2020	Basement Walls	\$0	\$0	\$0.00	0.09
B10	SUPER	STRUCTURE				
	B1010	Upper Floor Construction	\$1,050,175			
	B1020	Roof Construction	\$1,492,407	\$2,542,582	\$34.26	13.39
B20	EXTER	IOR CLOSURE				
	B2010	Exterior Walls	\$1,527,916			
	B2020	Windows	\$1,276,504			
	B2030	Exterior Doors	\$43,040	\$2,847,460	\$38.37	14.9%
Взо	ROOFI	NG				
	B3010	Roof Coverings	\$1,237,289			
	B3020	Roof Openings	\$5,000	\$1,242,289	\$16.74	6.5%
C10	INTERI	OR CONSTRUCTION				
	C1010	Partitions	\$1,484,300			
	C1020	Interior Doors	\$371,075			
	C1030	Specialties/Millwork	\$512,084	\$2,367,459	\$31.90	12.49
C20	STAIR	CASES				
	C2010	Stair Construction	\$78,000			
	C2020	Stair Finishes	\$20,550	\$98,550	\$1.33	0.5%
C30	INTERI	OR FINISHES				
	C3010	Wall Finishes	\$333,968			
	C3020	Floor Finishes	\$519,505			
	C3030	Ceiling Finishes	\$445,290	\$1,298,763	\$17.50	6.89
D10		YING SYSTEMS				
	D1010	Elevator	\$100,000	\$100,000	\$1.35	0.5%
D20	PLUME	BING				
	D20	Plumbing	\$890,580	\$890,580	\$12.00	4.69



Feasibility Design Estimate GFA 74,215

		CONSTRUCTION				
X 4 7 0 0 1	BUILDING		SUB-TOTAL	TOTAL	\$/SF	%
EW SCI	HOOL A	Γ MURACO ES 5C				
D30	HVAC					
	D30	HVAC	\$2,820,170	\$2,820,170	\$38.00	14.7%
D40	FIRE P	ROTECTION				
	D40	Fire Protection	\$333,968	\$333,968	\$4.50	1.7%
D50	ELECTI	RICAL				
	D5010	Complete System	\$2,523,310	\$2,523,310	\$34.00	13.2%
E10	EQUIP	MENT				
	E10	Equipment	\$396,100	\$396,100	\$5.34	2.1%
E20	FURNIS	SHINGS				
	E2010	Fixed Furnishings	\$382,588			
	E2020	Movable Furnishings	NIC	\$382,588	\$5.16	2.0%
F10	SPECIA	L CONSTRUCTION				
	F10	Special Construction	\$0	\$0	\$0.00	0.0%
F20	HAZMA	AT REMOVALS				
	F2010	Building Elements Demolition	\$0			
	F2020	Hazardous Components Abatement	\$0	\$0	\$0.00	0.0%
	- n-n-	CT COST (Trade Costs)		\$19,154,294	\$258.09	100.0%



Winchester Schools NEW MURACO + LYNCH COMBINED

Winchester, MA

Feasibility Design Estimate GFA 74,215

CSI				UNIT	EST'D	SUB	TOTAL
CODE	DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST
NEW	SCHOOL AT MURACO ES 5C						
i		-					
	GROSS FLOOR AREA CALCULATION						

First Floor 46,401 Second Floor 27,814

A10	FOUNDATIONS					
A1010	STANDARD FOUNDATIONS Strip footings - 2'-0" x 1'-0"					
	Excavation	1,329	cy	20.00	26,580	
	Store on site for reuse	1,329	cy	14.00	18,606	
	Backfill with existing fill	1,236	cy	16.00	19,776	
	Remove surplus fill off site	93	cy	25.00	2,325	
	Formwork	2,392	sf	12.00	28,704	
	Re-bar, 10#/lf	11,960	lbs	1.20	14,352	
	Concrete material; 3,000 psi	93	cy	125.00	11,625	
	Placing concrete	93	cy	55.00	5,115	
	Foundation walls at exterior - 14" thick					
	Formwork	9,568	sf	14.00	133,952	
	Re-bar, 4.5#/sf	21,528	lbs	1.20	25,834	
	Concrete material; 4,000 psi	218	cy	135.00	29,430	
	Placing concrete	218	cy	65.00	14,170	
	Dampproofing foundation wall and footing	7,176	sf	1.90	NIC	
	Insulation to foundation walls; 2" thick	4,784	sf	2.50	11,960	
	Form shelf	1,196	lf	8.00	9,568	
	Column footings, typical, 6' x 6' x 2'-0"					
	Excavation	998	cy	20.00	19,960	
	Store on site for reuse	998	cy	14.00	13,972	
	Backfill with new fill	760	cy	16.00	12,160	
	Remove surplus fill off site	238	cy	20.00	4,760	
	Formwork	4,080	sf	11.00	44,880	
	Re-bar	47,600	lbs	1.20	57,120	
	Concrete material; 3,000 psi	238	cy	125.00	29,750	
	Placing concrete	238	cy	55.00	13,090	
	Set anchor bolts grout plates	85	ea	150.00	12,750	
	Interior pilasters					
	Formwork	2,489	sf	11.00	27,379	
	Re-bar	15,300	lbs	1.20	18,360	
	Concrete material; 3,000 psi	44	cy	125.00	5,500	
	Placing concrete	44	cy	55.00	2,420	
	SUBTOTAL					614,098
A1020	SPECIAL FOUNDATIONS					011,000
	No Work in this section					

No Work in this section

SUBTOTAL

A1030 LOWEST FLOOR CONSTRUCTION

New Slab on grade, 5" thick



Winchester Schools NEW MURACO + LYNCH COMBINED

Winchester, MA

Feasibility Design Estimate GFA 74,215

CODE CODE	DESCRIPTION	QTY	UNIT	UNIT COST	EST'D COST	SUB TOTAL	TOTAL COST
NEW SCI	HOOL AT MURACO ES 5C						
	Structural gravel fill, 8"	1,146	cy	30.00	34,380		
	Base course, 8" gravel	1,146	cy	40.00	45,840		
	Rigid insulation	46,401	sf	2.25	104,402		
	Vapor barrier	46,401	sf	1.00	46,401		
	Mesh reinforcing 15% lap	53,361	sf	0.80	42,689		
	Concrete - 5" thick	758	cy	125.00	94,750		
	Placing concrete	758	cy	45.00	34,110		
	Finishing and curing concrete	46,401	sf	4.00	185,604		
	Control joints - saw cut	46,401	sf	0.50	23,201		
	<u>Miscellaneous</u>						
	Backfill existing foundations/basement	1	ea	50,000.00	50,000		
	Elevator pit	1	ea	30,000.00	30,000		
	Dewatering	1	ea	5,000.00	5,000		
	SUBTOTAL					696,377	

TOTAL - FOUNDATIONS \$1,310,475

A20 BASEMENT CONSTRUCTION

A2010 BASEMENT EXCAVATION

No items in this section

SUBTOTAL -

A2020 BASEMENT WALLS

No items in this section

SUBTOTAL

TOTAL - BASEMENT CONSTRUCTION

		7				
B10	SUPERSTRUCTURE					
		13	lbs/sf			
B1010	FLOOR CONSTRUCTION	483	tns			
	<u>Floor Structure - Steel:</u>					
	Steel beams and columns; 13/SF	181	tns	3,500.00	633,500	
	Shear studs	5,563	ea	2.50	13,908	
	Floor Structure					
	2" Metal floor Deck	27,814	sf	4.20	116,819	
	WWF reinforcement	31,986	sf	0.80	25,589	
	Concrete Fill to metal deck; 5" normal weight	443	cy	125.00	55,375	
	Place and finish concrete	27,814	sf	2.00	55,628	
	Misc. perimeter angles	1,196	lf	25.00	29,900	
	<u>Miscellaneous</u>					
	Barrier one at slab	443	cy	65.00	28,795	
	Fire proofing to columns and beams	27,814	sf	2.90	80,661	
	Fire stopping floors	2	flrs	5,000.00	10,000	
	SUBTOTAL					1,050,175



Feasibility Design Estimate GFA 74,215

CSI CODE	DESCRIPTION	QTY	UNIT	UNIT COST	EST'D COST	SUB TOTAL	TOTAL COST
NEW SCHOO	OL AT MURACO ES 5C						
B1020	O ROOF CONSTRUCTION						
	Roof Structure - Steel:						
	Steel beams/Joists; 13#/SF	302	tns	3,800.00	1,147,600		
	Roof Structure						
	1-1/2" Metal floor Deck @ roof	46,401	sf	3.00	139,203		
	<u>Miscellaneous</u>						
	Roof screen framing - allow	1	ls	20,000.00	20,000		
	Fire proofing to columns, beams and deck	46,401	sf	4.00	185,604		
	SUBTOTAL					1,492,407	
	TOTAL - SUPERSTRUCTURE						\$2,542,5
B20	EXTERIOR CLOSURE						
B2010	D EXTERIOR WALLS; 60% solid/40% glass	20,306	sf				
	Interior skin	_	•	~ ~ 0			
	6" metal stud backup	20,306	sf	7.50	152,295		
	Batt insulation in stud	20,306	sf	2.25	45,689		
	2 1/2" Rigid Insulation	20,306	sf	3.00	60,918		
	Air barrier	20,306	sf	6.00	121,836		
	Air barrier/flashing at windows	4,468	lf	7.00	31,276		
	Gypsum Sheathing	20,306	sf	2.75	55,842		
	Drywall lining to interior face of stud backup	20,306	sf	3.00	60,918		
	Exterior skin						
	Brick veneer; 75% of exterior wall	15,230	sf	35.00	533,050		
	Metal panels; 25% of exterior wall	5,076	sf	60.00	304,560		
	Miscellaneous						
	Roof screens - allow	1	ls	60,000.00	60,000		
	Staging to exterior wall	33,844	sf	3.00	101,532		
	SUBTOTAL					1,527,916	
B202	o WINDOWS	13,538	sf				
	Premium for sunscreen and light shelf elements	1	ls		NIC		
	Windows/storefront	13,538	sf	90.00	1,218,420		
	Backer rod & double sealant	4,468	lf	9.00	40,212		
	Wood blocking at openings	4,468	lf	4.00	17,872		
	SUBTOTAL					1,276,504	
Rana	D EXTERIOR DOORS						
D2U30	Glazed entrance doors including frame and hardware;	4	pr	8,000.00	32,000		
	double door at corridor exit	7	r	-,-,-	,		
	Other doors	1	ls	10,000.00	10,000		
	Backer rod & double sealant	80	lf	9.00	720		
	Wood blocking at openings	80	lf	4.00	320		
	SUBTOTAL					43,040	
	TOTAL - EXTERIOR CLOSURE						\$2,847,4

148



Feasibility Design Estimate

EW MUKACO + LYNCH COMBINED (inchester: MA

CSI CODE	0011001	DESCRIPTION	QTY	UNIT	UNIT COST	EST'D COST	SUB TOTAL	TOTAL COST
NEW :		LAT MURACO ES 5C	_					
<u>_</u>	В30	ROOFING						
	B3010	ROOF COVERINGS Flat roofing						
		PVC roof membrane fully adhered	46,401	sf	14.00	649,614		
		Insulation	46,401	sf	7.00	324,807		
		1/2" dens-deck protection board	46,401	sf	2.00	92,802		
		Reinforced vapor barrier	46,401	sf	1.50	69,602		
		Rough blocking	4,784	lf	6.00	28,704		
		Miscellaneous Roofing	•//					
		Roof screens - allow				NIC		
		Roof fascia/cornice	1,196	lf	60.00	71,760		
		SUBTOTAL	, -				1,237,289	
	Pagga	ROOF OPENINGS						
	B3020	Skylights, allow				NIC		
		Roof hatch	1	ea	5,000.00	5,000		
		SUBTOTAL	-	04	0,000.00	0,000	5,000	
		SOBTOTILE					0,000	
		TOTAL - ROOFING						\$1,242,28
-			_					
	C10	INTERIOR CONSTRUCTION						
	C1010	PARTITIONS						
		Allowance for interior walls/glazed partitions etc.	74,215	gfa	20.00	1,484,300		
		SUBTOTAL					1,484,300	
	C1020	INTERIOR DOORS						
		Interior doors, frames and hardware	74,215	gfa	5.00	371,075		
		SUBTOTAL					371,075	
	C1030	SPECIALTIES / MILLWORK						
		Marker boards/tackboards in classroom	74,215	gfa	1.15	85,347		
		Toilet partitions and accessories	74,215	gfa	0.75	55,661		
		Room Signs	74,215	gfa	0.25	18,554		
		Wood paneling/benches/display cases etc.	74,215	gfa	1.50	111,323		
		Lockers	74,215	sf	1.00	74,215		
		Miscellaneous metals throughout building	74,215	sf	1.25	92,769		
		Miscellaneous sealants throughout building	74,215	sf	1.00	74,215		
		SUBTOTAL					512,084	
		TOTAL - INTERIOR CONSTRUCTION						\$2,367,45
L								
	C20	STAIRCASES						
	C2010	STAIR CONSTRUCTION						
55100		Metal pan stair; egress stair	3	flt	24,000.00	72,000		
33000		Concrete fill to stairs	3	flt	2,000.00	6,000		
		SUBTOTAL	3				78,000	
	Coccc	CTAID DINIGHES						
	C2020	STAIR FINISHES						

01-Mar-17

74,215



Feasib	ility Desig	n Estimate					GFA	74,21
CSI CODE		DESCRIPTION	QTY	UNIT	UNIT COST	EST'D COST	SUB TOTAL	TOTAL COST
	SCHOOL	L AT MURACO ES 5C				•		
90009		High performance coating to stairs including all railings etc.	3	flt	3,000.00	9,000		
90006		Rubber tile at stairs - landings	330	sf	12.00	3,960		
90006		Rubber tile at stairs - treads & risers	345	lft	22.00	7,590		
		SUBTOTAL					20,550	
		TOTAL - STAIRCASES						\$98,550
	Сзо	INTERIOR FINISHES						
	C3010	WALL FINISHES Wall finishes SUBTOTAL	74,215	gfa	4.50	333,968	333,968	
	C3020	FLOOR FINISHES					000,000	
	-0	Floor finishes	74,215	sf	7.00	519,505		
		SUBTOTAL					519,505	
	С3030	CEILING FINISHES Ceiling finishes	5 4 915	sf	6.00	445,290		
		SUBTOTAL	74,215	51	0.00	443,230	445,290	
		TOTAL - INTERIOR FINISHES						\$1,298,76
	D10	CONVEYING SYSTEMS						
3000	D1010	ELEVATOR Passenger elevator; 2 stop, 3500 lbs	1	ea	100,000.00	100,000		
		SUBTOTAL					100,000	
		TOTAL - CONVEYING SYSTEMS						\$100,000
	D20	PLUMBING						
	D20	PLUMBING, GENERALLY	E4 045	act	12.00	890,580		
		Plumbing allowance SUBTOTAL	74,215	gsf	12.00	890,380	890,580	
		TOTAL - PLUMBING						\$890,580
	D30	HVAC						
			_					
	D30	HVAC, GENERALLY HVAC complete system	74,215	gsf	38.00	2,820,170		
		SUBTOTAL	/4,213	gsi	36.00	2,020,170	2,820,170	
		TOTAL - HVAC					2,020,110	\$2,820,17
		TOTAL MATE						Ψ=,020,1/
	D40	FIRE PROTECTION						
	D40	FIRE PROTECTION, GENERALLY Sprinkler system	74,215	gsf	4.50	333,968		
		CIDTOTAI	, 1, 0	0-		-,	222.060	

SUBTOTAL

333,968



Feasibility Design Estimate GFA 74,215

CODE	COLLOOI	DESCRIPTION	QTY	UNIT	UNIT COST	EST'D COST	SUB TOTAL	TOTAL COST
NEW	SCHOOL	L AT MURACO ES 5C TOTAL - FIRE PROTECTION						\$000 O
		TOTAL - FIRE PROTECTION						\$333,9
Ī	D50	ELECTRICAL						
ļ	<i>D</i> ₃ 0	ELECTRICAL						
	D5010	COMPLETE ELECTRICAL SYSTEM						
		Electrical system; complete	74,215	gsf	34.00	2,523,310		
		SUBTOTAL					2,523,310	
		TOTAL - ELECTRICAL						\$2,523,
L								
[E10	EQUIPMENT						
	E10	EQUIPMENT, GENERALLY						
1500		Gym wall pads	1	ls	10,000.00	10,000		
1500		Basketball backstops; swing up; electric operated	2	ea	9,800.00	19,600		
1500		Gymnasium dividing net; electrically operated	1	loc	45,000.00	45,000		
500		Volleyball net and standards	1	ea	2,000.00	2,000		
500		Telescoping bleachers	1	ls	25,000.00	25,000		
500		Cubicle curtain & track at nurse area	1	loc	500.00	500		
970		Platform curtains, rigging and controls	1	ls	35,000.00	35,000		
		AV Equipment at Café/Gym/ Learning			,	F,F&E		
400		Food Service equipment	1	ls	225,000.00	225,000		
500		Allowance for loading dock equipment	1	ls	10,000.00	10,000		
400		Refrigerator/Freezer	1	ea	1,000.00	1,000		
400		Kiln	1	ea	3,000.00	3,000		
999		Electrically operated projection screens in gym &			10,000.00	20,000		
,000		cafeteria	2	loc	10,000.00	•		
		AV Equipment (including Smartboards, Projectors, LED monitors, Digital information displays etc.)				FF+E		
		SUBTOTAL					396,100	
Ī		TOTAL - EQUIPMENT						\$206.1
ļ		TOTAL - EQUIPMENT						\$396,1
Ĺ	E20	FURNISHINGS						
	E2010	FIXED FURNISHINGS Entry mats & frames - recessed with carpet/rubber strips	100	sf	45.00	4,500		
		Manual operated roller shades	13,538	sf	6.00	81,228		
		Counters, base cabinets, tall storage in classrooms and other rooms	74,215	gfa	4.00	296,860		
		SUBTOTAL					382,588	
	E2020	MOVABLE FURNISHINGS All movable furnishings to be provided and installed by owner						
		SUBTOTAL					NIC	
		TOTAL - FURNISHINGS						\$382,5

F10

SPECIAL CONSTRUCTION

310

311



Feasibility Design Estimate

Winchester, MA

CSI				UNIT	EST'D	SUB	TOTAL
CODE	DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST

COD	E	DESCRIPTION	QIY	UNII	COSI	COSI	IOIAL	COSI
NE	W SCHOOL	L AT MURACO ES 5C						
312	F10	SPECIAL CONSTRUCTION						
313		No Work in this section						
314		SUBTOTAL						
315								
316		TOTAL - SPECIAL CONSTRUCTION						
317								
318			•					
319 320	F20	SELECTIVE BUILDING DEMOLITION						
321	F2010	BUILDING ELEMENTS DEMOLITION						
322		SUBTOTAL					-	
323								
324	F2020	HAZARDOUS COMPONENTS ABATEMENT						
325		None Included						
326		SUBTOTAL						
327								
328	TOT	TAL - SELECTIVE BUILDING DEMOLITION						

01-Mar-17

74,215



Feasibility Design Estimate GFA 85,455

	BUILDING		ON COST SUMM SUB-TOTAL	AKY TOTAL	\$/SF	%			
WSC		Γ LYNCH ES 5C	SUB-TOTAL	TOTAL	φ/51	/0			
A10	FOUND	DATIONS							
	A1010	Standard Foundations	\$483,746						
	A1020	Special Foundations	\$0						
	A1030	Lowest Floor Construction	\$620,592	\$1,104,338	\$12.92	5.39			
A20	BASEM	ENT CONSTRUCTION							
	A2010	Basement Excavation	\$0						
	A2020	Basement Walls	\$0	\$0	\$0.00	0.09			
B10	SUPER	STRUCTURE							
	B1010	Upper Floor Construction	\$1,527,694						
	B1020	Roof Construction	\$1,429,294	\$2,956,988	\$34.60	14.39			
B20	EXTER	IOR CLOSURE							
	B2010	Exterior Walls	\$1,442,406						
	B2020	Windows	\$1,202,011						
	B2030	Exterior Doors	\$43,040	\$2,687,457	\$31.45	13.09			
Взо	ROOFING								
	B3010	Roof Coverings	\$1,181,145						
	B3020	Roof Openings	\$5,000	\$1,186,145	\$13.88	5.79			
C10	INTER	OR CONSTRUCTION							
	C1010	Partitions	\$1,709,100						
	C1020	Interior Doors	\$427,275						
	C1030	Specialties/Millwork	\$589,640	\$2,726,015	\$31.90	13.19			
C20	STAIR	CASES							
	C2010	Stair Construction	\$78,000						
	C2020	Stair Finishes	\$20,550	\$98,550	\$1.15	0.59			
C30	INTER	OR FINISHES							
	C3010	Wall Finishes	\$384,548						
	C3020	Floor Finishes	\$598,185						
	C3030	Ceiling Finishes	\$512,730	\$1,495,463	\$17.50	7.29			
D10	CONVE	YING SYSTEMS							
	D1010	Elevator	\$100,000	\$100,000	\$1.17	0.59			
D20	PLUME	BING							
	D20	Plumbing	\$1,025,460	\$1,025,460	\$12.00	4.99			



Winchester Schools NEW MURACO + LYNCH COMBINED

Winchester, MA

Feasibility Design Estimate GFA 85,455

		CONSTRUCTION	COST SUMM	IARY		
	BUILDING		SUB-TOTAL	TOTAL	\$/SF	%
EW SCI	HOOL A	Γ LYNCH ES 5C				
D30	HVAC					
	D30	HVAC	\$3,247,290	\$3,247,290	\$38.00	15.7%
D40	FIRE P	ROTECTION				
	D40	Fire Protection	\$384,548	\$384,548	\$4.50	1.9%
D50	ELECT	RICAL				
	D5010	Complete System	\$2,905,470	\$2,905,470	\$34.00	14.0%
E10	EQUIP	MENT				
	E10	Equipment	\$396,100	\$396,100	\$4.64	1.9%
E20	FURNIS	SHINGS				
	E2010	Fixed Furnishings	\$422,808			
	E2020	Movable Furnishings	NIC	\$422,808	\$4.95	2.0%
F10	SPECIA	AL CONSTRUCTION				
	F10	Special Construction	\$0	\$0	\$0.00	0.0%
F20	HAZMA	AT REMOVALS				
	F2010	Building Elements Demolition	\$0			
	F2020	Hazardous Components Abatement	\$0	\$0	\$0.00	0.0%
TOTA	LDIDE	CT COST (Trade Costs)		\$20,736,632	\$242.66	100.0%



Winchester, MA

2

3

10 11

12

13

14

15

16

17

18

20

21

22

23

24

25

26

27

28

29

30

31

32

33

34

35

36

37

38

39

40

41

42

43

44 45

46

47

48 49 Feasibility Design Estimate GFA 85,455

CSI				UNIT	EST'D	SUB	TOTAL
CODE	DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST

NEW SCHOOL AT LYNCH ES 5C

First Floor

44,442 41,013

Second Floor

TOTAL GROSS FLOOR AREA (GFA)	85.455 sf

A10	FOUNDATIONS	

A1010	STANDARD FOUNDATIONS
	Strip footings - 2'-0" x 1'-0"

Excavation	1,221	cv	20.00	24,420
Store on site for reuse	1,221	cy	14.00	17,094
Backfill with existing fill	1,136	cy	16.00	18,176
Remove surplus fill off site	85	cy	25.00	2,125

85 cy Formwork \mathbf{sf} 12.00 26,376 2,198 Re-bar, 10#/lf 10,990 lbs 1.20 13,188 Concrete material; 3,000 psi 85 125.00 10,625

 Concrete material; 3,000 psi
 85
 cy
 125.00
 10,625

 Placing concrete
 85
 cy
 55.00
 4,675

 Foundation walls at exterior - 14" thick

123,088 Formwork 8,792 sf 14.00 Re-bar, 4.5#/sf lbs 1.20 23,738 19,782 Concrete material; 4,000 psi 135.00 27,000 200 cy Placing concrete 65.00 13,000 200 cy

Dampproofing foundation wall and footing 6,594 sf 1.90 NIC
Insulation to foundation walls; 2" thick 4,396 sf 2.50 10,990
Form shelf 1,099 lf 8.00 8,792

 Column footings. typical. 6' x 6' x 2'-0"

 Excavation
 611
 cy
 20.00
 12,220

 Store on site for reuse
 611
 cy
 14.00
 8,554

 Backfill with new fill
 465
 cy
 16.00
 7,440

 Remove surplus fill off site
 146
 cy
 20.00
 2,920

 Formwork
 2,496
 sf
 11.00
 27,456

 Re-bar
 29,120
 lbs
 1.20
 34,944

 Concrete material; 3,000 psi
 146
 cy
 125.00
 18,250

 Concrete material; 3,000 psi
 146 cy
 125.00
 18,250

 Placing concrete
 146 cy
 55.00
 8,030

 Set anchor bolts grout plates
 52 ea
 150.00
 7,800

 Interior pilasters

 Formwork
 1,523
 sf
 11.00
 16,753

Re-bar 9,360 lbs 1.20 11,232 Concrete material; 3,000 psi 27 cy 125.00 3,375

SUBTOTAL 483,746

27

cy

55.00

1,485

A1020 SPECIAL FOUNDATIONS

Placing concrete

No Work in this section

SUBTOTAL

A1030 LOWEST FLOOR CONSTRUCTION



Winchester, MA

Feasibility Design Estimate GFA 85,455

CSI				UNIT	EST'D	SUB	TOTAL
CODE	DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST
NEW SCI	HOOL AT LYNCH ES 5C					•	
	New Slab on grade, 5" thick						
	Structural gravel fill, 8"	1,098	cy	30.00	32,940		
	Base course, 8" gravel	1,098	cy	40.00	43,920		
	Rigid insulation	44,442	sf	2.25	99,995		
	Vapor barrier	44,442	sf	1.00	44,442		
	Mesh reinforcing 15% lap	51,108	sf	0.80	40,886		
	Concrete - 5" thick	726	cy	125.00	90,750		
	Placing concrete	726	cy	45.00	32,670		
	Finishing and curing concrete	44,442	sf	4.00	177,768		
	Control joints - saw cut	44,442	sf	0.50	22,221		
	Miscellaneous						
	Elevator pit	1	ea	30,000.00	30,000		
	Dewatering	1	ea	5,000.00	5,000		
	SUBTOTAL					620,592	
	TOTAL - FOUNDATIONS						\$1,104,3

A20 BASEMENT CONSTRUCTION

A2010 BASEMENT EXCAVATION

No items in this section

SUBTOTAL

A2020 BASEMENT WALLS

No items in this section

SUBTOTAL

TOTAL - BASEMENT CONSTRUCTION

B10	SUPERSTRUCTURE					
		13	lbs/sf			
B1010	FLOOR CONSTRUCTION	556	tns			
	Floor Structure - Steel:					
	Steel beams and columns; 13/SF	267	tns	3,500.00	934,500	
	Shear studs	8,203	ea	2.50	20,508	
	Floor Structure					
	2" Metal floor Deck	41,013	sf	4.20	172,255	
	WWF reinforcement	47,165	sf	0.80	37,732	
	Concrete Fill to metal deck; 5" normal weight	654	cy	125.00	81,750	
	Place and finish concrete	41,013	sf	2.00	82,026	
	Misc. perimeter angles	1,099	lf	25.00	27,475	
	<u>Miscellaneous</u>					
	Barrier one at slab	654	cy	65.00	42,510	
	Fire proofing to columns and beams	41,013	sf	2.90	118,938	
	Fire stopping floors	2	flrs	5,000.00	10,000	
	SUBTOTAL					1,527,694



Winchester Schools NEW MURACO + LYNCH COMBINED Winchester, MA

Feasil	oility Design Estimate					GFA	85,455
CSI				UNIT	EST'D	SUB	TOTAL
CODE	DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST

		•					
W SCHOOL	L AT LYNCH ES 5C		•				•
B1020	ROOF CONSTRUCTION						
	Roof Structure - Steel:						
	Steel beams/Joists; 13#/SF	289	tns	3,800.00	1,098,200		
	Roof Structure						
	1-1/2" Metal floor Deck @ roof	44,442	sf	3.00	133,326		
	Miscellaneous						
	Roof screen framing - allow	1	ls	20,000.00	20,000		
	Fire proofing to columns, beams and deck	44,442	sf	4.00	177,768		
	SUBTOTAL					1,429,294	
	TOTAL - SUPERSTRUCTURE						\$2,956,9
B20	EXTERIOR CLOSURE						
B2010	EXTERIOR WALLS; 60% solid/40% glass	19,123	sf				
	Interior skin	<i>),</i> 0					
	6" metal stud backup	19,123	sf	7.50	143,423		
	Batt insulation in stud	19,123	sf	2.25	43,027		
	2 1/2" Rigid Insulation	19,123	sf	3.00	57,369		
	Air barrier	19,123	sf	6.00	114,738		
	Air barrier/flashing at windows	4,207	lf	7.00	29,449		
	Gypsum Sheathing	19,123	sf	2.75	52,588		
	Drywall lining to interior face of stud backup	19,123	sf	3.00	57,369		
	Exterior skin						
	Brick veneer; 75% of exterior wall	14,342	sf	35.00	501,970		
	Metal panels; 25% of exterior wall	4,781	sf	60.00	286,860		
	Miscellaneous						
	Roof screens - allow	1	ls	60,000.00	60,000		
	Staging to exterior wall	31,871	sf	3.00	95,613		
	SUBTOTAL					1,442,406	
Ranan	WINDOWS	12,748	sf				
D2020	Premium for sunscreen and light shelf elements	12,/40 1	ls		NIC		
	Windows/storefront	12,748	sf	90.00	1,147,320		
	Backer rod & double sealant	4,207	lf	9.00	37,863		
	Wood blocking at openings	4,207	lf	4.00	16,828		
	SUBTOTAL	1,/	•		-, 0	1,202,011	
_						•	
B2030	EXTERIOR DOORS Glazed entrance doors including frame and hardware; double door at corridor exit	4	pr	8,000.00	32,000		
	Other doors	1	ls	10,000.00	10,000		
	Backer rod & double sealant	80	lf	9.00	720		
	Wood blocking at openings	80	lf	4.00	320		
	SUBTOTAL					43,040	
	TOTAL - EXTERIOR CLOSURE						\$2,687,4

01-Mar-17



Winchester, MA

Feasibility Design Estimate GFA 85,455

CSI				UNIT	EST'D	SUB	TOTAL
CODE	DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST
NEW	SCHOOL AT LYNCH ES 5C	ı					

<i>B</i> 30	ROOFING						
B3010	ROOF COVERINGS Flat roofing						
	PVC roof membrane fully adhered	44,442	sf	14.00	622,188		
	Insulation	44,442	sf	7.00	311,094		
	1/2" dens-deck protection board	44,442	sf	2.00	88,884		
	Reinforced vapor barrier	44,442	sf	1.50	66,663		
	Rough blocking	4,396	lf	6.00	26,376		
	Miscellaneous Roofing						
	Roof screens - allow				NIC		
	Roof fascia/cornice	1,099	lf	60.00	65,940		
	SUBTOTAL					1,181,145	
B3020	ROOF OPENINGS						
	Skylights, allow				NIC		
	Roof hatch	1	ea	5,000.00	5,000		
	SUBTOTAL					5,000	
	TOTAL - ROOFING						\$1,186
							,
	NAMED TO BE OF THE PARTY OF THE	¬					
C10	INTERIOR CONSTRUCTION						
C1010	PARTITIONS						
	Allowance for interior walls/glazed partitions etc.	85,455	gfa	20.00	1,709,100		
	SUBTOTAL					1,709,100	
C1020	INTERIOR DOORS						
C1020	Interior doors, frames and hardware	85,455	gfa	5.00	427,275		
	SUBTOTAL	07 100	8		ŕ	427,275	
C1030	SPECIALTIES / MILLWORK						
	Marker boards/tackboards in classroom	85,455	gfa	1.15	98,273		
	Toilet partitions and accessories	85,455	gfa	0.75	64,091		
	Room Signs	85,455	gfa	0.25	21,364		
	Wood paneling/benches/display cases etc.	85,455	gfa	1.50	128,183		
	Lockers	85,455	sf	1.00	85,455		
	Miscellaneous metals throughout building	85,455	sf	1.25	106,819		
	Miscellaneous sealants throughout building	85,455	sf	1.00	85,455		
	SUBTOTAL					589,640	
	TOTAL - INTERIOR CONSTRUCTION						\$2,720

Metal pan stair; egress stair

Concrete fill to stairs

196

197

55100

33000

flt

flt

3

3

24,000.00

2,000.00

72,000

6,000



Feasibility Design Estimate GFA 85,455

CSI					UNIT	EST'D	SUB	TOTAL
CODE		DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST
NEW	SCHOOL	L AT LYNCH ES 5C						
		SUBTOTAL					78,000	
	C2020	STAIR FINISHES						
90009		High performance coating to stairs including all	3	flt	3,000.00	9,000		
		railings etc.						
90006		Rubber tile at stairs - landings	330	sf	12.00	3,960		
90006		Rubber tile at stairs - treads & risers	345	lft	22.00	7,590		
		SUBTOTAL					20,550	
							.,	
		TOTAL - STAIRCASES						\$98,550
ļ								
ı			_					
	C30	INTERIOR FINISHES						
	C2010	WALL FINISHES						
	03010	Wall finishes	85,455	gfa	4.50	384,548		
		SUBTOTAL	×3,433	8	1.00	001,010	384,548	
		SOBIOTAL					304,340	
	Canan	FLOOR FINISHES						
	C3020	Floor finishes	85,455	sf	7.00	598,185		
		SUBTOTAL	05,455	51	7.00	550,105	E00 10E	
		SUBTUTAL					598,185	
	C3030	CEILING FINISHES						
	-0-0-	Ceiling finishes	85,455	sf	6.00	512,730		
		SUBTOTAL	۵, ۱۵۵				512,730	
							,	
		TOTAL - INTERIOR FINISHES						\$1,495,46;
ļ								
1	1		_					
	D10	CONVEYING SYSTEMS						
	Dioto	ELEVATOR						
93000	DIOIO	Passenger elevator; 2 stop, 3500 lbs	1	ea	100,000.00	100,000		
		SUBTOTAL	_	-	,	,	100,000	
		SOBIOTAL					100,000	
		TOTAL - CONVEYING SYSTEMS						\$100,000
•								
1	Doo	PLUMBING	٦					
	D20	FLUMBING						
	D20	PLUMBING, GENERALLY						
		Plumbing allowance	85,455	gsf	12.00	1,025,460		
		SUBTOTAL					1,025,460	
,								
		TOTAL - PLUMBING						\$1,025,46
!								
i	Doo	HVAC	٦					
	D30	HVAC						
	D30	HVAC, GENERALLY						
	J	HVAC complete system	85,455	gsf	38.00	3,247,290		
		SUBTOTAL	- 07 100	8-		, , , , , ,	3,247,290	
		TOTAL - HVAC						\$3,247,29
							-	
•								
·	D40	FIRE PROTECTION	7					

D40 FIRE PROTECTION, GENERALLY

254 255



NEW MURACO + LYNCH COMBINED
Winchester, MA

CSI		DESCRIPTION	OTT	TIMITE	UNIT	EST'D	SUB	TOTAL
NEW	SCHOOT	AT LYNCH ES 5C	QTY	UNIT	COST	COST	TOTAL	COST
7477 AA 1	5011001	Sprinkler system	85,455	gsf	4.50	384,548		
		SUBTOTAL	05,455	gsi	4.50	364,346	384,548	
		SUBTOTAL					304,340	
		TOTAL - FIRE PROTECTION						\$384,
ſ	D50	ELECTRICAL						
•			•					
	D5010	COMPLETE ELECTRICAL SYSTEM	0= 4==	ggf	34.00	2,905,470		
		Electrical system; complete	85,455	gsf	34.00	2,903,470	0.005.470	
		SUBTOTAL					2,905,470	
[TOTAL - ELECTRICAL						\$2,905,
[E10	EQUIPMENT						
•	E10	EQUIPMENT, GENERALLY						
11500	LIO	Gym wall pads	1	ls	10,000.00	10,000		
11500		Basketball backstops; swing up; electric operated	2	ea	9,800.00	19,600		
11500		Gymnasium dividing net; electrically operated	1	loc	45,000.00	45,000		
11500		Volleyball net and standards	1	ea	2,000.00	2,000		
11500		Telescoping bleachers	1	ls	25,000.00	25,000		
11500		Cubicle curtain & track at nurse area	1	loc	500.00	500		
11970					35,000.00	35,000		
11070		Platform curtains, rigging and controls	1	ls	33,000.00	55,000 F,F&E		
11400		AV Equipment at Café/Gym/ Learning	_	1-	997 000 00			
11500		Food Service equipment	1	ls	225,000.00	225,000		
11400		Allowance for loading dock equipment	1	ls	10,000.00	10,000		
		Refrigerator/Freezer	1	ea	1,000.00	1,000		
11400		Kiln	1	ea	3,000.00	3,000		
10999		Electrically operated projection screens in gym & cafeteria AV Equipment (including Smartboards, Projectors,	2	loc	10,000.00	20,000 FF+E		
		LED monitors, Digital information displays etc.) SUBTOTAL				rr+£	396,100	
		SODIO ME					550,100	
		TOTAL - EQUIPMENT						\$396,
ı								
ſ	E20	FURNISHINGS						
ļ			ı					
	E2010	FIXED FURNISHINGS Entry mats & frames - recessed with carpet/rubber strips	100	sf	45.00	4,500		
		Manual operated roller shades	12,748	sf	6.00	76,488		
		Counters, base cabinets, tall storage in classrooms and other rooms	85,455	gfa	4.00	341,820		
		SUBTOTAL					422,808	
	E2020	MOVABLE FURNISHINGS						
	22020	All movable furnishings to be provided and installed by owner						
		SUBTOTAL					NIC	



Winchester, MA

310 311

312

313

314 315

316 317 318

319 320

321

322 323

324

325

326 327 Feasibility Design Estimate GFA 85,455

CSI				UNIT	EST'D	SUB	TOTAL
CODE	DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST

NEW SCHOOL AT LYNCH ES 5C

06 TOTAL - FURNISHINGS \$2	422,808	;
----------------------------	---------	---

F10 SPECIAL CONSTRUCTION

F10 SPECIAL CONSTRUCTION
No Work in this section
SUBTOTAL

TOTAL - SPECIAL CONSTRUCTION

F20 SELECTIVE BUILDING DEMOLITION

F2010 BUILDING ELEMENTS DEMOLITION

SUBTOTAL

F2020 HAZARDOUS COMPONENTS ABATEMENT

None Included SUBTOTAL

TOTAL - SELECTIVE BUILDING DEMOLITION



01-Mar-17

Feasibility Design Estimate

CSI				UNIT	EST'D	SUB	TOTAL
CODE	DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST

SITEWORK NEW LYNCH SCHOOL

1 2	г			1				
	L	G	SITEWORK					
3		G10	SITE PREPARATION & DEMOLITION					
5		010	Site Demolitions and Relocations					
6	024100		Site construction fence/barricades; visual screen	2,000	lf	9.00	18,000	
7	02200		Demolish existing paving	100,000	sf	1.00	100,000	
8	02200		Demolish soccer field	1	loc	10,000	10,000	
9	02200		Site clearing/grubbing	1	ls	30,000.00	30,000	
10	02200		Miscellaneous demolition allowance including existing utilities	1	ls	50,000	50,000	
11			Site Earthwork					
12	310000		Construction entrances/wheel washes (allowance)	2	loc	12,000.00	24,000	
13	311000		Strip topsoil, store; assume 6"	3,704	cy	8.00	29,632	
14	310000		Cut/fill	16,667	cy	6.00	100,002	
15	310000		Export excess material - assumed balanced site		·			
16	310000		Fine grading	33,333	sy	0.75	25,000	
17	312500		Silt fence/erosion control (allowance)	2,000	lf	12.00	24,000	
18	312500		Erosion Control monitoring & maintenance	2,000	ls	30,000.00	30,000	
19			Hazardous Waste Remediation	•	15	00,000.00	55,555	
20			SUBTOTAL					440.624
21			SUBTUTAL					440,634
22		G20	SITE IMPROVEMENTS					
23 24			Doodways and Darking Late					
25			Roadways and Parking Lots Bituminous concrete paving	62,551	sf			
26	320000		gravel base; 12" thick	2,317		35.00	81,095	
27	320000		bituminous concrete; 4" thick	6,950	cy sy	26.00	180,700	
28	320000		6"x18" granite curb	3,811	lf	35.00	133,385	
29	320000		Premium for radius curbs	1	ls	25,000.00	25,000	
30	320000		Road markings	1	ls	15,000.00	15,000	
31	321724		Signage	1	ls	20,000.00	20,000	
32			Fire lane					
33			Bituminous concrete paving	23,260	sf		-	
34	320000		gravel base; 18" thick	1,292	cy	35.00	45,220	
35	320000		bituminous concrete; 4" thick	2,584	sy	26.00	67,184	
36 37	320000		6"x18" granite curb	1,806	lf	35.00	63,210	
38			Pedestrian paving: allowance of 10,000 sf		c			
39	320000		Concrete paving broom finish	10,000	sf	35.00	8,680	
40	033000		gravel base; 8" thick concrete paving; 4" thick	248 10,000	cy sf	6.50	65,000	
41			Concrete pavers; allowance of 5,000 sf	10,000	31	0.50	03,000	
42			Concrete pavers	5,000	sf		_	
43	320000		sand bedding; 1" thick	15	cy	25.00	375	
44	033000		Precast concrete pavers	5,000	sf	14.00	70,000	
45	320000		gravel base; 8" thick	124	cy	35.00	4,340	
46	033000		concrete base; 4" thick	5,000	sf	5.00	25,000	
47			Site Improvements					
48	129300		Bicycle racks - Allowance	20	ea	1,000.00	20,000	
49	129300		Flag pole	1	loc	7,500.00	7,500	
50	129300		Ornamental trash/recycling receptacles	8	loc	1,400.00	11,200	
51	129300		Bollards	10	ea	850.00	8,500	
52	129300		Bollards; moveable	4	loc	1,500.00	6,000	



Feasibility Design Estimate

	CSI					UNIT	EST'D	SUB	TOTAL
	CODE		DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST
				X					
		ORK N	EW LYNCH SCHOOL						
53	129300		Dumpster enclosure and pad	1	ls	15,000.00	15,000		
54	129300		Fence along perimeter	1,200	lf	90.00	108,000		
55	129300		New site entrance sign	1	ls	25,000.00	25,000		
56	129300		Miscellaneous site improvements	1	ls	100,000.00	100,000		
57			Soccer Field - assumed grass						
58	329210		Grass field including drainage etc.	71,500	sf	2.00	143,000		
59 60	116800 116800		Soccer Goal	2	loc	4,000.00	8,000		
61	323114		Benches - allowance Vinyl CL Fencing 4'	2	loc lf	2,250.00 55.00	4,500 52,855		
62	323114		Gate, single	961 2	ea	1,200.00	2,400		
63			Gate, Single	_	ca	1,200.00	2,400		
64			Landscaping & Plantings:						
65	329900		Spread existing amended topsoil @ seeded areas.	3,704	cy	22.00	81,488		
66	329900		New seeded areas	200,949	sf	0.25	50,237		
67	02830		Planting allowance	1	ls	150,000.00	150,000		
68			SUBTOTAL					1,597,869	
69									
70	•	G30	CIVIL MECHANICAL UTILITIES						
71 72	33	1000	WATER UTILITIES						
73	312003		New fire DI piping; 8"	400	lf	90.00	36,000		
74	312003		New DI piping; 6"	400	lf	75.00	30,000		
75	312003		New fire hydrant	2	loc	2,600.00	5,200		
76	312003		FD connection	1	loc	2,000.00	2,000		
77	312003		Gate valves	4	loc	750.00	3,000		
78				•			2,222		
79	333	3000	SANITARY SEWERAGE UTILITIES						
80	333000		Sanitary sewer						
81	333000		6" PVC Sanitary sewer	400	lf	45.00	18,000		
82	333000		SMH	4	ea	4,000.00	16,000		
83	333000		Grease trap; 9,000 Gal	1	loc	15,000.00	15,000		
84 85	334	4000	STORM DRAINAGE UTILITIES						
86	312003		Allowance for storm water management	77,551	sf	5.00	387,755		
87			Thowards for storm water management	//,555-	51	0.00	007,700		
88	312003		Gas service						
89	312003		E&B trench for new lines, pipe and install by utilities						
90	312003		New gas service	400	lf	25.00	10,000		
91 92			SUBTOTAL					522,955	
93		G40	ELECTRICAL UTILITIES						
94	016100	•	Electric handhole	2	ea	1,500.00	3,000		
95	016100		Primary ductbank	400	lf	120.00	48,000		
96	016100		Transformer by Utility Company	1	ea		NIC		
97	016100					2 000 00			
98	016100		Transformer pad Secondary service	1	ea	2,000.00	2,000		
99	016100		Ductbank	50	lf	500.00	25,000		
100	016100		Emergency service	,,,		300.00	20,000		
101	016100		Ductbank	100	lf	150.00	15,000		
102	016100		Generator pad	1	ea	1,500.00	1,500		
103	016100		Site lighting						
104	016100		Allowance for site lighting	1	ls	100,000.00	100,000		
105	016100		Allowance for sports lighting				NIC		




113

Feasibility Design Estimate

	CSI				UNIT	EST'D	SUB	TOTAL
	CODE	DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST
	SITEV	WORK NEW LYNCH SCHOOL						
106	016100	Site communications and security						
107	016100	Site security	1	ls	15,000.00	15,000		
108	016100	Communication riser pole	1	ea	2,500.00	2,500		
109	016100	Telecom handhole	2	ea	1,500.00	3,000		
110	016100	Ductbank	400	lf	130.00	52,000		
111		SUBTOTAL					267,000	
112								

SUBTOTAL - SITE DEVELOPMENT LYNCH SCHOOL

\$2,828,458



Feasibility Design Estimate

Winchester Schools NEW MURACO + LYNCH COMBINED

Winchester, MA

PM&C LLC 20 Downer Avenue, Suite 1c Hingham, MA 02043 (T) 781-740-8007 (F) 781-740-1012 Prepared for:

Flansburgh Architects

March 13, 2017



13-Mar-17

Feasibility Design Estimate

MAIN CONSTRUCTION COST SUMMARY

	Construction Start	Gross Floor Area	\$/sf	Estimated Construction Cost
OPTION ES-5C - NEW LYNCH ELI	EMENTARY S	SCHOOL		
DEMOLISH EXISTING SCHOOL		79,745	\$8.00	\$637,960
HAZMAT REMOVALS		79,745	\$15.00	\$1,196,175
NEW SCHOOL		85,455	\$242.66	\$20,736,632
SITEWORK				\$3,193,098
SUB-TOTAL	Mar-18	85,455	\$301.49	\$25,763,865
ESCALATION TO START - (assumed 3% PA)	6.0%			\$1,545,832
DESIGN AND PRICING CONTINGENCY	12%			\$3,091,664
SUB-TOTAL		85,455	\$355.76	\$30,401,361
GENERAL CONDITIONS				\$2,432,109
BONDS	1.00%			\$304,014
INSURANCE	2.00%			\$608,027
PERMIT				NIC
OVERHEAD AND FEE	3.00%			\$912,041
OWNER CONTINGENCY				By Owner
TOTAL OF ALL CONSTRUCTION	Mar-18	85,455	\$405.56	\$34,657,552



13-Mar-17

Feasibility Design Estimate

MAIN CONSTRUCTION COST SUMMARY

	Construction Start	Gross Floor Area	\$/sf	Estimated Construction Cost
OPTION ES-5C - NEW MURACO H	ELEMENTAR	Y SCHOOL		
DEMOLISH EXISTING SCHOOL		55,415	\$8.00	\$443,320
HAZMAT REMOVALS		55,415	\$15.00	\$831,225
NEW SCHOOL		74,215	\$258.09	\$19,154,294
SITEWORK - (Allowance of 12% of Building)				\$2,298,515
SUB-TOTAL	Mar-20	74,215	\$289.06	\$21,452,809
ESCALATION TO START - (assumed 4% PA)	12.0%			\$2,574,337
DESIGN AND PRICING CONTINGENCY	12%			\$2,574,337
SUB-TOTAL		74,215	\$358.44	\$26,601,483
GENERAL CONDITIONS				\$2,128,119
BONDS	1.00%			\$266,015
INSURANCE	2.00%			\$532,030
PERMIT				NIC
OVERHEAD AND FEE	3.00%			\$798,044
OWNER CONTINGENCY				By Owner
TOTAL OF ALL CONSTRUCTION	Mar-20	74,215	\$408.62	\$30,325,691



13-Mar-17

Feasibility Design Estimate

This Feasibility Design cost estimate was produced from preliminary drawings prepared by Flansburgh Architects Inc. and their design team dated February 28, 2017. Design and engineering changes occurring subsequent to the issue of these documents have not been incorporated in this estimate.

This estimate includes all direct construction costs, general contractor's overhead, fee and design contingency. Cost escalation assumes start dates indicated.

Bidding conditions are expected to be public bidding under Chapter 149 of the Massachusetts General Laws to pre-qualified general contractors, and pre-qualified sub-contractors, open specifications for materials and manufactures.

The estimate is based on prevailing wage rates for construction in this market and represents a reasonable opinion of cost. It is not a prediction of the successful bid from a contractor as bids will vary due to fluctuating market conditions, errors and omissions, proprietary specifications, lack or surplus of bidders, perception of risk, etc. Consequently the estimate is expected to fall within the range of bids from a number of competitive contractors or subcontractors, however we do not warrant that bids or negotiated prices will not vary from the final construction cost estimate.

ITEMS NOT CONSIDERED IN THIS ESTIMATE

Items not included in this estimate are:

Land acquisition, feasibility, and financing costs
All professional fees and insurance
Site or existing conditions surveys investigations costs, including to determine subsoil conditions
All Furnishings, Fixtures and Equipment
Items identified in the design as Not In Contract (NIC)
Items identified in the design as by others
Owner supplied and/or installed items as indicated in the estimate

Work to City streets and sidewalks, (except as noted in this estimate)

Utility company back charges, including work required off-site

Construction contingency



Winchester, MA

Feasibility Design Estimate GFA 74,215

			ON COST SUMM						
	BUILDING		SUB-TOTAL	TOTAL	\$/SF	%			
EW SC		Γ MURACO ES 5C							
A10		DATIONS							
	A1010	Standard Foundations	\$614,098						
	A1020	Special Foundations	\$0						
	A1030	Lowest Floor Construction	\$696,377	\$1,310,475	\$17.66	6.8%			
A20	BASEM	IENT CONSTRUCTION							
	A2010	Basement Excavation	\$0						
	A2020	Basement Walls	\$0	\$0	\$0.00	0.09			
B10	SUPER	STRUCTURE							
	B1010	Upper Floor Construction	\$1,050,175						
	B1020	Roof Construction	\$1,492,407	\$2,542,582	\$34.26	13.39			
B20	FYTED	IOR CLOSURE							
D20	B2010	Exterior Walls	\$1,527,916						
	B2020	Windows	\$1,276,504						
	B2030	Exterior Doors	\$43,040	\$2,847,460	\$38.37	14.99			
Pag	ROOFING								
B30	B3010	Roof Coverings	\$1,237,289						
	B3020	Roof Openings		¢1 949 980	\$16.74	6.59			
	DSUZU	Roof Openings	nings \$5,000 \$1,242,289	\$10.74	0.070				
C10		IOR CONSTRUCTION							
	C1010	Partitions	\$1,484,300						
	C1020	Interior Doors	\$371,075						
	C1030	Specialties/Millwork	\$512,084	\$2,367,459	\$31.90	12.49			
C20	STAIR	CASES							
	C2010	Stair Construction	\$78,000						
	C2020	Stair Finishes	\$20,550	\$98,550	\$1.33	0.59			
С30	INTER	IOR FINISHES							
-00	C3010	Wall Finishes	\$333,968						
	C3020	Floor Finishes	\$519,505						
	C3030	Ceiling Finishes	\$445,290	\$1,298,763	\$17.50	6.89			
D10	CONVE	YING SYSTEMS							
D10	D1010	Elevator	\$100,000	\$100,000	\$1.35	0.59			
_				·					
D20	PLUME D20		\$890,580	\$200 = 20	\$12.00	4.69			
	Dau	Plumbing	\$69U,36U	\$890,580	\$12.00	4.07			



Winchester, MA

Feasibility Design Estimate GFA 74,215

		CONSTRUCTION	COST SUMM	ARY			
	BUILDING	SYSTEM	SUB-TOTAL	TOTAL	\$/SF	%	
W SC	HOOL A	Γ MURACO ES 5C					
D30	HVAC						
	D30	HVAC	\$2,820,170	\$2,820,170	\$38.00	14.7%	
D40	FIRE P	ROTECTION					
	D40	Fire Protection	\$333,968	\$333,968	\$4.50	1.7%	
D50	ELECT						
	D5010	Complete System	\$2,523,310	\$2,523,310	\$34.00	13.2%	
E10	EQUIP	MENT					
	E10	Equipment	\$396,100	\$396,100	\$5.34	2.1%	
E20	FURNISHINGS						
	E2010	Fixed Furnishings	\$382,588				
	E2020	Movable Furnishings	NIC	\$382,588	\$5.16	2.0%	
F10	SPECIA	AL CONSTRUCTION					
	F10	Special Construction	\$0	\$0	\$0.00	0.0%	
F20	HAZMA	AT REMOVALS					
	F2010	Building Elements Demolition	\$0				
	F2020	Hazardous Components Abatement	\$0	\$0	\$0.00	0.0%	
TOTA	AL DIRE	CT COST (Trade Costs)		\$19,154,294	\$258.09	100.0%	



3

10 11

12

35 36 37

38

39

40

41

42

43

44

45 46

47

49

Winchester Schools NEW MURACO + LYNCH COMBINED Winchester, MA

GFA 74,215 Feasibility Design Estimate

CSI				UNIT	EST'D	SUB	TOTAL
CODE	DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST

NEW SCHOOL AT MURACO ES 5C

GROSS FLOOR AREA CALCULATION

First Floor 46,401 Second Floor 27,814

TOTAL GROSS FLOOR AREA (GFA) 74,215 sf

150.00

11.00

12,750

27,379

A10 FOUNDATIONS

A1010 STANDARD FOUNDATIONS Strip footings - 2'-0" x 1'-0"

Excavation	1,329	cy	20.00	26,580	
Store on site for reuse	1,329	cy	14.00	18,606	
Backfill with existing fill	1,236	cy	16.00	19,776	
Remove surplus fill off site	93	cy	25.00	2,325	
Formwork	2,392	sf	12.00	28,704	
Re-bar, 10#/lf	11,960	lbs	1.20	14,352	
Concrete material; 3,000 psi	93	cy	125.00	11,625	
Placing concrete	93	cy	55.00	5,115	
Foundation walls at exterior - 14" thick					
Formwork	9,568	sf	14.00	133,952	
Re-bar, 4.5#/sf	21,528	lbs	1.20	25,834	
Concrete material; 4,000 psi	218	cy	135.00	29,430	
Placing concrete	218	cy	65.00	14,170	
Dampproofing foundation wall and footing	7,176	sf	1.90	NIC	
Insulation to foundation walls; 2" thick	4,784	sf	2.50	11,960	
Form shelf	1,196	lf	8.00	9,568	
Column footings, typical, 6' x 6' x 2'-0"					
Excavation	998	cy	20.00	19,960	
Store on site for reuse	998	cy	14.00	13,972	
Backfill with new fill	760	cy	16.00	12,160	
Remove surplus fill off site	238	cy	20.00	4,760	
Formwork	4,080	sf	11.00	44,880	
Re-bar	47,600	lbs	1.20	57,120	
Concrete material; 3,000 psi	238	cy	125.00	29,750	
Placing concrete	238	cy	55.00	13,090	

Re-bar 15,300 lbs 1.20 18,360 Concrete material; 3,000 psi 125.00 5,500 44 cy

85

2,489

ea

sf

Placing concrete 55.00 2,420 44 cy SUBTOTAL

A1020 SPECIAL FOUNDATIONS

No Work in this section

Set anchor bolts grout plates

Interior pilasters

Formwork

SUBTOTAL

A1030 LOWEST FLOOR CONSTRUCTION

614,098



Winchester Schools NEW MURACO + LYNCH COMBINED Winchester MA

Feasibility Design Estimate

Winchester, MA

CSI CODE	DESCRIPTION	QTY	UNIT	UNIT COST	EST'D COST	SUB TOTAL	TOTAL COST
		QH	UNII	COSI	cosi	IOIAL	COST
NEW SCI	HOOL AT MURACO ES 5C						
	New Slab on grade, 5" thick						
	Structural gravel fill, 8"	1,146	cy	30.00	34,380		
	Base course, 8" gravel	1,146	cy	40.00	45,840		
	Rigid insulation	46,401	sf	2.25	104,402		
	Vapor barrier	46,401	sf	1.00	46,401		
	Mesh reinforcing 15% lap	53,361	sf	0.80	42,689		
	Concrete - 5" thick	758	cy	125.00	94,750		
	Placing concrete	758	cy	45.00	34,110		
	Finishing and curing concrete	46,401	sf	4.00	185,604		
	Control joints - saw cut	46,401	sf	0.50	23,201		
	<u>Miscellaneous</u>						
	Backfill existing foundations/basement	1	ea	50,000.00	50,000		
	Elevator pit	1	ea	30,000.00	30,000		
	Dewatering	1	ea	5,000.00	5,000		
	SUBTOTAL					696,377	
						ŕ	
	TOTAL - FOUNDATIONS						\$1,310,4

A20 BASEMENT CONSTRUCTION

A2010 BASEMENT EXCAVATION

No items in this section

SUBTOTAL

A2020 BASEMENT WALLS

No items in this section

SUBTOTAL

TOTAL - BASEMENT CONSTRUCTION

В10	SUPERSTRUCTURE				
		13	lbs/sf		
B1010	FLOOR CONSTRUCTION	483	tns		
	Floor Structure - Steel:				
	Steel beams and columns; 13/SF	181	tns	3,500.00	633,500
	Shear studs	5,563	ea	2.50	13,908
	Floor Structure				
	2" Metal floor Deck	27,814	sf	4.20	116,819
	WWF reinforcement	31,986	sf	0.80	25,589
	Concrete Fill to metal deck; 5" normal weight	443	cy	125.00	55,375
	Place and finish concrete	27,814	sf	2.00	55,628
	Misc. perimeter angles	1,196	lf	25.00	29,900
	<u>Miscellaneous</u>				
	Barrier one at slab	443	cy	65.00	28,795
	Fire proofing to columns and beams	27,814	sf	2.90	80,661
	Fire stopping floors	2	flrs	5,000.00	10,000

13-Mar-17

74,215



99 100

101

102

103

104

105

106

107

108

109

110

Winchester Schools NEW MURACO + LYNCH COMBINED Winchester MA

Feasibility Design Estimate

Winchester, MA

CSI				UNIT	EST'D	SUB	TOTAL
CODE	DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST

NEW SCHOOL AT MURACO ES 5C
SUBTOTAL 1,050,175

B1020 ROOF CONSTRUCTION

Roof Structure - Steel: Steel beams/Joists; 13#/SF 3,800.00 1,147,600 302 tns Roof Structure 1-1/2" Metal floor Deck @ roof 46,401 sf 3.00 139,203 Miscellaneous 20,000.00 20,000 Roof screen framing - allow ls Fire proofing to columns, beams and deck 4.00 185,604 sf 46,401

SUBTOTAL 1,492,407

TOTAL - SUPERSTRUCTURE \$2,542,582

B20	EXTERIOR CLOSURE					
B2010	EXTERIOR WALLS; 60% solid/40% glass Interior skin	20,306	sf			
	6" metal stud backup	20,306	sf	7.50	152,295	
	Batt insulation in stud	20,306	sf	2.25	45,689	
	2 1/2" Rigid Insulation	20,306	sf	3.00	60,918	
	Air barrier	20,306	sf	6.00	121,836	
	Air barrier/flashing at windows	4,468	lf	7.00	31,276	
	Gypsum Sheathing	20,306	sf	2.75	55,842	
	Drywall lining to interior face of stud backup	20,306	sf	3.00	60,918	
	Exterior skin					
	Brick veneer; 75% of exterior wall	15,230	sf	35.00	533,050	
	Metal panels; 25% of exterior wall	5,076	sf	60.00	304,560	
	Miscellaneous					
	Roof screens - allow	1	ls	60,000.00	60,000	
	Staging to exterior wall	33,844	sf	3.00	101,532	
	SUBTOTAL					1,527,916
B2020	WINDOWS	13,538	sf			
	Premium for sunscreen and light shelf elements	1	ls		NIC	
	Windows/storefront	13,538	sf	90.00	1,218,420	
	Backer rod & double sealant	4,468	lf	9.00	40,212	
	Wood blocking at openings	4,468	lf	4.00	17,872	
	SUBTOTAL					1,276,504
B2030	EXTERIOR DOORS					
500	Glazed entrance doors including frame and hardware; double door at corridor exit	4	pr	8,000.00	32,000	
	Other doors	1	ls	10,000.00	10,000	
	Backer rod & double sealant	80	lf	9.00	720	
	Wood blocking at openings	80	lf	4.00	320	
	SUBTOTAL					43,040

13-Mar-17

74,215



195 196

55100

Winchester Schools NEW MURACO + LYNCH COMBINED

Feasibility Design Estimate

Winchester, MA

CSI				UNIT	EST'D	SUB	TOTAL
CODE	DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST

	TOTAL - EXTERIOR CLOSURE						\$2
Взо	ROOFING						
B3010	ROOF COVERINGS Flat roofing						
	PVC roof membrane fully adhered	46,401	sf	14.00	649,614		
	Insulation	46,401	sf	7.00	324,807		
	1/2" dens-deck protection board	46,401	sf	2.00	92,802		
	Reinforced vapor barrier	46,401	sf	1.50	69,602		
	Rough blocking	4,784	lf	6.00	28,704		
	Miscellaneous Roofing						
	Roof screens - allow				NIC		
	Roof fascia/cornice	1,196	lf	60.00	71,760		
	SUBTOTAL					1,237,289	
_							
B3020	ROOF OPENINGS				NIC		
	Skylights, allow	_		r 000 00	NIC		
	Roof hatch	1	ea	5,000.00	5,000	r 000	
	SUBTOTAL					5,000	
	TOTAL - ROOFING						\$
Cto	INTERIOR CONCERNICATION	¬					
C10	INTERIOR CONSTRUCTION						
C1010	PARTITIONS						
	$Allowance\ for\ interior\ walls/glazed\ partitions\ etc.$	74,215	gfa	20.00	1,484,300		
	SUBTOTAL					1,484,300	
C1020	INTERIOR DOORS						
01020	Interior doors, frames and hardware	74,215	gfa	5.00	371,075		
	SUBTOTAL					371,075	
C1030	SPECIALTIES / MILLWORK						
	Marker boards/tackboards in classroom	74,215	gfa	1.15	85,347		
	Toilet partitions and accessories	74,215	gfa	0.75	55,661		
	Room Signs	74,215	gfa	0.25	18,554		
	Wood paneling/benches/display cases etc.	74,215	gfa	1.50	111,323		
	Lockers	74,215	sf	1.00	74,215		
	Miscellaneous metals throughout building	74,215	sf	1.25	92,769		
	Miscellaneous sealants throughout building	74,215	sf	1.00	74,215		
	SUBTOTAL					512,084	
	TOTAL - INTERIOR CONSTRUCTION						\$

C2010 STAIR CONSTRUCTION

Metal pan stair; egress stair

24,000.00

flt

3

72,000

13-Mar-17

74,215



Feasibility Design Estimate GFA 74,215

Feasib	ility Desig	n Estimate					GFA	74,215	
CSI CODE		DESCRIPTION	QTY	UNIT	UNIT COST	EST'D COST	SUB TOTAL	TOTAL COST	
NEW	SCHOO	L AT MURACO ES 5C							
33000		Concrete fill to stairs	3	flt	2,000.00	6,000			
		SUBTOTAL					78,000		
90009	C2020	STAIR FINISHES High performance coating to stairs including all railings etc.	3	flt	3,000.00	9,000			
90006		Rubber tile at stairs - landings	330	sf	12.00	3,960			
90006		Rubber tile at stairs - treads & risers	345	lft	22.00	7,590			
		SUBTOTAL	010			.,	20,550		
		TOTAL - STAIRCASES						\$98,550	
	Сзо	INTERIOR FINISHES							
	C3010	WALL FINISHES Wall finishes SUBTOTAL	74,215	gfa	4.50	333,968	333,968		
	C3020	FLOOR FINISHES		C	7.00	510 505	333,908		
		Floor finishes SUBTOTAL	74,215	sf	7.00	519,505	519,505		
	C3030	CEILING FINISHES Ceiling finishes SUBTOTAL	74,215	sf	6.00	445,290	445,290		
		TOTAL - INTERIOR FINISHES						\$1,298,763	
	D10	CONVEYING SYSTEMS							
93000	D1010	ELEVATOR Passenger elevator; 2 stop, 3500 lbs SUBTOTAL	1	ea	100,000.00	100,000	100,000		
		TOTAL - CONVEYING SYSTEMS						\$100,000	
	D20	PLUMBING							
	D20	PLUMBING, GENERALLY Plumbing allowance SUBTOTAL	74,215	gsf	12.00	890,580	890,580		
		TOTAL - PLUMBING						\$890,580	
	D30	HVAC	7						
		HVAC, GENERALLY							
	- 0~	HVAC complete system	74,215	gsf	38.00	2,820,170			
		SUBTOTAL					2,820,170		
		TOTAL - HVAC						\$2,820,170	
	D40	FIRE PROTECTION	7						
	D40						2,020,170		



Feasibility Design Estimate GFA 74,215

CSI CODE		DESCRIPTION	QTY	UNIT	UNIT COST	EST'D COST	SUB TOTAL	TOTAL COST
NEW S	SCHOOL	AT MURACO ES 5C				<u> </u>	1	
	D40	FIRE PROTECTION, GENERALLY Sprinkler system SUBTOTAL	74,215	gsf	4.50	333,968	333,968	
		TOTAL - FIRE PROTECTION						\$333,9
_								
Ĺ	D50	ELECTRICAL						
	D5010	COMPLETE ELECTRICAL SYSTEM						
		Electrical system; complete	74,215	gsf	34.00	2,523,310		
		SUBTOTAL					2,523,310	
		TOTAL - ELECTRICAL						\$2,523,
Г	E10	EQUIPMENT						
L	E10	EQUIPMENT, GENERALLY						
11500		Gym wall pads	1	ls	10,000.00	10,000		
11500		Basketball backstops; swing up; electric operated	2	ea	9,800.00	19,600		
11500		Gymnasium dividing net; electrically operated	1	loc	45,000.00	45,000		
11500		Volleyball net and standards	1	ea	2,000.00	2,000		
11500		Telescoping bleachers	1	ls	25,000.00	25,000		
11500		Cubicle curtain & track at nurse area	1	loc	500.00	500		
11970		Platform curtains, rigging and controls	1	ls	35,000.00	35,000		
		AV Equipment at Café/Gym/ Learning	•	13	00,000.00	F,F&E		
11400		Food Service equipment	1	ls	225,000.00	225,000		
11500		Allowance for loading dock equipment	1	ls	10,000.00	10,000		
11400		Refrigerator/Freezer			1,000.00	1,000		
11400		Kiln	1	ea				
10999		Electrically operated projection screens in gym &	1 2	ea loc	3,000.00 10,000.00	3,000 20,000		
		cafeteria AV Equipment (including Smartboards, Projectors, LED monitors, Digital information displays etc.)				FF+E		
		SUBTOTAL					396,100	
		TOTAL - EQUIPMENT						\$396,
ſ	E20	FURNISHINGS						
	Feers							
	E2010	FIXED FURNISHINGS Entry mats & frames - recessed with carpet/rubber strips	100	sf	45.00	4,500		
		Manual operated roller shades	13,538	sf	6.00	81,228		
		Counters, base cabinets, tall storage in classrooms and other rooms	74,215	gfa	4.00	296,860		
		SUBTOTAL					382,588	
	E2020	MOVABLE FURNISHINGS All movable furnishings to be provided and installed by owner						
		SUBTOTAL					NIC	



Winchester Schools NEW MURACO + LYNCH COMBINED Winchester, MA

Feasibility Design Estimate

Winchester, MA

_							
CSI				UNIT	EST'D	SUB	TOTAL
CODE	DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST

NEW SCHOOL A	MURACO	ES 5C
--------------	--------	-------

TOTAL - SELECTIVE BUILDING DEMOLITION

	TOTAL - FURNISHINGS	
F10	SPECIAL CONSTRUCTION	
F10	SPECIAL CONSTRUCTION	
	No Work in this section	
	SUBTOTAL	
	TOTAL - SPECIAL CONSTRUCTION	
F20	SELECTIVE BUILDING DEMOLITION	
F2010	D BUILDING ELEMENTS DEMOLITION	
	SUBTOTAL	_
	JODIOIAL	_
F202	O HAZARDOUS COMPONENTS ABATEMENT	
	None Included	
	SUBTOTAL	
	DODIGINE	

13-Mar-17

74,215



Winchester, MA

Feasibility Design Estimate GFA 85,455

		CONSTRUCTI	ON COST SUMM	ARY					
	BUILDING		SUB-TOTAL	TOTAL	\$/SF	%			
NEW SC	HOOL A	T LYNCH ES 5C							
A10		DATIONS							
	A1010	Standard Foundations	\$483,746						
	A1020	Special Foundations	\$0						
	A1030	Lowest Floor Construction	\$620,592	\$1,104,338	\$12.92	5.3%			
A20	BASEM	IENT CONSTRUCTION							
	A2010	Basement Excavation	\$0						
	A2020	Basement Walls	\$0	\$0	\$0.00	0.0%			
B10	SUPER	STRUCTURE							
	B1010	Upper Floor Construction	\$1,527,694						
	B1020	Roof Construction	\$1,429,294	\$2,956,988	\$34.60	14.3%			
B20	EXTER	IOR CLOSURE							
5=0	B2010	Exterior Walls	\$1,442,406						
	B2020	Windows	\$1,202,011						
	B2030	Exterior Doors	\$43,040	\$2,687,457	\$31.45	13.0%			
В30	o ROOFING								
200	B3010	Roof Coverings	\$1,181,145						
	B3020	Roof Openings	\$5,000	\$1,186,145	\$13.88	5.7%			
C10	INTER	IOR CONSTRUCTION							
010	C1010	Partitions	\$1,709,100						
	C1020	Interior Doors	\$427,275						
	C1030	Specialties/Millwork	\$589,640	\$2,726,015	\$31.90	13.1%			
C20	STAIR	CASES							
0_0	C2010	Stair Construction	\$78,000						
	C2020	Stair Finishes	\$20,550	\$98,550	\$1.15	0.5%			
С30	INTER	IOR FINISHES							
2,33	C3010	Wall Finishes	\$384,548						
	C3020	Floor Finishes	\$598,185						
	C3030	Ceiling Finishes	\$512,730	\$1,495,463	\$17.50	7.2%			
D10	CONVE	YING SYSTEMS							
210	D1010	Elevator	\$100,000	\$100,000	\$1.17	0.5%			
	D1010	Lioratoi	\$100,000	ΨΙΟΟ,ΟΟΟ	Ų1.11	0.070			
D20	PLUMI		01.007.100	.	010.00	4.007			
	D20	Plumbing	\$1,025,460	\$1,025,460	\$12.00	4.9%			



 $Winchester,\,MA$

Feasibility Design Estimate GFA 85,455

		CONSTRUCTION	COST SUMM	IARY		
	BUILDING		$SUB ext{-}TOTAL$	TOTAL	\$/SF	%
EW SC	HOOL A	Γ LYNCH ES 5C				
D30	HVAC					
	D30	HVAC	\$3,247,290	\$3,247,290	\$38.00	15.7%
D40	FIRE P	ROTECTION				
	D40	Fire Protection	\$384,548	\$384,548	\$4.50	1.9%
D50	ELECT	RICAL				
	D5010	Complete System	\$2,905,470	\$2,905,470	\$34.00	14.0%
E10	EQUIP	MENT				
	E10	Equipment	\$396,100	\$396,100	\$4.64	1.9%
E20	FURNIS	SHINGS				
	E2010	Fixed Furnishings	\$422,808			
	E2020	Movable Furnishings	NIC	\$422,808	\$4.95	2.0%
F10	SPECIA	AL CONSTRUCTION				
	F10	Special Construction	\$0	\$0	\$0.00	0.0%
F20	HAZMA	AT REMOVALS				
	F2010	Building Elements Demolition	\$0			
	F2020	Hazardous Components Abatement	\$0	\$0	\$0.00	0.0%
TOTA	I DIRF	CT COST (Trade Costs)		\$20,736,632	\$242.66	100.0%



3

5

10

11

12

25

44 45

46

47

48 49 Winchester Schools NEW MURACO + LYNCH COMBINED

NEW MURACO + LYNCH COMBINED
Winchester, MA

Feasibility Design Estimate GFA 85,455

CSI				UNIT	EST'D	SUB	TOTAL
CODE	DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST

NEW SCHOOL AT LYNCH ES 5C

GROSS FLOOR AREA CALCULATION

First Floor 44,442 Second Floor 41,013

1,221

TOTAL GROSS FLOOR AREA (GFA) 85,455 sf

cy

20.00

24,420

A10 FOUNDATIONS

Excavation

A1010 STANDARD FOUNDATIONS Strip footings - 2'-0" x 1'-0"

Store on site for reuse	1,221	cy	14.00	17,094	
Backfill with existing fill	1,136	cy	16.00	18,176	
Remove surplus fill off site	85	cy	25.00	2,125	
Formwork	2,198	sf	12.00	26,376	
Re-bar, 10#/lf	10,990	lbs	1.20	13,188	
Concrete material; 3,000 psi	85	cy	125.00	10,625	
Placing concrete	85	cy	55.00	4,675	
Foundation walls at exterior - 14" thick					
Formwork	8,792	sf	14.00	123,088	
Re-bar, 4.5#/sf	19,782	lbs	1.20	23,738	
Concrete material; 4,000 psi	200	cy	135.00	27,000	
Placing concrete	200	cy	65.00	13,000	
Dampproofing foundation wall and footing	6,594	sf	1.90	NIC	
Insulation to foundation walls; 2" thick	4,396	sf	2.50	10,990	
Form shelf	1,099	lf	8.00	8,792	
Column footings, typical, 6' x 6' x 2'-0"					
Excavation	611	cy	20.00	12,220	
Store on site for reuse	611	cy	14.00	8,554	
Backfill with new fill	465	cy	16.00	7,440	
Remove surplus fill off site	146	cy	20.00	2,920	
Formwork	2,496	sf	11.00	27,456	
Re-bar	29,120	lbs	1.20	34,944	
Concrete material; 3,000 psi	146	cy	125.00	18,250	
Placing concrete	146	cy	55.00	8,030	
Set anchor bolts grout plates	52	ea	150.00	7,800	
<u>Interior pilasters</u>					
Formwork	1,523	sf	11.00	16,753	
Re-bar	9,360	lbs	1.20	11,232	
Concrete material; 3,000 psi	27	cy	125.00	3,375	
Placing concrete	27	cy	55.00	1,485	
SUBTOTAL					

A1020 SPECIAL FOUNDATIONS

No Work in this section

SUBTOTAL

A1030 LOWEST FLOOR CONSTRUCTION

483,746



Winchester, MA

Feasibility Design Estimate GFA 85,455

CSI				UNIT	EST'D	SUB	TOTAL
CODE	DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST
NEW S	SCHOOL AT LYNCH ES 5C	 				I	
	New Slab on grade, 5" thick						
	Structural gravel fill, 8"	1,098	cy	30.00	32,940		
	Base course, 8" gravel	1,098	cy	40.00	43,920		
	Rigid insulation	44,442	sf	2.25	99,995		
	Vapor barrier	44,442	sf	1.00	44,442		
	Mesh reinforcing 15% lap	51,108	sf	0.80	40,886		
	Concrete - 5" thick	726	cy	125.00	90,750		
	Placing concrete	726	cy	45.00	32,670		
	Finishing and curing concrete	44,442	sf	4.00	177,768		
	Control joints - saw cut	44,442	sf	0.50	22,221		
	Miscellaneous						
	Elevator pit	1	ea	30,000.00	30,000		
	Dewatering	1	ea	5,000.00	5,000		
	SUBTOTAL					620,592	
	TOTAL - FOUNDATIONS						\$1,104,33
L							

A2010 BASEMENT EXCAVATION

No items in this section

SUBTOTAL

A2020 BASEMENT WALLS

No items in this section

SUBTOTAL

TOTAL - BASEMENT CONSTRUCTION

В10	SUPERSTRUCTURE					
		13	lbs/sf			
B1010	FLOOR CONSTRUCTION	556	tns			
	Floor Structure - Steel:					
	Steel beams and columns; 13/SF	267	tns	3,500.00	934,500	
	Shear studs	8,203	ea	2.50	20,508	
	Floor Structure					
	2" Metal floor Deck	41,013	sf	4.20	172,255	
	WWF reinforcement	47,165	sf	0.80	37,732	
	Concrete Fill to metal deck; 5" normal weight	654	cy	125.00	81,750	
	Place and finish concrete	41,013	sf	2.00	82,026	
	Misc. perimeter angles	1,099	lf	25.00	27,475	
	<u>Miscellaneous</u>					
	Barrier one at slab	654	cy	65.00	42,510	
	Fire proofing to columns and beams	41,013	sf	2.90	118,938	
	Fire stopping floors	2	flrs	5,000.00	10,000	
	SUBTOTAL					1,527,694



Feasibility Design Estimate

Winchester, MA

CSI				UNIT	EST'D	SUB	TOTAL
CODE	DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST

NEW SCHOO	L AT LYNCH ES 5C						
Propo	ROOF CONSTRUCTION						
Б1020	Roof Structure - Steel:						
	Steel beams/Joists; 13#/SF	289	tns	3,800.00	1,098,200		
	Roof Structure	209	uis	3,000.00	1,036,200		
	1-1/2" Metal floor Deck @ roof	44 449	sf	3.00	133,326		
	Miscellaneous	44,442	51	3.00	133,320		
	Roof screen framing - allow		ls	20,000.00	20,000		
	Fire proofing to columns, beams and deck	1	sf	4.00	177,768		
	SUBTOTAL	44,442	31	4.00	177,708	1,429,294	
	SOBIOTAL					1,423,234	
	TOTAL - SUPERSTRUCTURE						\$2,956,98
B20	EXTERIOR CLOSURE						
B2010	EXTERIOR WALLS; 60% solid/40% glass Interior skin	19,123	sf				
	6" metal stud backup	19,123	sf	7.50	143,423		
	Batt insulation in stud	19,123	sf	2.25	43,027		
	2 1/2" Rigid Insulation	19,123	sf	3.00	57,369		
	Air barrier	19,123	sf	6.00	114,738		
	Air barrier/flashing at windows	4,207	lf	7.00	29,449		
	Gypsum Sheathing	19,123	sf	2.75	52,588		
	Drywall lining to interior face of stud backup	19,123	sf	3.00	57,369		
	Exterior skin						
	Brick veneer; 75% of exterior wall	14,342	sf	35.00	501,970		
	Metal panels; 25% of exterior wall	4,781	sf	60.00	286,860		
	<u>Miscellaneous</u>						
	Roof screens - allow	1	ls	60,000.00	60,000		
	Staging to exterior wall	31,871	sf	3.00	95,613		
	SUBTOTAL					1,442,406	
B2020	WINDOWS	12,748	sf		•		
	Premium for sunscreen and light shelf elements	1	ls	a = - :	NIC		
	Windows/storefront	12,748	sf	90.00	1,147,320		
	Backer rod & double sealant	4,207	lf	9.00	37,863		
	Wood blocking at openings	4,207	lf	4.00	16,828		
	SUBTOTAL					1,202,011	
B2030	EXTERIOR DOORS						
	Glazed entrance doors including frame and hardware; double door at corridor exit	4	pr	8,000.00	32,000		
	Other doors	1	ls	10,000.00	10,000		
	Backer rod & double sealant	80	lf	9.00	720		
	Wood blocking at openings	80	lf	4.00	320		
	SUBTOTAL					43,040	
	TOTAL - EXTERIOR CLOSURE						\$2,687,4

13-Mar-17

85,455



196

55100

33000

Winchester Schools NEW MURACO + LYNCH COMBINED

Feasibility Design Estimate

Winchester, MA

UNIT EST'D SUB TOTAL CODE DESCRIPTION QTYUNIT costcostTOTAL COST

Взо	ROOFING						
B3010	ROOF COVERINGS Flat roofing						
	PVC roof membrane fully adhered	44,442	sf	14.00	622,188		
	Insulation	44,442	sf	7.00	311,094		
	1/2" dens-deck protection board	44,442	sf	2.00	88,884		
	Reinforced vapor barrier	44,442	sf	1.50	66,663		
	Rough blocking	4,396	lf	6.00	26,376		
	Miscellaneous Roofing						
	Roof screens - allow				NIC		
	Roof fascia/cornice	1,099	lf	60.00	65,940		
	SUBTOTAL					1,181,145	
Ranan	ROOF OPENINGS						
23020	Skylights, allow				NIC		
	Roof hatch	1	ea	5,000.00	5,000		
	SUBTOTAL					5,000	
	TOTAL - ROOFING						
	TOTAL - ROOFING						
C10	INTERIOR CONSTRUCTION						
C1010	PARTITIONS						
	Allowance for interior walls/glazed partitions etc.	85,455	gfa	20.00	1,709,100		
	SUBTOTAL					1,709,100	
C1020	INTERIOR DOORS						
01020	Interior doors, frames and hardware	85,455	gfa	5.00	427,275		
	SUBTOTAL					427,275	
C1000	CDECIALTIES / MILLWODY						
C1030	SPECIALTIES / MILLWORK Marker boards/tackboards in classroom	85,455	gfa	1.15	98,273		
			_				
	Toilet partitions and accessories	85,455	gfa	0.75	64,091		
	Room Signs	85,455	gfa	0.25	21,364		
	Wood paneling/benches/display cases etc. Lockers	85,455	gfa	1.50 1.00	128,183		
		85,455	sf		85,455		
	Miscellaneous metals throughout building Miscellaneous sealants throughout building	85,455	sf sf	1.25 1.00	106,819 85,455		
	SUBTOTAL	85,455	51	1.00	65,455	589,640	
						000,010	
	TOTAL - INTERIOR CONSTRUCTION						

Metal pan stair; egress stair

Concrete fill to stairs

3

3

flt

flt

24,000.00

2,000.00

72,000

6,000

13-Mar-17

85,455



Feasibility Design Estimate GFA 85,455

	CSI		DECOMPTION	OTTV	TINITE.	UNIT	EST'D	SUB	TOTAL
	CODE		DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST
	NEW	SCHOOL	L AT LYNCH ES 5C						
198			SUBTOTAL					78,000	
199 200		Casas	OTA ID EINIGHEG						
201	90009	C2020	STAIR FINISHES High performance coating to stairs including all	9	flt	3,000.00	9,000		
			railings etc.	3	110	3,000.00	3,000		
202	90006		Rubber tile at stairs - landings	330	sf	12.00	3,960		
203	90006		Rubber tile at stairs - treads & risers		lft	22.00	7,590		
204	30000			345	ш	22.00	7,390	00.550	
205			SUBTOTAL					20,550	
206			TOTAL - STAIRCASES						\$98,550
207									+ 7 - 700 -
208									
209		Сзо	INTERIOR FINISHES						
210 211		Cana	MALL EINIGHES						
212		C3010	WALL FINISHES Wall finishes	85,455	gfa	4.50	384,548		
213			SUBTOTAL	05,455	gru	4.50	304,340	204 540	
214			SUBTOTAL					384,548	
215		Canan	FLOOR FINISHES						
216		03020	Floor finishes	85,455	sf	7.00	598,185		
217			SUBTOTAL	-0,400			,	598,185	
218			SODIOTAL					330,163	
219		C3030	CEILING FINISHES						
220			Ceiling finishes	85,455	sf	6.00	512,730		
221			SUBTOTAL					512,730	
222									
223			TOTAL - INTERIOR FINISHES						\$1,495,463
224 225									
226		D10	CONVEYING SYSTEMS	7					
227				_					
228	00000	D1010	ELEVATOR			400 000 00	400.000		
229	93000		Passenger elevator; 2 stop, 3500 lbs	1	ea	100,000.00	100,000		
230 231			SUBTOTAL					100,000	
232			TOTAL - CONVEYING SYSTEMS						\$100,000
233									
234				7					
235 236		D20	PLUMBING						
237		D20	PLUMBING, GENERALLY						
238			Plumbing allowance	85,455	gsf	12.00	1,025,460		
239			SUBTOTAL					1,025,460	
240									
241			TOTAL - PLUMBING						\$1,025,460
242 243									
244		D30	HVAC	7					
245				_					
246		D30	HVAC, GENERALLY						
247			HVAC complete system	85,455	gsf	38.00	3,247,290		
248			SUBTOTAL					3,247,290	
249 250			TOTAL - HVAC						\$3,247,290
251		<u></u>	1011111 117110						ΨJ,=4/,=90
252				_					
253 254		D40	FIRE PROTECTION						
20 T									

D40 FIRE PROTECTION, GENERALLY

254 255



Feasibility Design Estimate GFA 85,455

CSI CODE		DESCRIPTION	QTY	UNIT	UNIT COST	EST'D COST	SUB TOTAL	TOTAL COST
NEW	SCHOOL	L AT LYNCH ES 5C			<u>l</u>			
		Sprinkler system	85,455	gsf	4.50	384,548		
		SUBTOTAL	07100	Ö			384,548	
							,	
		TOTAL - FIRE PROTECTION						\$384,54
	D	EL ECCENICA I						
	D50	ELECTRICAL						
	D5010	COMPLETE ELECTRICAL SYSTEM						
		Electrical system; complete	85,455	gsf	34.00	2,905,470		
		SUBTOTAL					2,905,470	
		TOTAL - ELECTRICAL						\$2,905,47
								. ,, 0, 1,
	E10	EQUIPMENT						
	E10	EQUIPMENT, GENERALLY						
11500	LIO	Gym wall pads	1	ls	10,000.00	10,000		
11500		Basketball backstops; swing up; electric operated	2	ea	9,800.00	19,600		
11500		Gymnasium dividing net; electrically operated	1	loc	45,000.00	45,000		
11500		Volleyball net and standards	1	ea	2,000.00	2,000		
11500		Telescoping bleachers			25,000.00	25,000		
11500			1	ls				
		Cubicle curtain & track at nurse area	1	loc	500.00	500		
11970		Platform curtains, rigging and controls	1	ls	35,000.00	35,000		
		AV Equipment at Café/Gym/ Learning				F,F&E		
11400		Food Service equipment	1	ls	225,000.00	225,000		
11500		Allowance for loading dock equipment	1	ls	10,000.00	10,000		
11400		Refrigerator/Freezer	1	ea	1,000.00	1,000		
11400		Kiln	1	ea	3,000.00	3,000		
10999		Electrically operated projection screens in gym $\&$ cafeteria	2	loc	10,000.00	20,000		
		AV Equipment (including Smartboards, Projectors, LED monitors, Digital information displays etc.)				FF+E		
		SUBTOTAL					396,100	
		TOTAL - EQUIPMENT						\$396,10
	E20	FURNISHINGS						
	E2010	FIXED FURNISHINGS Entry mats & frames - recessed with carpet/rubber strips	100	sf	45.00	4,500		
		Manual operated roller shades	12,748	sf	6.00	76,488		
		Counters, base cabinets, tall storage in classrooms and other rooms	85,455	gfa	4.00	341,820		
		SUBTOTAL					422,808	
	E2020	MOVABLE FURNISHINGS All movable furnishings to be provided and installed by owner						
		SUBTOTAL					NIC	



310 311

312

313

314

319 320

321

322 323

324

325

326

Winchester Schools NEW MURACO + LYNCH COMBINED Winchester MA

Feasibility Design Estimate

Winchester, MA

CSI				UNIT	EST'D	SUB	TOTAL
CODE	DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST

NEW SCHOOL AT LYNCH ES 5C

F10 SPECIAL CONSTRUCTION

F10 SPECIAL CONSTRUCTION
No Work in this section
SUBTOTAL

TOTAL - SPECIAL CONSTRUCTION

F20 SELECTIVE BUILDING DEMOLITION

F2010 BUILDING ELEMENTS DEMOLITION

SUBTOTAL

F2020 HAZARDOUS COMPONENTS ABATEMENT

None Included SUBTOTAL

TOTAL - SELECTIVE BUILDING DEMOLITION

13-Mar-17

85,455



NEW MURACO + LYNCH COMBINED
Winghoston MA

Feasibility Design Estimate

CSI				UNIT	EST'D	SUB	TOTAL
CODE	DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST

SITEWORK NEW LYNCH SCHOOL

2		G	SITEWORK					
3 4 5		G10	SITE PREPARATION & DEMOLITION Site Demolitions and Relocations					
6	024100		Site construction fence/barricades; visual screen; includes moving for phasing	2,000	lf	15.00	30,000	
7	02200		Demolish existing paving	100,000	sf	1.00	100,000	
8	02200		Demolish soccer field	1	loc	10,000	10,000	
9	02200		Site clearing/grubbing	1	ls	30,000.00	30,000	
10	02200		Miscellaneous demolition allowance including existing utilities	1	ls	50,000	50,000	
11			Site Earthwork					
12	310000		Construction entrances/wheel washes (allowance)	2	loc	12,000.00	24,000	
13	311000		Strip topsoil, store; assume 6"	3,704	cy	8.00	29,632	
14	310000		Cut/fill	16,667	cy	6.00	100,002	
15	310000		Export excess material - assumed balanced site					
16	310000		Fine grading	33,333	sy	0.75	25,000	
17	312500		Silt fence/erosion control (allowance)	2,000	lf	12.00	24,000	
18	312500		Erosion Control monitoring & maintenance	1	ls	30,000.00	30,000	
19			Temporary Work/Phasing					
20	310000		Contractor Parking; includes demolition	15,397	sf	3.50	53,890	
21	310000		Temporary Parking; includes demolition	19,142	sf	3.30	63,169	
22	310000		Construction access road; includes demolition	29,123	sf	3.00	87,369	
23	310000		Dust control/Mobilization costs	1	ls	50,000.00	50,000	
24								
25	311000		Strip topsoil, store; assume 6"	3,704	cy	8.00	29,632	
26			Hazardous Waste Remediation	• • • • • • • • • • • • • • • • • • • •	J			
27			SUBTOTAL					736,694
28								
29		G20	SITE IMPROVEMENTS					
30								
31			Roadways and Parking Lots					
32			Bituminous concrete paving	62,551	sf		-	
33	320000		gravel base; 12" thick	2,317	cy	35.00	81,095	
34 35	320000 320000		bituminous concrete; 4" thick	6,950	sy	26.00	180,700	
36	320000		6"x18" granite curb Premium for radius curbs	3,811	lf ls	35.00	133,385 25,000	
37	320000		Road markings	1	ls	25,000.00 15.000.00	15,000	
38	321724		Signage	1	ls	20,000.00	20,000	
39			Fire lane	•	15	20,000.00	20,000	
40			Bituminous concrete paving	23,260	sf		_	
41	320000		gravel base; 18" thick	1,292	сy	35.00	45,220	
42	320000		bituminous concrete; 4" thick	2,584	sy	26.00	67,184	
43	320000		6"x18" granite curb	1,806	lf	35.00	63,210	
44			Pedestrian paving: allowance of 10,000 sf					
45			Concrete paving broom finish	10,000	sf		-	
46	320000		gravel base; 8" thick	248	cy	35.00	8,680	
47	033000		concrete paving; 4" thick	10,000	sf	6.50	65,000	
48			Concrete pavers; allowance of 5,000 sf					
49 50	320000		Concrete pavers	5,000	sf	95.00	- 975	
30	320000		sand bedding; 1" thick	15	cy	25.00	375	



Feasibility Design Estimate

CSI					UNIT	EST'D	SUB	TOTAL
CODE		DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST
SITE	WORK N	NEW LYNCH SCHOOL		ı	1			
033000	0	Precast concrete pavers	5,000	sf	14.00	70,000		
320000	0	gravel base; 8" thick	124	сy	35.00	4,340		
033000	0	concrete base; 4" thick	5,000	sf	5.00	25,000		
		Site Improvements						
129300)	Bicycle racks - Allowance	20	ea	1,000.00	20,000		
129300)	Flag pole	1	loc	7,500.00	7,500		
129300)	Ornamental trash/recycling receptacles	8	loc	1,400.00	11,200		
129300)	Bollards	10	ea	850.00	8,500		
129300)	Bollards; moveable	4	loc	1,500.00	6,000		
129300)	Dumpster enclosure and pad	1	ls	15,000.00	15,000		
129300)	Retaining wall	381	lf	180.00	68,580		
129300)	Fence along perimeter	1,200	lf	90.00	108,000		
129300)	New site entrance sign	1	ls	25,000.00	25,000		
129300)	Miscellaneous site improvements	1	ls	100,000.00	100,000		
		Soccer Field - assumed grass			,	,		
329210)	Grass field including drainage etc.	71,500	sf	2.00	143,000		
116800		Soccer Goal	2	loc	4,000.00	8,000		
116800		Benches - allowance	2	loc	2,250.00	4,500		
323114		Vinyl CL Fencing 4'	961	lf	55.00	52,855		
323114		Gate, single	2	ea	1,200.00	2,400		
00000		Landscaping & Plantings:						
329900)	Spread existing amended topsoil @ seeded areas.	3,704	cy	22.00	81,488		
329900)	New seeded areas	200,949	sf	0.25	50,237		
02830		Planting allowance	1	ls	150,000.00	150,000		
		SUBTOTAL					1,666,449	
	Can	CHAIL MECHANICAL LINE INTEC						
	G30	CIVIL MECHANICAL UTILITIES						
	331000	WATER UTILITIES						
312003	3	New fire DI piping; 8"	400	lf	90.00	36,000		
312003	3	New DI piping; 6"	400	lf	75.00	30,000		
312003	3	New fire hydrant	. 2	loc	2,600.00	5,200		
312003	3	FD connection	1	loc	2,000.00	2,000		
312003	3	Gate valves	4	loc	750.00	3,000		
			•					
	333000	SANITARY SEWERAGE UTILITIES						
333000)	Sanitary sewer						
333000		6" PVC Sanitary sewer	400	lf	45.00	18,000		
333000	0	SMH	4	ea	4,000.00	16,000		
333000	0	Grease trap; 9,000 Gal	1	loc	15,000.00	15,000		
	334000	STORM DRAINAGE UTILITIES						
312003		Allowance for storm water management		sf	5.00	387,755		
-12000		Anowance for Storm water management	77,551	51	3.00	307,733		
312003	3	Gas service						
312003		E&B trench for new lines, pipe and install by utilities						
312003	3	New gas service	400	lf	25.00	10,000		
		SUBTOTAL	-				522,955	
	C 4.5	ELECTRICAL LIPHTITIES						
016100	G40	ELECTRICAL UTILITIES Electric handhole	2	ea	1,500.00	3,000		
016100				lf	120.00	48,000		
0.0100		Primary ductbank	400	11	120.00	40,000		




13-Mar-17

Feasibility Design Estimate

	CSI				UNIT	EST'D	SUB	TOTAL
	CODE	DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST
	SITEV	VORK NEW LYNCH SCHOOL						
103	016100	Transformer by Utility Company	1	ea		NIC		
104	016100	Transformer pad	1	ea	2,000.00	2,000		
105	016100	Secondary service						
106	016100	Ductbank	50	lf	500.00	25,000		
107	016100	Emergency service						
108	016100	Ductbank	100	lf	150.00	15,000		
109	016100	Generator pad	1	ea	1,500.00	1,500		
110	016100	Site lighting						
111	016100	Allowance for site lighting	1	ls	100,000.00	100,000		
112	016100	Allowance for sports lighting				NIC		
113	016100	Site communications and security						
114	016100	Site security	1	ls	15,000.00	15,000		
115	016100	Communication riser pole	1	ea	2,500.00	2,500		
116	016100	Telecom handhole	2	ea	1,500.00	3,000		
117	016100	Ductbank	400	lf	130.00	52,000		
118		SUBTOTAL					267,000	
119								
120	Ī	SUBTOTAL - SITE DEVELOPMENT LYNCH SCHOOL						\$2.102.008

SUBTOTAL - SITE DEVELOPMENT LYNCH SCHOOL

\$3,193,098



PM&C LLC 20 Downer Avenue, Suite 1c Hingham, MA 02043 (T) 781-740-8007 (F) 781-740-1012

Feasibility Design Estimate

Winchester Schools New Team Rooms

Winchester, MA

Prepared for:

Flansburgh Architects

March 30, 2017



Winchester Schools

New Team Rooms Winchester, MA

Feasibility Design Estimate

30-Mar-17

MAIN CONSTRUCTION COST SUMMARY

	Construction Start	Gross Floor Area	\$/sf	Estimated Construction Cost
RENOVATION TO McCALL MS - N	IEW TEAM R	OOMS		
New Team Rooms + Restrooms		1,740	\$205.82	\$358,130
SUB-TOTAL	Jun-18	1,740	\$205.82	\$358,130
ESCALATION TO START - (assumed 4% PA)	5.7%			\$20,413
DESIGN AND PRICING CONTINGENCY	15%			\$53,720
SUB-TOTAL		1,740	\$248.43	\$432,263
GENERAL CONDITIONS				\$64,839
BONDS	1.00%			\$4,323
INSURANCE	2.00%			\$8,645
PERMIT				NIC
OVERHEAD AND FEE	10.00%			\$43,226
OWNER CONTINGENCY				By Owner
TOTAL OF ALL CONSTRUCTION	Jun-18	1,740	\$317.99	\$553,296

This Feasibility Design cost estimate was produced from preliminary drawings prepared by Flansburgh Architects Inc. and their design team dated February 2, 2017. Design and engineering changes occurring subsequent to the issue of these documents have not been incorporated in this estimate.

This estimate includes all direct construction costs, general contractor's overhead, fee and design contingency. Cost escalation assumes start dates indicated

Bidding conditions are expected to be public bidding under Chapter 149 of the Massachusetts General Laws to pre-qualified general contractors, and pre-qualified sub-contractors, open specifications for materials and manufactures.

The estimate is based on prevailing wage rates for construction in this market and represents a reasonable opinion of cost. It is not a prediction of the successful bid from a contractor as bids will vary due to fluctuating market conditions, errors and omissions, proprietary specifications, lack or surplus of bidders, perception of risk, etc. Consequently the estimate is expected to fall within the range of bids from a number of competitive contractors or subcontractors, however we do not warrant that bids or negotiated prices will not vary from the final construction cost estimate.

ITEMS NOT CONSIDERED IN THIS ESTIMATE



Winchester Schools

New Team Rooms 30-Mar-17

Winchester, MA

Feasibility Design Estimate

Items not included in this estimate are:

Land acquisition, feasibility, and financing costs

All professional fees and insurance

Site or existing conditions surveys investigations costs, including to determine subsoil conditions $% \left(1\right) =\left(1\right) \left(

All Furnishings, Fixtures and Equipment

Items identified in the design as Not In Contract (NIC)

Items identified in the design as by others

Owner supplied and/or installed items as indicated in the estimate

Utility company back charges, including work required off-site

Work to City streets and sidewalks, (except as noted in this estimate)

Construction contingency



Winchester Schools New Team Rooms Winchester, MA 30-Mar-17

Feasibility Design Estimate GFA 1,740

	D1111		ON COST SUMMA		↑ /GE	04
NOVA	BUILDING TION TO	O McCALL MS - NEW TEAM ROOMS	SUB-TOTAL	TOTAL	\$/SF	%
A10		OATIONS				
7110	A1010	Standard Foundations	\$6,800			
	A1020	Special Foundations	\$0			
	A1030	Lowest Floor Construction	\$11,420	\$18,220	\$10.47	5.1%
B10	SUPER	STRUCTURE				
	B1010	Upper Floor Construction	\$0			
	B1020	Roof Construction	\$0	\$0	\$0.00	0.0%
B20	EXTER	IOR CLOSURE				
	B2010	Exterior Walls	\$7,000			
	B2020	Windows/Curtainwall	\$0			
	B2030	Exterior Doors	\$4,600	\$11,600	\$6.67	3.2%
Взо	ROOFI	NG				
	B3010	Roof Coverings	\$4,000			
	B3020	Roof Openings	\$0	\$4,000	\$2.30	1.1%
C10	INTER	OR CONSTRUCTION				
	C1010	Partitions	\$89,080			
	C1020	Interior Doors	\$8,200			
	C1030	Specialties/Millwork	\$80,450	\$177,730	\$102.14	49.6%
C20	STAIR	CASES				
	C2010	Stair Construction	\$0			
	C2020	Stair Finishes	\$0	\$0	\$0.00	0.0%
С30	INTER	OR FINISHES				
	C3010	Wall Finishes	\$7,220			
	C3020	Floor Finishes	\$22,620			
	C3030	Ceiling Finishes	\$12,180	\$42,020	\$24.15	11.7%
D10	CONVE	YING SYSTEMS				
	D1010	Elevator	\$0	\$0	\$0.00	0.0%
D20	PLUME	BING				
	D20	Plumbing	\$28,000	\$28,000	\$16.09	7.8%
D30	HVAC					
	D30	HVAC	\$43,500	\$43,500	\$25.00	12.1%
D40	FIRE P	ROTECTION				
-4-	D40	Fire Protection				



Winchester Schools New Team Rooms Winchester, MA 30-Mar-17

Feasibility Design Estimate GFA 1,740

	BUILDING	CONSTRUCTION SYSTEM	SUB-TOTAL	TOTAL	\$/SF	%	
ENOVA	TION TO	O McCALL MS - NEW TEAM ROOMS					
D50	ELECTI	RICAL					
	D5010	Electrical Systems	\$26,100	\$26,100	\$15.00	7.3%	
E10	EQUIP	MENT					
	E10	Equipment	\$0	\$0	\$0.00	0.0%	
E20	FURNIS	SHINGS					
	E2010	Fixed Furnishings	\$0				
	E2020	Movable Furnishings	NIC	\$0	\$0.00	0.0%	
F10	SPECIA	L CONSTRUCTION					
	F10	Special Construction	\$0	\$0	\$0.00	0.0%	
F20	SELEC	TIVE BUILDING DEMOLITION					
	F2010	Building Elements Demolition	\$3,480				
	F2020	Hazardous Components Abatement	\$0	\$3,480	\$2.00	1.0%	
TOTA	L DIRE	CT COST (Trade Costs)		\$358,130	\$205.82	100.0%	



Winchester Schools New Team Rooms

Feasibility Design Estimate

Winchester, MA

30-Mar-17

1,740

GFA

4,600

PMC - Project Management Cost

\$11,600

			UNIT	EST'D	SUB	TOTAL
DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST

RENOVATION TO McCALL MS - NEW TEAM ROOMS

	TOTAL RENOVATED AREA (GFA)				1,740 GS	F	
A10	FOUNDATIONS						
A1010	STANDARD FOUNDATIONS						
	Grading and patching of existing landscape/planting	1	ls	2,000.00	2,000		
	New versalok retaing wall	96	sf	50.00	4,800		
	SUBTOTAL					6,800	
A1020	SPECIAL FOUNDATIONS						
	No work in this section SUBTOTAL						
A1030	LOWEST FLOOR CONSTRUCTION						
	New exterior concrete walkway	160	sf	12.00	1,920		
	Patch existing slab at new bathroom	200	sf	20.00	4,000		
	Trenching and patching existing slab to connect to existing sanitary pipe	50	lf	110.00	5,500		
	SUBTOTAL					11,420	
	TOTAL - FOUNDATIONS						\$18
B10	SUPERSTRUCTURE						
БІО	SCIERSTRUCTURE						
B1010	FLOOR CONSTRUCTION						
	SUBTOTAL					-	
B1020	ROOF CONSTRUCTION						
	SUBTOTAL					-	
	TOTAL - SUPERSTRUCTURE						
B20	EXTERIOR CLOSURE						
B20	EXTERIOR CLOSURE						
B2010	EXTERIOR WALLS						
	Cut and patch exterior wall for new doors; including new lintels	2	loc	3,500.00	7,000		
	SUBTOTAL					7,000	
B2020	WINDOWS/CURTAINWALL						
	No work assumed to existing exterior						
	SUBTOTAL					-	
B2030	EXTERIOR DOORS						
-00	New HM door, frame and hardware	2	loc	2,300.00	4,600		
					-		

Page 6

Winchester Schools New Team Rooms

SUBTOTAL

TOTAL - EXTERIOR CLOSURE

48

49

50

51 52



New Team Rooms

Winchester, MA

53

54 55

57

61

66

67 68

69

70

80

82

84

85 86

87 88 89

90

93

94 95

97

98 99

100 101 102

103 104

105

30-Mar-17

Feasibility Design Estimate	GFA	1,740

			UNIT	EST'D	SUB	TOTAL
DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST

RENOVATION TO McCALL MS - NEW TEAM ROOMS

Взо ROOFING

B3010 ROOF COVERINGS

Patch roofing for new vents/exhausts 2,000.00 4,000

SUBTOTAL 4,000

B3020 ROOF OPENINGS

No work in this section

SUBTOTAL

TOTAL - ROOFING \$4,000

C10 INTERIOR CONSTRUCTION

C1010 PARTITIONS

Furred GWB walls at exterior 1,000 sf9.00 9,000 New CMU walls at team rooms and toilets 22.00 3,640 $\mathbf{s}\mathbf{f}$ 80,080

SUBTOTAL 89,080

C1020 INTERIOR DOORS

2,500.00 5,000 New egress doors at team rooms 2 ea New doors at toilets 1,600.00 3,200 ea

SUBTOTAL 8,200

C1030 SPECIALTIES / MILLWORK

Toilet accessories 1,555.00 3,110 2 rms Room Signs 150.00 600 loc 4 Team room lockers 200 ea 350.00 70,000 Team room benches 5,000.00 ls 5,000 Miscellaneous sealants 1.00 1,740 1,740 sf

SUBTOTAL 80,450

TOTAL - INTERIOR CONSTRUCTION

\$177,730

C20 STAIRCASES

C2010 STAIR CONSTRUCTION

No work in this section

SUBTOTAL

C2020 STAIR FINISHES

No work in this section

SUBTOTAL

TOTAL - STAIRCASES

INTERIOR FINISHES C30

C3010 WALL FINISHES

3.00 Paint to walls etc. 5,220 1,740 gsf



Winchester Schools New Team Rooms

Winchester, MA

Feasibility Design Estimate GFA 1,740

30-Mar-17

	DESCRIPTION	QTY	UNIT	UNIT COST	EST'D COST	SUB TOTAL	TOTAL COST
		411	01111	2051	CO31	TOTAL	
ENOVATION	N TO McCALL MS - NEW TEAM ROOMS		,	0.000.00			
	Patch/paint existing walls	1	ls	2,000.00	2,000		
	SUBTOTAL					7,220	
C3020	FLOOR FINISHES						
	New epoxy flooring	1,740	sf	11.00	19,140		
	Floor prep	1,740	sf	2.00	3,480		
	SUBTOTAL	<i>,,</i> •				22,620	
C3030	CEILING FINISHES		C	7.00	10.100		
	ACT, 2x2	1,740	sf	7.00	12,180		
	SUBTOTAL					12,180	
	TOTAL - INTERIOR FINISHES						\$42
D10	CONVEYING SYSTEMS						
	No work in this section						
	SUBTOTAL					_	
	SOSTOTILE						
	TOTAL - CONVEYING SYSTEMS						
D20	PLUMBING						
<u> </u>							
D20	PLUMBING, GENERALLY						
	New plumbing fixtures; includes all piping including connection to existing UG sanitary	4	fxt	7,000.00	28,000		
	SUBTOTAL					28,000	
	TOTAL - PLUMBING						\$28
							, ,
D30	HVAC						
D30	HVAC, GENERALLY	4	-r	97.00	40.500		
	HVAC to renovated area	1,740	sf	25.00	43,500	49.500	
	SUBTOTAL					43,500	
	TOTAL - HVAC						\$43
							
D40	FIRE PROTECTION						
-	THE PROPERTY OF THE PROPERTY O						
D40	FIRE PROTECTION, GENERALLY	4 = 40	c.f	9.00	2.400		
	Sprinkler system modifications	1,740	sf	2.00	3,480	0.400	
	SUBTOTAL					3,480	

D50 ELECTRICAL

156

157 158

D5010 COMPLETE ELECTRICAL SYSTEMS



New Team Rooms

30-Mar-17 Winchester Schools

Winchester, MA

206

207

Feasibility Des	sign Estimate					GFA	1
	NIGONARION	om.		UNIT	EST'D	SUB	TOTAL
	DESCRIPTION	QTY	UNIT	COST	COST	TOTAL	COST
RENOVATIO	ON TO McCALL MS - NEW TEAM ROOMS		0	15.00	00.100		
	Lighting, power and Tele/Data modifications	1,740	sf	15.00	26,100		
	SUBTOTAL					26,100	
	TOTAL - ELECTRICAL						\$26,1
E10	EQUIPMENT	Ī					
LIO	EQUII MENT	_					
E10	EQUIPMENT, GENERALLY						
	No work in this section						
	SUBTOTAL					-	
	TOTAL - EQUIPMENT						
E20	FURNISHINGS						
F201	o FIXED FURNISHINGS						
2201	No work in this section						
	SUBTOTAL					-	
_							
E202	O MOVABLE FURNISHINGS						
	All movable furnishings to be provided and installed by owner						
	SUBTOTAL					NIC	
	TOTAL - FURNISHINGS						
F10	SPECIAL CONSTRUCTION						
F10	SPECIAL CONSTRUCTION						
F10	SPECIAL CONSTRUCTION						
	No items in this section						
	SUBTOTAL						
	TOTAL ODECLAS CONCEDICATION						
	TOTAL - SPECIAL CONSTRUCTION						
F20	SELECTIVE BUILDING DEMOLITION						
	- NAME DANCE BY ENTENING DEMOLATION						
F201	o BUILDING ELEMENTS DEMOLITION Missellaneous dama (protestion	1 = 10	afo	2.00	3,480		
	Miscellaneous demo/protection SUBTOTAL	1,740	gfa	2.00	3,460	3,480	
	SODIOTAL					3,400	
F202	O HAZARDOUS COMPONENTS ABATEMENT						
	None Included						
	SUBTOTAL						

\$3,480

TOTAL - SELECTIVE BUILDING DEMOLITION