

**GENERAL** 

Yard number 553014 Delivery date December 2014

Basic functions Damen Offshore Carrier with 5000 ton cable laying installation

₱ 100 A1, Offshore Supply Ship, ₱ LMC, UMS, D.P (A.A.), NAV1, Classification

I.W.S., W.D.L. ECO (B.W.T., G.W., IHM., O.W., P)

Descriptive note "Cable Layer"

Dutch Flag Van Oord

DIMENSIONS

Flag

Owner

DIMENSIONS	
Length overall	122.75 m
Length B.P.P	116.15 m
Beam moulded	27.45 m
Depth main deck at side	9.00 m
Draught (Summer)	5.82 m
Deadweight	8,270 t
Gross Tonnage	9 675 GT

#### TANK CAPACITIES APPROX

Traint ora morneo ra i mora	
Fuel MGO	1.788 m <sup>3</sup>
(incl. settling and day tanks)	
Potable water	187 m <sup>3</sup>
Ballast (sea) water	8,347 m <sup>3</sup>
Ballast (fresh) water	4,544 m <sup>3</sup>
Lubrication oil	32 m <sup>3</sup>
Dirty oil	20 m <sup>3</sup>
Sludge	20 m <sup>3</sup>
Sewage	330 m <sup>3</sup>
Cooling water drain	14 m <sup>3</sup>
Bilge water collecting	62 m <sup>3</sup>
Drain water tanks main deck	2x 32 m <sup>3</sup>

# **PERFORMANCES**

Trial speed at summer draft @4200 kW 11.6 kn

# **PROPULSION SYSTEM**

2 x MAK 8M25 (each 2,560 kWe) & 2 x MAK 6M25 (each 1,912 Main generators

kWe)

2 x 2,100 kW azimuth, diameter 2,650 mm with 4 bladed FPP **Thrusters** 

2 x 1,000 kW tunnel thruster, diameter 2,250 mm with 4 bladed FPP Bow thrusters

1 x 1,000 kW retractable azimuth, diameter 2100 mm with 4 bladed

# NAUTICAL AND COMMUNICATION EQUIPMENT

Radio equipment is according to GMDSS for area A3

#### **AUXILIARY EQUIPMENT**

- 1 diesel generator set, 1500 kVA 1200 kWe @ 60 Hz 1 emergency generator set, 136 kVA – 170 kWe @ 60 Hz 1 thermal water boiler in combination with waste heat
- recovery
- 2 self-cleaning purifier units MGO
- 4 self-cleaning purifier units for LO
- 1 sewage treatment plant
- 1 ballast water treatment plant 750 m³/h 2 fresh water generators
- 2 starling air compressors
- 1 bilge water separator
- 1 NOVEC and water mist firefighting system for engine
- 4 ballast pumps in the cargo area each 1000 m $^3$ /h 4 general service pumps each 100 m $^3$ /h

# **DECK LAY-OUT AND EQUIPMENT**

- 1 knuckle boom 100 ton @ 20 m
- 1 stiff boom crane 4,5 ton @ 20 m
- 1 basket carousel cable laying installation for 5,000 load
- 1 small moonpool (1.5 x 1.3 m)
- 1 large moonpool (5.4 m x 5.4 m)
- 1 support for A-frame

# **DECK EQUIPMENT**

- 1 electric-hydraulic driven bow anchor winches
- 2 electric-hydraulic driven aft mooring winches
- 2 life boats, each 45 persons

### **ACCOMODATION**

For captain, officers, crew, and SPS for a total of 90 persons



# **Offshore Carrier 7500 CLV**



**NEXUS** 



