

OPERATION MANUAL

Concealed Ducted Split Series 18-60 MBH



50 Hz

Ducted Split With Hermetic Compressor Tropical



TABLE OF CONTENTS

Content	Page No.
About RIC	03
General.....	04
Warranty.....	06
Safety Considerations.....	07
Nomenclature	08
Installation & Commissioning	09
Home Automation System	13
Service Space	14
Electrical Data	15
Supply Air Performance	17
Unit Dimensions	18
Typical Wiring Diagram	20
Trouble Shooting	24
Maintenance	26
Commissioning Report	28



About RIC

Refrigeration Industries & Storage and Oil Services Company, occupies a leading position as one of the largest industrial companies in Kuwait which established in 1973, it plays a proactive role in providing various services and diverse activities such as manufacturing, storage, and oil services to meet the needs of customers both inside and outside Kuwait.

Since its inception, RIC has been committed to excellence and advancing its progress, leading to the establishment of the brand (Coolex) in 1986, a true milestone in the Kuwaiti market as the first in the region in the sector of manufacturing air conditioning systems and cooling solutions.

Furthermore, the company has consistently empowered its workforce, enhanced safety and competitiveness, and utilized innovative technologies to launch new products that meet the needs of various sectors, contributing to expansion and supporting growth and prosperity.

To ensure the highest performance in the future, RIC harnesses its continuous research to enhance efficiency and quality, while continuing its efforts to manufacture products capable of adapting to climate, environmental, and energy challenges.

Facts throughout the years

- 1973 Warehouses were established by Amiri Decree.
- 1979 RIC Constructed the Medical Cold Stores Complex, the world's largest at that time.
- 1980 RIC Air Conditioning manufacturing plant set up in Sulaibya.
- 1981 Production of Package & Mini-Split A/Cs started under York-Gulf.
- 1984 RIC was listed in Kuwait Stock Exchange.
- 1986 COOLEX brand Production Launched.
- 1991 RIC rebuilt the manufacturing plant destroyed during the war.
- 1997 Achieved ISO Certification ISO 9001:1994.
- 2002 ETL Designed testing lab became fully operational.
- 2004 Privatization of RIC.
- 2010 COOLEX becomes the first A/C Unit to Pass MEW's new regulations.
- 2010 RIC Factory Renovation and Expansion into neighboring countries.
- 2012 Achieved UL & AHRI Certification for Coolex Units.
- 2014 Achieved SASO Certification for Concealed Ducted Split Series.
- 2014 Achieved EUROVENT Certification for Air Handling Units AHU.
- 2014 Achieved UL Certification for Air Cooled Chillers.
- 2015 Achieved ISO 17025 Certification for Psychrometric Laboratory.
- 2016 Achieved Energy Efficiency Certification for Concealed Ducted Split Series & Rooftop Package units (Kingdom of Bahrain).
- 2016 Acquisition of Gulf Paramount for Electrical Services Company.
- 2021 Acquisition of Kuwait Pipes Industries & Oil Services factory, resulting in a change of the company's name from Refrigeration Industries & Storage Co. to Refrigeration Industries & Storage and Oil Services Co.

نبذة عن الشركة

تتوأ شركة صناعات التبريد والتخزين والخدمات النطقية مكانة رائدة باعتبارها واحدة من أكبر الشركات الصناعية في دولة الكويت، والتي تأسست عام 1973 لتؤدي دوراً غير استباقي في تقديم خدمات متعددة وأنشطة متنوعة كالصنيع والتخزين والخدمات النطقية لتلبية مختلف احتياجات العملاء داخل الكويت وخارجها.

ومنذ انطلاقة الشركة وهي تعمل على إبراز التميز ومواصلة مسيرة التقدم مما مكنتها من تأسيس العلامة التجارية (كولكس) عام 1986 والتي جاء ميلادها إنجازاً حقيقياً في السوق الكويتي باعتبارها الأولى في المنطقة في قطاع تصنيع أنظمة التكييف وحلول التبريد في الكويت. وعلى صعيد متصل، دأبت الشركة على تمكين قوتها العاملة وتعزيز السلامة والقدرة التنافسية والاستفادة من التقنيات المبتكرة لإطلاق منتجات جديدة تلي مختلف القطاعات وتسهم في تحقيق التوسع والذي من شأنه يدعم النمو والإزدهار.

ولضمان أعلى أداء في المستقبل، تسخر الشركة بعونها المستمرة لتعزيز الكفاءة والجودة كما تواصل جهودها لتصنيع منتجات قادرة على التكيف مع تحديات المناخ والبيئة والطاقة.

حقائق وتواريخ

- 1973 تم إنشاء المستودعات بناء على مرسوم أميري.
- 1979 عهدت وزارة الصحة الكويتية لشركة صناعات التبريد بإنشاء مجمع مستودعات مخازن التبريد الطبية، وقد كان هذا المجمع حينها هو الأضخم من نوعه على مستوى العالم، وقد وصلت تكلفته إلى 12.000.000 دينار كويتي.
- 1980 تم إنشاء مصنع مكيفات الهواء التابع لشركة صناعات التبريد في الصليبية.
- 1981 بدء إنتاج أجهزة التكييف المدمجة والمنفصلة الصغيرة تحت علامة York-Gulf.
- 1984 تم قيد شركة صناعات التبريد في سوق الكويت للأوراق المالية.
- 1986 بدء إنتاج مكيفات علامة كولكس.
- 1991 قامت شركة صناعات التبريد بإعادة بناء مصنعها الذي دمرته الحرب.
- 1997 الحصول على شهادة الأيزو 9001:1994
- 2002 بدء تشغيل مختبر فحص وحدات التكييف (ETL)
- 2004 خصخصة شركة صناعات التبريد.
- 2010 كانت وحدات كولكس أول وحدات تكييف هواء تجتاز اللوائح التي أقرتها (وزارة الكهرباء والماء).
- 2010 تم تجديد مصنع شركة صناعات التبريد وبدء التوسع والتصدير إلى الدول المجاورة.
- 2012 الحصول على شهادة UL و AHRI لأجهزة التكييف كولكس.
- 2014 الحصول على شهادة SASO لأجهزة التكييف المنفصلة.
- 2014 الحصول على شهادة EUROVENT لأجهزة مناولة الهواء.
- 2014 الحصول على شهادة UL لتبريد الهواء الشيلر.
- 2015 الحصول على شهادة الأيزو 17025 ISO لخبتر السيكرومترية.
- 2016 الحصول على شهادة كفاءة الطاقة لأجهزة التكييف المنفصلة و الوحدات المدمجة (مملكة البحرين).
- 2016 الاستحواذ على شركة بارامونت الخليج للخدمات الكهربائية.
- 2021 الاستحواذ على مصنع الشركة الكويتية لصناعة الأنابيب والخدمات النطقية مما أدى على إثره تغيير اسم الشركة من شركة صناعات التبريد والتخزين إلى شركة صناعات التبريد والتخزين والخدمات النطقية.

GENERAL

The following symbols are used to alert you to areas of potential hazard.



A NOTE is used to highlight additional data that may be helpful to you.



A WARNING is used to identify a hazard which could lead to personal death or machine destruction or break down.



A CAUTION is used to identify a hazard which could lead to personal injury and machine damage.

This manual will insure proper operation and ensures a long service life of the unit.



All procedure presented in this manual, like installation, operation and maintenance must be performed by trained and qualified person.



For more information please contact your local COOLEX and service center or refer to COOLEX factory.

DEAR CUSTOMER

Thanks for choosing COOLEX Concealed Ducted Split Air Conditioning Unit. Please take time to go through this manual since it contains valuable information on installation, operation and maintenance of the unit. This will ensure a longer life time for the unit.

Receiving

On arrival, inspect the unit before signing the delivery note. Specify any damage on the delivery note and send a letter of complaint to the last carrier of the goods.

Inspection

Check the shipment received according to the shipment list, to make sure the shipment is complete. After inspecting the unit, protect properly during storage or while moving it to the actual installation site, this step is important to maintain warranty and protect unit against adverse weather, theft or vandalism on job-site.

Damage to Units

Be sure to inspect the unit upon receipt for damage. If the unit has been damaged in transit, file a claim with transportation Company immediately and check your insurance company immediately.

WARRANTY

Refrigeration Industries & Storage Co. warrants this product to be free from defects in factory workmanship and material under normal use and service. And will repair or replace parts proved to have such a defects as per the following:

1. Five years for hermetic compressors
2. One year for all other parts

Time periods are measured from starting date of installation, or three months from date of dispatching, whichever comes first. Unless extended warranty has been agreed as part of the contract.

EXCLUSIONS

The following are not manufacturing defects and not covered by COOLEX warranty:

1. Damage resulting from handling during transportation, transit, installation and servicing of the product by others.
2. Damage or malfunction resulting from abrupt electrical power supply to the unit ($\pm 10\%$ from the rated voltage) and electrical hazards.
3. Damage resulting from a different application that it's designed for.
4. Damage or malfunction resulting from improper supply and return air distribution from and to the product.
5. Damage resulting from malfunctioning of thermostat or usage of wrong thermostat or wrong connection of thermostat.
6. Damage of malfunction resulting from improper maintenance of unit.
Improper electrical and/or control wiring connection and room thermostat location.
7. Installing of Concealed Ducted Split units with other brands.
8. Installation of non-recommended pipe connection and failure to install "oil trap or U-trap" – for central split units.
9. Damage resulting from accident, abuse, fire, unauthorized modification, improper storage, lightning and natural disasters.
10. Damage or malfunction resulting from installing electrical or mechanical components external to the unit.
11. Damage or malfunction resulting from installation of under size or over capacity air –conditioning unit by others.

SAFETY CONSIDERATION

Installation, start-up and service of air conditioning equipment can be hazardous due to system pressures, electrical components and equipment location. Therefore only trained and qualified installation and service technicians should install, start up and service this equipment.



When working with the equipment, observe precautions in the literature as well as the tags, stickers and labels places on the units.



Keep all panels and screws installed on unit while transporting the unit and installing ductwork. This will help ensure all the components all together during installation and duct work.



Follow all safety codes.



Ensure to disconnect power before servicing this equipment.



Before operating, make sure the unit is properly grounded to prevent injury or death from electrical shock.



Don't purge or release refrigerant in atmosphere, use recovery machine to collect the refrigerant.



Wear safety glasses and work gloves.



Use care and caution in handling, storing and placing bulky equipment.



During welding / brazing, make sure that cooling cloth and fire extinguishers is available.



Do not stack the units upside down position during transportation and installation to avoid damage of unit components.



Ensure that unit installations mounting screws will not hit the electrical and refrigerant lines.



The unit must not be operated outside the design limits specified in this manual.



The manufacturer will not be liable for any injury or damage caused by incorrect installation, operation or maintenance resulting from a failure to follow the procedures and instructions detailed in this manual.

NOMENCLATURE



Unit Series Description
CHC - Concealed High Efficiency condenser
CHE - Concealed High Efficiency Evaporator

Refrigerant

F : R410A
C : R407C

Cooling Capacity
Nominal MBH

018	-	024
030	-	036
042	-	048
060	-	

Electrical Specifications

CODE	DESCRIPTION
2	415V / 3 ph / 50hz
7	240V / 1 ph / 50hz

CODE	DESCRIPTION
A	First Series
B	Second Series
C	Third Series

INSTALLATION & COMMISSIONING

Before starting prepare refrigerant lines

To install refrigerant lines you will need annealed copper tubing. These tubes are available on the local market together with the insulation and mounting equipment.

Electrical connections

Use insulated copper wire. The section of the core varies depending on the length required. Refer to Electrical data for the recommended sections. The wiring and electrical connections must comply with national electricity regulations. Check that the electrical characteristics on the nameplate correspond to those of the national grid. The electrical installation shall include a disconnect switch in compliance with local electrical regulations.

Indoor unit installation position

To ensure correct installation, the following points must be considered:

- The ceiling must be strong enough to support the weight of the unit.
- Choose a place where it will be easy to comply with the recommended clearances, taking into account the additional space required due to external accessories.
- Take into consideration the drilling of the holes in the walls to connect the unit.
- Make sure the maximum distances between the two units are not exceeded. See following tables

Table-1: Evaporator is above the Condenser

Models CHCC/CHEC	Refrigerant Lines	Equivalent Length	
		0 - 40 Ft	41 - 60 Ft
24	Liquid Line	3/8	3/8
	Suction Line	5/8	3/4
30	Liquid Line	3/8	3/8
	Suction Line	5/8	3/4
36	Liquid Line	3/8	3/8
	Suction Line	3/4	7/8
42	Liquid Line	3/8	3/8
	Suction Line	7/8	1.1/8
48	Liquid Line	3/8	1/2
	Suction Line	7/8	1.1/8
60	Liquid Line	3/8	1/2
	Suction Line	7/8	1.1/8

Table-2: Condenser is above the Evaporator

Models CHCC/CHEC	Refrigerant Lines	Equivalent Length	
		0 - 60 Ft	61-100 Ft
24	Liquid Line	3/8	3/8
	Suction Line	5/8	3/4
30	Liquid Line	3/8	3/8
	Suction Line	5/8	3/4
36	Liquid Line	3/8	3/8
	Suction Line	3/4	7/8
42	Liquid Line	3/8	3/8
	Suction Line	7/8	1.1/8
48	Liquid Line	3/8	3/8
	Suction Line	7/8	1.1/8
60	Liquid Line	3/8	3/8
	Suction Line	7/8	1.1/8

Table-3: Evaporator & Condenser is same level

Models CHCC/CHEC	Refrigerant Lines	Equivalent Length	
		0 - 80 Ft	81-100 Ft
24	Liquid Line	3/8	3/8
	Suction Line	5/8	3/4
30	Liquid Line	3/8	3/8
	Suction Line	5/8	3/4
36	Liquid Line	3/8	3/8
	Suction Line	3/4	7/8
42	Liquid Line	3/8	3/8
	Suction Line	7/8	1.1/8
48	Liquid Line	3/8	3/8
	Suction Line	7/8	1.1/8
60	Liquid Line	3/8	3/8
	Suction Line	7/8	1.1/8

INSTALLATION & COMMISSIONING

Table-1: Evaporator is above the Condenser

Models CHCF/CHEF	Refrigerant Lines	Equivalent Length	
		0 - 40 Ft	41 - 60 Ft
18	Liquid Line	3/8	3/8
	Suction Line	5/8	3/4
24	Liquid Line	3/8	3/8
	Suction Line	5/8	3/4
30	Liquid Line	3/8	1/2
	Suction Line	3/4	3/4
36	Liquid Line	3/8	1/2
	Suction Line	3/4	3/4
42	Liquid Line	1/2	1/2
	Suction Line	3/4	7/8
48	Liquid Line	1/2	1/2
	Suction Line	7/8	7/8
60	Liquid Line	1/2	1/2
	Suction Line	7/8	7/8

Table-2: Condenser is above the Evaporator

Models CHCF/CHEF	Refrigerant Lines	Equivalent Length	
		0 - 60 Ft	61-100 Ft
18	Liquid Line	3/8	1/2
	Suction Line	3/4	3/4
24	Liquid Line	3/8	1/2
	Suction Line	3/4	3/4
30	Liquid Line	1/2	1/2
	Suction Line	3/4	3/4
36	Liquid Line	1/2	1/2
	Suction Line	3/4	7/8
42	Liquid Line	1/2	1/2
	Suction Line	7/8	7/8
48	Liquid Line	1/2	1/2
	Suction Line	7/8	7/8
60	Liquid Line	1/2	5/8
	Suction Line	7/8	1.1/8

Table-3: Evaporator & Condenser is same level

Models CHCF/CHEF	Refrigerant Lines	Equivalent Length	
		0 - 80 Ft	81-100 Ft
18	Liquid Line	3/8	1/2
	Suction Line	3/4	3/4
24	Liquid Line	3/8	1/2
	Suction Line	3/4	3/4
30	Liquid Line	1/2	1/2
	Suction Line	3/4	3/4
36	Liquid Line	1/2	1/2
	Suction Line	3/4	7/8
42	Liquid Line	1/2	1/2
	Suction Line	7/8	7/8
48	Liquid Line	1/2	1/2
	Suction Line	7/8	7/8
60	Liquid Line	1/2	5/8
	Suction Line	1.1/8	1.1/8



Note for TABLE 1 : Near to the evaporator Inverted vapor line trap should be installed.



Note for TABLE 2 : Depending on the vertical rise of the line set, oil traps are required in the suction line. Oil traps should be installed at equal intervals along the suction line. install 1 oil trap for a height difference of 15-25 feet between indoor and outdoor units. install 2 oil traps for a difference of 26-50 ft, 3 for 51-100 ft .



Note for TABLE 3 : Inverted vapor line trap & Oil trap not required.



Note: Equivalent length = Piping Length+ Fitting equivalent Length

Preparing the ceiling and installing the unit

- Drill holes in the ceiling to fix the threaded rods according to the dimensions given the Dimensions section. -Access is necessary on the refrigerant connection side to facilitate installation, maintenance and access to the cabinet.
- Four 8 mm diameter threaded rods must be securely fixed into the ceiling. Install the other end of the rods through the slots of the unit suspension brackets.
- Position the shock absorbers, add washers and screw the nuts down until the unit is correctly supported.
- The unit must be level following the correct angle in both direction to ensure the proper draining of the condensates.
- If there is enough space, a rubber or neoprene sheet can be placed between the ceiling and the unit.

Installation procedure

- Make sure the route taken by your refrigerant lines is as short as possible.
- Limit the pressure loss in refrigerant lines, like more number of bends and using short or small bending radius..
- Slope all the gas lines leaving the indoor unit so that oil can return to the

INSTALLATION & COMMISSIONING

compressor by gravity.

- Prevent any possibility of oil trapped in the gas lines.
- Before drilling into the wall make sure there are no pipes or electrical cables in the wall at the place where you are going to drill provide a protective sleeve for the bundle of tubes and cables at the point where it passes through the hole.
- If permitted by legislation, the condensate drainage line can also be included in the bundle. Wrap tape around all the lines and cables from the bottom of the outside unit to the point where the piping enters the wall. Carry out the same operation for each circuit.

Brazed connections

These lines will be created on the installation site. They will be installed according to normal trade practice by qualified personnel, in compliance with local legislation.

1. Remove the plugs from the units> refrigerant connections just before connecting the piping, when all the connections on the refrigerant lines have been terminated. This will prevent contamination by humidity. Remove the rubber plugs from the ends of the tubes.
2. Use a clean dry copper tube for refrigeration installations.
3. Use silver brazing alloy only. Do not overheat the welds and carry out nitrogen inside the tubes to prevent oxidization during brazing.
4. Once all the other connections have been made, debraze or cut the plug on the outdoor unit's refrigerant line connections. Proceed in the same way as for brazing of the indoor unit's lines.

Line insulation

To prevent heat losses and condensation, both liquid and gas lines must be thoroughly insulated.

Condensate connections

The unit must be perfectly level in both directions. Connect the indoor unit's condensate tray to a condensate drainage line.

To ensure correct condensate flow, the drainage tube must be given a 10° slope. There must not be a condensate trap at any point in the line. However, a trap can be provided to prevent outside air from being taken in by the indoor unit. If the tube enters a room, insulate it to prevent condensation damage.

Electrical connections

All the wiring and earthing arrangements must comply with local legislation.

INSTALLATION & COMMISSIONING

Vacuuming

For this operation, use a pump capable of creating a vacuum of 1 mm Hg (1.3mbar) or less. To create the vacuum you must connect the pump to the Schrader pressure connection on service valve A located on the outdoor unit (gas line).

Create a vacuum up to 2 mm Hg (2.6mbar) or less. Once the value of 2mm Hg or less has been reached, an increase in pressure will be observed after a certain time.

The maximum permissible increase is 1 mm Hg after 15 minutes. If the increase is greater and remains at a constant value, this means there is too much humidity in the system. In this case, break the vacuum using dry nitrogen and start the vacuum creation procedure again.

Additional refrigerant charge

When pipe length exceeds 6m, please add refrigerant according to the table below: Once the appropriate amount of refrigerant has been added, fully open liquid line valve and check the operating pressure

Liquid Line	Additional R407C Charge (OZ/FT)	Additional R410A Charge (OZ/FT)	Suction Line	Additional R407C Charge (OZ/FT)	Additional R410A Charge (OZ/FT)
3/8"	0.62	0.51	5/8"	0.04	0.06
3/8"	0.62	0.51	3/4"	0.06	0.09
3/8"	0.62	0.51	7/8"	0.08	0.12
3/8"-1/2"	0.62-1.12	0.51-1.01	1-1/8"	0.14	0.20

*Note: R407C & R410A Refrigerant Should be Charged in liquid stage



Never add liquid in the suction line of the compressor.

HOME AUTOMATION SYSTEM

Coolex App



Wi Fi Module




Typical Thermostat




Thermostat features:

1. Voltage rating: 24VAC
2. Room temperature/Set temperature display in °C or °F
3. Mode of operation: Cool/Heat/Auto
4. Fan mode: Auto/ON
5. Key lock function
6. Preset temperature setting: Comfort/Economy/Away
7. Duct/Remote sensor option
8. Temperature offset calibration
9. BMS Modbus option



SERVICE SPACE



MODEL	SERVICE SPACE (mm)		
	A	B	C
CHCF- 018	800	330	500
CHCC/CHCF- 024	800	330	500
CHCC/CHCF-030	800	330	500
CHCC/CHCF-036	1300	330	500
CHCC/CHCF-042	1300	330	500
CHCC/CHCF-048	1300	330	500
CHCC/CHCF-060	1300	330	500



SERVICE SPACE

ALL DIMENSIONS ARE IN mm

ELECTRICAL DATA

Outdoor Units		CHCC 024	CHCC 030	CHCC 036	CHCC 042	CHCC 048	CHCC 060
Unit Power Supply	Volt	240	240	415	415	415	415
	Phase	1	1	3	3	3	3
	Hz	50					
Compressor	V - Ph - Hz	220/240 - 1 - 50		380/420 - 3 - 50			
	RLA	11.4	13.6	6.4	7.9	8.3	10
	LRA	60	76	46	50	61.8	65.5
Condenser Fan Motor	V - Ph - Hz	240 - 1 - 50			415 - 3 - 50		
	Output kW	0.40	0.40	0.40x2	0.37 X 2	0.37 X 2	0.37 X 2
	FLA	1.70	1.70	1.70x2	0.7 x 2	0.7 x 2	0.7 x 2
Unit Ampacity, Ampere		16.0	18.7	11.4	11.3	11.8	13.9
Max. Fuse Size, Ampere		25	30	15	20	20	20
Minimum Wire Size, mm ²		4	4	2.5	2.5	2.5	2.5

Indoor Units		CHEC 024	CHEC 030	CHEC 036	CHEC 042	CHEC 048	CHEC 060
Unit Power Supply	Volt	240					
	Phase	1					
	Hz	50					
Blower Motor	V - Ph - Hz	240 - 1 - 50					
	Output Motor Hp	1/3	1/3	1/3	1/2	3/4	3/4
	FLA	2.5	2.5	2.5	3.1	4.5	4.5
Unit Ampacity, Ampere		3.1	3.1	3.1	3.9	5.6	5.6
Max. Fuse Size, Ampere		5	5	5	5	10	10
Minimum Wire Size, mm ²		1.5	1.5	1.5	1.5	1.5	1.5

LEGEND:

- FLA** : Full Load Amps
- RLA** : Rated Load Amps
- LRA** : Locked Rotor Amps

ELECTRICAL DATA

Outdoor Units		CHCF 018	CHCF 024	CHCF 030	CHCF 036	CHCF 042	CHCF 048	CHCF 060
Unit Power Supply	Volt	240	240	240	415	415	415	415
	Phase	1	1	1	3	3	3	3
	Hz	50						
Compressor	V - Ph - Hz	220/240 - 1 - 50			380/420 - 3 - 50			
	RLA	6.4	12.5	13.6	6.6	6.8	10.7	10
	LRA	38	60	67	46	43	64	64
Condenser Fan Motor	V - Ph - Hz	240 - 1 - 50			415 - 3 - 50			
	Output kW	0.16	0.16	0.16	0.37 x 2	0.37 x 2	0.37 x 2	0.37 x 2
	FLA	0.75	0.75	0.75	0.7 x 2	0.7 x 2	0.7 x 2	0.7 x 2
Unit Ampacity, Ampere		8.8	16.4	17.8	8.9	9.9	14.8	13.9
Max. Fuse Size, Ampere		15	25	30	15	15	25	25
Minimum Wire Size, mm ²		2.5	4	4	2.5	2.5	2.5	2.5

Indoor Units		CHEF 018	CHEF 024	CHEF 030	CHEF 036	CHEF 042	CHEF 048	CHEF 060
Unit Power Supply	Volt	240						
	Phase	1						
	Hz	50						
Blower Motor	V - Ph - Hz	240 - 1 - 50						
	Motor Hp	1/6	1/3	1/3	1/2	1/2	3/4	3/4
	FLA	1.5	2.5	2.5	3.1	3.1	4.5	4.5
Unit Ampacity, Ampere		1.9	3.1	3.1	3.9	3.9	5.6	5.6
Max. Fuse Size, Ampere		5	5	5	5	5	10	10
Minimum Wire Size, mm ²		1.5	1.5	1.5	1.5	1.5	1.5	1.5

LEGEND:

- FLA** : Full Load Amps
- RLA** : Rated Load Amps
- LRA** : Locked Rotor Amps

SUPPLY AIR PERFORMANCE





Model	SPEED	External Static Pressure [in.wg]					
		0	0.1	0.2	0.3	0.4	0.5
		Air Flow Rate [CFM]					
CHEF-018	HIGH	780	692	595	-	-	-
	MED	699	615	523	-	-	-
	LOW	648	567	477	-	-	-
CHEC/ CHEF-024	HIGH	814	773	673	622	519	457
	MED	770	714	619	571	-	-
	LOW	726	655	565	-	-	-
CHEC/ CHEF-030	HIGH	1214	1008	919	825	752	679
	MED	974	843	743	606	-	-
	LOW	923	817	721	-	-	-
CHEC/ CHEF-036	HIGH	1117	1050	961	867	794	721
	MED	1064	1001	911	790	-	-
	LOW	1028	952	860	-	-	-
CHEC/ CHEF-042	HIGH	1572	1338	1269	1210	1207	1143
	MED	1441	1294	1220	1173	-	-
	LOW	1311	1251	1172	1137	-	-
CHEC/ CHEF-048	HIGH	1766	1466	1426	1338	1224	1160
	MED	1608	1416	1358	1285	1060	-
	LOW	1450	1367	1291	1232	-	-
CHEC/ CHEF-060	HIGH	2020	1644	1583	1466	1241	1152
	MED	1784	1561	1497	1396	1187	1104
	LOW	1548	1477	1410	1327	1134	1059

UNIT DIMENSIONS

Indoor Unit

MODEL	DIMENSIONS					
	L	W	H	DUCT CINNECTION AXB	C	D
CHEF-018	952	636	325	912X288	980	380
CHEC/CHEF-024	952	636	325	912X288	980	380
CHEC/CHEF-030	952	636	325	912X288	980	380
CHEC/CHEF-036	952	707	370	912X333	980	425
CHEC/CHEF-042	952	707	370	912X333	980	425
CHEC-048	952	727	370	912X333	1050	425
CHEF-048	1022	877	400	980X363	1050	600
CHEC/CHEF-060	1022	877	400	980X363	1050	600

ALL DIMENSIONS ARE IN MM




UNIT DIMENSIONS

Outdoor Units



MODEL	DIMENSIONS		
	H	L	W
CHCF-018	804	1021	397
CHCC/CHCF-024	804	1021	397
CHCC/CHCF-030	892	1021	397

ALL DIMENSIONS ARE IN MM




BOLT MTG. HOLES
(4 PLACES)

TOP VIEW




FRONT VIEW



SIDE VIEW



MODEL	DIMENSIONS			
	H	L	L1	W
CHCC/CHCF-036	1332	1021	1090	397
CHCC/CHCF-042	1332	1021	1104	397
CHCC/CHCF-048	1332	1021	1104	397
CHCC/CHCF-060	1332	1021	1104	397

ALL DIMENSIONS ARE IN MM




BOLT MTG. HOLES
(4 PLACES)

TOP VIEW




FRONT VIEW



SIDE VIEW


TYPICAL WIRING DIAGRAM

ELECTRO-MECHANICAL CONTROLS(24VAC)




TYPICAL WIRING DIAGRAM

MICROPROCESSOR BASED CONTROLLER(OPTIONAL)




TYPICAL WIRING DIAGRAM

ELECTRO-MECHANICAL CONTROLS(24VAC)



TYPICAL WIRING DIAGRAM

WITH MICROPROCESSOR BASED CONTROLLER(OPTIONAL)



TROUBLE SHOOTING

Use the table in this section to assist and help you in indentifying the cause or causes of any malfunctions in the unit's operation. The column headed RECOMMENDED ACTION will suggest repair procedures.



Disconnect electrical power connection before servicing the unit and allow the rotating equipment to stop completely. Failure to do so may result in personal injury or death from electrical shock or entanglement in moving parts.

Problem	Causes	Recommended Action
1- The Air Condition does not operate	1- No power supply	Check and restore or start power supply
	2- Power supply Sequence Reverse	Check and change the power supply sequence.
	3- Fuse blown or circuit breaker tripped	Replace fuse or reset circuit breaker.
	4- Insufficient line voltage	Determine cause and correct.
	5- Incorrect or faulty wiring	Check wiring diagram and rewire correctly.
	6- Thermostat setting too high	Lower thermostat setting below room temperature.
2- Compressor not start but condenser fan runs	1- Faulty wiring or loose conections in compressor circuit	Check wiring and repair or replace
	2- Compressor motor burned out, seized or internal overload open	Determine cause. Replace compressor
	3- Defective overload	Determine cause and replace
	4- One leg of 3-phase power dead	Determine cause Replace fuse or reset circuit breaker
3- Compressor short cycles	1- Refrigerant overcharge or undercharge	Reclaim refrigerant, evacuate system and recharge
	2- Defective compressor	Replace and determine cause
	3- Insufficient line voltage	Determine cause and correct
	4- Blocked condenser	Determine cause and correct
	5- Defective overload	Determine cause and replace
	6- Defective thermostat	Replace thermostat
	7- Faulty condenser fan motor or capacitor	Replace motor or capacitor
	8- Restriction in refrigerant system	Locate restriction and remove

Problem	Causes	Recommended Action
4- Compressor operates continuously	1- Dirty air filter	Wash air filter
	2- Unit undersized for load	Decrease load or increase unit size
	3- Thermostat set too low	Reset thermostat
	4- Low refrigerant charge	Locate leak, repair and recharge
	5- Compressor less pumping	Replace compressor
	6- Air in system	Reclaim refrigerant, evacuate system and recharge
	7- Condenser coil dirty or restricted	Clean coil or remove restriction
5- Excessive high pressure	1- Dirty condenser coil	Clean coil
	2- Refrigerant overcharge	Reclaim excess refrigerant
	3- Air in system	Reclaim refrigerant, evacuate system and recharge
	4- Condenser air restricted or air short cycling	Determine cause and correct
6- High pressure too low	1- Low refrigerant charge	Check for leak, repair and recharge
	2- Compressor less pumping	Replace compressor
	3- Restriction in liquid tube	Remove restriction
7- Excessive suction pressure	1- High heat load	Check for source and eliminate
	2- Compressor less pumping	Replace compressor
	3- Refrigerant overcharge	Reclaim excess refrigerant
8- Suction pressure too low	1- Dirty air filter	Wash air filter
	2- Low refrigerant charge	Check for leak, repair and recharge
	3- Metering device, filter drier or low side restricted	Remove source of restriction
	4- Insufficient evaporator airflow	Increase air quantity and check and wash air filter
	5- Temperature too low in conditioned area	Reset thermostat
9- Motor stalls	1- low line voltage	check across AC line
	2- overload motor	Reduce load
10- Motor fails to start	1- Blown open circuit breaker	inspect and reset circuit breaker
	2- short circuited stator	Indicated by blown fuses. Motor must be rewind
	3- one phase of three-phase is open	Check line for open phase
	4- Overload trip (heated motor)	Check and reset overload

MAINTENANCE

Routine maintenance by owner

Regular scheduled maintenance and upkeep to be performed by the user includes for example: change of the one-time dust filter, clean casing, wash condenser, as well as testing of the equipment.

You can do some of the periodic maintenance functions for your unit yourself; this includes cleaning the permanent air filters, cleaning the unit cabinet, cleaning the condenser coil, and conducting a general unit inspection on a regular basis.

Cleaning the air filter

1. Dismantle the air filter.
2. Clean the air filter (Vacuum cleaner or pure water may be used to clean the air filter. If the dust accumulation is too heavy, please use soft brush and mild detergent to clean it and dry out.)
 - The air-in side should face up when using vacuum cleaner.
 - The air-in side should face down when using water.
3. Re-install the air filter

Maintenance performed by serviceman-cooling season

To keep your unit operating safely and efficiently, the manufacturer recommends that a qualified serviceman check the entire system at least once each year and any other time that you feel one is needed. Your serviceman should examine these areas of your unit:

S.R.	PREVENTIVE MAINTENANCE INSTRUCTIONS	PREVENTIVE ACTIONS
1	Wash Air-Filters	Every two months or sooner
2	Wash evaporator coil with water pressure pump	Once every year
3	Wash Condenser coil with water pressure pump	Once every year
4	Check any abnormal sound from condenser motor	Once every year
5	Check any abnormal sound from blower motor	Once every year
6	Check and clean electrical box and blower wheel with air blower	Once every year
7	Check for free drain water flow	Once every year
8	Check gas pressure and any oil traces due to leaks	Once every year
9	Check for any loose connection in power supply and in safety controls	Once every year



Caution: Do not operate the unit without the evaporator fan access panel in place. Reinstall the access panel after performing any maintenance procedures on the fan. Operating the unit without the access panel properly installed may result in severe personal injury or death.

NOTES



شركة صناعات التبريد والتخزين والخدمات النفطية
Refrigeration Industries & Storage and Oil Services Co. KSC



OPERATION MANUAL

Residential Installations Department
Unit Commissioning Report

Customer's Name					Contract #			Date				
Address (Area)					Foreman							
Block				Plot			Group (Include all Technicians Names)					
Street				House #								
Avenue				Tel. #			Commissioning Date					
Unit Details												
PNG / NGC Model				S. No.:			NGE Model:			S. No.:		
PRE - START CHECKS:				YES CHC	YES CHE	NO (Explain)						
1. Clearances as per RIC's specifications				<input type="checkbox"/>	<input type="checkbox"/>							
2. Washable Filters Installed				<input type="checkbox"/>	<input type="checkbox"/>							
3. Condensate Drain Pipe Installation				<input type="checkbox"/>	<input type="checkbox"/>							
4. Fuses (Wire/Cartridge) are of Correct Size				<input type="checkbox"/>	<input type="checkbox"/>							
5. Filter Drier Installed				<input type="checkbox"/>	<input type="checkbox"/>							
6. Suction Oil Trap Installed				<input type="checkbox"/>	<input type="checkbox"/>							
7. Refrigeration Pipe Insulated				<input type="checkbox"/>	<input type="checkbox"/>							
8. Vibration Isolators Installed				<input type="checkbox"/>	<input type="checkbox"/>							
9. AHU Room Cleared of all Foreign Materials				<input type="checkbox"/>	<input type="checkbox"/>							
10. All Duct Work Completed				<input type="checkbox"/>	<input type="checkbox"/>							
11. Supply and Return Grills Installed				<input type="checkbox"/>	<input type="checkbox"/>							
12. Room Thermostat installed at proper location				<input type="checkbox"/>	<input type="checkbox"/>							
POST START CHECKS :												
1. Record and check the following data against name plate												
Unit Running Voltage V	L 1			L2			L3			Evap. Motor Amps.		
Compressor Amps.	SYS. 1	AMP.		SYS. 2	AMP.		Cond. Motor Amps.					
2. Ambient Conditions as recorded below					Outdoor Motors							
SYS. 1	S.P.		D.P.		SYS. 2	S.P.		D.P.				
3. Motor Start: <input type="checkbox"/> Comp. Motor <input type="checkbox"/> Evap. Motor <input type="checkbox"/> Cond. Motor												
4. Blower Motor Fan Rotation				<input type="checkbox"/>	Condensor Motor Fan Rotation				<input type="checkbox"/>			
5. Uniform Air Distribution in All Rooms				<input type="checkbox"/>	Air Sound In All Rooms				<input type="checkbox"/>			
6. All Controls Function Properly				<input type="checkbox"/>	Operation Controls				<input type="checkbox"/>	Safety Controls		<input type="checkbox"/>
7. Replaced All Panels and Screws				<input type="checkbox"/>	Trained Owner About Unit Operation				<input type="checkbox"/>			
Materials Consumed: _____ _____												
Time Left RIC				Time Arrived RIC			Time Arrived Site			Time Left Site		
Group Leader Signature							Remarks _____ _____					
Copy # 1: Customer Copy # 2: A/C Maintenance File Copy # 3: QC (if Coolex Machine)												

**Residential Installations Department
Unit Commissioning Report**

Customer's Name		Contract #		Date	
Address (Area)			Foreman		
Block	Plot	Group (Include all Technicians Names)			
Street	House #				
Avenue	Tel. #	Commissioning Date			
Unit Details					
PNG / NGC Model		S. No.:		NGE Model:	
				S. No.:	
PRE - START CHECKS:		YES CHC	YES CHE	NO (Explain)	
1. Clearances as per RIC's specifications		<input type="checkbox"/>	<input type="checkbox"/>		
2. Washable Filters Installed		<input type="checkbox"/>	<input type="checkbox"/>		
3. Condensate Drain Pipe Installation		<input type="checkbox"/>	<input type="checkbox"/>		
4. Fuses (Wire/Cartridge) are of Correct Size		<input type="checkbox"/>	<input type="checkbox"/>		
5. Filter Drier Installed		<input type="checkbox"/>	<input type="checkbox"/>		
6. Suction Oil Trap Installed		<input type="checkbox"/>	<input type="checkbox"/>		
7. Refrigeration Pipe Insulated		<input type="checkbox"/>	<input type="checkbox"/>		
8. Vibration Isolators Installed		<input type="checkbox"/>	<input type="checkbox"/>		
9. AHU Room Cleared of all Foreign Materials		<input type="checkbox"/>	<input type="checkbox"/>		
10. All Duct Work Completed		<input type="checkbox"/>	<input type="checkbox"/>		
11. Supply and Return Grills Installed		<input type="checkbox"/>	<input type="checkbox"/>		
12. Room Thermostat installed at proper location		<input type="checkbox"/>	<input type="checkbox"/>		
POST START CHECKS :					
1. Record and check the following data against name plate					
Unit Running Voltage V	L1	L2	L3	Evap. Motor Amps.	
Compressor Amps.	SYS. 1	AMP.	SYS. 2	AMP.	Cond. Motor Amps.
2. Ambient Conditions as recorded below			Outdoor Motors		
SYS. 1	S.P.	D.P.	SYS. 2	S.P.	D.P.
3. Motor Start: <input type="checkbox"/> Comp. Motor <input type="checkbox"/> Evap. Motor <input type="checkbox"/> Cond. Motor					
4. Blower Motor Fan Rotation		<input type="checkbox"/>	Condensor Motor Fan Rotation		<input type="checkbox"/>
5. Uniform Air Distribution in All Rooms		<input type="checkbox"/>	Air Sound In All Rooms		<input type="checkbox"/>
6. All Controls Function Properly		<input type="checkbox"/>	Operation Controls		<input type="checkbox"/>
			Safety Controls		<input type="checkbox"/>
7. Replaced All Panels and Screws		<input type="checkbox"/>	Trained Owner About Unit Operation		<input type="checkbox"/>
Materials Consumed: _____					

Time Left RIC		Time Arrived RIC		Time Arrived Site	
Group Leader Signature			Remarks _____		
Copy # 1: Customer Copy # 2: A/C Maintenance File Copy # 3: QC (if Coolex Machine)					



شركة صناعات التبريد والتخزين والخدمات النفطية
Refrigeration Industries & Storage and Oil Services Co. KSC



الصيانة الدورية من المستخدم

الصيانة المنتظمة والصيانة التي يتعين القيام بها من قبل المستخدم ويشمل تغيير فلتر الغبار مرة واحدة، وتنظيف الوحدة، وغسل المكثف، وكذلك اختبار المعدات يمكنك القيام ببعض وظائف الصيانة الدورية للوحدة بنفسك. وهذا يشمل تنظيف مرشحات الهواء دائمة، وتنظيف وحدة، وتنظيف ملف المكثف، وإجراء تفتيش عام علي الوحدة بانتظام.

تنظيف فلتر الهواء

- 1 - قم بإزالة فلتر الهواء.
- 2 - قم بتنظيف الفلتر بواسطة مضخة الهواء او الغسيل بالماء او باستخدام فرشاة التنظيف
- 3 - قم بإعادة تركيب الفلتر

الصيانة بواسطة فني متخصص

للبقاء علي كفاءة عمل الوحدة ينصح المصنع بضرورة عمل صيانة دورية عن طريق فني متخصص لعمل الاتي:

رقم	شحنات الغاز الاضافية	شحنات الغاز الاضافية
1	غسيل فلاتر الهواء	كل شهرين او اقل
2	غسيل ملف التبريد باستخدام مضخة ماء	مرة بالسنة
3	غسيل ملف التكثيف باستخدام مضخة ماء	مرة بالسنة
4	فحص اي صوت غير اعتيادي من مروحة الوحدة الخارجية	مرة بالسنة
5	فحص اي صوت غير اعتيادي من مروحة الوحدة الداخلية	مرة بالسنة
6	فحص وتنظيف صندوق الكهرباء ومروحة الوحدة الداخلية باستخدام الهواء المضغوط	مرة بالسنة
7	فحص سلامة خطوط صرف الوحدة وخلوها من العوائق	مرة بالسنة
8	فحص ضغوط الغاز واي ترسبات زيتية ناتجة لتسرب الغاز	مرة بالسنة
9	فحص وصلات الكهرباء والتأكد من سلامتها	مرة بالسنة

لا تقم بتشغيل الوحدة قبل التأكد من احكام اغلاق جميع ابوابها لتفادي حدوث اي اصابات او وفاة للاشخاص



طريق الاصلاح	السبب	العطل
قم بالفحص واعادة ضبط قاطع الدائرة	1 - تلف بقاطع الدائرة	10 - المحرك الكهربائي لا يعمل
قم بفحص الفيوز واعادة لف الموتور	2 - قصر دائرة الاستاتور	
قم بفحص خطوط الكهرباء للطور المفتوح	3 - مشكلة بالطور	
قم بفحص واعادة ضبط الاوفر لود	4 - فصل بلاوفر لود	

طريق الإصلاح	السبب	العطل
اغسل فلتر الهواء	1 - فلتر الهواء متسخ	4 - الضاغط يعمل باستمرار
قلل الحمل او استخدم وحدة اكبر	2 - الوحدة اصغر من المطلوب	
اعد ضبط الثيرموستات	3 - اعدادات الثيرموستات منخفضة	
حدد مكان تسريب الغاز وقم باصلاحه وضبط شحنة الغاز	4 - شحنة الغاز قليلة	
استبدل الضاغط	5 - الضاغط قليل الضخ	
قم بسحب الغاز واعادة تفريغ الدائرة والشحن من جديد	6 - هواء بدائرة التبريد	
نظف الملف وقم بازالة اي عائق	7 - اتساخ او عائق بملف الكثف	
نظف الملف	1 - اتساخ ملف التكتيف	5 - ضغط عالي زائد
قم باستعادة الغاز الزائد	2 - شحنة الغاز زائدة	
استعادة الغاز وتفريغ الدائرة من الهواء	3 - هواء بالدائرة	
حدد السبب وصححه	4 - هواء المكثف محجوب او هناك مشكله بسريانه	
تحقق من التسريب وقم باصلاحه	1 - شحنة الغاز قليلة	6 - الضغط العالي منخفض
استبدل الضاغط	2 - الضاغط قليل الضخ	
قم بازالة العائق	3 - مانع بخط السائل	
تحقق من المصدر وقم بازالته	1 - حمل حراري عالي	7 - ضغط سحب زائد
استبدل الضاغط	2 - الضاغط قليل الضخ	
استعيد الغاز الزائد	3 - شحنة الغاز زائدة	
قم بغسل فلتر الهواء	1 - اتساخ فلتر الهواء	8 - ضغط السحب منخفض
تحقق من وجود تسريب وقم باصلاحه	2 - شحنة الغاز قليلة	
قم بازالة العائق	3 - سد بفلتر المحفف او بخط الضغط المنخفض	
قم بزيادة كمية الهواء وغسيل فلتر الهواء	4 - هواء التبريد غير كافي	
اعد ضبط الثرموستات	5 - درجة الحرارة منخفضة جدا بالماكن المكيف	
قم بفحص خطوط الكهرباء الرئيسية	1 - الجهد منخفض	9 - مشكلة بالمحرك
قلل الحمل	2 - المحرك محمل بحمل زائد	

تحديد الاعطال

استخدم الجدول التالي لتحديد الاعطال وكيفية الاصلاح


تاكد من فصل التيار الكهربائي قبل عمل اي صيانة للوحدة لتفادي حدوث اي اصابة او وفاة ناتج من الصدمة الكهربائية



طريق الاصلاح	السبب	العطل
تاكد من توصيل مصدر الكهرباء	1 - لا يوجد كهرباء واصلة للوحدة	1 - المكيف لا يعمل
افحص مصدر الكهرباء وعدل الطور	2 - مصدر الكهرباء معكوس الطور	
استبدل الفيوز او اعد ضبط قاطع الدائرة	3 - خلل بالفيوز او قاطع الدائرة	
راجع المخطط الكهربائي لضبط الوصلات	4 - الجهد غير كافي	
راجع المخطط الكهربائي	5 - خطأ بوصلات الكهرباء	
قم بضبط الثرموستات علي القيم الطبيعية	6 - خطأ في اعداد الثيرموستات	
حدد العطل وقم بالاستبدال	1 - خطأ بوصلات الكهرباء للضاغط	2 - الضاغط لا يعمل ولكن مروحة المكثف تعمل
حدد العطل وقم بالاستبدال	2 - احتراق موتور الضاغط او فتح الاوفرلود الداخلي	
حدد العطل وقم بالاستبدال	3 - عطل بالاوفرلود	
اعد ضبط قاطع الدائرة	4 - احد الفازات الثلاثة لا تعمل	
اعد ضبط شحنة الغاز	1 - شحنة غاز التبريد زائدة	3 - الضاغط يفصل سريعا
حدد العطل وقم بالاصلاح	2 - عيب بالضاغط	
حدد العطل وقم بالاصلاح	3 - الجهد غير كافي	
نظف الملف وقم بازالة اي عائق	4 - سدد بملف المكثف	
استبدل الاوفر لود	5 - خلل بالاوفر لود	
استبدل الثيرومستات	6 - خلل بالثيرمو	
استبدل المكثف	7 - خلل بمكثف مروحة المكثف	
حدد مكان العائق وقم بازالته	8 - عائق في دائرة التبريد	


المخطط الكهربائي للوحدة

التحكم باستخدام ميكروبروسيسور




المخطط الكهربائي للوحدة

التحكم باستخدام الكهروميكانيكية





المخطط الكهربائي للوحدة

التحكم باستخدام الكهروميكانيكية







الوحدة الخارجية



الوحدة الداخلية

MODEL	DIMENSIONS					
	L	W	H	DUCT CINNECTION AXB	C	D
CHEF-018	952	636	325	912X288	980	380
CHEC/CHEF-024	952	636	325	912X288	980	380
CHEC/CHEF-030	952	636	325	912X288	980	380
CHEC/CHEF-036	952	707	370	912X333	980	425
CHEC/CHEF-042	952	707	370	912X333	980	425
CHEC-048	952	727	370	912X333	1050	425
CHEF-048	1022	877	400	980X363	1050	600
CHEC/CHEF-060	1022	877	400	980X363	1050	600

ALL DIMENSIONS ARE IN MM



الضغط الاستاتيكي الخارجي (بوصة ماء)						السرعة	الموديل
0.5	0.4	0.3	0.2	0.1	0		
كمية الهواء (قدم ³ /دقيقة)							
-	-	-	595	692	780	العالية	CHEF-018
-	-	-	523	615	699	المتوسطة	
-	-	-	477	567	648	الصفرى	
457	519	622	673	773	814	العالية	CHEC/ CHEF-024
-	-	571	619	714	770	المتوسطة	
-	-	-	565	655	726	الصفرى	
679	752	825	919	1008	1214	العالية	CHEC/ CHEF-030
-	-	606	743	843	974	المتوسطة	
-	-	-	721	817	923	الصفرى	
721	794	867	961	1050	1117	العالية	CHEC/ CHEF-036
-	-	790	911	1001	1064	المتوسطة	
-	-	-	860	952	1028	الصفرى	
1143	1207	1210	1269	1338	1572	العالية	CHEC/ CHEF-042
-	-	1173	1220	1294	1441	المتوسطة	
-	-	1137	1172	1251	1311	الصفرى	
1160	1224	1338	1426	1466	1766	العالية	CHEC/ CHEF-048
-	1060	1285	1358	1416	1608	المتوسطة	
-	-	1232	1291	1367	1450	الصفرى	
1152	1241	1466	1583	1644	2020	العالية	CHEC/ CHEF-060
1104	1187	1396	1497	1561	1784	المتوسطة	
1059	1134	1327	1410	1477	1548	الصفرى	

البيانات الكهربائية


CHCF 060	CHCF 048	CHCF 042	CHCF 036	CHCF 030	CHCF 024	CHCF 018	الوحدة الخارجية	
415	415	415	415	240	240	240	الجهد	
3	3	3	3	1	1	1	الطور	
50							التردد	
380/420 - 3 - 50				220/240 - 1 - 50			فولت-طور-هرتز	
10	10.7	6.8	6.6	13.6	12.5	6.4	امبير حمل التشغيل	
64	64	43	46	67	60	38	امبير حبس الدوار	
415 - 3 - 50				240 - 1 - 50			فولت-طور-هرتز	
0.37 x 2	0.37 x 2	0.37 x 2	0.37 x 2	0.16	0.16	0.16	لطاقه المستهلكة (كيلو واط)	
0.7 x 2	0.7 x 2	0.7 x 2	0.7 x 2	0.75	0.75	0.75	امبير الحمل الكامل	
13.9	14.8	9.9	8.9	17.8	16.4	8.8	السعة الامبيرية للوحدة (امبير)	
25	25	15	15	30	25	15	اكبر حجم للفيوز (امبير)	
2.5	2.5	2.5	2.5	4	4	2.5	اقل مساحة مقطع للسلك (مم ²)	

CHEF 060	CHEF 048	CHEF 042	CHEF 036	CHEF 030	CHEF 024	CHEF 018	الوحدات الداخلية	
240							الجهد	
1							الطور	
50							التردد	
240 - 1 - 50							فولت-طور-هرتز	
3/4	3/4	1/2	1/2	1/3	1/3	1/6	قدرة المحرك (حصان)	
4.5	4.5	3.1	3.1	2.5	2.5	1.5	امبير الحمل الكامل	
5.6	5.6	3.9	3.9	3.1	3.1	1.9	السعة الامبيرية للوحدة (امبير)	
10	10	5	5	5	5	5	اكبر حجم للفيوز (امبير)	
1.5	1.5	1.5	1.5	1.5	1.5	1.5	اقل مساحة مقطع للسلك (مم ²)	

البيانات الكهربائية

CHCC 060	CHCC 048	CHCC 042	CHCC 036	CHCC 030	CHCC 024	الوحدة الخارجية	
415	415	415	415	240	240	الجهد	
3	3	3	3	1	1	الطور	
50						التردد	
380/420 - 3 - 50				220/240 - 1 - 50		فولت-طور-هرتز	
10	8.3	7.9	6.4	13.6	11.4	امبير حمل التشغيل	
65.5	61.8	50	46	76	60	امبير حبس الدوار	
415 - 3 - 50			240 - 1 - 50			فولت-طور-هرتز	
0.37 x 2	0.37 x 2	0.37 x 2	0.40 x 2	0.40	0.40	لطاقة المستهلكة (كيلو واط)	
0.7 x 2	0.7 x 2	0.7 x 2	1.70 x 2	1.70	1.70	امبير الحمل الكامل	
13.9	11.8	11.3	11.4	18.7	16.0	السعة الامبيرية للوحدة (امبير)	
20	20	20	15	30	25	اكبر حجم للفيوز (امبير)	
2.5	2.5	2.5	2.55	4	4	اقل مساحة مقطع للسلك (مم ²)	

CHEC 060	CHEC 048	CHEC 042	CHEC 036	CHEC 030	CHEC 024	الوحدات الداخلية	
240						الجهد	
1						الطور	
50						التردد	
240 - 1 - 50						فولت-طور-هرتز	
3/4	3/4	1/2	1/3	1/3	1/3	قدرة المحرك (حصان)	
4.5	4.5	3.1	2.5	2.5	2.5	امبير الحمل الكامل	
5.6	5.6	3.9	3.1	3.1	3.1	السعة الامبيرية للوحدة (امبير)	
10	10	5	5	5	5	اكبر حجم للفيوز (امبير)	
1.5	1.5	1.5	1.5	1.5	1.5	اقل مساحة مقطع للسلك (مم ²)	



مساحة الخدمة
كل الأبعاد بالمم

مسافة الخدمة (مم)			الموديل
C	B	A	
500	330	800	CHCF- 018
500	330	800	CHCC/CHCF- 024
500	330	800	CHCC/CHCF-030
500	330	1300	CHCC/CHCF-036
500	330	1300	CHCC/CHCF-042
500	330	1300	CHCC/CHCF-048
500	330	1300	CHCC/CHCF-060

Typical Thermostat



Wi Fi Module




Coolex App



مميزات الترموستات:

1. تصنيف الجهد: 24VAC
2. عرض درجة حرارة الغرفة / ضبط درجة الحرارة في درجة مئوية أو درجة فهرنهايت
3. طريقة التشغيل: بارد / ساخن / تلقائي
4. وضع المروحة: تلقائي / تشغيل
5. وظيفة مفتاح القفل
6. ضبط درجة الحرارة مسبقاً: مريح / اقتصادي / بعيداً
7. مجرى الهواء / خيار الاستشعار عن بعد
8. معايرة درجة الحرارة
9. خيار BMS Modbus



التركيب والتشغيل

- قبل الحفر بالحوائط لتثبيت خطوط الغاز تأكد من خلو المسارات من اية انابيب او وصلات كهرباء اخرى
وصلات اللحام

- تتم وصلات اللحام في موقع التركيب مع مراعاة اتباعها لكافة المواصفات القياسية للتركيب

- قم بإزالة السدادات من وصلات الانابيب بالوحدة بعد التأكد من جاهزية خطوط الغاز والانتهاء منها
جميعا لحماية الخطوط من تكون الرطوبة بداخلها.

- استخدم انابيب نحاسية جافة للتركيب

- استخدم لحام الفضة وتجنب التسخين الزائد لوصلات الانابيب مع مراعاة استخدام النيتروجين اثناء اللحام
لتجنب حدوث الاكسدة

عزل خط الغاز

- لمنع فقد الحرارة وتكثيف بخار الماء يجب عزل جميع خطوط الغاز

وصلات الصرف

- يجب التأكد من مستوي تركيب الوحدة للسماح بصرف المياه المكثفة

- للتأكد من سلامة مسار الصرف يجب ازالة خط الصرف ١٠ درجات مع مراعاة عدم وجود اي مصادم لمياه
الصرف بالخط ويسمح بعمل مصيدة واحدة خارج الوحدة لمنع تسرب اي هواء خارجي للوحدة

وصلات الكهرباء

جميع الوصلات والاسلاك والتارييض يجب ان يكون تبعا للمواصفات القياسية لبلد التركيب

سحب الهواء من خطوط التبريد

يجب استخدام مضخة لعمل سحب هواء بقيمة ١ مم زئبق (١,٣ بار) او اقل لعمل السحب يجب توصيل المضخة
بمحابس الخدمة الموجودة بالوحدة الخارجية.

قم بعمل السحب حتى ضغط ٢ مم زئبق او اقل عند الوصول الي ٢ مم زئبق اي زيادة في الضغط يمكن ملاحظتها
في فترة زمنية محددة اكبر زيادة مسموحة هي 1 مم زئبق خلال 15 دقيقة في حال كانت الزيادة اكبر رقم بكسر
عملية السحب وتدفع النيتروجين داخل الدائرة واعادة السحب من جديد.

شحنات الغاز الاضافية

بعد الانتهاء من عملية سحب الهواء والبدء في تشغيل الوحدة عند زيادة المسافة عن ٦ متر بين الوحدة الداخلية
والخارجية يجب مراعاة اضافة غاز التبريد لكل متر زائد من الانابيب طبقا للجدول التالي:

بمجرد إضافة الكمية المناسبة من مادة التبريد، افتح صمام خط السائل بالكامل وتحقق من ضغط التشغيل

خط السائل	Additional R407C Charge (OZ/FT)	Additional R410A Charge (OZ/FT)	خط السحب	Additional R407C Charge (OZ/FT)	Additional R410A Charge (OZ/FT)
3/8"	0.62	0.51	5/8"	0.04	0.06
3/8"	0.62	0.51	3/4"	0.06	0.09
3/8"	0.62	0.51	7/8"	0.08	0.12
3/8"-1/2"	0.62-1.12	0.51-1.01	1-1/8"	0.14	0.20

ملاحظة: يجب اضافة غاز التبريد R407C و R410A في خط السائل

يجب عدم اضافة اي سائل في خط سحب الضاغط



التركيب والتشغيل

جدول- 3 المبخر والمكثف في نفس المستوى			جدول- 2 المكثف اعلى من المبخر			جدول- 1 المبخر اعلى من المكثف		
الموديل		خطوط	الموديل		خطوط	الموديل		خطوط
الطول المكافئ		الغاز	الطول المكافئ		الغاز	الطول المكافئ		الغاز
رقم 0-80	رقم 81-100	CHCF/CHEF	رقم 0-60	رقم 61-100	CHCF/CHEF	رقم 0-40	رقم 41-60	CHCF/CHEF
1/2	3/8	خط السائل	1/2	3/8	خط السائل	1/2	3/8	خط السائل
3/4	3/4	خط السحب	3/4	3/4	خط السحب	3/4	5/8	خط السحب
1/2	3/8	خط السائل	1/2	3/8	خط السائل	3/8	3/8	خط السائل
3/4	3/4	خط السحب	3/4	3/4	خط السحب	3/4	5/8	خط السحب
1/2	1/2	خط السائل	1/2	1/2	خط السائل	1/2	3/8	خط السائل
3/4	3/4	خط السحب	3/4	3/4	خط السحب	3/4	3/4	خط السحب
1/2	1/2	خط السائل	1/2	1/2	خط السائل	1/2	3/8	خط السائل
3/4	3/4	خط السحب	3/4	3/4	خط السحب	3/4	3/4	خط السحب
1/2	1/2	خط السائل	1/2	1/2	خط السائل	1/2	1/2	خط السائل
7/8	3/4	خط السحب	7/8	3/4	خط السحب	3/4	3/4	خط السحب
1/2	1/2	خط السائل	1/2	1/2	خط السائل	1/2	1/2	خط السائل
7/8	7/8	خط السحب	7/8	7/8	خط السحب	7/8	3/4	خط السحب
1/2	1/2	خط السائل	1/2	1/2	خط السائل	1/2	1/2	خط السائل
7/8	7/8	خط السحب	7/8	7/8	خط السحب	7/8	7/8	خط السحب
5/8	1/2	خط السائل	5/8	1/2	خط السائل	1/2	1/2	خط السائل
1.1/8	1.1/8	خط السحب	1.1/8	7/8	خط السحب	7/8	7/8	خط السحب

ملاحظة جدول 1: قرب المبخر يجب عمل مصيدة مقلوبة علي خط الغاز.

ملاحظة جدول 2: طبقا للمsafات الراسية لخطوط الغاز يجب عمل مصائد للزيت علي خط السحب وتكون المصائد علي مسافات متساوية. قم بعمل مصيدة للزيت كل 4-6 متر ارتفاع.

ملاحظة جدول 3: لا يجب عمل مصيدة علي خط الغاز ومصيدة للزيت.

ملاحظة الطول المكافئ= اطوال الانابيب + الاطوال المكافئة للمحقات الخطوط.

تجهيز السقف للتركيب

- ثقب فتحات التثبيت بالسقف طبقا لابعاد الوحدات المعطاة.
- يجب ترك مسافة كافية من جانب الماكينة للسماح بتوصيل خطوط غاز التبريد.
- يجب استخدام عدد 4 قضبان تثبيت بقطر لا يقل عن 8 مم للتثبيت مع التأكد من قوة وسلامة التثبيت بالسقف والوحدة.
- تأكد من وضع ماص للصدمات مع ملحقات التثبيت اللازمة للتأكد من صحة تثبيت الوحدة.
- يجب التأكد من اعداد مستوي تثبيت الوحدة جيدا للسماح بتصريف المياه المكثفة من الهواء المبرد.
- عند وجود مسافة كافية يمكن وضع لوح عازل بين السقف والوحدة.

خطوات التركيب

- تأكد من سلامة مسارات خطوط الغاز
- تأكد من تقليل الفقد في الضغط عن طريق مراعاة استقامة خطوط الغاز وقللة عدد الملحقات بها
- قم بامالة خط السحب الخارج من الوحدة لتسهيل عودة الزيت الي الوحدة الخارجية
- تأكد من سلامة خطوط الغاز من اي عوائق لسريان الزيت.

التركيب والتشغيل

قبل بدء التشغيل جهز خطوط الغاز

عند انشاء خطوط الغاز يجب اختيار انابيب نحاسية ومواد عزل وتثبيت عالية الجودة طبقا للمتاح في السوق المحلي

التوصيلات الكهربائية

استخدم الاسلاك النحاسية المعزولة. مقطع الاسلاك المطلوبة يتغير طبقا لاطوال الاسلاك. يجب ان تتطابق

وصلات الكهرباء والخامات المستخدمة مع متطلبات وتعليمات الكهرباء ببلد التركيب. تاكد من مطابقة

مواصفات الوحدة الكهربائية مع المتطلبات المحلية تركيبات الكهرباء يجب ان تتضمن مفتاح فصل الكهرباء طبقا

للمواصفات المحلية

مكان تثبيت الوحدة الداخلية

للتاكد من صحة التركيب يجب التاكد من وضع التعليمات التالية في الاعتبار

- يجب أن يكون السقف قويا بما يكفي لدعم وزن الوحدة

- تاكد من اختيار المكان المناسب للتثبيت مع مراعاة ترك مساحات كافية حوله للصيانة وتركيب اي

ملحقات مطلوبة

- تاكد من ثقب اماكن تثبيت الوحدة بالسقف

- تاكد من الا تتجاوز المسافة بين الوحدة الداخلية والخارجية المسافات الموضحة في الجداول التالية:

جدول- 3 المبخر والمكثف في نفس المستوى		
الموديل	خطوط	الطول المكافئ
CHCC/CHEC	الغاز	قدم 0 - 80
24	خط السائل	3/8
	خط السحب	3/8
30	خط السائل	3/8
	خط السحب	5/8
36	خط السائل	3/8
	خط السحب	3/4
42	خط السائل	3/8
	خط السحب	7/8
48	خط السائل	3/8
	خط السحب	1.1/8
60	خط السائل	3/8
	خط السحب	1.1/8

جدول- 2 المكثف اعلى من المبخر		
الموديل	خطوط	الطول المكافئ
CHCC/CHEC	الغاز	قدم 0 - 60
24	خط السائل	3/8
	خط السحب	3/8
30	خط السائل	3/8
	خط السحب	3/4
36	خط السائل	3/8
	خط السحب	3/4
42	خط السائل	3/8
	خط السحب	7/8
48	خط السائل	3/8
	خط السحب	1.1/8
60	خط السائل	3/8
	خط السحب	1.1/8

جدول- 1 المبخر اعلى من المكثف		
الموديل	خطوط	الطول المكافئ
CHCC/CHEC	الغاز	قدم 0 - 40
24	خط السائل	3/8
	خط السحب	3/8
30	خط السائل	3/8
	خط السحب	5/8
36	خط السائل	3/8
	خط السحب	3/4
42	خط السائل	3/8
	خط السحب	7/8
48	خط السائل	3/8
	خط السحب	1.1/8
60	خط السائل	3/8
	خط السحب	1.1/8



Unit Series Description

CHC - Concealed High Efficiency condenser

CHE - Concealed High Efficiency Evaporator

Refrigerant

F : R410A

C : R407C

Cooling Capacity

Nominal MBH

018	-	024
030	-	036
042	-	048
060	-	

Electrical Specifications

CODE	DESCRIPTION
2	415V / 3 ph / 50hz
7	240V / 1 ph / 50hz

CODE	DESCRIPTION
A	First Series
B	Second Series
C	Third Series

التركيب وبدء التشغيل وصيانة معدات تكييف الهواء يمكن أن تكون خطيرة بسبب ضغوط النظام، والمكونات الكهربائية و موقع المعدات. فقط فنيي التركيب والتشغيل المدربين والمؤهلين هم من يسمح لهم تركيب و تشغيل الوحدة.

عند العمل مع المعدات، راقب الاحتياطات في الدليل و كذلك العلامات، والملصقات والعلامات على الوحدة.



إبقاء جميع الأبواب والمسامير المثبتة بالوحدة اثناء نقل الوحدة وتركيب مجاري الهواء. وهذا سيساعد على ضمان أن تبقى مكونات الوحدة متماسكة لتسهيل فتح ابواب الوحدة بعد تركيب مجاري الهواء.



اتبع جميع قوانين السلامة.



تأكد من فصل التيار الكهربائي قبل صيانة هذه المعدات.



قبل التشغيل، تأكد من تأريض الوحدة بشكل صحيح لمنع الإصابة أو الموت من صدمة كهربائية.



لا تقم بتنظيف صمامات تخفيف ضغط غازات التبريد داخل المبنى. صمامات تخفيف الضغط يجب ان يتم تنفيسها في الهواء الطلق.



ارتداء النظارات الواقية و قفازات العمل.



مراعاة الحرص والعناية في المناولة وتخزين ووضع المعدات الضخمة.



عند اللحام تأكد من وجود قماش التبريد وطفافات الحريق بالقرب منك.



لا تضع الوحدات علي جانبها اثناء النقل والتركيب لتلافي حدوث تلف بمكونات الوحدات.



عند تركيب مسامير التثبيت بالوحدة تأكد اولا من داخل الوحدة ان المسامير لن تصيب خطوط الكهرباء او انابيب غاز التبريد.



يجب ألا تعمل وحدة خارج حدود التصميم المحددة في هذا الدليل.



الشركة المصنعة لن تكون مسؤولة عن أي إصابة أو ضرر ناجم عن تركيب وتشغيل أو صيانة غير صحيحة الناتجة عن عدم اتباع الإجراءات والتعليمات المفصلة في هذا الدليل.



تضمن شركة صناعات التبريد والتخزين خلو هذا المنتج من العيوب في صناعة المصنع والمواد في ظل الاستخدام العادي والخدمة. وسوف تقوم باصلاح أو استبدال الأجزاء التي ثبت وجود عيوب فيها كما يلي:

١. خمس سنوات للضواغط المحكمة

٢. سنة واحدة لجميع الأجزاء الأخرى

يتم قياس الفترات الزمنية من تاريخ بدء التثبيت ، أو ثلاثة أشهر من تاريخ الإرسال أيهما يأتي أولاً. ما لم يكن الضمان الممتد متفق عليه كجزء من العقد.

الاستثناءات

العناصر التالية ليست عيوباً في التصنيع ولا يغطيها ضمان COOLEX :

١. الأضرار الناتجة عن المناولة أثناء النقل والعبور والتركيب و خدمة المنتج من قبل الآخرين.

٢. التلف أو العطل الناتج عن انقطاع التيار الكهربائي عن الوحدة ($\pm 10\%$ من الفولتية المقدرة) والمخاطر الكهربائية.

٣. الضرر الناتج عن تطبيق مختلف تم تصميمه من أجله.

٤. الضرر أو العطل الناتج عن الإمداد غير السليم و توزيع الهواء العائد من وإلى المنتج.

٥. الأضرار الناتجة عن خلل في الترموستات أو الاستخدام الخاطئ أو الاتصال الخاطئ بالترموستات.

٦. تلف الأعطال الناتجة عن الصيانة غير السليمة للوحدة.

توصيلات أسلاك كهربائية و / أو تحكم غير صحيح وموقع ترموستات الغرفة.

٧. تركيب وحدات التغليف من ماركات أخرى .

٨. تركيب وصلة أنابيب غير موصى بها وفشل تركيب «مصيدة الزيت» أو U-trap – لوحات الانقسام المركزية.

٩. الأضرار الناتجة عن حادث ، إساءة ، حريق ، تعديل غير مصرح به ، التخزين غير السليم والصواعق والكوارث الطبيعية.

١٠. التلف أو العطل الناتج عن التركيبات الكهربائية أو الميكانيكية للمكونات الخارجية للوحدة.

١١. التلف أو العطل الناتج عن التركيب بحجم أقل أو أكثر قدرة لوحدة تكييف الهواء من قبل الآخرين.

شكرا لاختيارك وحدات تكييف كولكس المنفصلة رجاء تصفح الدليل بعناية لاحتوائه علي معلومات هامة خاصة بالتركيب والتشغيل والصيانة للوحدات لضمان اطول فترة خدمة للوحدة.

الاستلام

عند وصول الوحدة وقبل التوقيع علي اوراق الاستلام يرجى التحقق من سلامة الوحدة وتسجيل اي ضرر لحق بالوحدة باوراق الاستلام وارسلها الي اخر من قام بنقل الوحدات

التفتيش

يرجي التحقق من الشحنة المستلمة طبقا لقائمة الشحن الملحقة بعد التحقق من الوحدة يرجى التأكد من حماية الوحدة بشكل صحيح اثناء التخزين او النقل الي موقع التركيب. هذه الخطوة مهمة للحفاظ على ضمان وحماية الوحدة ضد الأحوال الجوية السيئة أو السرقة أو التخريب في موقع العمل.

تلف بالوحدات

قم بفحص الوحدة عند الاستلام للتأكد من خلوها من اي تلف. في حالة وجود اي تلف او ضرر بالوحدة قم برفع شكوي فورا ضد شركة النقل وتحقق من شركة التامين الخاصة بك

الرموز التالية في هذا الدليل لتنبيهك لمجالات الخطر المحتملة.

ملاحظة: لتسليط الضوء على البيانات الإضافية التي قد تكون مفيدة لك.



تحذير: يستخدم لتحديد المخاطر التي يمكن أن تؤدي إلى الوفاة أو تدمير أو تلف الماكينة.



تنبيه: ويستخدم لتحديد المخاطر التي يمكن أن تؤدي إلى إصابة شخصية أو خلل بالماكينة.



هذا الدليل سوف يضمن التشغيل السليم و أطول عمر تشغيلي للوحدة

جميع الإجراءات الواردة في هذا الدليل، مثل تركيب وتشغيل والصيانة يجب أن يقوم بها شخص

مدرب ومؤهل.



لمزيد من المعلومات يرجى الاتصال بالموزع المعتمد لكوكس ببلدك أو الاتصال بالمصنع.





About RIC

Refrigeration Industries & Storage and Oil Services Company, occupies a leading position as one of the largest industrial companies in Kuwait which established in 1973, it plays a proactive role in providing various services and diverse activities such as manufacturing, storage, and oil services to meet the needs of customers both inside and outside Kuwait.

Since its inception, RIC has been committed to excellence and advancing its progress, leading to the establishment of the brand (Coolex) in 1986, a true milestone in the Kuwaiti market as the first in the region in the sector of manufacturing air conditioning systems and cooling solutions.

Furthermore, the company has consistently empowered its workforce, enhanced safety and competitiveness, and utilized innovative technologies to launch new products that meet the needs of various sectors, contributing to expansion and supporting growth and prosperity.

To ensure the highest performance in the future, RIC harnesses its continuous research to enhance efficiency and quality, while continuing its efforts to manufacture products capable of adapting to climate, environmental, and energy challenges.

Facts throughout the years

- 1973 Warehouses were established by Amiri Decree.
- 1979 RIC Constructed the Medical Cold Stores Complex, the world's largest at that time.
- 1980 RIC Air Conditioning manufacturing plant set up in Sulaibya.
- 1981 Production of Package & Mini-Split A/Cs started under York-Gulf.
- 1984 RIC was listed in Kuwait Stock Exchange.
- 1986 COOLEX brand Production Launched.
- 1991 RIC rebuilt the manufacturing plant destroyed during the war.
- 1997 Achieved ISO Certification ISO 9001:1994.
- 2002 ETL Designed testing lab became fully operational.
- 2004 Privatization of RIC.
- 2010 COOLEX becomes the first A/C Unit to Pass MEW's new regulations.
- 2010 RIC Factory Renovation and Expansion into neighboring countries.
- 2012 Achieved UL & AHRI Certification for Coolex Units.
- 2014 Achieved SASO Certification for Concealed Ducted Split Series.
- 2014 Achieved EUROVENT Certification for Air Handling Units AHU.
- 2014 Achieved UL Certification for Air Cooled Chillers.
- 2015 Achieved ISO 17025 Certification for Psychrometric Laboratory.
- 2016 Achieved Energy Efficiency Certification for Concealed Ducted Split Series & Rooftop Package units (Kingdom of Bahrain).
- 2016 Acquisition of Gulf Paramount for Electrical Services Company.
- 2021 Acquisition of Kuwait Pipes Industries & Oil Services factory, resulting in a change of the company's name from Refrigeration Industries & Storage Co. to Refrigeration Industries & Storage and Oil Services Co.

نبذة عن الشركة

تتوأ شركة صناعات التبريد والتخزين والخدمات النفطية مكانة رائدة باعتبارها واحدة من أكبر الشركات الصناعية في دولة الكويت، والتي تأسست عام 1973 لتؤدي دوراً غير استباقي في تقديم خدمات متعددة وأنشطة متنوعة كالصنيع والتخزين والخدمات النفطية لتلبية مختلف احتياجات العملاء داخل الكويت وخارجها.

ومنذ انطلاقة الشركة وهي تعمل على إبراز التميز ومواصلة مسيرة التقدم مما مكنتها من تأسيس العلامة التجارية (كولكس) عام 1986 والتي جاء ميلادها إنجازاً حقيقياً في السوق الكويتي باعتبارها الأولى في المنطقة في قطاع تصنيع أنظمة التكييف وحلول التبريد في الكويت. وعلى صعيد متصل، أدت الشركة على تمكين قوتها العاملة وتعزيز السلامة والقدرة التنافسية والاستفادة من التقنيات المبتكرة لإطلاق منتجات جديدة تلي مختلف القطاعات وتسهم في تحقيق التوسع والذي من شأنه يدعم النمو والإزهار.

ولضمان أعلى أداء في المستقبل، تسخر الشركة بعونها المستمرة لتعزيز الكفاءة والجودة كما تواصل جهودها لتصنيع منتجات قادرة على التكيف مع تحديات المناخ والبيئة والطاقة.

حقائق وتواريخ

- 1973 تم إنشاء المستودعات بناء على مرسوم أميري.
- 1979 عهدت وزارة الصحة الكويتية لشركة صناعات التبريد بإنشاء مجمع مستودعات مخازن التبريد الطبية، وقد كان هذا المجمع حينها هو الأضخم من نوعه على مستوى العالم، وقد وصلت تكلفته إلى 12.000.000 دينار كويتي.
- 1980 تم إنشاء مصنع مكيفات الهواء التابع لشركة صناعات التبريد في الصليبية.
- 1981 بدء إنتاج أجهزة التكييف المدمجة والمنفصلة الصغيرة تحت علامة York-Gulf.
- 1984 تم قيد شركة صناعات التبريد في سوق الكويت للأوراق المالية.
- 1986 بدء إنتاج مكيفات علامة كولكس.
- 1991 قامت شركة صناعات التبريد بإعادة بناء مصنعها الذي دمرته الحرب.
- 1997 الحصول على شهادة الأيزو 9001:1994
- 2002 بدء تشغيل مختبر فحص وحدات التكييف (ETL)
- 2004 خصخصة شركة صناعات التبريد.
- 2010 كانت وحدات كولكس أول وحدات تكييف هواء تجتاز اللوائح التي أقرتها (وزارة الكهرباء والماء).
- 2010 تم تجديد مصنع شركة صناعات التبريد وبدء التوسع والتصدير إلى الدول المجاورة.
- 2012 الحصول على شهادة UL و AHRI لأجهزة التكييف كولكس.
- 2014 الحصول على شهادة SASO لأجهزة التكييف المنفصلة.
- 2014 الحصول على شهادة EUROVENT لأجهزة مناولة الهواء.
- 2014 الحصول على شهادة UL لتبريد الهواء الشيلر.
- 2015 الحصول على شهادة الأيزو 17025 ISO لخبتر السيكرومترية.
- 2016 الحصول على شهادة كفاء الطاقة لأجهزة التكييف المنفصلة و الوحدات المدمجة (مملكة البحرين).
- 2016 الاستحواذ على شركة بارامونت الخليج للخدمات الكهربائية.
- 2021 الاستحواذ على مصنع الشركة الكويتية لصناعة الأنابيب والخدمات النفطية مما أدى على إثره تغيير اسم الشركة من شركة صناعات التبريد والتخزين إلى شركة صناعات التبريد والتخزين والخدمات النفطية.

الفهرس

رقم الصفحة	المحتويات
03	نبذة عن الشركة.....
04	عام.....
06	الضمان.....
07	اعتبارات السلامة.....
08	التسميات.....
09	التركيب والتشغيل.....
12	نظام التشغيل الآلي.....
13	مساحات الخدمة.....
14	البيانات الكهربائية.....
16	أداء هواء التبريد.....
17	أبعاد الوحدات.....
19	المخطط الكهربائي للوحدة.....
23	تحديد الأعطال.....
26	الصيانة.....
28	تقرير التشغيل.....



شركة صناعات التبريد والتخزين والخدمات النفطية
Refrigeration Industries & Storage and OIL Services Co. KSC

كوالكس راحة تفوق التوقعات

دليل التركيب والتشغيل والصيانة

وحدات التكييف المنفصلة المخفية بالسقف

18-60 (ألف وحدة حرارية بالساعة)



50 Hz

وحدات تكييف منفصلة مع ضاغط محكم للأجواء شديدة الحرارة



Ref no.: MSC 25-5-000

www.coolex.com.kw