

## WARNING 🔊

**DO NOT AIR PRESSURE TEST UNIT!** DOING SO MAY RESULT IN PROPERTY DAMAGE, SERIOUS BODILY INJURY, OR DEATH Refer to Installation Instructions for correct testing procedure.

## FOR BURIED APPLICATIONS ONLY LEAK/SEAL TESTING

Do not air test unit or Teleglide Riser system! Doing so may result in property damage,

personal injury or death. To perform a leak/seal test on the base unit, cap/plug all plumbing connections, remove the cover, and fill the unit with water just above the highest connection. Inspect unit and connections for leaks. Check water level at specific time intervals per local code. Note: This unit has been subjected to a 24 hour water test prior to shipment from the factory.

CUSTOMER SERVICE HOURS: Mon-Fri, 8 am - 5 pm CST



