

Installation and Compaction

- Maximum lift thicknesses of 24 inches (0.6 m)
- Compaction is performed with a tracked excavator or dozer 600 - 1,000 psf (30 - 50 kPa)
- 2 to 4 passes over the UL-FGA layer

