FACE OF BEAM (EXISTING)

FACE OF BEAM (NEW)

(E) 2X6 DECK BOARDS.
REMOVE & REPLACE AS
NEEDED TO REPLACE
EDGE BEAM.

1½"

(E) 2X10@16" JOISTS TO REMAIN.
INSTALL TEMP SHORING &
PRESERVE IN PLACE.

EXISTING

(E) 1-2X10 EDGE BEAM.
REMOVE & REPLACE W/
(N) BEAM. SEE BELOW.

(N) 2X8 DECK BOARD AS NEEDED TO
EXTEND EDGE OF DECK AT (N) EDGE BEAM.
IF CONDITIONS VARY, SELECT APPROPRIATE
2X DECK BOARDS AS NEEDED.

NEW

(N) 2-2X12 EDGE BEAM.

TYP REPAIR DETAIL: REMOVE & REPLACE EDGE BEAM

DETAIL#

SHEET#

SCALE: 3/4"=1'-0"