

JOINTLY SPONSORED BY:



ARCHITECTURAL WOODWORK  
MANUFACTURERS ASSOCIATION  
OF CANADA

ASSOCIATION DES MANUFACTURIERS  
DE MENUISERIE ARCHITECTURALE  
DU CANADA



WOODWORK  
INSTITUTE



3.1

# NORTH AMERICAN ARCHITECTURAL WOODWORK STANDARDS

NOW INCLUDING:

LABORATORY CASEWORK, SEISMIC CASEWORK INSTALLATION,  
RECLAIMED & NON-TRADITIONAL MATERIALS, ANTIMICROBIAL SURFACES,  
ENHANCED CABINET HARDWARE, WEB BASED DESIGN RESOURCES AND MORE.

MEETS OR EXCEEDS ANSI A161.1

# ADVISORY

## Dimensional Change in Architectural Woodwork

This advisory concerns prevention of dimensional problems in architectural woodwork products as the result of uncontrolled relative humidity. It is further intended as a reminder of the natural dimensional properties of wood and wood-based products such as plywood, particleboard, and high pressure decorative laminate (HPDL) and of the routine and necessary care and responsibilities which must be assumed by those involved.

For centuries, wood has served as a successful material for architectural woodwork, and as history has shown wood products perform with complete satisfaction when correctly designed and used. Problems directly or indirectly attributed to dimensional change of the wood are usually, in fact, the result of faulty design, or improper humidity conditions during site storage, installation, or use.

Wood is a hygroscopic material, and under normal use and conditions all wood products contain some moisture. Wood readily exchanges this molecular moisture with the water vapor in the surrounding atmosphere according to the existing relative humidity. In high humidity, wood picks up moisture and swells. In low humidity, wood releases moisture and shrinks. As normal minor fluctuations in humidity occur, the resulting dimensional response in properly designed construction will be insignificant. To reduce humidity related problems, the appropriate recommendations from Section 2 of the AWS should be considered. Uncontrolled extremes can likely cause problems.

Oxidation is a reaction of acids in wood (e.g., tannic acid), with iron, oxygen, and moisture, whether this be relative humidity or direct moisture. Control of moisture is a simple way to protect wood products from stains as a result of oxidation.

Together with proper design, fabrication, and installation, humidity control is obviously the important factor in preventing dimensional change problems.

Architectural woodwork products are manufactured as designed from wood that has been kiln dried to an appropriate average moisture content and maintained at this condition up to the time of delivery. Subsequent dimensional change in wood is and always has been an inherent natural property of wood. These changes cannot be the responsibility of the manufacturer or products made from it. Specifically:

- Responsibility for dimensional change problems in wood products resulting from design rests with the designer/ architect/specifier.
- Responsibility for dimensional change problems in wood products resulting from improper relative humidity exposure during site storage and installation rests with the general contractor.
- Responsibility for dimensional change problems in wood products resulting from humidity extremes after occupancy rests with engineering and maintenance.

**A FRENCH TRANSLATION of NAAWS** is available from AWMAC as an informational service to the global community. Translations are an unofficial, non-normative translation of the official North American Architectural Woodwork Standards (NAAWS) Edition 3.1, published jointly © 2017 by AWMAC and WI. In case of dispute or interpretation misunderstanding, it is the original English version of the NAAWS that must be considered as the reference for any issue related to standards.

**COVER**

**Kelowna Yacht Club,  
British Columbia, Canada  
Meiklejohn Architects**

# North American Architectural Woodwork Standards - 3.1

Effective July 1, 2017

## Sponsor Associations



### Architectural Woodwork Manufacturers Association of Canada (AWMAC)

Unit 02A, 4803 Centre Street NW, Calgary, Alberta, T2E 2Z6, Canada  
Phone: 403-981-7300 <http://awmac.com>



### Woodwork Institute (WI)

P. O. Box 980247, West Sacramento, CA 95798-0247  
Phone: 916-372-9943 / Fax: 916-372-9950  
<http://woodworkinstitute.com>

A Specification of Qualities, Methodologies, and Workmanship  
Requisite to the Production and Installation of Architectural Woodwork

Adopted and Published Jointly, As our Successor,  
Replacement, and Latest Edition of the  
Architectural Woodwork Standards (AWS)

### North American Architectural Woodwork Standards Committee

Kerry DePape - Chair • Mike Hansen - Vice Chair • Heather Zertuche - Secretary

#### WI

Ray Cerulli - California  
Bill Fenstermacher - California  
Mike Hansen - California  
Wayne Alexander - Oregon

#### AWMAC

Martin Boutet - Quebec  
Kerry DePape - Saskatchewan  
Jim Taylor - British Columbia  
Nick Anastas - Ontario

Executive Editor:

**Stanley R. (Rob) Gustafson, CAE, CSI**

CAO - Woodwork Institute

© 2017 jointly by the Architectural Woodwork Manufacturers Association of Canada (AWMAC) and Woodwork Institute (WI). All rights reserved under Pan American and International Copyright Conventions.

Price: \$125.00

# INTRODUCTION

## INTRODUCTION

Like all architectural components of the construction process, woodwork design and configuration possibilities are limited only by the creativity of the design professional. We have included architectural wood products which through evolution have become fixtures of our daily lives and have developed a measurable guideline to ensure these products meet these standards.

While these *North American Architectural Woodwork Standards* (NAAWS) are to be applied to the production and installation of all architectural wood products, the performance of wood products once installed outside of a climate controlled (interior) environment (as identified in Section 2 of these standards) cannot be measured by these standards. Wood products installed in non-climate controlled environments will have varying degrees of performance and should be governed by contractual agreements between the manufacturers and the buyers.

It is the intent of these standards to assist the design professional to specify a variety of millwork products which meet the functional and esthetic requirements of their clients. Encompassing all products in these standards is not possible; but by understanding and applying these standards and implementing the services provided by the signatory Sponsor Associations, the design professional will best serve their client needs and can be confident their quality criteria will be achieved.

When design professionals reference the NAAWS for their projects, they also assume the obligation to enforce that the quality standards are met.

## SPONSORS STATEMENT

The Architectural Woodwork Manufacturers Association of Canada (AWMAC), and the Woodwork Institute (WI) have jointly sponsored development of the *North American Architectural Woodwork Standards* (NAAWS) as our successor, replacement, and latest edition of the *Architectural Woodwork Standards* (AWS).

Publication of NAAWS is being accompanied by a French Canadian translation that will be available from AWMAC as an informational service to the global community. Translations are an unofficial, non-normative translation of the official North American Architectural Woodwork Standards (NAAWS) Edition. In case of dispute or interpretation misunderstanding, it is the original English version of the NAAWS that must be considered as the reference for any issue related to standards.

Development of NAAWS has opened many interesting paths of opportunity for improvement, enhancement, and functionality. The primary distribution platform is a free digital, interactive, full color pdf download; however, print on demand (POD) copies will be available in color for a nominal cost. Unfortunately, print versions will lack any tables of content, index or the interactive functionality of the digital version.

NAAWS is based on the 2nd Edition AWS, including all errata's; however, is now colorized for easier navigation and understanding, including page and table headers and most illustrations. Cautions, warnings, and other important information are highlighted in red text with a yellow/black identifier icon. Some of the specific material PRODUCT requirements have been gathered together into Section Annexes.

Laboratory Casework and Seismic Casework Installation standards have been added. Coverage of reclaimed/recycled wood, nontraditional materials, antimicrobial surfaces, electronic cabinet locks, and cabinet lighting have also been added. Glossary terms have been hot linked with the text body and URL's are now interactive.

Please help in continuing to improve NAAWS with your suggestions, a sample NAAWS Suggestion Form is available on the inside rear cover or can be accessed at <http://naaws-suggestion.com> and sent directly to the NAAWS Committee at: <http://naaws-committee.com>

## DISCLAIMERS & WARRANTIES

**The Sponsor Associations shall not be responsible to anyone for the use of or reliance upon these standards. The Sponsor Associations shall not incur any obligation nor liability for damages, including consequential damages, arising out of or in connection with the use, interpretation of, or reliance upon these standards.**



These *North American Architectural Woodwork Standards* (NAAWS) provide the minimum criteria for the concept, design, fabrication, finishing, and installation of architectural woodwork. Provisions for mechanical and electrical safety have not been included. References to life-safety requirements are included for information only. Governmental agencies or other national standards-setting organizations provide the standards for life-safety requirements.

While the NAAWS does establish Assembly and Installation standards for all wood products, the joint flushness and gap tolerance performance for wood products once installed outside of climate controlled (interior) environments (as identified in Section 2 of these standards) cannot be governed by these Standards.

Illustrations are intended to assist in understanding the standards and may not include all requirements for a specific product or unit, nor do they show the only method of fabrication. Such partial drawings shall not be used to justify improper or incomplete design and/or construction.

# DISCLAIMERS, WARRANTIES and LIMITED USE LICENSE

## DISCLAIMERS & WARRANTIES

The **APPENDIX** is provided as an additional resource to the manufacturer, design professional, educator, user, or certifying organization. The **APPENDIX** is only part of the standards when referenced.



This NAAWS includes citations and quotes from other industry Standards that are neither developed nor published by the Sponsor Associations. The reference to and usage of is not a validation of these citations and quotations outside the context of the NAAWS. Only when these citations and partial quotations are applied in concert with all other related provisions of this NAAWS are these citations and partial quotations recognized for application to architectural woodwork.

If a conflict is found in these standards, it shall be brought to the attention of the North American Architectural Woodwork Standards Committee (NAAWS Committee) by way of the NAAWS Improvement Suggestion Form (found at the Inside Back Cover) and at <http://naaws-committee.com> or <http://naaws-errata.com>. Until such believed conflict is specifically addressed by the NAAWS Committee, the least restrictive requirement shall prevail.

## LIMITED USE LICENSE AGREEMENT

### READ CAREFULLY



### BY USING NAAWS, RECIPIENT ACCEPTS THE TERMS AND CONDITIONS BELOW.

- **Legal Agreement.** This Limited Use License Agreement (the "Limited Use Agreement") constitutes a legal agreement between the addressee and his or her organization (collectively, "Recipient"), the Woodwork Institute and the Architectural Woodwork Manufacturers Association of Canada ("Owners").
  - **Controlling Terms.** This Limited Use Agreement sets forth herein the only terms and conditions governing the use of the enclosed product.
  - **License Grant.** Subject to the terms and conditions of this Limited Use Agreement, Owners hereby grant to Recipient a non-transferable, non-exclusive license to use NAAWS and its updates (the "Materials") for woodwork, millwork and case work design, construction, installation and specification purposes only.
  - **Use Only by Recipient.** Recipient will not transfer the Materials to any person or entity except its employees, nor authorize any third party to use or sell Materials or derivatives thereof.
  - **Compliance with Laws; Precautions.** Recipient shall use Materials in strict accordance with all applicable local, state and federal laws, regulations and guidelines. Recipient understands that the Materials are merely standards, and that they are to be used with caution and prudence, and in consultation with expert advisors.
- **Liability.** Recipient assumes all liability for damages that may arise from the use of the Materials. Owners will not be liable to Recipient for any loss, claim or demand made by the Recipient, or made against the Recipient by any other party, due to or arising from the use of the Materials by the Recipient, except to the extent permitted by law when caused by the gross negligence or willful misconduct of Owners.
  - **Disclaimer of Warranties.** The Owners disclaim any other representations and warranties, expressed or implied, including without limitation any warranty of non-infringement, title, merchantability, or fitness for a particular purpose.
  - **Limitation of Liability.** In no event shall Recipient be entitled to recover from Owners any special, indirect, incidental, consequential, or punitive damages in connection with this agreement or the license granted hereunder.
  - **Entire Agreement and Assignability.** This Limited Use Agreement sets forth the complete and entire agreement of the parties with respect to the subject matter hereof and supersedes and terminates all prior agreements and understandings between the parties. No subsequent amendment or addition to this Limited Use Agreement shall be binding upon the parties unless reduced to writing and signed by the respective authorized officers of the parties. This Limited Use Agreement shall not be assigned or otherwise transferred by Recipient.
  - **Publication.** Any publication or presentation of NAAWS will duly acknowledge Owners as their source.

# COMPONENT & REFERENCE STANDARDS

Most components used to build the products covered within these standards are regulated by separate, individual standards. Some of these standards are accredited by American National Standards Institute (ANSI) which accredits the procedures used in standards development. Some standards are not necessarily accredited by ANSI; however, are equally creditable and industry accepted.

Within NAAWS, these standards are typically used as a minimum starting point and built upon with additional restrictions or requirements as may be appropriate

The following is a listing of those used throughout this NAAWS document, with latest edition of such governing:

## ABRASION RESISTANCE:

ASTM C501 - <http://astm.org>  
NEMA LD3 - <http://nema.org>

## AGRIFIBER:

Shall meet or exceed the performance properties of ANSI A208.1 or 2  
<http://compositepanel.org>

## ANTIMICROBIAL SURFACE:

US - EPA Registered - <http://epa.gov>.  
Canada - Health Canada - <http://hc-sc.gc.ca>

## BUILDING CODE:

International Building Code (IBC)  
<http://iccsafe.org>  
California Building Code (CBC)  
<http://www.bsc.ca.gov/>  
National Building Code (Canada)  
<http://nrc-cnrc.gc.ca/eng/index.html>

## CASEWORK:

ANSI/KCMA 161.1 - <http://www.kcma.org>  
IANSI/BIFMA X5.9 - <http://www.bifma.org>  
SEFA 8 - <http://sefalabs.com>  
UL 210 - <http://www.ul.com/>  
NFPA 70 - <http://www.nfpa.org>  
LM 80 - <http://www.energy.gov>

## CHEMICAL RESISTANCE:

NEMA LD3 - <http://nema.org>  
SEFA 8 - <http://sefalabs.com>

## COMBINATION CORE:

Shall meet or exceed the performance characteristics of ANSI A208.1 or 2  
<http://compositepanel.org>

## DOOR, WOOD:

ANSI/WDMA I.S. 1A  
ANSI/WDMA I.S. 6A  
ANSI/WDMA TM 15  
<https://wdma.site-ym.com>

## ENDANGERED WOOD SPECIES:

Convention on International Trade in  
Endangered Species (CITES)  
<http://cites.org>

## EPOXY RESIN (Countertops):

ASTM D1763 - 00 - <http://astm.org>

## EXTERIOR WINDOWS:

ASTM E 283, Air Infiltration; E 330, Loading;  
E 547, Water Penetration - <http://astm.org>

## FIRE RETARDANCE & FLAME SPREAD:

Underwriters' Laboratories, Test # 723  
<http://ul.com>

ASTM-E-84 Tunnel Test - <http://astm.org>

NFPA 80, National Fire Protection  
Association - <http://nfpa.org>

## GLASS:

ASTM C1036 - <http://astm.org>  
Consumer Product Safety Commission's  
Safety Standard for Architectural Glazing  
Materials - <http://cpsc.gov>

## HARDWARE, CABINET:

ANSI/BHMA A156.9 - Cabinet Hardware  
ANSI/BHMA A156.11 Cabinet Locks  
ANSI/BHMA A156.18 Materials and Finishes  
ANSI/BHMA A156.26 Continuous Hinges  
<http://www.buildershardware.com>

## HARDBOARD:

ANSI A135.4 - <http://compositepanel.org>

## HARDWOOD LUMBER:

NHLA Grading Rules - <http://nhla.com>

## HARDWOOD PLYWOOD (veneer face grade

& thickness, squareness, straightness,  
characteristics, defects):

ANSI/HPVA HP-1 - <http://hpva.org>

## HIGH-DENSITY OVERLAY (HDO):

Voluntary Product Standard PS 1  
<http://nist.gov>

## HIGH-PRESSURE LAMINATE (HPDL):

NEMA's (National Electric Manufacturers  
Association, <http://nema.org>),  
ANSI/NEMA LD-3.

## HISTORIC RESTORATION:

United States Department of the Interior  
<http://doi.gov>  
National Park Service - <http://nps.gov>  
Historic Sites and Monuments  
Board of Canada - <http://parkscanada.gc.ca>

## LABORATORY CASEWORK:

Scientific Equipment and Furniture Association  
(SEFA), <http://sefalabs.com>

## LOW-PRESSURE LAMINATE (LPDL):

Uses - NEMA - LD-3 - <http://nema.org>

## LUMBER, EXTERIOR USE:

US Forest Products Laboratory  
<http://fpl.fs.fed.us/index.php>

## MEDIUM-DENSITY FIBERBOARD (MDF):

Composite Panel Association (CPA)  
ANSI A208.2 - <http://compositepanel.org>

## MEDIUM-DENSITY OVERLAY (MDO):

Voluntary Product Standard PS 1  
<http://nist.gov>

## MOISTURE CONTENT:

US Forest Products Laboratory  
<http://fpl.fs.fed.us/index.php>

## ORIENTED STRAND BOARD (OSB):

Voluntary Product Standard PS 2  
<http://nist.gov>

## ORNAMENT WOODWORK:

US Department of the Interior - <http://doi.gov>  
Historic Sites and Monuments Board of  
Canada - <http://parkscanada.gc.ca>

## PARTICLEBOARD:

ANSI A208.1 - <http://compositepanel.org>

## PRESERVATIVE TREATMENT:

Window and Door Manufacturers Association  
(WDMA) WDMA I.S. 4-15A - <http://wdma.com>

## SOFTWOOD LUMBER:

Voluntary Product Standard PS 20  
<http://nist.gov>

## SOFTWOOD PLYWOOD:

Voluntary Product Standard PS 1  
<http://nist.gov>

## SOLID SURFACE:

ICPA'S (International Cast Polymer  
Association) ANSI/ICPA SS-1,  
<http://icpa-hq.org>

## STAIN RESISTANCE:

ASTM D3023 and C1378 - <http://astm.org>

## SUSTAINABILITY:

Sustainable Architectural Woodwork (SAW)  
<http://sawcertified.org>

## THERMALLY FUSED OVERLAY:

NEMA - LD-3 - <http://nema.org>

# CONTENT GUIDE

	<a href="#">Introduction</a>	<a href="#">User Guide</a>	<a href="#">Preface</a>	<a href="#">Section 01</a>	<a href="#">Section 02</a>	<a href="#">Section 03</a>	<a href="#">Section 04</a>	<a href="#">Section 05</a>	<a href="#">Section 06</a>	<a href="#">Section 07</a>	<a href="#">Section 08</a>	<a href="#">Section 09</a>	<a href="#">Section 10</a>	<a href="#">Section 11</a>	<a href="#">Section 12</a>	<a href="#">Appendix</a>	<a href="#">Glossary</a>	<a href="#">Suggestion</a>
Introduction / Sponsor Statement	<a href="#">004</a>																	
Disclaimer, Warrants / Use License	<a href="#">004</a>																	
Component Standards	<a href="#">006</a>																	
Sponsor Associations	<a href="#">008</a>																	
Standards Review		<a href="#">015</a>	<a href="#">020</a>															
Dimensional Change			<a href="#">021</a>															
Variations in Natural Wood			<a href="#">022</a>															
Moisture			<a href="#">022</a>															
Specification Guidelines			<a href="#">023</a>															
Architectural Drawing Guidelines			<a href="#">024</a>															
System of Measure			<a href="#">024</a>															
Forest Management			<a href="#">025</a>															
Refinishing / Refacing / Refurbishing			<a href="#">025</a>															<a href="#">450</a>
Warranty/Guarantee Language			<a href="#">025</a>															
User's Guide		<a href="#">014</a>																
Resources				<a href="#">027</a>	<a href="#">040</a>	<a href="#">050</a>	<a href="#">082</a>	<a href="#">125</a>	<a href="#">146</a>	<a href="#">188</a>	<a href="#">211</a>	<a href="#">260</a>	<a href="#">303</a>	<a href="#">379</a>	<a href="#">423</a>			
Introductory Information				<a href="#">029</a>	<a href="#">042</a>	<a href="#">052</a>	<a href="#">084</a>	<a href="#">127</a>	<a href="#">148</a>	<a href="#">190</a>	<a href="#">213</a>	<a href="#">262</a>	<a href="#">305</a>	<a href="#">381</a>	<a href="#">425</a>	<a href="#">433</a>		
Advisories				<a href="#">029</a>	<a href="#">042</a>	<a href="#">052</a>	<a href="#">084</a>			<a href="#">190</a>	<a href="#">213</a>	<a href="#">262</a>	<a href="#">305</a>					
Recommendation				<a href="#">029</a>	<a href="#">042</a>		<a href="#">084</a>	<a href="#">127</a>	<a href="#">148</a>	<a href="#">190</a>	<a href="#">213</a>	<a href="#">263</a>	<a href="#">306</a>	<a href="#">381</a>	<a href="#">425</a>			
Specification Considerations				<a href="#">029</a>	<a href="#">042</a>	<a href="#">052</a>	<a href="#">084</a>	<a href="#">128</a>	<a href="#">148</a>	<a href="#">190</a>	<a href="#">214</a>	<a href="#">263</a>	<a href="#">307</a>	<a href="#">381</a>	<a href="#">426</a>			
Design Resources Menu				<a href="#">030</a>		<a href="#">068</a>	<a href="#">103</a>	<a href="#">135</a>	<a href="#">162</a>	<a href="#">194</a>	<a href="#">231</a>	<a href="#">274</a>	<a href="#">318</a>	<a href="#">390</a>	<a href="#">426</a>			
Compliance Requirements				<a href="#">031</a>	<a href="#">046</a>	<a href="#">069</a>	<a href="#">104</a>	<a href="#">136</a>	<a href="#">163</a>	<a href="#">195</a>	<a href="#">232</a>	<a href="#">275</a>	<a href="#">319</a>	<a href="#">391</a>	<a href="#">427</a>			
Product				<a href="#">032</a>	<a href="#">047</a>	<a href="#">071</a>	<a href="#">105</a>	<a href="#">137</a>	<a href="#">166</a>	<a href="#">196</a>	<a href="#">235</a>	<a href="#">278</a>	<a href="#">322</a>	<a href="#">394</a>	<a href="#">428</a>			
Product Annexes											<a href="#">241</a>		<a href="#">352</a>	<a href="#">400</a>				
Laboratory Casework -													<a href="#">359</a>					
Installation									<a href="#">180</a>	<a href="#">204</a>	<a href="#">250</a>	<a href="#">296</a>	<a href="#">361</a>	<a href="#">412</a>	<a href="#">430</a>			
Seismic Installation - Annex 10-D													<a href="#">368</a>					
Tests							<a href="#">144</a>	<a href="#">185</a>	<a href="#">208</a>	<a href="#">257</a>	<a href="#">300</a>	<a href="#">376</a>	<a href="#">420</a>					
Reference Directory/Listing																		<a href="#">434</a>
Code Sources																		<a href="#">437</a>
Adhesive Guidelines																		<a href="#">438</a>
Specific Gravity/Weight of Hardwoods																		<a href="#">439</a>
Joinery Details																		<a href="#">441</a>
Chemical & Stain Resistance (SEFA)																		<a href="#">443</a>
Casework Integrity (SEFA)																		<a href="#">445</a>
Cabinet Design Series (CDS)																		<a href="#">451</a>
Conversion Tables																		<a href="#">471</a>
Glossary																		<a href="#">474</a>
Suggestion Submittal Form																		<a href="#">518</a>

# SPONSOR ASSOCIATIONS

## Architectural Woodwork Manufacturers Association of Canada (AWMAC)



ASSOCIATION DES MANUFACTURIERS DE MENUISERIE ARCHITECTURALE DU CANADA

### **AWMAC – ARCHITECTURAL WOODWORK MANUFACTURERS ASSOCIATION OF CANADA**

**Mission:** To develop and promote the use of AWMAC’s quality standards for the manufacturing and installation of architectural woodwork, and promote assurance of adherence to those quality standards and sustainable practices in the woodworking industry.

The Architectural Woodwork Manufacturers Association of Canada (AWMAC) has its roots in the millwork industry in Vancouver, Canada going back to the 1920’s. Evolving from regional associations, AWMAC has grown to become a nationally registered Not-for-profit Corporation. AWMAC’s strength is the linkage between the national association and the eight regional AWMAC Chapters located coast to coast. Members include manufacturers, installers, industry suppliers, educational institutions, advisors, and design professionals. Today, AWMAC is the national voice of the Canadian Architectural Woodwork industry and is committed to:

- Partnering with other associations to define, develop and maintain North American Architectural Woodwork Standards (NAAWS). Our major and equal partner of this latest standard is the [Woodwork Institute \(WI\)](#) based in California, USA.
- Collaborating with educational institutions to enhance the apprentice and technical programs and to ensure quality human resources for the architectural woodwork industry.
- Communicating the traditional, and innovative architectural woodwork methods and materials to governments, industry, and design professionals, through various marketing media including seminars, tradeshows and websites.

- Publishing a Membership Directory and The Sounding Board, a newsletter containing information and photos from projects across the country.
- Educating and testing its members so they have a working knowledge of the NAAWS to be used as a manufacturing and reference tool.
- Reporting to members at an Annual General Meeting and Convention.
- Developing and maintaining the Guarantee and Inspection Service (GIS) designed to assist the Owner and Design Authority. This program is administered by the chapters (See below).

In conjunction with AWMAC, Regional AWMAC Chapters provide:

- A review and edit service for Design Professionals of their existing specifications for Finish Carpentry, Architectural Woodwork and Wood Doors.
- Inspections and Expert Opinions to resolve conflicts that may occur on projects.
- Networking opportunities, industry specific education, and learning opportunities for both AWMAC members and the design community.
- Annual Awards that celebrate the best in quality, service, and design excellence of manufacturers, suppliers, and design professionals.
- Promotion and administration of the Guarantee and Inspection Service (GIS). The GIS Program (when specified by the design professional) monitors and guarantees projects that specify AWMAC standards.

### **AWMAC GUARANTEE AND INSPECTION SERVICE (GIS)**

Initiated in 1990, AWMAC created a service that would ensure that the quality of materials and workmanship of the architectural woodwork specified on any project are in compliance with the current AWMAC standards at time of tender.

Regional chapters manage the GIS monitoring program. The AWMAC Guarantee and Inspection Service program (GIS) must be specified and be considered an integral component of the scope of work. Maintaining and enhancing this program is a major focus of AWMAC to deliver a comprehensive and uniform platform of inspection service across the country.

When Design Professionals reference the AWMAC Standards in their specifications on projects, they assume the obligation to ensure the quality standards are met. The GIS program alleviates the Design Professional obligation burden of ensuring the material and method quality standards are met.

### **GIS INSPECTORS**

Independent, Trained and Certified Inspectors review, inspect and report on pre-tender specifications, sample units (when required), and shop drawings. Inspectors also perform comprehensive on-site inspections of the architectural woodwork and provide a final written audit report outlining non-conformities to the standard.



ASSOCIATION DES MANUFACTURIERS  
DE MENUISERIE ARCHITECTURALE  
DU CANADA

## Architectural Woodwork Manufacturers Association of Canada (AWMAC)

### GIS OBJECTIVE

The objectives of the Guarantee and Inspection Service are:

1. To assist the design authority in achieving quality architectural woodwork.”
2. To offer the owner, customer, design authority, and woodwork contractor an assurance that strict monitoring of the architectural woodwork requirements on a given project will meet the specified AWMAC standards.

### GIS WORDING FOR SPECIFICATIONS

Architectural woodwork shall be manufactured [and/or] installed to the current AWMAC Architectural Woodwork Standards and shall be subject to an inspection at the factory and/or site by an appointed AWMAC Certified Inspector. Inspection costs shall be included in the tender price for this project. (Contact your local AWMAC Chapter for details of inspection costs). Shop drawings shall be submitted to the AWMAC Chapter office for review before work commences. Work that does not meet the AWMAC Architectural Woodwork Standards, as specified, and requested by the Design Authority shall be replaced, reworked and/or refinished by the architectural woodwork contractor, to the approval of AWMAC, at no additional cost to the owner.

Suggested wording is available on AWMAC’s website, <http://awmac.com>.

### GIS GUARANTEE

If the woodwork contractor is an AWMAC Manufacturer member in good standing, a two (2) year AWMAC Guarantee Certificate will be issued. The AWMAC Guarantee shall cover replacing, reworking and/or refinishing deficient architectural woodwork due to faulty workmanship or defective materials supplied and/or installed by the woodwork contractor, which may appear during a two (2) year period following the date of issuance.

If the woodwork contractor is not an AWMAC Manufacturer member, they shall provide the owner with a two (2) year maintenance bond, in lieu of the AWMAC Guarantee Certificate, to the full value of the architectural woodwork contract.

### CONTACT AWMAC

All chapters contact information is listed on the website, after selecting the region or as shown below:

Chapter Offices are located in the following Regions:

#### AWMAC British Columbia Chapter

Vancouver BC  
<http://bc.awmac.com>

#### AWMAC Northern Alberta Chapter

Edmonton Alberta  
<http://nab.awmac.com>

#### AWMAC Southern Alberta Chapter

Calgary Alberta  
<http://sab.awmac.com>

#### AWMAC Saskatchewan Chapter

Saskatoon Saskatchewan  
<http://sk.awmac.com>

#### AWMAC Manitoba Chapter

Winnipeg Manitoba  
<http://mb.awmac.com>

#### AWMAC Ontario Chapter

Mississauga Ontario  
<http://on.awmac.com>

#### AWMAC Quebec Chapter

Montreal Quebec  
<http://pq.awmac.com>

#### AWMAC Atlantic Chapter

Halifax Nova Scotia  
<http://atl.awmac.com>

For more information about AWMAC, the latest AWMAC quality standard manual, the regional chapters and the GIS Program visit our website at <http://awmac.com>.

# SPONSOR ASSOCIATIONS

## Woodwork Institute (WI) WOODWORK INSTITUTE

**ESTABLISHED IN 1951** as a not-for-profit trade organization dedicated to the preservation of the use of wood as a building material, Woodwork Institute (WI) has grown to a national organization whose primary purpose is to assure excellence and craftsmanship in woodwork.

As the Institute has grown, so too has its Quality Control Options. As a means of establishing quality control, WI and AWMAC have collaborated on the *North American Architectural Woodwork Standards* (NAAWS). This book is the essence of building and installing quality products.

Unique to WI are its certification programs which include the Certified Compliance Program (CCP), the Monitored Compliance Program (MCP) and the Certified Seismic Installation Program (CSIP).

As well, WI provides Independent Inspection Services (IIS) for projects and Expert Witness Services (EWS), when requested by a party to the contract.

For general information please visit WI's website at <http://woodworkinstitute.com> or call the administrative office at (916) 372-9943.

### DIRECTORS OF ARCHITECTURAL SERVICE (DAS)

Our Director's of Architectural Services provide a wealth of knowledge to the architectural community and the construction industry.

Their primary focus is compliance verification (inspection services) through CCP, MCP and CSIP.

Concentrating on the design community, the DAS are available to review specifications, answer millwork related requests for information, consult on design issues and present seminars for continuing education units as required by the America Institute of Architects (AIA). As well, the DAS are available to assist a design professional should they need an impartial opinion about millwork fabricated or installed on a project.

Focusing on fabricators and installers the DAS are available for unbiased consultation regarding specification interpretation, compliance issues, shop-drawing protocol, standards interpretation and other matters at no cost.

### ACCREDITED MILLWORK COMPANY (AMC)

Our AMC affiliates represent the best fabricators and installers in our industry, for more information, visit: <http://woodworkinstitute.com/membership-listing-2/>



### CERTIFIED MILLWORK PROFESSIONALS

Our CMP affiliates represent the knowledge base of our industry, for more information, visit: <http://woodworkinstitute.com/membership-listing-2/>



### MILLWORK INDUSTRY PARTNERS

Our MIP's (Millwork Industry Partners) represent the best of our industries material suppliers, for more information, visit: <http://woodworkinstitute.com/membership-listing-2/>



### ACKNOWLEDGED PRODUCT LISTINGS



If it's listed, you are assured it meets NAAWS minimum requirements, for more information, visit:

<http://woodworkinstitute.com/acknowledged-product-listing/>

### PRE-QUALIFY YOUR BIDDERS



With a discipline of bidder pre-qualification wherein your specifications protect you and your customer from the unknown. Include in your specification:

"To be eligible to bid or negotiate this job, the subcontractor must be a Woodwork Institute Accredited Millwork Company (AMC) in good standing, for more information, visit:

<http://woodworkinstitute.com/architectural-resources/quality-assurance>



## CERTIFIED COMPLIANCE PROGRAM (CCP)



Is a discipline of quality control used in conjunction with the NAAWS providing an unbiased means of ensuring conformance to a project's plans and specifications. CCP, together with the use of the desired Grade(s) in the specifications, informs all parties of the design professional's expectations, without bidder discrimination.

By specifying CCP, which covers both shop drawings and fabrication/installation of millwork products, the design professional is assured that all items conform to the contract documents and the requirements of the NAAWS.

CCP does not restrict bidding or bidders. Anyone may use the CCP inspection service without the requirement of being an Affiliate of WI.

Evidence of certification is provided by issuance of a Certified Compliance Certificate, listing the items certified, the applicable NAAWS Grade, and whether installation is included. Additionally, if so specified, shop drawings and each elevation of casework and/or countertops are labeled with an individually serial-numbered "Certified Compliance Label." Find further information at:

<http://woodworkinstitute.com/services/certified-compliance-program>

## MONITORED COMPLIANCE PROGRAM (MCP)



Is a discipline of quality affirmation used in conjunction with the NAAWS which provides ongoing reviews/inspections of a project from its beginning through completion.

The design professional, in specifying MCP, is ensuring that strict conformance to his/her design intent is adhered to throughout the millwork fabrication and installation process.

Shop drawings, millwork products, finishing and installation (of all involved parties) will be progressively inspected for compliance to the contract documents and the specified NAAWS Grade(s). Reports will be issued to all involved parties at each review/inspection.

Evidence of compliance is provided by issuance of a Monitored Compliance Certificate, listing the items certified, the applicable NAAWS Grade(s) and whether installation is included. Additionally, if so specified, shop drawings and each elevation of casework and/or countertops are labeled with an individually serial-numbered "Monitored Compliance Label". Find further information at:

<http://woodworkinstitute.com/services/monitored-compliance-program/>

## CERTIFIED SEISMIC INSTALLATION PROGRAM (CSIP)



Is a standalone Quality Control and Seismic Compliance Option, but can be specified in conjunction with CCP or MCP. CSIP offers design professionals and property owners specified use of WI's seismic casework pre-approvals from the Office of Statewide Health Planning and Development (OSHPD) without additional engineering costs and/or requirements. It further assures:

- Proper backing has been installed in the walls when and where required.
- Certified acknowledgement that the project's seismic casework installation requirements meet OSHPD and/or the Division of State Architect (DSA) compliance requirements.

Find further information at:

<http://woodworkinstitute.com/services/certified-seismic-installation-program/>

## INDEPENDENT INSPECTION SERVICE (IIS)

Is available on a fee basis with respect to issues pertaining to the architectural woodwork industry as defined within or covered by the NAAWS. Find further information at:

<http://woodworkinstitute.com/services/other-services/>

## EXPERT WITNESS SERVICE (EWS)

Expert Witness Service is available on a fee basis with respect to issues pertaining to the architectural woodwork industry as defined within or covered by the NAAWS. Find further information at:

<http://woodworkinstitute.com/services/other-services/>

# DESIGN PROFESSIONAL TOOLS

The **SPONSOR ASSOCIATIONS** and **NAAWS** offer the following tools to assist Design Professionals:

## Within Canada

### Architectural Woodwork Manufacturers of Canada Offers:

- **GUIDE SPECIFICATIONS** – Available for download in interactive digital format, including specification wording for AWMAC's national quality assurance program (GIS) at: <http://awmac.com/guide-specifications>.
- **GUARANTEE and INSPECTION SERVICE (GIS)** – The GIS is a national program designed to ensure that project owners get value and quality for their investment by supporting architects and design professionals to achieve project plans and specifications; and helping contractors avoid problems such as cost overruns, delays and loss of reputation. More information s available at: <http://awmac.com/gis>.
- **CONSULTATION and/or SPECIFICATION REVIEW** – Contact any of the local chapters for more information on the NAAWS or any other Architectural Woodwork Questions you may have, or if you would like your specifications reviewed for compliance to the NAAWS.
- **SEMINARS and PRESENTATIONS** – Contact your local chapter to arrange an informative presentation on any Architectural Woodwork topic. Some topic options – GIS, NAAWS, How to Specify Quality Architectural Woodwork.
- **INSPECTION SERVICE** – A GIS Certified Inspector will inspect specific areas of concern on a project for compliance to the NAAWS and provide a written report. Contact your local chapter for more information.
- **EXPERT OPINION** – An expert will be appointed to inspect specific areas of concern on a project and provide a written report. Contact your local chapter for more information.

### AWMAC CHAPTERS

- AWMAC British Columbia Chapter, Vancouver BC: <http://bc.awmac.com>
- AWMAC Norther Alberta Chapter, Edmonton Alberta: <http://nab.awmac.com>
- AWMAC Southern Alberta Chapter, Calgary Alberta: <http://sab.awmac.com>
- AWMAC Saskatchewan Chapter, Saskatoon Saskatchewan: <http://sk.awmac.com>
- AWMAC Manitoba Chapter, Winnipeg Manitoba: <http://mb.awmac.com>
- AWMAC Ontario Chapter, Toronto Ontario: <http://on.awmac.com>
- AWMAC Quebec Chapter, Montreal Quebec: <http://qc.awmac.com>
- AWMAC Atlantic Chapter, Halifax Nova Scotia: <http://atl.awmac.com>

## Within United States

### Woodwork Institute Offers:

- **GUIDE SPECIFICATIONS** - NAAWS based offerings, in interactive digital format with optional quality control options can be found and downloaded at: <http://woodworkinstitute.com/architectural-resources/specification-language/>
- **AIA SEMINARS** - American Institute of Architects (AIA) Continuing Education System (CES) program compliant. Current offerings and request access can be found at: <http://woodworkinstitute.com/architectural-resources/aia-seminars/>
- **CONSULTATION and/or SPECIFICATION REVIEW** - Our Directors of Architectural Services (DAS) are available upon request, a listing and contact information can be found at: <http://woodworkinstitute.com/about-us-2/about-us/>
- **ACCREDITED FABRICATORS and INSTALLERS** - Our AMC's (Accredited Millwork Company) represents the best fabricators and installers in our industry, a listing and contact information can be found at: <http://woodworkinstitute.com/membership-listing-2/>
- **ACKNOWLEDGED PRODUCTS LISTING** - If it's listed, you are assured it meets NAAWS minimum requirements, find the listing at: <http://woodworkinstitute.com/acknowledged-product-listing/>
- **QUALITY CONTROL OPTIONS** - Including:
  - **CERTIFIED COMPLIANCE PROGRAM (CCP)**
  - **MONITORED COMPLIANCE PROGRAM (MCP)**
  - **CERTIFIED SEISMIC INSTALLATION PROGRAM (CSIP)**
  - **EXPERT WITNESS SERVICE**
  - **INDEPENDENT INSPECTION SERVICE**
  - **SITE COMPLIANCE INSPECTION SERVICE**

Full details available at: <http://woodworkinstitute.com/>



## Internationally

### North American Architectural Woodwork Standards (NAAWS)

#### Offers:

- **CABINET DESIGN SERIES (CDS)** - Eliminate the need to include casework elevations in your architectural drawings, check out the CDS system in NAAWS "Design Resources" and access the cad files at: [https://www.naaws-committee.com/?page\\_id=259](https://www.naaws-committee.com/?page_id=259)
- **DESIGN RESOURCES** - A perpetually expanding, web based resource of pictures, videos, illustrations, ideas and design concepts for inspiring thought and design creativity - accessible at: <http://naaws-design-resources.com>

## CONTRIBUTING ASSOCIATIONS

### The Following Associations Are Gratefully Acknowledged:

---

American Institute of Architects (AIA)  
American National Standards Institute (ANSI)  
American Society of Interior Designers (ASID)  
American Society for Testing and Materials (ASTM)  
Architectural Woodwork Institute (AWI)  
Builders Hardware Manufacturers Association (BHMA)  
Composite Panel Association (CPA)  
Construction Specifications Canada (CSC)  
Construction Specifications Institute (CSI)  
The Engineered Wood Association (APA)  
Hardwood Plywood & Veneer Association (HPVA)  
Interior Design of Canada (IDC)  
International Solid Surface Fabricators Association (ISSFA)  
International Wood Products Association (IWPA)  
Laminating Materials Association (LMA)  
National Electrical Manufacturers Association (NEMA)  
National Fire Protection Association (NFPA)  
National Hardwood Lumber Association (NHLA)  
Royal Architectural Institute of Canada (RAIC)  
Scientific Equipment & Furniture Association (SEFA)  
Stair Manufacturer Association (SMA)  
Sustainable Architectural Woodwork (SAW)  
Western Wood Products Association (WWPA)  
Window and Door Manufacturers Association (WDMA)  
Wood Moulding and Millwork Producers Association (WMMPA)

# North American Architectural Woodwork Standards - 3.1

# USER'S GUIDE

<b>Introduction . . . . .</b>	<b><a href="#">15</a></b>
<b>Non-Compliance Portions . . . . .</b>	<b><a href="#">15</a></b>
<b>Standards Sub-division . . . . .</b>	<b><a href="#">15</a></b>
<b>Section Formatting . . . . .</b>	<b><a href="#">18</a></b>

# USER'S GUIDE

## INTRODUCTION

Sponsored by the Architectural Woodwork Manufacturers Association of Canada, and the Woodwork Institute (hereinafter called the Sponsor Associations), these joint standards represent the best of what these organizations have to offer in defining the minimum requirements of material and workmanship for the fabrication and installation of architectural woodwork in a climate controlled interior environment. The joint standards are based on three definitive levels of materials and workmanship: Economy, Custom, and Premium Grade.

The North American Architectural Woodwork Standards (NAAWS) is both a voluntary and a definitive document, intended to spell out the requirements for satisfactory performance when referenced as part of contract documents.

Sections in this document are interrelated and are intended to be used together, not in part. For example, if a project specification requires compliance with Section 10, then compliance with Sections 1-5 along with the Appendix and the Glossary are also required, as applicable.



NAAWS is primarily designed for free digital distribution and use on all types of computers, tablets and smart phones in interactive PDF format. Page flow is intended as a singular column with all header/footer information and page numbers in the same location on each page. In the interactive PDF Version all URL's are hot-linked and each page uses the following navigation buttons that will take you:

-  To the **CONTENT GUIDE**.
-  Back one page.
-  To previously viewed page.
-  Forward one page.
-  To the first page of each section/portion.

**GRADE HIGHLIGHTING**, is offered within the Compliance Requirements Rule Tables by use of the following four additional control buttons with the yellow highlight indicating which button is active:

	Economy Grade
	Custom Grade
	Premium Grade
	Clear

**PRINT ON DEMAND (POD)** versions of the standards are available for purchase at a nominal charge with the navigation buttons removed and replaced with page side tabs coordinated to match with the back cover directory.

**CONTENT GUIDE**, located within the Introduction, provides an interactive page links through a table formatted grid to help you navigate throughout and within each section/portion of the standard.

**DESIGN RESOURCES** uses the following icon to bring attention to such: The new Design Resources is a perpetually expanding, web based resource of pictures, videos, illustrations, ideas and design concepts for inspiring thought and design creativity - assessable at: <http://naaws-design-resources.com>



**SPECIFICATION CONSIDERATIONS** and other areas of importance use the following icon and **red text** to bring attention to them.



**INSIDE FRONT COVER** provides an important **PRODUCT ADVISORY** regarding dimensional change problems in architectural woodwork and its review and consideration is recommended by the Sponsor Associations. It also provides information about the front cover picture and translation offerings/stipulations.

**INSIDE BACK COVER** provides reference for access to an **IMPROVEMENT SUGGESTION FORM** which can be filled out and submitted online through the NAAWS Committee website at <http://www.naaws-committee.com>.

**SECTIONS** are organized into two distinct **NON-COMPLIANT** and **COMPLIANT** elements, that of:

- **Introductory Information** - Consisting of educational materials and resources relevant to the Section that are not standards or compliance requirements, such as:
  - Introduction
  - Advisories
  - Recommendations
  - Specification Considerations
  - General Information
  - Design Resources
- **Compliance Requirements** - Consisting of the standards requirements (rules) which are further organized into:
  - **Basic Considerations**, including grades, general subject matter and industry practices applicable to the scope of work.
  - **Product**, covering minimum manufacturing (material, machining, and assembly) requirements.
  - **Installation**, minimum installation requirements (not applicable to Sections 1-5).
  - **Test** - covers the ways of verifying compliance with the standards (not applicable to Sections 1-4).

## NON-COMPLIANCE PORTIONS

- **INTRODUCTION**
- **USER'S GUIDE**
- **INTRODUCTORY INFORMATION** within each Section

# USER'S GUIDE

## STANDARDS SUBDIVISION

- **INTRODUCTION** - Provides Introductory and Sponsor statements, Disclaimers, interactive Content Guide and brief introduction of the Sponsor Associations.
- **USER'S GUIDE** - Provides a tool to enhance your understanding of the philosophy behind the layout of these standards and its use.
- **PREFACE** - Provides information in areas of importance that should be reviewed in advance of using the standards.
- **SECTION 1 - SUBMITTALS** - Addresses minimum submittal requirements, including shop drawings, samples, etc.
- **SECTION 2 - CARE & STORAGE** - Addresses minimum care and storage (environmental condition) requirements to be maintained before, during, and after the delivery, storage, and installation of product.
- **SECTION 3 - LUMBER** - Addresses the minimum acceptable performance and appearance characteristics of lumber to be used within the standards' product Sections 6-12. This section does not attempt to establish raw material grades. It defines the minimum characteristics for lumber when used in a product governed by Sections 6-12 based on the Grade specified.
- **SECTION 4 - SHEET PRODUCTS** - Addresses the minimum acceptable performance and appearance characteristics of panel materials to be used within the standards' product Sections 6-12. This section does not attempt to establish raw material grades. It defines the minimum characteristics for panels when used in a product governed by Sections 6-12 based on the Grade specified.
- **SECTION 5 - FINISHING** - Addresses the

minimum acceptable performance and appearance characteristics for factory and field finishing used within the standards' product Sections 6-12 based on the Grade specified.

- **SECTION 6 - MILLWORK** - Addresses the minimum acceptable millwork fabrication and installation requirements for standing and running trim, door frames, window frames, sashes, blinds and shutters, screens, ornamental and miscellaneous millwork based on the Grade specified.
- **SECTION 7 - STAIRWORK & RAILS** - Addresses the minimum acceptable millwork fabrication and installation requirements for wood stairs, integral trim, handrails and guardrails based on the Grade specified.
- **SECTION 8 - WALL/CEILING SURFACING & PARTITIONS** - Addresses the minimum acceptable millwork fabrication and installation requirements for wood veneer, solid wood, stile and rail wood, decorative laminate, solid surface and solid phenolic wall/ceiling and partition surfacing based on the Grade specified.
- **SECTION 9 - DOORS** - Addresses the minimum acceptable millwork fabrication and installation requirements for passage doors of flush and stile & rail construction with wood and HPDL faces based on the Grade specified.
- **SECTION 10 - CASEWORK** - Addresses the minimum acceptable millwork fabrication and installation requirements for wood, decorative laminate and solid phenolic faced casework based on the Grade specified.
- **SECTION 11 - COUNTERTOPS** - Addresses

the minimum acceptable millwork fabrication and installation requirements for tops, wall caps, splashes and sills of high pressure decorative laminate, wood, solid surface, solid phenolic, epoxy resin and natural/engineered stone based on the Grade specified.

- **SECTION 12 - HISTORIC RESTORATION WORK** - Addresses the minimum acceptable millwork fabrication and installation requirements for historic restoration work, including stripping, repairs and finishing.
- **APPENDIX** - Provides additional resources to the manufacturer, design professional, educator, user, or certifying organization and is only part of these standards when referenced. For your convenience where the **APPENDIX** is referenced it is flagged by the above icon:  

- **GLOSSARY** - Provides definitions and in most cases illustrations or pictures of terms used throughout these standards.

# USER'S GUIDE

## SECTION FORMATTING

The **INTRODUCTORY INFORMATION** portion is in triple column, text book format with a non-shaded header including Section number, title, and Introductory Information Statement recognizing that the included text is non-compliant in nature similar to the following:

<b>SECTION 8</b> Wall/Ceiling Surfacing and Partitions		
		introductory information
<b>FLITCH SELECTION</b> The design professional may choose to see samples of veneer flitches to evaluate color and grain characteristics for other than pre-manufactured sets. This must be specified. Unless specified, layup is determined by the manufacturer.	• Since it will take at least 6 flitches, with a gross square footage of 2,500 square feet each to meet the project needs, give careful consideration to the following key criteria: <ul style="list-style-type: none"> <li>• <b>Length</b> - Is the length adequate for the requirements? The flitch needs to be at least 6" (152 mm) longer than the panel</li> </ul>	<b>VARIATIONS in NATURAL WOOD PRODUCTS</b> Wood is a natural material, with variations in color, texture, and figure. These variations are influenced by the natural growing process and are uncontrollable by the manufacturer. The color of wood within a tree varies between the "canwood"

Example: User's Guide - 001

Each page also includes a footer stating the page number, document name, and edition as follows:

North American Architectural Woodwork Standards - 3.1 220	©2017 AWMAC   WI
--	------------------

Example: User's Guide - 002

However in the Compliance Requirements portion the footer also includes an Errata statement advising "As may be updated by errata at [naaws-errata.com](http://naaws-errata.com)." and an effective date of the standard as follows:

North American Architectural Woodwork Standards - 3.1 234 Effective July 1, 2017	©2017 AWMAC   WI As may be updated by errata at <a href="http://naaws-errata.com">http://naaws-errata.com</a>
--	--

Example: User's Guide - 003

The **Compliance Requirement Sections** have a green shaded header with Section number, title, and compliance requirements statement recognizing that the included text is part of the standards for compliance purposes similar to:

<b>SECTION 8</b> Wall/Ceiling Surfacing and Partitions GENERAL/PRODUCT/INSTALLATION/TEST		Where the <b>E, C, or P</b> icon is not indicated, the rule applies to all Grades equally. <table border="1" style="display: inline-table; margin-left: 10px;"> <tr> <td style="padding: 2px;">E</td> <td style="padding: 2px;">C</td> <td style="padding: 2px;">P</td> </tr> </table>	E	C	P				
E	C	P							
		compliance requirements							
<table border="1" style="width: 100%;"> <tr> <td style="background-color: #f0f0f0; padding: 2px;"><b>8.4.5</b></td> <td style="padding: 2px;"><b>Basic Material Rules</b></td> </tr> <tr> <td style="padding: 2px;">LUMBER, VENEERED PROFILE or SHEET PRODUCTS shall be of</td> <td style="padding: 2px;"></td> </tr> </table>	<b>8.4.5</b>	<b>Basic Material Rules</b>	LUMBER, VENEERED PROFILE or SHEET PRODUCTS shall be of		<table border="1" style="width: 100%;"> <tr> <td style="background-color: #f0f0f0; padding: 2px;"><b>8.4.5</b></td> <td style="padding: 2px;"><b>Basic Material Rules</b></td> </tr> <tr> <td style="padding: 2px;">▲ From previous column</td> <td style="padding: 2px;"></td> </tr> </table>	<b>8.4.5</b>	<b>Basic Material Rules</b>	▲ From previous column	
<b>8.4.5</b>	<b>Basic Material Rules</b>								
LUMBER, VENEERED PROFILE or SHEET PRODUCTS shall be of									
<b>8.4.5</b>	<b>Basic Material Rules</b>								
▲ From previous column									

Example: User's Guide - 004

# USER'S GUIDE

## SECTION FORMATTING (continued)

Sections 8, 10 and 11 also include separate ANNEXES within their Compliance Requirements with a unique header similar to:

<b>SECTION 8 - ANNEX 8A</b> <b>Wood Wall/Ceiling Surfacing and Partitions</b> <small>GENERAL/PRODUCT/INSTALLATION/TEST</small>		<small>Where the E, C, or P icon is not indicated, the rule applies to all Grades equally</small>	<b>E C P</b>
<b>compliance requirements</b>			
<b>Additional Requirements for Wood Wall/Ceiling Surfacing and Partitions</b>			
8.4.5.A	Additional Requirements for Wood Material Rules	8.4.5.A	Additional Requirements for Wood Material Rules

Example: User's Guide - 005

All text is laid out in two column or table numerical, outline format, wherein each statement, issue, or rule becomes a specific, uniquely referenced item. Additional discussion or qualifications to an item are indented to the right, immediately below, or listed subsequently similar to:

8.4.5.A	Additional Requirements for Wood Material Rules	8.4.5.A	Additional Requirements for Wood Material Rules
<b>▲ From previous column</b> <b>1 VENEER SURFACING</b> (continued) 1 5 Have visible <b>EDGES, REVEALS, and/or SPLINES</b> (continued) 1 5 7 <b>WITHIN A PANEL</b> , shall have solid wood let into the core before the veneer is applied where the veneer is machined through, however. E C P 1 5 7 1 Reveals of 1/8" (3.2 mm) or less in width let into MDF to a maximum depth of one third of the core thickness do not require solid wood if finished same as exposed finish. 1 5 8 Allows <b>FINGER JOINTS</b> : 1 5 8 1 At manufacturers' choice. E C P 1 5 8 2 One per 96" (2440 mm) of length. E C P 1 5 8 3 Not allowed. E C P 1 6 Does not permit <b>BLEED THROUGH</b> of adhesive at veneer joints that visually affects an applied finish. 1 7 At <b>FLAME SPREAD RATED</b> paneling: 1 7 1 Shall be of the construction standard of the panel manufacturer and conform to the requirements of applicable labeling agencies. <b>2 STILE and RAIL WOOD SURFACING</b> requires: 2 1 No adhesive bleed through at joints. 2 2 <b>LUMBER</b> be plain sawn only. 2 3 <b>VENEERED</b> sheet products that comply with those requirements spelled out for Veneered Wall Surfacing within this section. 2 4 At <b>OPAQUE</b> finish: 2 4 1 Medium density fiberboard. 2 4 2 Paint grade hardwood or softwood at E C P		<b>▲ From previous column</b> <b>2 SOLID STILE and RAIL SURFACING</b> (continued) 2 5 At <b>TRANSPARENT</b> finish, finger joints. E C P <b>2 6 PANELS</b> : 2 6 1 <b>SHALL BE</b> solid stock or veneered construction, at the manufacturer's choice. 2 6 2 If <b>FLAT</b> shall be: 2 6 2 1 <b>SOLID WOOD</b> : 2 6 2 1 1 Minimum 1/2" (12.7 mm) in thickness and maximum 23-3/4" (603 mm) across the grain in width. E C P 2 6 2 1 2 Minimum 3/4" (19 mm) in thickness and maximum 13-3/4" (350 mm) across the grain in width. E C P 2 6 2 1 3 Not permitted. E C P 2 6 2 2 <b>SHEET PRODUCT</b> : 2 6 2 2 1 Minimum 1/4" (6.4 mm) in thickness. E C P 2 6 2 2 2 Minimum 1/2" (12.7 mm) in thickness. E C P 2 6 3 If <b>RAISED</b> shall be: 2 6 3 1 <b>SOLID WOOD</b> : 2 6 3 1 1 Permitted in any dimension. E C P 2 6 3 1 2 Minimum 3/4" (19 mm) in thickness and maximum 13-3/4" (350 mm) across the grain in width. E C P 2 6 3 1 3 Not permitted. E C P 2 6 3 2 <b>VENEERED STILES and RAILS or SHEET PRODUCT</b> :	

Example: User's Guide - 006

The **PRODUCT** and **INSTALLATION** portions add an additional table format to express particular requirements that are applicable only to a particular Grade or Grades of work.

- The **Product** portion is divided into Basic, Material, Machining, and Assembly sub-sections. They are intended to be read with the understanding that the more general rules are listed first in the Basic sub-section with the more specific or detailed rules following in other sub-sections.
- "**Unless Specified Otherwise**" is a significant aspect of these standards. 

When this standard is referenced in contract documents, it shall establish the minimum contractual compliance requirements for materials, fabrication, installation, and workmanship - in the absence of any specific contractual requirement to the contrary.

If there is a conflict between the contract documents and these standards, the contract documents shall prevail.

- Unless otherwise noted, the statements or rules contained within the **General, Product, Installation** and **Test** portions of each section are equally applicable to all Grades of work.
- Otherwise, within the **Product** or **Installation** portions, when a rule applies specifically to a particular Grade or Grades of work, it is shown by a bold **E, C, and/or P** in the corresponding right-hand columns to indicate Economy, Custom, or Premium Grade, respectively. If there are no columns or letters, the rule applies to all grades.
- Table headers and/or footers are used on a column-by-column and page-to-page basis to indicate where there is additional coverage of a topic on a previous or a subsequent page.

For further clarification or explanation, call your local Sponsor Association. 

# North American Architectural Woodwork Standards - 3.1

## PREFACE

<b>NAAWS Review . . . . .</b>	<b><a href="#">20</a></b>
<b>Dimensional Change . . . . .</b>	<b><a href="#">21</a></b>
<b>Variations in Natural Wood Products . . . . .</b>	<b><a href="#">22</a></b>
<b>Moisture &amp; Architectural Woodwork . . . . .</b>	<b><a href="#">22</a></b>
<b>Specification Guidelines . . . . .</b>	<b><a href="#">23</a></b>
<b>Architectural Drawing Guidelines . . . . .</b>	<b><a href="#">24</a></b>
<b>System of Measurement . . . . .</b>	<b><a href="#">24</a></b>
<b>Forest Management . . . . .</b>	<b><a href="#">25</a></b>
<b>Casework Refinishing/Refacing/Refurbishing . . .</b>	<b><a href="#">25</a></b>
<b>Warranty Language . . . . .</b>	<b><a href="#">25</a></b>

# PREFACE

## NORTH AMERICAN ARCHITECTURAL WOODWORK STANDARDS

### PURPOSE

Provide design professionals with logical and simple means to comprehensively specify elements of architectural woodwork for use in climate controlled environments.

Provide compliance criteria to ensure that manufacturers/installers bidding on a project compete on an equal basis and are obligated to perform work of equal quality.

Provide industry information, terminology, and test criteria to properly determine compliance.

### OVERVIEW

These standards are based on three Grades of quality that may be mixed within a single project. Limitless design possibilities and a wide variety of lumber and veneer species, along with overlays, high-pressure decorative laminates, factory finishes, and profiles are available in all three Grades.

- **ECONOMY GRADE** defines the minimum quality requirements for a project's workmanship, materials, or installation and is typically reserved for woodwork that is not in public view, such as in mechanical rooms and utility areas.
- **CUSTOM GRADE** is typically specified for and adequately covers most high-quality architectural woodwork, providing a well-defined degree of control over a project's quality of materials, workmanship, or installation.
- **PREMIUM GRADE** is selectively used in the most visible and high-profile areas of a project, such as reception counters, boardrooms, and executive areas, providing the highest level of quality in materials, workmanship, or installation.

These standards cannot address every contingency; however, this document is the most comprehensive architectural woodworking standard available.

When these standards are referenced, the client is protected, and the manufacturer/installer has a clear direction for what is required.

**These standards are not restrictive; they merely establish the minimum rules by which all parties shall conform. Issues not clearly defined in the contract documents or in these standards will be resolved by selection, fabrication, finishing, and/or installation at the option of the manufacturer or installer.** 

NAAWS is offered in two distinct versions, one for use in the United States and the other for use in Canada. While the "Compliance Requirements" of both versions remain identical some of the "Introductory Information" varies to accommodate the sponsor association requisites.

### FIRST-CLASS WORKMANSHIP

It is intended that architectural woodwork specified to meet these standards will conform to "First-Class Workmanship" as defined within these standards and the glossary.

### DEFAULT STIPULATION

When these standards are referenced as a part of the contract documents and no Grade is specified, Custom Grade will be the default stipulation. In the absence of material specifications, it will be the manufacturer's option to select materials suitable for opaque finish.

### EXCEPTION

**These standards are a guide from which the design professional is free to deviate. When the design professional, as part of the contract documents, deviates from these standards, the contract document takes precedence over the Standards. Such deviations cannot be adjudicated using the Standards as a basis.** 

These standards are intended for typical commercial, institutional and/or residential applications and environments and might not perform as expected in abusive or other environments where special design considerations should be taken.

### DISCLAIMERS

**The sponsors of these standards shall not be responsible to anyone for the use of or reliance upon these standards. They shall not incur any obligation nor liability for damages, including consequential damages, arising out of or in connection with the use, interpretation of, or reliance upon these standards.** 

These standards provide the minimum criteria for the concept, design, fabrication, finishing, and installation of architectural woodwork.

Provisions for mechanical and electrical safety have not been included. References to life-safety requirements are included for information only.

Governmental agencies or other national standards-setting organizations provide the standards for life-safety requirements.

**Illustrations are intended to assist in understanding these standards and might not include all requirements for a specific product or unit, nor do they show the only method of fabrication. Such partial drawings shall not be used to justify improper or incomplete design and/or construction.** 

### APPENDIX

Is provided as additional resources to the manufacturer, design professional, educator, user, or certifying organization and is only part of these standards when referenced. For your convenience where referenced it is flagged by the following icon: 

### DESIGN RESOURCES

Are provided as additional resources to the design professional, educator, or user. For your convenience where referenced it is flagged by the following icon: 

# PREFACE

## NORTH AMERICAN ARCHITECTURAL WOODWORK STANDARDS (continued)

### CITATIONS and QUOTES

Other industry standards, neither developed nor published by the Sponsor Associations, are used within these standards. The reference to and usage of is not a validation of these citations and quotations outside the context of these standards. Only when these citations and partial quotations are applied in concert with all other related provisions of these standards are these citations and partial quotations recognized for application to architectural woodwork.

### CONFLICT

If found in these standards, shall be brought to the attention of the North American Woodwork Standards Committee (NAAWS Committee) by way of the improvement suggestion form referenced on the inside back cover and until specifically addressed, the least restrictive requirement shall prevail.



### IMPROVEMENT

The Sponsor Associations encourage your suggestions for changes, revisions, and/or improvements to these standards. Please bring such to the attention of the North American Woodwork Standards Committee (NAAWS Committee) by way of the NAAWS Improvement Suggestion Form referenced on the inside back cover or on each of the Sponsor Associations' websites (<http://awmac.com> or <http://woodworkinstitute.com>). Simply follow the form's instructions.

### TOLERANCES

The tolerances found within these standards fall into two categories in Sections 6 – 11:

- Factory fabricated joinery, assembly and construction - found in the Product portion
- Field installation joinery and assembly - found in the Installation portion

Specific locations where the tolerances apply are

found in the Tests portion of each Section.

Most fabrication and installation assemblies include solid wood to solid wood joints, solid wood to wood veneer joints, solid wood to wood based products (HPDL, LPDL, Solid Phenolic and panel products), solid wood to non-wood based products (which can be drywall, glass, metal, stone, acrylics, and other surfaces), and non-wood to non-wood joints.

Tolerances found in these standards include:

- Flatness of wood based panel products
- Solid wood to solid wood joints and assemblies
- Solid wood to wood veneer joints and assemblies
- Wood veneer to wood veneer joints and assemblies
- Solid wood to wood based product joints and assemblies
- Solid surface to solid surface joints and assemblies

Because of the differences of expansion and contraction of non-wood products compared to solid wood and wood based products, these standards do not apply tolerances regarding flatness or joinery to these non-wood based products.

### DIMENSIONAL CHANGE IN ARCHITECTURAL MILLWORK

This advisory concerns prevention of dimensional problems in architectural woodwork products as the result of uncontrolled relative humidity. It is further intended as a reminder of the natural dimensional properties of wood and wood-based products such as plywood, particleboard, and high pressure decorative laminate (HPDL) and of the routine and necessary care and responsibilities which must be assumed by those involved.

For centuries, wood has served as a successful

material for architectural woodwork, and as history has shown wood products perform with complete satisfaction when correctly designed and used. Problems directly or indirectly attributed to dimensional change of the wood are usually, in fact, the result of faulty design, or improper humidity conditions during site storage, installation, or use.

Wood is a hygroscopic material, and under normal use and conditions all wood products contain some moisture. Wood readily exchanges this molecular moisture with the water vapor in the surrounding atmosphere according to the existing relative humidity. In high humidity, wood picks up moisture and swells. In low humidity, wood releases moisture and shrinks. As normal minor fluctuations in humidity occur, the resulting dimensional response in properly designed construction will be insignificant. To reduce humidity related problems, the appropriate recommendations from Section 2 should be considered. Uncontrolled extremes can likely cause problems.

Oxidation is a reaction of acids in wood (e.g., tannic acid), with iron, oxygen, and moisture, whether this be relative humidity or direct moisture. Control of moisture is a simple way to protect wood products from stains as a result of oxidation.

Together with proper design, fabrication, and installation, humidity control is obviously the important factor in preventing dimensional change problems.

Architectural woodwork products should be manufactured as designed from wood that has been dried to an appropriate average moisture content and maintained at this condition up to the time of delivery.

# PREFACE

## NORTH AMERICAN ARCHITECTURAL WOODWORK STANDARDS (continued)

Subsequent dimensional change in wood is and always has been an inherent natural property of wood. These changes cannot be the responsibility of the manufacturer or products made from it.



Specifically:

- Responsibility for dimensional change problems in wood products resulting from design rests with the designer/architect/specifier.
- Responsibility for dimensional change problems in wood products resulting from improper relative humidity exposure during site storage and installation rests with the general contractor.
- Responsibility for dimensional change problems in wood products resulting from humidity extremes after occupancy rests with engineering and maintenance.

## VARIATIONS IN NATURAL WOOD PRODUCTS

Wood is a natural material with variations in color, texture, and figure. These variations are influenced by the natural growing process and are uncontrollable by the manufacturer.

The color of wood within a tree varies between the “sapwood” (the outer layers of the tree that continue to transport sap), which is usually lighter in color, and the “heartwood” (the inner layers in which the cells have become filled with natural deposits).

Various species, veneer cuts, and/or lumber milling options produce different grain patterns (figures) which influence the selection process. There will be variations of grain patterns within any selected species.

The manufacturer cannot select solid lumber cuttings within a species by grain and color in the same manner in which veneers might be selected. Color, texture, and grain variations may occur in architectural woodworking.

## MOISTURE AND ARCHITECTURAL WOODWORK

The moisture content of wood is crucial. If wood is not properly dried and/or seasoned, the best of workmanship cannot prevent moisture-related defects such as surface checks, cracking, bowing, twisting, and glue-line failure that might occur during production and afterward. In severe cases, a product can even be destroyed; unfortunately, most moisture defects are irreversible.

Wood is a hygroscopic material, expanding when it takes on moisture, shrinking when it loses moisture. How much moisture will be absorbed or how fast lumber will dry depends upon the present moisture content of the wood, the wood species, the relative humidity, and the temperature of the surrounding air. The drying process of lumber has to be slow enough to avoid stress between the surface and the core because too much stress results in surface checks, cracks, split ends, and other drying effects.

If wet and dry pieces of wood are placed in an area, they will absorb or lose moisture until all pieces have the same final moisture content (Equilibrium Moisture Content or EMC). For instance, if you make furniture, cabinets, picture frames, or clocks for inside a home, an office, or other heated live-in area, all wooden parts will eventually dry to approximately 6-12% wood moisture (extreme climate zones might have slightly higher or lower values).

For lasting quality and beauty, use only wood with a moisture content between 6-12%. Moisture-related defects might occur if only one piece has a higher or lower moisture content than 6-12%. Without control of the moisture content, occurrences of moisture related defects increases dramatically.

Many manufacturers reduce the occurrences of moisture problems by buying only kiln-dried wood. Kiln-dried wood should have a moisture content between 6-12%. Even though the wood might be dried properly when it leaves the dry kiln, it can change in moisture content during manufacturing, transportation, or storage. Manufacturers might inadvertently further complicate the problem by assembling a project with materials that have dissimilar moisture contents.

To reduce the risk of moisture damage, the U.S. Department of Agriculture, Forest Service, Forest Products Laboratory recommends in their General Technical Report 113 that:



- Large assemblies, such as ornamental beams, cornices, newel posts, stair stringers, and handrails, should be built up from comparatively small pieces.
- Wide door and window casing and base molding should be hollow-backed.
- Backband trim, if mitered at the corners, should be glued and splined before erection.
- Large solid pieces, such as wood stile and rail paneling, should be designed and installed so that the panels are free to move across the grain. Narrow widths are preferable.

# PREFACE

## ARCHITECTURAL WOODWORK SPECIFICATION GUIDELINES

Specifications, along with the architectural drawings, are the road map for a project's success. Use of these standards will greatly reduce the text of your specifications and their development time. They eliminate the need to worry about every fabrication and material detail.

- **Budget constraints** should be communicated up front so that all parties can work together toward a successful resolution.
- **Requirements for each GRADE** are specifically defined within these standards; however, **special requirements** or **unusual applications** shall be communicated.
- **Compliance programs**, which both Sponsor Associations offer, are cost-effective and help enforce your contract documents. They ensure the performance and compliance of your architectural woodwork project's contract documents. With some, written status reports are issued during the project's progression, affording you timely notification of noncompliant findings.
- **Avoid conflict** in your specifications that might allow for interpretation other than what was envisioned. Use of certain words can make a big difference:
  - Requiring compliance to **Example A AND Example B** means that the end result will be in full compliance with both.
  - Requiring compliance to **Example A OR Example B** means that compliance to either is acceptable.
- **Enforce** your contract documents and their intent; however, be open-minded to proposed changes and cost savings. Materials and their availability are in constant flux; therefore, listen and be open to change when it does not affect your design intent.

- **Pre-qualify** your bidders to ensure their performance ability. Seek out and take advantage of our industry's knowledge and experience.
- **Guide specifications** for some and/or all of the Product Sections are offered by the Sponsor Associations on an individual association basis:



- **ARCHITECTURAL WOODWORK MANUFACTURERS ASSOCIATION OF CANADA (AWMAC)** offers Construction Specifications Canada (CSC) / Devis de Construction Canada (DCC) Master Formatted, guide specifications in digital, interactive, Word file formats .doc (Word 2003) and .docx (Word 2007).

Included in the guide specifications is wording for AWMAC's national quality control program, the Guarantee and Inspection Service (GIS) which is administered locally in Canada by AWMAC's chapters.

The Master Format sections covered by the guide specifications are:

- 064100 Architectural Wood Casework
- 064200 Wood Paneling
- 064600 Wood Trim
- 081400 Wood Doors
- 123553 Laboratory Casework

Downloads are available at: <http://awmac.com/naaws-guide-specifications>



- **WOODWORK INSTITUTE (WI)** offers CSI (Construction Specifications Institute) Master Formatted, guide specifications in digital, interactive, Word and plain text formats. Word file formats include .rtf (rich text format), .doc (Word 2003) and .docx (Word 2007). Specifically, WI offers guide specifications, including CCP, MCP and CSIP quality control options, for:

- Wood Standing and Running Trim
- Wall Paneling
- Wood Passage Doors
- Casework, including Green and Laboratory
- Countertops

Downloads are available at: <http://woodworkinstitute.com/architectural-resources/specification-language/>

# PREFACE

## ARCHITECTURAL WOODWORK DRAWING GUIDELINES

For design professionals, the proper use of these standards will greatly reduce drafting time. It is not necessary to produce standard joinery details on your drawings.

Requirements for each **GRADE** are defined throughout these standards; however, **SPECIAL REQUIREMENTS** or **UNUSUAL APPLICATIONS** need to be noted and detailed.



### CASEWORK:

Indicate the **CONSTRUCTION TYPE** desired:

- **FRAMELESS** casework construction.
- **FACE FRAME** casework construction (not recommended for decorative laminate faced or solid phenolic casework, and standards are not provided for such).



These standards define the following basic types:

- Wood Faced - **FRAMELESS**
- Wood Faced - **FACE FRAME**
- Decorative Laminate Faced - **FRAMELESS**
- Solid Phenolic Constructed - **FRAMELESS**

### CASEWORK ELEVATIONS:

Are not necessary if **CASEWORK DESIGN SERIES (CDS)** numbers, which can be found in the **APPENDIX** are utilized; however, a floor plan indicating each design number selection and relative dimensions is required.



When casework elevations are shown, they should indicate:

- The basic overall dimensions.
- Dimensions of items required to be of predetermined or controlled size.
- Dimensions required for installation of items of equipment.

- Whether sliding or hinged doors are desired, including swing if hinged.
- Thickness of cabinet doors if other than nominal 3/4" (19 mm) is required.
- If and where locks are required.
- Required details not shown in these standards or those that involve installation of unusual equipment.
- Shelf location and whether fixed or adjustable.
- Material and load capacity required.
- Type of countertop.

### COUNTERTOPS:

Indicate the **CONSTRUCTION TYPE** desired:

- **ASSEMBLY - 1**, HPDL countertop Construction with wall mount splash.
- **ASSEMBLY - 2**, HPDL countertop Construction with deck mount splash.

### STANDING AND RUNNING TRIM

Elevations should indicate the placement of standing and running trim, including cross section details along with overall dimensions should be shown for all trim types. If a finish schedule is used in lieu of elevations, it should be comprehensive enough to clearly indicate all of the above.

### ARCHITECTURAL WALL AND CEILING SURFACING

Elevations should indicate the placement of architectural wall surfacing, including each panel size, along with edge, corner, reveal, ceiling, and base treatments.

Door and/or other woodwork matching should be so indicated. Reveals, dimensions and locations should be as specified; however, a minimum of 1/4" (6.4 mm) wide reveal is recommended. If a finish schedule is used in lieu of elevations, it should clearly indicate all of the above.

### DOORS

Include a comprehensive door and hardware schedule indicating the location, type, size, and handling of each door, along with applicable requirements for:

- Pair and/or transom matching
- Room and/or panel matching
- Transom panel or Dutch door edge and/or shelf treatment
- Special core blocking
- Glass and louver cutouts
- Undercut tolerances
- Flame spread, acoustical, x-ray, and/or other ratings/requirements
- Hardware

Include elevations of typical door types to indicate glass and louver cutout sizes and locations.

### SYSTEMS OF MEASUREMENT

These standards are written with the U.S. Customary System of Measurement followed by the metric system in brackets.

The system of measurement used in the original design of a project's architectural drawings will dictate which system of measurement within these standards is used for verification of compliance.

The metric number is typically a "soft" conversion of the U.S. Customary System of measurement. In order to make the metric number more conceptually coherent and consistent, most conversions for less than 3" (76 mm) in dimension are "soft" converted to the nearest 0.1 mm; for measurements above 3" (76 mm), the "soft" value is converted to the nearest 1 mm.

Exceptions to this convention will occur as, for example, 1220 mm is commonly used for 48", as opposed to 1219 mm.

# PREFACE

## FOREST MANAGEMENT CERTIFICATION:

The Sponsor Associations acknowledge and have adopted the International Wood Products Association's (IWPA) Statement on Certification as modified below.

- We acknowledge the interest in certified timber products and verification of good forest management.
- A number of certification and verification systems are in operation or in development today, and we make no judgment against or endorsement of any single plan.
- Certification can serve as an audit of work already being done toward improved forest management. An absence of certification, however, does not mean there is a lack of quality forest management.
- We wish to recognize the efforts that many countries and companies are making with regard to improved forest management practices. Further, we strongly endorse the right of individual countries and companies that become involved with certification or the verification of forest management to pursue the development of their own internal auditing system or the selection of one that is already established.
- Global consensus has not been reached regarding the scope and viability for any single system of certification to be appropriate for all locations and conditions. Efforts are being made to develop an international framework of mutual recognition between credible and market-oriented sustainable forest management standards and certification systems.

The development of a mutual recognition process should ensure that these various certification or verification systems:

- Do not discriminate against different forest types.
- Should be regularly reviewed and updated.
- Should be transparent.
- Should be cost-effective.

We strongly endorse the development of a mutual recognition system and support any and all efforts that will further enhance management of the world's forests and the growth of global and sustainable trade in wood products.

## CASEWORK REFINISHING/REFACING/REFURBISHING

Is typically required to be done in the field and is not covered by these standards; however, guidelines can be found in the **APPENDIX**.



## WARRANTY/GUARANTEE LANGUAGE

There have been repeated requests for "industry standard" warranty or guarantee language, both on the part of design professionals and woodwork manufacturers. It is not the purpose or intent of this publication to give legal advice with regard to warranties. Such language varies from governing body to governing body.

**CAUTION:** You might use the following language as a starting point; however, the sponsors of these standards assume no liability whatsoever from its use. It is advised that warranty language be reviewed by competent counsel for the state or province in which it is intended.



Architectural woodwork is guaranteed to be of good material and workmanship and free from defects that render it unserviceable for the use for which it is intended. Natural variations in the color or texture of the wood are not to be considered defects. The quality of architectural woodwork is safeguarded while it is in the manufacturer's possession. To be protected by this guarantee, products must not be stored in damp warehouses or placed in moist or freshly plastered buildings. The woodwork must not be subjected to abnormal heat or dryness. Permanent-type heat and air conditioning must be in operation a sufficient length of time to "cure" the building before any woodwork or doors are delivered to the site. (Temporary-type heat sources might either add excessive moisture or create excessive dryness, depending upon the type of fuel. Thus, temporary heating can be a source of woodwork problems and should be avoided).

Adhere to the requirements in Section 2 for range and maintenance of relative humidity. Acclimatize delivered woodwork to the job site for a minimum of 72 hours before installation.

Woodwork must be inspected upon arrival, and all claims or complaints must be filed before painters' finish is applied. Doors must be properly sealed on all surfaces, including top and bottom edges, to prevent absorption of moisture. The manufacturer will not be responsible for defects resulting from neglect of these precautions.

The manufacturer agrees, within a period of (insert year) year(s) after delivery date, to repair or replace (in the white, unfinished, if so furnished originally) without charge any woodwork that is defective within the meaning of this guarantee. The manufacturer does not agree to be responsible for any work that was not originally performed by them. The manufacturer (insert does or does not) agree to pay charges for finishing or installing replaced woodwork. This guarantee is not effective if goods are repaired or replaced without first obtaining the manufacturer's written consent.

# North American Architectural Woodwork Standards - 3.1

## **S E C T I O N - 0 1**

# SUBMITTALS

<b>Resources . . . . .</b>	<b><a href="#">27</a></b>
<b>Introduction . . . . .</b>	<b><a href="#">29</a></b>
<b>Advisory . . . . .</b>	<b><a href="#">29</a></b>
<b>Recommendations . . . . .</b>	<b><a href="#">29</a></b>
<b>Specification Considerations . . . . .</b>	<b><a href="#">29</a></b>
<b>Design Resources . . . . .</b>	<b><a href="#">30</a></b>
<b>Compliance Requirements . . . . .</b>	<b><a href="#">31</a></b>
<b>Scope &amp; Default Stipulation . . . . .</b>	<b><a href="#">32</a></b>
<b>Basic Rules . . . . .</b>	<b><a href="#">32</a></b>
<b>Specific Section Rules . . . . .</b>	<b><a href="#">34</a></b>

### Within CANADA

#### SUPPORT

- **GUIDE SPECIFICATIONS** – Available for download in interactive digital format, including specification wording for Quality Assurance Program (GIS) at: <http://awmac.com/guide-specifications>
- **CONSULTATION** – Contact any of the local chapters for more information on the NAAWS or any other Architectural Woodwork Questions you may have. See below for contact information.
- **SPECIFICATION REVIEW** – Contact any of the local chapters if you would like your specifications reviewed for compliance to the NAAWS.
- **MANUFACTURER STANDARDS QUESTIONNAIRE (MSQ)** – AWMAC Manufacturer members have the opportunity to have at least one member of their staff study and write the MSQ. The MSQ is a questionnaire on the NAAWS and policy and procedures of the GIS program. A list of Manufacturer members that have passed the MSQ is available at: <http://awmac.com/members>
- **SEMINARS AND PRESENTATIONS** – Contact your local chapter to arrange an informative presentation on any Architectural Woodwork topic. Some topic options – GIS, NAAWS, How to Specify Quality Architectural Woodwork...
- **TRADE SHOWS** – Contact your local chapter to arrange for AWMAC to have a booth or do a presentation on Architectural Woodwork.
- **CONFERENCE** – AWMAC has an annual conference held at unique venues across Canada. The conferences provide an opportunity to learn more about Architectural Woodwork and network with Suppliers and Manufacturers from across Canada. More information is available at: <http://awmac.com/>
- **EDUCATION PARTNERS** – Contact the local chapters to find out more information about support for local Colleges and Universities offering woodworking related courses and programs.

#### QUALITY ASSURANCE

- **GUARANTEE AND INSPECTION SERVICE (GIS)** – The GIS is a national program designed to ensure that project owners get value and quality for their investment by:
  - Supporting architects and design professionals to achieve project plans and specifications; and
  - Helping contractors avoid problems such as cost overruns, delays and loss of reputation.More information is available at: <http://awmac.com/gis>

- **INSPECTION SERVICE** – A GIS Certified Inspector will inspect specific areas of concern on a project for compliance to the NAAWS and provide a written report. Contact your local chapter for more information.
- **EXPERT OPINION** – An expert will be appointed to inspect specific areas of concern on a project and provide a written report. Contact your local chapter for more information.

#### AWMAC CHAPTERS

- AWMAC British Columbia Chapter, Vancouver BC  
<http://bc.awmac.com>
- AWMAC Northern Alberta Chapter, Edmonton Alberta  
<http://nab.awmac.com>
- AWMAC Southern Alberta Chapter, Calgary Alberta  
<http://sab.awmac.com>
- AWMAC Saskatchewan Chapter, Saskatoon Saskatchewan  
<http://sk.awmac.com>
- AWMAC Manitoba Chapter, Winnipeg Manitoba  
<http://mb.awmac.com>
- AWMAC Ontario Chapter, Toronto Ontario  
<http://on.awmac.com>
- AWMAC Quebec Chapter, Montreal Quebec  
<http://qc.awmac.com>
- AWMAC Atlantic Chapter, Halifax Nova Scotia  
<http://atl.awmac.com>

### Within UNITED STATES

#### SUPPORT

- **GUIDE SPECIFICATIONS** - Available in interactive digital format including quality control options at: <http://woodworkinstitute.com/publications/architectural-woodwork-standards/>
- **AIA SEMINARS** - The Woodwork Institute is a Registered Provider of the American Institute of Architects (AIA), and its Continuing Education System (CES) program, check out our offerings at: <http://woodworkinstitute.com/architectural-resources/aia-seminars/> 
- **CONSULTATION** - Contact one of our Directors of Architectural Services (DAS) at: <http://woodworkinstitute.com/about-us-2/about-us/>
- **ACCREDITED FABRICATORS AND INSTALLERS** - Our AMC's (Accredited Millwork Company) represents the best fabricators and installers in our industry, check them out at: <http://woodworkinstitute.com/membership-listing-2/> 
- **CERTIFIED INDUSTRY PROFESSIONALS** - Our CMP's (Certified Millwork Professionals) represent the knowledge base of our industry, check them out at: <http://woodworkinstitute.com/membership-listing-2/> 
- **MILLWORK INDUSTRY PARTNERS** - Our MIP's (Millwork Industry Partners) represent the best of our industries material suppliers, check them out at: <http://woodworkinstitute.com/membership-listing-2/> 
- **ACKNOWLEDGED PRODUCTS LISTING** - If it's listed here, you are assured it meets NAAWS minimum requirements, find the listing at: <http://woodworkinstitute.com/acknowledged-product-listing/> 
- **CABINET DESIGN SERIES (CDS)** - Eliminate the need to include casework elevations in your architectural drawings, check out the CDS system in NAAWS "Design Resources" and access the cad files at: <http://woodworkinstitute.com/architectural-resources/cabinet-design-series/>

#### QUALITY ASSURANCE

- **BIDDER QUALIFICATION** - A discipline of bidder pre-qualification wherein your specifications protect you and your customer from the unknown: To be eligible to bid or negotiate this job, the subcontractor must be a Woodwork Institute Accredited Millwork Company (AMC) in good standing.   
<http://woodworkinstitute.com/architectural-resources/quality-assurance>
- **CERTIFIED COMPLIANCE PROGRAM (CCP)** - A discipline of quality control used in conjunction with NAAWS providing an unbiased means of ensuring conformance to a project's plans and specifications. CCP, together with the use of the desired Grade(s) in the specifications, informs all parties of the design professional's expectations, without bidder discrimination.   
<http://woodworkinstitute.com/services/certified-compliance-program>
- **MONITORED COMPLIANCE PROGRAM (MCP)** - A discipline of quality affirmation used in conjunction with the NAAWS which provides ongoing reviews/inspections of a project from its beginning through completion, ensuring strict conformance to the design intent throughout the millwork fabrication and installation process.   
<http://woodworkinstitute.com/services/monitored-compliance-program/>
- **CERTIFIED SEISMIC INSTALLATION PROGRAM (CSIP)** - A standalone seismic assurance option which can be specified in conjunction with or without CCP or MCP, offering design professionals and project owners specific use of WI's seismic casework pre-approvals from California's Office of Statewide Health Planning and Development (OSHPD) without additional engineering costs and/or requirements, assuring proper backing has been installed in the walls when and where required.   
<http://woodworkinstitute.com/services/certified-seismic-installation-program/>

# SECTION 1

## Submittals

## introductory information

### INTRODUCTION

At the beginning of every woodwork project is the submittal stage. This section deals with the various items that are the foundation of every project – Shop Drawings, Approvals, Samples and Scheduling. Each of the Product Sections (6 through 12) have criteria pertaining to their specific products.

Quality assurance can be achieved by adherence to these standards and will provide the owner a quality product at competitive pricing. Working with an AWMAC Member (in Canada) or a WI Certified Millwork Professional (CMP) (in the USA) and the WI Accredited Millwork Company (AMC) they represent to provide your woodwork will help ensure the understanding and performance of the quality level required. Illustrations in this Section are not intended to be all inclusive, other engineered solutions may be acceptable. In the absence of specifications; methods of fabrication are the manufacturer's choice. The design professional, by specifying compliance to these standards increases the probability of receiving the product quality expected.

### ADVISORY

**RESPONSIBILITIES** - It is the responsibility of the contractor to coordinate the manufacturer's shop drawings with work of all other trades and to ensure that hold-to/guaranteed dimensions are actually enforced.

It is the responsibility of the design professional or contractor, depending on contract relationships, to communicate design and field changes to all parties so that if dimensions are changed, each subcontractor can be held responsible for their work.



### RECOMMENDATIONS



- That only **TWO SETS** of shop drawings are required to be submitted for initial design professional review.
- If the review is Approved or Approved as Noted, the design professional keeps one copy, and a marked set is returned to the manufacturer with a request for the required number of final copies.
- If the review is not Approved or Approved as Noted, the design professional returns one set requesting correction and re-submittal. The other set is kept by the design professional to check against the re-submittal.

### SPECIFICATION CONSIDERATIONS



- **SPECIFIC REQUIREMENTS FOR:**
  - **Mock-ups**
  - **Hardware samples**
  - **Molding samples:**
    - Unless a catalog item, samples are typically not furnished until full-size details (in the shop drawings) have been approved.
  - **Finish Samples:**
    - Unless a catalog color, **DESIGN PROFESSIONAL** shall provide a sample (suggested minimum of 5" x 8" {122 mm x 196 mm}) indicating the desired color, sheen and/or transparency as applicable.
  - **Compliance to NAAWS for:**
    - Laboratory Casework
    - Seismic Casework Installation

### • QUALITY ASSURANCE OPTIONS:

#### Within CANADA

- **AWMAC's GUARANTEE AND INSPECTION SERVICE (GIS)** - See NAAWS's Resources page and/or <http://awmac.com/gis>
- **AWMAC's INSPECTION SERVICE** - See NAAWS's Resources page and/or <http://awmac.com/gis>
- **AWMAC's EXPERT OPINION SERVICE** - See NAAWS's Resources page and/or <http://awmac.com/gis>

#### Within UNITED STATES

- **WI'S AMC BIDDER PRE-QUALIFICATION** - See NAAWS's Resources page and/or <http://woodworkinstitute.com/architectural-resources/quality-assurance>
  - **WI'S CERTIFIED COMPLIANCE PROGRAM (CCP)** - See NAAWS's Resources page and/or <http://woodworkinstitute.com/services/certified-compliance-program/>
  - **WI'S MONITORED COMPLIANCE PROGRAM (MCP)** - See NAAWS's Resources page and/or <http://woodworkinstitute.com/services/monitored-compliance-program/>
  - **WI'S CERTIFIED SEISMIC INSTALLATION PROGRAM (CSIP)** - See NAAWS's Resources page and/or <http://woodworkinstitute.com/services/certified-seismic-installation-program/>
- **SUSTAINABILITY OPTIONS:**
    - **SUSTAINABLE ARCHITECTURAL WOODWORK (SAW)** - See NAAWS's Resources page and/or <http://sawcertified.org>

### PURPOSE

Shop drawings are the means by which the design concept is turned into reality, serving as the primary instructions for woodwork engineering and fabrication, and as a guide for other trades. As the primary communication among manufacturer, general contractor and design professional, shop drawings serve a valuable coordinating function. Shop drawings should indicate methods of construction, exact material selections, finishes, method of attachment and joinery, exact dimensions and should include the manufacturer's technical suggestions.

### WHAT TO EXPECT

The key to achieving a detailed and useful set of shop drawings is concise and continual communication between design professional and manufacturer.

The manufacturer shall submit samples, product data and shop drawings of sufficient detail and scale to demonstrate compliance with the Grade specified.

### LEVEL OF DETAIL

The level of detail required on shop drawings is established by the complexity of the project. The specifier is at liberty to specify any level of detail as a requirement of the project and of the contract documents. It should be noted that requirements for local codes and utilization of fire retardant wood products is to be researched and directed by the design professional and are not the responsibility of the manufacturer.

What constitutes the minimum expectation for a set of shop drawings is not simple, since there are many variables as to the complexity, quality and type of work being specified.

### SCHEDULING

Most projects are encumbered by a tight production schedule, especially for the finish trades such as woodworking, painting, carpeting and wall coverings. Prompt review of shop drawings and accurate coordination of multiple trades can save weeks of time and eliminate problems before construction begins.

The design professional should work with the manufacturer through the contractor to determine the maximum "approval-to-fabrication" timeline needed to keep the job on schedule (e.g., "Shop drawings must be returned approved to fabricate seven (7) days after submittal").

**Schedules vs Drawings** - In some cases shop drawings are not required to communicate the necessary quality, type, quantity and details of an item. Tabular schedules are used instead, generally for such items as doors, frames, stock factory cabinets, closet shelves, and furniture items.

### APPROVALS

For the design professional, the approval stage provides an opportunity, prior to fabrication, to review the manufacturer's proposed shop drawings. Shop drawings, however, are not an extension of the design development process; therefore, changes by either party of intent or concept made during shop drawing review may result in a change of cost and/or time.

During the review process the design professional should consider the following:

- Unless noted otherwise, two copies are necessary for checking purposes. After being reviewed, one marked copy should be returned to the contractor or manufacturer.
- Those charged with review of shop drawings should be familiar with woodwork fabrication, and have an understanding or working knowledge of the referenced standards as well as design concept.

- Deviations from the contract documents are often recommendations for improvement, and not necessarily a criticism of design. It is as wrong for a reviewer to arbitrarily stamp "Revise and Resubmit" on a shop drawing that proposes a change, as it is wrong to automatically accept shop drawings because they contain duplicates of the original plans.

For the manufacturer, shop drawings are drawings, diagrams, schedules and other data specifically prepared to illustrate their portion of the work. Their purpose is to demonstrate the way by which the manufacturer proposes to conform to the information given and the design concept expressed in the Contract Documents.

The four common levels of approval are:

- Approved
- Approved As Noted
- Revise and Resubmit
- Rejected

Approvals are generally indicated by a stamp on the cover sheet of the shop drawings. When selecting "Approved As Noted" rather than "Revise and Resubmit," the design professional can often save weeks of production time provided the concept and all changes are clearly marked on the drawings.

### DESIGN RESOURCES

Is a perpetually expanding, web based resource of pictures, videos, illustrations, ideas and design concepts for inspiring thought and design creativity - assessable at:  <http://naaws-design-resources.com>

Relative to this Section, offerings will include:

- Guides specifications'
- Sample shop drawings

# SECTION 1

## Submittals

### GENERAL/PRODUCT

### compliance requirements

#### **INCLUDING: Shop Drawings, Profile and Veneer Flitch Samples, Finish Samples, Hardware Samples**

#### 1.1 BASIC CONSIDERATIONS

##### 1 GRADES

1.1 None; shop drawing requirements are the same for all architectural woodwork projects regardless of Grade specified.

2 **RANGE OF COLOR** shall be expected on finished wood products due to variance in wood color within the same species and even within the same log.

##### 3 INDUSTRY PRACTICES

3.1 **SUBMITTALS** are submitted to the contractor, design professional, and/or owner for review prior to fabrication, and:

3.1.1 Are the property of the manufacturer, and the manufacturer is not responsible for errors caused by their unauthorized use by others.

3.1.2 The manufacturer is encouraged to make technical suggestions and raise questions based upon working experience; however:

3.1.2.1 Changes incorporated within shop drawings, in themselves, are not a request for approval.

3.1.2.2 Changes to material or design must be specifically identified in separate written documentation within the submittal package, requesting approval of the suggested changes.

3.1.2.2.1 Means and methods such as joinery details are not considered material changes.

##### 3.2 RESPONSIBILITY OF:



3.2.1 **CODE/REGULATION** research, and compliance direction is that of the design professional, not of the manufacturer and/or installer.

3.2.2 **COORDINATION** of manufacturer's shop drawing with work of all other trades and assurance that hold-to/guaranteed dimensions are actually enforced is that of the general contractor, not of the manufacturer and/or installer.

3.2.3 **COMMUNICATION** of design and field changes to all parties so that if dimensions are changed, each subcontractor can be held responsible for their work, is that of the design professional or contractor, depending on contract relationships.

# SECTION 1

## Submittals

### GENERAL/PRODUCT

## compliance requirements

### 1.2 SCOPE

1 All materials and products covered under the scope of these standards.

### 1.3 DEFAULT STIPULATION

1 Not used or applicable for this section.

### 1.4 RULES

- 1 The following rules shall govern unless a project's contract documents require otherwise.
- 2 These rules are intended to provide a well-defined degree of control over a project's quality of submittals.
- 3 **ERRATA**, published at <http://naaws-errata.com>, shall take precedence over these rules, subject to their date of posting and a project's bid date. 

#### 1.4.4 Basic General Rules

1	<b>SUBMITTALS</b> shall:
1 1	Be submitted to the contractor, design professional, and/or owner for review prior to fabrication, and:
1 2	If applicable, note project phasing on shop drawings.
1 3	Be specifically created illustrating the project requirements.
1 4	Allow reuse of a portion of the Contract Documents in the creation of shop drawings if permitted by the design professional prior to the original shop drawing submittal, and:
1 4 1	Copies with notations are not acceptable.
1 4 2	Be in compliance with the following rules.
2	<b>RULES</b> shall apply to all Grades equally.
3	<b>DRAWING SHEETS</b> shall:
3 1	Be of size required to convey design concept.
3 2	A minimum of 11" x 17" (279 x 432 mm), except:
3 2 1	Door submittals may be a minimum 8.5" x 11" (216 x 279 mm).
3 3	Numbered.
3 4	Dated.
3 5	Be electronic submittals if requested and/or approved by the design professional, and:
3 5 1	Are in Portable Document Format (PDF) only.
<b>Continues next column ▼</b>	

#### 1.4.4 Basic General Rules

##### ▲ From previous column

4	<b>COVER OR TITLE SHEET</b> is required and shall include as applicable:
4 1	Project name and address.
4 2	Design professional firm and contact information, including phone, fax and email.
4 3	Contractor firm and contact information, including phone, fax and email.
4 4	Manufacturer firm and contact information, including phone, fax and email.
4 5	Installer firm and contact information, including phone, fax and email.
4 6	Finisher firm and contact information, including phone, fax and email.
4 7	Grade requirement if same throughout, or:
4 7 1	If multiple grades apply Cover or Title Sheet shall indicate the applicable Grades and scope, and the drawings shall individually indicate which Grade.
4 8	A Table of Contents listing all items in the woodworker's submittal package including:
4 8 1	Number and title of each shop drawing page.
4 8 2	Names of material, hardware, etc. lists.
4 8 3	Description of finish samples supplied.
4 8 4	Description of substitution and/or change requests, which shall be itemized separately from the shop drawings, and shall:
4 8 4 1	Be submitted as soon as possible, and no later than the time of shop drawing submittal.
4 8 4 2	Include the reason for the request.
4 8 4 3	Include a comparison of the requested product or design to that specified or shown, including technical data from the product manufacturers and/or detailed drawings as applicable.
4 8 4 4	Include a statement of the cost impact and possible impact to other trades.
4 8 4 5	Include a statement of possible schedule impact.
4 8 5	When contract documents are in variance to these standards, a listing of all variant items with reference to the contract document and the standards citation.
<b>Continues next column ▼</b>	

# SECTION 1

## Submittals

### GENERAL/PRODUCT

### compliance requirements

1.4.4		Basic General Rules
▲ From previous column		
5	1	MATERIAL LIST shall include as applicable:
5	1	Items to be used for exposed, exposed interior, semi-exposed, and/or concealed surfaces, including:
5	1	1 Lumber species and cut for transparent finish; however:
5	1	1 Cut is not relevant for items exposed on several sides such as turnings, railings, and some moldings.
5	1	2 Veneer species, cut, leaf match/balance, panel match, and room match for transparent finish, and:
5	1	2 1 If specified, flitch number and supplier.
5	1	1 Items to be used for exposed, semi-exposed (continued)
5	1	3 Lumber and veneer species only for opaque finish.
5	1	4 Reclaimed or recycled wood requirements and source.
5	1	5 Non-traditional material requirements and source.
5	1	6 Panel core type and thickness with any special compliance requirements, such as:
5	1	6 1 Moisture resistant.
5	1	6 2 Fire retardant.
5	1	6 3 NAUF (No Added Urea Formaldehyde) or ULEF (Ultra Low Emitting Formaldehyde).
5	1	6 4 CARB (California Air Resources Board).
5	1	7 Laminates, including applicable NEMA grade, thickness and any antimicrobial requirements.
5	1	8 Solid phenolic core.
5	1	9 Solid surface, including any antimicrobial requirements.
5	1	10 Speciality work, such as metal, glass, fabric, etc.
5	1	11 All adhesive types being used, including:
5	1	11 1 Where they are being used and indication of the adhesive type used at detail drawings.
5	1	12 Hardware (except fasteners), including any antimicrobial requirements, with manufacturer's specification sheet.
5	1	13 Finishing requirements, including NAAWS System number, sheen and required application steps.
Continues next column ▼		

1.4.4		Basic General Rules
▲ From previous column		
6	1	DRAWINGS shall show:
6	1	Each item of woodwork in plan, elevation and section as needed to clearly indicate what is provided, its location, and its method(s) of construction and attachment, and:
6	1	1 Provide a reference plan drawn in minimum 1/4" = 1'-0" (1:50) scale showing location(s) of all work to be provided.
6	1	2 Plan and elevation views shall be drawn in minimum 3/8" = 1'-0" (1:20) scale.
6	1	3 Detailed section views shall be drawn in minimum 1-1/2" = 1'-0" (1:10) scale or as required within each product section below.
6	1	4 Be sufficient in detail scale, minimum 3" = 1'-0" (1:5) scale, to clearly indicate unique features in construction.
6	2	Internal blocking, where required, for woodwork installation, showing center line height or horizontal location and materials, for:
6	2	1 Side or back wall runs of all countertops not otherwise supported by casework or support brackets.
6	2	2 Wall or ceiling applied surfacing and/or standing and running trim.
6	2	3 Wall mounted shelf standards.
6	2	4 Door and window frames.
6	2	5 Wood or wood product blocking is required where nails are allowed for woodwork attachment.
6	2	6 Casework by a standard convention such as:
Continues next column ▼		

# SECTION 1

## Submittals

### GENERAL/PRODUCT

### compliance requirements

1.4.4 Basic General Rules	
▲ From previous column	
7	<b>SAMPLES</b> , if required, for:
7 1	<b>HARDWARE</b> shall include one sample of each decorative and functional hardware item.
7 2	<b>FINISHING</b> shall:
7 2 1	Be a minimum of 12" x 12" (304 mm x 304 mm) for panel products.
7 2 2	Be as wide as practical if on lumber by a minimum of 12" (304 mm) in length.
7 2 3	Be on material representative of that to be used for the project.
7 2 4	Bear a label identifying the date, job name, the design professional, the contractor, the manufacturer, the finisher and the finish system name and number and steps used.
7 2 5	At Transparent finish, require a minimum of three (3) sets, bound together, of three (3) samples each, indicating the range of color and grain to be expected for each finish selection.
7 2 6	At Opaque finish, require a minimum of three (3) samples for each color selection.
8	<b>MOCK-UPS</b> shall be provided as required by contract documents.
9	<b>FIRST-CLASS WORKMANSHIP</b> is required in compliance with these standards. 

1.4.5 Section 6 - 12 Specific Rules	
1	<b>SECTION 6 - MILLWORK:</b>
1 1	<b>LISTING</b> requirements shall additionally include:
1 1 1	Related material requirements and specifications, and if applicable:
1 1 1 1	1 Wood treatments.
1 1 1 2	2 Adhesive.
1 1 2	Trim schedule for each room or area, including as applicable:
1 1 2 1	1 Detail section reference.
1 1 2 2	2 Blocking requirements.
1 1 3	Column, pilaster, cornice, finial, and/or pediment for each location, including:
1 1 3 1	1 Opening number.
1 1 3 2	2 Location.
1 1 3 3	3 Elevation reference.
1 1 3 4	4 Section reference.
1 1 4	Frame, sash, screen, blind, and/or shutter schedule for each room or area, including as applicable:
1 1 4 1	1 Opening number and location.
1 1 4 2	2 Elevation and/or section references.
1 1 4 3	3 Opening size.
1 1 4 4	4 Handing and premachining requirements.
1 1 4 5	5 Hardware types and locations.
1 1 4 6	6 Screen specifications.
1 2	<b>DRAWINGS</b> requirements shall additionally include as applicable:
1 2 1	Frame, sash, screen, blind, and/or shutter members, drawn in full (1:1) scale profile, except:
1 2 1 1	1 Members too large to fit on a single sheet may be drawn in segments, or at half scale, 1:2 ratio.
1 2 2	Frame, sash, screen, blind, and/or shutter construction details drawn to a minimum 3" = 1'-0" (1:5) scale.
1 2 3	Frames in section detail with elevations as necessary for coordination with other trades.
1 2 4	Sash, screen, blind, and/or shutter in elevation.
Continues next column ▼	

# SECTION 1

## Submittals

### GENERAL/PRODUCT

## compliance requirements

1.4.5		Section 6 - 12 Specific Rules
▲ From previous column		
1	<b>SECTION 6 - MILLWORK</b> (continued)	
1	2	<b>DRAWINGS</b> (continued)
1	2	5 Column, pilaster, cornice, finial, and/or pediment construction details minimum 1-1/2" = 1'-0" (1:10 mm) scale, except:
1	2	5 1 Be sufficient in detail scale, minimum 3" = 1'-0" (1:5) scale, to clearly indicate unique features in construction.
1	2	6 <b>DETAILED SECTIONS</b> , minimum 1-1/2" = 1'-0" (1:10) scale, of:
1	2	6 1 Corners, inside and outside.
1	2	6 2 Joints within the woodwork item.
1	2	6 3 Joints between the woodwork item and other trim.
1	2	6 4 Woodwork item meeting features provided by other trades.
1	2	6 5 Attachment.
1	2	6 6 Relationships to adjacent trim members or features.
<b>SECTION 7 - STAIRWORK &amp; RAILS:</b>		
2	1	<b>LISTING</b> requirements shall additionally include related material requirements and specifications.
2	2	<b>DRAWINGS</b> requirements shall additionally include as applicable:
2	2	1 Professional Engineer seals if required of the manufacturer in the contract documents.
2	2	2 Rails and trim members, shown in full-size profile.
2	2	3 Plan and elevation views drawn to a minimum 3/4" = 1'-0" (1:20) scale for each:
2	2	3 1 Rise and run of stair.
2	2	3 2 Section of balustrade.
2	2	4 <b>DETAILED SECTIONS</b> , minimum 1-1/2" = 1'-0" (1:10) scale, of:
2	2	4 1 Joinery.
2	2	4 2 Attachment.
2	2	4 3 Relationships to adjacent features.
2	2	4 4 Handrail brackets and other hardware.
2	2	5 Location of field joints at all multi length pieces of stringers, riser and treads if such pieces cannot be made out of one piece of material in length.
Continues next column ▼		

1.4.5		Section 6 - 12 Specific Rules
▲ From previous column		
3	<b>SECTION 8 - WALL/CEILING SURFACING &amp; PARTITIONS:</b>	
3	1	<b>LISTING</b> requirements shall additionally include:
3	1	1 Cut, match, and balance of veneer leaves within the panel.
3	1	2 Match and balance of panels to adjacent panels.
3	1	3 Match and balance of panels within an elevation.
3	1	4 Match and balance of panels within a room.
3	1	5 Match and balance of panels to adjacent doors or casework.
3	1	6 Panel core type and thickness.
3	1	7 Backing or balance sheet, including thickness and material description.
3	1	8 Edgebanding, including thickness and material description.
3	1	9 Related material specifications, such as:
3	1	9 1 Reveals.
3	1	9 2 Metal panels or accents.
3	1	9 3 Plastic resin materials.
3	1	9 4 Adhesive types.
3	1	10 Orientation of veneer grain and/or directional pattern.
3	2	<b>DRAWINGS</b> requirements shall additionally include as applicable:
3	2	1 Trim members, shown in full-size profile.
3	2	2 Plan and elevation views for each panel location.
3	2	3 <b>DETAILED SECTIONS</b> , including:
3	2	3 1 Vertical and horizontal sections.
3	2	3 2 Corner joints, both inside and outside.
3	2	3 3 Panel to panel joints.
3	2	3 4 Panel to base or floor joint.
3	2	3 5 Panel to crown or ceiling joint.
3	2	3 6 Attachment.
3	2	3 7 Hardware.
Continues next column ▼		

# SECTION 1

## Submittals

### GENERAL/PRODUCT

### compliance requirements

1.4.5		Section 6 - 12 Specific Rules
▲ From previous column		
4	<b>SECTION 9 - DOORS:</b>	
4	1	<b>LISTING</b> requirements shall additionally include:
4	1	1 Panel core type and thickness for slab door.
4	1	2 Solid or veneer edgebanding, including:
4	1	2 1 Adhesive type.
4	1	2 2 Any fire rated components.
4	1	3 Match and/or balance of door veneer leaves, including:
4	1	3 1 Within door face.
4	1	3 2 To adjacent paneling.
4	1	4 Stile and rail construction, including:
4	1	4 1 Solid or veneered core.
4	1	4 2 Core type and thickness.
4	1	5 Frame schedule, including as applicable:
4	1	5 1 Opening number and location.
4	1	5 2 Elevation and/or section references.
4	1	5 3 Handing and pre-machining requirements.
4	1	5 4 Hardware types and locations.
4	1	5 5 Glass lite openings with size, type and location.
4	1	5 6 Louver openings with size, type and location.
4	1	6 Orientation of veneer grain and/or directional pattern.
4	2	<b>DRAWINGS</b> requirements shall additionally include as applicable:
4	2	1 Trim members, shown in full-size profile.
4	2	2 Manufacturer's specifications or cut sheet showing construction.
4	2	3 <b>DETAILED SECTIONS</b> , minimum 1-1/2" = 1'-0" (1:10) scale, of:
4	2	3 1 Construction Type, 3, 5, or 7-ply for slab doors; solid or veneered for stile and rail.
4	2	3 2 Panel core type and thickness.
4	2	3 3 Diagram of hardware blocking locations at slab doors.
4	2	3 4 Stile and rail construction, including that of stiles, rails, raised panels, and moldings.
Continues next column ▼		

1.4.5		Section 6 - 12 Specific Rules
▲ From previous column		
4	<b>SECTION 9 - DOORS</b> (continued)	
4	2	<b>DRAWINGS</b> requirements (continued)
4	2	3 <b>DETAILED SECTIONS</b> (continued)
4	2	3 5 Stile and rail joints.
4	2	3 6 Louvers and/or lites.
4	2	3 7 Flame spread rating.
5 <b>SECTION 10 - CASEWORK:</b>		
5	1	<b>LISTING</b> requirements shall additionally include:
5	1	1 Exposed surface materials and if HPDL, its thickness.
5	1	2 Exposed interior surface materials and if HPDL, its thickness.
5	1	3 Semi-exposed surface materials and if HPDL, its thickness.
5	1	4 Concealed surface materials.
5	1	5 Inside face of cabinet door material and if HPDL, its thickness.
5	1	6 Panel core type and thickness.
5	1	7 Edgebanding material and thickness.
5	1	8 Drawer box material and construction.
5	1	9 Drawer slides or guides.
5	1	10 Hinges including finish.
5	1	11 Adjustable shelf pins, brackets, and/or standards including finish.
5	1	12 Miscellaneous finish hardware, including finish.
5	1	13 Glass type(s) and thickness.
5	1	14 Special metal work and/or specialty items.
5	1	15 Adhesive type(s).
5	1	16 Other materials such as plastic resin or acrylic.
5	1	17 Orientation of veneer grain and/or directional pattern.
5	2	<b>DRAWINGS</b> requirements shall include additionally, as applicable:
5	2	1 Reference plan, so work areas can be located in building.
5	2	2 Trim and/or scribe shown in full-size profile.
Continues next column ▼		

# SECTION 1

## Submittals

### GENERAL/PRODUCT

### compliance requirements

1.4.5		Section 6 - 12 Specific Rules
▲ From previous column		
5	SECTION 10 - CASEWORK (continued)	
5	2	DRAWINGS requirements (continued)
5	2	3 Casework, shown in plan, elevation, and section view, minimum 1/2" = 1'-0" (1:30) scale, including:
5	2	3 1 Countertops, per the specific requirements for countertops listed below.
5	2	3 2 Details need not be drawn if properly referenced to a supplementary provided document.
5	2	3 3 Dimensions necessary to construct cabinets.
5	2	3 4 Dimensions and attachment method of face-frame members.
5	2	3 5 Type and thickness of drawer members, including heights and depths.
5	2	3 6 Type and thickness of cabinet doors.
5	2	3 7 Section of each cabinet type or configuration.
5	2	3 8 Details of all joinery and connections.
5	2	3 9 Specification and location of special metal work and/or specialty items.
5	2	3 10 Additional laboratory casework requirements or details.
5	2	3 11 Provision for field dimensions.
5	2	3 12 Section details showing method of cabinet attachment to walls, floors, ceilings and any special seismic requirements.
5	2	3 13 Blocking or strapping requirements and their locations (blocking to be furnished by others) shown on cabinet elevations with dimensions off finished floor.
Continues next column ▼		

1.4.5		Section 6 - 12 Specific Rules
▲ From previous column		
6	SECTION 11 - COUNTERTOPS:	
6	1	LISTING requirements shall include, as applicable:
6	1	1 Panel core type and thickness.
6	1	2 Exposed material(s) description and thickness.
6	1	3 Backing sheet material(s) and thickness at countertop and/or splash.
6	1	4 Adhesive type.
6	1	5 Sealing compound type used at sink cutouts and/or splashes.
6	1	6 Orientation of veneer grain and/or directional pattern .
6	2	DRAWINGS shall include, as applicable:
6	2	1 Each countertop, including indication of field joints, if applicable, and:
6	2	1 1 Type, quantity and layout of joint fasteners.
6	2	2 Sink size, type, mounting and location if provided to manufacturer prior to shop drawing submittal.
6	2	3 Support brackets with notation, if furnished by others.
6	2	4 In elevation view; and:
6	2	4 1 Interface to casework and support brackets.
6	2	5 In section detail, minimum 3" = 1'-0" (1:5) scale, showing:
6	2	5 1 Front and/or end overhang.
6	2	5 2 Front and/or end edge types.
6	2	5 3 Splash type and height.
6	2	5 4 Drip groove.
6	2	5 5 End splash return.
6	2	6 Attachment of casework, including fastener type, quantity and layout.
Continues next column ▼		

# SECTION 1

## Submittals

GENERAL/PRODUCT

compliance requirements

1.4.5		Section 6 - 12 Specific Rules	
▲ From previous column			
7	<b>SECTION 12 - HISTORIC RESTORATION WORK:</b>		
7	1	The previous basic and specific section shop drawing requirements shall prevail for specific product types.	
7	2	A written Restoration and Conservation Program shall be developed with a qualified wood conservator and submitted for each phase of the restoration process, outlining:	
7	2	1 Where existing wood materials will need to be removed, repaired, and retained, including.	
7	2	2 The means and methods to catalog the wood members, remove, crate and protect, store, and reinstall.	
7	2	3 A plan for protection of surrounding materials, including interface with other trades.	
7	2	4 A plan to retain toxic and/or offensive off-gassing and provide adequate ventilation.	
7	2	5 A plan to date-stamp all new work in letters minimum 1/4" (6.4 mm) high noting the month, year, and the installer's or manufacturer's name in an area not exposed to view as a record of when the work was installed.	
7	3	<b>LISTING</b> requirements shall include, as applicable:	
7	3	1 Items to be repaired, including description, location, original material, and material to be used in repair.	
7	3	2 Items to be replaced, including description, location, material to be used, and basis for design.	
7	3	3 Specific restoration requirements for:	
7	3	3	1 Removal.
7	3	3	2 Storage.
7	3	3	3 Repair or patching.
7	3	3	4 Replacement criteria.
7	3	3	5 Stripping.
7	3	3	6 Refinishing.
7	3	3	7 Installation.
7	3	3	8 Adhesive type(s).
7	3	4	Material requirements, see:
7	3	4	1 Applicable Section(s) above, if not otherwise specified.
Continues next column ▼			

1.4.5		Section 6 - 12 Specific Rules	
▲ From previous column			
7	<b>SECTION 12 - HISTORIC RESTORATION WORK</b> (continued)		
7	4	<b>DRAWINGS</b> shall include plan, elevation, and section views, as applicable, of:	
7	4	1 See applicable Section(s) above.	
7	4	2 Reference plan showing location of each item to be repaired or replaced.	
7	4	3 Relationship of items to be repaired or replaced to building and architectural features.	
7	4	4 Section details in minimum 1-1/2" = 1'-0" (1:10) scale, of:	
7	4	4	1 Trim members in full scale.
7	4	4	2 Fabrication.
7	4	4	3 Joinery.
7	4	4	4 Attachment.
7	5	<b>SAMPLES</b> and <b>MOCK-UPS</b> shall include:	
7	5	1 Design professional's written acceptance of all representative visual qualities before proceeding with work, including:	
7	5	1	1 Any altered or modified methods and techniques used, as required, to achieve intended results.
7	5	2	Acceptable samples, suitably marked, during the restoration process as a standard for work to be performed.
7	5	3	For new work, prepare and have approved samples representative of all:
7	5	3	1 New molding and/or decorative profiles.
7	5	3	2 Panel, frame, stile and rail door, railing, and/or otherwise unique millwork assemblies.
7	5	3	3 Typical trim joinery and casework construction.
7	5	3	4 Fasteners.
7	5	4	For restoration work, perform sample restoration work of the following general processes on existing materials in an area directed by the design professional, of sufficient scope to demonstrate the effectiveness of proposed materials and techniques of each process:
7	5	4	1 To remove existing finishes.
7	5	4	2 Of patching, plugging, and/or cut-ins.
7	5	4	3 Of refinishing.

# North American Architectural Woodwork Standards - 3.1

## **S E C T I O N - 0 2**

# CARE & STORAGE

<b>Resources</b> . . . . .	<b><a href="#">40</a></b>
<b>Introduction</b> . . . . .	<b><a href="#">42</a></b>
<b>Advisory</b> . . . . .	<b><a href="#">42</a></b>
<b>Recommendations</b> . . . . .	<b><a href="#">42</a></b>
<b>Specification Considerations</b> . . . . .	<b><a href="#">42</a></b>
<b>Compliance Requirements</b> . . . . .	<b><a href="#">46</a></b>
<b>Scope &amp; Default Stipulation</b> . . . . .	<b><a href="#">47</a></b>
<b>Basic Rules</b> . . . . .	<b><a href="#">47</a></b>

### Within CANADA

#### SUPPORT

- **GUIDE SPECIFICATIONS** – Available for download in interactive digital format, including specification wording for Quality Assurance Program (GIS) at: <http://awmac.com/guide-specifications>
- **CONSULTATION** – Contact any of the local chapters for more information on the NAAWS or any other Architectural Woodwork Questions you may have. See below for contact information.
- **SPECIFICATION REVIEW** – Contact any of the local chapters if you would like your specifications reviewed for compliance to the NAAWS.
- **MANUFACTURER STANDARDS QUESTIONNAIRE (MSQ)** – AWMAC Manufacturer members have the opportunity to have at least one member of their staff study and write the MSQ. The MSQ is a questionnaire on the NAAWS and policy and procedures of the GIS program. A list of Manufacturer members that have passed the MSQ is available at: <http://awmac.com/members>
- **SEMINARS AND PRESENTATIONS** – Contact your local chapter to arrange an informative presentation on any Architectural Woodwork topic. Some topic options – GIS, NAAWS, How to Specify Quality Architectural Woodwork...
- **TRADE SHOWS** – Contact your local chapter to arrange for AWMAC to have a booth or do a presentation on Architectural Woodwork.
- **CONFERENCE** – AWMAC has an annual conference held at unique venues across Canada. The conferences provide an opportunity to learn more about Architectural Woodwork and network with Suppliers and Manufacturers from across Canada. More information is available at: <http://awmac.com/>
- **EDUCATION PARTNERS** – Contact the local chapters to find out more information about support for local Colleges and Universities offering woodworking related courses and programs.

#### QUALITY ASSURANCE

- **GUARANTEE AND INSPECTION SERVICE (GIS)** – The GIS is a national program designed to ensure that project owners get value and quality for their investment by:
  - Supporting architects and design professionals to achieve project plans and specifications; and
  - Helping contractors avoid problems such as cost overruns, delays and loss of reputation.More information is available at: <http://awmac.com/gis>

- **INSPECTION SERVICE** – A GIS Certified Inspector will inspect specific areas of concern on a project for compliance to the NAAWS and provide a written report. Contact your local chapter for more information.
- **EXPERT OPINION** – An expert will be appointed to inspect specific areas of concern on a project and provide a written report. Contact your local chapter for more information.

#### AWMAC CHAPTERS

- AWMAC British Columbia Chapter, Vancouver BC  
<http://bc.awmac.com>
- AWMAC Northern Alberta Chapter, Edmonton Alberta  
<http://nab.awmac.com>
- AWMAC Southern Alberta Chapter, Calgary Alberta  
<http://sab.awmac.com>
- AWMAC Saskatchewan Chapter, Saskatoon Saskatchewan  
<http://sk.awmac.com>
- AWMAC Manitoba Chapter, Winnipeg Manitoba  
<http://mb.awmac.com>
- AWMAC Ontario Chapter, Toronto Ontario  
<http://on.awmac.com>
- AWMAC Quebec Chapter, Montreal Quebec  
<http://qc.awmac.com>
- AWMAC Atlantic Chapter, Halifax Nova Scotia  
<http://atl.awmac.com>

### Within UNITED STATES

#### SUPPORT

- **GUIDE SPECIFICATIONS** - Available in interactive digital format including quality control options at: <http://woodworkinstitute.com/publications/architectural-woodwork-standards/>
- **AIA SEMINARS** - The Woodwork Institute is a Registered Provider of the American Institute of Architects (AIA), and its Continuing Education System (CES) program, check out our offerings at: <http://woodworkinstitute.com/architectural-resources/aia-seminars/> 
- **CONSULTATION** - Contact one of our Directors of Architectural Services (DAS) at: <http://woodworkinstitute.com/about-us-2/about-us/>
- **ACCREDITED FABRICATORS AND INSTALLERS** - Our AMC's (Accredited Millwork Company) represents the best fabricators and installers in our industry, check them out at: <http://woodworkinstitute.com/membership-listing-2/> 
- **CERTIFIED INDUSTRY PROFESSIONALS** - Our CMP's (Certified Millwork Professionals) represent the knowledge base of our industry, check them out at: <http://woodworkinstitute.com/membership-listing-2/> 
- **MILLWORK INDUSTRY PARTNERS** - Our MIP's (Millwork Industry Partners) represent the best of our industries material suppliers, check them out at: <http://woodworkinstitute.com/membership-listing-2/> 
- **ACKNOWLEDGED PRODUCTS LISTING** - If it's listed here, you are assured it meets NAAWS minimum requirements, find the listing at: <http://woodworkinstitute.com/acknowledged-product-listing/> 
- **CABINET DESIGN SERIES (CDS)** - Eliminate the need to include casework elevations in your architectural drawings, check out the CDS system in NAAWS "Design Resources" and access the cad files at: <http://woodworkinstitute.com/architectural-resources/cabinet-design-series/>

#### QUALITY ASSURANCE

- **BIDDER QUALIFICATION** - A discipline of bidder pre-qualification wherein your specifications protect you and your customer from the unknown: To be eligible to bid or negotiate this job, the subcontractor must be a Woodwork Institute Accredited Millwork Company (AMC) in good standing.  <http://woodworkinstitute.com/architectural-resources/quality-assurance>
- **CERTIFIED COMPLIANCE PROGRAM (CCP)** - A discipline of quality control used in conjunction with NAAWS providing an unbiased means of ensuring conformance to a project's plans and specifications. CCP, together with the use of the desired Grade(s) in the specifications, informs all parties of the design professional's expectations, without bidder discrimination.  <http://woodworkinstitute.com/services/certified-compliance-program>
- **MONITORED COMPLIANCE PROGRAM (MCP)** - A discipline of quality affirmation used in conjunction with the NAAWS which provides ongoing reviews/inspections of a project from its beginning through completion, ensuring strict conformance to the design intent throughout the millwork fabrication and installation process.  <http://woodworkinstitute.com/services/monitored-compliance-program/>
- **CERTIFIED SEISMIC INSTALLATION PROGRAM (CSIP)** - A standalone seismic assurance option which can be specified in conjunction with or without CCP or MCP, offering design professionals and project owners specific use of WI's seismic casework pre-approvals from California's Office of Statewide Health Planning and Development (OSHPD) without additional engineering costs and/or requirements, assuring proper backing has been installed in the walls when and where required.  <http://woodworkinstitute.com/services/certified-seismic-installation-program/>

# SECTION 2

## Care & Storage

## introductory information

### INTRODUCTION

Section 2 handles one of the most important aspects of preserving a good woodworking installation. Storage, jobsite conditions and relative humidity requirements before, during and after installation are covered here.

Quality assurance can be achieved by adherence to these standards and will provide the owner a quality product at competitive pricing. Working with an AWMAC Member (in Canada) or a WI Certified Millwork Professional (CMP) (in the USA) and the WI Accredited Millwork Company (AMC) they represent to provide your woodwork will help ensure the understanding and performance of the quality level required. Illustrations in this Section are not intended to be all inclusive, other engineered solutions may be acceptable. In the absence of specifications; methods of fabrication are the manufacturer's choice. The design professional, by specifying compliance to these standards increases the probability of receiving the product quality expected.

### ADVISORY

**DIMENSIONAL CHANGE prevention** can be a problem in architectural woodwork products because of uncontrolled relative humidity. This is further intended as a reminder of the natural dimensional properties of wood and wood-based products such as plywood, particleboard, and high pressure decorative laminate (HPDL) and of the routine and necessary care and responsibilities which must be assumed by those involved.

For centuries, wood has served as a successful material for architectural woodwork, and as history has shown wood products perform with complete satisfaction when correctly designed and used. Problems directly or indirectly attributed to dimensional change of the wood are usually, in fact, the result of faulty design, or improper humidity conditions during site storage, installation, or use.



Wood is a hygroscopic material, and under normal use and conditions all wood products contain some moisture. Wood readily exchanges this molecular moisture with the water vapor in the surrounding atmosphere according to the existing relative humidity. In high humidity, wood picks up moisture and swells. In low humidity, wood releases moisture and shrinks.

As normal minor fluctuations in humidity occur, the resulting dimensional response in properly designed construction will be insignificant. To reduce humidity related problems, the appropriate recommendations from Section 2 should be considered. Uncontrolled extremes can likely cause problems.

Together with proper design, fabrication, and installation, humidity control is obviously the important factor in preventing dimensional change problems.

Architectural woodwork products are manufactured as designed from wood that has been kiln dried to an appropriate average moisture content. Subsequent dimensional change in wood is and always has been an inherent natural property of wood. These subsequent changes are not necessarily the responsibility of the manufacturer. Specifically, responsibility for dimensional change problems in wood products resulting from:

- **Design** rests with the designer/architect/specifier.
- **Improper relative humidity** exposure during site storage and installation rests with the general contractor.
- **Humidity extremes** after occupancy rests with engineering and maintenance.

### RECOMMENDATIONS

• **CLIMATE CONTROL MAINTENANCE** of relative humidity every hour of every day, within the ranges shown previously in this section is important. Uncontrolled extremes such as those listed below will likely cause problems:



- Relative humidity, above or below the ranges shown previously in this section.
- Sudden changes in the allowable relative humidity, especially when it is repetitive.

### SPECIFICATION CONSIDERATIONS



- **NON-COMPLIANT ENVIRONMENTAL CONDITIONS**, such as:
- HVAC not maintained during hours of non-occupancy or on weekends.
  - Windows and doors intended to be open during occupancy.

### CARE

All construction related products, regardless of material, have particular care and storage requirements. Woodwork is not unique in this respect.

Architectural woodwork should be treated like fine furniture, particularly that which is constructed of wood finished with a transparent finish system. Modern commercial finishes are durable and resistant to moisture.

- **Finish Maintenance** - With the exception of true oil-rubbed surfaces, modern finishes do not need to be polished, oiled, or waxed. In fact, applying some polishing oils, cleaning waxes, or products containing silicone may impede the effectiveness of touch-up or refinishing procedures in the future.

Remove oil or grease deposits with a mild flax soap, following the directions for dilution on the container.

### CARE (continued)

No abrasives, chemical or ammonia cleaners should be used to clean woodwork surfaces. Routine cleaning is best accomplished with a soft, lint-free cloth lightly dampened with water or an inert household dust attractant. Allowing airborne dust, which is somewhat abrasive, to build up will tend to dull a finish over time.

- **Impact** - Avoid excessive or repetitive impact, however lightly applied. The cellular structure of the wood will compact under pressure. Many modern finishes are flexible, and will show evidence of impact and pressure applied to them.
- **Heat** - Avoid localized high heat, such as a hot pan or plate, or a hot light source, close to or in contact with the finished surface.
- **Photodegradation** – Avoid exposure to direct sunlight as this may alter the appearance of woodwork over time.
- **Humidity** - Maintain the relative humidity around the woodwork in accordance with the guidelines published in these standards, every hour of every day, to minimize wood movement.
- **Moisture** - Architectural woodwork, when properly finished, is relatively durable and resistant to moisture. Prevent direct contact with moisture, and wipe it dry immediately should any occur. Allowing moisture to accumulate on, or stay in contact with, any wood surface, no matter how well finished, will cause damage.
- **Oxidation** - Is a reaction of acids in wood (e.g., tannic acid), with iron, oxygen, and moisture, whether this be relative humidity or direct moisture. Control of moisture is a simple way to protect wood products from stains as a result of oxidation.

- **Abuse** - Use the trims, cabinets and fixtures, paneling, shelving, ornamental work, stairs, frames, windows, and doors as they were intended. Abuse of cabinet doors and drawers, for example, may result in damage to them as well as to the cabinet parts to which they are joined.
- **CLEANING** should be routine and accomplished with a soft, lint-free cloth lightly dampened with water or an inert household dust attractant. Allowing airborne dust, which is somewhat abrasive, to build up will tend to dull a finish over time.
  - Remove oil or grease deposits with a mild flax soap, following its directions for dilution.
  - Do not use abrasives, chemical or ammonia cleaners on fine architectural woodwork surfaces.
- **Refinishing** - Contact a local Sponsor Association member/affiliate, to explore the options for repair or refinishing. It is often cost effective to replace damaged woodwork elements rather than attempting large scale, on site refinishing.

### RELATIVE HUMIDITY AND MOISTURE CONTENT

The space in which architectural woodwork is to be installed should be engineered with appropriate humidity controls to maintain its optimum relative humidity. Wood for architectural woodwork manufacturing use needs a moisture content within an optimum range.

A major cause for failure in architectural woodwork is the lack of controls for maintaining a consistent, year round, appropriate relative humidity in a building or building space. Wood is susceptible to movement, shrinkage, expansion and warpage when exposed to air that has not been humidified. Without considerations made to properly regulate the relative humidity in any space containing architectural woodwork, some degree of failure of the woodwork can be expected.

Relative humidity outside the range shown on Table 2-001 below for the respective region is particularly harmful to wood and wood products.

This table is intended to establish a range in which architectural millwork can be properly stored, acclimatized, installed and maintained.

The most important effect of temperature is the effect it has on altering relative humidity levels. See Table 2-002. Once a controlled humidity and temperature environment has been established the humidity shall be maintained without sudden changes, especially repetitive changes. It is suggested that daily/monthly range vary no more than 10 F (5.6 C) degrees and 15% relative humidity.

The table and map that follow (adapted from USDA's *The Wood Handbook* (latest edition), published by their Forest Products Laboratory, <http://fpl.fs.fed.us/index.php>) shows the Optimum Moisture Content and the Indoor Relative Humidity required to hold such moisture content within the general areas of the United States and Canada.

Some of these areas have additional micro-climates not shown or referenced.




# SECTION 2

## Care & Storage

### introductory information

TABLE: 2-001 - RELATIVE HUMIDITY and OPTIMUM MOISTURE CONTENT

Geographical Location	Optimum Moisture Content		Optimum Climate Controlled Relative Humidity
	Non-Climate Controlled Interior or Exterior Environment	Climate Controlled Environment	
Most of U.S. and Canada	9-15%	5-10%	25-55%
Damp Southern Coastal areas of the U.S. and Canadian Eastern Coastal Provinces	10-15%	8-13%	43-70%
Dry Southwestern U.S.	7-12%	4-9%	20-50%
Alberta, Saskatchewan, and Manitoba in Canada	10-15%	4-9%	20-50%



### RECLAIMED OR RECYCLED WOOD

Ambient humidity and initial moisture content of reclaimed wood can be very important factors in insuring dimensional stability of the end product.

- With reclaimed wood moisture content may need to be addressed on a case by case basis. Typically “barn wood” is supplied “dry” and is of little concern in this regard. On the other hand timbers encrusted in earth or reclaimed from moist environments exposed to rain and water may require further drying to ensure stability.

- Additional drying may be particularly important when secondary milling is required to create the final form. Wood that may appear to be dry may contain a reservoir of moisture at its core which could be activated by further milling. This could result in a product which checks, cracks and distorts in unacceptable ways.

- For some design purposes instability may be a desired result. In other words, initial high moisture content may cause lumber to twist and crack after installation over time in ways that achieve a particular aesthetic result. Achieving these effects is the responsibility of the design professional working in close collaboration with the architectural woodwork manufacturer.

# SECTION 2

## Care & Storage

## introductory information

TABLE: 2-002 - EQUILIBRIUM MOISTURE CONTENT VALUES AT VARIOUS TEMPERATURES AND HUMIDITIES

The following table indicates relative humidity must average between 25% and 55% to maintain wood moisture content between 5-10%. This range is best suited for most of the U.S. and Canada. While temperature has an impact on relative humidity, temperature alone has little effect on wood products if the relative humidity is maintained within recommended ranges.

		Wet bulb lowering in degrees Fahrenheit																													
		2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29		
Dry bulb temperature in degrees Fahrenheit	40	83 17.6	75 14.8	68 12.9	60 11.2	52 9.9	45 8.6	37 7.4	29 6.2	22 5.0	15 3.5	8 1.9																			
	45	85 18.3	78 15.6	72 13.7	64 12.0	58 10.7	51 9.5	44 8.5	37 7.5	31 6.5	25 5.3	19 4.2	12 2.9	6 1.5																	
	50	86 19.0	80 16.3	74 14.4	68 12.7	62 11.5	56 10.3	50 9.4	44 8.5	38 7.6	32 6.7	27 5.7	21 4.8	16 3.9	10 2.8	5 1.5															
	55	88 19.5	82 16.9	76 15.1	70 13.4	65 12.2	60 11.0	55 10.1	49 9.3	44 8.4	39 7.6	34 6.8	28 6.0	24 5.3	19 4.5	14 3.6	9 2.5	5 1.3													
	60	89 19.9	83 17.4	78 15.6	73 13.9	68 12.7	63 11.6	58 10.7	53 9.9	48 9.1	43 8.3	39 7.6	34 6.9	30 6.3	26 5.6	21 4.9	17 4.1	13 3.2	9 2.3	5 1.3	1 0.2										
	65	90 20.3	84 17.8	80 16.1	75 14.4	70 13.3	66 12.1	61 11.2	56 10.4	52 9.7	48 8.9	44 8.3	39 7.7	36 7.1	32 6.5	27 5.8	24 5.2	20 4.5	16 3.8	13 3.0	8 2.3	6 1.4	2 0.4								
	70	91 20.9	86 18.2	81 16.5	77 14.9	72 13.7	68 12.5	64 11.6	59 10.9	55 10.1	51 9.4	48 8.8	44 8.3	40 7.7	36 7.2	33 6.6	29 6.0	25 5.5	22 5.0	19 4.3	15 3.7	12 2.9	9 2.3	6 1.5	3 0.7						
	75	91 21.0	86 18.5	82 16.8	78 15.2	74 14.0	70 12.9	66 12.0	62 11.2	58 10.5	54 9.8	51 9.3	47 8.7	44 8.2	41 7.7	37 7.2	34 6.7	31 6.2	28 5.6	24 5.1	21 4.7	18 4.1	15 3.5	12 2.9	10 2.3	7 1.7	4 0.9	1 0.2			
	80	92 21.2	87 18.7	83 17.0	79 15.5	75 14.3	72 13.2	68 12.3	64 11.5	61 10.9	57 10.1	54 9.7	50 9.1	47 8.6	44 8.1	41 7.7	38 7.2	35 6.8	32 6.3	29 5.8	26 5.4	23 5.0	20 4.5	18 4.0	15 3.5	12 3.0	10 2.4	7 1.8	5 1.1		
	85	92 21.3	88 18.8	84 17.2	80 15.7	76 14.5	73 13.5	70 12.5	66 11.8	63 11.2	59 10.5	56 10.0	53 9.5	50 9.0	47 8.5	44 8.1	41 7.6	38 7.2	36 6.7	33 6.3	30 6.0	28 5.6	25 5.2	23 4.8	20 4.3	18 3.9	15 3.4	13 3.0	11 2.4		
	90	92 21.3	89 18.9	85 17.3	81 15.9	78 14.7	74 13.7	71 12.8	68 12.0	65 11.4	61 10.7	58 10.2	55 9.7	52 9.3	49 8.8	47 8.4	44 8.0	41 7.6	39 7.2	36 6.8	34 6.5	31 6.1	29 5.7	26 5.3	24 4.9	22 4.6	19 4.2	17 3.8	15 3.3		
	95	92 21.3	89 19.0	85 17.4	82 16.1	79 14.9	75 13.9	72 12.9	69 12.2	66 11.6	63 11.0	60 10.5	57 10.0	55 9.5	52 9.1	49 8.7	46 8.2	44 7.9	42 7.5	39 7.1	37 6.8	34 6.4	32 6.1	30 5.7	28 5.3	25 5.1	23 4.8	22 4.4	20 4.0		
100	93 21.3	89 19.0	86 17.5	83 16.1	80 15.0	77 13.9	73 13.1	70 12.4	68 11.8	65 11.2	62 10.6	59 10.1	56 9.6	54 9.2	51 8.9	49 8.5	46 8.1	44 7.8	41 7.4	39 7.0	37 6.7	35 6.4	33 6.1	30 5.7	28 5.4	26 5.2	24 4.9	22 4.6			
110	93 21.4	90 19.0	87 17.5	84 16.2	81 15.1	78 14.1	75 13.3	73 12.6	70 11.4	67 10.8	65 10.4	62 9.9	60 9.5	57 9.2	55 8.8	52 8.4	50 8.1	48 7.7	46 7.5	44 7.2	42 6.8	40 6.6	38 6.3	36 6.0	34 5.7	32 5.4	30 5.2	28 5.0			
120	94 21.3	91 19.0	88 17.4	85 16.2	82 15.1	80 14.1	77 13.4	74 12.7	72 12.1	69 11.5	67 11.0	65 10.5	63 10.1	60 9.7	58 9.4	55 9.0	53 8.7	51 8.3	49 7.9	47 7.7	45 7.4	43 7.2	41 6.8	40 6.6	38 6.3	36 6.1	34 5.8	33 5.6			
		13% moisture										10% moisture										5% moisture									

### TO USE TABLE

Obtain wet and dry bulb readings. Subtract wet bulb reading from dry bulb reading. Find dry bulb on left margin of table and follow across to the column where the value at the top corresponds with the difference between wet and dry readings. At point of intersection, the upper figure in the square gives relative humidity in percent and the lower figure gives equilibrium moisture content of the woodwork.

### EXAMPLES OF MOISTURE EQUILIBRIUM TABLE USE

The above may be used as a guide in determining whether or not the conditions in a construction area are suitable for receiving woodwork. For example: if woodwork with an 8% average moisture content is to be installed and the average temperature in the building will be maintained at 70°F, it can be determined by following the 70°F column horizontally to the right until the lower moisture content figures of 8.3% and 7.7% are reached.

Here the upper figures in the same squares show that ideally a relative humidity of between 44% and 40% should be maintained in order to achieve dimensional equilibrium. After the woodwork is painted or finished, moisture changes in the wood are retarded so that maintenance of relative humidity between the practical limits shown on the curve (between 5%-10% m.c.) of the humidity table, i.e., 25%-55% relative humidity, is usually satisfactory.

# SECTION 2

## Care & Storage

GENERAL/PRODUCT

# compliance requirements

### INCLUDING: Care and Moisture Considerations Before, During, and After Installation

#### 2.1 BASIC CONSIDERATIONS

##### 1 GRADES - None

1.1 Care and storage requirements are the same for all architectural woodwork projects, regardless of Grade specified or required.

2 **DIMENSIONAL CHANGE RESPONSIBILITY** in wood products resulting from:



2.1 **IMPROPER DESIGN** rests with the design professional.

2.2 **IMPROPER RELATIVE HUMIDITY EXPOSURE** during site storage and installation rests with the contractor.

2.3 **HUMIDITY EXTREMES** after occupancy rests with the owner.

##### 3 INDUSTRY PRACTICES

3.1 **OFF GAS REDUCTION** by raising the temperature in a building for a sustained period is unacceptable and will negatively affect the appearance and performance of architectural millwork.



3.1.1 Open joints, warped paneling/doors, and other defects caused by such are not to be considered a defect.

# SECTION 2

## Care & Storage

### GENERAL/PRODUCT

## compliance requirements

### 2.2 SCOPE

1 All materials and products covered under the scope of these standards.

### 2.3 DEFAULT STIPULATION

1 Not used or applicable for this section.

### 2.4 RULES

1 The following rules shall govern unless a project's contract documents require otherwise.

2 These rules are intended to provide a well-defined degree of control over a project's quality of finishing.

3 **ERRATA**, published at <http://naaws-errata.com>, shall take precedence over these rules, subject to their date of posting and a project's bid date.



2.4.4		Basic General Rules	
1	DELIVERY	shall be:	
1	1	Made in accordance with a progress schedule furnished by the contractor, and:	
1	1	1	For climate controlled applications, in an area in which:
1	1	1	1 Wet work is dry.
1	1	1	2 Overhead work is complete.
1	1	1	3 Area is broom clean.
1	1	2	For non-climate controlled interior or exterior applications, in an area which is:
1	1	2	1 Clean.
1	1	2	2 Protected from direct moisture.
1	1	2	3 Protected from direct sunlight.
2	HANDLING	shall:	
2	1	Be with clean hands or gloves.	
2	2	Include protection from marks or damage.	
3	STORAGE	shall be:	
3	1	Flat on a level surface.	
3	2	Clean.	
3	3	At least 4" (101.6 mm) off the floor or ground.	
Continues next column ▼			

### 2.4.4 Basic General Rules

#### ▲ From previous column

3	STORAGE	(continued)		
3	4	Protected from:		
3	4	1	Sunlight, wide swings in relative humidity, and/or abnormal heat or cold.	
3	4	2	Moisture.	
3	5	For climate controlled applications:		
3	5	1	In a clean, closed building or area with operational HVAC system, and:	
3	5	1	1	Relative humidity meeting the range appropriate for the region per Table 2-001.
3	5	1	2	Maintained Optimum Moisture Content between 5 - 10% inclusive, except in:
3	5	1	2	1 The damp Southern Coastal areas of the U.S. and Canadian Eastern Coastal Provinces shall be between 8 - 13% inclusive.
3	5	1	2	2 The dry Southwestern U.S., and Alberta, Saskatchewan, and Manitoba in Canada shall be between 4 - 9% inclusive.
4	INSTALLATION	shall only occur after materials have been acclimatized for a minimum of 72 hours, and:		
4	1	For climate controlled applications, that:		
4	1	1	Is between 60 - 90 degrees Fahrenheit (15.5 - 32 degrees Celsius) inclusive.	
4	1	2	Has a maintained Relative Humidity between 25 - 55% inclusive, except in:	
4	1	2	1	The damp Southern Coastal areas of the U.S. and Canadian Eastern Coastal Provinces shall be between 43 - 70% inclusive.
4	1	2	2	The dry Southwestern U.S., and Alberta, Saskatchewan, and Manitoba in Canada shall be between 20 - 50% inclusive.
5	AFTER INSTALL and ACCEPTANCE:			
5	1	At climate controlled applications:		
5	1	1	Woodwork shall be maintained in the same environmental conditions as during its storage and/or installation.	
5	1	2	Temperature in a building or area of a building shall not be raised or lowered for a sustained period (more than 24 hours) for any reason as it may negatively affect the appearance and performance of architectural woodwork.	
Continues next column ▼				

# SECTION 2

## Care & Storage

GENERAL/PRODUCT

compliance requirements

<b>2.4.4</b>		<b>Basic General Rules</b>
▲ From previous column		
5	<b>AFTER INSTALL</b> and <b>ACCEPTANCE</b> (continued)	
5	2	At non-climatic controlled interior or exterior applications woodwork shall:
5	2	1 Have its finish maintained, refinishing as necessary (especially oiled finishes).
5	2	2 Be protected from excessive moisture and standing water.
6		<b>SEVERE DAMAGE</b> can result from not adhering to the above rules: 
6	1	Fabricator/Installer shall not be held responsible for the damage caused by not adhering to the above. 

# North American Architectural Woodwork Standards - 3.1

## **S E C T I O N - 03**

# LUMBER

<b>Resources . . . . .</b>	<b><a href="#">50</a></b>
<b>Introduction . . . . .</b>	<b><a href="#">52</a></b>
<b>Advisories . . . . .</b>	<b><a href="#">52</a></b>
<b>Specification Considerations . . . . .</b>	<b><a href="#">52</a></b>
<b>Design Resources . . . . .</b>	<b><a href="#">68</a></b>
<b>Compliance Requirements . . . . .</b>	<b><a href="#">69</a></b>
<b>Scope &amp; Default Stipulation . . . . .</b>	<b><a href="#">71</a></b>
<b>Basic Rules . . . . .</b>	<b><a href="#">71</a></b>
<b>Hardwood Rules . . . . .</b>	<b><a href="#">72</a></b>
<b>Softwood Rules . . . . .</b>	<b><a href="#">78</a></b>

### Within CANADA

#### SUPPORT

- **GUIDE SPECIFICATIONS** – Available for download in interactive digital format, including specification wording for Quality Assurance Program (GIS) at: <http://awmac.com/guide-specifications>
- **CONSULTATION** – Contact any of the local chapters for more information on the NAAWS or any other Architectural Woodwork Questions you may have. See below for contact information.
- **SPECIFICATION REVIEW** – Contact any of the local chapters if you would like your specifications reviewed for compliance to the NAAWS.
- **MANUFACTURER STANDARDS QUESTIONNAIRE (MSQ)** – AWMAC Manufacturer members have the opportunity to have at least one member of their staff study and write the MSQ. The MSQ is a questionnaire on the NAAWS and policy and procedures of the GIS program. A list of Manufacturer members that have passed the MSQ is available at: <http://awmac.com/members>
- **SEMINARS AND PRESENTATIONS** – Contact your local chapter to arrange an informative presentation on any Architectural Woodwork topic. Some topic options – GIS, NAAWS, How to Specify Quality Architectural Woodwork...
- **TRADE SHOWS** – Contact your local chapter to arrange for AWMAC to have a booth or do a presentation on Architectural Woodwork.
- **CONFERENCE** – AWMAC has an annual conference held at unique venues across Canada. The conferences provide an opportunity to learn more about Architectural Woodwork and network with Suppliers and Manufacturers from across Canada. More information is available at: <http://awmac.com/>
- **EDUCATION PARTNERS** – Contact the local chapters to find out more information about support for local Colleges and Universities offering woodworking related courses and programs.

#### QUALITY ASSURANCE

- **GUARANTEE AND INSPECTION SERVICE (GIS)** – The GIS is a national program designed to ensure that project owners get value and quality for their investment by:
  - Supporting architects and design professionals to achieve project plans and specifications; and
  - Helping contractors avoid problems such as cost overruns, delays and loss of reputation.More information is available at: <http://awmac.com/gis>

- **INSPECTION SERVICE** – A GIS Certified Inspector will inspect specific areas of concern on a project for compliance to the NAAWS and provide a written report. Contact your local chapter for more information.
- **EXPERT OPINION** – An expert will be appointed to inspect specific areas of concern on a project and provide a written report. Contact your local chapter for more information.

#### AWMAC CHAPTERS

- AWMAC British Columbia Chapter, Vancouver BC  
<http://bc.awmac.com>
- AWMAC Northern Alberta Chapter, Edmonton Alberta  
<http://nab.awmac.com>
- AWMAC Southern Alberta Chapter, Calgary Alberta  
<http://sab.awmac.com>
- AWMAC Saskatchewan Chapter, Saskatoon Saskatchewan  
<http://sk.awmac.com>
- AWMAC Manitoba Chapter, Winnipeg Manitoba  
<http://mb.awmac.com>
- AWMAC Ontario Chapter, Toronto Ontario  
<http://on.awmac.com>
- AWMAC Quebec Chapter, Montreal Quebec  
<http://qc.awmac.com>
- AWMAC Atlantic Chapter, Halifax Nova Scotia  
<http://atl.awmac.com>

# SECTION 3

## Lumber

## resources

### Within UNITED STATES

#### SUPPORT

- **GUIDE SPECIFICATIONS** - Available in interactive digital format including quality control options at: <http://woodworkinstitute.com/architectural-resources/specification-language/>
- **AIA SEMINARS** - The Woodwork Institute is a Registered Provider of the American Institute of Architects (AIA), and its Continuing Education System (CES) program, check out our offerings at: <http://woodworkinstitute.com/architectural-resources/aia-seminars/> 
- **CONSULTATION** - Contact one of our Directors of Architectural Services (DAS) at: <http://woodworkinstitute.com/about-us-2/about-us/>
- **ACCREDITED FABRICATORS AND INSTALLERS** - Our AMC's (Accredited Millwork Company) represents the best fabricators and installers in our industry, check them out at: <http://woodworkinstitute.com/membership-listing-2/> 
- **CERTIFIED INDUSTRY PROFESSIONALS** - Our CMP's (Certified Millwork Professionals) represent the knowledge base of our industry, check them out at: <http://woodworkinstitute.com/membership-listing-2/> 
- **MILLWORK INDUSTRY PARTNERS** - Our MIP's (Millwork Industry Partners) represent the best of our industries material suppliers, check them out at: <http://woodworkinstitute.com/membership-listing-2/> 
- **ACKNOWLEDGED PRODUCTS LISTING** - If it's listed here, you are assured it meets NAAWS minimum requirements, find the listing at: <http://woodworkinstitute.com/acknowledged-product-listing/> 
- **CABINET DESIGN SERIES (CDS)** - Eliminate the need to include casework elevations in your architectural drawings, check out the CDS system in NAAWS "Design Resources" and access the cad files at: <http://woodworkinstitute.com/architectural-resources/cabinet-design-series/>

#### QUALITY ASSURANCE

- **BIDDER QUALIFICATION** - A discipline of bidder pre-qualification wherein your specifications protect you and your customer from the unknown: To be eligible to bid or negotiate this job, the subcontractor must be a Woodwork Institute Accredited Millwork Company (AMC) in good standing. <http://woodworkinstitute.com/architectural-resources/quality-assurance> 
- **CERTIFIED COMPLIANCE PROGRAM (CCP)** - A discipline of quality control used in conjunction with NAAWS providing an unbiased means of ensuring conformance to a project's plans and specifications. CCP, together with the use of the desired Grade(s) in the specifications, informs all parties of the design professional's expectations, without bidder discrimination. <http://woodworkinstitute.com/services/certified-compliance-program> 
- **MONITORED COMPLIANCE PROGRAM (MCP)** - A discipline of quality affirmation used in conjunction with the NAAWS which provides ongoing reviews/inspections of a project from its beginning through completion, ensuring strict conformance to the design intent throughout the millwork fabrication and installation process. <http://woodworkinstitute.com/services/monitored-compliance-program/> 
- **CERTIFIED SEISMIC INSTALLATION PROGRAM (CSIP)** - A standalone seismic assurance option which can be specified in conjunction with or without CCP or MCP, offering design professionals and project owners specific use of WI's seismic casework pre-approvals from California's Office of Statewide Health Planning and Development (OSHPD) without additional engineering costs and/or requirements, assuring proper backing has been installed in the walls when and where required. <http://woodworkinstitute.com/services/certified-seismic-installation-program/> 

# SECTION 3

## Lumber

## introductory information

### INTRODUCTION

Section 3 is the first of two “material” sections and covers hardwood and softwood lumber. Included is a basic primer identifying wood characteristics and considerations. Basic rules pertaining to all solid wood as well as specific Hardwood Rules and Softwood Rules make up most of this section.

Quality assurance can be achieved by adherence to these standards and will provide the owner a quality product at competitive pricing. Working with an AWMAC Member (in Canada) or a WI Certified Millwork Professional (CMP) (in the USA) and the WI Accredited Millwork Company (AMC) they represent to provide your woodwork will help ensure the understanding and performance of the quality level required. Illustrations in this Section are not intended to be all inclusive, other engineered solutions may be acceptable. In the absence of specifications; methods of fabrication are the manufacturer’s choice. The design professional, by specifying compliance to these standards increases the probability of receiving the product quality expected.

### ADVISORIES

**PHOTODEGRADATION** - is the effect on the appearance of exposed wood faces caused by exposure to both sun and artificial light sources. If an entire face is exposed to a light source, it will photo-degrade somewhat uniformly and hardly be noticeable, whereas partially exposed surfaces or surfaces with shadow lines might show nonuniform photodegradation.

- Some woods, such as American Cherry, Fir and Walnut, are more susceptible than others, and extra care should be taken to protect against the effects of nonuniform photodegradation.



**OXIDATION** - is the effect on the appearance of exposed wood faces caused by exposure to atmosphere. This is analogous to browning reactions in freshly cut fruit; for instance, apples. Hardwoods can develop deep yellow to reddish brown discolorations on the surface of the wood when exposed to air immediately after sawing or peeling.

- These discolorations are especially noticeable on Cherry, Birch, Red Alder, Sycamore, Oak, Maple, and Sweet Gum. Some species, such as Alder, Oak, Birch, and Maple, develop these discolorations during air-seasoning. A related gray stain on several varieties of Southern Oaks also appears to be oxidative in nature. Proper selection, sanding, and finishing can minimize the effects of oxidation. Care should be taken when using filler, as it might not change the same as the wood.

### SPECIFICATION CONSIDERATIONS



- **UNIFORM COLOR**; special finishing techniques might be required (see Section 5).
- **SPECIAL CHARACTERISTICS**, such as sapwood, heartwood, ribbon stripe, quarter sawn, rift sawn, or vertical grain are only required if so specified.
  - **Natural** as a type selection of a species allows an unlimited amount of heartwood or sapwood within a face and is the default selection.
  - **Select Red** or **White** means all heartwood or sapwood, respectively for Birch and Maple.
  - **Select Brown** means all heartwood for Ash.
- **FIRE RETARDANT TREATMENT**
- **PRESERVATIVE TREATMENT**
- **EXTERIOR APPLICATIONS / DECAY RESISTANCE**

### LUMBER

Lumber used in architectural woodwork is divided into two groups:

- **Hardwoods**: Lumber obtained from angiosperms, usually deciduous trees (broad leaf trees). There are more angiosperms on Earth than any other plant group, over 200,000 species. About 900 of those species are commonly available for lumber or veneer throughout the world.
- **Softwoods**: Lumber obtained from gymnosperms, about 600 of which are coniferous trees such as pine, spruce and fir. The gymnosperms are among the largest and oldest living plants.

The above groups have no relationship to the density or “hardness” within or between various species. Some softwoods are harder than some hardwoods, and hardness varies greatly between species within each group.

# SECTION 3

## Lumber

## introductory information

### SPECIES SELECTION

The selection of the proper wood species for an architectural design can be the end result of a number of contributing factors and conditions. Intended use, costs, hardness, and relative stability are among many important considerations.

Lumber grades should always be referenced when specifying architectural woodwork. Selection of a grade (Economy, Custom, or Premium) for the finished product will define both materials and workmanship for that product. Lumber grades defined by the lumber manufacturers' associations allow some defects which the manufacturer must remove (cut out), or otherwise work around (by gluing, etc.).

The architect and designer may make his selection from a large variety of foreign and domestic species, now commercially available. The unique quality that wood imparts to design is that each species has its own distinguishing characteristics. Once the species is chosen, its effectiveness may vary according to the manner in which it is sawn, sliced as veneer, treated, and finished.

This Section is designed to advise the architect and designer in the comparisons, considerations, and species which should be evaluated before decisions are made and specifications are written. This Section will help you correlate and tabulate the information needed. An informed choice will reward the owner with the best possible performance by a natural building material.

### WOOD AS A PLANT

The trunk and its branches: The cross section of a tree shows the following well-defined features in succession from the outside to the center: (1) bark and cambium layer, (2) wood, which in most species is clearly differentiated into sapwood and heartwood, and (3) pith, the small central core.

The pith and bark, of course, are excluded from finished lumber.

Most branches originate at the pith, and their bases are inter-grown with the wood of the trunk as long as they are alive. These living branch bases constitute inter-grown or tight knots. After the branches die, their bases continue to be surrounded by the wood of the growing trunk and therefore loose or encased knots are formed. After the dead branches fall off, the stubs become overgrown, and subsequently clear wood is formed.

Growth in thickness takes place in the cambium layer by cell division. No growth in either diameter or length takes place in wood already formed; new growth is purely the addition of new cells, not the further development of existing cells.

### ANNUAL RINGS

Most species grown in temperate climates produce well-defined annual growth rings, which are formed by the difference in density and color between wood formed early and late in the growing season. The inner part of the growth ring formed first is called "spring wood," and the outer part formed later in the growing season is called "summer wood."

Spring wood is characterized by cells having relatively large cavities and thin walls. Summer wood cells have smaller cavities and thicker walls, and consequently are more dense than spring wood. The growth rings, when exposed by conventional methods of sawing, provide the grain or characteristic pattern of the wood. The distinguishing features of the various species are thereby enhanced by the differences in growth ring formation.

Some tropical species, on the other hand, experience year long even growth which may result in less obvious growth rings.

### SOFTWOODS and HARDWOODS

Native species of trees and the wood produced by these trees are divided into two botanical classes: hardwoods, which have broad leaves; and softwoods, which have needle-like or scale-like leaves. This botanical classification is sometimes confusing, because there is no direct correlation between calling a species a hardwood or softwood and the hardness or softness of the wood itself. Generally, hardwoods are more dense than softwoods, but some hardwoods are softer than many softwoods. If hardness is a desired characteristic, refer to the Comparative Table of Wood Species later in this section.

# SECTION 3

## Lumber

## introductory information

### HEARTWOOD

Heartwood consists of inactive cells formed by changes in the living cells of the inner sapwood rings, presumably after their use for sap conduction and other life processes of the tree have largely ceased. The cell cavities of heartwood may also contain deposits of various materials that frequently provide a much darker color. Not all heartwood, however, is darker.

The infiltrations of material deposited in the cells of heartwood usually make lumber cut from there more durable when exposed to weather. All wood, with the possible exception of the heartwood of Redwood and Western Red Cedar, should be preservative-treated when used for exterior applications.

### SAPWOOD

Sapwood contains living cells and performs an active role in the life processes of the tree. It is located next to the cambium and functions in sap conduction and storage of food. Sapwood commonly ranges from 1" to 2" (25-50 mm) in thickness. The Maples, Hickories, Ashes, and some of the Southern Yellow Pines and Ponderosa Pine may have sapwood 3" to 6" (76-152 mm) in thickness, especially in second growth trees.

### MEDULLARY RAYS

Medullary rays extend radially from the pith of the log toward the circumference. The rays serve primarily to store food and transport it horizontally. They vary in height from a few cells in some species to four or more inches in the Oaks, and produce the fleck (sometimes called flake) effect common to the quarter-sawn lumber in these species.




Figure: 3-001

### COMPARATIVE TABLE OF WOOD SPECIES

In order to simplify species selection, the following Comparative Table of Wood Species has been prepared showing pertinent characteristics of some species of domestic and foreign woods used by the architectural woodwork industry. The table can aid a design professional in proper species selection after studying the characteristics.

Careful analysis of the table will make it possible for an architect, designer or specification writers (who may have only a limited knowledge of architectural wood species) to make an informed selection. It is our intent that this tool will enhance understanding between the manufacturer of the woodwork you have designed and your profession, thereby enabling the building industry to better service the client.

- **Cost** has been broken into Low, Moderate, High, and Very High (V. High). The cost of lumber, as with other commodities, is influenced by supply and demand, both of which are constantly changing.
- **Hardness** is broken into Soft, Medium, Hard and Very Hard and takes into consideration the ability of the lumber species to sustain stress; resist indentation, abuse and wear; and to carry its anticipated load in applications such as shelving and structural members.
- **Dimensional stability** is helpful in selecting woods for use where humidity conditions may vary widely and where design or fabrication of a wood product does not allow free movement or the use of sheet products. The column figures indicate extreme conditions and show the maximum amount of movement possible in a 12" (305 mm) wide piece of unfinished wood where its moisture content increases or decreases from 10% to 5%. The possible change in dimension demonstrates that unfinished interior woodwork must be carefully protected prior to finishing by keeping it in rooms where relative humidity is between 25% and 55%. The column also shows the variation between species, and between flat grain and edge grain where such cuts are available commercially.

# SECTION 3

## Lumber

## introductory information

Table: 3-002 - COMPARATIVE WOOD SPECIE VALUES

Species	Costs <sup>(1)</sup>	Practical Size Limits <sup>(2)</sup>			Hardness	Dimensional Stability <sup>(3)</sup>
		Thickness	Width	Length		
Alder, Red	Low	1-1/2"	5-1/2"	10'	Soft	10/64"
Anigre	High	1-1/2"	5-1/2"	12'	Very Hard	No data
Ash, White	Moderate	2-1/2"	5-1/2"	12'	Hard	10/64"
Basswood	Low	2-1/2"	5-1/2"	10'	Soft	10/64"
Beech, American	Low	1-1/2"	5-1/2"	12'	Hard	14/64"
Beech, European	Moderate	2-1/2"	7-1/2"	16'	Hard	No data
Birch, Yellow - natural	Moderate	1-1/2"	5-1/2"	12'	Hard	12/64"
Birch, Yellow - select red	Moderate	1-1/2"	4-1/2"	11'	Hard	12/64"
Birch, Yellow - select white	Moderate	1-1/2"	4"	11'	Hard	12/64"
Cedar, Western Red	High	3-1/4"	11"	16'	Soft	10/64"
Cherry, American Black	High	2-1/2"	4"	7'	Hard	9/64"
Fir, Douglas - flat grain	High	3-1/4"	11"	16'	Medium	10/64"
Fir, Douglas - vertical grain	High	1-1/2"	11"	16'	Medium	6/64"
Hickory, True Group	Low	1-1/2"	4-1/2"	12'	Very Hard	11/64"
Mahogany, African - plain sawn	High	2-1/2"	9"	15'	Medium	7/64"
Mahogany, African - quarter sawn	V. High	2-1/2"	5-1/2"	15'	Medium	5/64"
Mahogany, American	High	2-1/2"	11"	15'	Medium	6/64"
Makore	High	1-1/2"	5-1/2"	12'	Very Hard	No data
Maple, Hard - natural	Moderate	3-1/2"	7-1/2"	12'	Very Hard	12/64"
Maple, Hard - select white	Moderate	2-1/2"	5-1/2"	12'	Very Hard	12/64"
Maple, Soft - natural	Moderate	3-1/2"	7-1/2"	12'	Medium	9/64"
Oak, English Brown	V. High	1-1/2"	4-1/2"	8'	Hard	No data
Oak, Red - plain sawn	Moderate	2-1/2"	7-1/4"	12'	Hard	11/64"
Oak, Red - rift sawn	High	1-1/16"	3-1/2"	8'	Hard	7/64"
Oak, Red - quarter sawn	High	1-1/16"	5-1/2"	8'	Hard	7/64"
Oak, White - plain sawn	Low	1-1/2"	5-1/2"	10'	Hard	11/64"
Oak, White - rift sawn	High	3/4"	3"	8'	Hard	7/64"
Oak, White - quarter sawn	High	3/4"	4"	8'	Hard	7/64"
Pecan Group, Hickory	Low	1-1/2"	4-1/2"	12'	Hard	11/64"
Pine, Eastern or Northern White	Moderate	1-1/2"	9-1/2"	14'	Soft	8/64"
Pine, Ponderosa	Moderate	1-1/2"	9-1/2"	16'	Soft	8/64"
Pine, Southern Yellow	Low	1-1/2"	7-1/2"	16'	Medium	10/64"
Pine, Sugar	Moderate	3-1/4"	11"	16'	Soft	7/64"
Poplar, Yellow	Low	2-1/2"	7-1/2"	12'	Medium	9/64"
Redwood, flat grain heartwood	Moderate	2-1/2"	11"	16'	Soft	6/64"
Redwood, vert. grain heartwood	Moderate	2-1/2"	11"	16'	Soft	3/64"
Teak	V. High	1-1/2"	5-1/2"	8'	Hard	6/64"
Walnut, American Black	Moderate	2-1/2"	4"	6'	Hard	10/64"

(1) Market conditions will cause these relationships to vary. These are raw costs without consideration of labor.

(2) Maximum practical sizes without lamination/gluing. Only 10% of any order is required to be at maximum sizes.

(3) These figures represent possible width change in a 12" (304.8 mm) board when moisture content is reduced from 10% to 5%. Figures taken are for plain sawn unless indicated otherwise in the species column.

# SECTION 3

## Lumber

## introductory information

### ALDER, RED (*Alnus rubra*)

Red Alder (also known as Oregon, Pacific Coast and Western Alder) has become an important utility lumber. Stable, economical and plentiful, it is used as a core for veneer and in the solid for mass produced furniture. The inner bark turns a reddish orange when exposed to the air, hence the name. Sourced predominately from the states of Oregon and Washington. Varies in color from almost white to pale pinkish brown and there is no visible boundary between heartwood and sapwood. Moderately light in weight and intermediate in most strength properties with relatively low shrinkage.



### ANIGRE (*Aningeria poteria*)

Anigre grows in Africa and is most common in the tropical areas of east Africa. The color varies from light yellowish brown with a pinkish tinge in the heartwood to golden brown. The grain is straight with uniform texture but can be wavy producing a mottled figure. Overall working characteristics are fair. Good nailing, screwing, gluing and staining properties. Used for cabinetwork and furniture.



### ASH, WHITE (*Fraxinus americana*)

While White Ash has always enjoyed widespread use for industrial products where hardness, shock resistance, stability and strength were important, its acceptance for architectural woodwork is increasing. It is open grained and has a strong and pronounced grain pattern. The heartwood is light tan or brown and its sapwood creamy white. Color contrast between the two is minor and its blonde effect makes it particularly appealing when a light or near natural finish is desired. Finished with darker tones it presents a bold effect. Its cost is moderate and it is readily available in lumber form. In veneered form some size limitation may be experienced but it can be easily produced on special order.



### BASSWOOD (*Tilia americana*)

Basswood is well suited to woodcarving and pattern making. Its critical quality is there being no contrast between early wood and late wood. This is unusual in wood, as normally the late wood would tear as you attempt to work against its natural bias. Otherwise basswood is almost featureless. Creamy white to light tan in color with a pink hue; yellows when a finish is applied. Has a straight grain with fine and even texture. Shrinkage in width and thickness during drying is high; however, seldom warps in use.



### BEECH, AMERICAN (*Fagus grandifolia*)

Beech grows in Eastern U.S. and adjacent Canadian Provinces. Color varies from nearly white sapwood to reddish brown heartwood; however, sometimes there is no clear demarcation between them. Heavy in weight with hard and strong properties that are highly suitable for steam bending. Machines smoothly, wears well, is well suited for turning and is easily treated with preservatives. Used for flooring, furniture, veneer, woodenware and when treated, for railroad ties.



### BEECH, EUROPEAN (*Fagus sylvatica*)

European Beech grows from the southern parts of Scandinavia to Sicily and from the French Atlantic coast to Poland. The color varies from pale pink brown heartwood to reddish brown tone when steamed and may have some dark veining. The grain is straight and fine with an even texture. The steam bending properties are exceptionally good. Stains well and is permeable for preservation treatment. Used for cabinetwork, furniture, flooring, heavy construction and marine piling (when pressure treated).



# SECTION 3

## Lumber

## introductory information

### **BIRCH, YELLOW** - natural, select red, select white (*Betula alleghaniensis*)

Yellow Birch has been and continues to be one of the prominent wood species used for architectural woodwork. This is due not only to its attractive appearance but also to its general availability both as lumber and as veneered products, its adaptability to either paint or transparent finish, and its abrasion resistance. The heartwood of the tree varies in color from medium to dark brown or reddish brown while its sapwood, which comprises a better than average portion of the tree, is near white. Despite its wide usage some confusion exists as to the common terms used to describe Birch lumber and/or veneer. Virtually all commercially used Birch is cut from the Yellow Birch tree, not from the White Birch tree, which botanically is a distinct species. The term "Natural" or "Unselected" Birch means that the lumber or veneer may contain both the sapwood, or white portion, as well as the heartwood, or dark portion, of the tree in unrestricted amounts. The term "Select Red" Birch describes the lumber or veneer produced from the heartwood portion of the tree, and the term "Select White" Birch describes the lumber or veneer produced from the sapwood portion of the tree. To obtain "Red" or "White" Birch exclusively requires selective cutting with corresponding cost premium as well as considerable restriction on the width and length availability in lumber form. Birch, in veneer form, is readily available in all "selections" and is usually rotary cut. While some sliced veneer is produced which simulates the same grain effect as lumber, its availability and cost reflect the same cutting restrictions that are incurred in producing the "select" forms of Birch lumber.



Natural



Select Red



Select White

### **CEDAR, WESTERN RED** (*Thuja plicata*)

Found in the Pacific Northwest and along the Pacific Coast to Alaska. With nearly white sapwood which is typically narrow, its heartwood runs reddish or pinkish brown to dull brown. It is generally straight grained with uniform coarse grain. With very low shrinkage, its lightweight, moderately soft, low in strength; however, very resistant to decay. Principally used for shingles, exterior siding, decks, standing and running trim, sash and doors.



### **CHERRY, AMERICAN BLACK** (*Prunus serotina*)

Wild Black American Cherry is a fine and especially stable close grained cabinet and veneer wood. Its heartwood color ranges from light to medium reddish brown. Its sapwood, which is a light creamy color, is usually selectively eliminated from the veneer and lumber. In some respects it resembles Red Birch, but has a more uniform grain and is further characterized by the presence of small dark gum spots which, when sound, are not considered as defects but add to its interest.

Cherry is available in moderate supply as lumber and architectural paneling and is usually plain sawn or sliced. Exceptionally rich appearance is achieved with transparent finishes which, together with its machining characteristics, justifies its identity with Early American cabinetry and furniture manufacturing, thus adding to its prestige as one of our most desirable native woods.



### **FIR, DOUGLAS** - (*Pseudotsuga taxifolia*)

Douglas Fir is a large, fast growing species and is native to the northwest. It accounts for much of the lumber produced in North America. While the preponderance of its production is developed for structural and construction type products, some of its upper grades are used for stock millwork and specialized woodwork. Its heartwood is reddish tan while its sapwood is creamy yellow. Since its growth rings are conspicuous, a rather bold grain pattern develops when either plain sawn for lumber or rotary cut as is common in plywood. Some lumber and veneer is cut edge or vertical grain, producing a superior form of the product since the tendency to "grain-raise" is greatly reduced.



# SECTION 3

## Lumber

## introductory information

### HICKORY, PECAN GROUP (*Carya cordiformis*, *illinoensis*, *aquatica* and *myristiciformis*)

Harvested typically in the Eastern half of the U.S. Sapwood is white to nearly white and relatively wide with somewhat darker heartwood. Predominately used for implement handles, furniture and decorative paneling.



### HICKORY, TRUE GROUP (*Carya ovata*, *glabra*, and *lacinosa*)

Harvested typically in the Middle to Southern Atlantic and Central U.S. The sapwood is white and usually quite wide with reddish heartwood. It is extremely tough, heavy, hard, strong and experiences considerable shrinkage in drying. Typically used for implement handles, ladder rungs, furniture and flooring.



### MAHOGANY, AFRICAN - (*Khaya ivorensis*)

This, one of the true Mahoganies, is perhaps the most widely used of the several Mahogany species. This is due to its excellent cutting and working characteristics and versatility. While its use has been largely for interior purposes, its innate stability and moderate decay resistance justifies its consideration for selected and demanding exterior applications. It has a very pleasing open grain, with its heartwood ranging in color from light to medium dark reddish brown. In lumber form it is more readily available as plain sawn and selectively so as quartersawn.

In veneer form the quarter or "ribbon striped" cut predominates, but plain sliced, as well as many of the exotic "figure" cuts, can be produced on special order.



### MAHOGANY, AMERICAN (*Swietenia macrophylla* - CITES listed)

This Mahogany species is commonly known as "Honduras Mahogany," but actually encompasses all of this species that grow throughout Mexico, Brazil, Peru, and Central America. Its traditional identity with casework and furniture justifies its position as one of the finest woods for this purpose. Its stability, workability, warm appearance, and firm grain make it a favorite of all woodworking craftsmen. It is a semi open grain wood, with its heartwood color ranging from light tan to a rich golden brown depending to some extent on the country of its origin. Its outstanding stability and decay resistance expands its potential to include exterior applications for "monumental" projects. It is most generally available as plain sawn lumber and plain sliced veneer with different veneer cuts available on special order.



### MAKORE (*Tieghemella heckelii*, *Tieghemella africana*)

Makore grows in Western and Middle Africa. The color varies from pink to reddish brown. The grain has a fine texture with closed pores and can be straight, interlocked or wavy. Generally easy to work, although sections with interlocked grain can cause tear out during planing. Suitable for turning and is easy to glue and finish. Used for cabinetwork, furniture, flooring, boat building and turned objects.



### MAPLE, SOFT GROUP (*Acer saccharinum*, *rubrum*, *negundo* and *macrophyllum*)

Typically found in Eastern U.S. with some in the Oregon Pacific Coast. Similar in appearance to hard Maple, heartwood is somewhat lighter in color than sapwood and wider. Soft Maple is not as heavy, hard or strong as Hard Maple. Typically used for railroad ties, furniture, veneer and wooden ware.



# SECTION 3

## Lumber

## introductory information

### MAPLE, HARD GROUP - natural or select white (*Acer saccharum* and *nigrum*)

Hard Maple is very similar in general characteristics to Yellow Birch. It is heavy, hard, strong, and resistant to shock and abrasion. The heartwood of the tree is reddish brown and its sapwood is near white with a slight reddish brown tinge. Another natural characteristic is the prevalence of dark mineral streaks (predominantly in the heartwood), which can be minimized in the sapwood by selective cutting. Like Birch, common usage of descriptive terms does occasion some confusion. The term "Natural" or "Unselected" Maple indicates that the lumber or veneer may contain both the white sapwood and the darker heartwood. The term "White" Maple means that the lumber or veneer is selected and separated from the pieces containing the dark heartwood. Unlike Birch, the heartwood is so low in content that no comparable selection is available. Maple's close identity with furniture and specialized industrial use overshadows its potential for architectural woodwork. Its modest cost, and pleasing, mild grain pattern warrants its consideration, especially on items subject to hard usage.



### OAK, ENGLISH BROWN (*Quercus robur*)

The English Brown Oak, or Pollard Oak is a tree which varies in height from 60'-130' (18-40 m) depending on soil conditions. It varies in color from a light tan to a deep brown with occasional black spots. It produces burls and swirls which are very brittle and fragile, but beautiful work can be obtained with their use. English Brown Oak is considered one of the finest woods in use today. English Brown Oak is obtained from trees which have had their tops cut out before reaching maturity. This pruning leads to the production of a number of new branches around the cut, and if these are subsequently lopped off, more new branches are formed. This wood is difficult to season and to work, tending to warp and twist in drying and to tear in working. The best figure is obtained from trees which have been cut out regularly every few years, the branches never being left sufficiently long for the production of large knots. The constant exposure of freshly cut surfaces promotes attack from parasites, the result being that a considerable portion of these trees become decayed sooner or later. This has made the timber relatively scarce and costly.



### OAK, RED - (*Quercus rubra*)

Red Oak is one of the most abundant of our domestic hardwoods. Its moderate cost, strength, wearability, and appealing grain characteristics make its use widespread. It is open grained and in its plain sawn or sliced form expresses a very strong "cathedral" type grain pattern. The heartwood is reddish tan to brown and very uniform in color. Its sapwood is lighter in color and minimal in volume, making its elimination by selective cutting very easy. Red Oak is also available in rift sawn or sliced form, which produces a very uniform straight grained effect. Less frequently it is quarter sawn or sliced, still producing a straight grain but with the fleck (sometimes called flake) of the medullary ray accentuated. Some sacrifice in width and length availability occurs when producing either rift or quarter sawn lumber.



Rift

# SECTION 3

## Lumber

## introductory information

### OAK, WHITE (Quercus alba)

White Oak, like Red Oak, is perhaps one of the best known hardwoods in the world, and its use for architectural woodwork is widespread. It is hard and strong. Its heartwood has good weathering characteristics, making its use for selected exterior applications appropriate. It is open grained and in its plain sawn form is highly figured. The heartwood varies considerably in color from light grayish tan to brown, making the maintenance of color consistency difficult. Its sapwood is much lighter in color, is fairly prevalent, and its elimination is accomplished by selective ripping. White Oak is often rift sawn or sliced, producing a very straight grained effect or frequently quarter sawn or sliced, producing straight grain, but with the fleck (sometimes called flake) of the medullary ray greatly pronounced. The special cuts mentioned are more readily attained in veneer form since the solid lumber cutting techniques greatly restrict its width and length potential.



Plain Sliced



Rift

### PECAN - (see Hickory, Pecan Group)

### PINE, PONDEROSA (Pinus ponderosa)

Ponderosa Pine is said to be the softwood species most commonly used for exterior and interior woodwork components. Its heartwood is tannish pink, while its sapwood is a lighter creamy pink. Its supply is extensive; found in commercial quantities in every state west of the Great Plains. Ponderosa Pine grows in pure stands and is abundant in mixed stands. Also, like most Pines, the proportion of sapwood is high and its heartwood has only a moderate natural decay resistance. Fortunately, its receptivity to preservative treatment is high, and since all Pines should be so treated when used on the exterior, it can be used interchangeably with them.



### PINE, EASTERN WHITE (Pinus strobus)

Found from Maine to Northern Georgia and the Great Lake States, it is typically called White Pine. Heartwood light brown, often with a reddish tinge and turns darker when exposed to air. Has relatively uniform texture, straight grain, low shrinkage and high stability. It's light weight, moderately low in strength and stiffness. Extensively used in patterns, sash, doors, furniture, interior woodwork, knotty paneling and caskets.



### PINE, SOUTHERN YELLOW - short leaf (Pinus echinata)

Southern Yellow Pine, commonly called Short Leaf Pine, is commercially important in Arkansas, Virginia, Missouri, Louisiana, Mississippi, Texas, and South and North Carolina, and is found in varying abundance from New York and south central Pennsylvania, south and westerly to eastern Texas and Oklahoma. The yellowish wood is noticeably grained, moderately hard, strong, and stiff. A cubic foot of air dried Southern Yellow Pine weighs 36 to 39 pounds. It is used extensively in house building, including framing, ceiling, weather boarding, panels, window and door frames, casing, and carved work. The grain shows well in natural finish or when stained. Frames of overstuffed furniture, chairs, desks, agricultural machinery, wood pulp, mine props, barrels, and crates are also made of this Pine.



# SECTION 3

## Lumber

### introductory information

#### **PINE, SUGAR** (*Pinus lambertiana*)

The world's largest species of pine typically found in California and South Western Oregon. It's heartwood is buff to light brown and sometimes tinged with red. It's straight grained with fairly uniform texture, low shrinkage and dimensionally stable, lightweight, soft, and moderately low in strength and stiffness. Used almost exclusively for boxes, sashes, doors, frames, general millwork and foundry patterns.



#### **POPLAR, YELLOW** (*Liriodendron tulipifera*)

Yellow Poplar, sometimes incorrectly called "Whitewood," is an extremely versatile and moderately priced hardwood that is well adapted to general interior woodwork usage. It is even textured, close grained, stable, of medium hardness, and has an inconspicuous grain pattern. The heartwood is pale greenish yellow while the sapwood is white. Occasional dark purple streaks also occur. The tight, close grain results in outstanding paint ability, while its modest figure and even texture permits staining to simulate more expensive hardwood. Due to its indistinct grain figure, Poplar is seldom used for decorative veneered products. Its white sapwood is not appropriate for use in exterior applications.



#### **REDWOOD** - heartwood (*Sequoia sempervirens*)

Redwood is the product of one of nature's most impressive accomplishments. The enormous size and unique inherent characteristics of this tree produce a material ideally suited for exterior applications. Its heartwood color is a fairly uniform brownish red, while its very limited sapwood is lemon colored. In its plain sawn form medium "cathedral" type figure develops, while in the vertical grain a longitudinal striped figure results. Its availability in "all heartwood" form with its outstanding natural resistance to decay accounts for its wide usage for exterior purposes. It is considered a very stable wood and its paint retention qualities are excellent. Redwood's principal identity with painted exterior application should not preclude its consideration for either exterior or interior use with transparent finish. Its pleasing and uniform color lends to a variety of such finishes suggesting the warmth and honesty of wood in its natural state. The size of the trees yields lumber of unusually character free widths and lengths.



#### **TEAK** (*Tectona grandis*)

Teak is one of the most versatile and valuable woods and has attained great prestige value. The figure variations are extensive and it is available in both lumber and veneered products. Adding to its appeal is its distinctive tawny yellow to green to dark brown color, often with light and dark accent streaks. It is perhaps most appealing in plain sawn or sliced cuts. While it has unique stability and weathering properties, making it ideal for exterior applications, its high cost usually limits its use to decorative interior woodwork, most often in veneer form. Its great beauty and interest dictate it being finished in its near "natural state."



# SECTION 3

## Lumber

## introductory information

### WALNUT, AMERICAN BLACK (*Juglans nigra*)

American Black Walnut is perhaps our most highly prized domestic wood species. Its grain pattern variations are extensive and in veneered form produces, in addition to its normal plain sliced cut, quartered or “pencil striped” as well as specialty cuts such as crotches, swirls, burls, and others. Its heartwood color varies from gray brown to dark purplish brown. The sapwood, which is very prevalent in solid lumber, is cream colored and its complete elimination by selective cutting is very costly. Fortunately, if this natural effect is felt to be undesirable, its appearance can be neutralized by sap staining in the finishing process. The growth conditions of Walnut result in significant width and length limitations in its lumber form. Its potential is best expressed in veneered products.



### OTHER SPECIES

There are many other species, both domestic and imported, used in woodworking. Nearly all are ecologically sound and appropriate for use. Using hardwoods for architecture gives value to the species, encouraging improved forest management techniques and the continuation of the species.

### ENDANGERED SPECIES

For a current list of endangered species see the Convention on International Trade in Endangered Species (CITES) Appendix I restricted table at <http://cites.org>.

### AESTHETIC CHARACTERISTICS

One of the qualities which contributes to the widespread use of wood is the option offered for aesthetic selection. It varies between species, between two logs of the same species, and between two boards from the same log. Aesthetic considerations in specifying wood are influenced by the following characteristics:

- **Color** - The basic hue of the species, which may be further enhanced by the finishing process employed.
- **Sapwood and heartwood** - The color of wood within a tree varies between the “sapwood” (the outer layers of the tree that continue to transport sap), which is usually lighter in color than the “heartwood” (the inner layers in which the cells have become filled with natural deposits). If desired, sapwood may be stained in the finishing process to blend with the heartwood. This difference in color is so pronounced in certain species that the sapwood is marketed under a different nomenclature from the heartwood.

Some examples are:

- **Select White Birch** - sapwood of Yellow or Paper Birch
- **Select Red Birch** - heartwood of Yellow Birch
- **Natural Birch** - both sapwood and heartwood of any Birch
- **Select White Ash** - sapwood of White or Green Ash
- **Select Brown Ash** - heartwood of Black Ash
- **Natural Ash** - both sapwood and heartwood of any Ash
- **Select White Maple** - sapwood of the Sugar Maple
- **Grain** - The appearance produced by the arrangement of wood fibers and pores of the species. Lumber grain may not match veneer grain.

- **Open Grain and Closed Grain** - Open grain woods are said to be ring porous and usually show a distinct grain pattern. Close grain woods are said to be diffuse-porous with even grain. The size and distribution of the cellular structure of the wood influences the appearance and uniformity. Open grain hardwoods, such as Elm, Oak, Ash, and Chestnut are ring-porous species. These species have distinct figure and grain patterns. Close grain hardwoods, such as Cherry, Maple, Birch, and Yellow Poplar, are diffuse-porous species. Most North American diffuse-porous woods have small, dense pores resulting in less distinct figure and grain. Some tropical diffuse-porous species (e.g., Mahogany) have rather large pores.
- **Figure** - Various species produce different grain patterns (figures), which influence the selection process. There will be variations of grain patterns within any selected species. The manufacturer cannot select solid lumber cuttings within a species by grain and color in the same manner in which veneers may be selected.

# SECTION 3

## Lumber

## introductory information

### AESTHETIC CHARACTERISTICS


(continued)

- **Finishing Characteristics** - The many species of wood vary considerably in their receptivity to the multitude of finishing processes on the market. Some woods, because of their open pores, will accept fillers while tighter grained woods will not. Some will show greater contrast between the "early wood" and the "late wood" when stained than others. Design professionals should take into consideration the finish that will be applied when selecting a particular species.

Consult with a Sponsor Association member/ affiliate about finishing prior to selection or specification. Providing large samples of the desired finish to manufacturers during the design phase and bidding process will assure the designer of obtaining an acceptable final product, while enabling the manufacturer to be aware of exactly what is required. Lumber might not accept transparent finishes in the same manner as veneer and special finishing techniques may be required.

### METHODS OF SAWING

Lumber is typically furnished plain sawn unless otherwise specified. Sawing methods, and the selection of boards after sawing the log, as shown below, produce the following types of lumber:



- **Plain Sawn (Flat Sawn)** - Plain sawing, the most common type of lumber sawing, yields broad grain, the widest boards and least waste. The annular rings are typically 30 degrees or less to the face of the board.



Figure: 3-004

- **Quarter Sawn** - Most often cut as Rift and Quartered, and then sorted for appearance, quarter sawn lumber is available in certain species, yields a straight grain, narrow boards, and fleck (sometimes called flake) or figure which runs across the grain in some species (notably the Oaks). Dimensional stability across the grain is the best. The annular rings run approximately 60 to 90 degrees to the face of the board, with the optimum being 90 degrees. Quartered lumber is generally narrower and more expensive than plain sawn of the same species.



Figure: 3-005

- **Rift Sawn** - Rift sawing produces small flecks caused by cutting through the wood rays. Only certain species produce these flecks, primarily Red and White Oak. Rift cutting reduces yield and increases cost. The annular rings run about 30 to 60 degrees to the face of the board, with the optimum being 45 degrees.



Figure: 3-006

### AVAILABILITY and SIZE LIMITATIONS

The supply of lumber is in constant flux throughout the world. It is affected by many factors such as current demand, export regulations of the country of origin, natural forces of weather, fire, disease, political situations, etc. Certain trees (species) naturally grow larger, thus producing longer and wider lumber. Other trees are smaller and produce narrow and shorter boards. The manufacturer must work with the available lumber, which must be considered when selecting any species. Consult a Sponsor Association member/ affiliate before specifying an uncommon species, or thickness, and/or long lengths which may not typically be available. If available, the cost may be substantially higher. Economies can be realized by detailing and specifying thicknesses and widths within the finish sizes of these standards.

# SECTION 3

## Lumber

## introductory information

### VENEERED CONSTRUCTION

Lumber can be used to secure wide and thick members in species with limited cutting potential. An acceptable technique is to apply thin lumber or veneer to the faces and edges of a compatible density lumber, structural composite lumber (SCL), or a medium density fiberboard core.




Figure: 3-007

### DIMENSIONAL STABILITY, RELATIVE HUMIDITY, and MOISTURE CONTENT

All woods are affected significantly by moisture and to a lesser degree by heat. Lumber swells and shrinks primarily in two directions: thickness and width. There is insignificant change in length. The changes in dimension due to moisture vary with different species, thus influencing the selection of lumber to use and the design elements.

Prevention of dimensional problems in architectural woodwork products as a result of uncontrolled relative humidity is possible. Wood products perform, as they have for centuries, with complete satisfaction when correctly designed and used. Problems directly or indirectly attributed to dimensional change of the wood are usually, in fact, the result of faulty design or improper humidity conditions during site storage, installation, or use.

Wood is a hygroscopic material, and under normal conditions all wood products contain some moisture. Wood readily exchanges this moisture with the water vapor in the surrounding atmosphere according to the relative humidity. In high humidity, wood picks up moisture and swells. In low humidity, wood releases moisture

and shrinks. As normal minor changes in humidity occur, the resulting dimensional response in properly designed construction will be insignificant. To avoid problems, it is recommended that the appropriate recommendations from Section 2 be maintained. Uncontrolled extremes are likely to cause problems. Together with proper design, fabrication, and installation, humidity control is the important factor in preventing dimensional change problems. The book *Understanding Wood* by Bruce Hoadley contains excellent data of wood and moisture.





Figure: 3-008

### SHRINKAGE Due to Drying



Shrinkage of 1" x 8" x 10' (25.4 x 203 x 3,048 mm)  
Dried from Green to Oven Dry  
Approximates: 3/64" (1.2 mm) in thickness  
3/4" (19 mm) in width  
1/8" (3.2 mm) in length

Figure: 3-009

Wood is anisotropic in its shrinkage characteristics. It shrinks most in the direction of the annual rings when it loses moisture from the cell walls. This illustration from USDA's *The Wood Handbook* (latest edition), published by their Forest Products Laboratory, shows the typical distortion of cuts from various parts of a log.




Figure: 3-010

Moisture can also cause iron stain (oxidation) in wood, also referred to as blue/black stain. Iron stain is a natural reaction of acids with iron, oxygen, and moisture (either high relative humidity or direct moisture) in wood. Control of moisture is a simple way to protect wood products from iron stain.

### ADAPTABILITY FOR EXTERIOR USE

Years of performance have shown certain species to be more durable for exterior applications. Heartwood shall be furnished when these species are designated for external use, excluding the sapwood. The following is a list of species generally considered acceptable for exterior use, from USDA's *The Wood Handbook* (latest edition), published by their Forest Products Laboratory, <http://fpl.fs.fed.us>:

- Cherry, Black
- Chestnut
- Douglas, Fir
- Eastern and Western Red Cedar
- Locust, Black
- Mahogany, American
- Oak, White
- Redwood, heartwood
- Spanish Cedar
- Teak, old growth

Baldcypress (*Taxodium distichum*) has a long tradition as a species resistant to decay, but beware! There are at least nine other species of four different genus which are marketed under the common name cypress. Only the heartwood of Baldcypress, often marketed as Tidewater or Red Cypress, is decay resistant. Sinker Cypress, that is old trees which have been brought up from below water in which they have been submerged for some time and properly cured and dried, is also resistant. None of this Cypress will come from new cutting, but as salvaged wood.

### Table: 3-011 - EXTERIOR APPLICATIONS

Where species selection should take decay resistance into consideration. The following species, when selected for **HEARTWOOD ONLY**, exhibit the listed decay resistance adapted from USDA's *The Wood Handbook* (latest edition) published by their Forest Products Laboratory, <http://fpl.fs.fed.us>:

If none of these species are specified, these standards require exterior woodwork to be **TREATED** with an industry-tested and accepted preservative formulation listed by **WDMA**, <http://wdma.com>.



### PRESERVATIVE TREATMENTS

Modern technology has developed methods of treating certain species to extend their life when exposed to the elements. Some lumber species used for exterior architectural woodwork may be treated with an industry tested and accepted formulation. One such formulation is a liquid containing 3-iodo-2-propynyl butyl carbamate (IPBC) as its active ingredient, which must be used according to manufacturer's directions.

The Window & Door Manufacturers Association (WDMA), through the treatments and coatings committee, has reviewed information from third party testing laboratories which indicates that the number of formulations at the stated

in use concentration meet the requirements of WDMA I.S.4 (latest edition). The formulations are acceptable for use under the WDMA Hallmark Water Repellent Non Pressure Preservative Treatment Certification Program and are adopted to meet all requirements.

VERY RESISTANT:	
<b>Domestic:</b>	
Locust, Black	Yew, Pacific
<b>Import:</b>	
Goncalo Alves	Lignumvitae
Ipe (Iapacho)	Purpleheart
Jarrah	Teak (Old Growth)
RESISTANT:	
<b>Domestic:</b>	
Baldcypress (Old Growth)	Juniper
Cedar	Oak, White
Cherry, Black	Redwood (Old Growth)
Chestnut	Walnut, Black
Cypress, Arizona	
<b>Import:</b>	
Mahogany, American	Spanish Cedar
MODERATELY RESISTANT:	
<b>Domestic:</b>	
Baldcypress (Young Growth)	Redwood (Young Growth)
Fir, Douglas	Tamarack
Larch, Western	
<b>Import:</b>	
Avodire	Mahogany, African
Benge	Meranti, Dark Red
Bubinga	Sapele
Keruing	Teak (Young Growth)

# SECTION 3

## Lumber

## introductory information

### FIRE RETARDANT WOOD

The natural fire retardant qualities and acceptability of treatments vary among the species. Where items of architectural woodwork are required to have a flame spread classification to meet applicable building and safety codes, the choice of lumber species must be a consideration. Most treated species are structural softwoods.

Following are some references to assist in making these choices. Additional data on various species may be available from USDA's The Wood Handbook (latest edition), published by their Forest Products Laboratory.

- Built-up construction** to Improve Fire Rating: In lieu of solid lumber, it is often advisable, where a fire rating is required, to build up members by using treated cores clad with untreated veneers not thicker than 1/28" (1 mm). Some existing building codes, except where locally amended, provide that facing materials 1/28" (1 mm) or thinner finished dimension are not considered in determining the flame spread rating of the woodwork.
 

In localities where basic model building codes have been amended, it is the responsibility of the specifier to determine whether the application of the facing material specified will meet the code.

- Fire retardant treatments (FRT):** Some species may be treated with chemicals to reduce flammability and retard the spread of flame over the surface. This usually involves impregnating the wood, under pressure, with salts suspended in a liquid. The treated wood must be re-dried prior to fabrication. FRT wood may exude chemicals in relative humidity above 85%, damaging finishes and corroding metals in contact with the FRT surface. Consult with a manufacturer about the resulting appearance and availability of treated woods prior to specification.
 

Hardwoods currently being treated (Flame spread less than 25) include 4/4 Red Oak, and 4/4 to 8/4 Poplar. These woods can be machined after treatment, although machining may void the label classification. Fire retardant treatment does affect the color and finishing characteristics of the wood.

According to the traditional model codes in the USA and subject to local code modifications, untreated wood and wood products can usually be used in up to 10% of the combined surface area of the walls and ceiling. Casework, furniture, and fixtures are rarely fire rated, and can be built of combustible materials.

### FLAME SPREAD CLASSIFICATIONS

This is the generally accepted measurement for fire rating of materials. It compares the rate of flame spread on a particular species with the rate of flame spread on untreated Oak. Most authorities accept the following classes for flame spread:

- Class A 0-25
- Class B 26-75
- Class C 76-200

**Table: 3-012 - FLAME SPREAD and SMOKE DEVELOPED INDEXES**

Common woods species, adapted from USDA's The Wood Handbook (latest edition), published by their Forest Products Laboratory, and based on 3/4" (19 mm) thick solid lumber:

Species	Flame Spread Index	Smoke Developed Index
<b>SOFTWOODS</b>		
Yellow Cedar	78	90
Baldcypress	145 - 150	---
Cedar, Western Red	70	213
Fir, Douglas	70 - 100	---
Fir, Pacific Silver	69	58
Hemlock, Western	60 - 75	---
Pine, Eastern White	85 - 215	---
Pine, Ponderosa	105 - 230	---
Pine, Red	142	229
Pine, Southern	130 - 195	---
Pine, Western White	75	---
Redwood	70	---
Spruce, Eastern	65	---
Spruce, Sitka	74 - 100	---
<b>HARDWOODS</b>		
Birch, Yellow	105 - 110	---
Cottonwood	115	---
Maple	104	---
Poplar, Yellow	170-185	---
Oak, Red / White	100	100
Sweetgum	140-155	---
Walnut	130 - 140	---

# SECTION 3

## Lumber

## introductory information

### RECLAIMED or RECYCLED WOOD

**EVOLUTION** - In recent years, with the interest in “Green” alternative materials and the reuse of previously used materials, the architectural millwork industry has seen an increase in the specifying of reclaimed wood. While there are many similarities between reclaimed wood and new wood there are enough significant differences to create a need for enhanced industry standards.

**MOTIVATION** - The reuse of previously used wood in millwork projects comes from the desire to:

- Reduce the need for harvesting trees from our forests. Every board we can reclaim from prior use is a tree we do not need to cut down. This comes from a sincere desire to retain our natural resources for future generations.
- Reduce the unnecessary additions to our landfill. In the past most of the wood that was previously used was demolished and sent to landfill. In many cases the wood is of high quality and easily re-purposed for use again.
- Gain LEED credit.
- Create a connection to the past from characteristics such as weathering, nail holes, or other distress or patina imprinted on the material by time and previous use are elements which are valued in this design choice.

**SOURCES** - Examples of reclaimed lumber are so-called barn wood and wood from old demolished structures like water storage tanks, wine tanks, wood pilings and even underwater forests and sunken logs.

Sources and types of reclaimed materials vary greatly in their type, quality, availability, aesthetics and cost. A sample of material used for selection may not match actual available material in species, color, texture, surface quality or structural composition when it comes time to make a purchase.

Design professionals and specifiers should be aware of the limitations of availability of species, cut, quantity, lead time, waste factor and cost of material. These materials are normally sold “as is” and are not returnable.

Logs harvested over 100 years ago and transported by water often sank en route to mills. The resulting “lost underwater forest” lay on the bottoms of rivers and lakes until recently as proper environmental and mechanical procedures for retrieving them have been developed.

Reclaimed submerged materials are utilized in all aspects of construction of furniture, architectural woodwork and musical instruments. Submerged lumber is generally processed in both solid lumber, plain sliced and rotary veneer.

The uniqueness of the harvesting procedures, the high quality of the material and unusual aesthetic qualities are a few of desirable traits associated with this special material.

It is advisable that the design professional and woodworker see the material at the supplier to determine the availability and suitability for the intended use.

**LACK OF STANDARDS** - Whereas conventional wood and veneer materials have been relatively easy to set industry standards for, the very nature of reclaimed wood and the reasons we use it make its classification and standardization more subjective, such as:

- There are no standard dimensions for reclaimed wood.
- There are no grading standards for appearance or surface condition, therefore there are no measurable characteristics and defects established by which to reject unsuitable materials once such is purchased.
- Often, what are considered flaws and degrades in conventional lumber (checks, splits, knots and warp) might be considered desirable “character” in reclaimed applications.

- Because of the finite nature of reclaimed wood, the quantities available may not match the quantities required for a given project.

It is advisable that the design professional and woodworker see the material at the supplier to determine the availability, suitability and performance needs for the intended use and agree on the materials range of color, grain, distress, character, and patina.

**MATERIAL SELECTION** - Because reclaimed or recycled wood is unique and finite, specification begins with specific material selection made by the design professional or client, possibly in collaboration with the woodwork manufacturer.

Early involvement of the woodwork manufacturer will typically lead to a better understand the design intent and their assistance in finding suitable reclaimed material in the appropriate dimensions and quantities. They will also be able to help with suggestions about species, surface condition and color. Important considerations:

- Aesthetic consideration.
- Desired surface condition (original surface, re-sawn, surfaced).
- Desired finish condition (painted as it comes, newly painted, sealed, unfinished).
- Acceptability of natural defects (knots, checks, etc.), evidence of previous use (bolt holes, nail holes, gouges and notches) or evidence of previous bug infestation.
- Desired grain (flat sawn, vertical grain).
- Intended use (i.e. paneling, furniture, indoors, outdoors).
- Intended fastening (face nailed, blind nailed, panel clips).
- Approximate quantity of material required.

Once a material source has been selected, control samples (that are labeled, numbered, dated and signed) should be developed to establish the agreed acceptability of material finish, characteristics, whether natural or from previous use. Taking into consideration that providing large and repetitive samples to show a full range or material characteristics is recommended

# SECTION 3

## Lumber

## introductory information

### RECLAIMED or RECYCLED WOOD

(continued)

**CARE & STORAGE** - Beyond the basic rules of Section 2 ambient humidity and initial moisture content of reclaimed wood can be very important factors in insuring dimensional stability of the end product.

- With reclaimed wood moisture content may need to be addressed on a case by case basis. Typically “barn wood” is supplied “dry” and is of little concern in this regard. On the other hand timbers encrusted in earth or reclaimed from moist environments exposed to rain and water may require further drying to ensure stability.
- Additional drying may be particularly important when secondary milling is required to create the final form. Wood that may appear to be dry may contain a reservoir of moisture at its core which could be activated by further milling. This could result in a product which checks, cracks and distorts in unacceptable ways.
- For some design purposes instability may be a desired result. In other words, initial high moisture content may cause lumber to twist and crack after installation over time in ways that achieve a particular aesthetic result. Achieving these effects is the responsibility of the design professional working in close collaboration with the architectural woodwork manufacturer.

#### DESIGN PROFESSIONAL RESPONSIBILITY

With unique material like reclaimed or recycled wood for architectural millwork the design professional needs to take an active role in sourcing and pre-approving their desired selections. With these materials there is no traditional guidelines to reassure either the woodwork manufacturer or architect of achieving the result they expect.

There will be situations where the design professional may have to directly participate in the selection process piecemeal, accepting some material and rejecting others as not suited to the purpose.

**CONTRACT DOCUMENTS**, shall clearly indicate or delineate all material, fabrication, installation and applicable building code/regulation requirements with the clear understanding that incomplete design choices, changes in scope or material selection, lack of material selection, or design choices made after initial bid may impact the cost or not be possible.

The contract documents shall specifically list the material source and identifier, and address the allowable:

- Variation in color or tone
- Defects, such as nail holes, checking, cracking, discoloration, milling marks, roughness in terms of quantity, locations, repetition, etc.
- Distortion in terms of straightness, cupping, flatness, etc.

See SECTION 3 for additional information.

### NONTRADITIONAL MATERIALS

Covers materials re-purposed from other industrial and manufacturing areas, but assigned to the woodwork manufacturer and treated similarly to traditional millwork items like wall paneling. From a design perspective considerations of appearance, color, finish, variation and relation are deemed important as they would be with traditional wood products.

Examples of non-traditional materials could be a fiber/cement panel designed for fire resistance, insulation re-purposed as a decorative panel, metal products, cloth, acrylics, etc.

Because these materials are unique, contract documents, shall clearly indicate or delineate all of the necessary material, fabrication, installation and building code/regulation direction and requirements as may be applicable for the manufacturer/installer to reasonably accomplish the intended design concept.

### ENGINEERED PRODUCTS

#### STRUCTURAL COMPOSITE LUMBER (SCL) —

A man made composite that utilizes grain oriented wood strands from a variety of tree species, providing an alternative to dimension lumber. The material is engineered for strength and stability. While SCL is not really “lumber,” it is marketed as a lumber substitute. SCL can be specified as core, stile backers, and core for stiles and rails, so long as all other criteria of these standards are met in relation to its use.

**LAMINATED VENEER LUMBER (LVL)** - A lumber substitute made with veneer plies bonded in parallel. LVL is made using many tree species and this diversity increases the performance characteristics and product potential.

### DESIGN RESOURCES



Is a perpetually expanding, web based resource of pictures, videos, illustrations, ideas and design concepts for inspiring thought and design creativity - assessable at: <http://naaws-design-resources.com>

Relative to this Section, offerings will include:

- Wood specie spictures
- Wood cut options

# SECTION 3

## Lumber

### GENERAL/PRODUCT

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



## compliance requirements

Including: **Hardwood** and **Softwood**

### 3.1 BASIC CONSIDERATIONS

#### 1 GRADES

1.1 **GRADE CLASSIFICATIONS ECONOMY, CUSTOM, and PREMIUM** are used within these standards only in reference to the acceptable quality of workmanship, material, or installation in a completed architectural woodwork product covered in sections 6 - 12.

1.1.1 In this section, the use of these classifications is only for the purpose of identifying lumber that can be used in finished products meeting those Grades.

1.1.2 These classifications are not intended to be used as Grades of raw material or to judge a stand alone board or member.

2 **LUMBER ASSOCIATION RULES** shall not be used, since even their highest Grades permit defects unacceptable in architectural woodwork and are not based upon the use of the whole piece, but rather on a percentage of the piece.

2.1 The appearance of a piece in the end product is of importance, not whether it is cut from a larger board that contained defects that can be eliminated.




Figure: 3-013

#### 3 LUMBER RULES

3.1 Apply only to surfaces visible after manufacture and installation.

3.2 Establish criteria as to which, if any, natural or seasoning characteristics are acceptable.

3.3 Limit the extent of characteristics that will be permitted based on an exposed area's size and proximity of characteristics to one another.

3.4 Do not apply to special varieties of species that display unusual characteristics desirable for aesthetic and design reasons.

### 3.1 BASIC CONSIDERATIONS (continued)

4 **CONTRACT DOCUMENTS** shall govern if in conflict with these standards.

5 **TRANSPARENT FINISHES** in lumber may not be accepted in the same manner as plywood; special finishing techniques might be required (see Section 5).

6 **RECONSTITUTED LUMBER** is typically manufactured from sliced wood veneer, which in some cases are dyed, then glued up and sawn in such a manner as to imitate dimensional lumber species. Use of these engineered products are allowed only if specified and/or approved by the owner and/or design professional.

7 **SPECIAL and UNUSUAL CHARACTERISTICS**, for example **HICKORY, PECAN, BUTTERNUT, KNOTTY PINE, WORMY CHESTNUT, PECKY CYPRESS, and WATTLED WALNUT** are not covered by these standards, and:

7.1 If their use is contemplated, individual ranges of characteristics and availability should be investigated and specified accordingly.

8 **MAHOGANY, AMERICAN** varies in color from a light pink to a light red, reddish brown to a golden brown or yellowish tan, and:

8.1 Figure or grain includes plain sliced, plain to broken stripe, mottled, fiddleback, swirl and crotches.

8.2 It can turn darker or lighter in color after machining.

9 **LAUAN, TANGUILE**, and other species are native to the Philippine Islands and are sometimes referred to as Philippine Mahogany; however, they are not a true Mahogany.

9.1 **MAHOGANY** is a generic term and should not be specified without further definition, such as American or African Mahogany.

10 **CHERRY, WALNUT**, and certain other hardwood species are required to be specified by origin, such as American Cherry, American Walnut, or English Brown Oak, because they can be significantly different in color and texture.

# SECTION 3

## Lumber

### GENERAL/PRODUCT

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



## compliance requirements

### 3.1 BASIC CONSIDERATIONS (continued)

#### 11 INDUSTRY PRACTICES

- 11.1 Lumber is furnished plain sawn unless otherwise specified.
- 11.2 Hardwood is typically not recommended for exterior use.
- 11.2.1 Exceptions include Apitong, American Mahogany, White Oak, Teak, and Tanguile.
- 11.3 Lumber is dimensioned in the following conventional order: thickness, followed by width (across the grain direction), followed by length (with the grain direction); see drawing:




Figure 3-014

- 11.4 **GLUING** for thickness and/or width is permitted as governed by these standards; see drawing:



Figure 3-015




Figure 3-016

#### 11.5 SPECIFICATION:

- 11.5.1 Of **PHILIPPINE MAHOGANY** permits the use of Lauan, Tanguile, and other natural Philippine species.
- 11.5.2 By the generic term **MAHOGANY** means genuine Mahogany, such as American or African.
- 11.6 **SPECIES** not specifically covered by these standards shall be as agreed to between owner/design professional and manufacturer/installer as to length requirements and size/exposed area of permitted natural characteristics.

# SECTION 3

## Lumber

### GENERAL/PRODUCT

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



## compliance requirements

### 3.2 SCOPE

- 1 All materials and products covered under the scope of these standards.

### 3.3 DEFAULT STIPULATION

- 1 If not otherwise specified or indicated in the contract documents, sheet products shall match the default stipulation of the applicable product portion of these standards.



### 3.4 RULES

- 1 The following rules shall govern unless a project's contract documents require otherwise.
- 2 These rules are intended to provide a well-defined degree of control over a project's quality of materials and workmanship.
- 3 **ERRATA**, published at <http://naaws-errata.com>, shall take precedence over these rules, subject to their date of posting and a project's bid date.



### 3.4.4 Basic General Rules

1	<b>AESTHETIC</b> Grade rules apply only to exposed and semi-exposed surfaces visible after installation.
2	<b>VISIBLE SURFACES</b> shall be sound lumber, free of decay, shake, pith, wane and warp.
3	" <b>BOARD</b> " refers to a piece of lumber before gluing for width or thickness.
4	" <b>MEMBER</b> " refers to a piece of lumber after gluing for width or thickness.
5	<b>LUMBER</b> shall be plain sawn.
6	Lumber is <b>DIMENSIONED</b> by thickness, followed by width (across the grain direction), followed by length (with the grain direction).
7	<b>SPECIAL CHARACTERISTICS</b> , such as sapwood, heartwood, ribbon stripe, quarter sawn, rift sawn, and vertical grain are not required unless specified.
8	<b>MOISTURE CONTENT</b> of lumber shall be in compliance with Section 2.
9	<b>EXTERIOR</b> use of lumber for architectural millwork requires the lumber to be preservative treated in accordance with WDMA I.S. 4 (latest edition), unless the lumber is classified as "Resistant or Very Resistant" in accordance with USDA's The Wood Handbook (latest edition), published by the Forest Products Laboratory.
10	<b>GLUING</b> for thickness and/or width is permitted as governed by this Section, and:
10 1	Requires a <b>RIGID GLUE</b> line in accordance with the <b>ADHESIVE GUIDELINES</b> within the <b>APPENDIX</b> . 
10 2	<b>DELAMINATION</b> or <b>SEPARATION</b> shall not occur.
11	<b>PHILIPPINE MAHOGANY</b> shall permit the use of Lauan, Tanguille, and other natural Philippine species.
12	<b>SPECIES NOT specifically COVERED</b> by these standards shall be as agreed to between design professional and manufacturer/installer as to length requirements and size/exposed area of permitted natural characteristics.

# SECTION 3

## Lumber

### GENERAL/PRODUCT

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



## compliance requirements

3.4.5 Basic Material Rules	
1	Minimum <b>FINISHED THICKNESS</b> of S4S and profiled members:
1 1	Nominal 4/4 or 1" (25 mm) = 11/16" (18 mm)
1 2	Nominal 5/4 or 1-1/4" (32 mm) = 15/16" (24 mm)
1 3	Nominal 6/4 or 1-1/2" (38 mm) = 1-3/16" (30 mm)
1 4	Nominal 8/4 or 2" (51 mm) = 1-1/2" (38 mm)
1 5	Nominal 10/4 or 2-1/2" (64 mm) = 2" (51 mm)
1 6	Nominal 12/4 or 3" (76 mm) = 2-1/2" (64 mm)
1 7	Nominal 16/4 or 4" (102 mm) = 3-1/2" (89 mm)
1 8	
2	Minimum <b>FINISHED WIDTH</b> of S4S and profiled members:
2 1	Nominal 1" (25 mm) = 11/16" (18 mm)
2 2	Nominal 2" (51 mm) = 1-1/2" (38 mm)
2 3	Nominal 3" (76 mm) = 2-1/2" (64 mm)
2 4	Nominal 4" (102 mm) = 3-1/2" (89 mm)
2 5	Nominal 5" (127 mm) = 4-1/4" (108 mm)
2 6	Nominal 6" (152 mm) = 5-1/4" (133 mm)
2 7	Nominal 8" (203 mm) = 7" (178 mm)
2 8	Nominal 10" (254 mm) = 9" (229 mm)
2 9	Nominal 12" (305 mm) = 11" (279 mm)
2 10	Nominal 12+" (305+ mm) = 1" (25 mm) less than nominal size
2 11	
3	When <b>MACHINE SANDED</b> , a reduction of 1/32" (1 mm) off the above thicknesses or widths is permitted.

3.4.6 Hardwood Material Rules															
1	<p><b>APPLYING</b> to only the following species:</p> <table border="0"> <tr> <td><b>ALDER</b></td> <td><b>MAPLE, HARD &amp; SOFT</b></td> </tr> <tr> <td><b>ASH</b></td> <td><b>OAK, RED</b></td> </tr> <tr> <td><b>BIRCH</b></td> <td><b>OAK, WHITE</b></td> </tr> <tr> <td><b>CHERRY, AMERICAN</b></td> <td><b>POPLAR</b></td> </tr> <tr> <td><b>LAUAN</b></td> <td><b>TEAK</b></td> </tr> <tr> <td><b>MAHOGANY, AFRICAN</b></td> <td><b>WALNUT, AMERICAN</b></td> </tr> <tr> <td><b>MAHOGANY, AMERICAN</b></td> <td></td> </tr> </table>	<b>ALDER</b>	<b>MAPLE, HARD &amp; SOFT</b>	<b>ASH</b>	<b>OAK, RED</b>	<b>BIRCH</b>	<b>OAK, WHITE</b>	<b>CHERRY, AMERICAN</b>	<b>POPLAR</b>	<b>LAUAN</b>	<b>TEAK</b>	<b>MAHOGANY, AFRICAN</b>	<b>WALNUT, AMERICAN</b>	<b>MAHOGANY, AMERICAN</b>	
<b>ALDER</b>	<b>MAPLE, HARD &amp; SOFT</b>														
<b>ASH</b>	<b>OAK, RED</b>														
<b>BIRCH</b>	<b>OAK, WHITE</b>														
<b>CHERRY, AMERICAN</b>	<b>POPLAR</b>														
<b>LAUAN</b>	<b>TEAK</b>														
<b>MAHOGANY, AFRICAN</b>	<b>WALNUT, AMERICAN</b>														
<b>MAHOGANY, AMERICAN</b>															
1 1	For <b>SPECIES NOT LISTED</b> , length requirements and size/exposed area of permitted natural characteristics shall be as agreed to between owner/design professional and manufacturer/installer.														
2	<b>GLUING for THICKNESS</b> is permitted when finished dimensions exceed 1-1/16" (27 mm).														
3	<b>GLUING for WIDTH</b> is permitted when:														
3 1	Finished dimensions exceed 6" (152 mm), or:														
3 1 1	4-1/4" (108 mm) at Rift sawn White/Red Oak; quarter sawn White/Red Oak, Maple, and Walnut; and select White/Red Birch, White Ash, Alder and Cherry.														
3 2	Direction of the end grain of boards glued for width shall be alternated, see example:														
3 2 1															
4	Lumber of the <b>SAME SPECIES</b> but of <b>DIFFERENT ORIGINS</b> shall not be mixed on a project (example: American and European Cherry).														
5	If only the generic term <b>MAHOGANY</b> is specified, it shall mean African or American Mahogany.														
6	Specifications calling for <b>PHILIPPINE MAHOGANY</b> shall permit the use of Lauan, Tanguile, and other natural Philippine species of wood.														
<b>Continues next column</b> ▼															

# SECTION 3

## Lumber

### GENERAL/PRODUCT

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



## compliance requirements

3.4.6 Hardwood Material Rules	
▲ From previous column	
7	<b>OAK, RIFT GRAIN</b> , shall permit twenty-five percent (25%) of the exposed surface area of each board to contain medullary ray flake.
8	<b>NATURAL ASH, BIRCH, and MAPLE</b> shall permit both sapwood and heartwood in any board.
9 <b>MAXIMUM LENGTH</b> required for finish thickness up to 1-1/2" (38 mm):	
9 1	Boards required to be longer than those listed may be glued and joined for length or furnished in multiple pieces, and:
9 2 <b>ALDER:</b>	
9 2 1	<2" (51 mm) in finish width = 9'-10" (2997 mm).
9 2 2	2" (51 mm) to <3" (76 mm) in finish width = 8'-10" (2692 mm).
9 2 3	3" (76 mm) to <4" (102 mm) in finish width = 7'-6" (2286 mm).
9 2 4	4" (102 mm) to <5" (127 mm) in finish width = 6'-10" (2083 mm).
9 2 5	5" (127 mm) or wider is not usually available.
9 3 <b>ASH, NATURAL:</b>	
9 3 1	<3" (76 mm) in finish width = 15'-6" (4724 mm).
9 3 2	3" (76 mm) to <4" (102 mm) in finish width = 14'-6" (4420 mm).
9 3 3	4" (102 mm) to <5" (127 mm) in finish width = 13'-6" (4115 mm).
9 3 4	5" (127 mm) to <6" (152 mm) in finish width = 12'-6" (3810 mm).
9 3 5	6" (152 mm) to <7" (203 mm) in finish width = 10'-6" (3200 mm).
9 3 6	7" (203 mm) <9" (229 mm) in finish width = 8'-10" (2692 mm).
9 4 <b>ASH, SELECT BROWN or WHITE:</b>	
9 4 1	<4" (102 mm) in width = 11'-6" (3505 mm).
9 4 2	4" (102 mm) to <6" (152 mm) in finish width = 10'-6" (3200 mm).
9 4 3	6" (152 mm) to <7" (178 mm) in finish width = 8'-6" (2591 mm).
9 4 4	7" (178 mm) to <9" (229 mm) in finish width = 7'-10" (2388 mm).
9 5 <b>BIRCH, NATURAL:</b>	
9 5 1	<4" (102 mm) in width = 10'-6" (3200 mm).
9 5 2	4" (102 mm) to <6" (152 mm) in finish width = 9'-6" (2896 mm).
9 5 3	6" (152 mm) to <7" (178 mm) in finish width = 8'-6" (2591 mm).
9 5 4	7" (178 mm) to <9" (229 mm) in finish width = 7'-6" (2286 mm).
Continues next column ▼	

3.4.6 Hardwood Material Rules	
▲ From previous column	
9 <b>MAXIMUM LENGTH</b> (continued)	
9 6 <b>BIRCH, SELECT RED or WHITE:</b>	
9 6 1	<4" (102 mm) in finish width = 9'-6" (2896 mm).
9 6 2	4" (102 mm) to <6" (152 mm) in finish width = 8'-6" (2591 mm).
9 6 3	6" (152 mm) or finish wider is not usually available.
9 7 <b>CHERRY, AMERICAN:</b>	
9 7 1	<4" (102 mm) in finish width = 9'-10" (2997 mm).
9 7 2	4" (102 mm) to <6" (152 mm) in finish width = 8'-10" (2692 mm).
9 7 3	6" (152 mm) to <7" (178 mm) in finish width = 7'-10" (2388 mm).
9 7 4	7" (178 mm) or finish wider is not usually available.
9 8 <b>LAUAN; MAHOGANY, AMERICAN and AFRICAN:</b>	
9 8 1	<9" (229 mm) in finish width = 15'-10" (4826 mm).
9 9 <b>MAPLE, NATURAL:</b>	
9 9 1	<3" (76 mm) in finish width = 14'-10" (4521 mm).
9 9 2	3" (76 mm) to <4" (102 mm) in finish width = 13'-10" (4216 mm).
9 9 3	4" (102 mm) to <5" (127 mm) in finish width = 12'-10" (3912 mm).
9 9 4	7" (178 mm) to <7" (178 mm) in finish width = 10'-10" (3302 mm).
9 9 5	7" (178 mm) to <9" (229 mm) in finish width = 8'-10" (2692 mm).
9 10 <b>MAPLE, WHITE:</b>	
9 10 1	<2" (51 mm) in finish width = 14'-10" (4521 mm).
9 10 2	2" (51 mm) to <4" (102 mm) in finish width = 11'-10" (3607 mm).
9 10 3	4" (102 mm) to <5" (127 mm) in finish width = 10'-10" (3302 mm).
9 10 4	5" (127 mm) to <7" (178 mm) in finish width = 8'-10" (2692 mm).
9 10 5	7" (178 mm) or wider is not usually available.
9 11 <b>OAK, RED or WHITE</b> (except Rift or Quarter Sawn):	
9 11 1	<2" (51 mm) in finish width = 14'-10" (4521 mm).
9 11 2	2" (51 mm) to <4" (102 mm) in finish width = 13'-10" (4216 mm).
9 11 3	4" (102 mm) to <6" (152 mm) in finish width = 11'-10" (3607 mm).
9 11 4	6" (152 mm) to <7" (178 mm) in finish width = 9'-10" (2997 mm).
9 11 5	7" (178 mm) <9" (229 mm) in finish width = 8'-10" (2692 mm).
Continues next column ▼	

# SECTION 3

## Lumber

### GENERAL/PRODUCT

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally

<b>E</b>	<b>C</b>	<b>P</b>
----------	----------	----------

## compliance requirements

3.4.6		Hardwood Material Rules	
▲ From previous column			
9	MAXIMUM LENGTH (continued)		
9	12	OAK, RED or WHITE, RIFT or QUARTER SAWN:	
9	12	1	<3" (76 mm) in width = 13'-10" (4216 mm).
9	12	2	3" (76 mm) to <4" (102 mm) in finish width = 11'-10" (3607 mm).
9	12	3	4" (102 mm) to <6" (152 mm) in finish width = 9'-10" (2997 mm).
9	12	4	6" (152 mm) to <7" (178 mm) in finish width = 7'-10" (2388 mm).
9	12	5	7" (178 mm) or wider is not usually available.
9	13	POPLAR:	
9	13	1	<6" (152 mm) in finish width = 15'-10" 4826 mm).
9	13	2	6" (152 mm) to <7" (178 mm) in finish width = 13'-10" (4216 mm).
9	13	3	7" (178 mm) to <9" (229 mm) in finish width = 12'-10" (3912 mm).
9	14	TEAK:	
9	14	1	<2" (51 mm) in finish width = 9'-6" (2896 mm).
9	14	2	2" (51 mm) to <4" (102 mm) in finish width = 8'-6" (2591 mm).
9	14	3	4" (102 mm) to <7" (178 mm) in finish width = 7'-6" (2286 mm).
9	14	4	7" (178 mm) or wider is not usually available.
9	15	WALNUT, AMERICAN:	
9	15	1	<2" (51 mm) in finish width = 9'-6" (2896 mm).
9	15	2	2" (51 mm) to <4" (102 mm) in finish width = 8'-6" (2591 mm).
9	15	3	4" (102 mm) to <5" (127 mm) in finish width = 7'-6" (2286 mm).
9	15	4	5" (127 mm) to <6" (152 mm) in finish width = 5'-6" (1676 mm).
9	15	5	6" (152 mm) or wider is not usually available.
10 OPAQUE FINISH allows:			
10	1	NOT MATCHING for COLOR when glued for thickness or width.	
10	2	NATURAL CHARACTERISTICS if they are inconspicuous after two coats of finish.	
10	3	FILLING of checks, splits, or other open characteristics which is the responsibility of the millwork manufacturer.	
Continues next column ▼			

3.4.6		Hardwood Material Rules	
▲ From previous column			
10	OPAQUE FINISH allows (continued)		
10	4	QUANTITY, SPACING and DISTRIBUTION of NATURAL CHARACTERISTIC in any one board's exposed face of:	
10	4	1	NONE in any face smaller than 200 square inches (129,032 square mm), with: <b>E C P</b>
10	4	1	1 ONE permitted for each additional 100 square inches (64,516 square mm). <b>E C P</b>
10	4	1	2 A maximum of FIVE in any board. <b>E C P</b>
10	4	1	3 NO knots, pitch streaks, or pitch pockets within 18" (457 mm) of one another. <b>E C P</b>
10	4	2	NONE in any face smaller than 300 square inches (193,548 square mm), with: <b>E C P</b>
10	4	2	1 ONE permitted for each additional 150 square inches (96,774 square mm). <b>E C P</b>
10	4	2	2 A maximum of FOUR in any board. <b>E C P</b>
10	4	2	3 NO knots, pitch streaks, or pitch pockets within 24" (610 mm) of one another. <b>E C P</b>
10	4	3	NONE in any face smaller than 400 square inches <b>E C P</b>
10	4	3	1 ONE permitted for each additional 200 square inches (129,032 square mm). <b>E C P</b>
10	4	3	2 A maximum of THREE in any board. <b>E C P</b>
10	4	3	3 NO knots, pitch streaks, or pitch pockets within 36" (914 mm) of one another. <b>E C P</b>
10	5	The following NATURAL CHARACTERISTICS:	
10	5	1	BARK POCKET - None.
10	5	2	BIRDSEYE, Sound - Unlimited.
10	5	3	BIRDSEYE, Checked and Filled - Unlimited.
10	5	4	BURL, Sound:
10	5	4	1 < 1" (25 mm) in diameter. <b>E C P</b>
10	5	4	2 < 3/4" (19 mm) in diameter. <b>E C P</b>
Continues next column ▼			

# SECTION 3

## Lumber

### GENERAL/PRODUCT

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally

<b>E</b>	<b>C</b>	<b>P</b>
----------	----------	----------

## compliance requirements

3.4.6		Hardwood Material Rules			
▲ From previous column					
10	OPAQUE FINISH (continued)				
10 5	The following <b>NATURAL CHARACTERISTICS</b> (continued)				
10 5 5	<b>CHECK</b> , Filled:				
10 5 5 1	< 3/32" (2 mm) wide x 9" (229 mm) long.	<b>E</b>	<b>C</b>	<b>P</b>	
10 5 5 2	< 1/16" (2 mm) wide x 6" (152 mm) long.	<b>E</b>	<b>C</b>	<b>P</b>	
10 5 5 3	< 1/32" (1 mm) wide x 4" (102 mm) long.	<b>E</b>	<b>C</b>	<b>P</b>	
10 5 6	<b>HONEYCOMB</b> - None:				
10 5 7	<b>KNOT</b> , Sound and Tight:				
10 5 7 1	< 1" (25 mm) in diameter.	<b>E</b>	<b>C</b>	<b>P</b>	
10 5 7 2	< 5/8" (16 mm) in diameter.	<b>E</b>	<b>C</b>	<b>P</b>	
10 5 7 3	< 3/8" (10 mm) in diameter.	<b>E</b>	<b>C</b>	<b>P</b>	
10 5 8	<b>KNOT</b> , Checked and Filled:				
10 5 8 1	< 3/4" (19 mm) in diameter.	<b>E</b>	<b>C</b>	<b>P</b>	
10 5 8 2	< 1/2" (13 mm) in diameter.	<b>E</b>	<b>C</b>	<b>P</b>	
10 5 8 3	< 1/4" (6 mm) in diameter.	<b>E</b>	<b>C</b>	<b>P</b>	
10 5 9	<b>KNOT</b> , Open and Filled:				
10 5 9 1	< 1/2" (13 mm) in diameter.	<b>E</b>	<b>C</b>	<b>P</b>	
10 5 9 2	< 1/4" (6 mm) in diameter.	<b>E</b>	<b>C</b>	<b>P</b>	
10 5 9 3	< 1/8" (3 mm) in diameter.	<b>E</b>	<b>C</b>	<b>P</b>	
10 5 10	<b>MINERAL STAIN</b> - Unlimited				
10 5 11	<b>PATCH</b> ≤ 1-1/2" (38 mm) wide x 3-1/2" (89 mm) long.				
10 5 12	<b>PITCH POCKET</b> or <b>STREAK</b> , Filled:				
10 5 12 1	< 1/16" (2 mm) wide x 6" (152 mm) long or 1/8" (3 mm) wide x 4" (102 mm) long.	<b>E</b>	<b>C</b>	<b>P</b>	
10 5 12 2	< 1/16" (2 mm) wide x 3" (76 mm) long or 1/8" (3 mm) wide x 2" (51 mm) long.	<b>E</b>	<b>C</b>	<b>P</b>	
10 5 13	<b>SAPWOOD</b> - Unlimited.				
10 5 14	<b>SHAKE</b> , Filled:				
10 5 14 1	≤ 1/4" (6 mm) wide x 3" (76 mm) long.	<b>E</b>	<b>C</b>	<b>P</b>	
10 5 14 2	≤ 1/8" (3 mm) wide x 3" (76 mm) long.	<b>E</b>	<b>C</b>	<b>P</b>	
10 5 14 3	≤ 1/16" (2 mm) wide x 2" (51 mm) long.	<b>E</b>	<b>C</b>	<b>P</b>	
Continues next column ▼					

3.4.6		Hardwood Material Rules				
▲ From previous column						
10	OPAQUE FINISH (continued)					
10 5	The following <b>NATURAL CHARACTERISTICS</b> (continued)					
10 5 15	<b>SPLIT</b> , Filled:					
10 5 15 1	≤ 3/32" (2 mm) wide x 8" (203 mm) long.	<b>E</b>	<b>C</b>	<b>P</b>		
10 5 15 2	≤ 1/16" (2 mm) wide x 6" (152 mm) long.	<b>E</b>	<b>C</b>	<b>P</b>		
10 5 15 3	≤ 1/32" (1 mm) wide x 4" (102 mm) long.	<b>E</b>	<b>C</b>	<b>P</b>		
10 5 16	<b>STICKER BOARD DISCOLORATION</b> - Unlimited.					
10 5 17	<b>WORM HOLE</b> , Filled:					
10 5 17 1	≤ 1/8" (3 mm) in diameter.	<b>E</b>	<b>C</b>	<b>P</b>		
10 5 17 2	≤ 1/16" (2 mm) in diameter.	<b>E</b>	<b>C</b>	<b>P</b>		
10 5 17 3	No worm holes allowed.					
11 TRANSPARENT FINISH allows:						
11 1	<b>MATCHING</b> , when glued for thickness or width or when veneered construction is utilized, shall be:					
11 1 1	Not required.			<b>E</b>	<b>C</b>	<b>P</b>
11 1 2	Compatible for color and grain.			<b>E</b>	<b>C</b>	<b>P</b>
11 1 3	Well matched for color and grain.			<b>E</b>	<b>C</b>	<b>P</b>
11 2	<b>FILLING</b> of checks, splits, or other open characteristics is the responsibility of the finisher.					
11 3	<b>QUANTITY, SPACING</b> and <b>DISTRIBUTION</b> of <b>NATURAL CHARACTERISTIC</b> in any one board's exposed face of:					
11 3 1	<b>FOUR</b> with:			<b>E</b>	<b>C</b>	<b>P</b>
11 3 1 1	NO knots, pitch streaks, or pitch pockets within 24" (610 mm) of one another.			<b>E</b>	<b>C</b>	<b>P</b>
11 3 2	<b>THREE</b> with:			<b>E</b>	<b>C</b>	<b>P</b>
11 3 2 1	NO knots, pitch streaks, or pitch pockets within 36" (914 mm) of one another.			<b>E</b>	<b>C</b>	<b>P</b>
11 3 3	<b>TWO</b> with:			<b>E</b>	<b>C</b>	<b>P</b>
11 3 3 1	NO knots, pitch streaks, or pitch pockets within 48" (1219 mm) of one another.			<b>E</b>	<b>C</b>	<b>P</b>
Continues next column ▼						

# SECTION 3

## Lumber

### GENERAL/PRODUCT

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally

<b>E</b>	<b>C</b>	<b>P</b>
----------	----------	----------

## compliance requirements

3.4.6		Hardwood Material Rules				
▲ From previous column						
11 TRANSPARENT FINISH (continued)						
11 3 QUANTITY, SPACING and DISTRIBUTION of NATURAL CHARACTERISTIC (continued)						
		For: ALDER	MAHOGANY, African			
		ASH, Natural	MAPLE, Hard or Soft, Natural			
		BIRCH, Natural	POPLAR			
		LAUAN	RED & WHITE OAK			
		MAHOGANY, American	TEAK			
11 3 4	1	NONE in any face smaller than 300 square inches (193,548 square mm), with:		E	C	P
11 3 4	1	ONE permitted for each additional 100 square inches (64,516 square mm).		E	C	P
11 3 4	2	NONE in any face smaller than 400 square inches (258,064 square mm), with:		E	C	P
11 3 4	2	ONE permitted for each additional 150 square inches (96,774 square mm).		E	C	P
11 3 4	For: ALDER					
11 3 4	3	NONE in any face smaller than 600 square inches (387,096 square mm), with:		E	C	P
11 3 4	3	ONE permitted for each additional 200 square inches (129,032 square mm).		E	C	P
		For: ASH, Select Brown				
		BIRCH, Select Red & White				
		MAPLE, Select White				
11 3 5	1	NONE in any face smaller than 200 square inches (129,032 square mm), with:		E	C	P
11 3 5	1	ONE permitted for each additional 100 square inches (64,516 square mm).		E	C	P
11 3 5	2	NONE in any face smaller than 350 square inches (225,806 square mm), with:		E	C	P
11 3 5	2	ONE permitted for each additional 150 square inches (96,774 square mm).		E	C	P
11 3 5	3	NONE in any face smaller than 500 square inches (322,580 square mm), with:		E	C	P
11 3 5	3	ONE permitted for each additional 200 square inches (129,032 square mm).		E	C	P
Continues next column ▼						

3.4.6		Hardwood Material Rules				
▲ From previous column						
11 TRANSPARENT FINISH (continued)						
11 3 QUANTITY, SPACING and DISTRIBUTION of NATURAL CHARACTERISTIC (continued)						
		For: CHERRY, American				
		RED & WHITE OAK, Rift/Quarter Sawn				
		WALNUT, American				
11 3 6	1	NONE in any face smaller than 150 square inches (96,744 square mm), with:		E	C	P
11 3 6	1	ONE permitted for each additional 75 square inches (48,387 square mm).		E	C	P
11 3 6	2	NONE in any face smaller than 200 square inches (129,032 square mm), with:		E	C	P
11 3 6	2	ONE permitted for each additional 100 square inches (64,516 square mm).		E	C	P
11 3 6	3	NONE in any face smaller than 300 square inches (193,548 square mm), with:		E	C	P
11 3 6	3	ONE permitted for each additional 150 square inches (96,774 square mm).		E	C	P
11 4	The following NATURAL CHARACTERISTICS:					
11 4 1	BARK POCKET - None.					
11 4 2	BIRDSEYE, Sound - Unlimited.					
11 4 3	BIRDSEYE, Checked:					
11 4 3	1	Unlimited.		E	C	P
11 4 3	2	≤ 10% of face.		E	C	P
11 4 3	3	None.		E	C	P
11 4 4	BURL, Sound:					
11 4 4	1	Unlimited.		E	C	P
11 4 4	2	≤ 1" (25 mm) in diameter.		E	C	P
11 4 4	3	≤ 1/2" (13 mm) in diameter.		E	C	P
11 4 5	CHECK:					
11 4 5	1	≤ 3/32" (2 mm) wide x 8" (203 mm) long.		E	C	P
11 4 5	2	≤ 1/16" (2 mm) wide x 6" (152 mm) long.		E	C	P
11 4 5	3	≤ 1/32" (1 mm) wide x 4" (102 mm) long.		E	C	P
11 4 6	HEARTWOOD, in Select White Ash, Birch, and Maple - None.					
Continues next column ▼						

# SECTION 3

## Lumber

### GENERAL/PRODUCT

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally

<b>E</b>	<b>C</b>	<b>P</b>
----------	----------	----------

## compliance requirements

3.4.6 Hardwood Material Rules			
▲ From previous column			
11 TRANSPARENT FINISH (continued)			
11 4	The following <b>NATURAL CHARACTERISTICS</b> (continued)		
11 4 7	<b>HONEYCOMB</b> - None.		
11 4 8	<b>8 KNOT</b> , Sound and Tight:		
11 4 8 1	≤ 3/8" (10 mm) in diameter.	<b>E</b>	<b>C</b> <b>P</b>
11 4 8 2	≤ 1/4" (6 mm) in diameter.	<b>E</b>	<b>C</b> <b>P</b>
11 4 8 3	≤ 1/8" (3 mm) in diameter.	<b>E</b>	<b>C</b> <b>P</b>
11 4 9	<b>9 KNOT</b> , Checked:		
11 4 9 1	≤ 1/2" (13 mm) in diameter.	<b>E</b>	<b>C</b> <b>P</b>
11 4 9 2	≤ 1/4" (6 mm) in diameter.	<b>E</b>	<b>C</b> <b>P</b>
11 4 9 3	None.	<b>E</b>	<b>C</b> <b>P</b>
11 4 10	<b>10 KNOT</b> , Open - None.		
11 4 11	<b>11 MINERAL STAIN:</b>		
11 4 11 1	Unlimited.	<b>E</b>	<b>C</b> <b>P</b>
11 4 11 2	≤ 10% of face.	<b>E</b>	<b>C</b> <b>P</b>
11 4 11 3	None.	<b>E</b>	<b>C</b> <b>P</b>
11 4 12	<b>12 PATCH:</b>		
11 4 12 1	≤ 1-1/2" (38 mm) wide x 3-1/2" (89 mm) long, and inconspicuous from 60°.	<b>E</b>	<b>C</b> <b>P</b>
11 4 12 2	≤ 1-1/2" (38 mm) wide x 3-1/2" (89 mm) long, and inconspicuous from 36°.	<b>E</b>	<b>C</b> <b>P</b>
11 4 12 3	None.	<b>E</b>	<b>C</b> <b>P</b>
11 4 13	<b>13 PITCH POCKET or STREAK:</b>		
11 4 13 1	≤ 1/16" (2 mm) wide x 6" (152 mm) long or 1/8" (3 mm) wide x 4" (102 mm) long.	<b>E</b>	<b>C</b> <b>P</b>
11 4 13 2	None.	<b>E</b>	<b>C</b> <b>P</b>
11 4 14	<b>14 SAPWOOD</b> , in unselected species - Unlimited.		
11 4 15	<b>15 SAPWOOD</b> , in select Red Birch and Brown Ash - None.		
11 4 16	<b>16 SAPWOOD</b> in Cherry, and Walnut:		
11 4 16 1	Unlimited.	<b>E</b>	<b>C</b> <b>P</b>
11 4 16 2	≤ 10% of face.	<b>E</b>	<b>C</b> <b>P</b>
11 4 16 3	≤ 5% of face.	<b>E</b>	<b>C</b> <b>P</b>
Continues next column ▼			

3.4.6 Hardwood Material Rules			
▲ From previous column			
11 TRANSPARENT FINISH (continued)			
11 4 17	<b>17 SHAKE:</b>		
11 4 17 1	≤ 1/8" (3 mm) wide x 3" (76 mm) long.	<b>E</b>	<b>C</b> <b>P</b>
11 4 17 2	None.	<b>E</b>	<b>C</b> <b>P</b>
11 4 18	<b>18 SPLIT:</b>		
11 4 18 1	≤ 3/32" (2 mm) wide x 8" (203 mm) long.	<b>E</b>	<b>C</b> <b>P</b>
11 4 18 2	≤ 1/16" (2 mm) wide x 6" (152 mm) long.	<b>E</b>	<b>C</b> <b>P</b>
11 4 18 3	≤ 1/32" (1 mm) wide x 4" (102 mm) long.	<b>E</b>	<b>C</b> <b>P</b>
11 4 19	<b>19 STICKER BOARD DISCOLORATION:</b>		
11 4 19 1	≤ 10% of face.	<b>E</b>	<b>C</b> <b>P</b>
11 4 19 2	None.	<b>E</b>	<b>C</b> <b>P</b>
11 4 20	<b>20 WORM HOLE</b> , Filled:		
11 4 20 1	≤ 1/8" (3 mm) in diameter.	<b>E</b>	<b>C</b> <b>P</b>
11 4 20 2	≤ 1/16" (2 mm) in diameter.	<b>E</b>	<b>C</b> <b>P</b>
11 4 20 3	No worm holes allowed.	<b>E</b>	<b>C</b> <b>P</b>



# SECTION 3


## Lumber

### GENERAL/PRODUCT

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



## compliance requirements

3.4.7 Softwood Material Rules	
1	<b>APPLYING</b> only to the following species: <b>CEDAR, WESTERN RED PINE, SUGAR PINE, PONDEROSA</b> <b>HEMLOCK FIR, DOUGLAS REDWOOD</b>
1 1	For <b>SPECIES NOT LISTED</b> , length requirements and size/exposed area of permitted natural characteristics shall be as agreed to between owner/design professional and manufacturer/installer.
2	<b>GLUING</b> for <b>WIDTH</b> is permitted when finished dimensions exceed 7" (178 mm).
2 1	Direction of the end grain of boards glued for width shall be alternated.
2 2	
3	<b>GLUING</b> for <b>THICKNESS</b> is permitted when finished dimensions exceed 1-1/2" (38 mm).
4	<b>VERTICAL GRAIN</b> shall have a minimum average of 5 growth rings per inch at exposed surfaces.
5	<b>MAXIMUM LENGTH</b> required for thickness up to 1-1/2" (38.1 mm):
5 1	<b>DOUGLAS FIR, HEMLOCK, &amp; WESTERN RED CEDAR:</b>
5 1 1	4" to 8" (102 mm to 203 mm) in width = 15'-8" (4,775 mm).
5 1 2	10" (254 mm) in width = 13'-8" (4,166 mm).
5 1 3	12" (305 mm) is not usually available.
5 2	<b>PONDEROSA or SUGAR PINE:</b>
5 2 1	4" to 12" (102 mm to 305 mm) in width = 15'-8" (4,775 mm).
5 3	<b>REDWOOD:</b>
5 3 1	4" to 12" (102 mm to 305 mm) in width = 19'-8" (5,994 mm).
5 4	<b>BOARDS</b> required to be <b>WIDER</b> than those listed above may be glued for width.
5 5	<b>BOARDS</b> required to be <b>LONGER</b> than those listed as available above may be glued and joined or furnished in two pieces for length at the option of the manufacturer.
Continues next column ▼	

3.4.7 Softwood Material Rules				
▲ From previous column				
6	<b>OPAQUE FINISH</b> allows:			
6 1	<b>NATURAL CHARACTERISTICS</b> only if they are inconspicuous after two coats of finish are applied.			
6 2	<b>FILLING</b> of checks, splits, or other open characteristics which is the responsibility of the millwork manufacturer.			
6 3	<b>QUANTITY, SPACING and DISTRIBUTION</b> of <b>NATURAL CHARACTERISTIC</b> in any one board's exposed face of:			
6 3 1	<b>NONE</b> in any face smaller than 200 square inches (129,032 square mm), with:	E	C	P
6 3 1 1	<b>ONE</b> permitted for each additional 100 square inches (64,516 square mm).	E	C	P
6 3 1 2	<b>FIVE</b> in any board.	E	C	P
6 3 1 3	<b>NO</b> knots, pitch streaks, or pitch pockets within 18" (457 mm) of one another.	E	C	P
6 3 2	<b>NONE</b> in any face smaller than 400 square inches (258,064 square mm), with:	E	C	P
6 3 2 1	<b>ONE</b> permitted for each additional 150 square inches (96,774 square mm).	E	C	P
6 3 2 2	<b>FOUR</b> in any board.	E	C	P
6 3 2 3	<b>NO</b> knots, pitch streaks, or pitch pockets within 24" (610 mm) of one another.	E	C	P
6 3 3	<b>NONE</b> in any face smaller than 600 square inches (387,096 square mm), with:	E	C	P
6 3 3 1	<b>ONE</b> permitted for each additional 200 square inches (129,032 square mm).	E	C	P
6 3 3 2	<b>THREE</b> in any board.	E	C	P
6 3 3 3	<b>NO</b> knots, pitch streaks, or pitch pockets within 36" (914 mm) of one another.	E	C	P
6 4	The following <b>NATURAL CHARACTERISTIC:</b>			
6 4 1	<b>BARK POCKET</b> - None.			
6 4 2	<b>BIRDSEYE</b> , Sound - Unlimited.			
6 4 3	<b>BIRDSEYE</b> , Checked and Filled - Unlimited.			
6 4 4	<b>BURL</b> , Sound:			
6 4 4 1	≤ 1" (25 mm) in diameter.	E	C	P
6 4 4 2	≤ 3/4" (19 mm) in diameter.	E	C	P
Continues next column ▼				

# SECTION 3

## Lumber

### GENERAL/PRODUCT

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally

<b>E</b>	<b>C</b>	<b>P</b>
----------	----------	----------

## compliance requirements

3.4.7		Softwood Material Rules		
▲ From previous column				
6	OPAQUE FINISH (continued)			
6 4	The following <b>NATURAL CHARACTERISTICS</b> (continued)			
6 4 5	<b>CHECK</b> , Filled:			
6 4 5 1	≤ 3/32" (2 mm) wide x 9" (229 mm) long.	<b>E</b>	<b>C</b>	<b>P</b>
6 4 5 2	≤ 1/16" (2 mm) wide x 6" (152 mm) long.	<b>E</b>	<b>C</b>	<b>P</b>
6 4 5 3	≤ 1/32" (1 mm) wide x 4" (102 mm) long.	<b>E</b>	<b>C</b>	<b>P</b>
6 4 6	<b>HONEYCOMB</b> - None.			
6 4 7	<b>KNOT</b> , Sound and Tight:			
6 4 7 1	≤ 1" (25 mm) in diameter.	<b>E</b>	<b>C</b>	<b>P</b>
6 4 7 2	≤ 5/8" (16 mm) in diameter.	<b>E</b>	<b>C</b>	<b>P</b>
6 4 7 3	≤ 3/8" (10 mm) in diameter.	<b>E</b>	<b>C</b>	<b>P</b>
6 4 8	<b>KNOT</b> , Checked and Filled:			
6 4 8 1	≤ 3/4" (19 mm) in diameter.	<b>E</b>	<b>C</b>	<b>P</b>
6 4 8 2	≤ 1/2" (13 mm) in diameter.	<b>E</b>	<b>C</b>	<b>P</b>
6 4 8 3	≤ 1/4" (6 mm) in diameter.	<b>E</b>	<b>C</b>	<b>P</b>
6 4 9	<b>KNOT</b> , Open and Filled:			
6 4 9 1	< 1/2" (13 mm) in diameter.	<b>E</b>	<b>C</b>	<b>P</b>
6 4 9 2	< 1/4" (6 mm) in diameter.	<b>E</b>	<b>C</b>	<b>P</b>
6 4 9 3	< 1/8" (3 mm) in diameter.	<b>E</b>	<b>C</b>	<b>P</b>
6 4 10	<b>MINERAL STAIN</b> - Unlimited.			
6 4 11	<b>PATCH</b> ≤ 1-1/2" (38 mm) wide x 3-1/2" (89 mm) long.			
6 4 12	<b>PITCH POCKET</b> or <b>STREAK</b> :			
6 4 12 1	< 1/16" (2 mm) wide x 6" (152 mm) long or 1/8" (3 mm) wide x 4" (102 mm) long.	<b>E</b>	<b>C</b>	<b>P</b>
6 4 12 2	< 1/16" (2 mm) wide x 3" (76 mm) long or 1/8" (3 mm) wide x 2" (51 mm) long.	<b>E</b>	<b>C</b>	<b>P</b>
6 4 13	<b>SAPWOOD</b> - Unlimited.			
6 4 14	<b>SHAKE</b> , Filled:			
6 4 14 1	≤ 1/4" (6 mm) wide x 3" (76 mm) long.	<b>E</b>	<b>C</b>	<b>P</b>
6 4 14 2	≤ 1/8" (3 mm) wide x 3" (76 mm) long.	<b>E</b>	<b>C</b>	<b>P</b>
6 4 14 3	≤ 1/16" (2 mm) wide x 2" (51 mm) long.	<b>E</b>	<b>C</b>	<b>P</b>
6 4 15	<b>SPLIT</b> , Filled:			
6 4 15 1	≤ 3/32" (2 mm) wide x 8" (203 mm) long.	<b>E</b>	<b>C</b>	<b>P</b>
6 4 15 2	≤ 1/16" (2 mm) wide x 6" (152 mm) long.	<b>E</b>	<b>C</b>	<b>P</b>
6 4 15 3	≤ 1/32" (1 mm) wide x 4" (102 mm) long.	<b>E</b>	<b>C</b>	<b>P</b>
6 4 16	<b>STICKER BOARD DISCOLORATION</b> - Unlimited.			
Continues next column ▼				

3.4.7		Softwood Material Rules		
▲ From previous column				
6	OPAQUE FINISH (continued)			
6 4 17	<b>WORM HOLES</b> , Filled:			
6 4 17 1	≤ 1/8" (3 mm) in diameter.	<b>E</b>	<b>C</b>	<b>P</b>
6 4 17 2	≤ 1/16" (2 mm) in diameter.	<b>E</b>	<b>C</b>	<b>P</b>
6 4 17 3	No worm holes allowed.			
7 TRANSPARENT FINISH allows:				
7 1	<b>MATCHING</b> , when glued for thickness or width or when veneered construction is utilized, shall be:			
7 1 1	Not required.			
7 1 2	Compatible for color and grain.			
7 1 3	Well matched for color and grain.			
7 2	<b>FILLING</b> of checks, splits, or other open characteristics which is the responsibility of the finisher.			
7 3	<b>QUANTITY, SPACING</b> and <b>DISTRIBUTION</b> of <b>NATURAL CHARACTERISTIC</b> in any one board's exposed face of:			
7 3 1	<b>NONE</b> in any face smaller than 400 sq. in. (258,064 sq. mm), with:			
7 3 1 1	<b>ONE</b> permitted for each additional 200 sq. in. (129,032 sq. mm).			
7 3 2	<b>FOUR</b> , with:			
7 3 2 1	<b>NO</b> knots, pitch streaks, or pitch pockets within 24" (610 mm) of one another.			
7 3 3	<b>NONE</b> in any face smaller than 600 sq. in. (387,096 sq. mm), with:			
7 3 3 1	<b>ONE</b> permitted for each additional 300 sq. in. (193,548 sq. mm).			
7 3 4	<b>THREE</b> , with:			
7 3 4 1	<b>NO</b> knots, pitch streaks, or pitch pockets within 36" (914 mm) of one another.			
7 3 5	<b>NONE</b> in any face smaller than 900 sq. in. (580,644 sq. mm), with:			
7 3 5 1	<b>ONE</b> permitted for each additional 400 sq. in. (258,064 sq. mm).			
7 3 6	<b>TWO</b> , with:			
7 3 6 1	<b>NO</b> knots, pitch streaks, or pitch pockets within 48" (1219 mm) of one another.			
Continues next column ▼				

# SECTION 3

## Lumber

### GENERAL/PRODUCT

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally

<b>E</b>	<b>C</b>	<b>P</b>
----------	----------	----------

## compliance requirements

3.4.7		Softwood Material Rules		
▲ From previous column				
7	4	TRANSPARENT FINISH allows (continued)		
7	4	The following <b>NATURAL CHARACTERISTICS</b> :		
7	4	1	<b>BARK POCKET</b> - None.	
7	4	2	<b>BIRDSEYE</b> , Sound - Unlimited.	
7	4	3	<b>BIRDSEYE</b> , Checked:	
7	4	3	1	Unlimited. <b>E C P</b>
7	4	3	2	≤ 10% of face. <b>E C P</b>
7	4	3	3	None. <b>E C P</b>
7	4	4	<b>BURL</b> , Sound:	
7	4	4	1	≤ 3/4" (19 mm) in diameter. <b>E C P</b>
7	4	4	2	≤ 5/8" (16 mm) in diameter. <b>E C P</b>
7	4	4	3	≤ 1/2" (13 mm) in diameter. <b>E C P</b>
7	4	5	<b>CHECK</b> :	
7	4	5	1	≤ 3/32" (2 mm) wide x 8" (203 mm) long. <b>E C P</b>
7	4	5	2	≤ 1/16" (2 mm) wide x 6" (152 mm) long. <b>E C P</b>
7	4	5	3	≤ 1/32" (1 mm) wide x 4" (102 mm) long. <b>E C P</b>
7	4	6	<b>HONEYCOMB</b> - None.	
7	4	7	<b>KNOT</b> , Sound and Tight:	
7	4	7	1	≤ 3/4" (19 mm) in diameter. <b>E C P</b>
7	4	7	2	≤ 1/2" (13 mm) in diameter. <b>E C P</b>
7	4	7	3	≤ 1/4" (6 mm) in diameter. <b>E C P</b>
7	4	8	<b>KNOT</b> , Checked:	
7	4	8	1	≤ 1/2" (13 mm) in diameter. <b>E C P</b>
7	4	8	2	≤ 1/4" (6 mm) in diameter. <b>E C P</b>
7	4	8	3	None. <b>E C P</b>
7	4	9	<b>KNOT</b> , Open - None.	
7	4	10	<b>MINERAL STAIN</b> :	
7	4	10	1	Unlimited. <b>E C P</b>
7	4	10	2	≤ 10% of face. <b>E C P</b>
7	4	10	3	None. <b>E C P</b>
Continues next column ▼				

3.4.7		Softwood Material Rules		
▲ From previous column				
7	4	TRANSPARENT FINISH (continued)		
7	4	The following <b>NATURAL CHARACTERISTICS</b> (continued)		
7	4	11	<b>PATCH</b> :	
7	4	11	1	≤ 1-1/2" (38 mm) wide x 3-1/2" (89 mm) long, and inconspicuous from 60°. <b>E C P</b>
7	4	11	2	≤ 1-1/2" (38 mm) wide x 3-1/2" (89 mm) long, and inconspicuous from 36°. <b>E C P</b>
7	4	11	3	None. <b>E C P</b>
7	4	12	<b>PITCH POCKET</b> or <b>STREAK</b> :	
7	4	12	1	≤ 1/16" (2 mm) wide x 6" (152 mm) long or 1/8" (3 mm) wide x 4" (102 mm) long. <b>E C P</b>
7	4	12	2	≤ 1/16" (2 mm) wide x 3" (76 mm) long or 1/8" (3 mm) wide x 2" (51 mm) long. <b>E C P</b>
7	4	12	3	None. <b>E C P</b>
7	4	13	<b>SAPWOOD</b> , in unselected species - Unlimited.	
7	4	14	<b>SAPWOOD</b> , in All Heart Redwood - None.	
7	4	The following <b>NATURAL CHARACTERISTICS</b> (continued)		
7	4	15	<b>SHAKE</b> :	
7	4	15	1	≤ 1/8" (3 mm) wide x 3" (76 mm) long. <b>E C P</b>
7	4	15	2	≤ 1/16" (2 mm) wide x 2" (51 mm) long. <b>E C P</b>
7	4	15	3	None. <b>E C P</b>
7	4	16	<b>SPLIT</b> :	
7	4	16	1	≤ 1/16" (2 mm) wide x 6" (152 mm) long. <b>E C P</b>
7	4	16	2	≤ 1/32" (1 mm) wide x 4" (102 mm) long. <b>E C P</b>
7	4	16	3	None. <b>E C P</b>
7	4	17	<b>STICKER BOARD DISCOLORATION</b> :	
7	4	17	1	≤ 10% of the face. <b>E C P</b>
7	4	17	2	None. <b>E C P</b>
7	4	17	3	None. <b>E C P</b>
7	4	18	<b>WORM HOLES</b> :	
7	4	18	1	≤ 1/8" (3 mm) in diameter. <b>E C P</b>
7	4	18	2	≤ 1/16" (2 mm) in diameter. <b>E C P</b>
7	4	18	3	None. <b>E C P</b>

**Applicable TESTS, may be found in Sections 6 - 11; however, these tests are only applicable to the exposed and semi-exposed portions of installed millwork products.**



# North American Architectural Woodwork Standards - 3.1

## **S E C T I O N - 0 4**

# SHEET PRODUCTS

<b>Resources . . . . .</b>	<b><a href="#">82</a></b>
<b>Introduction . . . . .</b>	<b><a href="#">84</a></b>
<b>Advisories . . . . .</b>	<b><a href="#">84</a></b>
<b>Recommendations . . . . .</b>	<b><a href="#">84</a></b>
<b>Specification Considerations . . . . .</b>	<b><a href="#">84</a></b>
<b>Design Resources . . . . .</b>	<b><a href="#">103</a></b>
<b>Compliance Requirements . . . . .</b>	<b><a href="#">104</a></b>
<b>Scope &amp; Default Stipulation . . . . .</b>	<b><a href="#">105</a></b>
<b>Basic Rules . . . . .</b>	<b><a href="#">105</a></b>
<b>Hardwood Rules . . . . .</b>	<b><a href="#">107</a></b>
<b>Softwood Rules - . . . . .</b>	<b><a href="#">116</a></b>
<b>HPDL Rules . . . . .</b>	<b><a href="#">119</a></b>
<b>Miscellaneous Rules . . . . .</b>	<b><a href="#">120</a></b>

### Within CANADA

#### SUPPORT

- **GUIDE SPECIFICATIONS** – Available for download in interactive digital format, including specification wording for Quality Assurance Program (GIS) at: <http://awmac.com/guide-specifications>
- **CONSULTATION** – Contact any of the local chapters for more information on the NAAWS or any other Architectural Woodwork Questions you may have. See below for contact information.
- **SPECIFICATION REVIEW** – Contact any of the local chapters if you would like your specifications reviewed for compliance to the NAAWS.
- **MANUFACTURER STANDARDS QUESTIONNAIRE (MSQ)** – AWMAC Manufacturer members have the opportunity to have at least one member of their staff study and write the MSQ. The MSQ is a questionnaire on the NAAWS and policy and procedures of the GIS program. A list of Manufacturer members that have passed the MSQ is available at: <http://awmac.com/members>
- **SEMINARS AND PRESENTATIONS** – Contact your local chapter to arrange an informative presentation on any Architectural Woodwork topic. Some topic options – GIS, NAAWS, How to Specify Quality Architectural Woodwork...
- **TRADE SHOWS** – Contact your local chapter to arrange for AWMAC to have a booth or do a presentation on Architectural Woodwork.
- **CONFERENCE** – AWMAC has an annual conference held at unique venues across Canada. The conferences provide an opportunity to learn more about Architectural Woodwork and network with Suppliers and Manufacturers from across Canada. More information is available at: <http://awmac.com/>
- **EDUCATION PARTNERS** – Contact the local chapters to find out more information about support for local Colleges and Universities offering woodworking related courses and programs.

#### QUALITY ASSURANCE

- **GUARANTEE AND INSPECTION SERVICE (GIS)** – The GIS is a national program designed to ensure that project owners get value and quality for their investment by:
  - Supporting architects and design professionals to achieve project plans and specifications; and
  - Helping contractors avoid problems such as cost overruns, delays and loss of reputation.More information is available at: <http://awmac.com/gis>

- **INSPECTION SERVICE** – A GIS Certified Inspector will inspect specific areas of concern on a project for compliance to the NAAWS and provide a written report. Contact your local chapter for more information.
- **EXPERT OPINION** – An expert will be appointed to inspect specific areas of concern on a project and provide a written report. Contact your local chapter for more information.

#### AWMAC CHAPTERS

- AWMAC British Columbia Chapter, Vancouver BC  
<http://bc.awmac.com>
- AWMAC Northern Alberta Chapter, Edmonton Alberta  
<http://nab.awmac.com>
- AWMAC Southern Alberta Chapter, Calgary Alberta  
<http://sab.awmac.com>
- AWMAC Saskatchewan Chapter, Saskatoon Saskatchewan  
<http://sk.awmac.com>
- AWMAC Manitoba Chapter, Winnipeg Manitoba  
<http://mb.awmac.com>
- AWMAC Ontario Chapter, Toronto Ontario  
<http://on.awmac.com>
- AWMAC Quebec Chapter, Montreal Quebec  
<http://qc.awmac.com>
- AWMAC Atlantic Chapter, Halifax Nova Scotia  
<http://atl.awmac.com>

### Within UNITED STATES

#### SUPPORT

- **GUIDE SPECIFICATIONS** - Available in interactive digital format including quality control options at: <http://woodworkinstitute.com/architectural-resources/specification-language/>
- **AIA SEMINARS** - The Woodwork Institute is a Registered Provider of the American Institute of Architects (AIA), and its Continuing Education System (CES) program, check out our offerings at: <http://woodworkinstitute.com/architectural-resources/aia-seminars/> 
- **CONSULTATION** - Contact one of our Directors of Architectural Services (DAS) at: <http://woodworkinstitute.com/about-us-2/about-us/>
- **ACCREDITED FABRICATORS AND INSTALLERS** - Our AMC's (Accredited Millwork Company) represents the best fabricators and installers in our industry, check them out at: <http://woodworkinstitute.com/membership-listing-2/> 
- **CERTIFIED INDUSTRY PROFESSIONALS** - Our CMP's (Certified Millwork Professionals) represent the knowledge base of our industry, check them out at: <http://woodworkinstitute.com/membership-listing-2/> 
- **MILLWORK INDUSTRY PARTNERS** - Our MIP's (Millwork Industry Partners) represent the best of our industries material suppliers, check them out at: <http://woodworkinstitute.com/membership-listing-2/> 
- **ACKNOWLEDGED PRODUCTS LISTING** - If it's listed here, you are assured it meets NAAWS minimum requirements, find the listing at: <http://woodworkinstitute.com/acknowledged-product-listing/> 
- **CABINET DESIGN SERIES (CDS)** - Eliminate the need to include casework elevations in your architectural drawings, check out the CDS system in NAAWS "Design Resources" and access the cad files at: <http://woodworkinstitute.com/architectural-resources/cabinet-design-series/>

#### QUALITY ASSURANCE

- **BIDDER QUALIFICATION** - A discipline of bidder pre-qualification wherein your specifications protect you and your customer from the unknown: To be eligible to bid or negotiate this job, the subcontractor must be a Woodwork Institute Accredited Millwork Company (AMC) in good standing.   
<http://woodworkinstitute.com/architectural-resources/quality-assurance>
- **CERTIFIED COMPLIANCE PROGRAM (CCP)** - A discipline of quality control used in conjunction with NAAWS providing an unbiased means of ensuring conformance to a project's plans and specifications. CCP, together with the use of the desired Grade(s) in the specifications, informs all parties of the design professional's expectations, without bidder discrimination.   
<http://woodworkinstitute.com/services/certified-compliance-program>
- **MONITORED COMPLIANCE PROGRAM (MCP)** - A discipline of quality affirmation used in conjunction with the NAAWS which provides ongoing reviews/inspections of a project from its beginning through completion, ensuring strict conformance to the design intent throughout the millwork fabrication and installation process.   
<http://woodworkinstitute.com/services/monitored-compliance-program/>
- **CERTIFIED SEISMIC INSTALLATION PROGRAM (CSIP)** - A standalone seismic assurance option which can be specified in conjunction with or without CCP or MCP, offering design professionals and project owners specific use of WI's seismic casework pre-approvals from California's Office of Statewide Health Planning and Development (OSHPD) without additional engineering costs and/or requirements, assuring proper backing has been installed in the walls when and where required.   
<http://woodworkinstitute.com/services/certified-seismic-installation-program/>

# SECTION 4

## Sheet Products

## introductory information

### INTRODUCTION

Section 4 is the second “material” section. This section includes a wide range of sheet goods, Hardwood and Softwood Veneers, High Pressure Decorative Laminate, Overlays, Backers, Solid Surface, Solid Phenolic, Epoxy Resin, and Natural and Engineered Stone. This section identifies common panel cores and panel surfaces referred to in subsequent product sections. It contains material rules specific to all of the sheet products the section covers.

Quality assurance can be achieved by adherence to these standards and will provide the owner a quality product at competitive pricing. Working with a WI Certified Millwork Professional (CMP) and the WI Accredited Millwork Company (AMC) they represent to provide your woodwork will help ensure the understanding and performance of the quality level required. Illustrations in this Section are not intended to be all inclusive, other engineered solutions may be acceptable. In the absence of specifications; methods of fabrication are the manufacturer’s choice. The design professional, by specifying compliance to these standards increases the probability of receiving the product quality expected.

### ADVISORIES

**FR ULEF CORE USE** - Due to adverse reaction of some veneers laminated to fire rated (FR), ultra low emitting formaldehyde (ULEF or NAUF), medium density fiberboard (mdf) causing discoloration of the wood veneer even months after installation, major core manufacturers have issued disclaimers in the use of FR cores. They strongly suggest that use of FR ULEF mdf and particleboard cores should be done after testing compatibility of adhesives, wood veneer and cores.



Any resulting discoloration with the use of these cores may be exempt in their warranties. Use of FR ULEF cores should only be considered after consultation with the board supplier.

**HPDL or LPDL RESURFACING** - Some laminate manufacturers are marketing laminate with a peel and stick adhesive especially formulated for resurfacing existing HPDL or LPDL surfaces. Except for these speciality products:

- The application of any thickness of HPDL over the top of existing HPDL is not permitted. Experience shows that the adhesion of the new laminate to the existing surface is very low, often resulting in delamination and failure of the glue line.
- Likewise, the application of HPDL over existing thermoset decorative overlay (melamine) is strongly discouraged. Some fabricators report success by aggressively sanding the melamine surface, followed by applying sufficient contact adhesive and adequate pressure. Delamination is a defect. The risk of delamination is high. Specify or use this procedure with care.

### RECOMMENDATIONS



- **VENEER CORE PANELS** should not be used for cabinet doors because they are likely to warp, and:
  - Rotary cut softwood sheets with clear faces, free of patches, are not typically available.
  - Formaldehyde emission regulations should be carefully researched before shipping product into an unfamiliar area.
- **CHECKING** or **WARPAGE** of wood veneered sheets can be avoided by proper environmental maintenance, such as being:

- Protected from extremes in relative humidity and temperature.
- Finished on both surfaces to retard moisture movement in and out of the panel.
- Placed in locations that avoid directly facing air vents and/or radiant heat sources.

### SPECIFICATION CONSIDERATIONS



- **UNIFORM COLOR**, certain finishing techniques might be required to achieve uniformity (see Section 5).
- **CHARACTERISTICS**, such as sapwood, heartwood, ribbon stripe, quarter sawn, rift sawn, or vertical grain.
  - Natural, Sapwood and Heartwood are color and cut subsets of Ash, Beech, Birch, Maple, and Poplar. (see HPVA table herein).
  - Natural as a type of wood species selection, allows an unlimited amount of heartwood and/or sapwood within a face.
  - Sapwood is all sapwood and is generally referred to for example as Select White for Maple and Birch.
  - Heartwood is all heartwood and is generally referred to for example as Select Red for Birch.
- **SPECIAL FIGURE** characteristics.
- **TYPE I WATERPROOF BOND** for limited non climate controlled interior or exterior use (compliant with 2 Cycle Boil and Shear Tests).
- **FLAME SPREAD** and/or smoke development ratings.

# SECTION 4

## Sheet Products

## introductory information

### SPECIFICATION CONSIDERATIONS (continued)



- **SPECIALITY SHEET PRODUCTS**, such as plywood with textured faces, pre-finished plywood, overlaid plywood, composition sheets, flame spread rated plywood, moisture resistant plywood, lead lined sheets, projectile resistant armor (bullet resistant), reconstituted veneers, bamboo sheets, acrylic sheets, or PVC sheets which are the products of an individual manufacturer, are covered by their manufacturer's specification - not by these standards.

### PLYWOOD

The term "plywood" is defined as a panel manufactured of three or more layers (plies) of wood or wood products (veneers or overlays and/or core materials), generally laminated into a single sheet (panel).

### TYPES OF PANELS

There are a wide range of panel materials available for the fabrication of architectural woodwork.

Property and performance characteristics are influenced by the panel grade, panel thickness, and materials used for the core:

- Surface uniformity has a direct relationship to the performance of the face veneers.
- Dimensional stability relates to the effect of exposure to wide swings in temperature and relative humidity.
- Screw holding and bending strength are influenced by and should be considered in design engineering.

Architectural panels with applied decorative surface materials are made up of a variety of core types including: Particleboard, Medium Density Fiberboard (MDF), Veneer, Hardboard, Lumber, Combination and Agrifiber.

### PRIMARY CORE MATERIALS

- **Industrial Grade Particleboard** - Sometimes referenced as composite core, is made of wood particles of various sizes that are bonded together with a synthetic resin or binder under heat and pressure.

Medium Density Industrial Particleboard is used in the broadest applications of architectural woodwork. It is especially well suited as a core for veneers and decorative laminates.

When used as panels without surface plies, the product is referred to as particleboard. When used as an inner core with outer wood veneers, the panel is referred to as particle core plywood.

Industrial particleboard is commercially classified by "density," which is measured by the weight per cubic foot of the panel product.

- **Medium Density (M series)** = generally between 40-50 pounds per ft<sup>3</sup> (640-800 kg per m<sup>3</sup>).
- **High Density (H series)** = generally above 50 pounds per ft<sup>3</sup> (800 kg per m<sup>3</sup>).




Figure: 4-001

- **Moisture resistant particleboard** - Some Medium Density Industrial Particleboard is bonded with resins more resistant to swelling when exposed to moisture. The most common grades are ANSI A-208.1 (latest edition) Type M-2-Exterior Glue and M-3-Exterior Glue.

- **Fire Retardant Particleboard** - Some Medium Density Industrial Particleboard has been treated during manufacture to carry a UL stamp for Class A flame spread rating (Flame spread 20, Smoke developed 450). Fire retardant Medium Density Fiberboard is also available.
- **Medium Density Fiberboard (MDF)** - Sometimes referenced as composite core, is made of wood particles reduced to fibers in a moderate pressure steam vessel, combined with a resin, and bonded together under heat and pressure.
- Due to the finer texture of the fibers used in manufacturing Medium Density Fiberboard (MDF) it is smoother than Medium Density Particleboard. The uniform texture and density of the fibers create a homogenous panel that is very useful as a core for paint, thin overlay materials, veneers and decorative laminates. MDF is among the most stable of the mat formed panel products. When used as an inner core with outer wood veneers, the panel is referred to as MDF core plywood.




Figure: 4-002

- **Moisture Resistant Mdf** - Can be manufactured to meet the ANSI A-208.2 (latest edition) reduced thickness swell criteria.
- **Veneer** - Is separated into two groups according to materials and manufacturing:
  - **Hardwood Veneer** - Panels manufactured of hardwood veneers.
  - **Softwood Veneer** - Panels manufactured of softwood veneers.

# SECTION 4

## Sheet Products

## introductory information

### PRIMARY CORE MATERIALS (continued)

Hardwood or Softwood Veneers used as a core is not recommended in many areas of these standards due to poor stability, but do have many other structural characteristics. It is recommended that veneer core panels be used only when they can be housed or in areas where warping is not a significant issue.




Figure: 4-003

What many think of as traditional “plywood”, is a panel core made up of an odd number of plies, 3 or more (except when the center is constructed of two unidirectional plies), alternating layers of veneers, all less than 1/4” (6.4 mm) thick, pressed and glued into a single sheet. The two outside veneer layers are the Face and Back. The interior veneer bands are cross bands and parallel bands. The latter are sometimes referenced as centers. Veneer bands are layered at right angles to the adjoining veneer layer.

- **Hardboard** - Is defined as inter felted fibers consolidated under heat and pressure to a density of 500 kg per m<sup>3</sup> (31 pounds per cubic foot) or greater.

Hardboard is available with either one side (S1S) or two sides (S2S) smooth.

There are typically two types of hardboard core used by architectural manufacturers:

- **Standard** (untempered).
- **Tempered**, which is standard hardboard subjected to a curing treatment increasing its stiffness, hardness, and weight.




Figure: 4-004

- **Lumber** - Is where the center ply, called the “core” is composed of strips of lumber edge glued into a solid slab. This type is usually 5-ply, 3/4” (19 mm) thick, but other thickness from 1/2” (12.7 mm) to 1-1/8” (28.6 mm) are manufactured for special uses. There are three main types:

- **Staved** - is where the core strips are random length and butt joined.
- **Full Length** - is where the core strips are one piece in length.
- **Banded** - is where the outside strips run full length and the others are random length. Banding may be the same species of lumber as the rest of the core, but it is usually matched to the face and might include all four edges. Banded plywood is typically produced for special uses, such as furniture and desk tops.




Figure: 4-005

- **Agrifiber** - Panel products made from straw and similar fiber are appearing in the marketplace. Panels shall meet the performance characteristics of ANSI A208.1 or ANSI A208.2 standards.

The characteristics of agrifiber core material performance vary by manufacturer, and are not included in the following table.

- **Combination** - A balanced hybrid blend of veneer and composition core materials offering some of the properties of both. Typically these cores have internal layers which are constructed of three or five plies of veneer or a center layer of wafer board (randomly oriented wafers) or other wood fiber which are sandwiched between thin laminations of a composite product like MDF, particleboard, hardboard, etc.

Typically these products result in stronger, lighter weight, dimensionally stable panels with increased screw holding ability, and superior surface flatness. Combination panels shall meet the standards of particleboard or MDF as stated in this manual, density excepted.




Figure: 4-006

- **Forming (Bendable)** - Assembled and/or machined cores made of hardboard, veneer, particleboard and/or MDF for radius work are manufactured under various trade names. When used for freestanding work these Forming Cores must be a balanced panel but if bound (restrained) the panel is not required to be balanced.

### PRIMARY CORE MATERIALS (continued)

- **Solid Phenolic (SP)** - A composite of solid phenolic resins molded with a homogeneous core of organic fiber reinforced phenolic and one or more integrally cured surfaces of compatible thermoset nonabsorbent resins. SP has seen some use in recent years as wall surfacing, casework parts, and countertops.
- **Other Panel Material** - Shall meet the minimum performance characteristics of ANSI A208.1, ANSI A208.2 or ANSI/HPVA HP-1 (latest edition) standards.
  - **Engineered Wood/Panel** - Is a general term used to describe any wood or plant fiber composite panel. Such products as Particleboard, MDF, SCL and LVL are described as an engineered wood or plant fiber. Typically they are made from wood or plant fiber or wood pieces and have specific esthetic and physical attributes.
- **Bamboo** is a building material attracting much attention due to its quick replenishing and growing cycles as a green product. It is a grass product and not a true wood product. Due to its relatively new emergence in use as a building material, the performance evaluation as a stable and viable building material has not been established. These standards do not cover or endorse the use of bamboo and encourages the design professional to consult with Bamboo manufacturers and distributors as to its characteristics and viability as an architectural millwork product.

# SECTION 4

## Sheet Products

## introductory information

Table: 4-007 - CHARACTERISTICS OF CORE PERFORMANCE

It is important for the reader to understand the difference between “flatness” and “dimensional stability” characteristics. Particleboard and MDF are the recommended cores for high pressure decorative laminate and wood veneer work because of their excellent flatness. Fair dimensional stability (expansion/contraction in panel size) is acceptable unless the product is exposed to wide swings in relative humidity, generally below 25% or above 55% with swings of more than 30 points.

Core Type	Flatness (Warp Resistance)	Visual Edge Quality	Surface Uniformity	Dimensional Stability	Screw Holding Face	Bending Strength
Particleboard, Medium Density	Excellent	Good	Excellent	Fair	Fair	Good
Particleboard, Moisture Resistant	Excellent	Good	Good	Fair	Fair	Good
Particleboard, Fire Retardant	Excellent	Fair	Good	Fair	Fair	Good
Medium Density Fiberboard (MDF)	Excellent	Excellent	Excellent	Fair	Good	Good
MDF, Moisture Resistant	Excellent	Excellent	Excellent	Fair	Good	Good
MDF, Fire Retardant	Excellent	Excellent	Excellent	Fair	Good	Good
Veneer	Fair	Good	Fair	Excellent	Excellent	Excellent
Lumber	Fair	Good	Good	Fair	Excellent	Excellent
Combination	Good	Fair	Excellent	Good	Excellent	Excellent

Various characteristics above are influenced by the grade and thickness of the core and specific gravity of the core species. Visual Edge Quality is rated before treatment with edgebands or fillers and Visual Edge Quality of lumber core assumes the use of “clear edge” grade. Surface Uniformity has a direct relationship to the performance of veneers placed over the surface. Dimensional Stability is usually related to exposure to wide swings in relative humidity. Screw Holding and Bending Strength are influenced by proper design and engineering.

### DECORATIVE FACE MATERIAL AND CONSTRUCTION BALANCE

All panels may be used as cores for the application of decorative faces (e.g. veneer, plastic laminate) to the face and back. The whole is referred to as a panel. The parts being a core covered by a face and a balancing back. To achieve balanced construction, panels must be an odd number of layers (plies) symmetrical from the center line; e.g., inner plies, except the innermost middle ply, should occur in pairs, using materials and adhesives on both sides that contract and expand, or are moisture permeable, at the same rate.

A ply may consist of a single veneer, particleboard, medium density fiberboard, or hardboard. Each pair of inner plies should be of the same thickness and direction of grain at 90 degrees. Each ply of each pair is placed on opposite sides of the innermost ply or layer, alternating grain directions from the center out. (Particleboard and MDF do not have a specific grain orientation). The thinner the facing material, the less force it can generate to cause warping. The thicker the core, the more it can resist a warping movement or force.




Figure: 4-008

# SECTION 4

## Sheet Products

## introductory information

### TYPES OF PLYWOOD PANELS:

- **Particleboard Core**




Figure: 4-009

- **Medium Density Fiberboard (MDF) Core**




Figure: 4-010

- **Veneer Core**




Figure: 4-011

- **Lumber Core**




Figure: 4-012

- **Combination Core**




Figure: 4-013

### WOOD VENEERS

Wood veneer is produced by veneer manufacturers in a variety of "industry standard" thicknesses. The slicing process is controlled by a number of variables. The thickness of the raw veneer has little bearing on the ultimate quality of the end product so long as show-through and sand-through is avoided.

- **Hardwood Veneer - Species:** Available in many domestic and imported wood species. Normally cut as plain sliced. Rift sliced and quarter sliced available in certain species at additional cost.

- **Softwood Veneer - Species:** Most common is Douglas Fir; Pines are available; other softwoods in limited supply. Most softwood veneer is Rotary cut. Plain sliced softwood veneer and "vertical grain" (quarter sliced) softwood veneer are limited in availability with long lead times and higher prices associated with special orders.

Rotary-cut softwood sheets are typically manufactured in various grades referring to the appearance of the face, back, and interior plies of the sheet and are intended for exterior (with a fully waterproof glue line) or interior (with a moisture resistant, but not waterproof, glue line). Clear faces, free of patches, are not typically available.

- **Veneer Grain** might not match the grain of solid stock, and it might not accept transparent finishes in the same manner; additional finishing steps might achieve similar aesthetic value.

- **Figure** is not a function of a species grade, and special desires must be so specified.

- **Special Characteristics**, such as sapwood, heartwood, ribbon stripe, birdseye and comb grain, must be so specified.

- **Natural**, as a type of wood species selection, allows an unlimited amount of heartwood and/or sapwood within a face and is the default selection, unless specified otherwise.

- **Select Red or White** simply means all heartwood or all sapwood, respectively, and must be so specified.

- **Species**, such as Hickory, Pecan, Butternut, or Maple, may exhibit special character or figure and users are advised to thoroughly investigate the expected grain and color of these species.

- **Reconstituted Veneers** are logs that are first sliced into veneer leaves, the leaves may be dyed, then glued under pressure in a mold to produce a large laminated block. The laminated block is then sliced across the glue line to create a faux grain with a designed appearance that is highly repeatable. Not all pre-dyed veneers are colorfast, consult with manufacturer.

### SPECIALTY SHEET PRODUCTS

Plywood with textured faces, pre-finished plywood, overlaid plywood, composition sheets, flame spread rated plywood, moisture resistant plywood, lead lined sheets, projectile resistant armor (bullet proofing), reconstituted veneers, bamboo sheets, acrylic sheets, or PVC sheets are the products of the individual manufacturer, and are covered by their manufacturer's specification - not by these standards.

### PANEL ADHESIVES

Are defined as:

- **Type I** Waterproof bond for limited exterior use (2-Cycle Boil Test plus Shear Test).
- **Type II** Water resistant bond for interior use (3-Cycle Soak Test).

### FIRE RETARDANCE

Sheets are available with various types of fire retardant treated core, such as veneer, lumber, particleboard, and mineral core.

Flame-spread rating will vary for different species of untreated face veneers on treated cores, directly with the density of the untreated face veneers; the higher the density, the higher the flame spread rating.

Refer to the latest edition of the Underwriters' Laboratories listings for various flame-spread ratings available bearing U.L. Labels, <http://ul.com>.

### PHOTODEGRADATION

The effect on the appearance of exposed wood faces caused by exposure to both sun and artificial light sources is called photodegradation. If an entire face is exposed to a light source, it will photodegrade somewhat uniformly and hardly be noticeable, whereas partially exposed surfaces or surfaces with shadow lines might show nonuniform photodegradation. Some woods, such as American Cherry and Walnut, are more susceptible than others, and extra care should be taken to protect against the effects of nonuniform photodegradation.

### OXIDATION

The effect on the appearance of exposed wood faces caused by exposure to atmosphere is called oxidation. This is analogous to browning reactions in freshly cut fruit; for instance, apples. Hardwoods can develop deep yellow to reddish brown discolorations on the surface of the wood when exposed to air immediately after sawing or peeling. These discolorations are especially noticeable on Cherry, Birch, Red Alder, Sycamore, Oak, Maple, and Sweet Gum. Some species, such as Alder, Oak, Birch, and Maple, develop these discolorations during air-seasoning. A related gray stain on several varieties of Southern Oaks also appears to be oxidative in nature. Proper selection, sanding, and finishing can minimize the effects of oxidation.

### VENEER CUTTING

The manner in which a log segment is cut with relation to the annual rings will determine the appearance of the veneer. When sliced, the individual pieces of veneer, referred to as leaves, are kept in the order in which they are sliced, thus permitting a natural grain progression when assembled as veneer faces. The group of leaves from one slicing is called a flitch and is usually identified by a flitch number and the number of gross square feet of veneer it contains. The faces of the leaves with relation to their position in the log are identified as the tight face (toward the outside of the log) and the loose face (toward the inside or heart of the log). During slicing the leaf is stressed on the loose face and compressed on the tight face. When this stress is combined with the natural variation in light refraction caused by the pores of the wood, the result is a difference in the human perception of color and tone between tight and loose faces.

### FOUR COMMON VENEER CUTS

- **Plain Slicing** (or Flat Slicing) - This is the slicing method most often used to produce veneers for architectural woodwork. Slicing is done parallel to a line through the center of the log. A combination of cathedral and straight grain patterns results, with a natural progression of pattern from leaf to leaf.




Figure: 4-014

# SECTION 4

## Sheet Products

## introductory information

### FOUR COMMON VENEER CUTS

(continued)

- Quarter Slicing** (or Quarter Cut) - Quarter slicing simulates the quarter sawing process of solid lumber, roughly parallel to a radius line through the log segment. In many species the individual leaves are narrow as a result. A series of stripes is produced, varying in density and thickness from species to species. "Fleck" (sometimes called flake) is a characteristic of this slicing method in Red and White Oak.




Figure: 4-015



Figure: 4-016

- Rift Slicing** (or Rift Cut) - Rift veneers are produced most often in Red and White Oak. Note that rift veneers and rift sawn solid lumber are produced so differently that a "match" between rift veneers and rift sawn solid lumber is highly unlikely. In both cases the cutting is done slightly off the radius lines minimizing the "fleck" (sometimes called flake) associated with quarter slicing.




Figure: 4-017

- Rotary Slicing** - The log is center mounted on a lathe and "peeled" along the general path of the growth rings like unwinding a roll of paper, providing a generally bold random appearance.

When transparent finish is specified; rotary sliced hardwood veneers are sometimes specified for:

- Wall Surfacing:** Institutional panel faces.
- Doors:** Institutional flush door faces.
- Cabinets:** Semi-exposed (interior) surfaces and used in a limited way for exposed surfaces.

Some species may possess a special figure, for example birds eye, which is achieved by rotary slicing.

Careful consideration, specification, and communication are recommended when rotary cut is contemplated.




Figure: 4-018

# SECTION 4

## Sheet Products

## introductory information

Table: 4-019 - COMMON HARDWOOD VENEER SPECIES and CUTS

SPECIES	ROTARY	PLAIN SLICED	QUARTER SLICED	RIFT
Anigre		●	●	
Ash		●	●	
Beech		●	●	
Birch	●	●		
Cherry		●	●	
Hickory		●		
Lauan	●		●	
Mahogany, African		●	●	
Mahogany, American		●	●	
Makore		●	●	
Maple	●	●	●	
Oak, Red	●	●	●	●
Oak, White		●	●	●
Pecan		●		
Poplar	●	●		
Sapele		●	●	
Walnut		●	●	

# SECTION 4

## Sheet Products

## introductory information

Table: 4-020 - GENERAL CHARACTERISTICS OF SELECTED WOOD SPECIES:

SPECIES	CUT (1)	WIDTH TO	LENGTH	FLITCH SIZE	COST (2)	AVAILABILITY
<b>Alder</b>	Plain Sliced	12" (305 mm)	10' (3048 mm)	Medium	Moderate	Moderate
<b>Anigre</b>	Plain Sliced	12" (305 mm)	10' (3048 mm)	Large	Moderate	Good
	Quarter Sliced	8" (203 mm)	12' (3658 mm)	Medium	High	Good
<b>Anigre, Figured</b>	Quarter Sliced	8" (203 mm)	12' (3658 mm)	Medium	Very High	Limited
<b>Ash, American</b>	Plain Sliced	12" (305 mm)	10' (3048 mm)	Large	Moderate	Moderate
	Quarter Sliced	6" (153 mm)	10' (3048 mm)	Medium	High	Moderate
<b>Ash, European</b>	Plain Sliced	10" (254 mm)	10' (3048 mm)	Medium	Moderate	Limited
	Quarter Sliced	6" (153 mm)	10' (3048 mm)	Small	Moderate	Moderate
<b>Beech, European</b>	Plain Sliced	10" (254 mm)	10' (3048 mm)	Large	Moderate	Good
	Quarter Sliced	6" (153 mm)	10' (3048 mm)	Medium	High	Good
<b>Birch, Natural</b>	Rotary	36" (914 mm)	10' (3048 mm)	Large	Low	Good
	Plain Sliced	8" (203 mm)	10' (3048 mm)	Small	Medium	Limited
<b>Birch, Select Red and White</b>	Rotary	36" (914 mm)	10' (3048 mm)	Large	Moderate	Good
	Plain Sliced	8" (203 mm)	10' (3048 mm)	Small	High	Limited
<b>Cedar, Western Red</b>	Plain Sliced	18" (457 mm)	10' (3048 mm)	Medium	Moderate	Limited
	Quarter Sliced	8" (203 mm)	10' (3048 mm)	Medium	Moderate	Limited
<b>Cherry, American (3)</b>	Plain Sliced	12" (305 mm)	12' (3658 mm)	Medium	Moderate	Good
	Quarter Sliced	6" (153 mm)	10' (3048 mm)	Small	High	Moderate
<b>Ebony</b>	Plain Sliced	6" (153 mm)	10' (3048 mm)	Very Small	Extreme	Very Limited
<b>Fir, Douglas (Vertical Grain)</b>	Quarter Sliced	18" (457 mm)	12' (3658 mm)	Large	Moderate	Good
<b>Hickory</b>	Plain Sliced	12" (305 mm)	12' (3658 mm)	Medium	Moderate	Good
	Quarter Sliced	6" (153 mm)	10' (3048 mm)	Small	Moderate	Moderate
<b>Jatoba</b>	Plain Sliced	12" (305 mm)	12' (3658 mm)	Medium	Moderate	Good
<b>Lacewood</b>	Quarter Sliced	6" (153 mm)	10' (3048 mm)	Small	High	Very Limited
<b>Lauan (4)</b>	Plain Sliced	15" (381 mm)	12' (3658 mm)	Medium	Moderate	Good
	Quarter Sliced	8" (203 mm)	10' (3048 mm)	Small	Moderate	Moderate
<b>Mahogany, African (5)</b>	Plain Sliced	18" (457 mm)	12' (3658 mm)	Large	Moderate	Good
	Quarter Sliced	10" (254 mm)	12' (3658 mm)	Medium	High	Moderate
<b>Mahogany, American (5) (Swietenia macrophylla CITES listed (6))</b>	Plain Sliced	18" (457 mm)	12' (3658 mm)	Large	Moderate	Very Limited
	Quarter Sliced	10" (254 mm)	12' (3658 mm)	Medium	High	Very Limited
<b>Makore</b>	Plain Sliced	15" (381 mm)	12' (3658 mm)	Large	Moderate	Moderate
	Quarter Sliced	8" (203 mm)	12' (3658 mm)	Medium	High	Limited
<b>Maple, American</b>	Rotary	36" (914 mm)	10' (3048 mm)	Large	Low	Good
	Plain Sliced	12" (305 mm)	12' (3658 mm)	Medium	Moderate	Good (2)
	Quarter Sliced	6" (153 mm)	10' (3048 mm)	Small	High	Limited
<b>Maple, Birds Eye</b>	Rotary	24" (610 mm)	10' (3048 mm)	Medium	Very High	Limited

(continued)

# SECTION 4

## Sheet Products

## introductory information

Table: 4-020 - GENERAL CHARACTERISTICS OF SELECTED WOOD SPECIES: (continued)

SPECIES	CUT (1)	WIDTH TO	LENGTH	FLITCH SIZE	COST (2)	AVAILABILITY
Meranti	Plain Sliced	18" (457 mm)	12' (3658 mm)	Large	Moderate	Good
	Quarter Sliced	10" (254 mm)	12' (3658 mm)	Medium	High	Moderate
Oak, English Brown	Plain Sliced	12" (305 mm)	10' (3048 mm)	Medium	High	Limited
	Quarter Sliced	8" (203 mm)	10' (3048 mm)	Small	Very High	Limited
Oak, Red	Rotary	36" (914 mm)	10' (3048 mm)	Large	Low	Good
	Plain Sliced	18" (457 mm)	12' (3658 mm)	Large	Low	Good
	Quarter Sliced	8" (203 mm)	10' (3048 mm)	Medium	Moderate	Good
	Rift	8" (203 mm)	10' (3048 mm)	Medium	Moderate	Good
Oak, White	Plain Sliced	12" (305 mm)	12' (3658 mm)	Medium	Low	Good
	Quarter Sliced	8" (203 mm)	10' (3048 mm)	Small	Moderate	Good
	Rift	8" (203 mm)	10' (3048 mm)	Small	Moderate	Good
Poplar	Plain Sliced	15" (381 mm)	10' (3048 mm)	Medium	Low	Good
Rosewood, American	Plain Sliced	10" (254 mm)	10' (3048 mm)	Small	Very High	Very Limited
Sapele	Plain Sliced	15" (381 mm)	10' (3048 mm)	Large	Moderate	Good
	Quarter Sliced	8" (203 mm)	10' (3048 mm)	Medium	Moderate	Moderate
Sycamore	Plain Sliced	15" (381 mm)	12' (3658 mm)	Medium	High	Moderate
	Quarter Sliced	8" (203 mm)	10' (3048 mm)	Small	High	Limited
Teak	Plain Sliced	12" (305 mm)	12' (3658 mm)	Medium	High	Moderate
	Quarter Sliced	5" (127 mm)	10' (3048 mm)	Small	High	Limited
Walnut (3)	Plain Sliced	15" (381 mm)	12' (3658 mm)	Large	Moderate	Good
	Quarter Sliced	6" (152 mm)	10' (3048 mm)	Small	High	Moderate
Wenge	Plain Sliced	10" (254 mm)	10' (3048 mm)	Small	High	Limited

(1) When only Plain Sliced is listed, the width dimension for quartered Cut is narrower.

(2) Seasonal factors may affect availability.

(3) Cherry, Walnut and certain other hardwood species are required to be specified by origin, such as American Cherry, American Walnut, or English Brown Oak, because they can be significantly different in color and figure.

(4) Luan (White and Red), Tanguile, and other species are native to the Philippine Islands and are sometimes referred to as Philippine Mahogany; however, they are not a true Mahogany. The generic term Mahogany should not be specified without further definition.

(5) Mahogany, American and African vary in color from a light pink to a light red, reddish brown to a golden brown or yellowish tan. Some Mahogany turns darker or lighter in color after machining. The figure or grain runs from plain sliced, plain stripe to broken stripe, mottled, fiddleback, swirl, and crotches.

(6) CITES, Convention on International Trade in Endangered Species or Wild Fauna and Flora.

# SECTION 4

## Sheet Products

## introductory information

### MATCHING ADJACENT WOOD VENEER LEAVES

It is possible to achieve certain visual effects by the manner in which the leaves are arranged. Matching of adjacent wood veneer leaves, as with the effect of different veneer cuts, can alter the appearance of a given panel or an entire installation. To create a particular appearance, the veneer leaves of a flitch are edge glued together in patterns.

Individual leaves of veneer in a sliced flitch increase or decrease in width as the slicing progresses. Thus, if a number of panels are manufactured from a particular flitch, the number of veneer leaves per panel face will change as the flitch is utilized. The manner in which these leaves are "laid up" within the panel requires specification.

Rotary cut veneers are difficult to match; therefore most matching is done with sliced veneers. The matching of adjacent veneer leaves must be specified. Special arrangements of leaves such as "diamond" and "box" matching are available. Consult your manufacturer for choices.

White dashed lines on the following illustrations indicate the veneer trim lines.

- **Book Matching** - A common match used in the industry. Every other piece of veneer is turned over so adjacent pieces (leaves) are opened like the pages of a book.



Figure: 4-021

- Visual Effect - Veneer joints match, creating a symmetrical pattern. Yields maximum continuity of grain. When sequenced panels are specified, prominent characteristics will ascend or descend across the match as the leaves progress from panel to panel.

- **Barber Pole Effect in Book Match** - Because the tight side and loose side of the veneer leaf faces alternate in adjacent pieces of veneer, they may accept stain differently, and this may result in a noticeable color variation. Book matching also accentuates cell polarization, causing the perception of different colors. These natural characteristics are often called barber pole, and are not a manufacturing defect.




Figure: 4-022

- **Slip Matching** - Often used with quarter sliced and rift sliced veneers. Adjoining leaves are placed (slipped out) in sequence without turning, resulting in the same face sides being exposed.

Visual Effect - Grain figure repeats; but joints do not show visual grain match.



Figure: 4-023

The lack of grain match at the joints can be desirable. The relatively straight grain patterns of quartered and rift veneers generally produce pleasing results and a uniformity of color because all faces have the same light refraction.

- **Random Matching** - Veneer leaves are placed next to each other in a random order and orientation, producing a "board by board" effect in many species.

Visual Effect - Casual or rustic appearance, as though individual boards from a random pile were applied to the product. Conscious effort is made to mismatch grain at joints.

Degrees of contrast and variation may change from panel to panel. This match is more difficult to obtain than book or slip match, and should be clearly specified and detailed.




Figure:4-024

### MATCHING ADJACENT WOOD VENEER LEAVES (continued)

- **End or Butt Matching** (a.k.a. Architectural End Match) - Often used to extend the apparent length of available veneers for high wall panels and long conference tables.

Leaves are individually book (or slip) matched, first end to end and then side to side, alternating end and side.

- **Visual Effect** - Yields best continuous grain patterns for length as well as width. Minimizes misalignment of grain pattern.




Figure: 4-025

### MATCHING WITHIN INDIVIDUAL PANEL FACES

The individual leaves of veneer in a sliced flitch increase or decrease in width as the slicing progresses. Thus, if a number of panels are manufactured from a particular flitch, the number of veneer leaves per panel face will change as the flitch is utilized. The manner in which these leaves are “laid up” within the panel requires specification, and is classified as follows:

- **Running Match** - The panel face is made from components running through the flitch consecutively. Any portion of a component left over from a face is used as the beginning component or leaf in starting the next panel. **This method is the default for Custom Grade.**




Figure: 4-026

- **Balance Match** - Each panel face is assembled from veneer leaves of uniform width before edge trimming. Panels may contain an even or odd number of leaves, and distribution may change from panel to panel within a sequenced set. While **this method is the default for Premium Grade**, it must be specified for other Grades, and it is the most common assembly method at moderate cost.




Figure: 4-027

- **Balance and Center Match** - Each panel face is assembled of an even number from veneer leaves of uniform width before edge trimming. Thus, there is a veneer joint in the center of the panel, producing horizontal symmetry. A small amount of figure is lost in the process. Considered by some to be the most pleasing assembly at a modest increase in cost over Balance Match.




Figure: 4-028

- **Slip, Center, Book Match** - Each panel face is assembled of an even (four or more) number of veneer leaves, generally of uniform width. The veneer leaves are laid out as a slip matched panel face; then at the center, one half of the leaves are booked to the other half. Quarter and rift sliced veneers are generally used for this match, which allows for a pleasing balance of sweep and character marks.

Slip Left ◀ | ▶ Slip Right



Figure: 4-029

# SECTION 4

## Sheet Products

### introductory information

#### MATCHING WITHIN INDIVIDUAL PANEL FACES (continued)

- **Swing Match** - is made by dividing the panel into multiple paired sets. For each paired set, two leaves of veneer are cut at half the width of the set. One of these two veneer leaves is rotated 180 degrees and joined to the other. This pair is then adjoined to the other pairs assembled in the same way.




Figure: 4-030

#### SPECIALTY OR SKETCH MATCHES OF WOOD VENEERS

There are regional variations in the “names” of the following veneer leaf matching techniques, drawn as squares for simplicity. It is strongly recommended that the design professional use both names and drawings to define the desired effect, using a rectangle, polygon, circle, ellipse, or other shape. Rift sliced, quarter sliced, and highly figured veneers are generally used for these speciality matches. The different matches of veneer cause the reflection of light to vary from adjoining leaves, bringing “life” to the panel. Due to the inherent nature of the layup process, alignment at corners might vary.

- **Herringbone or V Book Match** - is one or more pairs of assembled slipped or booked leaves. Each assembled set of leaves is cut at generally 45 degrees to one edge of the panel. The assembled set of leaves is then end matched to the adjoining assembled set of leaves.




Figure: 4-031

- **Sunburst Match** - is made of six or more veneer leaves cut at the appropriate angle with the grain radiating from the center. These veneer leaves are then book matched, assembled, and trimmed for final size.




Figure: 4-032

- **Box Match** - is made of four leaves with the grain running parallel to the perimeter of the panel. The leaves are cut at the appropriate angle and end matched.



Figure: 4-033

- **Reverse or End Grain Box Match** - is made of four leaves with the grain running at right angles to the perimeter of the panel. The leaves are cut at the appropriate angle and book matched.




Figure: 4-034

### SPECIALTY OR SKETCH MATCHES OF WOOD VENEERS (continued)

- **Diamond Match** - is made of four leaves with the grain running 45 degrees to the perimeter of the panel and surrounding the center. The leaves are cut at the appropriate angle and end matched.




Figure: 4-035

- **Reverse Diamond Match** - is made of four leaves with the grain running 45 degrees to the perimeter of the panel and radiating from the center. The leaves are cut at the appropriate angle and book matched.



Figure: 4-036

- **Parquet Match** - is made by dividing the panel into multiple equal sized pieces and cutting the veneer to the same size. Each veneer leaf is joined at right angles to the adjoining piece of veneer.




Figure: 4-037

### MATCHES BETWEEN PANELS

- **Not Matched** - Veneered panels are generally manufactured without matching and may or may not be similar in grain and color.
- **Sequence Matched** - Veneered panels may be sourced and/or manufactured in sequence. These panels will be well matched for grain and color.
- **Sequence Matched & Custom Width** - Generally veneered panels are manufactured in 4'x 8' and occasionally in 4'x 10' panels. The design professional may specify veneered sequence panels in custom width for the specific project and/or elevation. These panels will be well matched for grain and color.
- **Blueprint Matched** - The design professional may specify blueprint matched panels which will be custom sized height and width as well as sequencing for the specific project and/or elevation. These panels will be matched for grain and color.

### DECORATIVE LAMINATES, OVERLAYS, and PRE-FINISHED PANEL PRODUCTS

Decorative surfacing materials are often applied to wood product cores such as industrial particleboard, fiberboard, hardboard, etc. Terminology and definitions of these overlay products follow, broadly grouped as:

- **Medium Density Overlay (MDO)** - Pressed resin impregnated paper overlays, highly resistant to moisture, applied to suitable cores for both interior and exterior uses. The seamless panel face and uniform density furnishes a sound base for opaque finishes and paint.
- **High Density Overlay (HDO)** - Is a thermosetting phenolic resin impregnated, cellulose fiber overlay that provides a hard, smooth, uniformly textured surface of such character that further finishing is not necessary. Some evidence of underlying grain may appear.
- **Thermoplastic Sheet** - Semi rigid sheet or roll stock extruded from a nonporous acrylic/polyvinyl chloride (PVC) alloy solid color throughout. Withstands high impact. Minor scratches and gouges are less conspicuous due to the solid color.
- **Vinyl Films** - Polyvinyl chloride (PVC) film, either clear or solid color, used extensively for decorative vertical surfaces in mobile homes, recreational vehicles, commercial panels and movable walls. Some films are available with scuff resistant top coatings.

# SECTION 4

## Sheet Products

## introductory information

### DECORATIVE LAMINATES, OVERLAYS, and PRE-FINISHED PANEL PRODUCTS

(continued)

- **High Pressure Decorative Laminate (HPDL)** - Is a stand alone product that can be laminated onto a core as the face of a sheet product or directly onto a structure as a covering. Decorative laminate is produced in a one step process by fusing together, under heat and pressure, multiple layers of kraft paper saturated with phenolic resin, together with a layer of melamine saturated decorative paper.

The assembly offers resistance to wear and many common stains and chemicals. Common uses include casework exteriors, countertops, and wall paneling.




Figure: 4-038

Some decorative laminates utilize a white background paper to achieve the high fidelity, contrast, and depth of color in their printed patterns, which leaves a white line at the exposed edges of the laminate and can be extremely noticeable in darker colors.

- **Low Pressure Decorative Laminate (LPDL)** - Decorative thermally fused panels flat pressed from a thermoset polyester or melamine resin impregnated web. Most products are pre-laminated to Industrial Particleboard or Medium Density Fiberboard cores when they arrive at the woodwork fabricator. Performance characteristics are similar to High Pressure decorative laminate except for the impact test.

Thermally fused papers and foils are similar to that used in the manufacture of decorative laminate. Saturated with reactive resins and partially cured during manufacture to allow for storage and handling, the papers achieve final curing when they are hot press laminated to a core, providing a hard, permanent thermoset bond between the paper and the core.

- Melamine - Impregnated papers, the most common, are noted for their hardness, scratch resistance, and color stability.
- Polyester - Impregnated papers are noted for their chemical, stain, water, and impact resistance; color clarity; and machinability.

### COMMON HPDL TYPES

The basic types form the majority of applications of high pressure decorative laminate in North America are:

- **General Purpose (HGS and HGL)** Used for most horizontal applications, such as desk tops and self-edged kitchen countertops, "HG" laminates offer durability, resistance to stains, and resistance to heat.
- **Vertical (VGS and VGL)** A slightly thinner material, "VG" laminates are produced for areas which will receive less wear and impact than typical horizontal materials. They are an excellent choice for cabinet doors, the sides of casework, primarily decorative display shelves and vertical panels.
- **Post-forming (HGP and VGP)** Specifically for applications where a radiused surface is desirable, "P" laminates offer strong performance in both horizontal and vertical applications.

A major advantage of formed surfaces on the exposed corners of casework and service counters is the edge's resistance to chipping damage. Most chip damage occurs at sharp 90° corners. Surfaces are thermo-formed under controlled temperature and pressure.

- **Cabinet Liner (CLS)** A thin vertical sheet, this type is designed for areas where the surface, which is not considered decorative, generally white or off white in color, but will need to withstand less wear, such as the inside surfaces of cabinets and closets.
- **Backing Sheet (BKL)** Backing materials are essential in the fabrication of decorative laminate clad surfaces to prevent warping and to protect against dimensional instability of both laminate and core in conditions of changing temperature and humidity. Backing sheets are non decorative, and both economical and effective in the creation of a successful application. Produced without a decorative face and available as standard (slightly thinner than decorative) or regrind (reclaimed decorative laminate with decorative sheet sanded off).
- **Flame Retardant (HGF)** Some of these laminates are capable of providing flame retardant characteristics as determined by test methods required by the authority having jurisdiction. HGF is the most common type used.

In summary, these common decorative laminate types have the limitations of high pressure decorative laminate:

- They are for interior use only, and will not be successfully used outdoors or under heavy exposure to the ultraviolet rays of the sun.
- They should not be used as cutting surfaces, because knives and other sharp tools will readily deface the surface and lower its other performance capabilities.
- They should not be exposed to caustic chemicals, such as drain and toilet bowl cleaners, which can permanently etch the surface.
- While they offer outstanding heat resistance, exposure to constant heat from a curling iron, an electric skillet or coffee pot, for example can harm the surface and may cause it to delaminate, discolor or blister.

### COLOR THROUGH DECORATIVE LAMINATES

The interest in specifying solid color decorative laminates and the resurgence of interest in very pale pastels and neutral shades have caused increasing concern with the brown line visible at glued decorative laminate edges.

Color through decorative laminates were formulated specifically to provide light colors without this brown line.

Color through decorative laminate may be applied to cores in three basic ways:

- **As sheets**, to form a decorative face with a true monolithic look;
- **As edge trims**, to match a face of conventional decorative laminate or to accent a natural material such as wood or leather;
- **As decorative inlays**.

Color through decorative laminate is produced with multiple layers of decorative papers, rather than the decorative plus kraft composition of conventional laminate. As a result, this material is slightly stiffer and slightly more brittle when flexed.

Selection of adhesive should take into consideration that a visible glue line may detract. Adhesive should be un-tinted.

### SOLID PHENOLIC LAMINATES (SP)

High pressure decorative laminates are produced by several manufacturers in thicknesses adequate to preclude the use of a core (minimum 1/8" (3.2 mm)).

Unlike conventional sheets, they may be drilled and tapped, and offer significant screw holding capacity.

Depending on thickness, these laminates may be used for many flat applications, such as toilet and dressing room partitions, workbenches, shelving, and table tops.

Panels are heavy for their size—an asset in sturdiness of the end application, but a factor which must be considered when planning for time and cost of labor and transportation as well as for support structures.

### STATIC-DISSIPATIVE LAMINATES

High pressure decorative laminate is a good electrical insulator—in fact, it was for the specific purpose of electrical insulation that the product was originally developed.

HPDL does not store static electricity, and it is therefore a suitable material for use in hospital areas, i.e.: operating rooms, X-ray rooms, and computer room controlled environments where the accumulation and retention of static electricity must be avoided.

However, the growing need for work surfaces in areas such as electronic clean rooms, where electrostatic charges must be actively, continuously channeled away, has triggered the development of specifically conductive (static-dissipative) laminates such as: Anti Static, Static Dissipative and Conductive.

These HPDL sheets have a conductive layer enclosed in, or backing, the sheet. Connected to suitable grounding, they create a decorative, sturdy, practical work surface. Applications include electronic workbench tops and work areas around instrument monitoring devices, in lab testing environments, around photo equipment and on computer desktops.

Antistatic laminates are produced in a number of compositions, thicknesses, colors and patterns. Consult manufacturers' literature for details.

### CHEMICAL-RESISTANT DECORATIVE LAMINATES

Chemical resistant HPDL offers the familiar advantages of HPDL: resistance to wear, conductive and radiant heat, and impact; as well as ease in cleaning, color fastness, and relatively light weight. Although this product may resist some chemicals, depending on the testing methods of the individual manufactures, it is the design professional's responsibility to select the appropriate material for the chemical resistance required.

These laminates may be applied on vertical as well as horizontal surfaces, to extend protection to cabinet doors and sides. And they may be post-formed for seamless edges.

Adhesives should be specified carefully. Edges which may be exposed to chemical attack should be glued with chemical-resistant adhesives.

Formulation of chemical-resistant decorative laminate differs from producer to producer. Consult product literature to make sure the material you specify meets the needs of your projects. They are available in varying thicknesses and a number of color and patterns depending on manufacturer.

### METAL-FACED LAMINATES

High pressure decorative laminates are produced with metal veneers and a backer of kraft paper and phenolic resin.

The material used for much of the metal laminates is interior-type anodized aluminum. Other materials, including copper and nickel alloys may be specified in various formats; however, some metals, such as stainless steel or plated metal, are not conducive to machining with woodworking equipment.

### FLAME SPREAD RATING OF DECORATIVE LAMINATES

Safer materials for interiors are a primary concern for commercial and institutional design professionals across North America. The threat of fire and its concomitant hazard of smoke has created a critical need for interior materials that address this concern without aesthetic sacrifice.

Manufacturers of decorative laminate materials offer fire and smoke retardant grades for interior application. The addition of fire retardant does not affect the performance characteristics of decorative laminate; wear and stain resistance, ease of maintenance, and color stability remain very strong.

Rated high pressure decorative laminates are evaluated and certified according to ASTM-E-84 test procedures (cataloged as ASTM-E-84 Tunnel Test, <http://astm.org>; and as Test No. 723 by Underwriters Laboratories, Inc., <http://ul.com>. Similar Canadian testing is cataloged by Underwriters Laboratories of Canada as CAN/ULC S-102, <http://canada.ul.com/ulcprograms/buildingandconstructionmaterials/>

With appropriate choices of core and adhesive, panels clad with fire-rated decorative laminate may be produced to comply with Class A fire codes. Finished panels, already certified, may also be specified from some decorative laminate manufacturers.

Major applications of rated decorative laminate include door, wall, and wainscot cladding in corridors, stairwells, entries, and elevators; as well as surfacing on fixtures and casework. These materials are supplied in both horizontal and vertical types, in a wide range of colors and patterns.

They may not be post-formed; the special formulation that produces fire retardant is not compatible with heat forming.

Adhesive choice for fire-rated decorative laminate is important. As with many types of fire retardant particleboard, some PVA adhesives are incompatible with the fire-retardant chemical composition of the decorative laminate material. Resorcinol adhesives are best for both chemical compatibility and flame spread rating of the end product. Contact adhesives do surprisingly well in some cases. Verify test ratings with your decorative laminate manufacturer.

### NATURAL WOOD LAMINATES

An excellent example of the ongoing evolution of the high pressure decorative laminate process. Presently, natural wood laminates may be specified in two formats; both feature thin veneers of woods bonded under high pressure and heat to a core of kraft papers and phenolic resins. One process leaves the face of the wood untreated, and ready to finish. The other adds a protective face of melamine resin.

Performance characteristics vary with the presence or absence of the melamine resin. In both cases, the ease of cutting and bonding, as well as the wear resistance, improve in comparison to raw wood veneer. With the melamine face, the natural wood assumes much of the easy care and long wear properties of conventional high pressure decorative laminate.

Sequence matching of natural wood laminate panels is extremely limited; consult the laminate manufacturer.

### SPECIAL SHEET PRODUCTS

Included in this classification are special panel products such as lead lined panels for X-ray areas, bullet resistant panels, honeycomb core panels when light weight is a consideration, etc.

- **Lead Lined Panels** - Usually a sheet of lead of a specified thickness, to meet X-ray shield requirements, is laminated between 2 layers of core material. A decorative overlay and balancing sheet can then be applied as required.
- **Bullet Resistant Panels** - Available as steel plate, glass, polycarbonate, acrylic or fiberglass reinforced material which can offer protection against many available small arms fire, depending upon the thickness specified. These panels are usually built into the interior of the structure of the counter, teller's lines, judge's benches, etc.

### SOLID SURFACE

Is a manufactured, filled cast polymeric resin panel. The fillers enhance both its performance properties and aesthetics. With a homogeneous composition throughout its thickness, solid surface requires no finish coat and is capable of being fabricated with inconspicuous seams and repaired to its original finish. Products (and manufacturer's warranties) vary and should be fabricated according to manufacturer's recommendations, including the use of unique fasteners and adhesives. Many decorative inlays are available. Consult your manufacturer about performance issues, materials, colors, and patterns. To ensure color and pattern match it is suggested to use same batch material at adjacent sheets.

### OTHER PANEL PRODUCTS

Many new panel products are available, from recycled glass and epoxy impregnated metal shavings to plastic or acrylic panels created from a variety of natural and recycled materials. The options are wide spread and the sheer volume of products make it difficult to quantify. These standards acknowledge these products and encourages design professionals to verify with individual product manufacturers that their products meet required performance standards. These standards do not at present address these products.

### ANTIMICROBIAL SURFACES

There is increasing availability of antimicrobial products, including solid surface and HPDL.

It is important to understand that regardless of the methodology used to create the antimicrobial surface there are two significantly different types of claims regarding such antimicrobial products. Common terminology refers to these:

- **Within Canada as:**
  - **Disinfectant Drugs** - Which Health Canada, <http://hc-sc.gc.ca>, classifies as a non market authorized claim, lacking a Drug Identification Number (DIN).
  - **Hard Surface Disinfectants** - Which Health Canada classifies as having received "Market Authorization" when such have been granted a Drug Identification Number (DIN).

### • Within the United States as:

- **Treated Article Claim** - Which the US Environmental Protection Agency (EPA), <http://epa.gov>, classifies as a "treated article exemption", typically referring to items that are treated with antimicrobial pesticide to protect the item itself, not the public. Such exemption will be absent any EPA registration number and is granted for non-public health use.
- **Public Health Claim** - Which the EPA classifies as "EPA registered products which have been shown, using EPA testing protocols, to demonstrate efficacy in the installed format. Such test protocol requires an efficacy of killing 99.9% of all bacteria, fungi and viruses within two hours.

### NONTRADITIONAL MATERIALS

Covers materials re-purposed from other industrial and manufacturing areas, but assigned to the woodwork manufacturer and treated similarly to traditional millwork items like wall paneling. From a design perspective considerations of appearance, color, finish, variation and relation are deemed important as they would be with traditional wood products.

Examples of non-traditional materials could be a fiber/cement panel designed for fire resistance, insulation re-purposed as a decorative panel, metal products, cloth, acrylics, etc.

Because these materials are unique, contract documents, shall clearly indicate or delineate all of the necessary material, fabrication, installation and building code/regulation direction and requirements as may be applicable for the manufacturer/installer to reasonably accomplish the intended design concept.

### RECLAIMED or RECYCLED WOOD

#### DESIGN PROFESSIONAL RESPONSIBILITY

Use of unique materials like reclaimed or recycled wood requires a more active role of the design professional in sourcing and pre-approving desired material selections. There are no traditional guidelines with these types of materials to assure either the woodwork manufacturer or the design professional of achieving an intended result. There will be situations where the design professional will be required to directly participate in the individual piecemeal selection and layout process of the product.

**CONTRACT DOCUMENTS**, shall clearly indicate or delineate all material, fabrication, installation and applicable building code/regulation requirements with the clear understanding that incomplete design choices, changes in scope or material selection, lack of material selection, or design choices made after initial bid may impact the cost or not be possible.

The contract documents shall specifically list the material source and identifier, and address the allowable:

- Variation in color or tone, grain, distress, character, and patina.
- Defects, such as nail/bolt holes, checking, cracking, discoloration, milling marks, roughness in terms of quantity, locations, repetition, etc.
- Distortion in terms of straightness, cupping, flatness, etc.

See SECTION 3 for additional information.

# SECTION 4

## Sheet Products

## introductory information

### DESIGN RESOURCES

Is a perpetually expanding, web based resource of pictures, videos, illustrations, ideas and design concepts for inspiring thought and design creativity - assessable at: <http://naaws-design-resources.com>



Relative to this Section, offerings will include:

- Veneer species pictures
- Veneer slicing examples

# SECTION 4

## Sheet Products

GENERAL/PRODUCT/TEST

Where the **E**, **C**, or **P** icon is not indicated,  
the rule applies to all Grades equally



## compliance requirements

**INCLUDING:** Hardwood and Softwood Veneer, High Pressure Decorative Laminate, Thermally Fused Overlays, Vinyl Film, Medium and High Density Overlays, Hardboard, Backers, Solid Surface, Solid Phenolic, Epoxy Resin, and Natural/Engineered Stone

### 4.1 BASIC CONSIDERATIONS

- 1 **GRADE CLASSIFICATIONS ECONOMY, CUSTOM, and PREMIUM** are used within these standards only in reference to the acceptable quality of workmanship, material, or installation in a completed architectural woodwork product.
- 1.2 This material section deals with sheet products, which are a component of finished products covered in Sections 6 - 12.
  - 1.2.1 In this section, the use of Grade classifications is only for the purpose of identifying sheet products that can be used in finished products meeting those Grades.
  - 1.2.2 These Grade classifications are not intended to be used as Grades of raw material or to judge a stand alone sheet.
- 2 **PANEL ASSOCIATION GRADES**, by themselves, should not be used for architectural woodwork, because even their highest grades might permit unacceptable defects, and:
  - 2.1 The appearance of a piece in the end product is of primary importance, not whether it is cut from a larger sheet that contained characteristics which can be eliminated.
- 3 **SHEET PRODUCT REQUIREMENTS**
  - 3.1 Apply only to surfaces visible after manufacture and installation.
  - 3.2 Establish criteria as to which, if any, natural characteristics are acceptable.
  - 3.3 Limit the extent of characteristics that will be permitted based on an exposed area's size and the proximity of characteristics to one another.
  - 3.4 Do not apply to special varieties of species that display unusual characteristics desirable for aesthetic and design reasons.

### 4.1 BASIC CONSIDERATIONS (continued)

- 4 **CONTRACT DOCUMENTS** shall govern if in conflict with these standards.
- 5 **LOW DENSITY FIBERBOARD (LDF)** sheets have distinct weight advantages; however, they typically offer substantially less in performance characteristics. LDF is permitted in general paneling products and/or woodwork fabrication, with the exception of casework.
  - 5.1 LDF may be used for casework construction, provided its performance characteristics meet or exceed those required of particleboard.
- 6 **CONTINUOUS PRESSURE LAMINATES** (melamine or polyester based) are an alternative to and may be used in lieu of HPDL, provided they conform to the same standards as HPDL.
- 7 **INDUSTRY PRACTICES**
  - 7.1 **PANEL GRAIN DIRECTION** is indicated by its size listing; for example, 48" x 96" (1219 mm x 2438 mm) means the grain direction runs with the 96" (2438 mm) direction, whereas a 96" x 48" (2438 mm x 1219 mm) panel's grain direction runs with the 48" (1219 mm) dimension.

# SECTION 4

## Sheet Products

GENERAL/**PRODUCT**/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



## compliance requirements

### 4.2 SCOPE

- 1 All sheet products used for the fabrication or production of the architectural woodwork are covered by these standards.

### 4.3 DEFAULT STIPULATION

- 1 If not otherwise specified or indicated in the contract documents, sheet products shall match the default stipulation of the applicable product portion of these standards.



### 4.4 RULES

- 1 The following rules shall govern unless a project's contract documents require otherwise.
- 2 These rules are intended to provide a well defined degree of control over a project's quality of materials and workmanship.
- 3 **ERRATA**, published at <http://naaws-errata.com>, shall **take precedence over these rules**, subject to their date of posting and a project's bid date.



### 4.4.4 Basic General Rules

1	<b>AESTHETIC</b> grade rules apply only to exposed and semi-exposed surfaces visible after installation.
2	<b>GRAIN DIRECTION</b> is indicated by a panel's size listing.
3	<b>SPECIES</b> not covered by these standards shall be as agreed to between owner/design professional and manufacturer/installer as to length requirements and size/exposed area of permitted natural characteristics.
4	<b>REFERENCE STANDARDS</b> , adopted for the performance, fabrication, and appearance of face veneers, laminates, overlays, backers, and cores are as follows:
4 1	Hardwood Plywood - ANSI/HPVA HP-1 (latest edition), <a href="http://hpva.org">http://hpva.org</a> .
4 2	Softwood Plywood - Voluntary Product Standard - PS1 (latest edition), <a href="http://nist.gov">http://nist.gov</a> .
4 3	Medium-Density Overlay (MDO) - Voluntary Product Standard - PS1 (latest edition), <a href="http://nist.gov">http://nist.gov</a>
4 4	High-Density Overlay (HDO) - Voluntary Product Standard - PS1 (latest edition), <a href="http://nist.gov">http://nist.gov</a>
4 5	Thermally Fused Overlay (Melamine or Polyester ) - NEMA - LD-3 (latest edition), <a href="http://nema.org">http://nema.org</a> , for face characteristic only.
4 6	High-Pressure Laminate (HPDL) - NEMA - LD-3 (latest edition), <a href="http://nema.org">http://nema.org</a>
4 7	Hardboard - ANSI A135.4 (latest edition), <a href="http://compositepanel.org">http://compositepanel.org</a>
4 8	Particleboard - ANSI A208.1 (latest edition), <a href="http://compositepanel.org">http://compositepanel.org</a> - Grade M2 or better.
4 9	Medium-Density Fiberboard (MDF), <a href="http://compositepanel.org">http://compositepanel.org</a> - ANSI A208.2 (latest edition).
4 10	Oriented Strand Board (OSB) - Voluntary Product Standard - PS2 (latest edition), <a href="http://nist.gov">http://nist.gov</a>
4 11	Agrifiber – shall meet or exceed the performance properties of particleboard or MDF as stated in this manual.
4 12	Combination Core – shall meet or exceed the performance characteristics of ANSI A208.1 or ANSI A208.2 (latest edition) standards, <a href="http://compositepanel.org">http://compositepanel.org</a> .

Continues next column ▼

# SECTION 4

## Sheet Products

GENERAL/PRODUCT/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



## compliance requirements

4.4.4 Basic General Rules	
▲ From previous column	
5	Additional <b>REQUIREMENTS</b> , if so specified:
5 1	<b>FIRE RETARDANT CORE</b> shall be color tinted or otherwise documented.
5 2	<b>MOISTURE RESISTANT CORE</b> shall be color tinted or otherwise documented.
5 3	<b>WATERPROOF ADHESIVE</b> .
6 <b>PANEL LAYUP:</b>	
6 1	Shall be for interior use, unless specified otherwise.
6 2	Shall be constructed with an odd number of plies.
6 3	Requires <b>BALANCED CONSTRUCTION</b> of faces, thickness, and moisture content to produce a warp-free panel suitable for its intended use.
6 4	Requires a <b>RIGID GLUE</b> line in accordance with the <b>ADHESIVE GUIDELINES</b> within the <b>APPENDIX</b> , and: 
6 4 1	<b>DELAMINATION</b> or <b>SEPARATION</b> shall not occur.
6 5	Requires <b>CORES</b> of veneer, lumber, particleboard, MDF, or a combination thereof, however:
6 5 1	Veneer core is not allowed at cabinet door or drawer front components.
6 6	Prohibits <b>SURFACE DISTORTIONS</b> or <b>DEFECTS</b> , such as bubbling, blistering, cracking, crazing or ridges in the exposed face veneer.
6 7	Prohibits <b>TELEGRAPHING</b> that exceeds 0.004" (0.10 mm) in any 3" (76.2 mm) span, except as indicated in Section 9 for wood doors, and:
6 7 1	<b>VENEER WITH BACKER SHEET</b> shall be balanced with appropriate balance material if required.
6 8	<b>LAMINATION OVER EXISTING HPDL</b> is not permitted, unless such product and adhesive is specifically formulated by its manufacturer for such application.
7 <b>THICKNESS TOLERANCE</b> shall be as established by ANSI/HPVA HP-1 <a href="http://hpva.org">http://hpva.org</a> and equal to:	
7 1	+0/-1/32" (0 / 0.8 mm) for nominal thickness less than 1/4" (6 mm).
7 2	+0/-3/64" (0 / 1.2 mm) for nominal thickness of 1/4" (6 mm) or greater.
Continues next column ▼	

4.4.4 Basic General Rules	
▲ From previous column	
8	<b>SQUARENESS TOLERANCE</b> shall be as established by ANSI/HPVA HP-1 <a href="http://hpva.org">http://hpva.org</a> and equal to:
8 1	3/32" (2.4 mm) for panels 48" x 48" (1220 mm x 1220 mm) or greater.
8 2	1/16" (1.6 mm) for panels smaller than 48" x 48" (1220 mm x 1220 mm).
9 <b>STRAIGHTNESS TOLERANCE</b> shall be as established by ANSI/HPVA HP-1 <a href="http://hpva.org">http://hpva.org</a> and equal to:	
9 1	1/16" (1.6 mm) for edges less than 96" (2440 mm) in length.
9 2	3/32" (2.4 mm) for edges 96" (2440 mm) or greater.
10 <b>CATHEDRAL</b> type figure shall be achieved by:	
10 1	A single component in "AA" Face Grade.
10 2	The split heart method in Face Grades "A - D", and:
10 2 1	Each half of a split heart shall be subject to the minimum component width requirements for Face Grade "B."
11 If <b>ANTIMICROBIAL SURFACE</b> is required, it shall be:	
11 1	Within the United States, EPA, <a href="http://epa.gov">http://epa.gov</a> , registered for public health use.
11 2	Within Canada, Health Canada, <a href="http://hc-sc.gc.ca">http://hc-sc.gc.ca</a> , recognized as having market authorization because of its granted Drug Identification Number (DIN).



# SECTION 4

## Sheet Products

GENERAL/PRODUCT/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



# compliance requirements

4.4.5		Hardwood Material Rules		
APPLIES to the following common species:				
1	ANIGRE	HICKORY	OAK, Red & White	
	ASH	LAUAN	PECAN	
	BEECH	MAHOGANY, American	POPLAR	
	BIRCH	MAKORE	SAPELE	
	CHERRY	MAPLE	WALNUT	
2	CORE shall be manufacturer's choice.			
3	VENEER shall be of sufficient thickness so as not to permit show through of cross banding after sanding or finishing.			
4	EDGES of multi leaf faces shall appear parallel.			
5	BACKING SPECIES shall be manufacturer's choice.			
6	FIGURE is not a function of a species grade, and special requirements shall have been so specified.			
7	NATURAL allows unlimited heartwood and/or sapwood within a face.			
8	GRAIN direction shall be manufacturer's choice unless otherwise specified in the contract documents or required within Sections 6 - 12.			
9	RIFT GRAIN OAK shall allow up to twenty-five percent (25%) of the exposed surface area to contain medullary ray flake.			
10	VENEER FACE GRADE REQUIREMENTS (based on the following ANSI/HPVA HP-1 <a href="http://hpva.org">http://hpva.org</a> definitions and characteristics) shall be for:			
10 1	OPAQUE FINISH:			
10 1 1	Grade - D.	E	C	P
10 1 2	Grade - C.	E	C	P
10 1 3	Grade - B.	E	C	P
10 2	TRANSPARENT FINISH:			
10 2 1	Grade - B.	E	C	P
10 2 2	Grade - A.	E	C	P
10 2 3	Grade - AA.	E	C	P
Continues next column ▼				

4.4.5		Hardwood Material Rules		
▲ From previous column				
10	VENEER FACE GRADE REQUIREMENTS (continued)			
10 3	For PRESELECTED FLITCHES, the following characteristics are applicable only when:			
10 3 1	Design professional has determined, in advance of bid, which characteristics and/or defects are acceptable or are to be eliminated for the total face appearance.			
10 3 1 1	Yield and leaf width/length are directly related to this determination and therefore there may be waste/yield implications.			
11	VENEER FACE GRADE DESCRIPTIONS - Range from AA through D, primarily based on appearance features with fewer natural characteristics allowed in higher grades.			
11 1	<p><b>GRADE - AA</b> - Veneer shall be smooth, tight cut, and full length. When the face consists of more than one veneer component or piece, the edges shall appear parallel and be edge matched. All components of a book or slip matched face shall be from the same flitch. Rotary cut faces may be whole piece or multi piece with edge joints tight and no sharp color contrast at the joints. Species specified for natural color will allow color contrasts but shall be book matched or conform to the type of matching as specified. The components of plain sliced (flat cut) and multi piece rotary faces will be book matched unless otherwise specified with a running, balanced, or center matched arrangement. Unless otherwise specified, components in plain sliced faces will have a matching arrangement selected by the manufacturer. Plain sliced faces will consist of two or more components with no component less than 6" (152 mm) wide except for outside components, which may be less than 6" (152 mm) to allow for certain types of matching or panel edge loss. No plain sliced components will have a split heart. No full quartered cut is allowed in plain sliced faces. The width of any single component in quarter cut, rift cut faces shall not be less than 3" (76 mm) except for outside components, which may be less than 3" (76 mm) to allow for certain types of matching or panel edge trim loss.</p>			
Continues next column ▼				

# SECTION 4

## Sheet Products

GENERAL/PRODUCT/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



# compliance requirements

4.4.5 Hardwood Material Rules	
▲ From previous column	
11	<b>VENEER FACE GRADE DESCRIPTIONS</b> (continued)
11 2	<p><b>GRADE - A</b> - Veneer shall be smooth, tight cut, and full length. When the face consists of more than one veneer component or piece, the edges shall appear parallel and be edge matched. All components of a book or slip matched face shall be from the same flitch. Rotary cut faces may be whole piece or multi piece with edge joints tight; however, no sharp color contrasts are permitted at the joints, and the face will provide a good general appearance. Species specified for natural color will allow color contrasts, but shall be book matched or conform to the type of matching as specified. The components of plain sliced (flat cut) and multi piece rotary faces will be book matched, unless otherwise specified with a running, balanced, or center matched arrangement. Unless otherwise specified, components in plain sliced faces will have a matching arrangement selected by the manufacturer. Plain sliced faces will consist of two or more components with no component less than 5" (127 mm) wide except for outside components, which may be less than 5" (127 mm) to allow for certain types of matching or panel edge trim loss. Split heart is permitted if manufactured cathedral is achieved. No full quarter cut is allowed in plain sliced faces. The width of any single component in quarter cut, rift cut, or comb grain faces shall not be less than 3" (76 mm) except for outside components, which may be less than 3" (76 mm) to allow for certain types of matching or panel edge trim loss. In some species, sapwood is permitted; however, in other species, it may be permitted by agreement between buyer and seller.</p>
Continues next column ▼	

4.4.5 Hardwood Material Rules	
▲ From previous column	
11	<b>VENEER FACE GRADE DESCRIPTIONS</b> (continued)
11 3	<p><b>GRADE - B</b> - Veneer shall be smooth, tight cut, and full length as described for the various species. All components of a book or slip matched face shall be from the same flitch. Slip or book matched veneers are available if specified by the buyer. If not specified, multi piece faces will be pleasingly matched. Sharp color contrasts at the joints are not permitted. Species specified for natural color will allow color contrasts, but shall be book matched or conform to the type of matching as specified. Plain sliced faces will consist of two or more components with no component less than 4" (102 mm) wide to allow for certain types of matching or panel edge trim loss. Some full quarter cut is permitted in plain sliced faces. For some species, unlimited sapwood is allowed, and in other species, a percentage of sapwood is allowed.</p>
11 4	<p><b>GRADE - C</b> - Permits unlimited color streaks and spots and color variation. An unlimited number of small burls and pin knots are allowed with no restrictions on the size of the dark pin knot centers, as long as the diameter of pin knots does not exceed 1/4" (6.4 mm) in diameter. The size of sound and repaired knotholes and similar shaped openings cannot exceed 1/2" (9.5 mm) in diameter, with a specified number allowed based on individual species. Faces shall provide a sound face, free of open defects, with only minimal areas of rough grain.</p>
11 5	<p><b>GRADE - D</b> - Permits unlimited color streaks and spots and color variation. An unlimited number of small burls and pin knots are permitted with no restrictions on the size of dark pin knot centers, as long as the diameter of pin knots does not exceed 1/4" (6.4 mm) in diameter. The size of repaired and sound knotholes and similar shaped openings cannot exceed 3/4" (19 mm) (repaired) and 1" (25.4 mm) (sound) diameters, with a specified number based on individual species. Faces shall provide a sound face, free of open defects. The size or percentage of rough grain on the panel surface depends on the species.</p>
11 6	<p><b>OTHER SPECIES</b> - May be covered by these standards, provided the buyer and seller agree to a species grouping as a basis for the evaluation and grade of the unlisted species. It is obviously not workable to try to develop and include the individual grade requirements for every known species.</p>
Continues next column ▼	



# SECTION 4

## Sheet Products

GENERAL/PRODUCT/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



## compliance requirements

4.4.5 Hardwood Material Rules	
▲ From previous column	
11 VENEER FACE GRADE DESCRIPTIONS (continued)	
11 7	<b>SPECIALTY GRADES</b> - Applicable to veneer in which the features of greatest significance are unusual characteristics that are not covered within grades AA-D. Characteristics shall be as agreed upon between buyer and seller. Species such as Wormy Chestnut, Birds Eye Maple, and English Brown Oak, which have unusual decorative features, are considered a Speciality Grade.
11 8	<b>NOTE</b> - Variance from these standards might invalidate certain criteria and tests.
11 8 1	Example - Strong color contrasts will occur when rotary natural Birch leaves are slip matched.
12 TERMINOLOGY DEFINITIONS for use with following ANSI/HPVA HP-1 (latest edition) <a href="http://hpva.org">http://hpva.org</a> Characteristic charts:	
12 1	<b>BARK POCKET:</b> Bark around which normal wood has grown.
12 2	<b>BRASHNESS:</b> Condition of wood characterized by low resistance to shock and by abrupt failure across the grain without splintering.
12 3	<b>BURL, BLENDING:</b> A swirl, twist, or distortion in the grain of the wood which usually occurs near a knot or crotch but does not contain a knot and does not contain abrupt color variation. A blending burl is detectable at 1.8 m to 2.4 m (6 feet to 8 feet) as a swirl or roundel.
12 4	<b>BURL, CONSPICUOUS:</b> A swirl, twist, or distortion in the grain of the wood which usually occurs near a knot or crotch. A conspicuous burl is associated with abrupt color variation and/or a cluster of small dark piths caused by a cluster of adventitious buds.
12 5	<b>COMB GRAIN:</b> A quality of rift cut veneer with exceptionally straight grain and closely spaced growth increments resembling the appearance of long strands of combed hair.
12 6	<b>CROSS BAR:</b> Irregularity of grain resembling a dip in the grain running at right angles, or nearly so, to the length of the veneer.
12 7	<b>FLAKE:</b> See Fleck, Ray.
Continues next column ▼	

4.4.5 Hardwood Material Rules	
▲ From previous column	
12 TERMINOLOGY DEFINITIONS (continued)	
12 8	<b>FLECK, RAY:</b> Portion of a ray as it appears on the quartered or rift cut surface. Fleck is often a dominant appearance feature in Oak.
12 9	<b>GUM POCKETS:</b> Well defined openings between rings of annual growth, containing gum or evidence of prior gum accumulations.
12 10	<b>GUM SPOTS AND STREAKS:</b> Gum or resinous material or color spots and streaks caused by prior resin accumulations sometimes found on panel surfaces.
12 11	<b>HAIRLINE:</b> A thin, perceptible line showing at the joint of two pieces of wood.
12 12	<b>HEARTWOOD:</b> The non active or dormant center of a tree, generally distinguishable from the outer portion (sapwood) by its darker color, sometime referred to as heart.
12 13	<b>KNOT:</b> Cross section of tree branch or limb with grain usually running at right angles to that of the piece of wood in which it occurs, further defined as:
12 13 1	<b>CONSPICUOUS PIN:</b> Sound knots 6.4 mm (1/4 inch) or less in diameter containing dark centers.
12 13 2	<b>HOLES:</b> Openings produced when knots drop from the wood in which they were embedded.
12 13 3	<b>OPEN:</b> Opening produced when a portion of the wood substance of a knot has dropped out or where cross checks have occurred to produce an opening.
12 13 4	<b>SOUND TIGHT:</b> Knots that are solid across their face and fixed by growth to retain their place.
12 13 5	<b>SPIKE:</b> Knots cut from 0° to 45° to the long axis of limbs.
12 14	<b>REPAIRS:</b> A patch, shim, or filler material inserted and/or glued into veneer or a panel to achieve a sound surface.
12 15	<b>RIFT CUT:</b> A straight grain appearance achieved through the process of cutting at a slight angle to the radial on the half round stay log or through the use of veneer cut in any fashion that produces a straight grain with minimal ray fleck.
Continues next column ▼	

# SECTION 4

## Sheet Products

GENERAL/PRODUCT/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



## compliance requirements

4.4.5 Hardwood Material Rules	
▲ From previous column	
12 TERMINOLOGY DEFINITIONS (continued)	
12 16	<b>ROUGH CUT:</b> Irregular shaped areas of generally uneven corrugation on the surface of veneer, differing from the surrounding smooth veneer and occurring as the veneer is cut by the lathe or slicer.
12 17	<b>RUPTURED GRAIN:</b> A break or breaks in the grain or between springwood and summerwood caused or aggravated by excessive pressure on the wood by seasoning, manufacturing, or natural processes. Ruptured grain appears as a single or series of distinct separations in the wood such as when springwood is crushed leaving the summerwood to separate in one or more growth increments.
12 18	<b>SAPWOOD:</b> The living wood of lighter color occurring in the outer portion of a tree, sometimes referred to as sap.
12 19	<b>SLIGHT:</b> Visible on observation, but does not interfere with the overall aesthetic appearance with consideration of the applicable grade of the panel.
12 20	<b>SPLITS:</b> Separations of wood fiber running parallel to the grain.
12 21	<b>STREAKS, MINERAL:</b> Sharply contrasting elongated discolorations of the wood substance.
12 22	<b>VINE MARK:</b> Bands of irregular grain running across or diagonally to the grain which are caused by the growth of climbing vines around the tree.
12 23	<b>WORMHOLES:</b> Holes resulting from infestation of worms.
12 24	<b>WORM TRACKS:</b> Marks caused by various types of wood attacking larvae. Often appear as sound discolorations running with or across the grain in straight to wavy streaks. Sometimes referred to as "pith flecks" in certain species of Maple, Birch and other hardwoods because of a resemblance to the color of pith.
Continues next column ▼	

4.4.5 Hardwood Material Rules	
▲ From previous column	
13	<b>SUMMARY TABLES of ALLOWABLE WOOD VENEER FACE GRADE CHARACTERISTICS</b> , printed with permission from the Hardwood Plywood and Veneer Association and their ANSI/HPVA HP1 (latest edition), <a href="http://hpva.org">http://hpva.org</a> , are as follows:
13 1	Tables for <b>STAND ALONE DOOR FACES</b> are in Section 9.
13 2	Table: 4-040 - <b>ASH, BEECH, BIRCH, MAPLE, and POPLAR.</b>
13 3	Table: 4-041 - <b>MAHOGANY</b> (African or American), <b>ANIGRE, MAKORE, and SAPELE.</b>
13 4	Table: 4-042 - <b>RED and WHITE OAK.</b>
13 5	Table: 4-043 - <b>PECAN and HICKORY.</b>
13 6	Table: 4-044 - <b>WALNUT and CHERRY.</b>
13 7	The following tables are not intended to create a face grade, they are <b>INTENDED ONLY TO ESTABLISH THE ACCEPTABLE REQUIREMENTS AND/OR CHARACTERISTICS AFTER THE WOODWORK IS COMPLETED OR INSTALLED.</b>



# SECTION 4

## Sheet Products

GENERAL/PRODUCT/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



# compliance requirements

Table: 4-039 - **ASH, BEECH<sup>a</sup>, BIRCH, MAPLE, and POPLAR** (ANSI/HPVA HP- 1 (latest edition)), <http://hpva.org>

Cut		Plain Sliced (Flat Cut), Quarter Cut, Rotary Cut										
Grade Description		AA			A			B			C	D
Color and Matching		Sap	Heart	Nat.	Sap	Heart	Nat.	Sap	Heart	Nat.		
Sapwood		Yes	No	Yes	Yes	No	Yes	Yes	No	Yes	Yes	Yes
Heartwood		No	Yes	Yes	No	Yes	Yes	No	Yes	Yes	Yes	Yes
Color Streaks or Spots		Slight			Slight			Yes			Yes	Yes
Color Variation		Slight	Yes		Slight	Yes		Yes			Yes	Yes
Sharp Color Contrast at Joints		Yes if Slip, Plank, or Random matched			Yes if Slip, Plank, or Random matched			Yes if Slip, Plank, or Random matched			Yes	Yes
Type of Matching,												
Book Matched		Yes			Yes			Specify			--	--
Slip Matched		Specify			Specify			Specify			--	--
Pleasant Matched		--			--			Yes			--	--
Nominal Minimum	Plain Sliced	6" (152 mm)			5" (127 mm)			3" (76 mm)				
Width of Face	Quarter	3" (76 mm)			3" (76 mm)			3" (76 mm)			No Limit	No Limit
Components <sup>b</sup>	Rotary	6" (152 m)			5" (127 mm)			4" (102 mm)				
Natural Characteristics												
Small Conspicuous Burls & Pin Knots Combined Average Number		1 per 5 sq ft (2 per 1 m <sup>2</sup> ) 6 per 32 sq ft			1 per 3 sq ft (4 per 1 m <sup>2</sup> ) 10 per 32 sq ft			1 per 2 sq ft (6 per 1 m <sup>2</sup> ) 16 per 32 sq ft			No Limit	No Limit
Conspicuous Burls, Maximum Size		1/4" (6.4 mm)			3/8" (9.5 mm)			1/2" (12.7 mm)			No Limit	No Limit
Conspicuous Pin Knots, Average Number		No			1 per 8 sq ft (4 per 3 m <sup>2</sup> ) 4 per 32 sq ft			1 per 4 sq ft (3 per 1 m <sup>2</sup> ) 8 per 32 sq ft			No Limit	No Limit
Maximum Size, Dark Part Total					1/8" (3.2 mm) 1/4" (6.4 mm)			1/8" (3.2 mm) 1/4" (6.4 mm)				
Scattered, Sound and Repaired Knots, Combined Average Number		No			No			1 per 8 sq ft (4 per 3 m <sup>2</sup> ) 4 per 32 sq ft			1 per 4 sq ft (3 per 1 m <sup>2</sup> ) 8 per 32 sq ft	1 per 3 sq ft (4 per 1 m <sup>2</sup> ) 10 per 32 sq ft
Maximum Size - Sound								3/8" (9.5 mm)			1/2" (12.7 mm)	1" (25.4 mm)
Maximum Size - Repaired								1/8" (3.2 mm)			1/2" (12.7 mm)	3/4" (19 mm)
Average Number - Repaired								1 per 8 sq ft (4 per 3 m <sup>2</sup> )			1 per 8 sq ft (4 per 3 m <sup>2</sup> )	1 per 6 sq ft (2 per 1 m <sup>2</sup> )
Mineral Streaks		No; Maple, Slight			Slight			Slight			Yes	Yes
Bark Pockets		No			No			Few to 1/8" x 1" (3.2 mm x 25.4 mm)			Few to 1/4" x 2" (6.4 mm x 50.8 mm)	1/4" x 2" (6.4 mm x 50.8 mm)
Worm Tracks		Slight			Slight			Slight; Ash, Yes			Yes	Yes
Vine Marks		Slight			Slight			Slight			Yes	Yes
Cross Bars		Slight			Slight			Yes			Yes	Yes
Manufacturing Characteristics												
Rough Cut/Ruptured Grain		No			No			Slight			Two 8" (203 mm) dia. areas or equivalent	5% of panel
Blended Repaired Tapering Hairline Splits		Two 1/32" x 3" (0.8 mm x 76 mm) on panel ends only			Two 1/16" x 6" (1.6 mm x 152 mm)			Four 1/8" x 8" (3.2 mm x 203 mm)			Four 3/16" x 8" (4.8 mm x 203 mm)	Six 1/4" x 10" (6.4 mm x 203 mm)
Repairs		Very small blending			Small blending			Blending			Yes	Yes
Special Characteristics												
Quartered		1" in 12" (25.4 mm in 305 mm) maximum grain slope; 2-1/2" in 12" (63.5 mm in 305 mm) maximum grain sweep										
<small>Open splits, open joints, open bark pockets, or doze not allowed in above grades.  <sup>a</sup> American or European  <sup>b</sup> Outside components will be different size to allow for edge trim loss and certain types of matching.</small>												

# SECTION 4

## Sheet Products

GENERAL/PRODUCT/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



## compliance requirements

Table: 4-040 - **MAHOGANY (African or American), ANIGRE, MAKORE, and SAPELE** (ANSI/HPVA HP- 1 (latest edition)), <http://hpva.org>

Cut	Plain Sliced (Flat Cut), Quarter Cut, Rotary Cut				
Grade Description	AA	A	B	C	D
<b>Color and Matching</b>					
Sapwood	No	No	No	Yes	Yes
Heartwood	Yes	Yes	Yes	Yes	Yes
Color Streaks or Spots	Slight	Slight	Occasional	Yes	Yes
Color Variation	Slight	Slight	Moderate	Yes	Yes
Sharp Color Contrast at Joints	Yes if Slip, Plank, or Random matched	Yes if Slip, Plank, or Random matched	Yes if Slip, Plank, or Random matched	Yes	Yes
Type of Matching					
Book Matched	Yes	Yes	Specify	--	--
Slip Matched	Specify	Specify	Specify	--	--
Pleasing Matched	--	--	Yes	--	--
Nominal Minimum Width of Face Components <sup>a</sup>	Plain Sliced 6" (152 mm) Quarter 3" (76 mm) Rotary 6" (152 m)	5" (127 mm) 3" (76 mm) 5" (127 mm)	3" (76 mm) 3" (76 mm) 4" (102 mm)	No Limit	No Limit
<b>Natural Characteristics</b>					
Small Conspicuous Burls & Pin Knots, Combined Average Number	1 per 5 sq ft (2 per 1 m <sup>2</sup> ) 6 per 32 sq ft	1 per 3 sq ft (4 per 1 m <sup>2</sup> ) 10 per 32 sq ft	1 per 2 sq ft (6 per 1 m <sup>2</sup> ) 16 per 32 sq ft	No Limit	No Limit
Conspicuous Burls, Maximum Size	1/4" (6.4 mm)	3/8" (9.5 mm)	1/2" (12.7 mm)	No Limit	No Limit
Conspicuous Pin Knots, Average Number Maximum Size, Dark Part Total	No	1 per 8 sq ft (4 per 3 m <sup>2</sup> ) 4 per 32 sq ft 1/8" (3.2 mm) 1/4" (6.4 mm)	1 per 4 sq ft (3 per 1 m <sup>2</sup> ) 8 per 32 sq ft 1/8" (3.2 mm) 1/4" (6.4 mm)	No Limit	No Limit
Scattered Sound and Repaired Knots, Combined Average Number Maximum Size - Sound Maximum Size - Repaired Average Number - Repaired	No	No	1 per 8 sq ft (4 per 3 m <sup>2</sup> ) 4 per 32 sq ft 3/8" (9.5 mm) 1/8" (3.2 mm) 1 per 8 sq ft (4 per 3 m <sup>2</sup> )	1 per 4 sq ft (3 per 1 m <sup>2</sup> ) 8 per 32 sq ft 1/2" (12.7 mm) 1/2" (12.7 mm) 1 per 8 sq ft (4 per 3 m <sup>2</sup> )	1 per 3 sq ft (4 per 1 m <sup>2</sup> ) 10 per 32 sq ft 1" (25.4 mm) 3/4" (19 mm) 1 per 6 sq ft (2 per 1 m <sup>2</sup> )
Mineral Streaks	No	Slight	Occasional	Yes	Yes
Bark Pockets	No	No	Few to 1/8" x 1" (3.2 mm x 25.4 mm)	Few to 1/4" x 2" (6.4 mm x 50.8 mm)	1/4" x 2" (6.4 mm x 50.8 mm)
Worm Tracks	No	No	Slight	Few	Yes
Vine Marks	Slight	Slight	Yes	Yes	Yes
Cross Bars	Occasional	Occasional	Yes	Yes	Yes
<b>Manufacturing Characteristics</b>					
Rough Cut/Ruptured Grain	No	No	Slight	Slight	Two 8" dia. areas or equivalent
Blended Repaired Tapering Hairline Splits	Two 1/32" x 3" on (0.8 mm x 76 mm) panel ends only	Two 1/16" x 6" (1.6 mm x 152 mm)	Four 1/8" x 8" (3.2 mm x 203 mm)	Four 3/16" x 8" (4.8 mm x 203 mm)	Six 1/4" x 10" (6.4 mm x 254 mm)
Repairs	Very Small Blending	Small Blending	Blending	Yes	Yes
<b>Special Characteristics</b>					
Unfilled Worm Holes	No	No	No	1/16" (1.6 mm) max. dia.	1/16" (1.6 mm) max. dia.
Quartered	1" in 12" (25.4 mm in 305 mm) maximum grain slope; 2-1/2" in 12" (63.5 mm in 305 mm) maximum grain sweep				

<sup>a</sup> Open splits, open joints, open bark pockets, or doze not allowed in above grades.  
<sup>a</sup> Outside components will be different size to allow for edge trim loss and certain types of matching.

# SECTION 4

## Sheet Products

GENERAL/PRODUCT/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



# compliance requirements

Table: 4-041 - **RED and WHITE OAK** (ANSI/HPVA HP- 1 (latest edition) as modified by notes 'd' and 'e'), <http://hpva.org>

Cut	Plain Sliced (Flat Cut), Quarter Cut, Rotary Cut							
	AA		A		B		C	D
Grade Description	Red	White	Red	White	Red	White		
<b>Color and Matching</b>								
Sapwood	No		5% <sup>a</sup>	Yes <sup>a</sup>	10-20% <sup>b</sup>	Yes	Yes	Yes
Heartwood	Yes		Yes		Yes		Yes	Yes
Color Streaks or Spots	Yes		Yes		Yes		Yes	Yes
Color Variation	Slight		Slight		Yes		Yes	Yes
Sharp Color Contrast at Joints	Yes if Slip, Plank, or Random matched		Yes if Slip, Plank, or Random matched		Yes if Slip, Plank, or Random matched		Yes	Yes
Type of Matching: Book Matched	Yes		Yes		Specify		--	--
Slip Matched	Specify		Specify		Specify		--	--
Pleasant Matched	--		--		Yes		--	--
Nominal Minimum	Plain-Sliced	6" (152 mm)	5" (127 mm)		3" (76 mm)		No Limit	No Limit
Width of Face	Quarter	3" (76 mm)	3" (76 mm)		3" (76 mm)			
Components <sup>c</sup>	Rotary	6" (152 mm)	5" (127 mm)		4" (102 mm)			
<b>Natural Characteristics</b>								
Small Conspicuous Burls & Pin Knots, Combined Average Number	1 per 4 sq ft (3 per 1 m <sup>2</sup> ) 6 per 32 sq ft		1 per 2-2/3 sq ft (4 per 1 m <sup>2</sup> ) 12 per 32 sq ft		1 per 1-1/3 sq ft (8 per 1 m <sup>2</sup> ) 24 per 32 sq ft		No Limit	No Limit
Conspicuous Burls, Maximum Size	1/4" (6.4 mm)		3/8" (9.5 mm)		1/2" (12.7 mm)		No Limit	No Limit
Conspicuous Pin Knots, Average Number	No		1 per 3 sq ft (4 per 1 m <sup>2</sup> ) 10 per 32 sq ft		1 per 2 sq ft (6 per 1 m <sup>2</sup> ) 16 per 32 sq ft		No Limit	No Limit
Maximum Size, Dark Part			1/8" (3.2 mm)		1/8" (3.2 mm)			
Total			1/4" (6.4 mm)		1/4" (6.4 mm)			
Scattered Sound and Repaired Knots, Combined Average Number	No		No		1 per 8 sq ft (4 per 3 m <sup>2</sup> ) 4 per 32 sq ft		1 per 4 sq ft (3 per 1 m <sup>2</sup> ) 8 per 32 sq ft	1 per 3 sq ft (4 per 1 m <sup>2</sup> ) 10 per 32 sq ft
Maximum Size - Sound					3/8" (9.5 mm)		1/2" (12.7 mm)	1" (25.4 mm)
Maximum Size - Repaired					1/8" (3.2 mm)		1/2" (12.7 mm)	3/4" (19 mm)
Average Number - Repaired					1 per 8 sq ft (4 per 3 m <sup>2</sup> )		1 per 8 sq ft (4 per 3 m <sup>2</sup> )	1 per 6 sq ft (2 per 1 m <sup>2</sup> )
Mineral Streaks	No		Slight, Blending		Few to 12" (305 mm)		Yes	Yes
Bark Pockets	No		No		Few to 1/8" x 1" (3.2 mm x 25.4 mm)		Few to 1/4" x 2" (6.4 mm x 50.8 mm)	1/4" x 2" (6.4 mm x 50.8 mm)
Worm Tracks	No		No		Slight		Few	Yes
Vine Marks	No		Slight		Yes		Yes	Yes
Cross Bars	Slight		Slight		Yes		Yes	Yes
<b>Manufacturing Characteristics</b>								
Rough Cut/Ruptured Grain	No		No		Slight		Slight	Two 8" (203 mm) dia. areas or equivalent
Blended Repaired Tapering Hairline Splits	Two 1/32" x 3" on (0.8 mm x 76 mm) panel ends only		Two 1/16" x 6" (1.6 mm x 152 mm)		Four 1/8" x 8" (3.2 mm x 203 mm)		Four 3/16" x 8" (4.8 mm x 203 mm)	Six 1/4" x 10" (6.4 mm x 254 mm)
Repairs	Very Small Blending		Small Blending		Blending		Yes	Yes
<b>Special Characteristics</b>								
Ray Fleck <sup>d</sup>	Slight, Blending		Slight, Blending		Slight, Blending		Yes	Yes
Rift and Comb Grain	Rift permits 1" in 12" (25.4 mm in 305 mm) max. grain slope, 2-1/2" in 12" (63.5 mm in 305 mm) max. grain sweep, fleck not to exceed 3/8" (9.5 mm) in width. Comb permits 1/2" in 12" (12.7 mm in 305 mm) max. grain slope, 1/2" in 12" (12.7 mm in 305 mm) max. grain sweep, fleck not to exceed 3/32" (2.4 mm) in width.							
Unfilled worm holes, open splits, open joints, open bark pockets, or doze not allowed in above grades. <sup>a</sup> Sap allowed in rotary only unless otherwise specified. <sup>b</sup> 10% sap allowed in rift, comb, and plain-sliced; 20% sap allowed in rotary. <sup>c</sup> Outside components will be different size to allow for edge trim loss and certain types of matching. <sup>d</sup> Unless otherwise specified, quartered permits unlimited fleck.								

# SECTION 4

## Sheet Products

GENERAL/PRODUCT/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



## compliance requirements

Table: 4-042 - **PECAN and HICKORY** (ANSI/HPVA HP- 1 (latest edition)), <http://hpva.org>

Cut	Plain-Sliced (Flat Cut), Quarter-Cut, Rotary Cut				
Grade Description	AA	A	B	C	D
<b>Color and Matching</b>					
Sapwood	Yes	Yes	Yes	Yes	Yes
Heartwood	Yes	Yes	Yes	Yes	Yes
Color Streaks or Spots	Yes	Yes	Yes	Yes	Yes
Color Variation	Yes	Yes	Yes	Yes	Yes
Sharp Color Contrast at Joints	Yes if Slip, Plank, or Random matched	Yes if Slip, Plank, or Random matched	Yes if Slip, Plank, or Random matched	Yes	Yes
Type of Matching					
Book-Matched	Yes	Yes	Specify	--	--
Slip-Matched	Specify	Specify	Specify	--	--
Pleasant-Matched	--	--	Yes	--	--
Nominal Minimum Plain-S. Width of Quarter Face Components <sup>a</sup> Rotary	6" (152 mm) 3" (76 mm) 6" (152 mm)	5" (127 mm) 3" (76 mm) 5" (127 mm)	3" (76 mm) 3" (76 mm) 4" (102 mm)	No Limit	No Limit
<b>Natural Characteristics</b>					
Small Conspicuous Burls & Pin Knots- Combined Avg. Number	1 per 1 sq ft (11 per 1 m <sup>2</sup> ) 32 per 32 sq ft	2 per 1 sq ft (22 per 1 m <sup>2</sup> ) 64 per 32 sq ft	No Limit	No Limit	No Limit
Conspicuous Burls - Max. Size	1/4" (6.4 mm)	3/8" (9.5 mm)	1/2" (12.7 mm)	No Limit	No Limit
Conspicuous Pin Knots <sup>b</sup> Avg. Number Max. Size: Dark Part Total	1 per 2 sq ft (6 per 1 m <sup>2</sup> ) 16 per 32 sq ft 1/8" (3.2 mm) 1/4" (6.4 mm)	2 per 1 sq ft (22 per 1 m <sup>2</sup> ) 64 per 32 sq ft 1/8" (3.2 mm) 1/4" (6.4 mm)	No Limit 1/8" (3.2 mm) 1/4" (6.4 mm)	No Limit	No Limit
Scattered Sound and Repaired Knots-Combined Avg. Number Max. Size - Sound Max. Size - Repaired Avg. No. - Repaired	No	No	1 per 8 sq ft (4 per 3 m <sup>2</sup> ) 4 per 32 sq ft 3/8" (9.5 mm) 1/8" (3.2 mm) 1 per 8 sq ft (4 per 3 m <sup>2</sup> )	1 per 3 sq ft (4 per 1 m <sup>2</sup> ) 10 per 32 sq ft 1/2" (12.7 mm) 1/2" (12.7 mm) 1 per 8 sq ft (2 per 1 m <sup>2</sup> )	1 per 3 sq ft (6 per 1 m <sup>2</sup> ) 10 per 32 sq ft 1" (25.4 mm) 3/4" (19 mm) 1 per 6 sq ft (3 per 1 m <sup>2</sup> )
Mineral Streaks	Slight	Slight	Yes	Yes	Yes
Bark Pockets	No	Small, Occasional	Few to 1/4" x 2" (6.4 mm x 50.8 mm)	Few to 3/8" x 4" (9.5 mm x 102 mm)	To 1/2" wide (12.7 mm)
Worm Tracks	No	Slight	Few	Yes	Yes
Vine Marks	Slight	Occasional	Yes	Yes	Yes
Cross Bars	Slight	Occasional	Yes	Yes	Yes
<b>Manufacturing Characteristics</b>					
Rough Cut/Ruptured Grain	No	No	Slight	Two 8" (203 mm) dia. areas or equivalent	5% of panel
Blended Repaired Tapering Hairline Splits	Two 1/32" x 3" on (0.8 mm x 76 mm) panel ends only	Two 1/16" x 6" (1.6 mm x 152 mm)	Four 1/8" x 8" (3.2 mm x 203 mm)	Four 3/16" x 8" (4.8 mm x 203 mm)	Six 1/4" x 10" (6.4 mm x 254 mm)
Repairs	Very Small Blending	Small Blending	Blending	Yes	Yes
<b>Special Characteristics</b>					
Bird Peck <sup>c</sup>	No	Slight	Yes	Yes	Yes
Knife Marks	Knife marks might occur in these dense species.				
Quartered	1" in 12" (25.4 mm in 305 mm) maximum grain slope; 2-1/2" in 12" (63.5 mm in 305 mm) maximum grain sweep				
Unfilled worm holes, open splits, open joints, open bark pockets, or doze are not allowed in above grades.					
<sup>a</sup> Outside components will be a different size to allow for edge trim loss and certain types of matching.					
<sup>b</sup> For Pecan and Hickory, conspicuous pin knots mean sound knots 1/4" (6.4 mm) or less in diameter with dark centers larger than 1/16" (1.6 mm). Blending pin knots are sound knots 1/4" (6.4 mm) or less in diameter with dark centers 1/16" (1.6 mm) or less and are allowed in all Grades.					
<sup>c</sup> To achieve a more rustic appearance, bird peck shall be specified.					

# SECTION 4

## Sheet Products

GENERAL/PRODUCT/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



## compliance requirements

Table: 4-043 - **WALNUT** and **CHERRY** (ANSI/HPVA HP- 1 (latest edition)), <http://hpva.org>

Cut		Plain-Sliced (Flat Cut), Quarter-Cut, Rotary Cut				
Grade Description		AA	A	B	C	D
<b>Color and Matching</b>						
Sapwood <sup>a</sup>		No	No <sup>a</sup>	No <sup>a</sup>	Yes	Yes
Heartwood		Yes	Yes	Yes	Yes	Yes
Color Streaks or Spots		Slight	Slight	Yes	Yes	Yes
Color Variation		Slight	Slight	Yes	Yes	Yes
Sharp Color Contrast at Joints		Yes if Slip, Plank, or Random Match	Yes if Slip, Plank, or Random Match	Yes if Slip, Plank, or Random Match	Yes	Yes
Type of Matching:						
Book-Matched		Yes	Yes	Specify	--	--
Slip-Matched		Specify	Specify	Specify	--	--
Pleasant-Matched		--	--	Yes	--	--
Nominal Minimum	Plain Sliced	6" (152 mm)	5" (127 mm)	3" (76 mm)		
Width of Face	Quarter	3" (76 mm)	3" (76 mm)	3" (76 mm)	No Limit	No Limit
Components: <sup>b</sup>	Rotary	6" (152 mm)	5" (127 mm)	4" (102 mm)		
<b>Natural Characteristics</b>						
Small Conspicuous Burls & Pin Knots, Combined Average Number		1 per 4 sq ft (3 per 1 m <sup>2</sup> ) 8 per 32 sq ft	1 per 1-1/3 sq ft (8 per 1 m <sup>2</sup> ) 24 per 32 sq ft	2 per 1 sq ft (22 per 1 m <sup>2</sup> ) 64 per 32 sq ft	No Limit	No Limit
Conspicuous Burls, Maximum Size		1/4" (6.4 mm)	3/8" (9.5 mm)	1/2" (12.7 mm)	No Limit	No Limit
Conspicuous Pin Knots, <sup>c</sup>					No Limit	No Limit
Average Number		1 per 5 sq ft (3 per 1 m <sup>2</sup> ) 6 per 32 sq ft	1 per 2 sq ft (6 per 1 m <sup>2</sup> ) 16 per 32 sq ft	1 per 1 sq ft (11 per 1 m <sup>2</sup> ) 32 per 32 sq ft		
Maximum Size, Dark Part		1/8" (3.2 mm)	1/8" (3.2 mm)	1/8" (3.2 mm)		
Total		1/4" (6.4 mm)	1/4" (6.4 mm)	1/4" (6.4 mm)		
Scattered Sound and Repaired Knots, Combined Average Number				1 per 8 sq ft (4 per 3 m <sup>2</sup> ) 4 per 32 sq ft	1 per 4 sq ft (3 per 1 m <sup>2</sup> ) 8 per 32 sq ft	1 per 3 sq ft (4 per 1 m <sup>2</sup> ) 10 per 32 sq ft
Maximum Size - Sound		No	No	3/8" (9.5 mm)	1/2" (12.7 mm)	1" (25.4 mm)
Maximum Size - Repaired				1/8" (3.2 mm)	1/2" (12.7 mm)	3/4" (19 mm)
Average Number - Repaired				1 per 8 sq ft (4 per 3 m <sup>2</sup> )	1 per 8 sq ft (4 per 3 m <sup>2</sup> )	1 per 6 sq ft (2 per 1 m <sup>2</sup> )
Mineral Streaks		Slight	Slight	Yes	Yes	Yes
Bark Pockets		No	No	Few to 1/8" x 1" (3.2 mm x 25.4 mm)	Few to 1/4" x 2" (6.4 mm x 50.8 mm)	1/4" x 2" (6.4 mm x 50.8 mm)
Worm Tracks		No	No	Slight	Few	Yes
Vine Marks		Slight	Occasional	Yes	Yes	Yes
Cross Bars		Slight	Occasional	Yes	Yes	Yes
<b>Manufacturing Characteristics</b>						
Rough Cut/Ruptured Grain		No	No	Slight	Slight	Two 8" (203 mm) dia. areas or equivalent
Blended Repaired Tapering Hairline Splits		Two 1/32" x 3" (0.8 mm x 76 mm) on panel ends only	Two 1/16" x 6" (1.6 mm x 152 mm)	Four 1/8" x 8" (3.2 mm x 203 mm)	Four 3/16" x 8" (4.8 mm x 203 mm)	Six 1/4" x 10" (6.4 mm x 254 mm)
Repairs		Very Small Blending	Small Blending	Blending	Yes	Yes
<b>Special Characteristics</b>						
Gum Spots and Streaks, Cherry only		Occasional Spots			Gum Spots and Streaks in Cherry	
Quartered		1" in 12" (25.4 mm in 305 mm) maximum grain slope; 2-1/2" in 12" (63.5 mm in 305 mm) maximum grain sweep				
Unfilled worm holes, open splits, open joints, open bark pockets, or doze are not allowed in above grades.						
<sup>a</sup> Sapwood is allowed in Grades A and B; however, the percentage shall be agreed upon between buyer and seller.						
<sup>b</sup> Outside components will be a different size to allow for edge trim loss and certain types of matching.						
<sup>c</sup> For Walnut and Cherry, conspicuous pin knots mean sound knots 1/4" (6.4 mm) or less in diameter with dark centers larger than 1/16" (1.6 mm). Blending pin knots are sound knots 1/4" (6.4 mm) or less in diameter with dark centers 1/16" (1.6 mm) or less and are allowed in all Grades.						

# SECTION 4

## Sheet Products

GENERAL/PRODUCT/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



## compliance requirements

4.4.6		Softwood Material Rules		
1	Applies only to the following species: <b>DOUGLAS FIR</b> , <b>REDWOOD</b> , <b>WESTERN RED CEDAR</b> , and <b>WHITE PINE</b> .			
2	<b>TYPE I ADHESIVE</b> is required at non climatic controlled interior or exterior applications.			
3	<b>CORE</b> shall be manufacturer's choice, within the provisions of these standards.			
4	<b>VERTICAL GRAIN</b> shall have over 90% of the visible face, a minimum average of:			
4 1	5 annual growth rings per 1" (24.4 mm) in width.	<b>E</b>	<b>C</b>	<b>P</b>
4 2	10 annual growth rings per 1" (24.4 mm) in width.	<b>E</b>	<b>C</b>	<b>P</b>
4 3	15 annual growth rings per 1" (24.4 mm) in width.	<b>E</b>	<b>C</b>	<b>P</b>
5	For <b>TRANSPARENT FINISH</b> , boat, router, and/or sled patches shall be limited to 12 in any 4' x 8' (1239 mm x 2438 mm) panel and proportionately reduced for smaller size panels.	<b>E</b>	<b>C</b>	<b>P</b>
6	<b>FACE GRADE REQUIREMENTS</b> (based on the following Voluntary Product Standard - PS1 (latest edition) and ANSI/HPVA HP-1 (latest edition), <a href="http://hpva.org">http://hpva.org</a> , definitions and characteristics as indicated) for:			
6 1	<b>WESTERN RED CEDAR</b> and <b>WHITE PINE</b> , rotary, and knotty sliced (ANSI/HPVA HP-1 (latest edition)), <a href="http://hpva.org">http://hpva.org</a> , are as follows:			
6 1 1	Grade - B.	<b>E</b>	<b>C</b>	<b>P</b>
6 1 2	Grade - A.	<b>E</b>	<b>C</b>	<b>P</b>
6 2	<b>DOUGLAS FIR</b> and <b>REDWOOD</b> , vertical grain sliced (ANSI/HPVA HP-1 (latest edition)), <a href="http://hpva.org">http://hpva.org</a> , are as follows:			
6 2 1	Grade - A.			
6 3	<b>DOUGLAS FIR</b> , rotary sliced (Voluntary Product Standard - PS1 (latest edition)), <a href="http://nist.gov">http://nist.gov</a> , for:			
6 3 1	<b>OPAQUE FINISH</b> are:			
6 3 1 1	Grade - B.	<b>E</b>	<b>C</b>	<b>P</b>
6 3 1 2	Grade - A.	<b>E</b>	<b>C</b>	<b>P</b>
<b>Continues next column ▼</b>				

4.4.6		Softwood Material Rules		
<b>▲ From previous column</b>				
6	<b>FACE GRADE REQUIREMENTS</b> (continued)			
6 3	<b>DOUGLAS FIR</b> (continued)			
6 3 2	<b>TRANSPARENT FINISH</b> are:			
6 3 2 1	Grade - A.			
7	<b>SUMMARY TABLES of ALLOWABLE WOOD VENEER FACE GRADE CHARACTERISTICS</b> are as follows:			
7 1	<i>Table: 4-045 - WESTERN RED CEDAR, WHITE PINE, and VERTICAL GRAIN DOUGLAS FIR/REDWOOD</i> , was:			
7 1 1	Reprinted with permission from the Hardwood Plywood Veneer Association and their ANSI/HPVA HP-1 (latest edition), <a href="http://hpva.org">http://hpva.org</a> .			
7 2	<i>Table: 4-046 - DOUGLAS FIR</i> , was:			
7 2 1	Reprinted with permission from the Voluntary Product Standard - PS1 (latest edition), <a href="http://nist.gov">http://nist.gov</a> .			
<b>Continues next column ▼</b>				



# SECTION 4

## Sheet Products

GENERAL/PRODUCT/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



## compliance requirements

Table: 4-044 - **WESTERN RED CEDAR, WHITE PINE, and VERTICAL GRAIN DOUGLAS FIR/REDWOOD** (ANSI/HPVA HP-1 (latest edition)), <http://hpva.org>

Species	Western Red Cedar		White Pine		Douglas Fir	Redwood
Cut	Plain Sliced (Flat Cut), Quarter Cut, Rotary Cut				Sliced Vertical Grain	
Grade Description	A	B	A	B	A	A
<b>Color and Matching</b>						
Sapwood	Yes				Limited - No Bright Sapwood	Yes
Heartwood <sup>a</sup>	Yes				Yes <sup>a</sup>	
Color Streaks or Spots	Slight	Yes	Slight	Yes	No	No
Color Variation	No	Slight	No	Yes	Slight	Slight
Stain, Blue or Brown	No	Slight	No	Slight	No	No
<b>Type of Matching</b>						
Book Match	Not Applicable				Yes - Matched for color and grain at the joints	
Random Match	Yes, for pleasing appearance				Not Applicable	
Slip Match	Not Applicable				Yes, for color	
End Match	Specify - Not readily available				Specify - Not readily available	
<b>Natural Characteristics</b>						
Burls	Yes				Small	
Pin Knots	Yes				No	Yes
Sound Knots, maximum size	2" (50.8 mm)		3-1/2" (89 mm)		No	
Spike Knots, maximum size	2" (50.8 mm)	3-1/2" (89 mm)	2" (50.8 mm)	3-1/2" (89 mm)	No	
Repaired Knot Holes, maximum size	3/4" (19 mm)	1-1/2" (38 mm)	3/4" (19 mm)	1-1/2" (38 mm)	No	
Pitch Streaks	Small				Small	No
Pitch Pockets	Few to 1/8" x 1" (3.2 mm x 25.4 mm)	Few to 1/8" x 2" (3.2 mm x 50.8 mm)	Few to 1/8" x 1" (3.2 mm x 25.4 mm)	Few to 1/8" x 2" (3.2 mm x 50.8 mm)	No	
Crow's Foot	Slight	Occasional	Slight	Yes	No	
<b>Manufacturing Characteristics</b>						
Rough Cut	No	Slight	No	Slight	No	
Blended, Repaired, Tapering, Hairline Splits	Yes				Yes	
Repairs	Blending				Blending	
<b>Special Characteristics</b>						
Cross Bar	Not Applicable				No	

Unfilled worm holes, open splits, open joints, or doze are not allowed in above Grades.  
<sup>a</sup> Heartwood must have 6 or more annual rings per 1" (25.4 mm).

# SECTION 4

## Sheet Products

GENERAL/PRODUCT/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



## compliance requirements

Table: 4-045 - **ROTARY CUT DOUGLAS FIR** (Voluntary Product Standard - PS1 (latest edition)), <http://nist.gov>

Species	Douglas Fir		
Cut	Rotary Cut		
Grade Description	N	A	B
<b>Color and Matching</b>			
Sapwood	Yes - 100%	Yes	Yes
Heartwood	Yes - 100%	Yes	Yes
Color Streaks or Spots	No	Yes	Yes
Color Variation	Well Matched	Yes	Yes
Stain	No	Yes	Yes
<b>Type of Matching</b>			
Rotary Sliced	Yes		
<b>Natural Characteristics</b>			
Chipped or Depressed Areas	Less than 1/8" x 1/4" (3.2 mm x 6.4 mm)	Less than 1/2" x 2" (12.7 mm x 50.8 mm)	Less than 1/2" x 2" (12.7 mm x 50.8 mm)
Cracks or Checks	Less than 1/32" (0.8 mm) wide	Less than 3/16" (4.8 mm) wide	Less than 3/16" (4.8 mm) wide
Knots, tight	No	No	Yes, maximum 1" (25.4 mm) dia.
Pitch Streaks	Average 3/8" (9.5 mm) wide and blended in color with wood	Average 3/8" (9.5 mm) wide and blended in color with wood	Average 1" (25.4 mm) wide and blended in color with wood
Pitch Pockets	No	No	No
Splits	Repaired - less than 1/16" x 2" (1.6 mm x 50.8 mm)	Repaired - less than 1-1/4" (31.8 mm) x unlimited	Open - less than 1/32" (0.8 mm)
Worm or borer holes	No	No	Yes
<b>Manufacturing Characteristics</b>			
Rough Cut	No	No	Yes, maximum 5% of face
Repairs	Maximum 6, well matched	Maximum 18, excluding shims	Unlimited
Patches	Maximum 3 "Router Patches" 1" x 3-1/2" (25.4 mm x 88.9 mm)	Boat, Router, or Sled, maximum 2-1/4" x 4-1/2" (57.2 mm x 114 mm)	Maximum 4" (102 mm) wide
Shims	Maximum 3/16" x 12" (4.8 mm x 305 mm)	Yes	Yes

# SECTION 4

## Sheet Products

GENERAL/PRODUCT/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



# compliance requirements

4.4.7 HPDL Material Rules	
<p><b>SHALL BE CONSTRUCTED</b> (in conformance with NEMA LD3 (latest edition)) <a href="http://nema.org">http://nema.org</a> of multiple layers of phenolic resin saturated kraft paper in combination with a layer of decorative melamine saturated paper, fused together under heat and pressure with the following minimum performance properties, and:</p>	
1	Laminate types are abbreviated as "HGS/L" and "VGS/L" for horizontal and vertical general purpose; "HGP" and "VGP" for post-forming; "HGF" for fire rated, "CLS" for cabinet liner; and "BKL" for backer in accordance with latest NEMA usage. See Table below:
Continues next column ▼	

4.4.7 HPDL Material Rules	
▲ From previous column	
2	CORE shall be manufacturer's choice, within the provisions of these standards.
3 If FLAME SPREAD required, it shall:	
3 1	Be CLASS A.
3 2	Have minimum 0.028" (0.71 mm) thick BACKING SHEET.
3 3	Be BONDED with a Class A, rigid set adhesive.
4 Shall be within the THICKNESS range indicated below in Table 4-047:	

Table: 4-046 - HPDL TYPES and MINIMUM PERFORMANCE REQUIREMENTS

	HGS	HGL	VGS	VGL	HGP	VGP	HGF	CLS	BKL
Nominal thickness inch / (mm)	0.048" (1.2)	0.039" (1.0)	0.028" (0.7)	0.020" (0.5)	0.039" (1.0)	0.028" (0.7)	0.048" (1.2)	0.020" (0.5)	0.020" (0.5)
Thickness tolerance ± inch / (mm)	0.005" (0.12)	0.005" (0.12)	0.004" (0.10)	0.004" (0.10)	0.005" (0.12)	0.004" (0.10)	0.005" (0.12)	0.004" (0.10)	0.004" (0.10)
Wear (cycles, min.)	400	400	400	400	400	400	400	400	n/a
% Dim change (cross-direction)	0.9	1.0	1.2	1.3	1.4	1.4	0.9	2.0	n/a
Stain (variety of agents)	No effect 1-10 Moderate effect 11-15							Moderate effect 1-15	n/a
Cleanability (cycles, maximum)	20								n/a
Light	Slight effect							Moderate effect	n/a
High temperature	Slight effect							Moderate effect	n/a
Radiant heat (seconds, minimum)	125	100	80	60	100	80	75	n/a	n/a
Boiling water	No effect				Slight effect		No effect	Moderate effect	n/a
Impact (inches, min.)	50	35	20	15	30	20	45	10	n/a

Test procedures and minimum requirements shall comply with NEMA-LD3 (latest edition), <http://nema.org>, for HPDL.

### DIMENSIONAL BEHAVIOR OF HPDL

Similar to that of wood; when humidity varies, the width of a laminate (cross-direction) undergoes greater dimensional changes than the length by a ratio of nearly two to one.




Figure: 4-047

# SECTION 4

## Sheet Products

GENERAL/**PRODUCT**/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



## compliance requirements

4.4.8 LPDL Material Rules	
Shall be melamine, polyester, or foil resin impregnated paper thermally fused under pressure to an approved core, conforming to the following minimum performance properties taken in part from NEMA LD3 (latest edition), <a href="http://nema.org">http://nema.org</a> .	
<b>PROPERTY</b>	<b>MINIMUM PERFORMANCE</b>
Wear	Solid Color, 400 Cycles Wood Grain, 125 Cycles
1 Scuff	No Effect
Stain	No Effect on Agents 1-23 Moderate on Agents 24-29
Cleanability	No Effect (Cleaned in 20 or Fewer Strokes)
Light	Slight
High Temperature	Slight
Radiant Heat	No Effect (After 60 Seconds)
Boiling Water	No Effect
Impact	15" (380 mm) Without Fracture
2 <b>CORE</b> shall be manufacturer's choice, within the provisions of these standards.	
3 Shall have <b>BALANCE SHEET</b> .	

4.4.9 Vinyl Film Material Rules		
1 Shall be a minimum of 2 mils in <b>THICKNESS</b> .		
2 <b>CORE</b> shall be manufacturer's choice, within the provisions of these standards.		
3 Shall be opaque or reverse printed.		
Shall conform to the following average property requirements:		
<b>PROPERTY</b>	<b>VALUE</b>	<b>TEST PROCEDURE</b>
Mil Thickness	2 Minimum	Caliper Gauge
Light Stability	300 hrs with no change	ASTM-E-42-64
Flame Retardance	Self Extinguishing (free film)	ASTM E-82-67
4 Gloss Level	10-45	Gardner Glossmeter
Abrasion Resistance	Opaque 25-60 10	MG loss - 1000 Cyc., CS
	Reverse Prints 30-45 Reverse Prints 6000-11000	Cycles to Print Failure,
CS 17		
Shall not have <b>SURFACE APPEARANCE</b> affected when exposed to the following agents:		
Water	Coffee	Olive Oil
5 Beet Juice	Vinegar	Alcohol
Mustard	Shoe Polish	Mercurochrome
Washable Inks	Crayon	Tea
Household Detergents and Soaps		

4.4.10 MDO Material Rules	
1 Shall be (in conformance with Voluntary Product Standard - PS1 (latest edition)), <a href="http://nist.gov">http://nist.gov</a> , a thermosetting phenolic resin impregnated cellulose fiber sheet or sheets containing not less than 34% phenolic resin after pressing.	
2 <b>CORE</b> shall be manufacturer's choice, within the provisions of these standards.	
3 Shall have <b>BALANCE SHEET</b> .	



# SECTION 4

## Sheet Products

GENERAL/PRODUCT/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



# compliance requirements

4.4.11 HDO Material Rules	
1	Shall be (in conformance with Voluntary Product Standard - PS1 (latest edition)), <a href="http://nist.gov">http://nist.gov</a> , a thermosetting phenolic resin impregnated cellulose fiber sheet or sheets, not less than 0.012" (0.30 mm) in thickness after pressing.
2	Shall be allowed in lieu of paint grade wood veneer for opaque finish.
3	<b>CORE</b> shall be manufacturer's choice, within the provisions of these standards.
4	Shall have <b>BALANCE SHEET</b> .

4.4.12 Hardboard Material Rules																															
1	Shall be (in conformance with CAP/ANSI A135.4 (latest edition)), <a href="http://compositepanel.org">http://compositepanel.org</a> , a panel manufactured of interfelted lignocellulosic fibers, consolidated under heat and pressure to a density of 31 lb/ft <sup>3</sup> or greater with the following minimum performance properties based on 1/4" (6.4 mm) thickness, as follows for:																														
1 1	<b>STANDARD GRADE:</b>																														
1 1 1	<table border="1"> <thead> <tr> <th>PROPERTY PERFORMANCE</th> <th></th> <th>E</th> <th>C</th> <th>P</th> </tr> </thead> <tbody> <tr> <td>Water Absorption</td> <td>25% Maximum</td> <td></td> <td></td> <td></td> </tr> <tr> <td>Thickness Swelling</td> <td>20% Maximum</td> <td>E</td> <td>C</td> <td>P</td> </tr> <tr> <td>Modulus of Rupture</td> <td>4500 psi</td> <td></td> <td></td> <td></td> </tr> <tr> <td>Tensile Strength - Parallel</td> <td>2200 psi</td> <td></td> <td></td> <td></td> </tr> <tr> <td>Tensile Strength - Perpendicular</td> <td>90 psi</td> <td></td> <td></td> <td></td> </tr> </tbody> </table>	PROPERTY PERFORMANCE		E	C	P	Water Absorption	25% Maximum				Thickness Swelling	20% Maximum	E	C	P	Modulus of Rupture	4500 psi				Tensile Strength - Parallel	2200 psi				Tensile Strength - Perpendicular	90 psi			
PROPERTY PERFORMANCE		E	C	P																											
Water Absorption	25% Maximum																														
Thickness Swelling	20% Maximum	E	C	P																											
Modulus of Rupture	4500 psi																														
Tensile Strength - Parallel	2200 psi																														
Tensile Strength - Perpendicular	90 psi																														
1 2	<b>TEMPERED GRADE:</b>																														
1 2 1	<table border="1"> <thead> <tr> <th>PROPERTY PERFORMANCE</th> <th></th> <th>E</th> <th>C</th> <th>P</th> </tr> </thead> <tbody> <tr> <td>Water Absorption</td> <td>20% Maximum</td> <td></td> <td></td> <td></td> </tr> <tr> <td>Thickness Swelling</td> <td>15% Maximum</td> <td>E</td> <td>C</td> <td>P</td> </tr> <tr> <td>Modulus of Rupture</td> <td>6000 psi</td> <td></td> <td></td> <td></td> </tr> <tr> <td>Tensile Strength - Parallel</td> <td>3000 psi</td> <td></td> <td></td> <td></td> </tr> <tr> <td>Tensile Strength - Perpendicular</td> <td>130 psi</td> <td></td> <td></td> <td></td> </tr> </tbody> </table>	PROPERTY PERFORMANCE		E	C	P	Water Absorption	20% Maximum				Thickness Swelling	15% Maximum	E	C	P	Modulus of Rupture	6000 psi				Tensile Strength - Parallel	3000 psi				Tensile Strength - Perpendicular	130 psi			
PROPERTY PERFORMANCE		E	C	P																											
Water Absorption	20% Maximum																														
Thickness Swelling	15% Maximum	E	C	P																											
Modulus of Rupture	6000 psi																														
Tensile Strength - Parallel	3000 psi																														
Tensile Strength - Perpendicular	130 psi																														

4.4.13 Particleboard Material Rules									
1	Shall be (in conformance with ANSI A208.1 (latest edition) as published by the Composite Panel Association, <a href="http://compositepanel.org">http://compositepanel.org</a> ) a generic term for a composite panel primarily composed of cellulosic materials (usually wood), generally in the form of discrete pieces or particles, as distinguished from fibers, bonded together with a bonding system, and which may contain additives to a density between 40-50 lb/ft <sup>3</sup> (640-800 kg/m <sup>3</sup> ), requiring:								
1 1	<b>GRADE M2</b> or better with the following minimum properties:								
1 1 1	<table border="1"> <thead> <tr> <th>PROPERTY</th> <th>VALUE</th> </tr> </thead> <tbody> <tr> <td>Thickness Swelling</td> <td>5.5% Maximum</td> </tr> <tr> <td>Modulus of Rupture (M-2)</td> <td>1885 psi</td> </tr> <tr> <td>Modulus of Rupture (M-3)</td> <td>2393 psi</td> </tr> </tbody> </table>	PROPERTY	VALUE	Thickness Swelling	5.5% Maximum	Modulus of Rupture (M-2)	1885 psi	Modulus of Rupture (M-3)	2393 psi
PROPERTY	VALUE								
Thickness Swelling	5.5% Maximum								
Modulus of Rupture (M-2)	1885 psi								
Modulus of Rupture (M-3)	2393 psi								
1 2	<b>MOISTURE RESISTANT</b> particleboard shall not exceed a maximum 5.5% thickness swell after 24 hour submersion in accordance with Section 24 Linear Expansion with Change in Moisture Content and notes 8 - 50 of ASTM D120-37-12 as published by ASTM International, <a href="http://astm.org">http://astm.org</a> .								

4.4.14 Medium Density Fiberboard (MDF) Material Rules									
1	Shall be (in conformance with ANSI A208.2 (latest edition) as published by the Composite Panel Association, <a href="http://compositepanel.org">http://compositepanel.org</a> ) a panel composed of cellulosic fibers and a bonding system cured under heat and pressure. MDF density is typically between 31 lbs/ft <sup>3</sup> (500 kg/m <sup>3</sup> ) and 62 lbs/ft <sup>3</sup> (1000 kg/m <sup>3</sup> ). For formaldehyde emission limits, thin MDF is defined as MDF with a thickness less than or equal to 0.315 inches (8 mm), requiring:								
1 1	<b>GRADE 130</b> or better with the following minimum properties:								
1 1 1	<table border="1"> <thead> <tr> <th>PROPERTY</th> <th>VALUE</th> </tr> </thead> <tbody> <tr> <td>Thickness Swelling</td> <td>11% Maximum</td> </tr> <tr> <td>Modulus of Rupture (Grade 130)</td> <td>3130 psi</td> </tr> <tr> <td>Modulus of Rupture (Grade 155)</td> <td>4050 psi</td> </tr> </tbody> </table>	PROPERTY	VALUE	Thickness Swelling	11% Maximum	Modulus of Rupture (Grade 130)	3130 psi	Modulus of Rupture (Grade 155)	4050 psi
PROPERTY	VALUE								
Thickness Swelling	11% Maximum								
Modulus of Rupture (Grade 130)	3130 psi								
Modulus of Rupture (Grade 155)	4050 psi								
1 2	<b>MOISTURE RESISTANT</b> MDF shall not exceed a maximum 4.5% thickness swell after 24 hour submersion in accordance with Section 24 Linear Expansion with Change in Moisture Content and notes 8 - 50 of ASTM D120-37-12 as published by ASTM International, <a href="http://astm.org">http://astm.org</a> .								

# SECTION 4

## Sheet Products

GENERAL/**PRODUCT**/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



## compliance requirements

4.4.15		Balance Sheet Material Rules		
1	Where required within the Product Sections, shall include:			
1	1	<b>WOOD VENEER</b> of the same thickness and compatible species, or:		
1	1	1	Any independently tested material that maintains panel flatness as set forth in this standard.	
1	2	<b>HPDL</b> of the same material and thickness.		
1	3	<b>OVERLAY</b> of the same material and thickness.		

4.4.16		Backer Material Rules			
1	Where required within the Product Sections, shall include:				
1	1	Brown colored, minimum 0.002" (0.05 mm) thick, factory applied, hot-melt coating of blended wax petroleum, copolymer resins, and anti oxidants with swipe controlling agents.	E	C	P
1	2	Polyester or melamine overlay.	E	C	P
1	3	Man made wood fiber veneers, impregnated with acrylic melamine, fortified, high load resin system, a minimum of 0.020" (0.51 mm).	E	C	P
1	4	Synthetic polymer treated backing sheet 0.017" (0.43 mm) - 0.019" (0.48 mm) nominal thickness, designed for use with HPDL.	E	C	P
1	5	Dark brown colored, 0.015" (0.38 mm) nominal thickness, phenolic resin impregnated kraft paper.	E	C	P
1	6	Thermoset resin treated wood fiber, brown colored, 3-ply construction, a minimum of 0.020" (0.51 mm) in thickness.	E	C	P
1	7	Minimum 0.020" (0.51 mm) thick laminate, conforming to NEMA LD3 (latest edition) <a href="http://nema.org">http://nema.org</a> .	E	C	P

4.4.17		Epoxy Resin Material Rules		
1	Shall be a panel produced from a composite of epoxy resin, silica, inert fillers, and organic hardeners, cast and cured in ovens at elevated temperatures, homogenous throughout, and nonabsorbent, with the following minimum performance properties:			
1	1	<b>PROPERTY</b> <b>PROCEDURE</b> <sup>1</sup>	<b>VALUE</b>	<b>TEST</b>
		Compressive Strength	30, 000 psi minimum	ASTM-D-695
		Density	120 lbs./ft <sup>3</sup>	ASTM-D-792
		Flexural Strength	11,000 psi minimum	ASTM-D-790
		Hardness (Rockwell M)	100(Min.)	ASTM-D-785
		Water Absorption	0.05% minimum	ASTM-D-570
		<sup>1</sup> Latest edition		

4.4.18		Natural Stone Material Rules		
1	Shall not be subject to minimum performance properties established by these standards, because it is a natural product.			

4.4.19		Engineered Stone Material Rules		
1	Shall be as specified and subject to the manufacturer's instructions and these standards.			



# SECTION 4

## Sheet Products

GENERAL/PRODUCT/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



## compliance requirements

### 4.4.20 Solid Surface Material Rules

1	<p>Shall be a manufactured, filled cast polymeric resin panel. Fillers may be used to enhance both its performance properties and aesthetics.</p> <p>With a homogeneous composition throughout its thickness, solid surface requires no finish coat and is capable of being fabricated with inconspicuous seams and the following minimum performance properties:</p>		
	<b>PROPERTY</b>	<b>VALUE</b>	<b>TEST PROCEDURE<sup>1</sup></b>
	Abrasion Resistance	Pass	ANSI-Z124.7
	Bacterial Resistance	Pass	ASTM-G-22
	Boiling Water Surface Resistance	No visible effect	NEMA LD3-3.05
	Color Stability (200 Hrs.)	No visible effect	NEMA LD-3
	Fungal Resistance	Pass	ASTM-G-22, or ISO.846
	Gloss (60° Gardner)	5-20 minimum	NEMA LD-3
	Hardness (Rockwell M)	90 minimum	ASTM-D-785
		50 minimum	Barcol
	High Temp. Resistance	No visible effect	NEMA LD-3-3.06
	Impact Resistance	No failure	NEMA LD-3-3.08
	Izod Impact	0.25 ft.-lbs./in. of notch	ASTM-D-256
	Radiant Heat Resistance	No visible effect	NEMA LD-3-3.010
	Specific Gravity <sup>2</sup>	1.5 gram/cm <sup>3</sup> minimum	
	Stain Resistance	Pass	ANSI-Z-124
1	1	Surface Flammability	Meet or exceed applicable code and regulations
		Tensile Strength	4,000 psi minimum
		Tensile Modulus	500,000 psi minimum, or 25,000 psi minimum at 1/8" nominal material
		Tensile Elongation	1% maximum, or 10% maximum at 1/8" nominal material
		Thermal Expansion	2.3 x 10 <sup>-5</sup> in./in./F° max.
		Water Absorption	1% maximum, 24 hr
		<sup>1</sup> Latest edition	
		<sup>2</sup> Approximate weight per 12" x 12" (305 x 305 mm): 1/8" (3 mm) 1.02 lbs. (0.544 kg), 1/4" (6 mm) 2.10 lbs. (0.953 kg), 1/2" (13 mm) 4.20 lbs. (1.905 kg), 3/4" (19 mm) 6.20 lbs. (2.812 kg).	
1	2	Shall be <b>COLOR</b> and <b>PATTERN MATCHED</b> , use of same batch materials is required for adjacent sheets.	
1	3	<b>REPAIRS</b> , while fully functional might be visible.	

### 4.4.21 Solid Phenolic Material Rules

1	<p>Shall be a panel composed of melamine impregnated decorative surface papers superimposed over a varying number of kraft phenolic core sheets to achieve a desired thickness, with the following minimum performance properties:</p>		
	<b>PROPERTY</b>	<b>VALUE</b>	<b>TEST PROCEDURE<sup>1</sup></b>
	Compressive Strength	24,000 psi minimum	ASTM-D-695
	Density	90 lbs./ft <sup>3</sup>	ASTM-D-792
	Flame Test	Self-Extinguishing	ASTM-D-635
	Flexural Strength	15,000 psi minimum	ASTM-D-790
	High Temp. Resistance	No Visible Effect	NEMA LD-3-3.06
	Impact Resistance (1/2 lb. Ball at 120")	No Effect	NEMA LD-3-3.08
	Modulus of Elasticity	1,400,000 psi minimum	ASTM-D-790
1	1	Screw Pull Out <sup>2</sup>	340 lbs. (154 kg) minimum
			at 3/8" (9.5 mm) penetration
			680 lbs. (308 kg) minimum
			at 3/4" (19 mm) penetration
	Shear Strength	2,000 psi minimum	
	Tensile Strength	15,000 psi minimum	ASTM-D-638
	Thickness Tolerance	± 1/32" (0.8 mm) minimum	
	Water Absorption	3% maximum	ASTM-D-570
		<sup>1</sup> Latest edition	
		<sup>2</sup> Resistance based on 1/4" (6.4 mm) machine screw	

Applicable TESTS, may be found in Sections 6 - 11; however, these tests are only applicable to the exposed and semi-exposed portions of installed millwork products.



# North American Architectural Woodwork Standards - 3.1

## **S E C T I O N - 05**

# FINISHING

<b>Resources . . . . .</b>	<b><a href="#">125</a></b>
<b>Introduction . . . . .</b>	<b><a href="#">127</a></b>
<b>Recommendations . . . . .</b>	<b><a href="#">127</a></b>
<b>Specification Considerations . . . . .</b>	<b><a href="#">128</a></b>
<b>NAAWS Finishing Systems . . . . .</b>	<b><a href="#">131</a></b>
<b>NAAWS Systems Usage &amp; Performance . . . . .</b>	<b><a href="#">134</a></b>
<b>Design Resources . . . . .</b>	<b><a href="#">135</a></b>
<b>Compliance Requirements . . . . .</b>	<b><a href="#">136</a></b>
<b>Scope &amp; Default Stipulation . . . . .</b>	<b><a href="#">137</a></b>
<b>Basic Rules . . . . .</b>	<b><a href="#">137</a></b>
<b>Tests . . . . .</b>	<b><a href="#">144</a></b>

### Within CANADA

#### SUPPORT

- **GUIDE SPECIFICATIONS** – Available for download in interactive digital format, including specification wording for Quality Assurance Program (GIS) at: <http://awmac.com/guide-specifications>
- **CONSULTATION** – Contact any of the local chapters for more information on the NAAWS or any other Architectural Woodwork Questions you may have. See below for contact information.
- **SPECIFICATION REVIEW** – Contact any of the local chapters if you would like your specifications reviewed for compliance to the NAAWS.
- **MANUFACTURER STANDARDS QUESTIONNAIRE (MSQ)** – AWMAC Manufacturer members have the opportunity to have at least one member of their staff study and write the MSQ. The MSQ is a questionnaire on the NAAWS and policy and procedures of the GIS program. A list of Manufacturer members that have passed the MSQ is available at: <http://awmac.com/members>
- **SEMINARS AND PRESENTATIONS** – Contact your local chapter to arrange an informative presentation on any Architectural Woodwork topic. Some topic options – GIS, NAAWS, How to Specify Quality Architectural Woodwork...
- **TRADE SHOWS** – Contact your local chapter to arrange for AWMAC to have a booth or do a presentation on Architectural Woodwork.
- **CONFERENCE** – AWMAC has an annual conference held at unique venues across Canada. The conferences provide an opportunity to learn more about Architectural Woodwork and network with Suppliers and Manufacturers from across Canada. More information is available at: <http://awmac.com/>
- **EDUCATION PARTNERS** – Contact the local chapters to find out more information about support for local Colleges and Universities offering woodworking related courses and programs.

#### QUALITY ASSURANCE

- **GUARANTEE AND INSPECTION SERVICE (GIS)** – The GIS is a national program designed to ensure that project owners get value and quality for their investment by:
  - Supporting architects and design professionals to achieve project plans and specifications; and
  - Helping contractors avoid problems such as cost overruns, delays and loss of reputation.More information is available at: <http://awmac.com/gis>

- **INSPECTION SERVICE** – A GIS Certified Inspector will inspect specific areas of concern on a project for compliance to the NAAWS and provide a written report. Contact your local chapter for more information.
- **EXPERT OPINION** – An expert will be appointed to inspect specific areas of concern on a project and provide a written report. Contact your local chapter for more information.

#### AWMAC CHAPTERS

- AWMAC British Columbia Chapter, Vancouver BC  
<http://bc.awmac.com>
- AWMAC Northern Alberta Chapter, Edmonton Alberta  
<http://nab.awmac.com>
- AWMAC Southern Alberta Chapter, Calgary Alberta  
<http://sab.awmac.com>
- AWMAC Saskatchewan Chapter, Saskatoon Saskatchewan  
<http://sk.awmac.com>
- AWMAC Manitoba Chapter, Winnipeg Manitoba  
<http://mb.awmac.com>
- AWMAC Ontario Chapter, Toronto Ontario  
<http://on.awmac.com>
- AWMAC Quebec Chapter, Montreal Quebec  
<http://qc.awmac.com>
- AWMAC Atlantic Chapter, Halifax Nova Scotia  
<http://atl.awmac.com>

### Within UNITED STATES

#### SUPPORT

- **GUIDE SPECIFICATIONS** - Available in interactive digital format including quality control options at: <http://woodworkinstitute.com/publications/architectural-woodwork-standards/>
- **AIA SEMINARS** - The Woodwork Institute is a Registered Provider of the American Institute of Architects (AIA), and its Continuing Education System (CES) program, check out our offerings at: <http://woodworkinstitute.com/architectural-resources/aia-seminars/> 
- **CONSULTATION** - Contact one of our Directors of Architectural Services (DAS) at: <http://woodworkinstitute.com/about-us-2/about-us/>
- **ACCREDITED FABRICATORS AND INSTALLERS** - Our AMC's (Accredited Millwork Company) represents the best fabricators and installers in our industry, check them out at: <http://woodworkinstitute.com/membership-listing-2/> 
- **CERTIFIED INDUSTRY PROFESSIONALS** - Our CMP's (Certified Millwork Professionals) represent the knowledge base of our industry, check them out at: <http://woodworkinstitute.com/membership-listing-2/> 
- **MILLWORK INDUSTRY PARTNERS** - Our MIP's (Millwork Industry Partners) represent the best of our industries material suppliers, check them out at: <http://woodworkinstitute.com/membership-listing-2/> 
- **ACKNOWLEDGED PRODUCTS LISTING** - If it's listed here, you are assured it meets NAAWS minimum requirements, find the listing at: <http://woodworkinstitute.com/acknowledged-product-listing/> 
- **CABINET DESIGN SERIES (CDS)** - Eliminate the need to include casework elevations in your architectural drawings, check out the CDS system in NAAWS "Design Resources" and access the cad files at: <http://woodworkinstitute.com/architectural-resources/cabinet-design-series/>

#### QUALITY ASSURANCE

- **BIDDER QUALIFICATION** - A discipline of bidder pre-qualification wherein your specifications protect you and your customer from the unknown: To be eligible to bid or negotiate this job, the subcontractor must be a Woodwork Institute Accredited Millwork Company (AMC) in good standing.   
<http://woodworkinstitute.com/architectural-resources/quality-assurance>
- **CERTIFIED COMPLIANCE PROGRAM (CCP)** - A discipline of quality control used in conjunction with NAAWS providing an unbiased means of ensuring conformance to a project's plans and specifications. CCP, together with the use of the desired Grade(s) in the specifications, informs all parties of the design professional's expectations, without bidder discrimination.   
<http://woodworkinstitute.com/services/certified-compliance-program>
- **MONITORED COMPLIANCE PROGRAM (MCP)** - A discipline of quality affirmation used in conjunction with the NAAWS which provides ongoing reviews/inspections of a project from its beginning through completion, ensuring strict conformance to the design intent throughout the millwork fabrication and installation process.   
<http://woodworkinstitute.com/services/monitored-compliance-program/>
- **CERTIFIED SEISMIC INSTALLATION PROGRAM (CSIP)** - A standalone seismic assurance option which can be specified in conjunction with or without CCP or MCP, offering design professionals and project owners specific use of WI's seismic casework pre-approvals from California's Office of Statewide Health Planning and Development (OSHPD) without additional engineering costs and/or requirements, assuring proper backing has been installed in the walls when and where required.   
<http://woodworkinstitute.com/services/certified-seismic-installation-program/>

# SECTION 5

## Finishing

## introductory information

### INTRODUCTION

Section 5 pertains to shop and field finishing of architectural woodwork. Thirteen finishing systems are outlined with application rules and methods of testing.

Quality assurance can be achieved by adherence to these standards and will provide the owner a quality product at competitive pricing. Working with an AWMAC Member (in Canada) or a WI Certified Millwork Professional (CMP) (in the USA) and the WI Accredited Millwork Company (AMC) they represent to provide your woodwork will help ensure the understanding and performance of the quality level required. Illustrations in this Section are not intended to be all inclusive, other engineered solutions may be acceptable. In the absence of specifications; methods of fabrication are the manufacturer's choice. The design professional, by specifying compliance to these standards increases the probability of receiving the product quality expected.

### PURPOSE

The purpose of finishing woodworking is twofold. First, the finish is used traditionally as a means to enhance or alter the natural beauty of the wood. Second, the finish shall offer protection to the wood from damage by moisture, contaminants, and handling. It is important to understand that a quality finish must offer acceptable performance and also meet the aesthetic requirements of the project.

The Standard illustrates a number of finishing systems. The finishing system provides a protective surface for the product. Some of these systems are in general use; others are intended for special conditions and can only be applied under a strictly controlled environment. The cost of the systems vary, the higher performing finishes usually being more costly than the lower performing finishes. Unnecessary cost could be added to a project through over specification.

When specifying, use the system name as set forth in these Standards. Involve your woodwork manufacturer early in the design process to evaluate the systems in relation to your project requirements. Choose performance characteristics which meet, but do not exceed, the needs of your project in the interest of value engineering.

The listing of a finish system in these Standards does not imply an endorsement of the materials and/or methods or compliance with federal and/or local Environmental Protection Agency or other requirements.

### RECOMMENDATIONS

- **FIELD FINISHED**, include in Division 09 of the specifications:
  - "Before finishing, all exposed portions of woodwork shall have handling marks or effects of exposure to moisture removed with a thorough, final sanding over all surfaces of the exposed portions, using appropriate grit sandpaper, and shall be cleaned before applying sealer or finish."
  - "Concealed surfaces of all architectural woodwork that might be exposed to moisture, such as those adjacent to exterior concrete walls, shall be primed."
- **REVIEW** the GENERAL portion of Sections 3 and 4 for an overview of the characteristics and the minimum acceptable requirements of lumber and/or sheet products that might be used herein.
- Avoid **BRUSH-APPLIED** finishes for architectural woodwork; they are not covered by these standards.
- Avoid **BLEACHED VENEERS** because of potential finishing problems.



- Avoid **JOBSITE FINISHING** because a factory-controlled finishing environment offers a superior finished product; however, jobsite finishing is permitted, provided there is no violation of applicable codes and regulations.
- Avoid **EXTERIOR WOOD DOORS** finished in a dark color that will absorb heat when exposed to direct sunlight or without adequate overhead soffit protection.
- For **CHEMICAL RESISTANCE**, these standards have adapted SEFA's (Scientific Equipment and Fixture Association) standard list of 49 chemicals/concentrations, their required methods of testing, and their minimum acceptable results as the minimum acceptable chemical-resistance requirement for finishes used at exposed and semi-exposed surfaces, when such is required by specification.
- **SEFA's** chemical listing, methods of testing, and minimum acceptable results can be found in **APPENDIX**. 
- **FIRE-RETARDANT or RESISTANT FINISHES** are subject to applicable codes and regulations, the use of fire-rated cores in lieu of fire-retardant finishes is recommended. 
- Some **PRE-FINISHED** wood panels or decorative overlays have aesthetic and performance characteristics that meet or exceed these standards without using a listed or recommended finish system.
- Such products should be evaluated and/or specified by the design professional.

### SPECIFICATION CONSIDERATIONS



- **FIRE RESISTANCE**
- **CHEMICAL RESISTANCE**
- **Use of FILLER, WASH COAT, or STAIN**
- **FILLED FINISH**
- **NAAWS FINISHING SYSTEM** for transparent or opaque application:
  - **SYSTEM - 1**, LACQUER, NITROCELLULOSE
  - **SYSTEM - 2**, LACQUER, PRE CATALYZED
  - **SYSTEM - 3**, LACQUER, POST CATALYZED
  - **SYSTEM - 4**, LATEX ACRYLIC, WATER-BASED
  - **SYSTEM - 5**, VARNISH, CONVERSION
  - **SYSTEM - 6**, OIL, SYNTHETIC PENETRATING (available in transparent only)
  - **SYSTEM - 7**, VINYL, CATALYZED
  - **SYSTEM - 8**, ACRYLIC CROSS LINKING, WATER-BASED
  - **SYSTEM - 9**, UV CURABLE, ACRYLATED EPOXY, POLYESTER OR URETHANE
  - **SYSTEM - 10**, UV CURABLE, WATER-BASED
  - **SYSTEM - 11**, POLYURETHANE, CATALYZED
  - **SYSTEM - 12**, POLYURETHANE, WATER-BASED
  - **SYSTEM - 13**, POLYESTER, CATALYZED

### FACTORY or FIELD FINISHING

Both are permitted, provided there is no violation of applicable codes or regulations.

- **Factory finishing** is usually specified for high quality work where superior appearance and performance of the finish is desired. Benefits of factory finishing include consistency, control of film thickness, environmental compliance, and curing/drying of the finish in a controlled atmosphere. Its use assumes a maximum degree of manufacturer prefabrication so that site installation can be performed with a minimum amount of cutting, fitting, and adjustment to facilitate project completion.
- **Field finishing** is typically specified when there is not a demand or specific need for a superior appearance and is not necessarily part of the woodwork contract. This would normally be specified in the painting specification section. The finisher/painter is responsible for examining and accepting the woodwork as supplied prior to the commencement of finishing. The finisher/painter is responsible for meeting or exceeding the control sample for surface performance characteristics (such as color, texture, and sheen), including proper surface preparation, shading, and blending of color, and other requirements as defined in this standard when so referenced.
- **Wood parts on decorative laminate cabinets:** finish is required on all wood pulls, trims, applied molding, edgebands, drawer boxes, and interior wood parts of decorative laminate casework.

### IMPORTANT CONSIDERATIONS:

- **Specifications** too often, call for finishes based on samples or guide language from a specialty manufacturer.

Select the performance criteria which best meets the needs of your client from the finish tables. Finish chemistry, performance, value to performance ratio, and your finisher's abilities should be considered.

- **Varying costs** of finish systems typically relate directly to their performing characteristics.
- **Intermixing systems** will likely cause quality and/or performance problems; they are usually not compatible with each other.

Examples include the over specification of polyurethane or polyester topcoats when they are neither necessary or available from a custom fabricator.

- **Application** of finish material in excess of manufacturer's film thickness recommendations can cause the finish to fail.

Brush applied finishes are not recommended for factory finished architectural woodwork, and are not covered by these Standards.

Application techniques and other variances make the execution of the finish system difficult to determine. These standards provide the minimum requirements. The desired end result is to provide a finish that is both durable and achieves the desired appearance.

- **Curing** of finish systems have a wide range of variance. Shortest cure time is UV cured coatings, and longest being water based air dry coatings. Heat and air movement will speed the recoat and cure time.

For the most part the method should not concern the design professional or specification writer. It is the performance of the topcoat which is important.

# SECTION 5

## Finishing

## introductory information

### IMPORTANT CONSIDERATIONS:

(Continued)

UV (ultraviolet light) is typically used for high volume, repetitive applications, and requires special reactors to cure. A number of pre-finished panel products are coated with materials designed specifically for UV curing. A wide range of UV cured roll coat flat line panel finishes are available. Just as there are in the conventional spray/air cured coatings. Consult with the fabricator for performance tests and details

- **Pre-finished Wood Panels** and decorative overlays have aesthetic and performance characteristics which meet or exceed these Standards, and should be evaluated, approved and specified by the design professional when desired.
- **Panel products** and/or wood doors require balanced coats of finishing materials for stability and to remain free of warp.
- **Barber pole** effect is most evident when veneer leaves are book matched. Because book matched veneer panels or door faces are made up by turning every other piece (leaf) of veneer over, like the pages of a book, the face of one leaf and the back of the next leaf is exposed. This exposes the "tight" and "loose" face of the leaves. One of the most striking examples of Barber Pole effect can be seen in book matched rift and quarter cut Oak. Check with your manufacturer when you are considering specifying rift or quartered veneers.
- **Grain** can significantly impact a finish's visual appearance and smoothness. If a filled finish is required it must be so specified. As a rule, close grain woods do not require filler. See Table.

For finishing purposes, the following woods are classified as:

#### Open Grain

Ash	Mahogany,
Butternut	Philippine
Chestnut	Oak, Red
Mahogany, African	Oak, White
Mahogany, American	Walnut

#### Close Grain

Alder, Red	Gum
Beech	Maple
Birch	Pine
Cherry	Poplar
Fir	

- **Color and grain enhancement** of a system, from the addition of a single stain, to a multiple step build of one color on another with wash coats in between for enhanced appearance is not included in the basic systems and needs to be specified.

Aesthetically, systems may vary from no stain, to a single stain, to a multiple step application. Some samples will require multiple color and finish steps in order to meet the architect's requirements. The system specified may not include all steps necessary to match the architect's example or requirements. Color and grain enhancement of some finishes require the build of one color step on another. This will sometimes require an additional protective wash coat between color steps. Generally, this procedure adds to the depth and beauty of the finish. Each added step increases costs and shall be specified.

- **Color match and consistency** is often misleading. The best case achievable using a natural product like wood in a wide variety of lighting conditions is a good "blend" of color and tone throughout the project area. The natural color of the wood product is altered by the application of even a clear topcoat. Further alteration is achieved through the use of stains, glazes, bleaches, etc. Wood changes color; especially Cherry, Fir, American and African Mahogany, Walnut, Teak, and others. Filled nail holes will not change with wood. The apparent consistency of the color is a combination of light reflectance, cellular structure, natural characteristics, applied colors, and sheen.

Color and "matching" of a sample are often highly subjective. Individual perception, ambient lighting, and reflectivity influence judgement. Design professionals are encouraged to consult directly with a manufacturer during the design and selection phase of each project.

- **Sheen** is the result of many factors, including finishing techniques, processes, stains, topcoats and the wood itself. Coating manufacturers use a variety of names for different sheens. An untrained eye can see a 10 point or greater difference in sheen.

The following sheen ranges were developed by measuring the reflectance of a direct light source at a 60 degree angle with a gloss meter:

- **Flat = 8 - 14**
- **Satin = 15 - 25**
- **Satin Gloss = 26 - 49**
- **Semi gloss = 50 - 70**
- **Gloss = 71 - 90**
- **Transparent** finishes are applied in varying operations, typically consisting of some combination of hand sanding to remove job handling marks, staining, filling, sealing, sanding, and surface coating. Some exotic species have a high natural oil content and do not accept finishes similar to other hardwoods; because of this, the most common finish used is penetrating oil without any filling or sealing dyes or pigments in a stain.

### IMPORTANT CONSIDERATIONS:

(Continued)

- **Blotchy appearance** occurs because some wood species exhibit an uneven distribution of large and small pores in their structure. The occurrence of this is readily apparent in such hardwood species as Maple and Birch and, to a lesser degree, in Cherry. This irregular distribution of pores usually causes an uneven absorption of stain, hence, an apparent blotchy appearance in the finish. Reduction of the blotching condition can sometimes be achieved by proper sanding, wash coating (prior to staining) or by choosing non penetrating pigments, such as dyes, alcohol stains or glaze. When these steps are required or desired, they shall be specified in addition to finish system selection.

### TECHNIQUES TO CONSIDER

While a blotchy appearance and the “barber pole effect” may occur in any species, due to the natural characteristics of wood, there are steps that can be taken to reduce these effects. The following are two of the techniques that are of particular importance.

- **Sanding** - While the selection of species, cut and match are major factors in the final appearance of a project, the first step, in controlling the quality of finished appearance, is proper sanding.

An important element of this standard is the statement “just prior to staining.” Specifications that indicate “factory shall finish sand prior to shipment” do not provide a correct solution for proper surface preparation. Such a directive fails to take into account the length of time panels will be stored at the job site, potential damage from handling and the effects of changes in the relative humidity. Proper sanding can only be done, just prior to staining/finishing.

The successful sanding of panels, or flush doors, is best accomplished with a hand block, powered pad sander, wide belt sander or stroke sander, exerting uniform pressure over the entire surface. Depending upon the condition of the surface it may be necessary to use successively finer grits of abrasive to properly prepare the surface, brushing off the surface between grits. These Standards set forth the smoothness requirement for all Grades of work. Proper and complete surface preparation is the key factor in the successful finish procedure.

- **Wash Coat** - A wash coat is a thin coat of material, usually clear lacquer or vinyl sealer (6 to 10 parts thinner to one part sealer, topcoat). A wash coat can fulfill several purposes such as: to stiffen the small wood fibers that are raised by the staining operation, so they can be cut off easily with fine sandpaper (320 grit), to seal the stain, particularly if it is a bleeding type, to aid in the wiping and clean up of filler, and to minimize excessive penetration of stain or filler to minimize blotchiness. As with any finish process, samples should always be prepared to ensure that the desired finish is achieved.

### IRON STAIN

Iron stain occurs in some species of veneers when natural tannic acid in the wood comes in contact with iron and or moisture. Enough moisture may occur during heavy rains or high humidity in buildings not yet temperature controlled.

To prevent iron stain, never use steel wool on the bare wood. Fine particles of the wool will cling to the wood and cause trouble later. If you use shellac (a solvent for iron), it should not be stored in iron containers. To remove iron stain prior to finishing, we recommend a solution of oxalic acid crystals. The solution is made by dissolving 12 ounces of crystals in one gallon of lukewarm water. Use a plastic or rubber container. Wear rubber gloves while working with the solution. Apply it to the stained areas with a brush or sponge.

To remove the oxalic acid, use a sponge and a bucket filled with lukewarm water. Squeeze the sponge to remove excess water and wipe the entire surface of the Oak wood to remove the acid residue. Rinse the sponge frequently in clean lukewarm water as you wipe. Pour out the water and add 1 qt. of fresh lukewarm water to the bucket. Add 2 tablespoons. baking soda to the water and stir with a spoon to dissolve. Insert a fresh sponge into the solution and squeeze out the excess water. Wipe the entire surface of the Oak to neutralize any remaining acid residue and stop the bleaching process. Allow the surface to dry and sand with 150 to 180 grit sandpaper. The entire surface should be treated to avoid spotting. Failure to rinse the treated area adequately may have a damaging effect on the finish subsequently applied, or may cause damage to nearby glass, porcelain or other surfaces in confined areas. Damage may not result immediately, but may result during storage or after installation.

### FIRE RETARDANT TREATED WOOD and COATINGS

Fire retardant treatments may affect the finishes intended to be used on the wood, particularly if transparent finishes are planned. The compatibility of finishes should be tested before they are applied.

“Fire retardant” coatings usually are of the intumescent type. They may be water based or solvent based, but both contain ingredients which, under the influence of heat, produce gases and char like products, resulting in the formation of a thick nonflammable crust that effectively insulates combustible cores from heat and flame. However, these ingredients are for the most part water sensitive and therefore reduce durability and range of usage of the coatings.

These coatings only delay the spread of fire and help contain it to its origin. To be of appreciable value, fire retardant coatings must be applied in strict conformance with the manufacturer’s instructions. These finishes are not particularly durable and their use should be restricted to application over interior surfaces.

The need for, and effectiveness of, fire retardant and fire resistant finishes depends on the type of construction, nature of occupancy, and other technical features of the building. Because these finishes are considerably more expensive and have reduced durability, their use should be carefully limited to those areas where confining fire spread is the overwhelming consideration; for example, interior entrances, hallways, stairwells and ceilings.

### NAAWS FINISHING SYSTEMS

Apply to both transparent or opaque applications, unless otherwise indicated: Specification of a system requires listing both the system number and the name, along with any desired enhancements.

**SYSTEM - 1**, LACQUER, NITROCELLULOSE

**SYSTEM - 2**, LACQUER, PRE CATALYZED

**SYSTEM - 3**, LACQUER, POST CATALYZED

**SYSTEM - 4**, LATEX ACRYLIC, WATER BASED

**SYSTEM - 5**, VARNISH, CONVERSION

**SYSTEM - 6**, OIL, SYNTHETIC PENETRATING (available in transparent only)

**SYSTEM - 7**, VINYL, CATALYZED

**SYSTEM - 8**, ACRYLIC CROSS LINKING, WATER-BASED

**SYSTEM - 9**, UV CURABLE, ACRYLATED EPOXY, POLYESTER OR URETHANE

**SYSTEM - 10**, UV CURABLE, WATER BASED

**SYSTEM - 11**, POLYURETHANE, CATALYZED

**SYSTEM - 12**, POLYURETHANE, WATER BASED

**SYSTEM - 13**, POLYESTER, CATALYZED

# SECTION 5

## Finishing

## introductory information

Table: 5-001 - GENERAL PERFORMANCE CHARACTERISTICS of NAAWS FINISHING SYSTEMS:

	SYSTEM NUMBER and DESCRIPTION												
	LACQUER, NITROCELLULOSE	LACQUER, PRE CATALYZED	LACQUER, POST CATALYZED	LATEX ACRYLIC, WATER BASED	VARNISH, CONVERSION	OIL, SYNTHETIC PENETRATING (available in transparent only)	VINYL, CATALYZED	ACRYLIC CROSS LINKING, WATER-BASED	UV CURABLE, ACRYLATED EPOXY, POLYESTER OR URETHANE	UV CURABLE, WATER BASED	POLYURETHANE, CATALYZED	POLYURETHANE, WATER BASED	POLYESTER, CATALYZED
	1	2	3	4	5	6	7	8	9	10	11	12	13
<b>General Durability</b>	2	2	3	2	4	1	4	2	5	5	5	3	5
<b>Repairability</b>	5	4	3	3	3	5	4	4	1	3	2	4	1
<b>Abrasion Resistance</b>	2	4	4	3	4	1	4	4	5	4	5	4	5
<b>Finish Clarity</b>	5	4	5	2	3	5	3	4	5	5	3	4	4
<b>Yellowing in Time</b>	1	2	3	5	4	2	1	4	3	5	4	4	3
<b>Finish Flexibility</b>	1	2	3	3	4	5	4	3	2	3	4	4	1
<b>Moisture Resistance</b>	3	3	4	1	4	1	5	3	5	4	5	4	5
<b>Solvent Resistance</b>	1	2	4	1	5	1	5	3	5	5	5	4	5
<b>Stain Resistance</b>	2	4	5	3	5	1	5	4	5	5	5	4	5
<b>Heat Resistance</b>	1	2	5	1	5	1	5	3	5	5	5	4	5
<b>Household Chemical Resistance</b>	3	4	5	3	5	2	5	4	5	5	5	4	5
<b>Build/Solids</b>	2	3	3	3	4	1	4	3	5	4	4	3	4
<b>Drying Time</b>	5	5	5	2	4	2	5	4	5	5	3	5	2

5 = Excellent to 1 = Poor. The numerical ratings are subjective judgments based on the general performance of generic products. Special formulations and facilities will influence some of the performance characteristics.

### NOTES for Table: 5-002 on following page.

Testing was evaluated in an ISO 9000-certified laboratory using the following ASTM test criteria: Chemical Resistance Testing - ASTM D1308 (latest edition), Wear Index - Abrasion Resistance Testing - ASTM D4060 (latest edition), Cold Check Resistance - ASTM D1211 (latest edition), Cross Hatch Adhesion - ASTM D3359 (latest edition).

Baseline data for application prior to testing: A. 45-55% humidity at 70-80 degrees Fahrenheit; B. Water-borne coatings must be cured in a dehumidified atmosphere and can be assisted with infrared light and good air movement.

Performance indicator numbers are used, with the following definitions:

For chemical resistance and wear index - abrasion resistance:

- 5 - No effect from the test.
- 4 - Minimal effect or slight change and little repair required.
- 3 - Some effect; noticeable change, and the coating will recover with minimal repairs.
- 2 - Moderate effect, performance adversely affected and repairs required.
- 1 - Poor performance and film failure is imminent and repairs difficult.

For cross-hatch adhesion:

- 5 - Edges of the cuts are completely smooth; none of the squares of the lattice are detached.
- 4 - Small flakes of the coating are detached at intersections; less than 5% of the area is affected.
- 3 - Small flakes of the coating are detached along the edges and at the intersections of cuts; 5 to 15% of the area is affected.
- 2 - Coating has flaked along the edges and on parts of the squares; 15 to 35% of the area is affected.
- 1 - Coating has flaked along the edges of the cuts in large ribbons and whole squares have detached; 35 to 65% of the area is affected.

# SECTION 5

## Finishing

## introductory information

Table: 5-002 - **SPECIFIC PERFORMANCE CHARACTERISTICS** for **NAAWS FINISHING SYSTEMS** for **TRANSPARENT** and **OPAQUE TOPCOATS**:

	SYSTEM NUMBER and DESCRIPTION												
	LACQUER, NITROCELLULOSE	LACQUER, PRE CATALYZED	LACQUER, POST CATALYZED	LATEX ACRYLIC, WATER BASED	VARNISH, CONVERSION	OIL, SYNTHETIC PENETRATING (transparent only)	VINYL, CATALYZED	ACRYLIC CROSS LINKING, WATER-BASED	UV CURABLE, ACRYLATED EPOXY, POLYESTER OR URETHANE	UV CURABLE, WATER BASED	POLYURETHANE, CATALYZED	POLYURETHANE, WATER BASED	POLYESTER, CATALYZED
	1	2	3	4	5	6	7	8	9	10	11	12	13
Vinegar	3	4	5	4	5	3	5	5	5	5	5	4	5
Lemon Juice	3	4	5	4	5	3	5	5	5	5	5	4	5
Orange Juice	3	4	5	4	5	3	5	5	5	5	5	4	5
Catsup	3	4	5	4	5	2	5	5	5	5	5	4	5
Coffee	3	4	5	4	5	2	5	5	5	5	5	4	5
Olive Oil	2	3	5	3	5	2	5	5	5	5	5	4	5
Boiling Water	3	4	5	4	5	3	5	5	5	5	5	4	5
Cold Water	5	5	5	5	5	3	5	5	5	5	5	4	5
Nail Polish Remover	1	2	3	2	4	1	2	2	5	5	4	3	4
Household Ammonia	3	4	5	4	5	2	4	2	5	5	5	4	5
VM&P Naphtha	3	4	5	4	5	1	4	5	5	5	5	4	5
Isopropyl Alcohol	1	2	3	1	5	2	4	3	5	5	5	4	5
Wine	3	4	5	4	5	2	4	5	5	5	5	5	5
Windex™	3	3	4	3	5	2	3	4	5	4	5	4	5
409 Cleaner™	3	3	4	4	5	1	4	4	5	5	5	4	5
Lysol™	3	5	5	4	5	2	4	3	5	5	5	4	5
33% Sulfuric Acid	3	4	5	3	5	1	4	5	5	5	5	4	5
77% Sulfuric Acid	1	2	3	1	1	1	2	1	4	3	4	3	4
28% Ammonium Hydroxide	1	2	3	1	5	1	4	2	5	5	5	3	5
Gasoline	1	2	5	2	5	1	4	5	5	5	5	4	4
Murphy's Oil Soap™	5	5	5	5	5	2	4	4	5	5	5	5	5
Vodka 100 Proof	3	4	5	4	5	2	4	3	5	5	5	4	5
1% Detergent	3	4	5	4	5	3	4	5	5	5	5	5	5
10% TSP	3	4	5	4	4	1	5	2	5	5	5	5	5
<b>SUBTOTAL</b>	<b>65</b>	<b>86</b>	<b>110</b>	<b>82</b>	<b>114</b>	<b>46</b>	<b>100</b>	<b>95</b>	<b>119</b>	<b>117</b>	<b>118</b>	<b>97</b>	<b>117</b>
Wear	2	3	4	2	5	1	4	4	5	5	5	5	4
Cold Check	5	5	5	5	5	5	5	5	5	5	5	5	5
Adhesion	5	5	5	5	5	5	5	5	5	5	5	5	5
<b>TOTAL SCORE</b>	<b>77</b>	<b>99</b>	<b>124</b>	<b>94</b>	<b>129</b>	<b>57</b>	<b>114</b>	<b>109</b>	<b>134</b>	<b>132</b>	<b>133</b>	<b>112</b>	<b>131</b>

NOTES are on previous page.

# SECTION 5

## Finishing

## introductory information

The following system overview tables are intended to give an overview of and help identify the correct standard or specialty finishing system to meet a project's needs; however, they are only relative to the topcoat, not any prior color or filler coats.

Differences between systems of 10 points or fewer are not generally considered significant enough to justify the typical added expense of a higher-rated system. This systems listing does not imply an endorsement of the materials or

compliance with applicable codes and regulations. Due to changing environmental regulations and finish technologies, design professionals need to discuss finish options with a manufacturer located in the area of the project.

Table: 5-003 - **USAGE and PERFORMANCE SCORE COMPARISONS for NAAWS FINISHING SYSTEMS for TRANSPARENT and OPAQUE TOPCOATS:**

	TYPICAL USAGE	SCORE	WHY AND WHY NOT
1 - LACQUER, NITROCELLULOSE	Use in climate controlled environment for trims, furniture, paneling, and ornamental work.	77	Why - Repairable; widely available; quick-drying Why not - Lack of durability and resistance to most solvents and water; yellows over time.
2 - LACQUER, PRECATALYZED	Use in climate controlled environment for furniture, casework, paneling, ornamental work, stair parts (except treads), frames, windows, blinds, shutters, and doors.	99	Why - Repairable; stain-, abrasion-, chemical-resistance. Why not - Some yellowing; moderate build.
3 - LACQUER, POSTCATALYZED	Use in climate controlled environment for furniture, casework, paneling, ornamental work, stair parts (except treads), frames, windows, blinds, shutters, and doors.	124	Why - Repairable; finish clarity; stain-, heat-, abrasion-, chemical-resistance. Why not - Some yellowing; moderate build.
4 - LATEX ACRYLIC, WATER BASED	Use in climate controlled environment for furniture, casework, paneling, ornamental work, stair parts (except treads), frames, windows, blinds, shutters, and doors.	94	Why - Low VOCs; finish clarity (some formulations); stain resistance; yellowing resistance. Why not - Low durability; solvent- and heat-resistance; slow drying time.
5 - VARNISH, CONVERSION	Use in climate controlled environment for furniture, casework, paneling, ornamental work, stair parts, frames, windows, blinds, shutters, and doors.	129	Why - Durable; widely available; good build. Why not - Occasional lack of finish clarity.
6 - OIL, SYNTHETIC PENETRATING	Use in climate controlled environment on furniture or trims requiring a close-to-the-wood look or very low sheen.	57	Why - Close-to-wood, antique look; low sheen. Why not - Labor-intensive to apply and maintain, refreshing finish required from time-to-time; low resistance properties to most substances.
7 - VINYL, CATALYZED	Use in climate controlled environment, often on kitchen, bath, office furniture, and laboratory casework.	114	Why - Durable; widely available; fast drying. Why not - Occasional lack of finish clarity.
8 - ACRYLIC CROSS LINKING, WATER-BASED	Use in climate controlled environment for furniture, casework, paneling, ornamental work, stair parts, frames, windows, blinds, shutters, and doors.	109	Why - Fine durability; excellent abrasion-, solvent-, stain-, and chemical-resistance; moderately fast-drying; resists moisture Why not - Possibility of discoloration over time.
9 - UV CURABLE, ACRYLATED EPOXY, POLYESTER OR URETHANE	Use in climate controlled environment, doors, paneling, flooring, stair parts, and casework, where applicable; consult your finisher before specifying.	134	Why - Low VOCs; durable; near 100% solids usage; quick-drying (cure), may qualify as Green Guard. Why not - Difficult to repair with UV finish, as this requires a handheld UV lamp; availability varies; easy repair with lacquers or conversion varnish.
10 - UV CURABLE, WATER BASED	Use in climate controlled environment, doors, paneling, flooring, stair parts, and casework where applicable; consult your finisher before specifying.	132	Why - Low VOCs; quick-drying (cure), maybe Green Guard. Why not - Difficult to repair with UV finish, requires handheld UV lamp; availability varies; easy repair with lacquers or conversion varnish.
11 - POLYURETHANE, CATALYZED	Use in climate controlled environment; some formulas available for exterior environments; floors, stairs, high-impact areas; some doors; generally not good for casework, paneling, windows, blinds, and shutters.	133	Why - Durable; good build. Why not - Slow-drying; very difficult to repair; some formulations hazardous to spray-personnel without air make-up suits.
12 - POLYURETHANE, WATER BASED	Use in climate controlled environment for furniture, casework, paneling, ornamental work, stair parts, frames, windows, blinds, shutters, and doors.	112	Why - Improved durability; excellent abrasion-, solvent-, stain-, and chemical-resistance; moderately fast-drying; resists moisture. Why not - Tannins in some wood species may cause discoloration over time.
13 - POLYESTER, CATALYZED	Use in climate controlled environment for furniture, casework, paneling, ornamental work, blinds, shutters, and some doors.	131	Why - Durable; good build; can be polished. Why not - Not widely available; slow-curing; requires special facilities and skills; very difficult to repair; brittle finish flexibility.

### ANTIMICROBIAL SURFACES

There is increasing availability of antimicrobial products, including solid surface and HPDL. It is important to understand that regardless of the methodology used to create the antimicrobial surface there are two significantly different types of claims regarding such antimicrobial products. Common terminology refers to these:

- **Within the United States as:**
  - **Treated Article Claim** - Which the US Environmental Protection Agency (EPA), <http://epa.gov>, classifies as a “treated article exemption”, typically referring to items that are treated with antimicrobial pesticide to protect the item itself, not the public. Such exemption will be absent any EPA registration number and is granted for non-public health use.
  - **Public Health Claim** - Which the EPA classifies as “EPA registered products which have been shown, using EPA testing protocols, to demonstrate efficacy in the installed format. Such test protocol requires an efficacy of killing 99.9% of all bacteria, fungi and viruses within two hours.
- **Within Canada as:**
  - **Disinfectant Drugs** - Which Health Canada, <http://hc-sc.gc.ca>, classifies as a non market authorized claim, lacking a Drug Identification Number (DIN).
  - **Hard Surface Disinfectants** - Which Health Canada classifies as having received “Market Authorization” when such have been granted a Drug Identification Number (DIN).

### DESIGN RESOURCES



Is a perpetually expanding, web based resource of pictures, videos, illustrations, ideas and design concepts for inspiring thought and design creativity - assessable at: <http://naaws-design-resources.com>

Relative to this Section, offerings will include:

- Finish options
- Finish problems examples

# SECTION 5

## Finishing

### GENERAL PRODUCT TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



## compliance requirements

### INCLUDING: Factory and Field Finishing

#### 5.1 BASIC CONSIDERATIONS

##### 1 GRADE

1.1 **CLASSIFICATIONS** of **ECONOMY**, **CUSTOM**, and **PREMIUM** are used within these standards only in reference to the acceptable quality of workmanship, material, or installation in a completed architectural woodwork product.

1.2 Section deals with finish application, which is a component of finished products covered in Sections 6 - 12.

1.2.1 Grade classifications are only for the purpose of identifying finish applications that can be used in finished products meeting those Grades.

1.2.2 They are not intended to be used as a Grade or to judge a particular finish system.

##### 2 COMPLIANCE REQUIREMENTS

2.1 Apply only to surfaces visible after fabrication and installation.

2.2 Establish criteria as to which, if any, application characteristics are acceptable.

2.3 Address priming, when required.

3 **CONTRACT DOCUMENTS** shall govern if in conflict with these standards.

4 **AESTHETIC COMPLIANCE** requirements apply only to surfaces visible after manufacturing, installation and finishing.

5 **LISTING** of a finish system in these standards does not imply an endorsement of such or compliance with applicable codes and regulations.



#### 5.1 BASIC CONSIDERATIONS (continued)

6 **FACTORY** or **FIELD** finishing are permitted, provided there is no violation of applicable codes or regulations.

6.1 **FACTORY** finishing is usually specified for high-quality work where superior appearance and performance of the finish is desired.

6.2 **FIELD** finishing is typically specified when there is not a demand or specific need for a superior appearance and is not necessarily part of the woodwork contract.

6.2.1 The finisher is responsible for examining and accepting the woodwork as supplied prior to the commencement of finishing.

6.2.2 The finisher is responsible for meeting or exceeding the control sample for surface performance characteristics (such as color, texture, and sheen), including proper surface preparation, shading, and blending of color, and other requirements as defined in this standard when so referenced.

##### 7 INDUSTRY PRACTICES

7.1 **DOOR MANUFACTURERS** typically offer only their own standard finishes. If one or more acceptable door manufacturers are listed in a project's specifications, it indicates that each manufacturer's standard finish system is acceptable.

7.2 **FINISHING** of **WOOD COMPONENTS** on **DECORATIVE LAMINATE** casework (including pulls, trims, moldings, and edgebanding) is included in the manufacturer's scope of work.

7.3 **FINISHING SYSTEMS** are applied per the manufacturer's recommendations.

# SECTION 5

## Finishing

### GENERAL PRODUCT TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



## compliance requirements

### 5.2 SCOPE

1 All factory finishing of architectural woodwork.

#### 2 TYPICAL INCLUSIONS

- 2.1 The application of transparent or opaque finish on all architectural woodwork specified to be factory pre-finished and/or jobsite finished within the architectural woodwork contract.
- 2.2 The application of primer prior to delivery to the jobsite for final paint finish to be applied later by others.
- 2.3 Raw wood parts on decorative laminate cabinets, except as specified in the contract documents, such as wood finger pulls or wood drawer bodies incorporated into the assembly.
- 2.4 All preparatory work, labor, equipment, materials, and related supplies to produce the specified finish.

#### 3 TYPICAL EXCLUSIONS

- 3.1 All painting or priming of building surfaces not specified within the architectural woodwork contract.
- 3.2 All finishing of architectural woodwork specified within the painting specifications.
- 3.3 Jobsite touch up after delivery or installation.
- 3.4 Brush applied topcoat finishes, except as called out under the scope of work for the custom woodwork manufacturer, such as faux finishes.
- 3.5 Items to receive subsequent coats of finish materials by others.
- 3.6 Exterior painting or priming.

### 5.3 DEFAULT STIPULATION

- 1 If not otherwise specified or indicated in the contract documents, all work under this section shall meet the same Grade as the item being finished, and/or the finishing system selected shall be the choice of the finishing contractor. 

### 5.4 RULES

- 1 The following rules shall govern unless a project's contract documents require otherwise.
- 2 These rules are intended to provide a well defined degree of control over a project's quality of finishing.
- 3 **ERRATA, published at <http://naaws-errata.com>, shall take precedence over these rules, subject to their date of posting and a project's bid date.** 

5.4.4		Basic General Rules	
<b>1 FINISHER shall:</b>			
1	1	Determine and report in writing before the start of finishing, and:	
1	1	1	Material or finish system requirements in violation of applicable codes or regulations, and:
1	1	1	1 It shall <b>NOT</b> be the responsibility of the finisher to comply with a specification requirement or finishing system that is illegal or otherwise disallowed in a particular area by some regulatory agency.
1	1	2	Any condition that might affect proper finish application.
1	1	3	Moisture content of product and/or surrounding wall surfaces, such as drywall or plaster, above 12%.
1	1	4	<b>FILLED FINISH</b> is only required if so specified.
<b>2 SAMPLES shall</b>			
2	1	Be submitted and approved before finishing of product, and:	
2	1	1	Due to variance in wood color within the same species and even within the same log, a range of color shall be expected on finished wood products, and:
2	1	1	1 To establish an acceptable sheen and color range, a minimum of three samples shall be submitted.
Continues next column ▼			

# SECTION 5

## Finishing

### GENERAL PRODUCT TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



## compliance requirements

5.4.4		Basic General Rules		
▲ From previous column				
2	SAMPLES shall (continued)			
2	1	Be submitted and approved (continued)		
2	1	2	Shall be at least 12" x 12" (305 mm x 305 mm) if on a panel product, and:	
2	1	2	1	Protected from light.
2	1	2	2	Be as wide as practical if on lumber by a minimum of 12" (305 mm) in length.
2	1	3	Shall be on material representative of that to be used for the project.	
2	1	4	Shall each bear a label identifying the job name, the design professional, the contractor, and the finish system number.	
3	AESTHETIC RULES apply only to exposed and semi-exposed surfaces visible after installation.			
4	OVERALL APPEARANCE shall be:			
4	1	Not required to be compatible for color or grain		E C P
4	2	Compatible in color and grain.		E C P
4	3	Well matched for color and grain.		E C P
5	APPLICATION TECHNIQUES and other variances make the execution of the finish system difficult to determine. These standards provide the minimum requirements. The desired end result is to provide a finish that is both durable and achieves the desired appearance.			
6	INCOMPATIBILITY of finish to wood shall be prevented, and:			
6	1	It is the responsibility of the finisher to:		
6	1	1	Conduct, as applicable, a test sample to check for species of wood that reacts unfavorably with certain finishes.	
6	1	2	Apply a sealer, if required, before finishing to nullify such a chemical reaction.	
7	PANELING requires:			
7	1	Adjacent panels to be finished together to achieve maximum uniformity of color, and:		
7	1	1	If possible, entire elevations shall be finished together.	
8	TRIM and FRAMES require only the exposed faces and edges to be top-coated.			
Continues next column ▼				

5.4.4		Basic General Rules		
▲ From previous column				
9	DOORS require:			
9	1	Two faces and two vertical edges to be finished and:		
9	1	1	The top/bottom edges and hardware preparation areas at hinges and lock edges to be sealed.	
9	2	An equal number of coats of the same material applied to each side.		
9	3	Pairs of doors and openings with sidelights and transoms finished together to achieve maximum uniformity of color.		
9	4	FINISHES, other than those furnished by a door manufacturer, be specified to be applied by the woodwork finisher.		
10	CASEWORK requires:			
10	1	All exposed exterior, exposed interior and semi-exposed surfaces be finished.		
10	2	All six faces of cabinet doors receive the same number of coats to prevent warping and/or twisting.		
11	DEFECTS and WORKMANSHIP:			
11	1	Regardless of requirements otherwise stated in these standards, final sanding prior to the application of finishing materials is the responsibility of the finisher.		
11	2	HANDLING, MACHINING, or TOOL MARKS are not allowed.		
11	3	INDENTATIONS and SCRAPES shall be for:		
11	3	1	Opaque - Filled or patched.	E C P
11	3	2	Transparent - Filled or patched.	E C P
11	3	3	Transparent - Steamed out.	E C P
11	4	MOISTURE EFFECTS, such as raised grain or blue stain, shall be removed.		
11	5	PARTICLES and DUST shall be removed.		
11	6	At finish, SANDING SCRATCHES shall be:		
11	6	1	Inconspicuous beyond 72" (1830 mm).	E C P
11	6	2	Inconspicuous beyond 36" (915 mm).	E C P
11	6	3	Not permitted.	E C P
11	7	ORANGE PEEL (slight depressions in the surface similar to the skin of an orange) shall be:		
11	7	1	Inconspicuous beyond 72" (1830 mm).	E C P
11	7	2	Inconspicuous beyond 36" (915 mm).	E C P
11	7	3	Not permitted.	E C P
Continues next column ▼				

# SECTION 5

## Finishing

### GENERAL PRODUCT TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



## compliance requirements

5.4.4		Basic General Rules		
▲ From previous column				
11	<b>DEFECTS and WORKMANSHIP</b> (continued)			
11 8	<b>RUNS</b> (running of wet finish film in rivulets) shall be:			
11 8 1	Inconspicuous beyond 36" (915 mm).	E	C	P
11 8 2	Not permitted.	E	C	P
11 9	<b>SAGS</b> (partial slipping of finish film creating a curtain effect) shall be:			
11 9 1	Inconspicuous beyond 72" (1830 mm).	E	C	P
11 9 2	Inconspicuous beyond 36" (915 mm).	E	C	P
11 9 3	Not permitted.	E	C	P
11 10	<b>BLISTERING</b> (small, swelled areas like water blisters on human skin) shall be:			
11 10 1	Inconspicuous beyond 36" (915 mm).	E	C	P
11 10 2	Not permitted.	E	C	P
11 11	<b>BLUSHING</b> (whitish haze, cloudy) shall be:			
11 11 1	Inconspicuous beyond 36" (915 mm).	E	C	P
11 11 2	Not permitted.	E	C	P
11 12	<b>CHECKING</b> or <b>CRAZING</b> (crowfeet or irregular line separation) shall be:			
11 12 1	Inconspicuous beyond 36" (915 mm).	E	C	P
11 12 2	Not permitted.	E	C	P
11 13	<b>CRACKING</b> (formation like dried mud) shall be:			
11 13 1	Inconspicuous beyond 36" (915 mm).	E	C	P
11 13 2	Not permitted.	E	C	P
11 14	<b>PARTICLES</b> shall be:			
11 14 1	Inconspicuous beyond 36" (915 mm).	E	C	P
11 14 2	Not permitted.	E	C	P
11 15	<b>ADHESIVE SPOTS</b> shall be:			
11 15 1	Inconspicuous beyond 36" (915 mm).	E	C	P
11 15 2	Not permitted.	E	C	P
11 16	<b>FILLED NAIL HOLES</b> shall be:			
11 16 1	Inconspicuous beyond 108" (2745 mm).	E	C	P
11 16 2	Inconspicuous beyond 72" (1830 mm).	E	C	P
11 16 3	Inconspicuous beyond 36" (915 mm).	E	C	P
11 17	<b>FIELD REPAIRS</b> and <b>TOUCH UPS</b> shall be:			
11 17 1	Inconspicuous beyond 108" (2745 mm).	E	C	P
11 17 2	Inconspicuous beyond 72" (1830 mm).	E	C	P
11 17 3	Inconspicuous beyond 36" (915 mm).	E	C	P
Continues next column ▼				

5.4.4		Basic General Rules		
▲ From previous column				
12	If <b>ANTIMICROBIAL SURFACE</b> is required, it shall be:			
12 1	Within the United States, EPA, <a href="http://epa.gov">http://epa.gov</a> , registered for public health use.			
12 2	Within Canada, Health Canada, <a href="http://hc-sc.gc.ca">http://hc-sc.gc.ca</a> , recognized as having market authorization because of its granted Drug Identification Number (DIN).			
13	<b>FIRST CLASS WORKMANSHIP</b> is required in compliance with these standards.			

5.4.5		Basic Material Rules		
<b>1 BACK PRIMING/SEALING: OF CONCEALED SURFACES</b>				
1 1	Is required when factory finishing is required, and:			
1 1 1	Shall be of a compatible material and conform to the following application requirements:			
1 1 2	<b>STANDING</b> and <b>RUNNING TRIM</b> shall be sealed at 1 mil dry.	E	C	P
1 1 3	<b>BACKS</b> of wood wall and ceiling surfacing shall be sealed at 2 mil dry.	E	C	P
1 1 4	<b>CASEWORK</b> shall be sealed at 1 mil dry.	E	C	P
1 1 5	<b>DECORATIVE LAMINATE</b> faced woodwork shall be sealed at 1 mil dry.	E	C	P
2	<b>FLOW PROPERTIES</b> requires capability of drying and/or curing free of streaks, sags, or mottle.			
3	<b>CHEMICAL RESISTANCE</b> , if so specified, at exposed horizontal surfaces shall pass a 24 hour exposure test, whereas exposed vertical surfaces and semi-exposed surfaces shall pass a 1 hour exposure test (ASTM 1308, latest edition).			

# SECTION 5

## Finishing

### GENERAL PRODUCT TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



## compliance requirements

5.4.6 Basic Application Rules	
1	Requires <b>SANDING</b> before and during all finishing procedures and:
1 1	Exposed surfaces being block sanded parallel with the grain direction and the appropriate grit paper to prevent unacceptable blotchy and/or nonuniform appearance after staining or finishing.
1 2	Removal of handling marks or effects of exposure to moisture.
1 3	Steaming out of deep scratches.
1 4	Easing of sharp edges with a light sanding.
1 5	Removal of all raised grain, cross sanding, burnishing and machining marks, sanding inconsistencies, and/or defects.
1 6	Light sanding between coats per manufacturer's recommendations.
2	<b>FACTORY PRIMING</b> with one coat of primer applied to appropriate surfaces is required, however:
2 1	Factory sanding of the primed surfaces, after priming is not required.
3	<b>VENTILATION</b> , adequate and continuous, is required with sufficient heat to maintain temperatures above 65° F for 24 hours before, during, and 48 hours after application of finishes.
4	<b>OVER SPRAY</b> protection is required to prevent spray or droppings from fouling surfaces not being finished, as is:
4 1	Repair of damage as a result of inadequate or unsuitable protection.
5	<b>REMOVAL</b> of electrical plates, surface hardware, fittings, and fastenings prior to finishing operation is required, and:
5 1	Removed items are to be carefully stored, cleaned, and replaced on completion of work in each area, and:
5 2	Use of solvent for cleaning that might remove permanent finish is not allowed.
6	<b>CLEANING</b> of surfaces with a dry brush or a tack cloth before applying sealer, stain, or primer is required.
7	<b>SCRATCHES</b> , dents, marks, screw and nail holes, and rough edges shall be properly repaired before finishing.
8	<b>CONSISTENCY</b> of each coat shall be as recommended by the manufacturer.
9	<b>FILM THICKNESS</b> shall conform to manufacturer's data or recommendation.
Continues next column ▼	

5.4.6 Basic Application Rules	
▲ From previous column	
10	<b>FILLER</b> (including paste types) when specified shall be applied before sealers or topcoats. <span style="float: right;">E C P</span>
11	<b>THOROUGHLY DRY</b> each coat before sanding or applying additional coats.
12	<b>SAPWOOD</b> treatment:
12 1	At <b>EXPOSED SURFACES</b> :
12 1 1	Blending is not required. <span style="float: right;">E C P</span>
12 1 2	Sapwood must be blended in the final finish appearance. <span style="float: right;">E C P</span>
12 2	At <b>SEMI-EXPOSED SURFACES</b> , blending is not required.
13	<b>STAINING</b> at:
13 1	Dark stain finishes, the surface shall be wash coat sealed.
13 2	Oil stain shall be wipe applied in small areas at a time.
13 3	Non grain raising dye stains can be spray applied.
13 4	Open grain species shall be stained before applying sealer.
14	<b>GENERIC COATING SCHEDULE</b> :
14 1	<b>CONCEALED CASEWORK SURFACES</b> that abut walls, floors, and ceilings, require a sanding sealer or self seal system. <span style="float: right;">E C P</span>
14 2	<b>SEMI-EXPOSED</b> surfaces, including wood drawer sides and cabinet interiors and [bracketed items if specified] requires:
14 2 1	[Wash coat] (only at stained finish on close grain).
14 2 2	[Stain].
14 2 3	Sanding sealer.
14 2 4	Sand.
14 2 5	First topcoat. <span style="float: right;">E C P</span>
14 2 6	Second topcoat. <span style="float: right;">E C P</span>
Continues next column ▼	

# SECTION 5

## Finishing

### GENERAL PRODUCT TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



## compliance requirements

5.4.6		Basic Application Rules				
▲ From previous column						
14	GENERIC COATING SCHEDULE (continued)					
14	3	EXPOSED surfaces, including wood components on decorative laminate casework, with [bracketed items if specified] requires:				
14	3	1 [Wash coat] (only at stained finish on close grain).				
14	3	2 [Stain].				
14	3	3 Sanding sealer.				
14	3	4 Sand.				
14	3	5 First topcoat.				
14	3	6 Second topcoat.	E	C	P	
15 SYSTEM COATING SCHEDULE:						
15	1	SYSTEM - 1, LACQUER, NITROCELLULOSE including [bracketed items if specified] requires at:				
15	1	1 CLOSE GRAIN woods:				
15	1	1 1 [Wash coat, nitrocellulose] (only at stained finish).	E	C	P	
15	1	1 2 [Wash coat, vinyl] (only at stained finish).	E	C	P	
15	1	1 3 [Stain].				
15	1	1 4 Sealer, nitrocellulose.	E	C	P	
15	1	1 5 Sealer, vinyl.	E	C	P	
15	1	1 6 First topcoat.				
15	1	1 7 Second topcoat.	E	C	P	
15	1	2 OPEN GRAIN woods (including filled finish) requires:				
15	1	2 1 [Wash coat, nitrocellulose] (only at filled finish).	E	C	P	
15	1	2 2 [Wash coat, vinyl] (only at filled finish).	E	C	P	
15	1	2 3 [Stain].				
15	1	2 4 Filler (only at filled finish).	E	C	P	
15	1	2 5 Sealer, nitrocellulose.	E	C	P	
15	1	2 6 Sealer, vinyl.	E	C	P	
15	1	2 7 First topcoat.				
15	1	2 8 [Second topcoat] (only at filled finish).	E	C	P	
15	1	2 9 Second topcoat.	E	C	P	
Continues next column ▼						

5.4.6		Basic Application Rules				
▲ From previous column						
15	SYSTEM COATING SCHEDULE (continued)					
15	2	SYSTEMS - 2 and 3, LACQUER, PRE AND POST CATALYZED including [bracketed items if specified] requires at:				
15	2	1 CLOSE GRAIN woods:				
15	2	1 1 [Wash coat, vinyl] (only at stained finish).				
15	2	1 2 [Stain].				
15	2	1 3 Sealer, vinyl.				
15	2	1 4 First topcoat.				
15	2	1 5 Second topcoat.	E	C	P	
15	2	2 OPEN GRAIN woods (including filled finish):				
15	2	2 1 [Washcoat, vinyl] (only at filled finish).	E	C	P	
15	2	2 2 [Stain].				
15	2	2 3 Filler (only at filled finish).	E	C	P	
15	2	2 4 Sealer, vinyl.				
15	2	2 5 First topcoat.				
15	2	2 6 Second topcoat.	E	C	P	
15	3	SYSTEM - 4, LATEX ACRYLIC, WATER BASED including [bracketed items if specified] requires at:				
15	3	1 CLOSE and OPEN GRAIN woods;				
15	3	1 1 [Stain].				
15	3	1 2 Sealer, water reduced.				
15	3	1 3 First topcoat, water reducible acrylic.				
15	3	1 4 Second topcoat, water reducible acrylic.	E	C	P	
15	4	SYSTEM - 5, VARNISH, CONVERSION including [bracketed items if specified] requires at:				
15	4	1 CLOSE GRAIN woods:				
15	4	1 1 [Wash coat, reduced conversion varnish] (only at stained finish).	E	C	P	
15	4	1 2 [Wash coat, vinyl] (only at stained finish).	E	C	P	
15	4	1 3 [Stain].				
15	4	1 4 Sealer, reduced conversion varnish.	E	C	P	
15	4	1 5 Sealer, vinyl.	E	C	P	
15	4	1 6 First topcoat.				
15	4	1 7 Second topcoat.	E	C	P	
Continues next column ▼						

# SECTION 5

## Finishing

### GENERAL PRODUCT TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



## compliance requirements

5.4.6		Basic Application Rules	
▲ From previous column			
15	SYSTEM COATING SCHEDULE (continued)		
15 4	SYSTEM - 5, VARNISH, CONVERSION (continued)		
15 4 2	OPEN GRAIN woods (including filled finish):		
15 4 2 1	[Wash coat, reduced conversion varnish] (only at filled finish).	E	C P
15 4 2 2	[Wash coat, vinyl] (only at filled finish).	E	C P
15 4 2 3	[Stain].		
15 4 2 4	[Filler] (only at filled finish).	E	C P
15 4 2 5	Sealer, reduced conversion varnish.	E	C P
15 4 2 6	Sealer, vinyl.	E	C P
15 4 2 7	First topcoat.		
15 4 2 8	Second topcoat.	E	C P
15 5	SYSTEM - 6, OIL, PENETRATING including [bracketed items if specified] requires at:		
15 5 1	CLOSE and OPEN GRAIN woods:		
15 5 1 1	[Simulated oil finish].	E	C P
15 5 1 2	First coat, penetrating oil.		
15 5 1 3	Sealer, catalyzed vinyl.	E	C P
15 5 1 4	Scuff sand with appropriate grit.	E	C P
15 5 1 5	Brass wool rubdown.	E	C P
15 5 1 6	Second coat, penetrating oil.	E	C P
15 5 1 7	Wax coat.	E	C P
15 6	SYSTEM - 7, VINYL, CATALYZED including [bracketed items if specified] requires at:		
15 6 1	CLOSE GRAIN woods:		
15 6 1 1	[Wash coat, vinyl] (only at stained finish).	E	C P
15 6 1 2	[Wash coat, vinyl, catalyzed] (only at stained finish).	E	C P
15 6 1 3	[Stain].		
15 6 1 4	Sealer, vinyl.	E	C P
15 6 1 5	Sealer, vinyl, catalyzed.	E	C P
15 6 1 6	First topcoat.		
15 6 1 7	Second topcoat.	E	C P
Continues next column ▼			

5.4.6		Basic Application Rules	
▲ From previous column			
15	SYSTEM COATING SCHEDULE (continued)		
15 6	SYSTEM - 7, VINYL, CATALYZED (continued)		
15 6 2	OPEN GRAIN woods including filled finish:		
15 6 2 1	[Wash coat, vinyl] (only at filled finish).	E	C P
15 6 2 2	[Wash coat, vinyl, catalyzed] (only at filled finish).	E	C P
15 6 2 3	[Stain].		
15 6 2 4	Sealer, vinyl.	E	C P
15 6 2 5	[Filler] (only at filled finish).	E	C P
15 6 2 6	Sealer, vinyl, catalyzed.	E	C P
15 6 2 7	First topcoat.		
15 6 2 8	Second topcoat.	E	C P
15 7	SYSTEM - 8, ACRYLIC CROSS LINKING, WATER BASED including [bracketed items if specified] requires at:		
15 7 1	CLOSE GRAIN woods:		
15 7 1 1	[Wash coat, acrylic] (only at stained finish).	E	C P
15 7 1 2	[Stain].		
15 7 1 3	Sealer, acrylic.		
15 7 1 4	First topcoat.		
15 7 1 5	Second topcoat.	E	C P
15 7 2	OPEN GRAIN woods, including filled finish:		
15 7 2 1	[Wash coat, acrylic] (only at filled finish).	E	C P
15 7 2 2	[Stain].		
15 7 2 3	Sealer, acrylic.		
15 7 2 4	[Filler] (only at filled finish).	E	C P
15 7 2 5	First topcoat.		
15 7 2 6	Second topcoat.	E	C P
15 8	SYSTEM - 9 and 10, UV CURABLE, ACRYLATED EPOXY, POLYESTER, URETHANE, applicable only to PREMIUM GRADE and including [bracketed items if specified] requires at:		
15 8 1	CLOSE and OPEN GRAIN woods:		
15 8 1 1	[Stain].		P
15 8 1 2	Sealer with B-stage curing.		P
15 8 1 3	Sealer with full cure.		P
15 8 1 4	First topcoat with B-stage curing.		P
15 8 1 5	Second topcoat with full cure.		P
Continues next column ▼			

# SECTION 5

## Finishing

### GENERAL PRODUCT TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



## compliance requirements

<b>5.4.6</b>		<b>Basic Application Rules</b>	
<b>▲ From previous column</b>			
<b>15</b>	<b>SYSTEM COATING SCHEDULE</b> (continued)		
<b>15 9</b>	<b>SYSTEM - 11 and 12, POLYURETHANE, CATALYZED, or WATER BASED</b> including [bracketed items if specified] requires at:		
<b>15 9 1</b>	<b>CLOSE GRAIN</b> woods:		
<b>15 9 1 1</b>	[Wash coat, reduced vinyl sealer] (only at stained finish).		
<b>15 9 1 2</b>	[Stain].		
<b>15 9 1 3</b>	Sealer, vinyl.		
<b>15 9 1 4</b>	First topcoat.		
<b>15 9 1 5</b>	Second topcoat. <span style="float: right;">E C P</span>		
<b>15 9 2</b>	<b>OPEN GRAIN</b> woods (including filled finish):		
<b>15 9 2 1</b>	[Wash coat, reduced vinyl sealer] (only at filled finish). <span style="float: right;">E C P</span>		
<b>15 9 2 2</b>	[Stain].		
<b>15 9 2 3</b>	[Filler] (only at filled finish). <span style="float: right;">E C P</span>		
<b>15 9 2 4</b>	Sealer, vinyl.		
<b>15 9 2 5</b>	First topcoat.		
<b>15 9 2 6</b>	Second topcoat. <span style="float: right;">E C P</span>		
<b>15 10</b>	<b>SYSTEM - 13, POLYESTER, CATALYZED</b> , applicable only to <b>PREMIUM GRADE</b> and including [bracketed items if specified] requires at:		
<b>15 10 1</b>	<b>CLOSE and OPEN GRAIN</b> woods:		
<b>15 10 1 1</b>	[Stain]. <span style="float: right;">E C P</span>		
<b>15 10 1 2</b>	First sealer, polyester. <span style="float: right;">E C P</span>		
<b>15 10 1 3</b>	Second sealer, polyester. <span style="float: right;">E C P</span>		
<b>15 10 1 4</b>	Sand with appropriate grit. <span style="float: right;">E C P</span>		
<b>15 10 1 5</b>	Topcoat, polyester. <span style="float: right;">E C P</span>		
<b>15 10 1 6</b>	Rub and polish, mechanical. <span style="float: right;">E C P</span>		
<b>16</b>	<b>AFTER FINISHING:</b>		
<b>16 1</b>	Remove all spilled, splashed, or spattered finish materials.		
<b>16 2</b>	Remove all fingerprints or other marks.		
<b>16 3</b>	Provide a final dusting of all exterior and interior surfaces, including drawers.		
<b>16 4</b>	Provide properly labeled touch up materials to allow for minor touch up.		
<b>17</b>	<b>TOUCH UP</b> of:		
<b>17 1</b>	Factory finished materials are the responsibility of the installation contractor.		
<b>17 2</b>	Jobsite finished materials are the responsibility of the finishing contractor.		



# SECTION 5

## Finishing

### GENERAL PRODUCT TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



### compliance requirements

#### 5.5 BASIC CONSIDERATIONS

- 1 **TOLERANCES** typically found within NAAWS:
- 1.1 Fall into two **CATEGORIES**:
- 1.1.1 Factory fabricated joinery, assembly and construction - found in the **PRODUCT** portion.
- 1.1.2 Field installation joinery and assembly - found in the **INSTALLATION** portion.
- 1.2 **INCLUDE:**
- 1.2.1 Flatness of wood based panel products.
- 1.2.2 Solid wood to solid wood joints and assemblies.
- 1.2.3 Solid wood to wood veneer joints and assemblies.
- 1.2.4 Wood veneer to wood veneer joints and assemblies.
- 1.2.5 Solid wood to wood based product joints and assemblies (decorative laminate Solid Phenolic and panel products).
- 1.2.6 Solid surface to solid surface joints and assemblies.
- 1.3 **EXCLUDE:**
- 1.3.1 **BECAUSE of EXPANSION and CONTRACTION DIFFERENCES of non-wood products compared to solid wood and wood based products, these Standards do not apply tolerances regarding flatness or joinery to:** 
- 1.3.1.1 Solid wood to non-wood based products (which can be drywall, glass, metal, stone, acrylics, and other surfaces).
- 1.3.1.2 Non-wood to non-wood joints.
- 2 **VISUAL TESTING** is only applicable to exposed surfaces:
- 2.1 View finished surfaces in the ambient conditions in which they will be installed and used.
- 2.1.1 Perception of color varies with the light source and between individuals.
- 2.2 Tests apply only to new work at the time of installation.
- 2.2.1 They shall not be applied to refinishing conditions, except as agreed in advance between buyer and seller.

#### 5.5 BASIC CONSIDERATIONS (continued)

- 3 **TESTING for CONSISTENCY of GRAIN and COLOR:**
- 3.1 **COMPLIANCE WITH STANDARDS** for color and grain are highly subjective, and:
- 3.1.1 Each person's perception of color is unique.
- 3.1.2 The apparent color of a finished wood species is affected by many variables, such as:
- 3.1.2.1 Ambient lighting.
- 3.1.2.2 Cellular structure of the individual piece of wood.
- 3.1.2.3 Cutting or slicing of the wood.
- 3.1.2.4 Machining and sanding of the surface.
- 3.1.2.5 Orientation of the surface to the viewer.
- 3.2 **COMPLIANCE SHALL BE EVALUATED** (by comparison to an approved panel, minimum 8" x 12" [203 x 305 mm], that has been signed and dated and protected from light) based on the following conditions:
- 3.2.1 Viewing of the surfaces in the lighting and orientation in which they will be installed.
- 3.2.2 Observing a color and tone blending that is not significantly lighter than the lightest of the range, nor darker than the darkest of the range.
- 3.2.3 Because of natural variations in color and grain, it cannot be expected that all panels will match one particular sample exactly; however, shall match within the sample range submitted.
- 4 **SHEEN TEST**
- 4.1 Compliance shall be evaluated by comparison to the approved range of sample panels, that has been signed and dated and protected from light based on the following conditions:
- 4.1.1 Testing of the surfaces with a gloss meter, parallel to the grain, in identical lighting conditions:
- 4.1.1.1 When comparisons of sheen tests between the approved sample panels and the installed work show sheen readings within 10 points of each other they shall be considered to be in compliance.

# North American Architectural Woodwork Standards - 3.1

## **S E C T I O N - 06**

# MILLWORK

<b>Resources . . . . .</b>	<b><a href="#">146</a></b>
<b>Introduction . . . . .</b>	<b><a href="#">148</a></b>
<b>Recommendations . . . . .</b>	<b><a href="#">148</a></b>
<b>Specification Considerations . . . . .</b>	<b><a href="#">148</a></b>
<b>Design Resources . . . . .</b>	<b><a href="#">162</a></b>
<b>Compliance Requirements . . . . .</b>	<b><a href="#">163</a></b>
<b>Scope &amp; Default Stipulation . . . . .</b>	<b><a href="#">166</a></b>
<b>Basic Requirements . . . . .</b>	<b><a href="#">166</a></b>
<b>Installation Requirements . . . . .</b>	<b><a href="#">180</a></b>
<b>Tests . . . . .</b>	<b><a href="#">185</a></b>

### Within CANADA

#### SUPPORT

- **GUIDE SPECIFICATIONS** – Available for download in interactive digital format, including specification wording for Quality Assurance Program (GIS) at: <http://awmac.com/guide-specifications>
- **CONSULTATION** – Contact any of the local chapters for more information on the NAAWS or any other Architectural Woodwork Questions you may have. See below for contact information.
- **SPECIFICATION REVIEW** – Contact any of the local chapters if you would like your specifications reviewed for compliance to the NAAWS.
- **MANUFACTURER STANDARDS QUESTIONNAIRE (MSQ)** – AWMAC Manufacturer members have the opportunity to have at least one member of their staff study and write the MSQ. The MSQ is a questionnaire on the NAAWS and policy and procedures of the GIS program. A list of Manufacturer members that have passed the MSQ is available at: <http://awmac.com/members>
- **SEMINARS AND PRESENTATIONS** – Contact your local chapter to arrange an informative presentation on any Architectural Woodwork topic. Some topic options – GIS, NAAWS, How to Specify Quality Architectural Woodwork...
- **TRADE SHOWS** – Contact your local chapter to arrange for AWMAC to have a booth or do a presentation on Architectural Woodwork.
- **CONFERENCE** – AWMAC has an annual conference held at unique venues across Canada. The conferences provide an opportunity to learn more about Architectural Woodwork and network with Suppliers and Manufacturers from across Canada. More information is available at: <http://awmac.com/>
- **EDUCATION PARTNERS** – Contact the local chapters to find out more information about support for local Colleges and Universities offering woodworking related courses and programs.

#### QUALITY ASSURANCE

- **GUARANTEE AND INSPECTION SERVICE (GIS)** – The GIS is a national program designed to ensure that project owners get value and quality for their investment by:
  - Supporting architects and design professionals to achieve project plans and specifications; and
  - Helping contractors avoid problems such as cost overruns, delays and loss of reputation.More information is available at: <http://awmac.com/gis>

- **INSPECTION SERVICE** – A GIS Certified Inspector will inspect specific areas of concern on a project for compliance to the NAAWS and provide a written report. Contact your local chapter for more information.
- **EXPERT OPINION** – An expert will be appointed to inspect specific areas of concern on a project and provide a written report. Contact your local chapter for more information.

#### AWMAC CHAPTERS

- AWMAC British Columbia Chapter, Vancouver BC  
<http://bc.awmac.com>
- AWMAC Northern Alberta Chapter, Edmonton Alberta  
<http://nab.awmac.com>
- AWMAC Southern Alberta Chapter, Calgary Alberta  
<http://sab.awmac.com>
- AWMAC Saskatchewan Chapter, Saskatoon Saskatchewan  
<http://sk.awmac.com>
- AWMAC Manitoba Chapter, Winnipeg Manitoba  
<http://mb.awmac.com>
- AWMAC Ontario Chapter, Toronto Ontario  
<http://on.awmac.com>
- AWMAC Quebec Chapter, Montreal Quebec  
<http://qc.awmac.com>
- AWMAC Atlantic Chapter, Halifax Nova Scotia  
<http://atl.awmac.com>

# SECTION 6

## Millwork

## resources

### Within UNITED STATES

#### SUPPORT

- **GUIDE SPECIFICATIONS** - Available in interactive digital format including quality control options at: <http://woodworkinstitute.com/publications/architectural-woodwork-standards/>
- **AIA SEMINARS** - The Woodwork Institute is a Registered Provider of the American Institute of Architects (AIA), and its Continuing Education System (CES) program, check out our offerings at: <http://woodworkinstitute.com/architectural-resources/aia-seminars/> 
- **CONSULTATION** - Contact one of our Directors of Architectural Services (DAS) at: <http://woodworkinstitute.com/about-us-2/about-us/>
- **ACCREDITED FABRICATORS AND INSTALLERS** - Our AMC's (Accredited Millwork Company) represents the best fabricators and installers in our industry, check them out at: <http://woodworkinstitute.com/membership-listing-2/> 
- **CERTIFIED INDUSTRY PROFESSIONALS** - Our CMP's (Certified Millwork Professionals) represent the knowledge base of our industry, check them out at: <http://woodworkinstitute.com/membership-listing-2/> 
- **MILLWORK INDUSTRY PARTNERS** - Our MIP's (Millwork Industry Partners) represent the best of our industries material suppliers, check them out at: <http://woodworkinstitute.com/membership-listing-2/> 
- **ACKNOWLEDGED PRODUCTS LISTING** - If it's listed here, you are assured it meets NAAWS minimum requirements, find the listing at: <http://woodworkinstitute.com/acknowledged-product-listing/> 
- **CABINET DESIGN SERIES (CDS)** - Eliminate the need to include casework elevations in your architectural drawings, check out the CDS system in NAAWS "Design Resources" and access the cad files at: <http://woodworkinstitute.com/architectural-resources/cabinet-design-series/>

#### QUALITY ASSURANCE

- **BIDDER QUALIFICATION** - A discipline of bidder pre-qualification wherein your specifications protect you and your customer from the unknown: To be eligible to bid or negotiate this job, the subcontractor must be a Woodwork Institute Accredited Millwork Company (AMC) in good standing. <http://woodworkinstitute.com/architectural-resources/quality-assurance> 
- **CERTIFIED COMPLIANCE PROGRAM (CCP)** - A discipline of quality control used in conjunction with NAAWS providing an unbiased means of ensuring conformance to a project's plans and specifications. CCP, together with the use of the desired Grade(s) in the specifications, informs all parties of the design professional's expectations, without bidder discrimination. <http://woodworkinstitute.com/services/certified-compliance-program> 
- **MONITORED COMPLIANCE PROGRAM (MCP)** - A discipline of quality affirmation used in conjunction with the NAAWS which provides ongoing reviews/inspections of a project from its beginning through completion, ensuring strict conformance to the design intent throughout the millwork fabrication and installation process. <http://woodworkinstitute.com/services/monitored-compliance-program/> 
- **CERTIFIED SEISMIC INSTALLATION PROGRAM (CSIP)** - A standalone seismic assurance option which can be specified in conjunction with or without CCP or MCP, offering design professionals and project owners specific use of WI's seismic casework pre-approvals from California's Office of Statewide Health Planning and Development (OSHPD) without additional engineering costs and/or requirements, assuring proper backing has been installed in the walls when and where required. <http://woodworkinstitute.com/services/certified-seismic-installation-program/> 

# SECTION 6

## Millwork

## introductory information

### INTRODUCTION

Section 6 includes information on standing & running trim, door frames, window frames, sashes, blinds & shutters, screens, ornamental & miscellaneous millwork composed of solid wood and/or sheet products and their related parts.

Quality assurance can be achieved by adherence to these standards and will provide the owner a quality product at competitive pricing. Working with an AWMAC Member (in Canada) or a WI Certified Millwork Professional (CMP) (in the USA) and the WI Accredited Millwork Company (AMC) they represent to provide your woodwork will help ensure the understanding and performance of the quality level required. Illustrations in this Section are not intended to be all inclusive, other engineered solutions may be acceptable. In the absence of specifications; methods of fabrication are the manufacturer's choice. The design professional, by specifying compliance to these standards increases the probability of receiving the product quality expected.

### RECOMMENDATIONS

- **FIELD FINISHED**, include in Division 09 of the specifications:



- **BEFORE FINISHING**, exposed portions of woodwork shall have handling marks or effects of exposure to moisture, removed with a thorough, final sanding over all surfaces of the exposed portion and shall be cleaned before applying sealer or finish.
- **CONCEALED SURFACES** - Architectural woodwork that may be exposed to moisture, such as those adjacent to exterior concrete walls, etc., shall be primed.

- **REVIEW** the **GENERAL** portion of Sections 3 and 4 for an overview of the characteristics and the minimum acceptable requirements of lumber and/or sheet products that might be used herein.
- **STRUCTURAL MEMBERS**, grounds, in wall blocking, backing, furring, brackets, or other anchorage which becomes an integral part of the building's walls, floors, or ceilings, required for the installation of architectural woodwork are not to be furnished or installed by the architectural woodwork manufacturer or installer.
- **WOOD SASH** and **WINDOWS**, finish coats will be flowed onto the glass area approximately 1/16" (1.6 mm) to properly seal against weather, wind, and rain.

It is not recommended to use a razor blade to scrape the glass, as it might break the seal. A broad-blade putty knife is recommended to be used to protect the seal between the glass and the wood members.



- **FABRICATION METHODS** can affect the final appearance, especially regarding the direction of the grain and the visibility of the glue joints. As a design professional, you may wish to specify the method; however, it is recommended that an architectural woodwork firm be consulted before making a particular selection. Mock-ups may be required to visualize the end product.

### SPECIFICATION CONSIDERATIONS



- **FLAME SPREAD RATINGS** or special code compliance.
- **WINDOW PERFORMANCE** testing, labeling and hardware.
- **GLASS** type and thickness.
- **WOOD SPECIES** for exterior sash, shutters, or screens and frame parts and required level of decay resistance.

- **CLOSET** and **UTILITY SHELVING** shelf size, thickness, and support system.
- **ADA** or barrier-free compliance design and requirements.
- **QUALITY ASSURANCE OPTIONS:**

#### Within CANADA

- **AWMAC's GUARANTEE AND INSPECTION SERVICE (GIS)** - See NAAWS's Resources page and/or <http://awmac.com/gis>
- **AWMAC's INSPECTION SERVICE** - See NAAWS's Resources page and/or <http://awmac.com/gis>
- **AWMAC's EXPERT OPINION SERVICE** - See NAAWS's Resources page and/or <http://awmac.com/gis>

#### Within UNITED STATES

- **WI'S AMC BIDDER PRE-QUALIFICATION** - See NAAWS's Resources page and/or <http://woodworkinstitute.com/architectural-resources/quality-assurance>
- **WI'S CERTIFIED COMPLIANCE PROGRAM (CCP)** - See NAAWS's Resources page and/or <http://woodworkinstitute.com/services/certified-compliance-program>
- **WI'S MONITORED COMPLIANCE PROGRAM (MCP)** - See NAAWS's Resources page and/or <http://woodworkinstitute.com/services/monitored-compliance-program/>
- **WI'S CERTIFIED SEISMIC INSTALLATION PROGRAM (CSIP)** - See NAAWS's Resources page and/or <http://woodworkinstitute.com/services/certified-seismic-installation-program/>

# SECTION 6

## Millwork

## introductory information

### METHODS OF PRODUCTION

#### Flat Surfaces:

- **Sawing** - This produces relatively rough surfaces that are not utilized for architectural woodwork except where a "rough sawn" texture or finish is desired for design purposes. To achieve the smooth surfaces generally required, the rough sawn boards are further surfaced by the following methods:
- **Planing** - Sawn lumber is passed through a planer or jointer, which has a revolving head with projecting knives, removing a thin layer of wood to produce a relatively smooth surface.
- **Abrasive Planing** - Sawn lumber is passed through a powerful belt sander with tough, coarse belts, which remove the rough top surface.

#### Molded Surfaces:

Sawn lumber is passed through a molder or shaper that has knives ground to a pattern which produces the molded profile desired.

### SMOOTHNESS of FLAT and MOLDED SURFACES

**Planers and Molders:** The smoothness of surfaces which have been machine planed or molded is determined by the closeness of the knife cuts. The closer the cuts to each other (i.e., the more knife cuts per inch [KCPI]) the closer the ridges, and therefore the smoother the resulting appearance.




**Sanding and Abrasives:** Surfaces can be further smoothed by sanding. Sandpapers come in grits from coarse to fine and are assigned ascending grit numbers. The coarser the grit, the faster the stock removal. The surface will show the striations caused by the grit. Sanding with progressively finer grit papers will produce smoother surfaces.

### DESIGN and USE of RESOURCES

Moldings should be cut from lumber approximately the same size as the finished piece to make the best use of our natural resources. Designing moldings with the size of typical boards in mind has several advantages.

The typical 1" x 4" (25.4 mm x 101.6 mm) will yield a very nice 3/4" (19 mm) thick molding, but will not be thick enough to develop a molding which is a full 1" (25.4 mm) thick in finish dimension. The typical 2" x 4" (50.8 mm x 101.6 mm) piece of lumber can be made into moldings about 1-3/4" (44.5 mm) thick in a similar manner.

Deep or large moldings are often best cut from more than one piece and built up to make the final profile. Just as in the manufacturing of single moldings, this process minimizes waste and reduces the tendency of the finished profiles to twist, warp, cup, or bow as a result of removing too much material from either side of the initial board.




# SECTION 6

## Millwork

## introductory information

### EXAMPLES OF STANDING and RUNNING TRIM and RAIL PARTS





# SECTION 6


## Millwork

### introductory information


#### EXAMPLES OF STANDING and RUNNING TRIM




1 Cornice



4 Casing



2 Chair Rail



3 3-piece Base



5 Panel Molding



Figure: 6-005

# SECTION 6


Millwork

introductory information

## EXAMPLES OF STANDING and RUNNING TRIM and RAIL




1 Skylight Cornice



2 Crown



3 Panel Molding



4 Handrail

# SECTION 6

## Millwork

### introductory information

#### RADIUS MOLDINGS

Both traditional and nontraditional architectural styles often call for radius standing and running trim either in plan, elevation, or both. In situations where the size of the molding and the radius to which it is to be formed is such that a straight molding will not conform to the core, the architectural manufacturer can use several methods to fabricate radius moldings. Moldings applied to radii can be segmented, (typically only by direct specification) bent or steam bent, laminated and formed, preshaped, or machined to the radius. Manufacturers will fabricate the moldings in the longest practical lengths, with the purpose of minimizing the field joints.

- **Solid Machined** (Illustration A) woodwork typically starts with a large, often glued up piece of material, from which several nested pieces can be machined. Characteristically, this method limits the length of pieces that can be developed without a joint. It also yields a piece of material with the grain straight on the face, not following the curve. Profiles with a flat face can be machined from sheet products with an edgeband applied, yielding larger pieces with more consistent grain.

- **Core Veneered** (Illustration B) woodwork consists of core machined from lumber or panel product to which finish material is laminated as an exposed face. This technique is limited to certain profiles; however, it offers the ability to minimize glue joints and control grain directions.
- **Laminated Plies** (Illustration C) woodwork consists of thin, bendable plies of lumber in a form that will hold its shape without having to be secured to another surface. The curved piece can then be milled to the desired profile. The glue lines follow the edge grain and the curve, thus minimizing their visibility. The species of wood and the tightness of the radius determine the maximum thickness of each ply.
- **Block Laminated** (Illustration D) woodwork is made of solid machined pieces, glued up typically in a staggered fashion for width and length. When dealing with some cross sections, it can be advantageous to combine band sawing and laminating; however, it must be limited to certain profiles. It does, however, offer the ability to minimize glue joints, is used in radius jambs and often becomes the core for core veneered woodwork.

- **Kerfed** (Illustration E) woodwork consists of lumber with repeated saw cuts on the back face of the piece, perpendicular to the bend. The tightness of the radius determines the spacing and depth of the kerfs. Kerfing allows the piece to be bent to the required radius and then secured in place to hold the bend. Kerfing could result in “flats” on the face, which show in finishing. When dealing with a large radius, it is sometimes possible to stop the kerf prior to going through an exposed edge. In most cases, however, the kerf runs through, and the edge must be concealed.

**Cross Grain** in band sawn or laminated members and edges in veneer laminated members or where multiple layers are exposed by shaping may cause objectionable color variation when finished.

Unless specifically called out, the architectural manufacturer will have the option of which method to use for fabricating radius molding. Since the fabrication method determines the final appearance of the pieces, especially regarding the direction of grain and visibility of glue joints, the architect or designer may wish to specify the method. It is recommended that an architectural woodwork firm be consulted before making a selection. Mock-ups may be required to visualize the end product.




Figure: 6-007

# SECTION 6

## Millwork

### introductory information

#### SOLID LUMBER PANELING PATTERNS

The variety of solid lumber paneling is only limited by the imagination of the design professional. Virtually any machinable profile can be custom

manufactured. The following profiles are some of the traditional patterns associated with solid board paneling. They are not dimensioned intentionally, allowing the design professional to determine the scale and proportions most appropriate for the project.




Single Bead



Beaded Ceiling or Wainscot



Reveal Detail Options



Pickwick Paneling



Tongue and Groove "V" Joint




Beaded Siding



Rough Sawn w/ Lap Reveal




Simulated Lap Siding



Bevel Siding



Drop/Lap Siding



Molded Insert



Beaded Bevel Siding



Coved Paneling

# SECTION 6

## Millwork

## introductory information

### BUILT UP MOLDINGS FOR LARGER PROFILES

Used with permission of the Wood Molding and Millwork Producers Association.

- **Ceilings** are the most obvious area for "built up" moldings. This is primarily true of rooms with high ceilings. In low ceiling rooms (8' [2438 mm]), single molding profiles usually work best.

A series of "built up" moldings would have a tendency to make a low ceiling appear even lower. But if your ceilings are high (10' [3048 mm] or higher), there is no limit to the rich three dimensional elegance you can add to the room's appearance with the creative application of moldings. Below are several suggested combinations. Let your imagination create your own combinations and designs.

- **Chair Rails** are a very traditional method of breaking up walls, adding both interest and protection. They prevent the wall from being bumped or scuffed by chairs and can also be used to separate two types of decorating material such as paneling, wallpaper, and paint. Following are some variations of "built up" chair rail combinations.

### EXAMPLES OF CEILING PROFILES




Figure: 6-009

### EXAMPLES OF CHAIR RAIL PROFILES




Figure: 6-010

# SECTION 6

## Millwork

## introductory information

### BUILT UP MOLDINGS FOR LARGER PROFILES (continued)

- **Fireplaces** highlighted or framed with “built up” moldings is an excellent way to add depth and richness. Below are a few creative but simple to install profile combinations.






Figure: 6-011



casing / back band   casing / base cap   casing / half rounds   casing / base cap

Figure: 6-012

- **Doors and Windows** are most commonly done with single molding profiles, but by adding other patterns, the basic trim can easily be transformed into a window or door casing of classical depth and beauty. Installing plinth blocks at the bottom of casing further enhances the traditional look.




Figure: 6-013






Figure: 6-014

- **Base** the elaborate look of elegance can even be carried through to base moldings where the wall meets the floor, as illustrated in the following variations.



base / base shoe   base / stop   base / shoe / half round   s4s / shoe base & cap



base / base shoe   base / shingle   s4s / cove   s4s / bed base shoe


Figure: 6-015

# SECTION 6


## Millwork

### introductory information


#### BUILT-UP CORNICE and WALL TRIM EXAMPLES




Example 1




Example 2




Example 3




Example 4




Example 5




Example 6




Example 7



Example 8



Example 9



Example 10

Example 11


Figure: 6-016

# SECTION 6


## Millwork

## introductory information

### DOOR FRAME and JAMB EXAMPLES



### FRAME JOINERY EXAMPLES:




**LABELED** (flame spread-rated) jamb assemblies are typically available in 20-, 45-, 60-, and 90-minute classifications of limited design/species; however, new designs/ratings are in ongoing development.



Only firms recognized by applicable code officials are authorized to label a frame assembly. If a label will be required by the applicable code officials, it is the obligation of the design professional to so specify, and the obligation of the manufacturer to assure a properly licensed assembly. These standards do not cover labeled frames.




### WINDOW SASH and FRAME EXAMPLES



### SASH JOINERY EXAMPLES



### GLAZING EXAMPLES



### THERMAL INTEGRITY

Wood is a natural insulator that retains heat in winter without a thermal break, resists conduction of cold temperatures 2000 times better than aluminum, and is approximately 30% more thermally efficient than comparable aluminum windows. Wood's minimal conduction keeps the inside wood surface of windows warm in the winter and cool in the summer. Wood windows are available in single-, double-, and triple-glazing systems, increasing thermal efficiency.

# SECTION 6

## Millwork

## introductory information

### THERMAL INTEGRITY (continued)

**PERFORMANCE TESTING** is applicable only to complete exterior window units and, if required, must be specified and may include all or part of ASTM E 283, Air Infiltration; E 330, Loading; and/or E 547, Water Penetration. ASTM tests must be specified for the current ASTM Grade Level. <http://astm.org>.



### BLINDS and SHUTTERS

- **Hardware** must be specified, as it dictates the details of construction.
- **Manufacturer** does not typically supply, machine for, or install operating hardware, locking devices, pulls, lifts, etc.




Figure: 6-026

### SCREENS

- **Hardware** must be specified, as it dictates the details of construction.
- **Manufacturer** does not typically supply, machine for, or install operating hardware, locking devices, pulls, lifts, etc.

Typical bead detail examples:




Figure: 6-028




Figure: 6-027

### ORNAMENTAL WOODWORK

**TYPICAL SOURCES** of wood ornamentation are either mass-produced or custom carved and tooled.

- **Mass-produced** product is often limited in available species, sizes and design, which is often a variety of historic styles which may lack detail, however can be appropriate for many applications. Often the detail lacks clarity because of the tooling, sanding or finish. However, the product is relatively inexpensive, consistent in appearance and appropriate for many applications.
- **Custom carved** or **Tooled** work has a special appearance, with depth and clarity or crispness that machine tooling often cannot achieve. Because it is done by a skilled artisan there will be slight irregularities, but this is deemed desirable as it lends character and credence to the work. Whether the surface is sanded smooth or the texture of tool marks is left, is one of the points of discussion between the millwork company and carver.

# SECTION 6

## Millwork

## introductory information

### ORNAMENTAL WOODWORK

(continued)

Hand tooled and carved work has a special appearance. It has a depth and clarity or crispness which machine tooling often cannot achieve.

There are a number of reasons to contact a custom carver, when:

- Pieces required are impractical or impossible to shape on conventional factory machinery. Examples are tapering profiles as in keystones, acute (interior) corners such as in Gothic tracery and compound curves as in stair handrails.
- Small quantities are specified which are impractical or too expensive to fabricate by computerized methods.
- There is a need to replicate missing (hand carved) elements for restoration or renovation.
- Elements of specified dimensions are required and unavailable otherwise.
- A particular wood species is required.
- Customized logos or lettering is desired.
- Patterns are required for casting in another material such as plaster, metal, or glass.
- Uniqueness is valued by the customer.

**WORKING WITH AN ARTISAN** - custom carvers usually work by themselves in a studio situation, but this does not necessarily indicate limitations either in quality, production time or fabrication capability. Work is typically done on a commission basis, so it is common to expect reasonable lead times. They will need to know (from the millwork specifier or customer):

- **Type of element** - molding, capital, bracket, etc.

- **Sizes** - drawings showing elevations and Sections are absolutely necessary for accurate cost estimates, whether provided by the millwork company or drawn by the carver. Often the carver will redraw computer-generated designs or ones not full sized.
- **Species** - of wood and who will supply the "blanks". Finishes (paint grade, gilding, faux finish) should also be discussed.
- **Context** - and/or installed location should be made clear in order to understand lighting and the degree of detail necessary.
- **Schedule** - or completion date.
- **Budget** - if available as the carver can propose subtle changes in order to oblige a tight budget.

A rudimentary explanation of some carving terms will assist the design professional in communicating with the custom carver:

Moldings have multiple uses but one important one is to visually set apart various elements. For instance, they are transitions between the parts of the entablature. They accentuate the trim (architrave) around doors and windows, and around an arch (archivolt). The various terms depend primarily on the profiles, but there are a few terms which indicate use, location or size.

The curving profiles are often separated or off set by a relatively small flat called a fillet.

The small half round is an astragal, often decorated with beads or bead and billet. A larger half round, usually associated with the base of a column or base of a structure is called a torus (plural tori) molding, sometimes decorated with ribbon bundled Bay Laurel, Oak leaves, or reeds.

The ovolo is a quarter ellipse (Greek) or quarter round (Roman) profile, most often carved with egg and dart design, but many other possibilities make it a very popular molding.

The cyma recta is a double curved molding with the concave curve on the outside of the molding, pointing toward the viewer as if reaching, outward. The cyma reversa is the opposite, the convexity nearer the viewer and seems to support or bolster the element to which it is attached. Both profiles are often carved with foliage, generically termed acanthus leaf. Both of these profiles as well as the ovolo often have the curved portion separated from the fillet by deep valleys or quirks.

Medieval moldings were often made of a number of closely placed profiles, often with deep hollows and repeated rounds.

Romanesque architecture continued many of the same principles of classical architecture, though much of the decoration; such as column capitals became more idiosyncratic and depicted the profusion of natural foliage. The innovation of the pointed arch (loosely called the Gothic arch), ubiquitous in Gothic architecture, allowed buildings to soar to great heights and to redistribute weight. This allowed larger windows and the lacy stone work termed tracery. The designs of this tracery are geometrically derived from, for the most part, overlapping and intersecting circles. The circular voids are called foils and the pointed intersections cusps; thus a three lobbed design is a trefoil, while one of four is a quatrefoil, one of five is a cinquefoil. Tracery was found incorporated into the woodwork of choir stalls, paneling and memorial structures.

### ORNAMENTAL WOODWORK

(continued)

Much decoration was derived from nature in depictions of vines and animals. Of course, religious figures and symbols were also a primary motif. Foliage climbing the edges of pinnacles and spires consists of the leaves, called crockets, and the terminating leaves, a finial or (especially on pew ends) poppyhead. Moldings were made of multiple profiles and combined with running vines and crestings, or stylized leaves. Square flowers and ballflowers were often spaced along moldings. At intersections of the ribbed vaults were bosses, which depict foliage (like a rosette), figures, or heraldic devices. The Glossary contains selected and partially illustrated terms related to ornament and architecture.

**CARVER** should provide skill and knowledge through experience. The majority of the cost may be in the labor. Carving is a unique product which adds immeasurably to the character and attractiveness of the overall project, and:

- Carving that closely resembles what is represented in drawings and verbal descriptions.
- Product that is cleanly carved without distracting irregularities and chips or fuzz in the recesses. The agreed upon surface treatment: sanded, tool textured, primed or gilded, etc. should be consistent throughout.
- Completion in a timely manner as agreed upon.
- Quality in artistic handwork which is often a subjective matter, but proper communication and agreement among parties should reduce variance of interpretation.

**MILLWORKER** should make reasonable efforts to provide as much information as possible as to design, and material. If providing blanks, effort should be made to fabricate them as accurately as possible. Material should be straight grained and contain a minimum of glue lines and therefore, grain directional changes. Consultation concerning what should be provided (sizes, species, special fabrication such as turning) with the carver is essential.

There are four methods of depicting a design in wood:

- **Incised:** Designs are simply made by shallow grooves in the surface of the material.
- **Relief:** Most architectural carving is carved in relief. The degree to which the design is lifted off the surface is described as low or high relief.
- **Pierced:** Some voids in the design are literally cut through the material and are termed pierced carvings.
- **Sculpture:** Carving in-the-round or sculptural works are incorporated into architectural surroundings.

Unless required by the details and/or woodwork specifications, the manufacturer does not typically:

- **Provide or Prepare for** electrical, telephone, mechanical, or plumbing equipment;
- **Install** woodwork or furnish common in wall blocking, furring or hanging devices for the support or attachment of the woodwork;
- **Supply** exposed materials other than wood or plastic laminate;
- **Factory finish;** or
- **Supply** "stock" or specialty products. If they are to be supplied, they must be specified by a brand name or manufacturer.

**ORNAMENTAL WOODWORK** can be considered any addition to the purely functional and may partly rely on context for its aesthetic appeal. Among various definitions, the one pertinent here is: "Something that lends grace or beauty; a manner or quality that adorns." Ornamentation is defined as a decorative device or embellishment. A good example is the molding which can have functional uses such as covering joints, or with a profile, can be a design element. The profile can be further embellished or enriched by decorative carving.

Architectural carving combines the flat surfaces and clearly defined lines of geometry with the interpretive modeling of naturalistic forms.

Historic preservation, conservation and restoration disciplines are extensions of ornamental woodwork. Aspects of this work include, but are not limited to, stripping, repair, reconstruction, reuse of historic material, addition of new material, and special documentation for the work.

The United States Department of the Interior (<http://doi.gov/>), the National Park Service (<http://nps.gov/>), and the Historic Sites and Monuments Board of Canada (<http://parkscanada.gc.ca>) publish documents related to work under their jurisdiction. The most recent publications from these entities will provide valuable information for the design professional and the woodwork fabrication, finishing, and installation.

There are a number of related arts which are incorporated into wood constructions, such as stained glass, ceramic tiles, mosaic, fabric, plaster or composition ornament, faux finishes, metal hardware and stone inlays.

Excludes standing and running trim except as incorporated as integral parts of elements.

# SECTION 6

## Millwork

## introductory information

### FIRE-RETARDANT SOLID LUMBER

Fire Retardant treatments may affect the finishes intended to be used on the wood, particularly if transparent finishes are planned. The compatibility of finishes should be tested before they are applied.

### RECLAIMED or RECYCLED WOOD

#### DESIGN PROFESSIONAL RESPONSIBILITY

Use of unique materials like reclaimed or recycled wood requires a more active role of the design professional in sourcing and pre-approving desired material selections. There are no traditional guidelines with these types of materials to assure either the woodwork manufacturer or the design professional of achieving an intended result. There will be situations where the design professional will be required to directly participate in the individual piecemeal selection and layout process of the product.

**CONTRACT DOCUMENTS**, shall clearly indicate or delineate all material, fabrication, installation and applicable building code/regulation requirements with the clear understanding that incomplete design choices, changes in scope or material selection, lack of material selection, or design choices made after initial bid may impact the cost or not be possible.

The contract documents shall specifically list the material source and identifier, and address the allowable:

- Variation in color or tone, grain, distress, character, and patina.
- Defects, such as nail/bolt holes, checking, cracking, discoloration, milling marks, roughness in terms of quantity, locations, repetition, etc.
- Distortion in terms of straightness, cupping, flatness, etc.

See SECTION 3 for additional information.

### NONTRADITIONAL MATERIALS

Covers materials re-purposed from other industrial and manufacturing areas, but assigned to the woodwork manufacturer and treated similarly to traditional millwork items like wall paneling. From a design perspective considerations of appearance, color, finish, variation and relation are deemed important as they would be with traditional wood products.

Examples of non-traditional materials could be a fiber/cement panel designed for fire resistance, insulation re purposed as a decorative panel, metal products, cloth, acrylics, etc.

Because these materials are unique, contract documents, shall clearly indicate or delineate all of the necessary material, fabrication, installation and building code/regulation direction and requirements as may be applicable for the manufacturer/installer to reasonably accomplish the intended design concept.

### DESIGN RESOURCES



Is a perpetually expanding, web based resource of pictures, videos, illustrations, ideas and design concepts for inspiring thought and design creativity - assessable at: <http://naaws-design-resources.com>

Relative to this Section, offerings will include:

- Molding illustrations including:
  - Base
  - Picture
  - Casing
  - Panel
  - Crown
  - Bed
  - Handrail
  - Chair rail
- Historic ornamental woodwork
  - Illustrations
  - Terminology Glossary

# SECTION 6

## Millwork

### GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



## compliance requirements

**INCLUDING:** Standing & Running Trim, Door Frames, Window Frames, Sashes, Blinds & Shutters, Screens, Ornamental & Miscellaneous Millwork Composed of Solid Wood and/or Sheet Products

### 6.1 BASIC CONSIDERATIONS

#### 1 GRADE

1.1 These standards are characterized in three Grades of quality that may be mixed within a single project. Limitless design possibilities and a wide variety of lumber and veneer species, along with overlays, high pressure decorative laminates, factory finishes, and profiles are available in all three Grades.

1.2 **ECONOMY GRADE** defines the minimum quality requirements for a project's workmanship, materials, or installation and is typically reserved for woodwork that is not in public view, such as in mechanical rooms and utility areas.

1.3 **CUSTOM GRADE** is typically specified for and adequately covers most high quality architectural woodwork, providing a well defined degree of control over a project's quality of materials, workmanship, or installation.

1.4 **PREMIUM GRADE** is typically specified for use in those areas of a project where the highest level of quality, materials, workmanship, and installation is required.

2 **CONTRACT DOCUMENTS** shall govern if in conflict with these standards.

3 **ACCEPTABLE REQUIREMENTS** of lumber and/or sheet products used within this woodwork product section are established by Sections 3 and 4, unless otherwise modified herein.

4 **AESTHETIC COMPLIANCE REQUIREMENTS** apply only to surfaces visible after fabrication and installation, and:

4.1 Shall be judged from a normal viewing stance and considered compliant if inconspicuous when viewed from:

4.1.1 72" (1830 mm) for Economy Grade

4.1.2 48" (1219 mm) for Custom Grade

4.1.3 24" (610 mm) for Premium Grade

### 6.1 BASIC CONSIDERATIONS (continued)

4.2 For **RECLAIMED** or **RECYCLED WOOD**, the aesthetic compliance requirements of NAAWS does not apply, such shall be as agreed between owner/design professional and the woodwork manufacturer/installer.

4.3 For **NON-TRADITIONAL MATERIALS**, the aesthetic compliance requirements of NAAWS does not apply, such shall be as agreed between owner/design professional and the woodwork manufacturer/installer.

#### 5 EXPOSED SURFACES INCLUDE:

5.1 Visible surfaces of standing/running trim, door/window frames, sashes, screens, blinds, shutters, and miscellaneous woodwork, excluding:

5.1.1 Top horizontal surfaces 80" (2032 mm) or more above the finished floor, unless visible from above.

5.1.2 Bottom horizontal surfaces 42" (1067 mm) or less above the finished floor.

#### 6 SEMI-EXPOSED SURFACES INCLUDE:

6.1 Top horizontal surfaces 80" (2032 mm) or more above the finished floor, unless visible from above.

6.2 Bottom horizontal surfaces 42" (1067 mm) or less above the finished floor.

#### 7 CONCEALED SURFACES INCLUDE:

7.1 Non visible surfaces attached to and/or covered by another.

7.2 Non visible blocking, spacers, etc., used for attachment.

8 To **PREVENT TELEGRAPHING**, inset solid wood edging when used must have similar moisture content as panel core, be glued securely and calibrated with panel core thickness prior to being laminated with a wood veneer on both faces.

# SECTION 6

## Millwork

### GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



## compliance requirements

### 6.1 BASIC CONSIDERATIONS (continued)

#### 9 INDUSTRY PRACTICES

- 9.1 **FLAME SPREAD RATED WOOD DOOR FRAMES** shall be of the manufacturer's standard design and construction, conforming to the requirements of their applicable labeling service.
- 9.1.1 **These standards do not cover labeled frames.** 
- 9.1.1.1 Only firms recognized by applicable code officials are authorized to label a frame assembly. If a label will be required by the applicable code officials, it is the obligation of the design professional to so specify, and the obligation of the manufacturer to assure a properly licensed assembly.
- 9.2 **STRUCTURAL MEMBERS**, grounds, in wall blocking, backing, furring, brackets, or other anchorage that becomes an integral part of the building's walls, floors, or ceilings, that are required for the installation of architectural woodwork are not furnished or installed by the architectural woodwork manufacturer or installer.
- 9.3 **WALL, CEILING, and/or OPENING VARIATIONS** in excess of 1/4" (6.4 mm) or **FLOORS** in excess of 1/2" (12.7 mm) in 144" (3658 mm) of being plumb, level, flat, straight, square, or of the correct size are not acceptable for the installation of architectural woodwork, nor is it the responsibility of the installer to scribe or fit to tolerances in excess of such.
- 9.4 **PRIMING** of architectural woodwork is not the responsibility of the manufacturer and/or installer, unless the material is being furnished pre-finished.
- 9.5 **RADIUS MOLDINGS** are laminated and formed, pre-shaped, or machined to the radius and fabricated in the longest practical lengths to minimize installer joints.
- 9.5.1 The **METHOD of FABRICATION**, unless specified otherwise, is the manufacturer's choice.

# SECTION 6

## Millwork

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated,  
the rule applies to all Grades equally



## compliance requirements

### 6.2 SCOPE

- 1 All exposed interior and exterior standing and running wood trim members, door frames, window frames, sashes, blinds and shutters, screens, and ornamental and miscellaneous millwork that are not structural in nature.
- 2 **TYPICAL INCLUSIONS**, Interior or Exterior:
  - 2.1 Base; shoe, casing, picture, ceiling, apron, and stool molds.
  - 2.2 Wood thresholds, plinth, corner blocks, and other exposed wood trim.
  - 2.3 Ornamental & Miscellaneous Millwork Composed of Solid Wood and/or Sheet Products.
  - 2.4 Decorative turned or boxed wood columns, pilasters, false beams, screens, or louvers, including brackets, corbels, pedestals, finials, drops, and lookouts.
  - 2.5 Band sawn, scrolled, turned, or carved ornamental woodwork.
  - 2.6 Solid, paneled, or veneered wood door jambs/frames with sidelights, louvers, transoms, and borrowed lights, including extensions, linings, stops, mullions, transom bars, sills, other components, and flame spread ratings.
  - 2.7 Mill built sliding door and sash pockets, including operating hardware.
  - 2.8 Cleat and standards/bracket supported shelves, including hook strips, cleats, rods, and required hardware.
  - 2.9 Cornice moldings, corner and edge boards, fascia and soffits, water tables, and casing.
  - 2.10 Metal sash surrounds.
  - 2.11 Wood belt and base courses, verge boards, and miscellaneous moldings.
  - 2.12 Decorative sun screens, trellises, louvers, blinds, and window/porch screens.
  - 2.13 Board and cleat, louvered, or paneled blinds or shutters, fixed or active.
  - 2.14 Seat and bench parts, duck boards, and similarly worked wood members.
  - 2.15 Sheet products applied in the form of multiple boards, including decorative laminate or other sheet products.
  - 2.16 Staff moldings, blind stops, and parting beads, attached flashing, sill pans, inside/back linings, and balances.

### 6.2 SCOPE (continued)

- 2 **TYPICAL INCLUSIONS** (continued)
  - 2.17 Wood caps, pediments, casing, stucco molds, or stops for exterior door frames.
  - 2.18 Columns, pilasters, brackets, corbels, paneling, and moldings integral to a frame's design.
  - 2.19 Elliptical, segment, or full circle head, arched, peaked, gothic, irregular, and divided entrance specialty units.
  - 2.20 Frames and sash for double hung, hopper, tilt/turn, casement, awning, sidelights, clerestory, and fixed windows.
  - 2.21 Glass and glazing unless specified otherwise; open sash may be included by agreement.
  - 2.22 Ornamental woodwork making use of molded, shaped, and carved elements to create a decorative appearance.
- 3 **TYPICAL EXCLUSIONS**
  - 3.1 Any structural wood framing, timbers or sheet products, sheathing, siding, decking, or planking and S4S boards or battens.
  - 3.2 Any composition or plaster wallboards or coverings, lath, shingles, or shakes.
  - 3.3 Any bucks, grounds, stripping, furring, in wall blocking, reglets, cant strips, or waste molding.
  - 3.4 Any wood members not exposed.
  - 3.5 Wood wainscoting and caps, wall, ceiling, soffit, or decorative paneling.
  - 3.6 Non wood, carved, or embossed moldings, including paper, vinyl, or foil wrapped.
  - 3.7 Commodity frames not governed by these standards.
  - 3.8 Machining of frames for hardware supplied by others.
  - 3.9 Any metal stops, frames, or wood cores for metal frames.
  - 3.10 Hardware, except as noted above.
  - 3.11 Priming or painting, glass and glazing, weather stripping, operating hardware, and/or sash balances.
  - 3.12 Flush or stile and rail doors.
  - 3.13 Pre-manufactured or stock window units.

# SECTION 6

## Millwork

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



# compliance requirements

### 6.2 SCOPE (continued)

- 3 TYPICAL EXCLUSIONS** (continued)
- 3.14 Fence posts or fence material where standard stock lumber yard material is indicated.
  - 3.15 Metal sash, skylights, screens, or weather stripping/milling for same.
  - 3.16 Cabinet sash and hardware.
  - 3.17 Roller screens and hardware.
  - 3.18 Factory assembled shelving units.
  - 3.19 In wall or ceiling blocking.
  - 3.20 Pre-manufactured or stock screen units.
  - 3.21 Providing or preparing for electrical, telephone, mechanical, or plumbing equipment.
  - 3.22 Supplying exposed materials other than those covered herein or specified to be included.
  - 3.23 Factory finish.

### 6.3 DEFAULT STIPULATION

- 1 If not otherwise specified or indicated in the contract documents, work shall be unfinished, Custom Grade, solid stock softwood intended for opaque finish.



### 6.4 RULES

- 1 The following rules shall govern unless a project's contract documents require otherwise.
- 2 These rules are intended to provide a well defined degree of control over a project's quality of materials and workmanship.
- 3 **ERRATA**, published at <http://naaws-errata.com>, shall take precedence over these rules, subject to their date of posting and a project's bid date.



#### 6.4.4 Basic General Rules

1	<b>AESTHETIC</b> grade rules apply only to exposed and semi-exposed surfaces visible after installation.
2	<b>WOODWORK</b> not addressed herein shall be manufactured from solid stock, laminated stock, veneered stock, or a combination thereof.
3	<b>LUMBER</b> shall conform to the requirements established in Section 3.
4	<b>SHEET PRODUCTS</b> shall conform to the requirements established in Section 4.
5	<b>EXPOSED SURFACES</b> include:
5 1	Visible surfaces of standing/running trim, door/window frames, sashes, screens, blinds, shutters, and miscellaneous woodwork, including:
5 1 1	Top horizontal surfaces less than 80" (2032 mm) above the finished floor, unless visible from above.
5 1 2	Bottom horizontal surfaces 42" (1067 mm) or more above the finished floor.
6	<b>SEMI-EXPOSED SURFACES</b> include:
6 1	Top horizontal surfaces 80" (2032 mm) or more above the finished floor, unless visible from above.
6 2	Bottom horizontal surfaces less than 42" (1067 mm) above the finished floor.
7	<b>CONCEALED SURFACES</b> include:
7 1	Non visible surfaces attached to and/or covered by another.
7 2	Non visible blocking, spacers, etc., used for attachment.
8	<b>STANDING</b> and <b>RUNNING TRIM</b> shall be furnished as material only, not assembled.

Continues next column ▼

# SECTION 6

## Millwork



GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



# compliance requirements

6.4.4 Basic General Rules	
▲ From previous column	
9	Where <b>MULTIPLE OPTIONS</b> are permitted, it shall be the manufacturer's choice unless specified otherwise.
10	<b>FLAME SPREAD RATING</b> , if required, shall be so specified.
11	<b>SPECIFIC PROFILE</b> , if required, shall be so specified or drawn.
12	<b>SPECIAL ORNAMENTAL DETAIL</b> or joinery, if required, shall be so specified or drawn.
13	<b>CATHEDRAL</b> type figure shall be achieved by:
13 1	A single component in "AA" Face Grade.
13 2	The split heart method in Face Grades "A - D", and:
13 2 1	Each half of a split heart shall be subject to the minimum component width requirements for Face Grade "B."
14	<b>EXTERIOR APPLICATION</b> requires:
14 1	Type I, waterproof adhesive.
14 2	Sheet products be of exterior type.
14 3	Nails and screws be corrosion resistant.
14 4	Preservative treatment of exposed and concealed exterior frame members in accordance with Section 3.
15	<b>GLUING</b> or <b>LAMINATION</b> shall be in accordance with the <b>ADHESIVE GUIDELINES</b> within the <b>APPENDIX</b> , and: 
15 1	<b>DELAMINATION</b> or <b>SEPARATION</b> shall not occur.
15 2	<b>LUMBER</b> shall conform to the requirements established in Section 3.
15 3	<b>SHEET PRODUCTS</b> shall conform to the requirements established in Section 4.
16	<b>CUTOUTS</b> at <b>HPDL</b> or <b>SOLID SURFACE</b> shall have a minimum 1/4" (6.4 mm) radius at inside corners.
17	<b>FIRST CLASS WORKMANSHIP</b> is required in compliance with these standards. 

6.4.5 Basic and Specific Material Rules	
1	<b>LUMBER, VENEERED PROFILE</b> or <b>SHEET PRODUCTS</b> shall be of the species and Grade specified, and:
1 1	Shall conform in finish width, thickness, and length of lumber.
1 2	Shall not have defects, either natural or manufactured, exceeding those permitted, however:
1 2 1	Permits unlimited finger joints. <span style="float: right;">E C P</span>
1 2 2	Finger joints not permitted. <span style="float: right;">E C P</span>
1 3	If solid lumber, requires plain sawn lumber.
1 4	At veneered profile, face veneer shall be of sufficient thickness to prohibit show through and requires:
1 4 1	Cores of solid or laminated wood, medium density fiberboard or other suitable material.
1 4 2	Fleece backing.
2	<b>NATURAL</b> and <b>MANUFACTURED DEFECTS</b> are permitted, if covered by adjoining members or otherwise concealed when installed.
3	<b>FIGURE</b> is not a function of a species grade and must be specified in the contract document.
4	<b>WARP</b> that can be held flat and straight with normal attachment is permitted.
<b>RADIUS WOODWORK</b> requires construction of solid machined, block laminated, laminated plies, core veneered, or kerfed solid stock:	
5	
5 1	Chord segmentation is not permitted. 
Continues next column ▼	

# SECTION 6

## Millwork


GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally

**E C P**

# compliance requirements

6.4.5		Basic and Specific Material Rules				
▲ From previous column						
5	<b>RADIUS WOODWORK</b> (continued)					
5	2	Members of solid stock or block laminations shall be furnished in such sections as to avoid pronounced cross grain and reduce joints to a minimum, and:				
5	3	Glue shall be selected for color to avoid a prominent glue line.				
6 For <b>OPAQUE FINISH</b> :						
6	1	Medium density fiberboard (MDF) is permitted.				
6	2	Veneer is permitted; however:				
6	2	1	SPECIES of manufacturer's choice, closed grain hardwood conforming to ANSI/HPHA HP-1 (latest Edition), <a href="http://hpva.org">http://hpva.org</a> , definitions and characteristics for:			
6	2	1	1	Grade - D.	E C P	
6	2	1	2	Grade - C.	E C P	
6	2	1	3	Grade - B.	E C P	
7 For <b>TRANSPARENT FINISH, VENEER</b> :						
7	1	SPECIES of manufacturer's choice, hardwood conforming to ANSI/HPHA HP-1 (latest Edition), <a href="http://hpva.org">http://hpva.org</a> , definitions and characteristics for:				
7	1	1	Grade - B.	E C P		
7	1	2	Grade - A.	E C P		
7	1	3	Grade - AA.	E C P		
7	2	<b>SLICING</b> of:				
7	2	1	Manufacturer's choice.			E C P
7	2	2	Plain sliced.			E C P
7	3	<b>MATCHING ADJACENT LEAVES</b> be:				
7	3	1	Manufacturer's choice.			E C P
7	3	2	Book matching.			E C P
7	4	<b>MATCHING WITHIN PANEL FACE</b> be:				
7	4	1	Running.			E C P
7	4	2	Balance.			E C P
7	5	<b>MATCHING BETWEEN ADJACENT PANELS</b> be:				
7	5	1	Manufacturer's choice.			E C P
7	5	2	Compatible for color and grain.			E C P
7	5	3	Well matched for color and grain.			E C P
7	5	4	<b>END, SEQUENCE, and BLUE PRINT MATCHING</b> shall be specified.			
Continues next column ▼						

6.4.5		Basic and Specific Material Rules				
▲ From previous column						
8	<b>EXPOSED SURFACES:</b>					
8	1	Require end grain be kept to a minimum.			E C P	
8	2	Require ends be self returned with no end grain showing.			E C P	
						
8	3	Require sheet product edges to be edgebanded with the same species as the face:			E C P	
8 4 For <b>TRANSPARENT FINISH</b> :						
8	4	1	Permits hardwood or softwood.			E C P
8	4	2	Permits only one species for the entire project.			E C P
8	4	3	Prohibits finger joints.			E C P
8	4	4	Requires adhesive, used for laminating, to be selected for color to avoid a prominent glue line.			E C P
8	4	5	Requires lumber (including block segments or veneer of laminated material) and sheet products to be compatible in color and grain.			E C P
8	4	6	Requires lumber (including block segments or veneer of laminated material) to be well matched for color and grain; sheet products shall be compatible in color with solid stock, and adjacent sheet products shall be well matched for color and grain.			E C P
8	4	7	Requires radius frames to be constructed of laminated plies or core veneered.			E C P
						
8	4	8	Requires <b>INTERSECTIONS</b> of radius and straight members to be splined or half lapped, securely glued, and mechanically fastened.			E C P
8 4 9 At <b>BLOCK LAMINATION</b> :						
8	4	9	1	Requires segments to be cut from the same board, when practical.		E C P
8	4	9	2	Requires segment joints to be staggered.		
8	4	9	3	Requires adjacent segment ends to have a similar grain angle.		E C P
Continues next column ▼						

# SECTION 6

## Millwork

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally

**E C P**

# compliance requirements

6.4.5		Basic and Specific Material Rules		
▲ From previous column				
8	<b>EXPOSED SURFACES</b> (continued)			
8 4	For <b>TRANSPARENT FINISH</b> (continued)			
8 4 10	At <b>VENEER LAMINATIONS</b> :			
8 4 10 1	Requires exposed layers to be resawn from the same or matched boards, and:			
8 4 10 1 1	Veneer layers to be reassembled in the same order and orientation as cut.	E	C	P
8 4 11	Have visible <b>EDGES, REVEALS, and/or SPLINES</b> , when appropriate, that are:			
8 4 11 1	Full length.			
8 4 11 2	Manufacturers' choice.	E	C	P
8 4 11 3	Match species of panel face.	E	C	P
8 4 11 4	Compatible for color and grain.	E	C	P
8 4 11 5	Well matched for color and grain.	E	C	P
8 4 11 6	A minimum of 0.020" (0.5 mm) nominal thickness that precludes show through of core.	E	C	P
<b>9 SEMI-EXPOSED SURFACES:</b>				
9 1	<b>OPAQUE</b> finish, permits natural and manufacturing defects, provided the surface is filled solid.			
<b>10 CONCEALED SURFACES:</b>				
10 1	Permits voids, wane, and unfilled knots.			
10 2	Requires blocking or shims to be of a compatible material.			
<b>11 DOOR and WINDOW FRAMES:</b>				
11 1	<b>FLAT STYLE</b> cased opening or with applied stop, shall be:			
11 1 1	Minimum of 11/16" (17 mm) in thickness.	E	C	P
11 1 2	Minimum of 3/4" (19 mm) in thickness.	E	C	P
11 1 3	Minimum of 1-1/16" (27 mm) in thickness.	E	C	P
11 1 4	Stops shall be 3/8" (9 mm) in thickness.	E	C	P
11 1 5	Stops shall be 1/2" (13 mm) in thickness.	E	C	P
11 2	<b>RABBETED STYLE</b> shall be:			
11 2 1	Minimum of 1-1/16" (27 mm) in thickness.	E	C	P
11 2 2	Minimum of 1-5/16" (33 mm) in thickness.	E	C	P
11 2 3	Minimum of 1-1/2" (38 mm) in thickness.	E	C	P
Continues next column ▼				

6.4.5		Basic and Specific Material Rules		
▲ From previous column				
11	<b>DOOR and WINDOW FRAMES</b> (continued)			
11 3	<b>PLOUGHED STYLE</b> with T-stop, shall be:			
11 3 1	Minimum of 3/4" (19 mm) in thickness.	E	C	P
11 3 2	Minimum of 1-1/16" (27 mm) in thickness.	E	C	P
11 3 3	Stops shall be minimum 3/4" (19 mm) in thickness set in 1/4" (6 mm) groove.	E	C	P
11 4	<b>SPLIT STYLE</b> with T-stop, shall be:			
11 4 1	Minimum of 11/16" (17 mm) in thickness at thin member.	E	C	P
11 4 2	Minimum of 3/4" (19 mm) in thickness.	E	C	P
<b>11 5 VENEERED CONSTRUCTION:</b>				
11 5 1	Shall be of the same species.			
11 5 2	Is permitted for use only in climate controlled environments, and face veneer shall:			
11 5 2 1	Be of sufficient thickness to prohibit show through.			
11 5 2 2	Extend over the edgebands when edgebands exceed 1/8" (3.2 mm) in thickness.			
11 6	<b>FLAME SPREAD RATING</b> shall be of the manufacturer's permitted design and construction in conforming with the requirements of their applicable labeling service.			
<b>12 SASH:</b>				
12 1	<b>LUMBER SPECIES</b> shall be:			
12 1 1	Pine, Fir, Hemlock, or Larch.	E	C	P
12 1 2	Idaho White Pine, Northern White Pine, American or African Mahogany, or Douglas Fir.	E	C	P
12 1 3	Ponderosa and Sugar Pine, Teak (except at opaque finish), American Mahogany, White Oak, or Western Red Cedar.	E	C	P
12 2	Shall be a minimum of 1-3/8" (35 mm) in thickness.	E	C	P
12 3	Shall be a minimum of 1-3/4" (44 mm) in thickness.	E	C	P
12 4	May require the minimum thickness to be different than this standard in consideration of the size of the window and the applicable codes.			
Continues next column ▼				

# SECTION 6

## Millwork

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally

**E C P**

# compliance requirements

6.4.5 Basic and Specific Material Rules					
▲ From previous column					
<b>13</b> <b>BLINDS and SHUTTERS:</b>					
<b>13 1</b> <b>LUMBER SPECIES</b> shall be:					
13	1	1	Pine, Fir, Hemlock, or Larch.	E	C P
13	1	2	Idaho White Pine, Northern White Pine, American or African Mahogany, or Douglas Fir.	E	C P
13	1	3	Ponderosa and Sugar Pine, Teak (except at opaque finish), American Mahogany, White Oak, or Western Red Cedar.	E	C P
<b>13 2</b> <b>STILES and RAILS</b> shall be:					
<b>13 2 1</b> Solid stock.					
<b>13 2 2</b> Minimum of 3/4" (19 mm) in thickness.					
<b>13 3</b> <b>PANELS:</b>					
<b>13 3 1</b> <b>FLAT</b> shall be:					
<b>13 3 1 1</b> <b>SOLID WOOD:</b>					
13	3	1	1	Minimum 1/2" (12.7 mm) in thickness and maximum 23-3/4" (603 mm) across the grain in width.	E C P
13	3	1	2	Minimum 3/4" (19 mm) in thickness and maximum 13-3/4" (350 mm) across the grain in width.	E C P
13	3	1	3	Not permitted.	E C P
<b>13 3 1 2</b> <b>SHEET PRODUCT:</b>					
<b>13 3 1 2 1</b> Minimum 1/4" (6.4 mm) in thickness.					
<b>13 3 1 2 2</b> Minimum 1/2" (12.7 mm) in thickness.					
<b>13 3 2</b> <b>RAISED</b> shall be:					
<b>13 3 2 1</b> <b>SOLID WOOD:</b>					
<b>13 3 2 1 1</b> Permitted in any dimension.					
13	3	2	1	2	Minimum 3/4" (19 mm) in thickness and maximum in width 13-3/4" (350 mm) across the grain.
13	3	2	1	3	Not permitted.
<b>13 3 2 2</b> <b>VENEERED:</b>					
<b>13 3 2 2 1</b> Minimum 1/2" (12.7 mm) in thickness.					
<b>13 3 2 2 2</b> Minimum 3/4" (19 mm) in thickness.					
Continues next column ▼					

6.4.5 Basic and Specific Material Rules					
▲ From previous column					
<b>14</b> <b>SCREENS:</b>					
<b>14 1</b> Shall be solid lumber.					
<b>14 1</b> <b>LUMBER SPECIES</b> shall be:					
14	1	1	Pine, Fir, Hemlock, or Larch.	E	C P
14	1	2	Idaho White Pine, Northern White Pine, American or African Mahogany, or Douglas Fir.	E	C P
14	1	3	Ponderosa and Sugar Pine, Teak (except at opaque finish), American Mahogany, White Oak, or Western Red Cedar.	E	C P
<b>14 2</b> <b>FRAME THICKNESS</b> shall be:					
<b>14 2 1</b> Manufacturers' choice.					
<b>14 2 2</b> Minimum of 3/4" (19 mm).					
<b>14 2 3</b> Minimum of 1" (25 mm).					
<b>14 3</b> <b>FRAME PARTS</b> shall be coped:					
<b>14 3 1</b> Not required.					
<b>14 3 2</b> With mortise and tenon, slot mortise and tenon, or doweled joinery.					
<b>14 3 3</b> With haunched blind mortise and tenon or doweled joinery.					
<b>14 3 4</b> With half lap joints permitted at intersecting muntins.					
<b>14 4</b> <b>SCREEN MOLD</b> shall be of sufficient thickness and width to cover wire edges.					
<b>14 5</b> <b>WIRE CLOTH</b> shall be:					
<b>14 5 1</b> Nylon or fiberglass mesh.					
<b>14 5 2</b> Aluminum or bronze wire (18 x 14 mesh).					
<b>14 5 3</b> Bronze wire (18 x 14 mesh).					
<b>14 5 4</b> Secured:					
<b>14 5 4 1</b> At manufacturers' option.					
<b>14 5 4 2</b> At a maximum of 3" (76 mm) on center with staples.					
<b>14 5 4 3</b> By force into a kerf by use of a spline or a projecting bead.					
Continues next column ▼					

# SECTION 6

## Millwork

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally

<b>E</b>	<b>C</b>	<b>P</b>
----------	----------	----------

# compliance requirements

6.4.5		Basic and Specific Material Rules				
▲ From previous column						
15	1	<b>CLOSET and UTILITY SHELVING:</b>				
15	1	Shall be one type of material for each project:				
15	1	1	Medium Density Fiberboard (MDF), particleboard, or veneer core product.	E	C	P
15	1	2	Medium Density Fiberboard (MDF), particleboard with UV filled coating, or veneer core product.	E	C	P
15	1	3	Medium Density Fiberboard (MDF), thermoset overlay on particleboard, or veneer core product.	E	C	P
15	2	Shelf thickness shall be a minimum of 3/4" (19 mm).				
15	3	Wood shelf rods shall be a minimum of 1-3/8" (34.9 mm) in diameter.				
15	4	Ends and back cleats shall be a minimum of 3/4" (19 mm) thick by:				
		3-1/2" (89 mm) wide when receiving a clothes rod or hooks.				
15	4	1				
		1-1/2" (38 mm) wide when not receiving a clothes rod or hooks.				
15	4	2				
Continues next column ▼						

6.4.5		Basic and Specific Material Rules					
▲ From previous column							
16	<b>GLASS:</b>						
16	1	Shall conform to applicable codes and regulations; these standards shall not supersede such regulations.					
16	2	Safety type, shall conform to the Consumer Product Safety Commission's Safety Standard for Architectural Glazing Materials, <a href="http://cpsc.gov">http://cpsc.gov</a> .					
16	3	Clear, single strength, shall be furnished within the appropriate size limitation; however:					
16	3	1	When required because of limitations, double strength shall be furnished.				
16	4	Obscure type, shall be roll figured sheet glass, 1/8" (3.2 mm) in thickness, of standard pattern set with the smooth side facing the exterior or corridor, unless otherwise specified.					
16	5	Wire type, whether polished or obscure, shall be 1/4" (6.4 mm) in thickness.					
16	6	Float type, shall be 1/4" (6.4mm) in thickness.					
16	7	Beveled type, at exterior openings, shall be set with the beveled face to the outside.					
16	8	Leaded or zinc cane installation, shall have the individual light carefully fitted together with cane intersections neatly soldered and the whole assembly watertight. Reinforcing bars shall be provided where necessary.					
16	9	Insulating units shall have the panes hermetically sealed and separated by a dehydrated air space.					
17	When <b>FACTORY FINISHING</b> is specified, concealed surfaces shall be factory sealed at 1 mil dry.				E	C	P



# SECTION 6

## Millwork



GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally

**E C P**

# compliance requirements

6.4.6		Basic and Specific Machining Rules					
1		EXPOSED SURFACES shall comply with:					
1	1	SMOOTHNESS REQUIREMENTS (see SMOOTHNESS in TESTS), and:					
1	1	1	Sharp edges shall be eased with a fine abrasive.	E	C	P	
1	1	2	TOP FLAT WOOD surfaces, those that can be sanded with a drum or wide belt sander, with:				
1	1	2	1	Minimum 15 KCPI or 100 grit sanding.	E	C	P
1	1	2	2	120 grit sanding.	E	C	P
1	1	2	3	150 grit sanding.	E	C	P
1	1	3	PROFILED and/or SHAPED WOOD surfaces require:				
1	1	3	1	Minimum 15 KCPI or 100 grit sanding.	E	C	P
1	1	3	2	Minimum 20 KCPI or 120 grit sanding.	E	C	P
1	1	3	3	120 grit sanding.	E	C	P
1	1	4	TURNED WOOD surfaces require:				
1	1	4	1	Minimum 15 KCPI or 100 grit sanding.	E	C	P
1	1	4	2	120 grit sanding.	E	C	P
1	1	4	3	180 grit sanding.	E	C	P
1	1	5	CROSS SANDING, excluding turned surfaces, require:				
1	1	5	1	Is not a defect.	E	C	P
1	1	5	2	Is not allowed.	E	C	P
1	1	6	TEAR OUTS, knife nicks, or hit or miss machining is not permitted.				
1	1	7	KNIFE MARKS are not permitted where sanding is required.				
1	1	8	GLUE or FILLER, if used, shall be inconspicuous and match the adjacent surface for smoothness.				
1	2	HPDL, PVC, and PRE-FINISHED WOOD edges shall be machined flush and filed, sanded, or buffed to remove machine marks and sharp edges, and:					
Continues next column ▼							

6.4.6		Basic and Specific Machining Rules					
▲ From previous column							
1		EXPOSED SURFACES (continued)					
1	2	HPDL, PVC, and PRE-FINISHED WOOD edges (continued)					
1	2	1	OVERLAP (See Test F illustrations in TESTS) such as				
			shall not exceed:				
							
1	2	1	1	0.005" (0.13 mm) for a maximum length of 2" (50.8 mm) in any 12" (305 mm) run.	E	C	P
1	2	1	2	0.005" (0.13 mm) for a maximum length of 1" (25.4 mm) in any 24" (610 mm) run.	E	C	P
1	2	1	3	0.003" (0.08 mm) for a maximum length of 1" (25.4 mm) in any 48" (1220 mm) run.	E	C	P
1	2	2	CHIP OUT (See Test G illustrations in TESTS) such as				
							
			shall be inconspicuous when viewed at:				
1	2	2	1	72" (1829 mm).	E	C	P
1	2	2	2	48" (1220 mm).	E	C	P
1	2	2	3	24" (610 mm).	E	C	P
Continues next column ▼							



# SECTION 6



## Millwork

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



# compliance requirements

6.4.6 Basic and Specific Machining Rules						
▲ From previous column						
1 EXPOSED SURFACES (continued)						
1 2 HPDL, PVC, and PRE-FINISHED WOOD edges (continued)						
OVER MACHINED (See Test H illustrations in TESTS) removal of color or pattern of face material such as,						
						
shall be limited to:						
1	2	3	1	3/32" x 6" (2.4 mm x 152 mm) and may not occur within 48" (1220 mm) of a similar occurrence.	E	C P
1	2	3	2	1/32" x 4" (0.8 mm x 102 mm) and may not occur within 60" (1524 mm) of a similar occurrence.	E	C P
1	2	3	3	1/32" x 1-1/2" (0.8 mm x 38.1 mm) and may not occur within 72" (1829 mm) of a similar occurrence.	E	C P
2 TRIM applied on flat surfaces shall have the reverse side backed out.						
2 1 Door and window trim over 2" (50.8 mm) in width with non exposed ends shall be backed out.						
3 SOLID MACHINED and BLOCK LAMINATED members shall be divided to minimize the exposure of cross grain in the face of the member, and:						
Angle of grain at the face of the curved member shall not exceed 30 degrees, unless a small part size requires otherwise.						
						
4 INTERSECTIONS at radius and straight members shall be splined or half lapped, securely glued, and mechanically fastened.						
Continues next column ▼						

6.4.6 Basic and Specific Machining Rules						
▲ From previous column						
5 DADOES shall completely house the male member throughout the entire length of the joint.						
6 STANDING & RUNNING TRIM:						
6 1 For EXTERIOR application, 5-1/4" (133.4 mm) and wider shall require kerfing, 1/8" (3.2 mm) wide by 1/4" (6.4 mm) deep, a maximum of 1-1/2" (38.1 mm) on center.						
7 WINDOW FRAMES:						
7 1 Shall have a drip groove on the underside of the sill.						
7 2 Shall have stiles and/or rails machined for cords, balances, and other operating hardware as required, and:						
7 2 1 Stop profile shall be of manufacturer's choice.						
8 SASH:						
8 1 Stile and rail profile shall be of manufacturer's choice.						
8 2 For awning type, stiles and rails shall be machined to accommodate the type of hardware specified and shall be prefit, ready to install.						
8 3 For circle, gothic, or irregular type, conform to square head construction with irregular joints splined, slot mortised, or doweled.						
8 4 Shall have bottom rails beveled to fit slope of sill.						
9 SCREENS shall:						
9 1 Be of mortise and tenon, slot mortise, or doweled construction.						
9 2 Have wire cloth stretched taut and securely attached to the frame or rolled into a kerf rabbeted frame.						
9 3 Have molds neatly mitered and securely attached to the frame.						
9 4 Be of manufacturer's choice frame width and profile.						
Continues next column ▼						



# SECTION 6




## Millwork


GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



# compliance requirements

6.4.6		Basic and Specific Machining Rules				
▲ From previous column						
10	<b>BLINDS and SHUTTERS:</b>					
10	1	Shall be of mortise and tenon, or doweled construction.				
10	2	Slats shall overhang each other a minimum of 1/8" (3.2 mm), and:				
10	2	1	<b>STATIONARY SLATS</b> shall be mortised into stiles and set at an angle 45 to 60 degrees from horizontal, and:			
			Round edge slats shall be set in routed slot.			
10	2	1	1			
10	2	1	2	Flat edge slats shall be set in dado slot.		E C P
				Flat edge slats shall be set in dado slot with molding applied to face rails to cover dado.		
10	2	1	3			
				E C P		
				<b>MOVABLE SLATS</b> shall pivot on a wood, metal, or nylon dowel, and:		
10	2	2				
10	2	2	1	Pivot pins for damp coastal climates shall be nylon, stainless steel, or brass.		
10	2	2	2	Have a vertical control bar set to movable slats with curved staples to allow movement.		
11	<b>ORNAMENTAL MILLWORK:</b>					
11	1	Permits cut sawn edges at scroll work.				
11	2	Requires turnings to be clean, cut, sanded, and well matched for alignment.				

6.4.7		Basic and Specific Assembly Rules					
1	These standards do not establish Grade rules for joint flushness and/or gap tolerances for woodwork products installed in a non climate controlled environment; however:						
1	1	Prior to installation, the flushness and/or gap tolerances of woodwork products intended for non climate controlled environments shall meet the test requirements herein.					
2	<b>JOINTS at ASSEMBLED WOODWORK</b> shall:						
2	1	Be neatly and accurately made.					
2	2	Be securely glued, with:					
2	2	1	Adhesive residue removed from exposed and semi-exposed surfaces.				
2	3	Be reinforced with glue blocks where essential.					
2	4	Utilize clamp nail, biscuit spline, butterfly, scarf, or dowel joinery.				E C P	
2	5	Utilize biscuit spline, butterfly, scarf, or dowel joinery.				E C P	
2	6	Be <b>MECHANICALLY FASTENED</b> with nails or screws, where practical, with fasteners:					
2	6	1	Countersunk.				
2	6	2	Located in molding quirks or reliefs where possible.				E C P
2	7	<b>NOT PERMIT</b> visible fasteners at exposed surfaces of sheet products.					
2	8	Require <b>FLUSHNESS VARIATIONS</b> at exposed surfaces (See Test D illustrations in TESTS), when mitered or butted, such as					
							
			not to exceed at:				
2	8	1	Wood to wood:				
2	8	1	1	0.010" (0.25 mm).		E C P	
2	8	1	2	0.007" (0.18 mm).		E C P	
2	8	1	3	0.005" (0.13 mm).		E C P	
2	8	2	Non wood to non wood:				
2	8	2	1	0.025" (0.64 mm).		E C P	
2	8	2	2	0.015" (0.38 mm).		E C P	
2	8	2	3	0.010" (0.25 mm).		E C P	
Continues next column ▼							

# SECTION 6



## Millwork



GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally

**E C P**

# compliance requirements

6.4.7		Basic and Specific Assembly Rules			
▲ From previous column					
2	9	JOINTS at ASSEMBLED WOODWORK (continued)			
	9	Allow <b>GAPS</b> at exposed surface (see Test A illustrations in TESTS), when mitered or butted, such as,			
	9				
	9	not to exceed:			
2	9	1	0.025" (0.64 mm) wide by 20% of the joint length.	E	C P
2	9	2	0.015" (0.38 mm) wide by 20% of the joint length.	E	C P
2	9	3	0.010" (0.25 mm) wide by 20% of the joint length.	E	C P
	10	Allow <b>GAPS</b> at exposed surface joints of parallel members (See Test B illustrations in TESTS), such as			
	10				
	10	not to exceed:			
2	10	1	0.025" x 9" (0.64 mm x 229 mm) shall not occur within 48" (1219 mm) of a similar gap in the same joint.	E	C P
2	10	2	0.015" x 6" (0.38 mm x 152 mm) shall not occur within 60" (1524 mm) of a similar gap in the same joint.	E	C P
2	10	3	0.010" x 4" (0.25 mm x 102 mm) shall not occur within 72" (1829 mm) of a similar gap in the same joint.	E	C P
Continues next column ▼					

6.4.7		Basic and Specific Assembly Rules			
▲ From previous column					
2	11	JOINTS at ASSEMBLED WOODWORK (continued)			
	11	Allow <b>GAPS</b> at exposed surface joints (See Test C illustrations in TESTS) when mitered or butted, such as			
	11				
	11	not to exceed at:			
2	11	1	0.025" (0.64 mm).	E	C P
2	11	2	0.015" (0.38 mm).	E	C P
2	11	3	0.010" (0.25 mm).	E	C P
2	12	Allows use of <b>FILLER</b> :			
2	12	1	If inconspicuous when viewed at 36" (914 mm).	E	C P
2	12	2	If inconspicuous when viewed at 24" (610 mm).	E	C P
2	12	3	<b>NOT ALLOWED.</b>	E	C P
3	3	<b>FLATNESS or WARP</b> of installed and removable sheet products (see Test E illustrations in TESTS) such as 			
	3	shall not to exceed grade tolerance listed for 12" (303 mm) diagonal, width and/or length or as lineal ratio (not geometric ratio) thereof. Example, twice the grade tolerance listed for 24" (610 mm), three times the tolerance for 36" (914 mm):			
3	3	1	0.045" (1.1 mm) per 12" (305 mm) or portion thereof.	E	C P
3	3	2	0.030" (0.8 mm) per 12" (305 mm) or portion thereof.	E	C P
3	3	3	0.020" (0.5 mm) per 12" (305 mm) or portion thereof.	E	C P
Continues next column ▼					

# SECTION 6

## Millwork

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



## compliance requirements

6.4.7 Basic and Specific Assembly Rules	
▲ From previous column	
4	APPLIED MOLDINGS shall be spot glued and mechanically fastened.
5	MITER JOINTS and CAPS shall be well fitted and cleaned.
6	STILE and RAIL ASSEMBLIES shall be built up in units as large as practical, and:
6 1	Members shall be mortised and tenoned, doweled, or splined. <span style="float: right;">E C P</span>
7	SHEET and LAMINATED LUMBER PANELS shall be allowed to move, float, expand or contract in reaction to ambient humidity changes.
8	BUILT UP ITEMS shall be soundly fabricated with half lapped, mitered, shoulder mitered, tongued, or equivalent construction.
9	STANDING & RUNNING TRIM shall require:
9 1	Radius moldings to be glued up for length in the longest practical lengths. <span style="float: right;">E C P</span>
9 2	Exterior trim to be furnished as material only; items required to be assembled shall be so specified.
<b>10 DOOR FRAMES:</b>	
10 1	Flame spread rated shall be of the manufacturer's standard design and construction, conforming to the requirements of their applicable labeling service.
10 2	With molded edges, other than square or with 1/16" (1.6 mm) or more in radius, shall have mitered joints. <span style="float: right;">E C P</span>
10 3	With square heads shall have:
10 3 1	Jamb furnished machined KD (knocked down).
10 3 2	Stops cut to approximate length; however, not mitered or coped.
10 3 3	Heads and sills dadoed to receive side jambs, or vice versa.
10 4	With side jambs shall be dadoed into the sills and heads.
Continues next column ▼	

6.4.7 Basic and Specific Assembly Rules	
▲ From previous column	
10	DOOR FRAMES (continued)
10 5	With transom bars shall have them dadoed into side jambs.
10 6	With mullions shall have them dadoed into sills and heads.
10 7	For exterior opaque finished applications, shall have sill and jamb dadoes coated with mastic. <span style="float: right;">E C P</span>
10 8	Shall be shipped:
10 8 1	As oversize material for installer cutting and joinery. <span style="float: right;">E C P</span>
10 8 2	As appropriately labeled pre-sized sets with premachined joinery. <span style="float: right;">E C P</span>
10 8 3	As pre-sized, built up assemblies in as large as practical sections for safe transportation and installation, with:
10 8 3 1	Joints glued and fit tight, true, and secure. <span style="float: right;">E C P</span>
10 9	At radius heads:
10 9 1	Jamb shall be furnished assembled. <span style="float: right;">E C P</span>
10 9 2	Curved stops and casing shall be attached to frame. <span style="float: right;">E C P</span>
10 9 3	Joints at intersection of radius and straight members shall be splined or half lapped. <span style="float: right;">E C P</span>
<b>11 WINDOW FRAMES:</b>	
11 1	With molded edges, other than square or with 1/16" (1.6 mm) or more in radius, shall have mitered joints. <span style="float: right;">E C P</span>
11 2	With transom bars shall have them dadoed into side jambs.
11 3	With square edge members shall have the heads and sills dadoed to receive side jambs, or vice versa.
11 4	With glazed openings shall be trimmed on both sides with wood stops; however, one side shall be removable and the removable stop shall be on exterior side of exterior frames, with:
11 4 1	Stops shipped loose as material only. <span style="float: right;">E C P</span>
11 4 2	Stops shipped in properly labeled sets, cut to size. <span style="float: right;">E C P</span>
11 4 3	Stops tacked in place. <span style="float: right;">E C P</span>
11 5	Shall include sills and applied exterior trim.
Continues next column ▼	

# SECTION 6

## Millwork

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



## compliance requirements

6.4.7		Basic and Specific Assembly Rules		
▲ From previous column				
11	<b>WINDOW FRAMESS</b> (continued)			
11 6	Shall have stiles and/or rails machined for cords, balances, and other operating hardware as required.			
11 7	Shall have, at opaque finished exterior applications, the sill and jamb dadoes coated with mastic.	E	C	P
11 8	Shall include machining for:			
11 8 1	Operating hardware (if templates or a physical sample is provided prior to shop drawing preparation); however, it is not required to be furnished or installed.			
11 8 2	Weather stripping (provided templates or a physical sample is provided prior to shop drawing preparation); however, it is not required to be furnished or installed.			
11 8 3	Sash balances (provided templates or a physical sample is provided prior to shop drawing preparation); however, it is not required to be furnished or installed.			
11 9	Shall not include machining for non operating hardware, such as locking devices, pulls, lifts, etc., nor is it required to be furnished or installed.			
11 10	When glass is furnished and installed, it shall be bedded in a glazing compound prior to the installation of a face compound or wood bead, and:			
11 10 1	Glazing materials and the method of glazing are optional.			
11 10 2	Glass shall be cut slightly scant to prevent binding and set so as to prevent shifting.			
11 10 3	Glazier's points shall be spaced a maximum of 16" (406 mm) on center with a minimum of one on each edge of each light.			
11 10 4	Bedding of glass is required.	E	C	P
11 10 5	When putty (excluding primeless putty or glazing compound) is used, glass rabbets shall be primed with linseed oil before glazing.			
<b>12 SASH:</b>				
12 1	Half lap joints are permitted at intersecting muntins, and:			
12 1 1	Bar and muntin alignment shall:			
12 1 1 1	Be at right angles to each other and to the sash member.			
12 1 1 2	Align with each other vertically and horizontally.			
12 1 1 3	Align with similar members on the adjoining sash.			
Continues next column ▼				

6.4.7		Basic and Specific Assembly Rules		
▲ From previous column				
12	<b>SASH</b> (continued)			
12 2	Mullions shall be dadoed into heads and sills.			
12 3	At double glazed units requires one stop to be left loose for finishing.			
12 4	If glass is furnished and installed, it shall conform to the requirements set herein.			
<b>13 BLINDS and SHUTTERS:</b>				
13 1	Require dadoed or equivalent joinery.			
<b>14 SCREENS</b> require:				
14 1	They be assembled under pressure and pinned.			
<b>15 ORNAMENTAL MILLWORK:</b>				
15 1	Woodwork shall be manufacturer sized except where installer adjustments are required.			
15 2	Column fabrication for opaque finish shall allow finger joints, with:			
15 2 1	Maximum of one per 96" (2400 mm) or portion thereof in any individual member.			
15 2 2	Joints offset a minimum of 3" (76 mm) from adjacent joints.			
15 2 3	Joints perpendicular to the face of the column resulting in the appearance of a single horizontal line with column upright.			
15 2 4	Compliance Tests C and Flushness shall apply to such joints.			
<b>15 3 SHEET PRODUCTS:</b>				
15 3 1 Of <b>SOLID LUMBER</b> shall be:				
15 3 1 1	Edge glued for width.	E	C	P
15 3 1 2	Maximum 10" (254 mm) in width.	E	C	P
15 3 1 3	Not permitted.	E	C	P
15 3 2 With <b>RAISED PANEL RIMS:</b>				
15 3 2 1	Mitered and glued to sheet product body.	E	C	P
15 3 2 2	Mitered, splined, or doweled to sheet product body.	E	C	P
15 3 3 With <b>PANEL PRODUCT CENTERS</b> require:				
15 3 3 1	No edge treatment.	E	C	P
15 3 3 2	Edge covered by veneer or concealed by molding.	E	C	P
Continues next column ▼				

# SECTION 6

## Millwork

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



# compliance requirements

6.4.7		Basic and Specific Assembly Rules			
▲ From previous column					
15		At <b>ORNAMENTAL MILLWORK</b> (continued)			
15	3	<b>SHEET PRODUCTS</b> (continued)			
15	3	4	With <b>LOOSE JOINTS</b> between sections require:		
15	3	4	1	No preparation.	E C P
15	3	4	2	Manufacturer preparation, utilizing mortise and tenon, dowel, or spline joinery.	E C P
15	3	4	3	Manufacturer assembly (if practical), utilizing mortise and tenon, dowel, or spline joinery.	E C P
15	3	5	With <b>OUTSIDE CORNERS</b> require:		
15	3	5	1	No preparation.	E C P
15	3	5	2	Manufacturer prepared and shipped loose for installer fitting.	E C P
15	3	5	3	Manufacturer prepared, glued, and braced (if practical).	E C P
15	3	6	With <b>INSIDE CORNERS</b> require:		
15	3	6	1	No preparation.	E C P
15	3	6	2	Shipped oversize for installer fitting.	E C P
15	3	7	With <b>APPLIED MOLDINGS</b> , contained wholly within an individual item or used as rim or panel retention members, require:		
15	3	7	1	Mitered corners.	
15	3	7	2	No preparation.	E C P
15	3	7	3	Manufacturer application with spot glue and finish nails.	E C P
15	3	7	4	Manufacturer application with spot glue, finish nails, and:	E C P
15	3	7	4	1 Filled and sanded.	E C P
15	3	8	For <b>HISTORIC WORK</b> , see Section 12.		
					
Continues next column ▼					

6.4.7		Basic and Specific Assembly Rules			
▲ From previous column					
16		At <b>MISCELLANEOUS MILLWORK</b> such as:			
16	1	<b>DECORATIVE SUN SCREENS</b> or <b>LOUVERS</b> shall be soundly constructed, with:			
16	1	1	All members dadoed together and, where design permits, assembled in the mill.		
16	2	<b>BOXED BEAMS, COLUMNS, PILASTERS, SEATS, BENCHES,</b> and overhead <b>TRELLISES</b> shall be soundly constructed, with:			
16	2	1	Tongued, shoulder mitered, mortised and tenoned, or doweled joints; securely glued, nailed, and reinforced with glue blocks or metal brackets, as appropriate.		
16	3	<b>STAVED COLUMNS</b> or <b>NEWELS</b> shall be of lock joint, tongue, or spline construction and securely glued with:			
16	3	1	Caps and bases furnished loose.		
16	4	<b>HANDRAILS</b> and <b>CROOKS</b> shall be furnished mill cut and doweled unless jobsite conditions dictate otherwise.			
16	5	<b>CLOSET &amp; UTILITY SHELVING</b> , shall have:			
16	5	1	Shelves and dividers furnished:		
16	5	1	1	Unassembled.	
16	5	1	2	Cut to width in lengths suitable for installer fitting.	
16	5	2	Cleats furnished as lineal footage.		
16	5	3	Shelves with unsupported length exceeding 36" (914 mm) shall:		
16	5	3	1	Be a minimum of 1" (25.4 mm) in thickness, or:	
16	5	3	1	1	Have a minimum 3/4" x 2" (19 mm x 51 mm) applied frontdrop edge.
					
Continues next column ▼					

# SECTION 6



## Millwork

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



## compliance requirements

<b>6.4.7</b>		<b>Basic and Specific Assembly Rules</b>					
<b>▲ From previous column</b>							
<b>16</b>	<b>At</b>	<b>MISCELLANEOUS MILLWORK</b> (continued)					
<b>16</b>	<b>5</b>	<b>CLOSET &amp; UTILITY SHELVING</b> (continued)					
<b>16</b>	<b>5</b>	<b>4</b>	Exposed edges of sheet good cleats and shelves are defined as visible in normal use position, and:				
<b>16</b>	<b>5</b>	<b>4</b>	<b>1</b>	Do not require edge work.	<b>E</b>	<b>C</b>	<b>P</b>
<b>16</b>	<b>5</b>	<b>4</b>	<b>2</b>	Shall be edgebanded to match face with edges eased, and:	<b>E</b>	<b>C</b>	<b>P</b>
<b>16</b>	<b>5</b>	<b>4</b>	<b>2</b>	<b>1</b> Sequence of lamination is optional.	<b>E</b>	<b>C</b>	<b>P</b>
<b>16</b>	<b>5</b>	<b>4</b>	<b>3</b>	Adjoining adjustable shelves shall have ends edgebanded.			
<b>16</b>	<b>5</b>	<b>4</b>	<b>4</b>	When miter folded, shall have no open gaps, and:			
<b>16</b>	<b>5</b>	<b>4</b>	<b>4</b>	<b>1</b> Shall be filed or sanded just enough to remove sharpness.			
<b>16</b>	<b>5</b>	<b>4</b>	<b>5</b>	Gaps between the end of the shelf and the wall up to 1/4" (6.4 mm) are allowed. 	<b>E</b>	<b>C</b>	<b>P</b>
<b>16</b>	<b>5</b>	<b>4</b>	<b>6</b>	Ends of shelves held more than 1/4" (6.4 mm) away from a wall shall be edgebanded. 	<b>E</b>	<b>C</b>	<b>P</b>



# SECTION 6

## Millwork

### GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



## compliance requirements

### 6.5 PREPARATION and QUALIFICATION REQUIREMENTS

- 1 **CARE, STORAGE, and BUILDING CONDITIONS** shall be in compliance with the requirements set forth in Section 2 of these standards.
- 1.1 Severe damage to the woodwork can result from noncompliance. The manufacturer and/or installer of the woodwork shall not be held responsible for damage that might develop by not adhering to the requirements.
- 2 **CONTRACTOR IS RESPONSIBLE FOR** 
- 2.1 Furnishing and installing structural members, grounds, in wall blocking, backing, furring, brackets, or other anchorage required for architectural woodwork installation that becomes an integral part of walls, floors, or ceilings to which architectural woodwork, such as wall applied surfacing, standing and running trim, wall mounted shelf standards and door/window frames shall be installed.
- 2.1.1 In the absence of contract documents calling for the contractor to supply the necessary in wall blocking/backing in the wall or ceilings, either through inadvertence or otherwise, the architectural woodwork installer shall not proceed with the installation until such time as the in wall blocking/backing is installed by others.
- 2.1.2 Preparatory work done by others shall be subject to inspection by the architectural woodwork installer and may be accepted or rejected for cause prior to installation.
- 2.1.2.1 **WALL, CEILING,** and/or opening variations in excess of 1/4" (6.4 mm) or **FLOORS** in excess of 1/2" (12.7 mm) in 144" (3658 mm) of being plumb, level, flat, straight, square, or of the correct size are not acceptable for the installation of architectural woodwork, nor is it the responsibility of the installer to scribe or fit to tolerances in excess of such.
- 2.1.3 Installation site being properly ventilated, protected from direct sunlight, excessive heat and/or moisture, and that the HVAC system is functioning and maintaining the appropriate relative humidity and temperature.

### 6.5 PREPARATION and QUALIFICATION (continued)

- 2.2 Priming the architectural woodwork in accordance with the contract documents prior to its installation:
- 2.2.1 If the architectural woodwork is factory finished, priming by the factory finisher is required.
- 3 **INSTALLER IS RESPONSIBLE FOR** 
- 3.1 Having adequate equipment and experienced craftsmen to complete the installation in a first class manner.
- 3.2 Checking architectural woodwork specified and studying the appropriate portions of the contract documents, including these standards and the reviewed shop drawings to familiarize themselves with the requirements of the Grade specified, understanding that:
- 3.2.1 Appearance requirements of Grades apply only to surfaces visible after installation.
- 3.2.2 For transparent finish, special attention needs to be given to the color and the grain of the various woodwork pieces to ensure they are installed in compliance with the Grade specified.
- 3.3 Verification that installation site is properly ventilated, protected from direct sunlight, excessive heat and/or moisture, and that the HVAC system is functioning and maintaining the appropriate relative humidity and temperature.
- 3.4 Verification that required priming of woodwork has been completed by others before woodwork is installed.
- 3.5 Verification that woodwork has been acclimated to the field conditions for a minimum of 72 hours before installation is commenced.
- 3.6 Woodwork specifically built or assembled in sequence for match of color and grain is installed to maintain that same sequence.

# SECTION 6

## Millwork

### GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



## compliance requirements

### 6.6 RULES

- 1 The following rules shall govern unless a project's contract documents require otherwise.
- 2 These rules are intended to provide a well defined degree of control over a project's quality of installation.
- 3 **ERRATA**, published at <http://naaws-errata.com>, shall take precedence over these rules, subject to their date of posting and a project's bid date. 

6.6.4		Basic General Rules		
1	<b>AESTHETIC</b> grade rules apply only to exposed and semi-exposed surfaces visible after installation.			
2	<b>TRANSPARENT FINISHED</b> woodwork shall be:			
2 1	Installed with consideration for color and grain.	E	C	P
2 2	Compatible in color and grain.	E	C	P
2 3	Well matched for color and grain, and:	E	C	P
2 3 1	Sheet products shall be compatible in color with solid stock.	E	C	P
2 3 2	Adjacent sheet products shall be well matched for color and grain.	E	C	P
3	<b>REPAIRS</b> are allowed, provided they are made neatly and are inconspicuous when viewed, from a normal viewing stance, at:			
3 1	72" (1830 mm).	E	C	P
3 2	48" (1219 mm).	E	C	P
3 3	24" (610 mm).	E	C	P
4	<b>INSTALLER FABRICATION</b> and <b>MODIFICATIONS</b> shall comply to the general, material, machining, and assembly rules within the <b>PRODUCT</b> portion of this section and, if applicable, the finishing rules in Section 5.			
5	<b>WOODWORK</b> shall be:			
5 1	Securely fastened and tightly fitted with flush joints, and:			
5 1 1	Joinery shall be consistent throughout the project.			
5 2	Of maximum available and/or practical lengths.	E	C	P
5 3	Trimmed equally from both sides when fitted for width.	E	C	P
5 4	Splined or doweled when miters are over 4" (100 mm) long.	E	C	P
Continues next column ▼				

### 6.6.4 Basic General Rules

#### ▲ From previous column

5	<b>WOODWORK</b> (continued)			
5 5	Profiled or self mitered when trim ends are exposed.	E	C	P
5 6	Self mitered when trim ends are exposed.	E	C	P
5 7	Mitered at outside corners.			
5 8	Mitered or butted for S4S at inside corners.	E	C	P
5 9	Coped at inside corners, except S4S shall be mitered.	E	C	P
5 10	Installed plumb, level, square, and flat within 1/8" (3.2 mm) in 96" (2438 mm), and when required:			
5 10 1	Grounds and hanging systems set plumb and true.	E	C	P
5 11	Installed free of:			
5 11 1	Warp, twisting, cupping, and/or bowing that cannot be held true.			
5 11 2	Open joints, visible machine marks, cross sanding, tear outs, nicks, chips, and/or scratches.			
5 11 3	Natural defects exceeding the quantity and/or size limits defined in Sections 3 & 4.			
5 12	Smooth and sanded without cross scratches in conformance to the product portion of this section.			
5 13	Scribed at:			
5 13 1	Flat surfaces.	E	C	P
5 13 2	Shaped surfaces.	E	C	P

**THESE STANDARDS** do not establish Grade rules for joint flushness and or gap tolerances for woodwork products installed in a non climate controlled environment, however:

Continues next column ▼

# SECTION 6


## Millwork


### GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally

<b>E</b>	<b>C</b>	<b>P</b>
----------	----------	----------

## compliance requirements

6.6.4		Basic General Rules	
▲ From previous column			
GAPS at field joints (see Test I illustrations in TESTS) such as,			
7			
	and:		
7 1	Not be considered a defect or the responsibility of the installer if caused by excessive deviations in the building's walls and ceilings being in excess of 1/4" (6.4 mm) in 144" (3658 mm) of being plumb, level, flat, straight, square, or of the correct size, or 1/2" (12.7 mm) for floors.		
7 2	Not exceed 30% of a joint's length and:		
7 2 1	Be allowed if filled or caulked, and:		E C P
7 2 1 1	If color compatible.		E C P
7 3	At WOOD to WOOD shall not exceed:		
7 3 1	At FLAT surfaces:		
7 3 1 1	0.030" (0.76 mm) in width.		E C P
7 3 1 2	0.020" (0.51 mm) in width.		E C P
7 3 1 3	0.015" (0.38 mm) in width.		E C P
7 3 2	At SHAPED surfaces:		
7 3 2 1	0.040" (1.02 mm) in width.		E C P
7 3 2 2	0.025" (0.64 mm) in width.		E C P
7 3 2 3	0.015" (0.38 mm) in width.		E C P
7 4	At WOOD to NON WOOD shall not exceed:		
7 4 1	At FLAT and SHAPED surfaces:		
7 4 1 1	0.075" (1.91 mm) in width.		E C P
7 4 1 2	0.050" (1.27 mm) in width.		E C P
7 4 1 3	0.035" (0.89 mm) in width.		E C P
7 5	At NON WOOD to NON WOOD and/or ALL ELEMENTS shall not exceed:		
7 5 1	At FLAT surfaces:		
7 5 1 1	0.075" (1.91 mm) in width.		E C P
7 5 1 2	0.050" (1.27 mm) in width.		E C P
7 5 1 3	0.035" (0.89 mm) in width.		E C P
Continues next column ▼			

6.6.4		Basic General Rules	
▲ From previous column			
7	GAPS (see Test I illustrations in TESTS) (continued)		
7 5 2	At SHAPED surfaces:		
7 5 2 1	0.120" (3.05 mm) in width.		E C P
7 5 2 2	0.075" (1.91 mm) in width.		E C P
7 5 2 3	0.050" (1.27 mm) in width.		E C P
FLUSHNESS of field joinery (see Test J illustrations in TESTS) such as,			
8			
	and:		
8 1	Of WOOD to WOOD shall not exceed:		
8 1 1	At FLAT surfaces:		
8 1 1 1	0.025" (0.64 mm).		E C P
8 1 1 2	0.015" (0.38 mm).		E C P
8 1 1 3	0.010" (0.25 mm).		E C P
8 1 2	At SHAPED surfaces:		
8 1 2 1	0.040" (0.97 mm).		E C P
8 1 2 2	0.025" (0.65 mm).		E C P
8 1 2 3	0.020" (0.51 mm).		E C P
8 2	Of WOOD to NON WOOD shall not exceed:		
8 2 1	At FLAT and SHAPED surfaces:		
8 2 1 1	0.075" (1.91 mm).		E C P
8 2 1 2	0.050" (1.27 mm).		E C P
8 2 1 3	0.035" (0.89 mm).		E C P
8 3	Of NON WOOD to NON WOOD and/or ALL ELEMENTS shall not exceed:		
8 3 1	At FLAT surfaces:		
8 3 1 1	0.075" (1.91 mm).		E C P
8 3 1 2	0.050" (1.27 mm).		E C P
8 3 1 3	0.035" (0.89 mm).		E C P
Continues next column ▼			

# SECTION 6

## Millwork

### GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



## compliance requirements

6.6.4		Basic General Rules						
▲ From previous column								
8	FLUSHNESS of joinery (continued)							
8	3	Of <b>NON WOOD</b> to <b>NON WOOD</b> (continued)						
8	3	2	At <b>SHAPED</b> surfaces:					
8	3	2	1	0.120" (3.05 mm).	E	C	P	
8	3	2	2	0.075" (1.91 mm)	E	C	P	
8	3	2	3	0.050" (1.27 mm).	E	C	P	
9 FASTENING and FASTENERS shall:								
9	1	Include the use of construction adhesive, finish nails, trim screws, pins and/or staples, except:						
9	1	1	Staples with a crown exceeding 3/16" (4.8 mm) are not permitted.					
9	2	Not permit the use of drywall or bugle head screws.						
9	3	Require exposed fasteners to be countersunk.						
9	4	Require exposed fasteners to be set in quirks and reliefs where possible.				E	C	P
9	5	Require exposed fasteners to be inconspicuous when viewed at 24" (610 mm).				E	C	P
9	6	Allow use of construction adhesive for inconspicuous fastening.						
9	7	Not permit exposed fastening through decorative laminate.						
9	8	REQUIRE allowable fastener holes, when:						
9	8	1	Pre-finished materials to be filled by the installer with matching filler furnished by the manufacturer.					
9	8	2	Unfinished materials to be filled by the paint contractor or others.					
10 GLUE and filler residue is not permitted on exposed faces.								
EQUIPMENT CUTOUTS, including electrical and plumbing, shall be cut out by the installer, provided templates are furnished prior to installation, and:								
11	1	Shall be neatly cut and properly sized to be covered by standard cover plates or rosettes.						
11	2	In <b>HPDL</b> or <b>SOLID SURFACE</b> shall have a minimum 1/4" (6.4 mm) radius at inside corners.						
Continues next column ▼								

6.6.4		Basic General Rules							
▲ From previous column									
12	HARDWARE shall be:								
12	1	Installed neatly without tear out of surrounding stock.					E	C	P
12	2	Installed per manufacturer's instructions.							
12	3	Installed using furnished fasteners and fasteners' provisions. When fastener provisions are countersunk, fasteners shall be countersunk.							
12	4	Adjusted for smooth operation, within limits of the specified hardware.							
13 AREAS OF INSTALLATION shall be left broom clean.									
13	1	Debris shall be removed and dumped in containers provided by the contractor.							
13	2	Items installed shall be cleaned of pencil or ink marks.							
14 <b>FIRST CLASS WORKMANSHIP</b> is required in compliance with these standards. 									



# SECTION 6

## Millwork

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally

<b>E</b>	<b>C</b>	<b>P</b>
----------	----------	----------

## compliance requirements

6.6.5		Product Specific Rules			
<b>1 STANDING and RUNNING TRIM</b> shall require:					
1	1	Running joints be diagonal scarf or butted, if butted must use a dowel biscuit spline or spline.	E	C	P
1	2	Running joints on multimember trim be staggered from adjacent members.	E	C	P
1	3	Large, one piece or multimember moldings be installed with back blocking as needed.			
<b>1 4 MULTIPLE JOINTS</b> in running trim shall not be within:					
1	4	1 24" (609 mm).	E	C	P
1	4	2 36" (914 mm).	E	C	P
1	4	3 48" (1220 mm).	E	C	P
<b>1 5</b> Base be scribed to the floor, only if so specified: however:					
1	5	1 If not scribed it shall be caulked.	E	C	P
1	6	Miters over 4" (102 mm) long be joined with spline, dowel, or biscuit spline.	E	C	P
<b>2 CLOSET RODS</b> shall be supported at a maximum of 48" (1219 mm) on center.					
<b>3 DOOR &amp; WINDOW FRAMES</b> shall:					
3	1	Have rough wood bucks secured at openings.			
3	2	Be set plumb.			
3	3	Be seated on the floor.			
3	4	Be securely fastened through shims into the framing.			
<b>3 5</b> Have <b>LEGS</b> set square with header and parallel to each other within:					
3	5	1 3/16" (4.8 mm).	E	C	P
3	5	2 1/8" (3.2 mm).	E	C	P
3	5	3 1/16" (1.6 mm).	E	C	P
3	6	Allow horns to be removed before installation.			
3	7	Require fire door frames to be installed per the manufacturers' basic instructions.			
3	8	Not permit prehung and pre-cased door/jamb assemblies that are fastened only through the casing.	E	C	P
Continues next column ▼					

6.6.5		Product Specific Rules			
<b>▲ From previous column</b>					
<b>4 BLINDS and SHUTTERS</b>					
4	1	If installed in a frame, screen, blind, or shutter, shall have a maximum clearance of 1/8" (3.2 mm) at all sides and be set uniformly within 1/8" (3.2 mm) of the frame face.			
<b>5 SCREENS</b>					
5	1	If installed in a frame, screen, blind, or shutter, shall have a maximum clearance of 1/8" (3.2 mm) at all sides and be set uniformly within 1/8" (3.2 mm) of the frame face.			
<b>6 ORNAMENTAL MILLWORK</b>					
6	1	Wood filler strip to cover a maximum of 1-1/2" (38 mm).	E	C	P
6	2	Scribe/fillers securely fastened with trim screws.	E	C	P
6	3	Scribe/fillers securely fastened with sheet goods adhesive, face nails, or pins.	E	C	P
6	4	Exposed surface scribed to the wall with a scribe strip, 1/32" (0.8 mm) maximum gap.	E	C	P



# SECTION 6

## Millwork

### GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally




## compliance requirements

### 6.7 BASIC CONSIDERATIONS

- 1 **TOLERANCES** typically found within NAAWS:
- 1.1 Fall into two **CATEGORIES**:
- 1.1.1 Factory fabricated joinery, assembly and construction - found in the **PRODUCT** portion.
- 1.1.2 Field installation joinery and assembly - found in the **INSTALLATION** portion.
- 1.2 **INCLUDE:**
- 1.2.1 Flatness of wood based panel products.
- 1.2.2 Solid wood to solid wood joints and assemblies.
- 1.2.3 Solid wood to wood veneer joints and assemblies.
- 1.2.4 Wood veneer to wood veneer joints and assemblies.
- 1.2.5 Solid wood to wood based product joints and assemblies (decorative laminate Solid Phenolic and panel products).
- 1.2.6 Solid surface to solid surface joints and assemblies.
- 1.3 **EXCLUDE:**
- 1.3.1 **BECAUSE of EXPANSION and CONTRACTION DIFFERENCES of non-wood products compared to solid wood and wood based products, these Standards do not apply tolerances regarding flatness or joinery to:** 
- 1.3.1.1 Solid wood to non-wood based products (which can be drywall, glass, metal, stone, acrylics, and other surfaces).
- 1.3.1.2 Non-wood to non-wood joints.

### 6.7 BASIC CONSIDERATIONS (continued)

- 2 **FABRICATED and INSTALLED** woodwork shall be tested for compliance to these standards as follows.
- 2.1 **SMOOTHNESS** of exposed surfaces:
- 2.1.1 **KCPI** (Knife Cuts Per Inch) is determined by holding the surfaced board at an angle to a strong light source and counting the visible ridges per inch, usually perpendicular to the profile.
- 
- Figure: 6-029
- 2.1.2 **SANDING** is checked for compliance by sanding a sample piece of the same species with the required grit of abrasive, and:
- 2.1.2.1 Observation with a hand lens of the prepared sample and the material in question will offer a comparison of the scratch marks of the abrasive grit.
- 2.1.2.2 Reasonable assessment of the performance of the finished product will be weighed against absolute compliance with the standard.
- 2.1.2.3 A product is sanded sufficiently smooth when knife cuts are removed and remaining sanding marks are or will be concealed by applied finishing coats.
- 2.1.2.4 Grain raise at unfinished wood, due to moisture or humidity in excess of the ranges set forth in this standard, shall not be considered a defect and must be sanded prior to finishing.
- 2.2 **GAPS, FLUSHNESS, FLATNESS and ALIGNMENT:**
- 2.2.1 Maximum gaps between exposed components shall be tested with a feeler gauge at points designed to join, where members contact or touch.
- 2.2.2 Joint length shall be measured with a ruler with minimum 1/16" (1 mm) divisions and calculations made accordingly.
- 2.2.3 Reasonable assessment of the performance of the finished product will be weighed against absolute compliance with the standards.

# SECTION 6

## Millwork

### GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally




## compliance requirements

### 6.7 BASIC CONSIDERATIONS (continued)

#### 2.2 GAPS, FLUSHNESS, FLATNESS, and (continued)

2.2.4 The following is intended to provide examples of how and where compliance testing is measured:



- A - Fabrication Gaps When Surfaces Are Mitered Or Butted
- B - Fabrication Gaps When Parallel Pieces Are Joined
- C - Fabrication Gaps When Edges Are Mitered Or Butted
- D - Fabrication Flushness Between Two Surfaces
- E - Flatness Of Panel Product

- F - Overlap (Flushness Of Laminate)
- G - Chip Out
- H - Over Machining
- I - Installation Gaps
- J - Installation Flushness

Figure: 6-030

# North American Architectural Woodwork Standards - 3.1

## **S E C T I O N - 0 7**

# STAIRWORK & RAILS

<b>Resources . . . . .</b>	<b><a href="#">188</a></b>
<b>Introduction . . . . .</b>	<b><a href="#">190</a></b>
<b>Advisories . . . . .</b>	<b><a href="#">190</a></b>
<b>Recommendations . . . . .</b>	<b><a href="#">190</a></b>
<b>Specification Considerations . . . . .</b>	<b><a href="#">190</a></b>
<b>Design Resources . . . . .</b>	<b><a href="#">194</a></b>
<b>Compliance Requirements . . . . .</b>	<b><a href="#">195</a></b>
<b>Scope &amp; Default Stipulation . . . . .</b>	<b><a href="#">196</a></b>
<b>Basic Requirements . . . . .</b>	<b><a href="#">196</a></b>
<b>Installation Requirements . . . . .</b>	<b><a href="#">204</a></b>
<b>Tests . . . . .</b>	<b><a href="#">208</a></b>

### Within CANADA

#### SUPPORT

- **GUIDE SPECIFICATIONS** – Available for download in interactive digital format, including specification wording for Quality Assurance Program (GIS) at: <http://awmac.com/guide-specifications>
- **CONSULTATION** – Contact any of the local chapters for more information on the NAAWS or any other Architectural Woodwork Questions you may have. See below for contact information.
- **SPECIFICATION REVIEW** – Contact any of the local chapters if you would like your specifications reviewed for compliance to the NAAWS.
- **MANUFACTURER STANDARDS QUESTIONNAIRE (MSQ)** – AWMAC Manufacturer members have the opportunity to have at least one member of their staff study and write the MSQ. The MSQ is a questionnaire on the NAAWS and policy and procedures of the GIS program. A list of Manufacturer members that have passed the MSQ is available at: <http://awmac.com/members>
- **SEMINARS AND PRESENTATIONS** – Contact your local chapter to arrange an informative presentation on any Architectural Woodwork topic. Some topic options – GIS, NAAWS, How to Specify Quality Architectural Woodwork...
- **TRADE SHOWS** – Contact your local chapter to arrange for AWMAC to have a booth or do a presentation on Architectural Woodwork.
- **CONFERENCE** – AWMAC has an annual conference held at unique venues across Canada. The conferences provide an opportunity to learn more about Architectural Woodwork and network with Suppliers and Manufacturers from across Canada. More information is available at: <http://awmac.com/>
- **EDUCATION PARTNERS** – Contact the local chapters to find out more information about support for local Colleges and Universities offering woodworking related courses and programs.

#### QUALITY ASSURANCE

- **GUARANTEE AND INSPECTION SERVICE (GIS)** – The GIS is a national program designed to ensure that project owners get value and quality for their investment by:
  - Supporting architects and design professionals to achieve project plans and specifications; and
  - Helping contractors avoid problems such as cost overruns, delays and loss of reputation.More information is available at: <http://awmac.com/gis>

- **INSPECTION SERVICE** – A GIS Certified Inspector will inspect specific areas of concern on a project for compliance to the NAAWS and provide a written report. Contact your local chapter for more information.
- **EXPERT OPINION** – An expert will be appointed to inspect specific areas of concern on a project and provide a written report. Contact your local chapter for more information.

#### AWMAC CHAPTERS

- AWMAC British Columbia Chapter, Vancouver BC  
<http://bc.awmac.com>
- AWMAC Northern Alberta Chapter, Edmonton Alberta  
<http://nab.awmac.com>
- AWMAC Southern Alberta Chapter, Calgary Alberta  
<http://sab.awmac.com>
- AWMAC Saskatchewan Chapter, Saskatoon Saskatchewan  
<http://sk.awmac.com>
- AWMAC Manitoba Chapter, Winnipeg Manitoba  
<http://mb.awmac.com>
- AWMAC Ontario Chapter, Toronto Ontario  
<http://on.awmac.com>
- AWMAC Quebec Chapter, Montreal Quebec  
<http://qc.awmac.com>
- AWMAC Atlantic Chapter, Halifax Nova Scotia  
<http://atl.awmac.com>

### Within UNITED STATES

#### SUPPORT

- **GUIDE SPECIFICATIONS** - Available in interactive digital format including quality control options at: <http://woodworkinstitute.com/publications/architectural-woodwork-standards/>
- **AIA SEMINARS** - The Woodwork Institute is a Registered Provider of the American Institute of Architects (AIA), and its Continuing Education System (CES) program, check out our offerings at: <http://woodworkinstitute.com/architectural-resources/aia-seminars/> 
- **CONSULTATION** - Contact one of our Directors of Architectural Services (DAS) at: <http://woodworkinstitute.com/about-us-2/about-us/>
- **ACCREDITED FABRICATORS AND INSTALLERS** - Our AMC's (Accredited Millwork Company) represents the best fabricators and installers in our industry, check them out at: <http://woodworkinstitute.com/membership-listing-2/> 
- **CERTIFIED INDUSTRY PROFESSIONALS** - Our CMP's (Certified Millwork Professionals) represent the knowledge base of our industry, check them out at: <http://woodworkinstitute.com/membership-listing-2/> 
- **MILLWORK INDUSTRY PARTNERS** - Our MIP's (Millwork Industry Partners) represent the best of our industries material suppliers, check them out at: <http://woodworkinstitute.com/membership-listing-2/> 
- **ACKNOWLEDGED PRODUCTS LISTING** - If it's listed here, you are assured it meets NAAWS minimum requirements, find the listing at: <http://woodworkinstitute.com/acknowledged-product-listing/> 
- **CABINET DESIGN SERIES (CDS)** - Eliminate the need to include casework elevations in your architectural drawings, check out the CDS system in NAAWS "Design Resources" and access the cad files at: <http://woodworkinstitute.com/architectural-resources/cabinet-design-series/>

#### QUALITY ASSURANCE

- **BIDDER QUALIFICATION** - A discipline of bidder pre-qualification wherein your specifications protect you and your customer from the unknown: To be eligible to bid or negotiate this job, the subcontractor must be a Woodwork Institute Accredited Millwork Company (AMC) in good standing.   
<http://woodworkinstitute.com/architectural-resources/quality-assurance>
- **CERTIFIED COMPLIANCE PROGRAM (CCP)** - A discipline of quality control used in conjunction with NAAWS providing an unbiased means of ensuring conformance to a project's plans and specifications. CCP, together with the use of the desired Grade(s) in the specifications, informs all parties of the design professional's expectations, without bidder discrimination.   
<http://woodworkinstitute.com/services/certified-compliance-program>
- **MONITORED COMPLIANCE PROGRAM (MCP)** - A discipline of quality affirmation used in conjunction with the NAAWS which provides ongoing reviews/inspections of a project from its beginning through completion, ensuring strict conformance to the design intent throughout the millwork fabrication and installation process.   
<http://woodworkinstitute.com/services/monitored-compliance-program/>
- **CERTIFIED SEISMIC INSTALLATION PROGRAM (CSIP)** - A standalone seismic assurance option which can be specified in conjunction with or without CCP or MCP, offering design professionals and project owners specific use of WI's seismic casework pre-approvals from California's Office of Statewide Health Planning and Development (OSHPD) without additional engineering costs and/or requirements, assuring proper backing has been installed in the walls when and where required.   
<http://woodworkinstitute.com/services/certified-seismic-installation-program/>

# SECTION 7

## Stairwork & Rails

## introductory information

### INTRODUCTION

Section 7 includes information on wood stairs, integral trim, handrails, and guardrails and their related parts.

Quality assurance can be achieved by adherence to these standards and will provide the owner a quality product at competitive pricing. Working with an AWMAC Member (in Canada) or a WI Certified Millwork Professional (CMP) (in the USA) and the WI Accredited Millwork Company (AMC) they represent to provide your woodwork will help ensure the understanding and performance of the quality level required. Illustrations in this Section are not intended to be all inclusive, other engineered solutions may be acceptable. In the absence of specifications; methods of fabrication are the manufacturer's choice. The design professional, by specifying compliance to these standards increases the probability of receiving the product quality expected.

### ADVISORIES

**CONTRACT DOCUMENTS**, furnished by the design professional, should clearly indicate or delineate material, fabrication, installation, and applicable building code/regulation requirements.

**CROSS GRAIN** in band sawn or laminated members might cause objectionable color variation when finished.

**EDGES** in veneer laminated members or where multiple layers are exposed by shaping might cause objectionable color variation when finished.

**CURVED MEMBERS**, depending on the Grade, can be band sawn, block laminated, or veneer laminated at the option of the manufacturer.

### RECOMMENDATIONS



- **FIELD FINISHED**, include in Division 09 of the specifications:
  - **BEFORE FINISHING**, exposed portions of woodwork shall have handling marks or effects of exposure to moisture, removed with a thorough, final sanding over all surfaces of the exposed portions, and shall be cleaned before applying sealer or finish.
  - At **CONCEALED SURFACES**, architectural woodwork that might be exposed to moisture, such as those adjacent to exterior concrete walls, shall be primed.
- **REVIEW** the GENERAL portion of Sections 3 and 4 for an overview of the characteristics and the minimum acceptable requirements of lumber and/or sheet products that might be used herein.
- **STRUCTURAL MEMBERS**, grounds, in wall blocking, backing, furring, brackets, or other anchorage which becomes an integral part of the building's walls, floors, or ceilings, required for the installation of architectural woodwork are not to be furnished or installed by the architectural woodwork manufacturer or installer.
- **DESIGN CONSIDERATIONS** - Stairs, rails, and handrail/guardrails are subject to building code requirements. Code restrictions apply to rise, run, handrail, and guardrail heights, structural strength and other issues. It is the responsibility of the design professional to comply with applicable building code(s) and regulations, and:
- **CONSULTATION** with an experienced stair builder is strongly recommended.



### SPECIFICATION CONSIDERATIONS



- **FLAME SPREAD RATING.**
- **SPECIAL CODE OR REGULATION COMPLIANCE.**
- **QUALITY ASSURANCE OPTIONS:**
  - Within CANADA**
    - **AWMAC's GUARANTEE AND INSPECTION SERVICE (GIS)** - See NAAWS's Resources page and/or <http://awmac.com/gis>
    - **AWMAC's INSPECTION SERVICE** - See NAAWS's Resources page and/or <http://awmac.com/gis>
    - **AWMAC's EXPERT OPINION SERVICE** - See NAAWS's Resources page and/or <http://awmac.com/gis>
  - Within UNITED STATES**
    - **WI'S AMC BIDDER PRE-QUALIFICATION** - See NAAWS's Resources page and/or <http://woodworkinstitute.com/architectural-resources/quality-assurance>
    - **WI'S CERTIFIED COMPLIANCE PROGRAM (CCP)** - See NAAWS's Resources page and/or <http://woodworkinstitute.com/services/certified-compliance-program>
    - **WI'S MONITORED COMPLIANCE PROGRAM (MCP)** - See NAAWS's Resources page and/or <http://woodworkinstitute.com/services/monitored-compliance-program/>
    - **WI'S CERTIFIED SEISMIC INSTALLATION PROGRAM (CSIP)** - See NAAWS's Resources page and/or <http://woodworkinstitute.com/services/certified-seismic-installation-program/>

# SECTION 7

## Stairwork & Rails

### introductory information

#### DESIGN SUMMARY

This short summary is a collection of options and illustrations about the challenges of designing and building safe stairs. This Standard cannot and does not offer this data as advice on code compliance. Safe stairs and design and engineering to meet local codes remains the responsibility of the design professional.

#### CRITICAL STEPS IN STAIR DESIGN:

- Check local code.
- Consult with an experienced stair builder to double check your geometry.
- Pre clear your stair design with the local building officials.



#### CUSTOM DESIGNED STAIRS OFFER:

- **Design flexibility:** The use of custom designed stairs in a building allows the design professional freedom of expression while meeting the functional needs of the client. Since custom woodwork is normally produced by a specialty architectural woodwork firm, dimensions can easily be changed prior to actual fabrication, if required by job conditions. Special situations such as designing for the disabled can readily be accommodated by the custom architectural woodwork manufacturer.
- **Cost effective:** Custom woodwork competes favorably with mass produced millwork, and offers practically limitless variations of design and material. Most woodwork lasts the life of the building, quality counts.

- **No restrictions:** Custom architectural woodwork permits complete freedom of selection of the numerous hardwoods and softwoods available for transparent or opaque finish. Other unique materials available from woodwork manufacturers require no further finishing at all, such as plastic laminates and decorative overlays. These materials can be fashioned into a wide variety of profiles, sizes, and configurations. The design professional has the best of both worlds, high quality and freedom of choice.

#### RUN and RISE DIMENSION POINTS




Figure: 07-001

#### TYPICAL STAIR RUNS

- **STRAIGHT**




Figure: 07-002




Figure: 07-003

# SECTION 7

## Stairwork & Rails

### introductory information

#### TYPICAL STAIR RUNS (continued)

##### • TURNING




Figure: 07-004

##### • WINDING




Figure: 07-005

#### STAIR and HANDRAIL/GUARDRAIL NOMENCLATURE





Figure: 07-006

# SECTION 7

## Stairwork & Rails


## introductory information

### HANDRAIL/GUARDRAIL COMPONENT NOMENCLATURE




Volute

Goose Neck




Quarter Turn, Rake to Level


Figure: 07-007



Half Turn




Starting Easement




Easement Rake to Level

Figure: 07-008



Turn Out Easement



Level Quarter Turn



Half Turn, Double Rake


Figure: 07-009

### HANDRAIL/GUARDRAIL FABRICATION




Large dimension rail fabrication techniques are typically the option of the manufacturer. Lamination on a radius depends on many factors:

Typical lamination orientations:




Laminated




Butcher-block

Figure: 07-010


### HANDRAIL/GUARDRAIL JOINERY




Rail Bolt



Scarf



Dowel



Miter

Figure: 07-011

Guard/Handrail illustrations may not be compliant with current or applicable codes.



### RECLAIMED or RECYCLED WOOD

#### DESIGN PROFESSIONAL RESPONSIBILITY

Use of unique materials like reclaimed or recycled wood requires a more active role of the design professional in sourcing and pre-approving desired material selections. There are no traditional guidelines with these types of materials to assure either the woodwork manufacturer or the design professional of achieving an intended result. There will be situations where the design professional will be required to directly participate in the individual piecemeal selection and layout process of the product.

**CONTRACT DOCUMENTS**, shall clearly indicate or delineate all material, fabrication, installation and applicable building code/regulation requirements with the clear understanding that incomplete design choices, changes in scope or material selection, lack of material selection, or design choices made after initial bid may impact the cost or not be possible.

The contract documents shall specifically list the material source and identifier, and address the allowable:

- Variation in color or tone, grain, distress, character, and patina.
- Defects, such as nail/bolt holes, checking, cracking, discoloration, milling marks, roughness in terms of quantity, locations, repetition, etc.
- Distortion in terms of straightness, cupping, flatness, etc.

See SECTION 3 for additional information.

### NONTRADITIONAL MATERIALS

Covers materials re-purposed from other industrial and manufacturing areas, but assigned to the woodwork manufacturer and treated similarly to traditional millwork items like wall paneling. From a design perspective considerations of appearance, color, finish, variation and relation are deemed important as they would be with traditional wood products.

Examples of non-traditional materials could be a fiber/cement panel designed for fire resistance, insulation re purposed as a decorative panel, metal products, cloth, acrylics, etc.

Because these materials are unique, contract documents, shall clearly indicate or delineate all of the necessary material, fabrication, installation and building code/regulation direction and requirements as may be applicable for the manufacturer/installer to reasonably accomplish the intended design concept..

### DESIGN RESOURCES

Is a perpetually expanding, web based resource of pictures, videos, illustrations, ideas and design concepts for inspiring thought and design creativity - assessable at: <http://naaws-design-resources.com>



Relative to this Section, offerings will include:

- Staircase pictures
  - Residential
  - Commercial

# SECTION 7

## Stairwork & Rails

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated,  
the rule applies to all Grades equally



## compliance requirements

**INCLUDING:** Wood Stairs, Integral Trim, Handrails, and Guardrails

### 7.1 BASIC CONSIDERATIONS

- 1 **GRADE**
- 1.1 These standards are characterized in three Grades of quality that may be mixed within a single project. Limitless design possibilities and a wide variety of lumber and veneer species, along with overlays, high pressure decorative laminates, factory finishes, and profiles are available in all three Grades.
- 1.2 **ECONOMY GRADE** defines the minimum quality requirements for a project's workmanship, materials, or installation and is typically reserved for woodwork that is not in public view, such as in mechanical spaces and utility areas.
- 1.3 **CUSTOM GRADE** is typically specified for and adequately covers most high quality architectural woodwork, providing a well defined degree of control over a project's quality of materials, workmanship, or installation.
- 1.4 **PREMIUM GRADE** is typically specified for use in those areas of a project where the highest level of quality, materials, workmanship, and installation is required.
- 2 **CONTRACT DOCUMENTS** shall govern in conflict with these standards.
- 3 **ACCEPTABLE REQUIREMENTS** of lumber and/or sheet products used within this woodwork product section are established by Sections 3 and 4, unless otherwise modified herein.
- 4 **AESTHETIC COMPLIANCE** requirements apply only to surfaces visible after fabrication and installation.
- 4.1 Shall be judged from a normal viewing stance and considered compliant if inconspicuous when viewed from:
- 4.1.1 72" (1830 mm) for Economy Grade
- 4.1.2 48" (1219 mm) for Custom Grade
- 4.1.3 24" (610 mm) for Premium Grade
- 4.2 For **RECLAIMED** or **RECYCLED WOOD**, the aesthetic compliance requirements of NAAWS does not apply, such shall be as agreed between owner/design professional and the woodwork manufacturer/installer.

### 7.1 BASIC CONSIDERATIONS (continued)

- 4.3 For **NON-TRADITIONAL MATERIALS**, the aesthetic compliance requirements of NAAWS does not apply, such shall be as agreed between owner/design professional and the woodwork manufacturer/installer.
- 5 **EXPOSED SURFACES INCLUDE:**
- 5.1 All visible surfaces of stringers, skirt boards, treads, risers, and balustrades.
- 6 **CONCEALED SURFACES INCLUDE:**
- 6.1 All non visible surfaces attached to and/or covered by another.
- 6.2 All non visible in wall blocking or spacers used for attachment.
- 7 To **PREVENT TELEGRAPHING**, inset solid wood edging when used must have similar moisture content as panel core, be glued securely and calibrated with panel core thickness prior to being laminated with a wood veneer on both faces.
- 8 **INDUSTRY PRACTICES**
- 8.1 **STRUCTURAL MEMBERS**, grounds, in wall blocking, backing, furring, brackets, or other anchorage that becomes an integral part of the building's walls, floors, or ceilings, that are required for the installation of architectural woodwork are not furnished or installed by the architectural woodwork manufacturer or installer.
- 8.2 **WALL, CEILING**, and/or opening variations in excess of 1/4" (6.4 mm) or **FLOORS** in excess of 1/2" (12.7 mm) in 144" (3658 mm) of being plumb, level, flat, straight, square, or of the correct size are not acceptable for the installation of architectural woodwork, nor is it the responsibility of the installer to scribe or fit to tolerances in excess of such.
- 8.3 **PRIMING** of architectural woodwork is not the responsibility of the manufacturer and/or installer, unless the material is being furnished pre-finished.
- 8.4 **RADIUS MOLDINGS** are laminated and formed, pre shaped, or machined to the radius and fabricated in the longest practical lengths to minimize installer joints.

# SECTION 7

## Stairwork & Rails

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



## compliance requirements

### 7.2 SCOPE

- 1 Wood stairs and allied wood stair material.
- 2 **TYPICAL INCLUSIONS:**
  - 2.1 Wood stringers of skirt boards.
  - 2.2 Treads, risers, nosing, and scotia.
  - 2.3 Starting steps.
  - 2.4 All wedges and glue blocks.
  - 2.5 Newels, balusters, handrails, guardrails, and crooks.
  - 2.6 Well hole trim.
  - 2.7 Shoe rail, fillet, and spandrels.
  - 2.8 All other wood parts of a stair.
  - 2.9 Installation; if un-installed, stair materials shall be furnished machined KD (knocked down).
- 3 **TYPICAL EXCLUSIONS:**
  - 3.1 Any rough horses, structural wood framing, or timbers.
  - 3.2 Any metal handrail/guardrail brackets or safety nosing.
  - 3.3 Any flooring.
  - 3.4 Priming and/or finishing of any kind.

### 7.3 DEFAULT STIPULATION

- 1 If not otherwise specified or indicated in the contract documents, all work shall be unfinished, Custom Grade, solid stock softwood intended for opaque finish. 

### 7.4 RULES

- 1 The following rules shall govern unless a project's contract documents require otherwise.
- 2 These rules are intended to provide a well defined degree of control over a project's quality of materials and workmanship.
- 3 **ERRATA**, published at <http://naaws-errata.com>, shall take precedence over these rules, subject to their date of posting and a project's bid date. 

### 7.4.4 Basic General Rules

- 1 **AESTHETIC** grade rules apply only to exposed and semi-exposed surfaces visible after installation.
- 2 **LUMBER** shall conform to the requirements established in Section 3.
- 3 **SHEET PRODUCTS** shall conform to the requirements established in Section 4.
- 4 **WOODWORK** not addressed herein shall be manufactured from solid stock, laminated stock, veneered stock, or a combination thereof.
- 5 **BACKING SHEET** shall conform to the requirements established in Section 4.
- 6 **EXPOSED SURFACES** include:
  - 6 1 All visible surfaces of stringers, skirt boards, treads, risers, and balustrades.
- 7 **CONCEALED SURFACES** include:
  - 7 1 All non visible surfaces attached to and/or covered by another.
  - 7 2 All non visible blocking or spacers used for attachment.
- 8 **STANDING** and **RUNNING TRIM** shall be furnished as material only, not assembled.
- 9 Where **MULTIPLE OPTIONS** are permitted, it shall be the manufacturer's choice unless specified otherwise.
- 10 **FLAME SPREAD RATING**, if required, shall be so specified.
- 11 **SPECIFIC PROFILE**, if required, shall be so specified or drawn.
- 12 **SPECIAL ORNAMENTAL DETAIL** or joinery, if required, shall be so specified or drawn.
- 13 **RADIUS MOLDINGS** are laminated and formed, pre shaped, or machined to the radius and fabricated in the longest practical lengths to minimize installer joints.
- 14 **TRANSPARENT FINISH**, if species is not specified, the use of either hardwood or softwood (plywood or solid stock) of one species for the entire job is permitted at the manufacturer's option.

Continues next column ▼

# SECTION 7

## Stairwork & Rails

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally




## compliance requirements

### 7.4.4 Basic General Rules

<b>▲ From previous column</b>	
15	<b>CATHEDRAL</b> type figure shall be achieved by:
15 1	A single component in "AA" Face Grade.
15 2	The split heart method in Face Grades "A - D", and:
15 2 1	Each half of a split heart shall be subject to the minimum component width requirements for Face Grade "B."
16	<b>STAIRWORK</b> , including handrail/guardrails, shall conform to applicable codes and requirements, and:
16 1	Nothing in these standards shall overrule such.
17	<b>GLUING</b> or <b>LAMINATION</b> shall be in accordance with the <b>ADHESIVE GUIDELINES</b> within the <b>APPENDIX</b> , and: 
17 1	<b>DELAMINATION</b> or <b>SEPARATION</b> shall not occur.
17 2	<b>LUMBER</b> shall conform to the requirements established in Section 3.
17 3	<b>SHEET PRODUCTS</b> shall conform to the requirements established in Section 4.
18	<b>CUTOUTS</b> in <b>HPDL</b> or <b>SOLID SURFACE</b> shall have a minimum 1/4" (6.4 mm) radius at inside corners.
19	<b>PRIMING</b> is not the responsibility of the manufacturer and/or installer, unless the material is furnished pre-finished.
20	<b>FIRST CLASS WORKMANSHIP</b> is required in compliance with these standards. 

### 7.4.5 Basic Material Rules

1	<b>SPECIES</b> and <b>GRADE</b> of lumber or sheet products shall be as specified, and:
1 1	Plain sawn lumber is required.
2	<b>DIMENSIONS</b> of finished lumber shall conform to Section 3.
3	<b>DEFECTS</b> , natural or manufactured, shall not exceed those permitted, except:
3 1	Unlimited finger joints are permitted. <span style="float: right;">E C P</span>
3 2	Are permitted if covered by adjoining members or otherwise concealed when installed.
4	<b>TREADS</b> shall be a minimum of 1" (25.4 mm) in thickness.
5	<b>CLOSED STRINGERS</b> shall be a minimum of 3/4" (19 mm) in thickness after machining and machining for treads and risers shall be a minimum of 1/2" (12.7 mm) in depth.
6	<b>FIGURE</b> is not a function of a species grade and must be specified in the contract document.
7	<b>WARP</b> , which can be held flat and straight with normal attachment is permitted.
8	<b>RADIUS WOODWORK</b> shall be constructed of solid machined, block laminated, laminated plies, core veneered, or kerfed solid stock, 
8 1	Solid stock or block lamination members shall be furnished in such sections as to avoid pronounced cross grain and reduce joints to a minimum.
8 2	Glue shall be selected for color to avoid a prominent glue line.
<b>Continues next column ▼</b>	

# SECTION 7

## Stairwork & Rails


GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally

**E C P**

# compliance requirements

7.4.5 Basic Material Rules						
▲ From previous column						
9 SOFFIT and SPANDREL PANELS shall conform to Section 8.						
10 For OPAQUE FINISH:						
10 1 Medium density fiberboard (MDF) is permitted.						
10 2 Veneer is permitted; however:						
10 2 1 SPECIES shall be of manufacturer's choice, closed grain hardwood conforming to ANSI/HPHA HP-1 (latest Edition), <a href="http://hpva.org">http://hpva.org</a> , definitions and characteristics for:						
10 2 1 1 Grade - D. <span style="float:right">E C P</span>						
10 2 1 2 Grade - C. <span style="float:right">E C P</span>						
10 2 1 3 Grade - B. <span style="float:right">E C P</span>						
11 For TRANSPARENT FINISH, VENEER:						
11 1 SPECIES of manufacturer's choice, hardwood conforming to ANSI/HPHA HP-1 (latest Edition), <a href="http://hpva.org">http://hpva.org</a> , definitions and characteristics for:						
11 1 1 1 Grade - B. <span style="float:right">E C P</span>						
11 1 1 2 Grade - A. <span style="float:right">E C P</span>						
11 1 1 3 Grade - AA. <span style="float:right">E C P</span>						
11 1 2 SLICING of:						
11 1 2 1 Manufacturer's choice. <span style="float:right">E C P</span>						
11 1 2 2 Plain sliced. <span style="float:right">E C P</span>						
11 1 3 MATCHING ADJACENT LEAVES be:						
11 1 3 1 Manufacturer's choice. <span style="float:right">E C P</span>						
11 1 3 2 Book matched. <span style="float:right">E C P</span>						
11 1 4 MATCHING WITHIN PANEL FACE be:						
11 1 4 1 Running. <span style="float:right">E C P</span>						
11 1 4 2 Balance. <span style="float:right">E C P</span>						
11 1 5 MATCHING BETWEEN ADJACENT PANELS be:						
11 1 5 1 Manufacturer's choice. <span style="float:right">E C P</span>						
11 1 5 2 Compatible for color and grain. <span style="float:right">E C P</span>						
11 1 5 3 Well matched for color and grain, and: <span style="float:right">E C P</span>						
11 1 5 4 END, SEQUENCE, and BLUEPRINT MATCHING shall be specified.						
Continues next column ▼						

7.4.5 Basic Material Rules						
▲ From previous column						
12 EXPOSED SURFACES:						
12 1 End grain shall be kept to a minimum. <span style="float:right">E C P</span>						
12 2 Ends to be self returned with no end grain showing.						
<div style="display: flex; align-items: center;">  <div style="margin-left: 20px;"> <span style="float:right">E C P</span> </div> </div>						
12 3 Medium density fiberboard (MDF) is permitted for opaque finish.						
12 4 Sheet product edges shall be edgebanded with the same species as the face. <span style="float:right">E C P</span>						
12 5 Plain sliced veneer is required for transparent finish.						
12 6 Manufacturers' choice veneer is permitted for opaque finish.						
12 7 TRANSPARENT FINISH:						
12 7 1 Hardwood or softwood is permitted.						
12 7 2 Only one species is permitted for the entire project. <span style="float:right">E C P</span>						
12 7 3 Finger joints are prohibited. <span style="float:right">E C P</span>						
12 7 4 Adhesive used for laminating shall be selected for color to avoid a prominent glue line. <span style="float:right">E C P</span>						
12 7 5 Lumber (including block segments or veneer of laminated material) and sheet products are to be compatible in color and grain. <span style="float:right">E C P</span>						
12 7 6 Lumber (including block segments or veneer of laminated material) are to be well matched for color and grain; sheet products shall be compatible in color with solid stock, and adjacent sheet products shall be well matched for color and grain. <span style="float:right">E C P</span>						
12 7 7 Intersections of radius and straight members are to be splined or half lapped, securely glued, and mechanically fastened. <span style="float:right">E C P</span>						
12 7 8 BLOCK LAMINATION:						
12 7 8 1 Segments shall be cut from the same board. <span style="float:right">E C P</span>						
12 7 8 2 Segment joints shall be staggered.						
12 7 8 3 Adjacent segment ends shall have similar grain angle. <span style="float:right">E C P</span>						
Continues next column ▼						

# SECTION 7

## Stairwork & Rails

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally

**E C P**

## compliance requirements

7.4.5 Basic Material Rules					
▲ From previous column					
12		EXPOSED SURFACES (continued)			
12	7	TRANSPARENT FINISH (continued)			
12	7	9	VENEER LAMINATIONS:		
12	7	9	1	Exposed layers shall be sawn from the same or matched boards.	E C P
12	7	9	2	Veneer layers shall be reassembled in the same order and orientation as cut.	E C P
12	7	10	Visible panel edges, reveals, and/or splines, when appropriate, shall be:		
12	7	10	1	Full length.	
12	7	10	2	Manufacturers' choice.	E C P
12	7	10	3	Same species as panel face.	E C P
12	7	10	4	Compatible for color and grain.	E C P
12	7	10	5	Well matched for color and grain.	E C P
12	7	10	6	A minimum of 0.020" (0.5 mm) nominal thickness that precludes show through of core.	E C P
13	CONCEALED SURFACES:				
13	1	Allows defects such as voids, wane, or unfilled knots.			
13	2	Required blocking or shims shall be of a compatible material.			
14	BOXED or CURB STRINGERS, shall be of two or more members.				
15	STRINGER TURNOUTS, including quarter turns, half turns, and the like, shall be of laminated or veneered face construction, and:				
15	1	Such turns shall be a continuous part of the straight stringer, where feasible.			
16	GLUE UP is permitted of handrails, guardrails, newel posts, and balusters.				
17	RISERS, bull nosed or radius, shall be veneered construction with one piece face.				
18	FACTORY FINISHING, when specified, shall have concealed surfaces factory sealed at 1 mil dry.				E C P

7.4.6 Basic Machining Rules					
1	EXPOSED SURFACES shall comply with:				
1	1	SMOOTHNESS REQUIREMENTS (see SMOOTHNESS in TESTS) and:			
1	1	1	SHARP EDGES are to be eased with fine abrasive.		E C P
1	1	2	TOP FLAT WOOD surfaces; those that can be sanded with a drum or wide belt sander, requires:		
1	1	2	1	Minimum 15 KCPI or 100 grit sanding.	E C P
1	1	2	2	120 grit sanding.	E C P
1	1	2	3	150 grit sanding.	E C P
1	1	3	PROFILED and SHAPED WOOD surfaces require:		
1	1	3	1	Minimum 15 KCPI or 100 grit sanding.	E C P
1	1	3	2	Minimum 20 KCPI or 120 grit sanding.	E C P
1	1	3	3	120 grit sanding.	E C P
1	1	4	TURNED WOOD surfaces require:		
1	1	4	1	Minimum 15 KCPI or 100 grit sanding.	E C P
1	1	4	2	120 grit sanding.	E C P
1	1	4	3	180 grit sanding.	E C P
1	1	5	CROSS SANDING, excluding turned surfaces, is:		
1	1	5	1	Not a defect.	E C P
1	1	5	2	Not allowed.	E C P
1	1	6	TEAR OUTS, KNIFE NICKS, or HIT OR MISS machining are not permitted.		
1	1	7	KNIFE MARKS are not permitted where sanding is required.		
1	1	8	GLUE or FILLER, if used, shall be inconspicuous and match adjacent surface for smoothness.		
Continues next column ▼					

# SECTION 7



## Stairwork & Rails



GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally

**E C P**

# compliance requirements

7.4.6 Basic Machining Rules						
▲ From previous column						
1	EXPOSED SURFACES (continued):					
1	2	HPDL, PVC, and PRE-FINISHED WOOD edges shall be machined flush and filed, sanded, or buffed to remove machine marks and sharp edges, and:				
1	2	1	OVERLAP (See Test F illustrations in TESTS) such as,			
						
			shall not exceed:			
1	2	1	1	0.005" (0.13 mm) for a maximum length of 2" (50.8 mm) in any 12" (305 mm) run.	E	C P
1	2	1	2	0.005" (0.13 mm) for a maximum length of 1" (25.4 mm) in any 24" (610 mm) run.	E	C P
1	2	1	3	0.003" (0.08 mm) for a maximum length of 1" (25.4 mm) in any 48" (1220 mm) run.	E	C P
1	2	2	CHIP OUT (See Test G illustrations in TESTS) such as,			
						
			shall be inconspicuous when viewed at:			
1	2	2	1	72" (1829 mm).	E	C P
1	2	2	2	48" (1220 mm).	E	C P
1	2	2	3	24" (610 mm).	E	C P
Continues next column ▼						

7.4.6 Basic Machining Rules							
▲ From previous column							
1	EXPOSED SURFACES (continued):						
1	2	HPDL, PVC, and PRE-FINISHED WOOD edges (continued):					
1	2	3	OVER MACHINED (See Test H illustrations in TESTS) removal of color or pattern of face material such as,				
							
			shall be limited to:				
1	2	3	1	3/32" x 6" (2.4 mm x 152 mm) and may not occur within 48" (1220 mm) of a similar occurrence.	E	C P	
1	2	3	2	1/32" x 4" (0.8 mm x 102 mm) and may not occur within 60" (1524 mm) of a similar occurrence.	E	C P	
1	2	3	3	1/32" x 1-1/2" (0.8 mm x 38.1 mm) and may not occur within 72" (1829 mm) of a similar occurrence.	E	C P	
2	TRIM to be applied on flat surfaces shall have the reverse side backed out, except at those members that have exposed ends, and:						
2	1	Trim over 2" (50.8 mm) in width with unexposed ends shall be backed out.				E	C P
3	BAND SAWN and BLOCK LAMINATED members shall be divided to minimize the exposure of cross grain in the face of the member, and:						
3	1	Grain angle at the face of curved members shall not exceed 30 degrees, unless a small part size requires otherwise.				E	C P
							
4	INTERSECTIONS at radius and straight members shall be splined or half lapped, securely glued, and mechanically fastened.						
Continues next column ▼							

# SECTION 7

## Stairwork & Rails

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



## compliance requirements

7.4.6		Basic Machining Rules	
▲ From previous column			
5	DADOES shall completely house the male member throughout the entire length of the joint.	E	C P
6	PROFILE for items such as nosing, handrail/guardrail, or balusters, if not indicated, shall be manufacturer's choice.		
7	FACE STRINGERS at open end stairs shall be cut and mitered to receive treads and risers.		
8	SHOE RAIL shall include them being plowed to receive balusters and fillet, unless otherwise indicated.		
9	SCOTIA or COVE MOLD, if indicated, shall be provided for each riser; and for open string stairs, shall be mitered with the end returned.		
10	CLOSED STRINGERS shall include machining to receive the treads, risers, and wedges.	E	C P
11 TREADS at open string stairs shall include:			
11 1	Boring or cutting required to receive balusters.	E	C P
11 2	Exposed ends of treads shaped to match nosing.	E	C P
11 3	Exposed ends of treads shall have a mitered return nosing, and:	E	C P
11 3 1	Leading corner of the tread return shall be mitered to the leading edge of the tread with a shoulder miter, and:	E	C P
11 3 1 1	Doweled or biscuit spline joined.	E	C P
12 RISERS shall be rabbeted to receive the back edge of the tread, and:			
12 1	At open string stairs shall be mitered.		
13	RAILS to receive balusters with square or rectangular heads shall be plowed on under side and provided with fillet.		
14	NEWEL POSTS, when built up, shall be of shoulder miter, lock joint, tongues, or splined construction.		

7.4.7		Basic Assembly Rules	
1 THESE STANDARDS do not establish Grade rules for joint flushness and or gap tolerances for woodwork products installed in a non climate controlled environment; however:			
1 1	Prior to installation, the flushness and/or gap tolerances of woodwork products intended for non climate controlled environments shall meet the test requirements herein.		
2 JOINTS at ASSEMBLED WOODWORK shall be:			
2 1	Neatly and accurately made.		
2 2	Securely glued with residue removed from exposed and semi-exposed surfaces, and:		
2 2 1	Reinforced with glue blocks where essential.		
2 3	Assembled at stringer aprons, fascias, and flat base with:		
2 3 1	Clamp nail, biscuit spline, spline, butterfly, scarf, or dowel joinery.	E	C P
2 3 2	Biscuit spline, spline, butterfly, scarf, or dowel joinery.	E	C P
2 4 HANDRAILS/GUARDRAILS shall utilize:			
2 4 1	Clamp nails or stair bolts.	E	C P
2 4 2	Stair bolts.	E	C P
2 4 3	Stair bolts and dowels.	E	C P
2 4 4	When mitered, screws if stair bolts are impractical, and		
2 4 4 1	Have holes plugged, unless covered by fillet, and shall be:		
2 4 4 1 1	Compatible for color and grain.	E	C P
2 4 4 1 2	Well matched for color and grain.	E	C P
2 4 4 1 3	Aligned with handrail/guardrail grain.	E	C P
2 5 MECHANICALLY FASTENED with nails or screws, where practical, and at solid wood:			
2 5 1	Countersunk.		
2 5 2	In molding quirks or reliefs where possible.	E	C P
2 6	FREE of exposed fasteners at exposed surfaces of decorative laminate sheet products.		
Continues next column ▼			

# SECTION 7


## Stairwork & Rails


GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally

**E C P**

# compliance requirements

7.4.7 Basic Assembly Rules					
▲ From previous column					
<b>2 JOINTS at ASSEMBLED WOODWORK</b> (continued)					
2 7	Require <b>FLUSHNESS VARIATIONS</b> at exposed surfaces (See Test D illustrations in TESTS), when mitered or butted, such as,				
					
not to exceed:					
2 7 1	0.010" (0.25 mm).	E	C	P	
2 7 2	0.007" (0.18 mm).	E	C	P	
2 7 3	0.005" (0.13 mm).	E	C	P	
2 8	Allow <b>GAPS</b> at exposed surface (see Test A illustrations in TESTS), when mitered or butted, such as,				
					
not to exceed:					
2 8 1	0.025" (0.64 mm) wide by 20% of the joint length.	E	C	P	
2 8 2	0.015" (0.38 mm) wide by 20% of the joint length.	E	C	P	
2 8 3	0.010" (0.25 mm) wide by 20% of the joint length.	E	C	P	
<b>Continues next column ▼</b>					

7.4.7 Basic Assembly Rules					
▲ From previous column					
<b>2 JOINTS at ASSEMBLED WOODWORK</b> (continued)					
2 9	Allow <b>GAPS</b> at exposed surface joints of parallel members (See Test B illustrations in TESTS), such as				
					
not to exceed:					
2 9 1	0.025" x 9" (0.64 mm x 229 mm) shall not occur within 48" (1219 mm) of a similar gap in the same joint.	E	C	P	
2 9 2	0.015" x 6" (0.38 mm x 152 mm) shall not occur within 60" (1524 mm) of a similar gap in the same joint.	E	C	P	
2 9 3	0.010" x 4" (0.25 mm x 102 mm) shall not occur within 72" (1829 mm) of a similar gap in the same joint.	E	C	P	
2 10	Allow <b>GAPS</b> at exposed surface joints (See Test C illustrations in TESTS) when mitered or butted, such as				
					
not to exceed:					
2 10 1	0.025" (0.64 mm).	E	C	P	
2 10 2	0.015" (0.38 mm).	E	C	P	
2 10 3	0.010" (0.25 mm).	E	C	P	
2 11	<b>FILLER</b> is permitted:				
2 11 1	If inconspicuous when viewed at 36" (914 mm).	E	C	P	
2 11 2	If inconspicuous when viewed at 24" (610 mm).	E	C	P	
2 11 3	Not allowed.	E	C	P	
<b>Continues next column ▼</b>					

# SECTION 7

## Stairwork & Rails

GENERAL/**PRODUCT**/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally




## compliance requirements

### 7.4.7 Basic Assembly Rules

▲ From previous column

**FLATNESS** or **WARP** of installed and removable sheet products (see Test E illustrations in **TESTS**) such as



shall not to exceed grade tolerance listed for 12" (303 mm) diagonal, width and/or length or as lineal ratio (not geometric ratio) thereof. Example, twice the grade tolerance listed for 24" (610 mm), three times the tolerance for 36" (914 mm):

3	1	0.045" (1.1 mm) per 12" (305 mm) or portion thereof.	<b>E</b>	<b>C</b>	<b>P</b>
3	2	0.030" (0.8 mm) per 12" (305 mm) or portion thereof.	<b>E</b>	<b>C</b>	<b>P</b>
3	3	0.020" (0.5 mm) per 12" (305 mm) or portion thereof.	<b>E</b>	<b>C</b>	<b>P</b>

4 **APPLIED MOLDINGS** shall be spot glued and mechanically fastened.

5 **MITER JOINTS** shall be well fitted and cleaned.

6 **BUILT UP ITEMS** shall be soundly fabricated with half lapped, mitered, shoulder mitered, tonged, or equivalent construction.

7 **SHEET** and **LAMINATED LUMBER PANELS** shall be allowed to move, float, expand or contract in reaction to ambient humidity changes.

8 **STAIRWORK** shall be furnished KD (knocked down), with:

8	1	<b>TRIM MEMBERS</b> cut to required length plus allowance for fitting.
8	2	<b>STARTING STEPS</b> with return riser assembled ready for installation.
8	3	<b>SCOTIA</b> and <b>SHOE MOLDS</b> temporarily attached.
8	4	<b>BALUSTERS</b> for open string stairs shall be provided with dowel or tenon to fit into treads.
8	5	<b>CROOKS</b> and <b>RETURNS</b> shall be doweled and provided with rail bolts ready for assembly.
8	6	<b>GLUE BLOCKS</b> shall be provided at a minimum of 12" (305 mm) on center for each riser.



# SECTION 7

## Stairwork & Rails

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



## compliance requirements

### 7.5 PREPARATION and QUALIFICATION REQUIREMENTS (unless otherwise specified)

- 1 **CARE, STORAGE, and BUILDING CONDITIONS** shall be in compliance with the requirements set forth in Section 2 of these standards.
- 1.1 Severe damage to the woodwork can result from noncompliance. The manufacturer and/or installer of the woodwork shall not be held responsible for any damage that might develop by not adhering to the requirements.
- 2 **CONTRACTOR IS RESPONSIBLE FOR:** 
- 2.1 Furnishing and installing structural members, grounds, in wall blocking, backing, furring, brackets, or other anchorage required for architectural woodwork installation that becomes an integral part of walls, floors, or ceilings to which architectural woodwork shall be installed.
- 2.1.1 In the absence of contract documents calling for the contractor to supply the necessary in wall blocking/backing in the wall or ceilings, either through inadvertence or otherwise, the architectural woodwork installer shall not proceed with the installation until such time as the in wall blocking/backing is installed by others.
- 2.1.2 Preparatory work done by others shall be subject to inspection by the architectural woodwork installer, and shall be accepted or rejected for cause prior to installation.
- 2.1.2.1 **WALL, CEILING, and/or OPENING VARIATIONS** in excess of 1/4" (6.4 mm) or **FLOORS** in excess of 1/2" (12.7 mm) in 144" (3658 mm) of being plumb, level, flat, straight, square, or of the correct size are not acceptable for the installation of architectural woodwork, nor is it the responsibility of the installer to scribe or fit to tolerances in excess of such.
- 2.2 Installation site being properly ventilated, protected from direct sunlight, excessive heat and/or moisture, and that the HVAC system is functioning and maintaining the appropriate relative humidity and temperature.

### 7.5 PREPARATION and QUALIFICATION (continued)

- 2.3 Priming the architectural woodwork in accordance with the contract documents prior to its installation, and:
- 2.3.1 If the architectural woodwork is factory finished, priming by the factory finisher is required.
- 3 **INSTALLER IS RESPONSIBLE FOR:** 
- 3.1 Having adequate equipment and experienced craftsmen to complete the installation in a first class manner.
- 3.2 Checking architectural woodwork specified and studying the appropriate portions of the contract documents, including these standards and the reviewed shop drawings to familiarize themselves with the requirements of the Grade specified, understanding that:
- 3.2.1 Appearance requirements of Grades apply only to surfaces visible after installation.
- 3.2.2 For transparent finish, special attention needs to be given to the color and the grain of the various woodwork pieces to ensure they are installed in compliance with the Grade specified.
- 3.3 Verification that installation site is properly ventilated, protected from direct sunlight, excessive heat and/or moisture, and that the HVAC system is functioning and maintaining the appropriate relative humidity and temperature.
- 3.4 Verification that required priming of woodwork has been completed by others before woodwork is installed.
- 3.5 Verification that woodwork has been acclimated to the field conditions for a minimum of 72 hours before installation is commenced.
- 3.6 Woodwork specifically built or assembled in sequence for match of color and grain is installed to maintain that same sequence.

# SECTION 7

## Stairwork & Rails

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally

<b>E</b>	<b>C</b>	<b>P</b>
----------	----------	----------

## compliance requirements

### 7.6 RULES

- 1 The following rules shall govern unless a project's contract documents require otherwise.
- 2 These rules are intended to provide a well defined degree of control over a project's quality of installation.
- 3 **ERRATA**, published at <http://naaws-errata.com>, shall take precedence over these rules, subject to their date of posting and a project's bid date.



7.6.4		Basic General Rules		
1	<b>AESTHETIC</b> Grade rules apply only to exposed and semi-exposed surfaces visible after installation.			
2	<b>TRANSPARENT</b> finished woodwork shall be installed with:			
2 1	<b>CONSIDERATION</b> of color and grain.	E	C	P
2 2	<b>COMPATIBLE</b> in color and grain.	E	C	P
2 3	<b>WELL MATCHED</b> for color and grain, and:	E	C	P
2 3 1	Sheet products shall be compatible in color with solid stock.	E	C	P
2 3 2	Adjacent sheet products shall be well matched for color and grain.	E	C	P
3	<b>INSTALLER FABRICATION</b> or <b>MODIFICATIONS</b> shall comply to the general, material, machining, and assembly rules within the <b>PRODUCT</b> portion of this section and, if applicable, the finishing rules in Section 5.			
4	<b>REPAIRS</b> are allowed, provided they are neatly made and inconspicuous when viewed at:			
4 1	72" (1830 mm).	E	C	P
4 2	48" (1219 mm).	E	C	P
4 3	24" (610 mm).	E	C	P
5	<b>WOODWORK</b> shall be:			
5 1	<b>SECURELY</b> fastened and tightly fitted with flush joints, and:			
5 1 1	Joinery shall be consistent throughout the project.			
5 2	Of maximum available and/or practical length.	E	C	P
5 3	<b>TRIMMED EQUALLY</b> from both sides when fitted for width.	E	C	P
5 4	<b>SPLINE</b> or <b>DOWELED</b> when miters are over 4" (100 mm) long.	E	C	P
Continues next column ▼				

7.6.4		Basic General Rules		
▲ From previous column				
5	<b>WOODWORK</b> (continued)			
5 5	<b>PROFILED</b> or <b>SELF MITERED</b> when trim ends are exposed.	E	C	P
5 6	<b>SELF MITERED</b> when trim ends are exposed.	E	C	P
5 7	<b>MITERED</b> at outside corners.			
5 8	<b>MITERED</b> at inside corners.	E	C	P
5 9	<b>COPE</b> d at inside corners.	E	C	P
5 10	<b>INSTALLED</b> plumb, level, square, and flat within 1/8" (3.2 mm) in 96" (2438 mm), and when required:			
5 10 1	<b>GROUND</b> s and <b>HANGING SYSTEMS</b> set plumb and true.	E	C	P
5 11	Installed <b>FREE</b> of:			
5 11 1	Warp, twisting, cupping, and/or bowing that cannot be held true.			
5 11 2	Open joints, visible machine marks, cross sanding, tears, nicks, chips, and/or scratches.			
5 11 3	Natural defects exceeding the quantity or size limits defined in Sections 3 & 4.			
5 12	<b>SMOOTH</b> and <b>SANDED</b> without <b>CROSS SCRATCHES</b> in conformance to the <b>PRODUCT</b> portion of this section.			
5 13	<b>SCRIBED</b> at:			
5 13 1	Flat surfaces.	E	C	P
5 13 2	Shaped surfaces.	E	C	P
6	<b>THESE STANDARDS</b> do not establish Grade rules for joint flushness and or gap tolerances for woodwork products installed in a non climate controlled environment.			
Continues next column ▼				

# SECTION 7


## Stairwork & Rails


GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



# compliance requirements

7.6.4 Basic General Rules	
▲ From previous column	
<b>GAPS</b> at field installation (see Test I illustrations in TESTS) such as, 	
and:	
7 1	<b>CAUSED</b> by <b>EXCESSIVE DEVIATIONS</b> (deviations in excess of 1/4" (6.4 mm) in 144" [3658 mm] of being plumb, level, flat, straight, square, or of the correct size) in the building's walls and ceilings, or 1/2" (12.7 mm) for floors, shall not be considered a defect or the responsibility of the installer.
7 2	Shall not exceed 30% of a joint's length, and <b>FILLER</b> or <b>CAULKING</b> is allowed:
7 2 1	If color compatible: <span style="float: right;">E C P</span>
7 2 2	At <b>WOOD</b> to <b>WOOD</b> shall not exceed:
7 2 2 1	At <b>FLAT</b> surfaces:
7 2 2 1 1	0.030" (0.76 mm) in width. <span style="float: right;">E C P</span>
7 2 2 1 2	0.020" (0.51 mm) in width. <span style="float: right;">E C P</span>
7 2 2 1 3	0.015" (0.38 mm) in width. <span style="float: right;">E C P</span>
7 2 2 2	At <b>SHAPED</b> surfaces:
7 2 2 2 1	0.040" (1.02 mm) in width. <span style="float: right;">E C P</span>
7 2 2 2 2	0.025" (0.64 mm) in width. <span style="float: right;">E C P</span>
7 2 2 2 3	0.015" (0.38 mm) in width. <span style="float: right;">E C P</span>
7 2 3	Of <b>WOOD</b> to <b>NON WOOD</b> shall not exceed:
7 2 3 1	At <b>FLAT</b> and <b>SHAPED</b> surfaces:
7 2 3 1 1	0.075" (1.91 mm) in width. <span style="float: right;">E C P</span>
7 2 3 1 2	0.050" (1.27 mm) in width. <span style="float: right;">E C P</span>
7 2 3 1 3	0.035" (0.89 mm) in width. <span style="float: right;">E C P</span>
Continues next column ▼	

7.6.4 Basic General Rules	
▲ From previous column	
7	<b>GAPS</b> (continued)
7 2	Shall not exceed (continued)
7 2 4	Of <b>NON WOOD</b> to <b>NON WOOD</b> and/or <b>ALL ELEMENTS</b> shall not exceed:
7 2 4 1	At <b>FLAT</b> surfaces:
7 2 4 1 1	0.075" (1.91 mm) in width. <span style="float: right;">E C P</span>
7 2 4 1 2	0.050" (1.27 mm) in width. <span style="float: right;">E C P</span>
7 2 4 1 3	0.035" (0.89 mm) in width. <span style="float: right;">E C P</span>
7 2 4 2	At <b>SHAPED</b> surfaces:
7 2 4 2 1	0.120" (3.05 mm). <span style="float: right;">E C P</span>
7 2 4 2 2	0.075" (1.91 mm). <span style="float: right;">E C P</span>
7 2 4 2 3	0.050" (1.27 mm). <span style="float: right;">E C P</span>
<b>FLUSHNESS</b> of field joinery (see Test J illustrations in TESTS), such as, 	
and:	
8 1	At <b>WOOD</b> to <b>WOOD</b> shall not exceed:
8 1 1	At <b>FLAT</b> surfaces:
8 1 1 1	0.025" (0.64 mm). <span style="float: right;">E C P</span>
8 1 1 2	0.015" (0.38 mm). <span style="float: right;">E C P</span>
8 1 1 3	0.010" (0.25 mm). <span style="float: right;">E C P</span>
8 1 2	At <b>SHAPED</b> surfaces:
8 1 2 1	0.40" (0.97 mm). <span style="float: right;">E C P</span>
8 1 2 2	0.025" (0.65 mm). <span style="float: right;">E C P</span>
8 1 2 3	0.020" (0.51 mm). <span style="float: right;">E C P</span>
8 2	At <b>WOOD</b> to <b>NON WOOD</b> shall not exceed:
8 2 1	At <b>FLAT</b> and <b>SHAPED</b> surfaces:
8 2 1 1	0.075" (1.91 mm). <span style="float: right;">E C P</span>
8 2 1 2	0.050" (1.27 mm). <span style="float: right;">E C P</span>
8 2 1 3	0.035" (0.89 mm). <span style="float: right;">E C P</span>
Continues next column ▼	

# SECTION 7

## Stairwork & Rails

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



## compliance requirements

7.6.4		Basic General Rules				
▲ From previous column						
8	3	At <b>NON WOOD</b> to <b>NON WOOD</b> and/or <b>ALL ELEMENTS</b> shall not exceed:				
8	3	1	At <b>FLAT</b> surfaces:			
8	3	1	1	0.075" (1.91 mm).	E C P	
8	3	1	2	0.050" (1.27 mm).	E C P	
8	3	1	3	0.035" (0.89 mm).	E C P	
8	3	2	At <b>SHAPED</b> surfaces:			
8	3	2	1	0.120" (3.05 mm).	E C P	
8	3	2	2	0.075" (1.91 mm).	E C P	
8	3	2	3	0.050" (1.27 mm).	E C P	
9 <b>FASTENING and FASTENERS</b> shall:						
9	1	Include the use of construction adhesive, finish nails, trim screws, and/or pins, and:				
9	2	Not permit the use of drywall, bugle head, or case hardened screws.				
9	3	Be countersunk when through an exposed surface, and:				
9	3	1	Set in quirks and reliefs where possible.			E C P
9	3	2	Inconspicuous, as defined in the Glossary.			E C P
9	4	Allow use of construction adhesive for inconspicuous fastening.				
9	5	Not permit exposed fastening through decorative laminate.				
9	6	<b>REQUIRE</b> allowable fastener holes, when:				
9	6	1	Pre-finished materials to be filled by the installer with matching filler furnished by the manufacturer.			
9	6	2	Unfinished materials to be filled by the paint contractor or others.			
10 <b>GLUE</b> and filler residue is not permitted on exposed faces.						
11 <b>EQUIPMENT CUTOUTS</b> , including electrical and plumbing, shall be cut out by the installer, provided any needed templates are furnished prior to installation, and:						
11	1	Shall be neatly cut and properly sized to be covered by standard cover plates or rosettes.				
11	2	In <b>HPDL</b> or <b>SOLID SURFACE</b> shall have a minimum 1/4" (6.4 mm) radius at inside corners.				
Continues next column ▼						

7.6.4		Basic General Rules				
▲ From previous column						
12	<b>HARDWARE</b> shall be installed:					
12	1	Neatly without tear out of surrounding stock.			E C P	
12	2	Per manufacturer's instructions.				
12	3	Using all furnished fasteners and fasteners' provisions and when fastener provisions are countersunk, fasteners shall be countersunk.				
12	4	And adjusted for smooth operation.				
13 <b>AREAS</b> of <b>INSTALLATION</b> shall be left broom clean, with:						
13	1	Debris removed and dumped in containers provided by the contractor.				
13	2	Items installed cleaned of pencil or ink marks.				
14	<b>FIRST CLASS WORKMANSHIP</b> is required in compliance with these standards.					



# SECTION 7

## Stairwork & Rails

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally




## compliance requirements

### 7.7 BASIC CONSIDERATIONS

- 1 **TOLERANCES** typically found within NAAWS:
- 1.1 Fall into two **CATEGORIES**:
- 1.1.1 Factory fabricated joinery, assembly and construction - found in the **PRODUCT** portion.
- 1.1.2 Field installation joinery and assembly - found in the **INSTALLATION** portion.
- 1.2 **INCLUDE:**
- 1.2.1 Flatness of wood based panel products.
- 1.2.2 Solid wood to solid wood joints and assemblies.
- 1.2.3 Solid wood to wood veneer joints and assemblies.
- 1.2.4 Wood veneer to wood veneer joints and assemblies.
- 1.2.5 Solid wood to wood based product joints and assemblies (decorative laminate Solid Phenolic and panel products).
- 1.2.6 Solid surface to solid surface joints and assemblies.
- 1.3 **EXCLUDE:**
- 1.3.1 **BECAUSE of EXPANSION and CONTRACTION DIFFERENCES of non-wood products compared to solid wood and wood based products, these Standards do not apply tolerances regarding flatness or joinery to:** 
- 1.3.1.1 Solid wood to non-wood based products (which can be drywall, glass, metal, stone, acrylics, and other surfaces).
- 1.3.1.2 Non-wood to non-wood joints.

### 7.7 BASIC CONSIDERATIONS (continued)

- 2 **FABRICATED and INSTALLED** woodwork shall be tested for compliance to these standards as follows.
- 2.1 **SMOOTHNESS** of exposed surfaces:
- 2.1.1 **KCPI** (Knife Cuts Per Inch) is determined by holding the surfaced board at an angle to a strong light source and counting the visible ridges per inch, usually perpendicular to the profile.
- 
- Figure: 7-012
- 2.1.2 **SANDING** is checked for compliance by sanding a sample piece of the same species with the required grit of abrasive, and:
- 2.1.2.1 Observation with a hand lens of the prepared sample and the material in question will offer a comparison of the scratch marks of the abrasive grit.
- 2.1.2.2 Reasonable assessment of the performance of the finished product will be weighed against absolute compliance with the standard.
- 2.1.2.3 A product is sanded sufficiently smooth when knife cuts are removed and remaining sanding marks are or will be concealed by applied finishing coats.
- 2.1.2.4 Grain raise at unfinished wood, due to moisture or humidity in excess of the ranges set forth in this standard, shall not be considered a defect and must be sanded prior to finishing.
- 2.2 **GAPS, FLUSHNESS, FLATNESS and ALIGNMENT:**
- 2.2.1 Maximum gaps between exposed components shall be tested with a feeler gauge at points designed to join, where members contact or touch.
- 2.2.2 Joint length shall be measured with a ruler with minimum 1/16" (1 mm) divisions and calculations made accordingly.
- 2.2.3 Reasonable assessment of the performance of the finished product will be weighed against absolute compliance with the standards.

# SECTION 7

## Stairwork & Rails

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally




**compliance requirements**

### 6.7 BASIC CONSIDERATIONS (continued)

#### 2.2 GAPS, FLUSHNESS, FLATNESS and (continued):

2.2.4 The following is intended to provide examples of how and where compliance testing is measured:



- A - Fabrication Gaps When Surfaces Are Mitered Or Butted
- B - Fabrication Gaps When Parallel Pieces Are Joined
- C - Fabrication Gaps When Edges Are Mitered Or Butted
- D - Fabrication Flushness Between Two Surfaces
- E - Flatness Of Panel Product

- F - Overlap
- G - Chip Out
- H - Over Machined
- I - Installation Gaps
- J - Installation Flushness

Figure: 07-013

# North American Architectural Woodwork Standards - 3.1

## **S E C T I O N - 08**

# WALL/CEILING SURFACING & PARTITIONS

<b>Resources . . . . .</b>	<b><a href="#">211</a></b>
<b>Introduction . . . . .</b>	<b><a href="#">213</a></b>
<b>Advisories . . . . .</b>	<b><a href="#">213</a></b>
<b>Recommendation . . . . .</b>	<b><a href="#">213</a></b>
<b>Specification Considerations . . . . .</b>	<b><a href="#">214</a></b>
<b>Design Resources . . . . .</b>	<b><a href="#">231</a></b>
<b>Compliance Requirements . . . . .</b>	<b><a href="#">232</a></b>
<b>Scope &amp; Default Stipulation . . . . .</b>	<b><a href="#">234</a></b>
<b>Basic Requirements . . . . .</b>	<b><a href="#">235</a></b>
<b>Annexes 8A - 8D (Material Specific) . . . . .</b>	<b><a href="#">241</a></b>
<b>Installation Requirements . . . . .</b>	<b><a href="#">250</a></b>
<b>Tests . . . . .</b>	<b><a href="#">257</a></b>

# SECTION 8

## Wall/Ceiling Surfacing and Partitions

### resources

### Within CANADA

#### SUPPORT

- **GUIDE SPECIFICATIONS** – Available for download in interactive digital format, including specification wording for Quality Assurance Program (GIS) at: <http://awmac.com/guide-specifications>
- **CONSULTATION** – Contact any of the local chapters for more information on the NAAWS or any other Architectural Woodwork Questions you may have. See below for contact information.
- **SPECIFICATION REVIEW** – Contact any of the local chapters if you would like your specifications reviewed for compliance to the NAAWS.
- **MANUFACTURER STANDARDS QUESTIONNAIRE (MSQ)** – AWMAC Manufacturer members have the opportunity to have at least one member of their staff study and write the MSQ. The MSQ is a questionnaire on the NAAWS and policy and procedures of the GIS program. A list of Manufacturer members that have passed the MSQ is available at: <http://awmac.com/members>
- **SEMINARS AND PRESENTATIONS** – Contact your local chapter to arrange an informative presentation on any Architectural Woodwork topic. Some topic options – GIS, NAAWS, How to Specify Quality Architectural Woodwork...
- **TRADE SHOWS** – Contact your local chapter to arrange for AWMAC to have a booth or do a presentation on Architectural Woodwork.
- **CONFERENCE** – AWMAC has an annual conference held at unique venues across Canada. The conferences provide an opportunity to learn more about Architectural Woodwork and network with Suppliers and Manufacturers from across Canada. More information is available at: <http://awmac.com/>
- **EDUCATION PARTNERS** – Contact the local chapters to find out more information about support for local Colleges and Universities offering woodworking related courses and programs.

#### QUALITY ASSURANCE

- **GUARANTEE AND INSPECTION SERVICE (GIS)** – The GIS is a national program designed to ensure that project owners get value and quality for their investment by:
  - Supporting architects and design professionals to achieve project plans and specifications; and
  - Helping contractors avoid problems such as cost overruns, delays and loss of reputation.More information is available at: <http://awmac.com/gis>

- **INSPECTION SERVICE** – A GIS Certified Inspector will inspect specific areas of concern on a project for compliance to the NAAWS and provide a written report. Contact your local chapter for more information.
- **EXPERT OPINION** – An expert will be appointed to inspect specific areas of concern on a project and provide a written report. Contact your local chapter for more information.

#### AWMAC CHAPTERS

- AWMAC British Columbia Chapter, Vancouver BC  
<http://bc.awmac.com>
- AWMAC Northern Alberta Chapter, Edmonton Alberta  
<http://nab.awmac.com>
- AWMAC Southern Alberta Chapter, Calgary Alberta  
<http://sab.awmac.com>
- AWMAC Saskatchewan Chapter, Saskatoon Saskatchewan  
<http://sk.awmac.com>
- AWMAC Manitoba Chapter, Winnipeg Manitoba  
<http://mb.awmac.com>
- AWMAC Ontario Chapter, Toronto Ontario  
<http://on.awmac.com>
- AWMAC Quebec Chapter, Montreal Quebec  
<http://qc.awmac.com>
- AWMAC Atlantic Chapter, Halifax Nova Scotia  
<http://atl.awmac.com>

# SECTION 8

## Wall/Ceiling Surfacing and Partitions

### Within UNITED STATES

#### SUPPORT

- **GUIDE SPECIFICATIONS** - Available in interactive digital format including quality control options at: <http://woodworkinstitute.com/publications/architectural-woodwork-standards/>
- **AIA SEMINARS** - The Woodwork Institute is a Registered Provider of the American Institute of Architects (AIA), and its Continuing Education System (CES) program, check out our offerings at: <http://woodworkinstitute.com/architectural-resources/aia-seminars/> 
- **CONSULTATION** - Contact one of our Directors of Architectural Services (DAS) at: <http://woodworkinstitute.com/about-us-2/about-us/>
- **ACCREDITED FABRICATORS AND INSTALLERS** - Our AMC's (Accredited Millwork Company) represents the best fabricators and installers in our industry, check them out at: <http://woodworkinstitute.com/membership-listing-2/> 
- **CERTIFIED INDUSTRY PROFESSIONALS** - Our CMP's (Certified Millwork Professionals) represent the knowledge base of our industry, check them out at: <http://woodworkinstitute.com/membership-listing-2/> 
- **MILLWORK INDUSTRY PARTNERS** - Our MIP's (Millwork Industry Partners) represent the best of our industries material suppliers, check them out at: <http://woodworkinstitute.com/membership-listing-2/> 
- **ACKNOWLEDGED PRODUCTS LISTING** - If it's listed here, you are assured it meets NAAWS minimum requirements, find the listing at: <http://woodworkinstitute.com/acknowledged-product-listing/> 
- **CABINET DESIGN SERIES (CDS)** - Eliminate the need to include casework elevations in your architectural drawings, check out the CDS system in NAAWS "Design Resources" and access the cad files at: <http://woodworkinstitute.com/architectural-resources/cabinet-design-series/>

#### QUALITY ASSURANCE

- **BIDDER QUALIFICATION** - A discipline of bidder pre-qualification wherein your specifications protect you and your customer from the unknown: To be eligible to bid or negotiate this job, the subcontractor must be a Woodwork Institute Accredited Millwork Company (AMC) in good standing. <http://woodworkinstitute.com/architectural-resources/quality-assurance> 
- **CERTIFIED COMPLIANCE PROGRAM (CCP)** - A discipline of quality control used in conjunction with NAAWS providing an unbiased means of ensuring conformance to a project's plans and specifications. CCP, together with the use of the desired Grade(s) in the specifications, informs all parties of the design professional's expectations, without bidder discrimination. <http://woodworkinstitute.com/services/certified-compliance-program> 
- **MONITORED COMPLIANCE PROGRAM (MCP)** - A discipline of quality affirmation used in conjunction with the NAAWS which provides ongoing reviews/inspections of a project from its beginning through completion, ensuring strict conformance to the design intent throughout the millwork fabrication and installation process. <http://woodworkinstitute.com/services/monitored-compliance-program/> 
- **CERTIFIED SEISMIC INSTALLATION PROGRAM (CSIP)** - A standalone seismic assurance option which can be specified in conjunction with or without CCP or MCP, offering design professionals and project owners specific use of WI's seismic casework pre-approvals from California's Office of Statewide Health Planning and Development (OSHPD) without additional engineering costs and/or requirements, assuring proper backing has been installed in the walls when and where required. <http://woodworkinstitute.com/services/certified-seismic-installation-program/> 

# SECTION 8

## Wall/Ceiling Surfacing and Partitions

### introductory information

#### INTRODUCTION

Section 8 includes information on wood veneer, solid wood, stile and rail wood, decorative laminate, solid surface, solid phenolic and factory built framing for wall, ceiling and partition surfacing.

Quality assurance can be achieved by adherence to these standards and will provide the owner a quality product at competitive pricing. Working with an AWMAC Member (in Canada) or a WI Certified Millwork Professional (CMP) (in the USA) and the WI Accredited Millwork Company (AMC) they represent to provide your woodwork will help ensure the understanding and performance of the quality level required. Illustrations in this Section are not intended to be all inclusive, other engineered solutions may be acceptable. In the absence of specifications; methods of fabrication are the manufacturer's choice. The design professional, by specifying compliance to these standards increases the probability of receiving the product quality expected.

#### CONTRACT DOCUMENTS

Contract documents, furnished by the design professional, shall clearly indicate or delineate material, fabrication, installation, and applicable building code/regulation requirements.

Shop drawings, engineering, listings and mock-ups are the means by which the design intent is turned into reality. They shall indicate methods of construction, exact material selections, grain direction(s), methods of attachment and joinery, and exact dimensions. They should also include the manufacturer's technical suggestions. Listings (schedules) are sometimes used to list core, edge and face materials, adhesives etc. when not included on the shop drawings. Mock-ups may be specified for review as a full scale model showing, materials, joinery and finishes and are often used as the project control sample.

#### CONTRACT DOCUMENTS SHALL INCLUDE

Species, Slicing and Matching of individual leaves are reviewed and governed by Section 4, Sheet Products (Note unless otherwise specified; plain sliced and bookmatch are the default standards).

- **Species:** There are numerous foreign and domestic species available. Involve your manufacturer early in the design and selection process.
- **Slicing:** Select either rotary, plain sliced, quarter sliced, or (in the case of Oak only) rift sliced.
- **Matching of individual leaves:** Select either book matched (most appropriate for plain sliced), slip matched (most appropriate for quartered and rift sliced), or random matched (for a rustic look, usually more expensive).
- **Matching on each panel face:** Select either running match, balance match, or balance and center match. Specify type of end matching for tall elevations.
- **Sequence matching between full width pre manufactured panel sets.**

#### ADVISORIES

**FIRE RATED CORES** - Due to adverse reaction of some veneers laminated to fire rated (FR), ultra low emitting formaldehyde (ULEF or NAUF), medium density fiberboard MDF - causing discoloration of the wood veneer even months after installation, major core manufacturers have issued disclaimers in the use of FR cores. They strongly suggest that use of FR ULEF MDF and particleboard cores should be done after testing compatibility of adhesives, wood veneer and cores. Any resulting discoloration with the use of these cores may be exempt in their warranties. Use of FR ULEF cores should only be considered after consultation with the board supplier.



#### HPDL CONCERNS

- High gloss HPDL will highlight minor core and surface imperfections, often unacceptably.
- HPDL panels and doors are not recommended for exterior use due to the potential differentials in humidity between the faces.
- Some HPDLs utilize a WHITE BACKGROUND paper to achieve the high fidelity, contrast, and depth of color of their printed pattern, while leaving a white line at exposed edges, which is extremely noticeable with darker colors.

#### RECOMMENDATIONS



- If **FIELD FINISHED**, include in Division 09 of the specifications:
  - **BEFORE FINISHING**, exposed portions of woodwork shall have handling marks or effects of exposure to moisture, removed with a thorough, final sanding over all surfaces of the exposed portions and shall be cleaned before applying sealer or finish.
  - At **CONCEALED SURFACES** - Architectural woodwork that may be exposed to moisture, such as those adjacent to exterior concrete walls, etc., shall be primed.
- **REVIEW** the GENERAL portion of Sections 3 and 4 for an overview of the characteristics and the minimum acceptable requirements of lumber and/or sheet products that might be used herein.

# SECTION 8

## Wall/Ceiling Surfacing and Partitions

## introductory information

### RECOMMENDATIONS

(continued)



- **STRUCTURAL MEMBERS**, grounds, in wall blocking, backing, furring, brackets, or other anchorage which becomes an integral part of the building's walls, floors, or ceilings, required for the installation of architectural woodwork are not to be furnished or installed by the architectural woodwork manufacturer or installer.
- **COMPOSITE CORES** (e.g., particleboard, medium-density fiberboard, agrifiber, or combination core products) are recommended in lieu of veneer core, because these cores produce a smoother exposed face, vary less in thickness, and are less likely to warp.
- **SOLID SURFACE**
  - Coordinate material applications within the manufacturer's guidelines.
  - Use of the same batch of materials is important at adjacent sheets to lessen color variations.
  - Thicknesses are nominal and may be a fabrication concern where thickness is critical.
- **SOLID PHENOLIC** performs well in high moisture and heavy use applications.

### SPECIFICATION CONSIDERATIONS



- **FLAME SPREAD RATINGS.**
- **SPECIAL CODE COMPLIANCE.**
- **SPECIAL MOLDING PROFILE.**
- **WOOD VENEER**
  - Species of veneer.
  - Method of slicing (plain, quarter, rotary, or rift).
  - Matching of veneer leaves (book, slip, or random) and veneer leaves within a panel face (running, balance, or center-balanced).
  - Sequence of adjacent panels (non-sequenced, sequenced, or blueprint panels and components) and end-matching.
  - Grain direction, if other than vertical.
  - For selected flitches, the sources, gross footage of flitches, and cost per square foot.
  - Special figure, which is not a function of a species grade, must be specified.
- **SOLID WOOD**
  - Species of wood.
  - Method of cutting (plain, quarter or rift).
  - Grain direction, if other than vertical.
  - Special figure, which is not a function of a species grade, must be specified.
- **LAMINATE, SOLID SURFACE and SOLID PHENOLIC**
  - Manufacturer.
  - Pattern or Color.
  - Sheen.
  - Special pattern direction - with lack of specification, pattern direction will be vertical at panels and optional at joints.

### • QUALITY ASSURANCE OPTIONS:

#### Within CANADA

- **AWMAC's GUARANTEE AND INSPECTION SERVICE (GIS)** - See NAAWS's Resources page and/or <http://awmac.com/gis>
- **AWMAC's INSPECTION SERVICE** - See NAAWS's Resources page and/or <http://awmac.com/gis>
- **AWMAC's EXPERT OPINION SERVICE** - See NAAWS's Resources page and/or <http://awmac.com/gis>

#### Within UNITED STATES

- **WI'S AMC BIDDER PRE-QUALIFICATION** - See NAAWS's Resources page and/or <http://woodworkinstitute.com/architectural-resources/quality-assurance>
- **WI'S CERTIFIED COMPLIANCE PROGRAM (CCP)** - See NAAWS's Resources page and/or <http://woodworkinstitute.com/services/certified-compliance-program>
- **WI'S MONITORED COMPLIANCE PROGRAM (MCP)** - See NAAWS's Resources page and/or <http://woodworkinstitute.com/services/monitored-compliance-program/>
- **WI'S CERTIFIED SEISMIC INSTALLATION PROGRAM (CSIP)** - See NAAWS's Resources page and/or <http://woodworkinstitute.com/services/certified-seismic-installation-program/>

# SECTION 8

## Wall/Ceiling Surfacing and Partitions

### introductory information

#### MATERIAL SELECTIONS

For **OPAQUE** finishes:

- **Medium Density Fiberboard (MDF)** is suggested for cost savings and an optimum paintable surface.
- **Medium Density Overlay (MDO)**, which may be machined and detailed with little loss of quality surface characteristics, requires a seal coat prior to application of finish coats with no sheen limitation providing a paintable surface for panels. The thermosetting resin overlay is designed to take and hold paint. Opaque finish sheens above 40 Satin require special finishing procedures.
- **Close Grain Hardwood** - Although allowed, extra preparation may be required by the finisher as there may be grain show-through, split veneer joints, and other wood characteristics.
- **Manufacturers' option** - Face materials are determined by the manufacturer.

For **TRANSPARENT** finishes:

Selection starts by looking at "hand samples," pieces of veneer or lumber representing a particular species, but not necessarily a particular tree or log. Wood is a natural material (unlike a manufactured product), which varies from tree to tree in its color and texture. Rather than simply choosing an appropriate wood for its color, consider the size and availability of the species. A species that grows in smaller diameter, with shorter logs, lends itself to furniture and smaller projects, whereas an abundant species that grows in large diameter lends itself more to larger public spaces. Many projects have run into difficulties because the species availability was not compatible with the project's needs.

# SECTION 8

## Wall/Ceiling Surfacing and Partitions

### introductory information

#### PANEL SEQUENCING:

- **Running Match** (cannot be end matched) - Each panel face is assembled from as many veneer leaves as necessary. This often results in a non-symmetrical appearance, with some veneer leaves of unequal width. Often the most economical method at the expense of aesthetics.




FIGURE: 8-001

- **Balance Match** - Each panel face is assembled from veneer leaves of uniform width before edge trimming. Panels may contain an even (balance and center) or odd (balanced) number of leaves and may change from panel to panel within a sequenced set.




FIGURE: 8-002




FIGURE: 8-003

# SECTION 8

## Wall/Ceiling Surfacing and Partitions

### introductory information

#### SEQUENCING of PANELS WITHIN A ROOM

- Balanced End Match




FIGURE: 8-004




FIGURE: 8-005

#### SEQUENCING of PANELS WITHIN A ROOM:

Selections include: no sequence, pre-manufactured sets - full width, pre-manufactured sets - selectively reduced in width (equally sized), sequenced uniform size set(s), or blueprint sequenced panels and components.

Although many panel distributors maintain a panel inventory of pre-manufactured sets of different species and grades, only a limited quantity of species, cut and grades will be available.

Sequenced custom sized and blueprint sequenced panels offer variables of veneer leaf match and panel width, therefore pre-manufactured sets shall not be used for sequenced custom sized and blueprint sequenced panels.

Sequenced panels and examples of their room layout are as follows:

# SECTION 8

## Wall/Ceiling Surfacing and Partitions

### introductory information

#### SEQUENCING of PANELS WITHIN A ROOM (continued)

- **PRE-MANUFACTURED SEQUENCED SETS**

Full width utilization is composed of a specific quantity of sequenced and numbered panels based on a per room basis for net footage selected from available inventory. They are usually only available in 48" x 96" or 120" (1219 mm x 2438 mm or 3048 mm) sheets in sets varying from 6-12 panels. If more than one set is required, sequencing between sets cannot be expected. Similarly, doors or components cannot be fabricated from the same set.

- **FULL WIDTH PANEL UTILIZATION** with running matched panels.




FIGURE: 8-006

# SECTION 8

## Wall/Ceiling Surfacing and Partitions

### introductory information

#### SEQUENCING of PANELS WITHIN A ROOM (continued)

- PRE-MANUFACTURED SEQUENCED SETS (continued)
  - FULL WIDTH PANEL UTILIZATION with balanced matched panels.




FIGURE: 8-007

# SECTION 8

## Wall/Ceiling Surfacing and Partitions

### introductory information

#### SEQUENCING of PANELS WITHIN A ROOM (continued)

- PRE-MANUFACTURED SEQUENCED SETS (continued)
  - SELECTIVELY REDUCED PANEL UTILIZATION with balanced matched panels.




FIGURE: 8-008

# SECTION 8

## Wall/Ceiling Surfacing and Partitions

### introductory information

#### SEQUENCING of PANELS WITHIN A ROOM (continued)

- **MADE TO ORDER SEQUENCED SETS** (must be specified). Balance matched or balance and center matched panels are manufactured to exact sizes based on the project's net footage and height requirements.




FIGURE 8-009



# SECTION 8

## Wall/Ceiling Surfacing and Partitions

## introductory information

### FLITCH SELECTION

The design professional may choose to see samples of veneer flitches to evaluate color and grain characteristics for other than pre-manufactured sets. This must be specified. Unless specified, layout is determined by the manufacturer.

When it is determined that the use of pre-manufactured panel sets is not adequate for the scope of the project, then selecting specific veneer flitches is an option to consider.

When sliced from a log, the individual pieces of veneer are referred to as leaves. These leaves are kept in order as they are sliced and then dried. As the leaves come out of the dryer, the log is literally reassembled. This sliced, dried and reassembled log or partial log is called a flitch. The flitch is given a number and the gross square footage of the flitch is tallied.

#### To select specific veneer flitches for a project:

- Determine the net square footage of face veneer required for the project. This should include paneling, casework, built-in furniture, and flush doors items when specifying a blueprint sequenced project.
- Multiply the net square footage times three (this is the average ratio. Some species require a higher multiplier). Example: 5,000 (net square feet) x 3 = 15,000 square feet; this is the gross square footage that should be sampled for this project.

While this may sound like a daunting quantity of veneer to look through, there is an established process that simplifies the task.

When a numbered flitch is sampled, typically, three leaves of veneer are removed from the flitch and numbered sequentially. Starting from the top of the flitch, a leaf is removed from one-quarter of the way down, then from one-half, and from three quarters in the flitch. These three sequentially numbered leaves of veneer form a representative sample of that flitch.

- Since it will take at least 6 flitches, with a gross square footage of 2,500 square feet each to meet the project needs, give careful consideration to the following key criteria:

- **Length** - Is the length adequate for the requirements? The flitch needs to be at least 6" (152 mm) longer than the panel requirements.
- **Width** - What will the net yield for width be from each flitch?
- **Gross square footage of each flitch** - total yield must be 15,000 square feet.
- **Color and grain compatibility** - While exact matching is not possible, from flitch to flitch, this is the opportunity to select the range of color and grain compatibility that will enhance the visual continuity of the entire project.

The reality of this process is that the square footage of individual flitches of veneer will probably range from 1,200 square feet up to 3,000 square feet. This means that one may end up selecting 9 or 10 flitches, instead of just 6. But the goal remains the same as in the example: selecting flitches that will satisfy the aesthetic needs, while fulfilling the face veneer requirements for the project.

It is recommended that specifications be written with the foregoing objective in mind. Then, when the project has been awarded to a qualified manufacturer, talk directly to the manufacturer and be involved in one of the most exciting aspects of bringing the design concepts to reality.

### VARIATIONS in NATURAL WOOD PRODUCTS

Wood is a natural material, with variations in color, texture, and figure. These variations are influenced by the natural growing process and are uncontrollable by the manufacturer. The color of wood within a tree varies between the "sapwood" (the outer layers of the tree which continue to transport sap), which is usually lighter in color than the "heartwood" (the inner layers in which the cells have become filled with natural deposits). Various species produce different grain patterns (figures), which influence the selection process. There will be variations of grain patterns within selected species. The architectural woodwork manufacturer cannot select solid lumber cuttings within a species by grain and color in the same manner in which veneers may be selected. Color, texture, and grain variations will occur in architectural woodworking.

### FINISHING

Site conditions and air quality regulations for finishing are rarely conducive to good results. Poor lighting, dust-laden air, and techniques available are limiting factors. Depending upon local practice, many manufacturers will factory finish, yielding better results than can be achieved from field finishing. Unless specified in the Contract Documents, the manufacturer is not responsible for the appearance of field finished panels or doors.

# SECTION 8

## Wall/Ceiling Surfacing and Partitions

## introductory information

### EDGEBANDING EXAMPLES

Veneer edgebanded:





Figure: 8-011

Inset Solid Wood edgebanding:



Figure: 8-012

Applied Solid Wood with corner joint options:



A - Lapped

B - Mitered

Figure: 8-013

For durability, the bottom edge of wall surfacing is edgebanded.




Figure: 8-014

### FIELD-CUT CORNER and TRANSITION EXAMPLES

Butt - Outside Corner




Figure: 8-015

Mitered - Outside Corner




Figure: 8-016

Solid Wood - Outside Corner




Figure: 8-017

Butt - Inside Corner




Figure: 8-018

Non-reveal - Transition




Figure: 8-019

### REVEALS and REVEAL JOINT EXAMPLES




Figure: 8-020




Figure: 8-021




Figure: 8-022




Figure: 8-023




Figure: 8-024




Figure: 8-025



Figure: 8-026

**To PREVENT TELEGRAPHING,** inset solid wood edging when used must have similar moisture content as panel core, be glued securely and calibrated with panel core thickness prior to being laminated with a wood veneer on both faces.



# SECTION 8

## Wall/Ceiling Surfacing and Partitions

### introductory information

#### REVEALS and REVEAL JOINT

(continued)




Figure: 8-027




Figure: 8-028

#### FACTORY-PREPARED CORNER and TRANSITION EXAMPLES

Lock Mitered - Outside Corner




Figure: 8-029

Splined - Outside Corner




Figure: 8-030

Miter Fold - Outside Corner




Figure: 8-031

Solid Wood - Outside Corner




Figure: 8-032

Solid Wood - Outside Corner




Figure: 8-033

Non-reveal Transition




Figure: 8-034

#### FACTORY PREPARED TRANSITION EXAMPLE OF BUILT-UP SECTION

Loose joint fit in plant and sanded flush




Figure: 8-035

# SECTION 8

## Wall/Ceiling Surfacing and Partitions

### introductory information

#### STILE and RAIL PANELING

Flat or raised panels with wood veneer faces or of solid lumber, combined with stiles and rails. Design may encompass face application of mouldings. Joints between panels, stiles, rails, and other members to be as designed for functional or decorative purposes.




Figure: 8-036

# SECTION 8

## Wall/Ceiling Surfacing and Partitions

### introductory information

#### EXAMPLES of STILE and RAIL PANELING (continue)





Figure:8-037

Veneered stile and rail with concealed\*  
stile and rail edges and panel rim



\* Likely to cause telegraphing through face veneer

Figure:8-038

Solid lumber stile and rail with  
panel products and solid rims




Figure:8-039

Solid stile and rail with lip moulding  
and panel product with solid rim




Figure:8-040

Medium density fiberboard (MDF) for  
stiles, rails and panels




Figure:8-41

Inside corner  
Figure:8-042




Figure:8-042

Outside corner - spline  
Figure:8-043




Figure:8-043

Outside corner - lock miter  
Figure:8-044






Figure:8-044



Mortise and Tenon  
construction

Figure:8-045



Doweled  
construction

Figure:8-046

# SECTION 8

## Wall/Ceiling Surfacing and Partitions

### introductory information

#### EXAMPLE of FLAT PANELING WITH REVEALS WITHIN a NICHE






Figure: 8-047

# SECTION 8


## Wall/Ceiling Surfacing and Partitions

### introductory information

#### EXAMPLE of PANELING FOR RECEPTION WALLS WITH FACTORY BUILT STRUCTURES



Plan Section A



Section B

Figure: 8-048

# SECTION 8

## Wall/Ceiling Surfacing and Partitions

## introductory information

### STANDING and RUNNING TRIM

Site-applied cornice, chair rail, base, trim, and mouldings are governed by the areas of NAAWS covering Standing and Running Trim.

### SMOOTHNESS of FLAT and MOLDED SURFACES

- **Planers and Molders:** The smoothness of surfaces that have been machine planed or moulded is determined by the closeness of the knife cuts. The closer the cuts to each other (i.e., the more knife cuts per inch [KCPI]), the closer the ridges, and therefore the smoother the resulting appearance.
- **Sanding and Abrasives:** Surfaces can be further smoothed by sanding. Sandpapers come in grits from coarse to fine and are assigned ascending grit numbers. The coarser the grit, the faster the stock removal. The surface will show the striations caused by the grit. Sanding with finer grit papers will produce smoother surfaces.

### INSTALLATION

The methods and skill involved in the installation of paneling and doors in large measure determine the final appearance of the project. The design, detailing, and fabrication should be directed toward achieving installation with a minimum of exposed face fastening. The use of interlocking wood cleats or metal hanging clips combined with accurate furring and shimming will accomplish this. Such hanging of panels has the additional advantage of permitting panel movement that results from humidity changes or building movement. Depending upon local practice, many manufacturers will perform the wall preparation and installation of the paneling and related doors.

### FIRE RETARDANCE and TREATMENT

The natural fire-retardant qualities and acceptability of treatments vary among the species. Where certain items of architectural woodwork are required to have a flame spread classification to meet applicable building and safety codes, the choice of lumber species must be a consideration. Additional data on various species may be available from U.S. Department of Agriculture Forest Service, <http://fs.fed.us>, Fire Safety of Wood Products Work Unit at (608) 231-9265.

- **Flame Spread Classification:** This is the generally accepted measurement for flame spread rating of materials. It compares the rate of flame spread on a particular species with the rate of flame spread on untreated Oak. Most authorities accept the following classes for flame spread:
  - Class A 0-25
  - Class B 26-75
  - Class C 76-200
- **Fire Retardant Treatments:** Some species may be treated with chemicals to reduce flammability and retard the spread of flame over the surface. This usually involves impregnating the wood, under pressure, with salts suspended in a liquid. The treated wood must be re-dried prior to fabrication. Consult with a manufacturer about the appearance and availability of treated woods prior to specification.

The sizes and species currently being treated (flame spread less than 25), are very limited, and not available in all markets. Fire-retardant treatment does affect the color and finishing characteristics of the wood.

Subject to the authority having jurisdiction, untreated wood and wood products may be used. The location and quantity to be determined by the design professional.

- **Intumescent Coatings for Wood:** It is possible to reduce flammability by using intumescent coatings in either opaque or transparent finishes. These are formulated to expand or foam when exposed to high heat, and create an insulating effect that reduces the speed of spread of flame. Improvements are continually being made on these coatings. Consequently, the specifier must ascertain whether they will be permitted under the code governing the project, the relative durability of the finish, and the effect of the coating on the desired color of the finished product.
- **Finishing Of Fire Retardant Treated Lumber:** Fire-retardant treatments may affect the finishes intended to be used on the wood, particularly if transparent finishes are planned. The compatibility of finishes should be tested before they are applied.

### FIRE RETARDANT PANEL PRODUCTS

- **Core** - The flame spread rating of the core material determines the rating of the assembled panel. Fire-retardant veneered panels must have a fire-retardant core. Particleboard core is available with a Class A rating. Veneer core and MDF (Medium Density Fiberboard) cores are available with a flame spread rating in some markets.
- **Face** - The International Codes, except where locally amended, provide that facing materials less than 0.036" (0.9mm) or thinner and applied directly to the surface of the walls or ceilings are not required to be tested.

If a Class A panel assembly is specified with a decorative laminate face, the decorative laminate and the laminate balancing sheet must be applied to a Class A core material, with the laminate manufacturer's recommended adhesive. It is the responsibility of the specifier to indicate what flame spread rating, if any, is required for the paneling. In the absence of such a specified rating, the manufacturer shall supply un-rated paneling.

# SECTION 8

## Wall/Ceiling Surfacing and Partitions

### introductory information

#### ANTIMICROBIAL SURFACES

There is increasing availability of antimicrobial products, including solid surface and HPDL. It is important to understand that regardless of the methodology used to create the antimicrobial surface there are two significantly different types of claims regarding such antimicrobial products. Common terminology refers to these:

- **Within the United States as:**
  - **Treated Article Claim** - Which the US Environmental Protection Agency (EPA), <http://epa.gov>, classifies as a "treated article exemption", typically referring to items that are treated with antimicrobial pesticide to protect the item itself, not the public. Such exemption will be absent any EPA registration number and is granted for non-public health use.
  - **Public Health Claim** - Which the EPA classifies as "EPA registered products which have been shown, using EPA testing protocols, to demonstrate efficacy in the installed format. Such test protocol requires an efficacy of killing 99.9% of all bacteria, fungi and viruses within two hours.
- **Within Canada as:**
  - **Disinfectant Drugs** - Which Health Canada, <http://hc-sc.gc.ca>, classifies as a non market authorized claim, lacking a Drug Identification Number (DIN).
  - **Hard Surface Disinfectants** - Which Health Canada classifies as having received "Market Authorization" when such have been granted a Drug Identification Number (DIN).

#### NON-TRADITIONAL MATERIALS

Covers materials re-purposed from other industrial and manufacturing areas, but assigned to the woodwork manufacturer and treated similarly to traditional millwork items like wall paneling. From a design perspective considerations of appearance, color, finish, variation and relation are deemed important as they would be with traditional wood products.

Examples of non-traditional materials could be a fiber/cement panel designed for fire resistance, insulation re purposed as a decorative panel, metal products, cloth, acrylics, etc.

Because these materials are unique, contract documents, shall clearly indicate or delineate all of the necessary material, fabrication, installation and building code/regulation direction and requirements as may be applicable for the manufacturer/installer to reasonably accomplish the intended design concept.

#### RECLAIMED or RECYCLED WOOD

##### DESIGN PROFESSIONAL RESPONSIBILITY

Use of unique materials like reclaimed or recycled wood requires a more active role of the design professional in sourcing and pre-approving desired material selections. There are no traditional guidelines with these types of materials to assure either the woodwork manufacturer or the design professional of achieving an intended result. There will be situations where the design professional will be required to directly participate in the individual piecemeal selection and layout process of the product.

**CONTRACT DOCUMENTS**, shall clearly indicate or delineate all material, fabrication, installation and applicable building code/regulation requirements with the clear understanding that incomplete design choices, changes in scope or material selection, lack of material selection, or design choices made after initial bid may impact the cost or not be possible.

The contract documents shall specifically list the material source and identifier, and address the allowable:

- Variation in color or tone, grain, distress, character, and patina.
- Defects, such as nail/bolt holes, checking, cracking, discoloration, milling marks, roughness in terms of quantity, locations, repetition, etc.
- Distortion in terms of straightness, cupping, flatness, etc.

See SECTION 3 for additional information.

#### DESIGN RESOURCES



Is a perpetually expanding, web based resource of pictures, videos, illustrations, ideas and design concepts for inspiring thought and design creativity - assessable at:

<http://naaws-design-resources.com>

Relative to this Section, offerings will include:

- Millwork partitions
  - Wood veneer
  - Wood, solid
  - Solid surface
  - Decorative laminate plastic
- Wall surfacing
  - Wood veneer
  - Wood, solid
  - Solid surface
  - Decorative laminate plastic
- Ceiling surfacing
  - Wood veneer
  - Wood, solid

# SECTION 8

## Wall/Ceiling Surfacing and Partitions

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



## compliance requirements

### INCLUDING: Wood Veneer, Solid Wood, Stile and Rail Wood, Decorative Laminate, Solid Surface and Solid Phenolic Wall/Ceiling Surfacing and Partition Products

#### 8.1 BASIC CONSIDERATIONS

##### 1 GRADE

1.1 These standards are characterized in three Grades of quality that might be mixed within a single project. Limitless design possibilities and a wide variety of lumber and veneer species, along with overlays, high-pressure decorative laminates, factory finishes, and profiles are available in all three Grades.

1.2 **ECONOMY GRADE** defines the minimum quality requirements for a project's workmanship, materials, or installation and is typically reserved for woodwork that is not in public view, such as in mechanical rooms and utility areas.

1.3 **CUSTOM GRADE** is typically specified for and adequately covers most high-quality architectural woodwork, providing a well-defined degree of control over a project's quality of materials, workmanship, or installation.

1.4 **PREMIUM GRADE** is typically specified for use in those areas of a project where the highest level of quality, materials, workmanship, and installation is required.

##### 1.5 GRADE LIMITATIONS

1.5.1 **SOLID SURFACE** wall surfacing is only defined in Custom and Premium Grade.

1.5.2 **SOLID PHENOLIC CORE** wall surfacing is only defined in Premium Grade.

2 **CONTRACT DOCUMENTS** shall govern if in conflict with these standards.

3 **ACCEPTABLE REQUIREMENTS** of lumber and/or sheet products used within this woodwork product section are established by Sections 3 and 4, unless otherwise modified herein.

#### 8.1 BASIC CONSIDERATIONS (continued)

4 **AESTHETIC COMPLIANCE REQUIREMENTS** apply only to surfaces visible after fabrication and installation.

4.1 Shall be judged from a normal viewing stance and considered compliant if inconspicuous when viewed from:

4.1.1 72" (1830 mm) for Economy Grade

4.1.2 48" (1219 mm) for Custom Grade

4.1.3 24" (610 mm) for Premium Grade

4.2 For **RECLAIMED** or **RECYCLED WOOD**, the aesthetic compliance requirements of NAAWS does not apply, such shall be as agreed between owner/design professional and the woodwork manufacturer/installer.

4.3 For **NON-TRADITIONAL MATERIALS**, the aesthetic compliance requirements of NAAWS does not apply, such shall be as agreed between owner/design professional and the woodwork manufacturer/installer.

##### 5 Sequencing of Panels Within a Room **EXPOSED SURFACES**

5.1 All visible surfaces of architectural wall surfacing.

##### 6 **CONCEALED SURFACES**

6.1 All non-visible surfaces attached to and/or covered by another.

6.2 All non-visible blocking or spacers used for attachment.

7 **SOLID SURFACE** referenced in these standards refers to filled cast polymeric resin panels per Section 4.

8 **SOLID PHENOLIC** (compact laminate) referenced in these standards refers to panels of melamine impregnated decorative sheets over kraft phenolic core sheets per Section 4.

9 **HPDL BACKED WOOD VENEERS** is permitted, if so specified or otherwise approved.

10 **CONTINUOUS PRESSURE LAMINATES** (melamine and polyester-based) used as an alternative to HPDL is permitted, provided they conform to the same physical properties and thickness as required for HPDL.

# SECTION 8

## Wall/Ceiling Surfacing and Partitions

Where the **E**, **C**, or **P** icon is not indicated,  
the rule applies to all Grades equally



GENERAL/PRODUCT/INSTALLATION/TEST

compliance requirements

### 8.1 BASIC CONSIDERATIONS (continued)

- 11 **FURRING**, when required, shall be in accordance with the International Building Code (IBC), National Building Code of Canada (NBC) or regional building code.
- 12 **BLEACHED VENEERS** may cause finishing problems and are not recommended.
- 13 **HIGH-GLOSS HPDL** may telegraph minor core and surface imperfections and are not recommended.
- 14 To **PREVENT TELEGRAPHING**, inset solid wood edging when used must have similar moisture content as panel core, be glued securely and calibrated with panel core thickness prior to being laminated with a wood veneer on both faces.
- 15 **INDUSTRY PRACTICES**
- 15.1 **STRUCTURAL MEMBERS**, grounds, in wall blocking, backing, furring, brackets, or other anchorage that are an integral part of the building's walls, floors, or ceilings, that are required for the installation of architectural woodwork are not furnished or installed by the architectural woodwork manufacturer or installer.
- 15.2 **WALL, CEILING** and **OPENING** variations in excess of 1/4" (6.4 mm) or **FLOORS** in excess of 1/2" (12.7 mm) in 144" (3658 mm) of being plumb, level, flat, straight, square, or of the correct size are not acceptable for the installation of architectural woodwork, nor is it the responsibility of the installer to scribe or fit to tolerances in excess of such.
- 15.3 **PRIMING** of architectural woodwork is not the responsibility of the manufacturer and/or installer, unless the material is being furnished pre-finished.
- 15.4 **RADIUS MOLDINGS** are laminated and formed, preshaped, or machined to the radius and fabricated in the longest practical lengths to minimize field joints.
- 15.5 **WAINSCOT** is defined as being 48" (1219 mm) or less in height above the finished floor.
- 15.6 **WALL SURFACING** with a defined grain and/or pattern is installed vertically.

# SECTION 8

## Wall/Ceiling Surfacing and Partitions

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



## compliance requirements

### 8.2 SCOPE

- 1 All decorative, solid or veneered wood, laminated plastic, solid phenolic composite and solid surface for architectural:
  - 1.1 Wall Surfacing.
  - 1.2 Ceiling Surfacing.
  - 1.3 Partitions.
- 2 **TYPICAL INCLUSIONS:**
  - 2.1 All decorative, solid or veneered wood, laminated plastic, solid phenolic composite and solid surface wall and ceiling surfacing, including wainscoting.
  - 2.2 All decorative, solid or veneered wood, laminated plastic, solid phenolic composite and solid surface partitions.
  - 2.3 All doors required to be blueprint matched to wood paneling, not specified otherwise, and:
    - 2.3.1 If doors are specified to be furnished by others, the paneling supplier shall control matching.
  - 2.4 If installed, furring or on wall blocking, shims, and methods of attachment from the face of the wall and ceiling out.
  - 2.5 All exposed decorative solid phenolic composite wall and ceiling surface.
  - 2.6 Class A Flame Spread Rated HPDL wall and ceiling surfacing assembly.
  - 2.7 Class A Flame Spread Rated veneered wood wall and ceiling surfacing assembly.
- 3 **TYPICAL EXCLUSIONS:**
  - 3.1 Non climate controlled interior or exterior architectural wall and ceiling surfacing.
  - 3.2 Casework soffits, fascia or filler panels.
  - 3.3 Room, closet, or access doors, unless sequence matched and blueprint matched with paneling.
  - 3.4 Any bucks, grounds on in wall blocking.
  - 3.5 Composition or plaster wallboards or coverings.
  - 3.6 Site built framing or sheathing.

### 8.2 SCOPE (continued)

- 3.7 Exposed base other than wood, decorative laminate, or solid surface.
- 3.8 Fabric wrapped and/or acoustic panels or partitions.

### 8.3 DEFAULT STIPULATION



- 1 **IF NO FINISH IS SPECIFIED, THE DEFAULT STIPULATION FOR OPAQUE FINISH APPLIES:**
  - 1.1 **WOOD SURFACING AT OPAQUE FINISH** - unless otherwise specified or detailed, work shall be **CUSTOM GRADE**, panels shall be Medium Density Fiberboard and where details show solid wood components, shall be close grain hardwood.
  - 1.2 **WOOD SURFACING AT TRANSPARENT FINISH** - unless otherwise specified or detailed, work shall be **CUSTOM GRADE**, panels shall be plain sliced hardwood veneer and where details show solid wood components, shall be plain sawn hardwood.
- 2 **DECORATIVE LAMINATE SURFACING** - unless otherwise specified or detailed, work shall be **CUSTOM GRADE** with retention moldings at field joints. Colors to be selected from non premium priced standard patterns and texture.
- 3 **SOLID SURFACE SURFACING** - unless otherwise specified or detailed, work shall be **CUSTOM GRADE**, 1/4" (6.4 mm) minimum thickness, directly applied, with 1/4" x 1" (6.4 mm x 25.4 mm) trim bats at vertical butt joints on continuous horizontal runs. Colors to be selected from non premium priced standard patterns.
- 4 **SOLID PHENOLIC SURFACING** - unless otherwise specified or detailed, work shall be **PREMIUM GRADE**, 1/8" (3 mm) minimum thickness with 1/8" x 1" (3 mm x 25 mm) battens at vertical joints on continuous horizontal runs. Colors to be selected from the manufacturer's standard patterns and colors.

# SECTION 8

## Wall/Ceiling Surfacing and Partitions

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



## compliance requirements

### 8.4 RULES

- 1 The following rules shall govern unless a project's contract documents require otherwise.
- 2 These rules are intended to provide a well defined degree of control over a project's quality of materials and workmanship.
- 3 **ERRATA**, published at <http://naaws-errata.com>, shall take precedence over these rules, subject to their date of posting and a project's bid date. 

8.4.4 Basic General Rules	
1	<b>AESTHETIC</b> grade rules apply only to the faces visible after installation.
2	<b>LUMBER</b> shall conform to the requirements established in Section 3.
3	<b>SHEET PRODUCTS</b> shall conform to the requirements established in Section 4.
4	<b>BACKING SHEET</b> shall conform to the requirements established in Section 4.
5	<b>EXPOSED SURFACES</b> include:
5 1	All visible surfaces of wall and ceiling surfacing.
6	<b>CONCEALED SURFACES</b> include:
6 1	All non visible surfaces attached to and/or covered by another.
6 2	All non visible blocking or spacers used for attachment.
7	<b>FURRING</b> shall be used as required, and:
7 1	It shall be in accordance with applicable codes and regulations for maximum thickness, fire blocking, and void fills.
8	<b>DEFINED GRAIN</b> and/or <b>PATTERN</b> of wall surfacing shall be installed with the grain or pattern direction running vertically.
9	<b>WAINSCOT</b> shall be 48" (1219 mm) or less in height above the finished floor.
10	<b>MULTIPLE OPTIONS</b> , when permitted, shall be the manufacturer's choice.
11	<b>FLAME SPREAD RATING</b> requirements shall be specified.
Continues next column ▼	

### 8.4.4 Basic General Rules

▲ From previous column

12 **SPECIFIC PROFILE**, if required, shall be specified or drawn.

13 For **TRANSPARENT FINISHED WOOD**, if the species is not specified, use of hardwood or softwood (panel product or solid stock) of one species for the entire project is permitted.

14 **GLUING** or **LAMINATION** shall be in accordance with the **ADHESIVE GUIDELINES** within the **APPENDIX**, and: 

14 1 **DELAMINATION** or **SEPARATION** shall not occur.

14 2 **LUMBER** shall conform to the requirements established in Section 3.

14 3 **SHEET PRODUCTS** shall conform to the requirements established in Section 4.

15 **CUTOUTS** in **HPDL** or **SOLID SURFACE** shall have a minimum 1/4" (6.4 mm) radius at inside corners.

16 **CATHEDRAL** type figure shall be achieved by:

16 1 A single component in "AA" Face Grade.

16 2 The split heart method in Face Grades "A - D", and:

16 2 1 Each half of a split heart shall be subject to the minimum component width requirements for Face Grade "B."

17 **SINGLE SOURCE** is required at blueprint matched doors and panels.

18 If **ANTIMICROBIAL SURFACE** is required, it shall be:

18 1 Within the United States, EPA, <http://epa.gov>, registered for public health use.

18 2 Within Canada, Health Canada, <http://hc-sc.gc.ca>, recognized as having market authorization because of its granted Drug Identification Number (DIN).

19 **FIRST CLASS WORKMANSHIP** is required in compliance with these standards. 

# SECTION 8

## Wall/Ceiling Surfacing and Partitions

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally

**E C P**

## compliance requirements

8.4.5		Basic Material Rules				
1	<b>LUMBER, VENEERED PROFILE or SHEET PRODUCTS</b> shall be of the species and Grade specified, and:					
1	1	Shall not have defects, either natural or manufactured, that exceed those permitted.				
2	<b>NATURAL and MANUFACTURED DEFECTS</b> are permitted, if covered by adjoining members or otherwise concealed when installed.					
3	<b>FIGURE</b> is not a function of a species grade and must be specified in the contract document.					
4	<b>PERMITS WARP</b> that can be held flat and straight with methods described in the Installation portion of this Section.					
5	<b>PARTITION CORES</b> of particleboard or medium density fiberboard (MDF) of:					
5	1	Up to and including 48" (1219 mm) in width or 84" (2137 mm) in height shall be a minimum 11/16" (17.5 mm) in thickness.				
5	2	Over 48" (1219 mm) in width or 84" (2137 mm) in height shall be a minimum 1" (25.4 mm) in thickness.				
5	3	Partition doors up to and including 36" (914 mm) in width or 72" (1829 mm) in height shall be a minimum 11/16" (17.5 mm) in thickness.				
5	4	Partition doors over 36" (914 mm) in width or 72" (1829 mm) in height shall be a minimum 1" (25.4 mm) in thickness.				
6	For <b>OPAQUE FINISH</b> :					
6	1	Medium density fiberboard (MDF) is permitted.				
6	2	Veneer is permitted; however:				
6	2	1	<b>SPECIES</b> of manufacturer's choice, closed grain hardwood conforming to ANSI/HPVA HP-1 (latest Edition) definitions and characteristics for:			
6	2	1	1 Grade - D	E	C	P
6	2	1	2 Grade - C	E	C	P
6	2	1	3 Grade - B	E	C	P
7	For <b>TRANSPARENT FINISH, VENEER</b> :					
7	1	<b>SPECIES</b> of manufacturer's choice, hardwood conforming to ANSI/HPVA HP-1 (latest Edition) definitions and characteristics for:				
7	1	1	Grade - B	E	C	P
7	1	2	Grade - A	E	C	P
7	1	3	Grade - AA	E	C	P
Continues next column ▼						

8.4.5		Basic Material Rules				
▲ From previous column						
7	For <b>TRANSPARENT FINISH, VENEER</b> (continued)					
7	2	<b>SLICING</b> of:				
7	2	1	Manufacturer's choice.	E	C	P
7	2	2	Plain sliced.	E	C	P
7	3	<b>MATCHING AT ADJACENT LEAVES</b> shall be:				
7	3	1	Manufacturer's choice.	E	C	P
7	3	2	Book matching.	E	C	P
7	4	<b>MATCHING WITHIN PANEL FACE</b> shall be:				
7	4	1	Running match.	E	C	P
7	4	2	Balance match.	E	C	P
7	5	At <b>ADJACENT PANELS</b> shall be:				
7	5	1	Sequenced			
7	5	2	Specified when end matching, made to order sequence sets and blueprint sequencing is required.	E	C	P
8	<b>EXPOSED SURFACES:</b>					
8	1	Requires end grain to be kept to a minimum.		E	C	P
8	2	Requires no end grain showing.		E	C	P
8	3	Permits medium density fiberboard (MDF) for opaque finish.				
8	4	For <b>TRANSPARENT FINISH</b> :				
8	4	1	Permits hardwood or softwood.			
8	4	2	Permits only one species for the entire project.	E	C	P
8	4	3	Requires adjacent veneer and lumber to be:			
8	4	3	1 Manufacturers' choice species.	E	C	P
8	4	3	2 Compatible for color and grain.	E	C	P
8	4	3	3 Well matched for color and grain.	E	C	P
9	<b>CONCEALED SURFACES:</b>					
9	1	Permits defects such as voids, wane, or unfilled knots.				
9	2	Requires <b>STRUCTURAL FRAMING MEMBERS</b> for items such as reception desk walls, die walls, podiums, benches, partitions etc., to be veneer core plywood, hardwood lumber, particleboard, MDF or SCL.				
Continues next column ▼						

# SECTION 8

## Wall/Ceiling Surfacing and Partitions

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally

**E C P**

## compliance requirements

8.4.5		Basic Material Rules			
▲ From previous column					
10 PRIMING:					
10	1	When <b>FACTORY FINISHING</b> is specified, concealed surfaces shall be factory sealed with two coats at 2 mil dry.	E	C	P

Specific **PRODUCT** Requirements for Wood, Decorative Laminate, Solid Surface and Solid Phenolic surfacing are in Annex A, B, C and/or D which may be found at the end of this **PRODUCT** portion of Section 8.



8.4.6		Basic Machining Rules			
1 EXPOSED SURFACES shall comply with <b>SMOOTHNESS REQUIREMENTS</b> (see <b>SMOOTHNESS</b> in <b>TESTS</b> ), and:					
1 1 <b>SHARP EDGES</b> be eased.					
1 2 <b>TOP FLAT WOOD</b> surfaces, those that can be sanded with a drum or wide belt sander, be:					
1	2	1	Minimum 15 KCPI or 100 grit sanding.	E	C P
1	2	2	120 grit sanding.	E	C P
1	2	3	150 grit sanding.	E	C P
1 3 <b>PROFILED</b> and <b>SHAPED WOOD</b> surfaces be:					
1	3	1	Minimum 15 KCPI or 100 grit sanding.	E	C P
1	3	2	Minimum 20 KCPI or 120 grit sanding.	E	C P
1	3	3	120 grit sanding.	E	C P
1 4 <b>HPDL</b> , <b>PVC</b> , and <b>PRE-FINISHED WOOD</b> edges shall be machined flush and filed, sanded, or buffed to remove machine marks and sharp edges, and:					
1 4 1 <b>OVERLAP</b> (See Test F illustrations in <b>TESTS</b> ) such as,					
<div style="display: flex; align-items: center; justify-content: center;"> </div> <p>shall not exceed:</p>					
1	4	1	1	0.005" (0.13 mm) for a maximum length of 2" (50.8 mm) in any 12" (305 mm) run.	E C P
1	4	1	2	0.005" (0.13 mm) for a maximum length of 1" (25.4 mm) in any 24" (610 mm) run.	E C P
1	4	1	3	0.003" (0.08 mm) for a maximum length of 1" (25.4 mm) in any 48" (1220 mm) run.	E C P
Continues next column ▼					



# SECTION 8



## Wall/Ceiling Surfacing and Partitions

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally

<b>E</b>	<b>C</b>	<b>P</b>
----------	----------	----------

## compliance requirements

8.4.6 Basic Machining Rules					
▲ From previous column					
<b>1 EXPOSED SURFACES</b> (continued)					
<b>1 4 HPDL, PVC, and PRE-FINISHED WOOD</b> edges (continued)					
<b>CHIP OUT</b> (See Test G illustrations in TESTS) such as,					
					
shall be inconspicuous when viewed at:					
1	4	2	1	72" (1829 mm).	E C P
1	4	2	2	48" (1220 mm).	E C P
1	4	2	3	24" (610 mm).	E C P
<b>OVER MACHINED</b> (See Test H illustrations in TESTS) removal of color or pattern of face material such as,					
					
shall be limited to:					
1	4	3	1	3/32" x 6" (2.4 mm x 152 mm) and may not occur within 48" (1220 mm) of a similar occurrence.	E C P
1	4	3	2	1/32" x 4" (0.8 mm x 102 mm) and may not occur within 60" (1524 mm) of a similar occurrence.	E C P
1	4	3	3	1/32" x 1-1/2" (0.8 mm x 38.1 mm) and may not occur within 72" (1829 mm) of a similar occurrence.	E C P
<b>1 5 TURNED WOOD</b> surfaces be:					
1	5	1	Minimum 15 KCPI or 100 grit sanding.		E C P
1	5	2	120 grit sanding.		E C P
1	5	3	180 grit sanding.		E C P
Continues next column ▼					

8.4.6 Basic Machining Rules					
▲ From previous column					
<b>1 EXPOSED SURFACES</b> (continued)					
<b>1 6 CROSS SANDING</b> , excluding turned surfaces:					
1	6	1	Is not a defect.		E C P
1	6	2	Is not allowed.		E C P
<b>1 7 TEAR OUTS, KNIFE NICKS, or HIT OR MISS</b> machining is not permitted.					
<b>1 8 KNIFE MARKS</b> not to be permitted where sanding is required.					
<b>1 9 GLUE</b> or <b>FILLER</b> , if used, to be inconspicuous and match the adjacent surface for smoothness.					
<b>1 10</b> At <b>SOLID SURFACE, SOLID PHENOLIC, EPOXY RESIN,</b> and <b>NATURAL STONE</b> shall be per the manufacturer's recommendations.					



# SECTION 8


## Wall/Ceiling Surfacing and Partitions



GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally

**E C P**

## compliance requirements

8.4.7		Basic Assembly Rules						
1 THESE STANDARDS do not establish grade rules for joint flushness and or gap tolerances for woodwork products installed in a non climate controlled environment: however:								
1	1	Prior to installation, the flushness and/or gap tolerances of woodwork products intended for non climate controlled environments shall meet the test requirements herein.						
2 JOINTS at ASSEMBLED WOODWORK shall:								
2	1	Be neatly and accurately made.						
2	2	Be <b>SECURELY GLUED</b> , with:						
2	2	1	Adhesive residue removed from exposed and semi-exposed surfaces.					
2	3	Be <b>REINFORCED</b> with glue blocks where essential.						
2	4	Utilize biscuit spline, butterfly, scarf, spline, dowel or miter fold joinery.			E	C	P	
2	5	Be <b>MECHANICALLY FASTENED</b> with nails or screws, where practical, with fasteners:						
2	5	1	Countersunk.					
2	5	2	Located in molding quirks or reliefs where possible.			E	C	P
2	6	Not permit <b>VISIBLE FASTENERS</b> at exposed surfaces of sheet products.						
2	7	Require <b>FLUSHNESS VARIATIONS</b> at exposed surfaces (See Test D illustrations in TESTS), when mitered or butted, such as,						
								
not to exceed at:								
2	7	1	Wood to wood:					
2	7	1	1	0.010" (0.25 mm).		E	C	P
2	7	1	2	0.007" (0.18 mm).		E	C	P
2	7	1	3	0.005" (0.13 mm).		E	C	P
Continues next column ▼								

8.4.7		Basic Assembly Rules						
▲ From previous column								
2 JOINTS at ASSEMBLED WOODWORK (continued)								
2	7	Require <b>FLUSHNESS VARIATIONS</b> (continued)						
2	7	2	Non wood to non wood:					
2	7	2	1	0.025" (0.64 mm).		E	C	P
2	7	2	2	0.015" (0.38 mm).		E	C	P
2	7	2	3	0.010" (0.25 mm).		E	C	P
2	8	Allow <b>GAPS</b> at exposed surface (see Test A illustrations in TESTS), when mitered or butted, such as,						
								
not to exceed:								
2	8	1	0.025" (0.64 mm) wide by 20% of the joint length.			E	C	P
2	8	2	0.015" (0.38 mm) wide by 20% of the joint length.			E	C	P
2	8	3	0.010" (0.25 mm) wide by 20% of the joint length.			E	C	P
2	9	Allow <b>GAPS</b> at exposed surface joints of parallel members (See Test B illustrations in TESTS), such as,						
								
not to exceed:								
2	9	1	0.025" x 9" (0.64 mm x 229 mm) shall not occur within 48" (1219 mm) of a similar gap in the same joint.			E	C	P
2	9	2	0.015" x 6" (0.38 mm x 152 mm) shall not occur within 60" (1524 mm) of a similar gap in the same joint.			E	C	P
2	9	3	0.010" x 4" (0.25 mm x 102 mm) shall not occur within 72" (1829 mm) of a similar gap in the same joint.			E	C	P
Continues next column ▼								

# SECTION 8


## Wall/Ceiling Surfacing and Partitions


GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally

**E C P**

### compliance requirements

8.4.7 Basic Assembly Rules	
▲ From previous column	
2	<b>JOINTS at ASSEMBLED WOODWORK</b> (continued)
2 10	<p>Allow <b>GAPS</b> at exposed surface edge joints (See Test C illustrations in TESTS) when mitered or butted, such as,</p>  <p>not to exceed:</p>
2 10 1	0.025" (0.64 mm). <b>E C P</b>
2 10 2	0.015" (0.38 mm). <b>E C P</b>
2 10 3	0.010" (0.25 mm). <b>E C P</b>
2 11	Allows use of <b>FILLER</b> :
2 11 1	If inconspicuous when viewed at 36" (914 mm). <b>E C P</b>
2 11 2	If inconspicuous when viewed at 24" (610 mm). <b>E C P</b>
2 11 3	Not allowed. <b>E C P</b>
2 12	Shall be mitered.
2 13	Shall be spot glued and mechanically fastened: <b>E C P</b>
2 13 1	Only to non panel surfaces, panel is required to float.
2 13 2	With a maximum of two positioning nails per 12" (300 mm) of length before a joint. <b>E C P</b>
2 13 3	With nails set, and: <b>E C P</b>
2 13 3 1	Filled and sanded if pre-finished.
2 14	<b>MITER JOINTS</b> shall be well fitted and cleaned.
2 15	<b>BUILT UP ITEMS</b> shall be soundly fabricated with half lapped, mitered, miter fold, shoulder mitered, tonged, or equivalent construction.
2 16	<b>SHEET and LAMINATED LUMBER PANELS</b> shall be allowed to move, float, expand or contract in reaction to ambient humidity changes.
Continues next column ▼	

8.4.7 Basic Assembly Rules	
▲ From previous column	
3	<p>Requires <b>FLATNESS</b> or <b>WARP</b> of installed and removable sheet products (see Test E illustrations in TESTS) such as,</p>  <p>not to exceed grade tolerance listed for 12" (303 mm) diagonal, width and/or length or as lineal ratio (not geometric ratio) thereof. Example, twice the grade tolerance listed for 24" (610 mm), three times the tolerance for 36" (914 mm):</p>
3 1	0.045" (1.1 mm) per 12" (305 mm). <b>E C P</b>
3 2	0.030" (0.8 mm) per 12" (305 mm). <b>E C P</b>
3 3	0.020" (0.5 mm) per 12" (305 mm). <b>E C P</b>

**Specific PRODUCT Requirements for Wood, Decorative Laminate, Solid Surface and Solid Phenolic surfacing are in Annex A, B, C and/or D which follow herein.**



# SECTION 8 - ANNEX 8A

## Wood Wall/Ceiling Surfacing and Partitions

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally

<b>E</b>	<b>C</b>	<b>P</b>
----------	----------	----------

**compliance requirements**

# Additional Requirements for Wood Wall/Ceiling Surfacing and Partitions

8.4.5.A		Additional Requirements for Wood Material Rules		
1	<b>VENEER SURFACING</b> requires:			
1	1	Requires <b>CORES</b> of particleboard or medium density fiberboard (MDF) to be:		
1	1	1	A minimum of 1/4" (6.4 mm) in thickness.	E C P
1	1	2	A minimum of 7/16" (11.1 mm) in thickness.	E C P
1	1	3	A minimum of 11/16" (17.5 mm) in thickness.	E C P
1	2	<b>MATCHING</b> , such as book match and end match, slip match and end match, or special sketch faces, to be so specified and detailed.		
1	3	For <b>OPAQUE</b> finish, face shall:		
1	3	1	<b>NOT</b> require the selection of color and/or grain.	
1	3	2	<b>PERMIT</b> the use of paint grade hardwood, medium density fiberboard (MDF), or medium density overlay (MDO), and:	
1	3	2	1 If <b>MDF</b> is used, edgebanding is not required.	
1	3	3	Permit manufacturers' choice of veneer slicing.	
1	3	4	<b>NOT</b> require matching of veneer leaves.	
1	3	5	<b>NOT</b> require matching of adjacent panels.	
1	3	6	Have visible <b>REVEALS</b> and <b>SPLINES</b> that are:	
1	3	6	1 Full length.	
1	3	6	2 Manufacturers' choice of species.	
1	3	7	Have <b>EDGES</b> :	
1	3	7	1 Filled and sanded.	E C P
1	3	7	2 Edgebanded with close grain material, with:	E C P
1	3	7	2 1 <b>FINGER JOINTS</b> permitted.	E C P
<b>Continues next column ▼</b>				

8.4.5.A		Additional Requirements for Wood Material Rules		
<b>▲ From previous column</b>				
1	<b>VENEER SURFACING</b> (continued)			
1	4	For <b>TRANSPARENT</b> finish, shall:		
1	4	1	Have <b>FACES</b> that are:	
1	4	1	1 Between <b>ADJACENT PANELS</b> of:	
1	4	1	1 1 Manufacturers' choice.	E C P
1	4	1	1 2 Sequenced pre-manufactured sets.	E C P
1	4	1	1 3 Balance matched, sequenced pre-manufactured sets, except:	E C P
1	4	1	1 3 1 At trimmed ends of sequenced panel sets	
1	4	1	1 4 Balance matched when required to be end matched.	E C P
1	4	1	2 Between <b>ADJACENT PANELS</b> when <b>SEPARATED BY SOLID WOOD</b> greater than 2 1/2" (63.5mm) wide of:	
1	4	1	2 1 Manufacturers' choice.	E C P
1	4	1	2 2 Compatibly matched for color and grain.	E C P
1	4	1	2 3 Balance matched, sequenced pre-manufactured sets, except:	E C P
1	4	1	2 3 1 At trimmed ends of sequenced panel sets	
1	4	1	2 4 Balance matched when required to be end matched.	E C P
1	5	Have visible <b>EDGES, REVEALS, and/or SPLINES</b> , when appropriate, that are:		
1	5	1	Full length.	
1	5	2	<b>MANUFACTURERS'</b> choice.	E C P
1	5	3	<b>MATCH</b> species of panel face.	E C P
1	5	4	<b>COMPATIBLE</b> for color and grain.	E C P
1	5	5	<b>WELL MATCHED</b> for color and grain.	E C P
1	5	6	A minimum of 0.020" (0.5 mm) nominal thickness that precludes show through of core.	E C P
<b>Continues next column ▼</b>				

# SECTION 8 - ANNEX 8A

## Wood Wall/Ceiling Surfacing and Partitions

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally

<b>E</b>	<b>C</b>	<b>P</b>
----------	----------	----------

**compliance requirements**

# Additional Requirements for Wood Wall/Ceiling Surfacing and Partitions

8.4.5.A		Additional Requirements for Wood Material Rules					
▲ From previous column							
1 VENEER SURFACING (continued)							
1	5	Have visible <b>EDGES, REVEALS, and/or SPLINES</b> (continued)					
1	5	7	<b>WITHIN A PANEL</b> , shall have solid wood let into the core before the veneer is applied where the veneer is machined through, however:				
			E	C	P		
1	5	7	Reveals of 1/8" (3.2 mm) or less in width let into MDF to a maximum depth of one third of the core thickness do not require solid wood if finished same as exposed finish.				
1	5	8 Allows <b>FINGER JOINTS</b> :					
1	5	8	1 At manufacturers' choice.				
			E	C	P		
1	5	8	2 One per 96" (2440 mm) of length.				
			E	C	P		
1	5	8	3 Not allowed.				
			E	C	P		
1	6 Does not permit <b>BLEED THROUGH</b> of adhesive at veneer joints that visually affects an applied finish.						
1	7 At <b>FLAME SPREAD RATED</b> paneling:						
1	7	1 Shall be of the construction standard of the panel manufacturer and conform to the requirements of applicable labeling agencies.					
2 <b>STILE and RAIL WOOD SURFACING</b> requires:							
2	1 No adhesive bleed through at joints.						
2	2 <b>LUMBER</b> be plain sawn.						
2	3 <b>VENEERED</b> sheet products that comply with those requirements spelled out for Veneered Wall Surfacing within this section.						
2	4 At <b>OPAQUE</b> finish:						
2	4	1 Medium density fiberboard.					
2	4	2 Paint grade hardwood or softwood at manufacturer's choice.			E	C	P
2	4	3 Paint grade hardwood.			E	C	P
2	4	4 Finger joints.			E	C	P
Continues next column ▼							

8.4.5.A		Additional Requirements for Wood Material Rules			
▲ From previous column					
2 <b>SOLID STILE and RAIL SURFACING</b> (continued)					
2	5	At <b>TRANSPARENT</b> finish, finger joints.			
			E	C	P
2	6 <b>PANELS</b> :				
2	6	1 <b>SHALL BE</b> solid stock or veneered construction, at the manufacturer's choice.			
2	6	2 <b>If FLAT shall be:</b>			
2	6	2 1 <b>SOLID WOOD</b> :			
2	6	2	1 Minimum 1/2" (12.7 mm) in thickness and maximum 23-3/4" (603 mm) across the grain in width.		
			E	C	P
2	6	2	2 Minimum 3/4" (19 mm) in thickness and maximum 13-3/4" (350 mm) across the grain in width.		
			E	C	P
2	6	2	3 Not permitted.		
			E	C	P
2	6	2 <b>SHEET PRODUCT</b> :			
2	6	2	2 1 Minimum 1/4" (6.4 mm) in thickness.		
			E	C	P
2	6	2	2 2 Minimum 1/2" (12.7 mm) in thickness.		
			E	C	P
2	6	3 <b>If RAISED shall be:</b>			
2	6	3 1 <b>SOLID WOOD</b> :			
2	6	3	1 Permitted in any dimension.		
			E	C	P
2	6	3	2 Minimum 3/4" (19 mm) in thickness and maximum 13-3/4" (350 mm) across the grain in width.		
			E	C	P
2	6	3	3 Not permitted.		
			E	C	P
2	6	3 2 <b>VENEERED STILES and RAILS or SHEET PRODUCT</b> :			
2	6	3	2 1 Minimum 1/2" (12.7 mm) in thickness.		
			E	C	P
2	6	3	2 2 Minimum 11/16" (17.5 mm) in thickness.		
			E	C	P
Continues next column ▼					

# SECTION 8 - ANNEX 8A

## Wood Wall/Ceiling Surfacing and Partitions

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally

<b>E</b>	<b>C</b>	<b>P</b>
----------	----------	----------

**compliance requirements**

# Additional Requirements for Wood Wall/Ceiling Surfacing and Partitions

<b>8.4.5.A</b>		<b>Additional Requirements for Wood Material Rules</b>	
▲ From previous column			
2	<b>SOLID STILE and RAIL SURFACING</b> (continued)		
2	6	3	If <b>RAISED</b> (continued)
2	6	4	<b>EDGES</b> of veneered constructed components shall:
2	6	4	1 Be veneer edgebanded with compatible species. <span style="float:right">E C P</span>
2	6	4	2 Be veneer edgebanded with same species as face. <span style="float:right">E C P</span>
2	6	4	3 Not require mitering at corners.
3 <b>SOLID WOOD SURFACING</b> requires:			
3	1	No adhesive bleed through.	
3	2	At <b>OPAQUE</b> finish, use of:	
3	2	1	Medium Density Fiberboard (MDF).
3	2	2	Paint grade hardwood or softwood at manufacturer's choice. <span style="float:right">E C P</span>
3	2	3	Paint grade hardwood. <span style="float:right">E C P</span>
3	2	4	Finger joints. <span style="float:right">E C P</span>
3	3	At <b>TRANSPARENT</b> finish, use of finger joints. <span style="float:right">E C P</span>	

<b>8.4.7.A</b>		<b>Additional Requirements for Wood Assembly Rules</b>	
1	<b>VENEER SURFACING</b> requires:		
1	1	<b>PANELS</b> are to be cut to size by the:	
1	1	1	Installer. <span style="float:right">E C P</span>
1	1	2	Manufacturer and scribed to fit by installer. <span style="float:right">E C P</span>
1	2	Requires <b>VENEER SEQUENCE</b> at:	
1	2	1	Pre-manufactured <b>BALANCED MATCH</b> panels with the width of outer leaves after trimming at the edges not to exceed:
1	2	1	1 Unlimited. <span style="float:right">E C P</span>
1	2	1	2 1-1/2" (38.1 mm) less than the adjoining leaf. <span style="float:right">E C P</span>
1	2	1	3 3/4" (19 mm) less than the adjoining leaf. <span style="float:right">E C P</span>
1	2	2	Custom made to order <b>SEQUENCE BALANCE MATCH</b> panels with the width of outer leaves after trimming at edges not to exceed:
1	2	2	1 Unlimited. <span style="float:right">E C P</span>
1	2	2	2 1" (25.4 mm) less than the adjoining leaf. <span style="float:right">E C P</span>
1	2	2	3 1/2" (12.7 mm) less than the adjoining leaf. <span style="float:right">E C P</span>
1	2	3	Panels when divided with <b>VENEER GRAIN</b> aligned vertically and/or horizontally within a maximum of:
1	2	3	1 Unlimited. <span style="float:right">E C P</span>
1	2	3	2 1/4" (6.4 mm) variance. <span style="float:right">E C P</span>
1	2	3	3 1/8" (3.2 mm) variance. <span style="float:right">E C P</span>
1	2	4	Panels <b>WITHIN A ROOM</b> utilizing:
1	2	4	1 The <b>FULL WIDTH</b> of <b>PRE-MANUFACTURED SETS</b> , except the trimmed side of a make up panel, to be:
1	2	4	1 1 Running match when panels are not end matched. <span style="float:right">E C P</span>
1	2	4	1 2 Balance match when end matched. <span style="float:right">E C P</span>
1	2	4	1 3 Balance match. <span style="float:right">E C P</span>
Continues next column ▼			

# SECTION 8 - ANNEX 8A

## Wood Wall/Ceiling Surfacing and Partitions

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally

<b>E</b>	<b>C</b>	<b>P</b>
----------	----------	----------

**compliance requirements**

# Additional Requirements for Wood Wall/Ceiling Surfacing and Partitions

8.4.7.A		Additional Requirements for Wood Assembly Rules	
▲ From previous column			
1	VENEER SURFACING (continued)		
1	2	VENEER SEQUENCE (continued)	
1	2	4	Panels <b>WITHIN A ROOM</b> (continued)
1	2	4	2 <b>SELECTIVELY REDUCED WIDTH of PRE-MANUFACTURED SETS</b> , are <b>NOT</b> required to be balance matched; however:
1	2	4	2 1 <b>CUSTOM SEQUENCED</b> panels are required to be balance matched, including make up panels. <span style="float:right">E C P</span>
1	2	4	2 2 <b>BLUEPRINT SEQUENCED PANELS</b> are required to be balance matched with veneer alignment at common size panels, make up panels, and components. <span style="float:right">E C P</span>
1	2	4	3 When veneer flitch quantity does not allow for sequence matching for the entire room, flitch transition shall be at changes in plane (e.g. corners), and/or wall openings and shall be:
1	2	4	3 1 Compatible for color and figure. <span style="float:right">E C P</span>
1	2	4	3 2 Well matched for color and figure. <span style="float:right">E C P</span>
1	3 <b>BUTT JOINTS</b> shall:		
1	3	1 Not be factory prepared. <span style="float:right">E C P</span>	
1	3	2 Be factory prepared with edges eased. <span style="float:right">E C P</span>	
1	3	3 Be factory prepared and grooved with splines furnished and edges eased. <span style="float:right">E C P</span>	
Continues next column ▼			

8.4.7.A		Additional Requirements for Wood Assembly Rules	
▲ From previous column			
1	VENEER SURFACING (continued)		
1	4 <b>REVEAL JOINTS and CORNERS</b> shall:		
1	4	1 <b>NOT</b> be factory prepared. <span style="float:right">E C P</span>	
1	4	2 Be factory prepared with edges eased and articulation strip(s) furnished. <span style="float:right">E C P</span>	
1	4	3 Be factory prepared and machined for furnished articulation strip(s) with edges eased. <span style="float:right">E C P</span>	
1	5 <b>INSIDE CORNERS</b> to be shipped oversize for field fitting.		
1	6 <b>MITERED</b> outside corners shall:		
1	6	1 <b>NOT</b> be factory prepared. <span style="float:right">E C P</span>	
1	6	2 Be factory prepared and shipped loose. <span style="float:right">E C P</span>	
1	6	3 Be factory prepared, and if site conditions permit, glued and braced prior to shipping. <span style="float:right">E C P</span>	
1	7	<b>FIELD JOINERY</b> shall be factory prepared to the greatest extent possible with feature strips and joint trim furnished oversize, where possible, to allow for jobsite fitting. <span style="float:right">E C P</span>	
1	8	<b>EXPOSED CORNERS</b> shall be shoulder mitered, lock mitered, spline mitered, mitered with a biscuit spline, or miter folded unless specified and/or detailed otherwise.	
1	9 <b>MOLDINGS</b> within an individual panel face shall be:		
1	9	1 Shipped loose. <span style="float:right">E C P</span>	
1	9	2 Factory applied. <span style="float:right">E C P</span>	
1	10 <b>VENEER JOINTS</b> shall be plumb, within:		
1	10	1 1/4" (6.4 mm). <span style="float:right">E C P</span>	
1	10	2 3/16" (4.8 mm). <span style="float:right">E C P</span>	
1	10	3 1/8" (3.2 mm). <span style="float:right">E C P</span>	
Continues next column ▼			

# SECTION 8 - ANNEX 8A

## Wood Wall/Ceiling Surfacing and Partitions

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally

<b>E</b>	<b>C</b>	<b>P</b>
----------	----------	----------

GENERAL/**PRODUCT**/INSTALLATION/TEST

**compliance requirements**

# Additional Requirements for Wood Wall/Ceiling Surfacing and Partitions

<b>8.4.7.A</b>		<b>Additional Requirements for Wood Assembly Rules</b>		
<b>▲ From previous column</b>				
<b>1</b>	<b>VENEER SURFACING</b> (continued)			
1 11	<b>VENEER LOSS, SIDE</b> between sequenced adjacent panels shall not exceed:			
1 11 1	1-1/2" (38.1 mm).	E	C	P
1 11 2	1" (25.4 mm).	E	C	P
1 12	<b>VENEER LOSS, END</b> between sequenced adjacent end matched panels shall not exceed:			
1 12 1	2" (50.8 mm).	E	C	P
1 12 2	1-1/2" (38.1 mm).	E	C	P
1 13	<b>END MATCHED VENEER MISALIGNMENT</b> between sequenced adjacent panels shall not exceed:			
1 13 1	3/8" (9.5 mm).	E	C	P
1 13 2	3/16" (4.8 mm).	E	C	P
1 14	<b>FIGURE</b> and/or heart progression shall be uniform and natural between adjacent sequenced panels and not exceed:			
1 14 1	1" (25.4 mm).	E	C	P
1 14 2	1/2" (12.7 mm).	E	C	P
1 14 3	Except at doors and other components that adjoin at blueprint panels shall not exceed:			
1 14 3 1	2" (50.8 mm).	E	C	P
1 14 3 2	1-1/2" (38.1 mm).	E	C	P
<b>Continues next column ▼</b>				

<b>8.4.7.A</b>		<b>Additional Requirements for Wood Assembly Rules</b>		
<b>▲ From previous column</b>				
<b>2</b>	<b>SOLID STILE and RAIL SURFACING</b> requires:			
2 1	<b>PANELING</b> shall be factory assembled in sections as large as practical for field installation.	E	C	P
2 2	<b>At FIELD JOINTS:</b>			
2 2 1	Factory preparation is not required.	E	C	P
2 2 2	Shall be factory preparation to the greatest extent possible with feature strips and joint trim furnished oversize, where possible, to allow for jobsite fitting.	E	C	P



# SECTION 8 - ANNEX 8B

## Decorative Laminate Wall/Ceiling Surfacing and Partitions

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally

**E C P**

**compliance requirements**

# Additional Requirements for Decorative Laminate Wall/Ceiling Surfacing and Partitions

8.4.5.B		Additional Requirements for Decorative Laminate Material Rules		
1	<b>CONFORMANCE</b> to NEMA LD -3 (latest edition).			
2	Colors selected from non premium priced standard patterns and texture, and:			
2 1	No minimum thickness.	E	C	P
2 2	Minimum 0.028" (0.7 mm) in thickness.	E	C	P
3	<b>ADJACENT SHEETS</b> be pre-matched by the manufacturer and/ or installer to minimize color variation within the scope of the manufacturer's guarantee, and:			
3 1	Be fabricated from the longest sheet lengths available.			
4	If <b>FLAME SPREAD RATING</b> required:			
4 1	Shall be of the construction standard of the panel manufacturer and conform to the requirements of applicable labeling agencies.			
5	<b>PATTERNED</b> or <b>WOOD GRAIN</b> :			
5 1	Shall <b>MATCH VERTICALLY</b> , provided the total height does not exceed the maximum length of the available sheet.			
5 2	Is not required to <b>MATCH HORIZONTALLY</b> .			
6	<b>CORES</b> of particleboard or medium density fiberboard (MDF) shall be:			
6 1	A minimum of 1/4" (6.4 mm) in thickness.	E	C	P
6 2	A minimum of 7/16" (11.1 mm) in thickness.	E	C	P
6 3	A minimum of 11/16" (17.5 mm) in thickness.	E	C	P
7	<b>BACKING SHEET</b> shall be:			
7 1	A minimum of 0.020" (0.5 mm) thickness conforming to NEMA LD-3 (latest edition) and:			
7 1 1	Applied to the backside of the core using the same adhesive as the face lamination.			
7 2	If <b>FLAME SPREAD RATING</b> required:			
7 2 1	Shall be of the construction standard of the panel manufacturer and conform to the requirements of applicable labeling agencies.			
7 3	Shall be applied in the same machine or grain direction as the face laminate.			
<b>Continues next column</b> ▼				

8.4.5.B		Additional Requirements for Decorative Laminate Material Rules		
▲ From previous column				
8	<b>VISIBLE SPLINES</b> and <b>REVEALS</b> that are:			
8 1	1/4" (6.4 mm) or less in any face dimension by depth require:			
8 1 1	MDF core.	E	C	P
8 1 2	No treatment of sides or bottom.	E	C	P
8 1 3	Edges and bottom painted to match face.	E	C	P
8 2	Greater than 1/4" (6.4 mm) in any face dimension by depth require:			
8 2 1	Manufacturers' choice edgebanding or painting of edges and bottom to preclude show through of core.	E	C	P
8 2 2	Manufacturers' choice edgebanding or painting of bottom to preclude show through of core.	E	C	P
8 2 3	Matching edgeband of partial edges.	E	C	P
9	<b>EDGEBANDING</b> of square edged panel parts:			
9 1	Is required at exposed vertical and horizontal edges.			
9 2	Shall be color matched to the exposed face.			
9 3	Shall be <b>HPDL</b> or <b>PVC</b> , a minimum of 0.018" (0.5 mm) in thickness.			
9 4	Shall be applied before or after the face laminate.			
9 5	Does <b>NOT</b> require mitering of corners, and:			
9 5 1	If <b>MITER FOLDED</b> , they shall be machined with the core.			



# SECTION 8 - ANNEX 8B

## Decorative Laminate Wall/Ceiling Surfacing and Partitions



GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally

**E C P**

**compliance requirements**

# Additional Requirements for Decorative Laminate Wall/Ceiling Surfacing and Partitions

8.4.7.B		Additional Requirements for Decorative Laminate Assembly Rules			
<b>1 ALIGNMENT VARIATIONS</b> at special patterns not to exceed:					
1	1	1/4" (6 mm).	E	C	P
1	2	1/8" (3 mm).	E	C	P
1	3	1/16" (1.5 mm).	E	C	P
<b>2 PLUMBNESS</b> at special patterns not to exceed:					
2	1	3/8" (9 mm) in 96" (2440 mm).	E	C	P
2	2	1/4" (6 mm) in 96" (2440 mm).	E	C	P
2	3	1/8" (3 mm) in 96" (2440 mm).	E	C	P
Allow <b>GAPS</b> at butted edges glued to the same piece of core (See Test M illustrations in TESTS) such as,					
					
not to exceed:					
3	1	3 occurrences of 0.030" x 5" (0.76 mm x 127 mm) in any 65 sq/ft (6 sq/m).	E	C	P
3	2	2 occurrences of 0.015" x 5" (0.38 mm x 127 mm) in any 65 sq/ft (6 sq/m).	E	C	P
3	3	1 occurrence of 0.007" x 3" (0.18 mm x 76 mm) in any 65 sq/ft (6 sq/m).	E	C	P
Allow <b>FLUSHNESS</b> at butted edges (See Test N illustrations in TESTS) such as,					
					
not to exceed:					
4	1	0.009" (0.23 mm).	E	C	P
4	2	0.006" (0.15 mm).	E	C	P
4	3	0.003" (0.08 mm).	E	C	P
Continues next column ▼					

8.4.7.B		Additional Requirements for Decorative Laminate Assembly Rules			
<b>▲ From previous column</b>					
<b>5 RETENTION MOLDINGS</b> are permitted at field joints, and:					
5	1	Shall be secured to wall studs or in wall blocking.			
<b>6 VERTICAL or HORIZONTAL JOINTS</b> shall have a slight "V", and:					
6	1	Be splined full length or have biscuit splines at a minimum of 12" (305 mm) on center.			
<b>7 PANELS</b> shall:					
7	1	<b>NOT</b> be factory prepared; panels are to be shipped as full size panels for cutting and fitting in the field.	E	C	P
7	2	Be factory sized, except where field adjustment is required.	E	C	P
<b>8 BUTT JOINTS</b> shall:					
8	1	<b>NOT</b> be factory prepared.	E	C	P
8	2	Be factory prepared with edges eased.	E	C	P
8	3	Be factory prepared and grooved with splines furnished and edges eased.	E	C	P
<b>9 REVEAL JOINTS and CORNERS</b> shall:					
9	1	<b>NOT</b> be factory prepared.	E	C	P
9	2	Be factory prepared with edges eased and articulation strip(s) furnished.	E	C	P
9	3	Be factory prepared and machined for furnished articulation strip(s) with edges eased.	E	C	P
<b>10 INSIDE CORNERS</b> to be shipped oversize for field fitting.					
<b>11 OUTSIDE CORNERS</b> shall:					
11	1	<b>NOT</b> be factory prepared.	E	C	P
11	2	Be factory prepared and shipped loose.	E	C	P
11	3	Be factory prepared, and if site conditions permit, glued and braced prior to shipping.	E	C	P

# SECTION 8 - ANNEX 8C

## Solid Surface Wall/Ceiling Surfacing and Partitions

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



**compliance requirements**

# Additional Requirements for Solid Surface Wall/Ceiling Surfacing and Partitions

<b>8.4.5.C</b>		<b>Additional Requirements for Solid Surface Material Rules</b> <i>(only available in Custom and Premium Grade)</i>	
<b>1</b>	<b>DIRECTLY</b> applied to wall or ceiling surfaces shall be a minimum of:		
1	1 1/4" (6.4 mm) in thickness.	<b>C</b>	<b>P</b>
1	2 1/2" (12.7 mm) in thickness.	<b>C</b>	<b>P</b>
<b>2</b>	<b>JOINERY</b> shall be:		
2	1 <b>BUTT JOINTED</b> and caulked or covered with a trim batten.	<b>C</b>	<b>P</b>
2	2 <b>HARD SEAMED</b> , except at building expansion joints.	<b>C</b>	<b>P</b>
<b>3</b>	<b>COLOR</b> selection shall be from the manufacturer's full range of colors available for the thickness required.		
<b>4</b>	<b>FINISH</b> to be manufacturer's standard matte finish unless otherwise specified.		

<b>8.4.7.C</b>		<b>Additional Requirements for Solid Surface Assembly Rules</b> <i>(only available in Custom and Premium Grade)</i>	
<b>1</b>	<b>BUTT JOINT</b> components to be spaced approximately 1/8" (3.2 mm) apart to allow satisfactory caulking or seaming:		
1	1 Shall be <b>CAULKED</b> with compatible color matched sealant.	<b>C</b>	<b>P</b>
1	2 Shall be <b>SEAMED</b> with compatible hard seam adhesive.	<b>C</b>	<b>P</b>
<b>2</b>	<b>VERTICAL JOINTS</b> in horizontal panel runs to be:		
2	1 <b>CAULKED</b> or trimmed with an <b>APPLIED</b> 1/4" x 1" (6.4 mm x 25.4 mm) <b>BATTEN</b> using silicone or other manufacturer approved adhesive.	<b>C</b>	<b>P</b>
2	2 <b>HARD SEAMED</b> with manufacturer approved hard seam adhesive.	<b>C</b>	<b>P</b>
<b>3</b>	<b>EXPANSION</b> joints where required by building design or manufacturer recommendation.		



**SECTION 8 - ANNEX 8D**  
**Solid Phenolic Wall/Ceiling Surfacing and Partitions**

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



GENERAL/**PRODUCT**/INSTALLATION/TEST

**compliance requirements**

## Additional Requirements for Solid Phenolic Wall/Ceiling Surfacing and Partitions

<b>8.4.5.D</b>	<b>Additional Requirements for Solid Phenolic Material Rules</b> <small>(only available in Premium Grade)</small>
1	<b>THICKNESS</b> to be a minimum of 1/8" (3.2 mm).
2	<b>COLOR</b> to be selected from the manufacturer's standard product line.
3	<b>FINISH</b> to be selected from the manufacturer's standard product line.

<b>8.4.7.D</b>	<b>Additional Requirements for Solid Phenolic Assembly Rules</b> <small>(only available in Premium Grade)</small>
1	<b>JOINT WIDTH</b> shall be at least 1/8 " (3.2 mm) to allow satisfactory caulking penetration.
2	<b>JOINTS</b> shall provide for panel movement in both horizontal and vertical directions, such as by use of:
2	1 <b>TRIMS</b> or <b>GASKETS</b> made of aluminium, PVC, and neoprene.
3	At rabbeted or tongue and groove joints, panel thickness shall be a minimum of 3/8" (9.5 mm).



# SECTION 8

## Wall/Ceiling Surfacing and Partitions

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



## compliance requirements

### 8.5 PREPARATION and QUALIFICATION REQUIREMENTS

- 1 **CARE, STORAGE, and BUILDING CONDITIONS** shall be in compliance with the requirements set forth in Section 2 of these standards.
- 1.1 Severe damage to the woodwork can result from noncompliance. **THE MANUFACTURER AND/OR INSTALLER OF THE WOODWORK SHALL NOT BE HELD RESPONSIBLE FOR DAMAGE THAT MIGHT DEVELOP BY NOT ADHERING TO THE REQUIREMENTS.**
- 2 **CONTRACTOR IS RESPONSIBLE FOR** 
- 2.1 Furnishing and installing structural members, grounds, in wall blocking, backing, furring, brackets, or other anchorage required for architectural woodwork installation that becomes an integral part of walls, floors, or ceilings to which architectural woodwork shall be installed.
- 2.1.1 In the absence of contract documents calling for the contractor to supply the necessary in wall blocking/backing in the wall or ceilings, either through inadvertence or otherwise, the architectural woodwork installer shall not proceed with the installation until such time as the in wall blocking/backing is installed by others.
- 2.1.2 Preparatory work done by others shall be subject to inspection by the architectural woodwork installer and shall be accepted or rejected for cause prior to installation.
- 2.1.2.1 **WALL, CEILING, and/or OPENING VARIATIONS** in excess of 1/4" (6.4 mm) or **FLOORS** in excess of 1/2" (12.7 mm) in 144" (3658 mm) of being plumb, level, flat, straight, square, or of the correct size are not acceptable for the installation of architectural woodwork, nor is it the responsibility of the installer to scribe or fit to tolerances in excess of such.
- 2.2 Installation site being properly ventilated, protected from direct sunlight, excessive heat and/or moisture, and that the HVAC system is functioning and maintaining the appropriate relative humidity and temperature.

### 8.5 PREPARATION and QUALIFICATION REQUIREMENTS (continued)

- 2.3 Priming the architectural woodwork in accordance with the contract documents prior to its installation, and:
- 2.3.1 Building wall surfaces shall be primed where construction adhesive is used for panelling installation.
- 2.4 If the architectural woodwork is factory finished, priming by the factory finisher is required.
- 3 **INSTALLER IS RESPONSIBLE FOR** 
- 3.1 Having adequate equipment and experienced craftsmen to complete the installation in a first class manner.
- 3.2 Checking architectural woodwork specified and studying the appropriate portions of the contract documents, including these standards and the reviewed shop drawings to familiarize themselves with the requirements of the Grade specified, understanding that:
- 3.2.1 Appearance requirements of Grades apply only to surfaces visible after installation.
- 3.2.2 For transparent finish, special attention needs to be given to the color and the grain of the various woodwork pieces to ensure they are installed in compliance with the Grade specified.
- 3.3 Verification that installation site is properly ventilated, protected from direct sunlight, excessive heat and/or moisture, and that the HVAC system is functioning and maintaining the appropriate relative humidity and temperature.
- 3.4 Verification that required priming of woodwork has been completed by others before woodwork is installed.
- 3.5 Verification that woodwork has been acclimated to the field conditions for a minimum of 72 hours before installation is commenced.
- 3.6 Woodwork specifically built or assembled in sequence for match of color and grain is installed to maintain that same sequence.

# SECTION 8

## Wall/Ceiling Surfacing and Partitions

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



## compliance requirements

### 8.6 RULES

- 1 The following rules shall govern unless a project's contract documents require otherwise.
- 2 These rules are intended to provide a well defined degree of control over a project's quality of installation.
- 3 **ERRATA**, published at <http://naaws-errata.com>, shall take precedence over these rules, subject to their date of posting and a project's bid date.



8.6.1		Basic General Rules		
1	<b>AESTHETIC</b> grade rules apply only to exposed and semi-exposed surfaces visible after installation.			
2	<b>TRANSPARENT FINISHED</b> woodwork shall be installed:			
2 1	With <b>CONSIDERATION</b> of color and grain.	E	C	P
2 2	<b>COMPATIBLE</b> in color and grain.	E	C	P
2 3	<b>WELL MATCHED</b> for color and grain, with:	E	C	P
2 3 1	<b>SHEET PRODUCTS</b> compatible in color with solid stock.	E	C	P
3	<b>REPAIRS</b> are allowed, provided they are neatly made and inconspicuous when viewed at:			
3 1	72" (1830 mm).	E	C	P
3 2	48" (1219 mm).	E	C	P
3 3	24" (610 mm).	E	C	P
4	<b>INSTALLER FABRICATION</b> or <b>MODIFICATIONS</b> shall comply to the general, material, machining, and assembly rules within the <b>PRODUCT</b> portion of this section and the applicable finishing rules in Section 5.			
5	<b>WOODWORK</b> shall be:			
5 1	<b>SECURELY</b> fastened and tightly fitted with flush joints.			
5 1 1	Joinery shall be <b>CONSISTENT</b> throughout the project.			
5 2	Of <b>MAXIMUM</b> available and/or practical lengths.	E	C	P
5 3	<b>TRIMMED EQUALLY</b> from both sides when fitted for width.	E	C	P
5 4	<b>SPLINED</b> or <b>DOWELED</b> when miters are over 4" (100 mm) long.	E	C	P
Continues next column ▼				

8.6.1		Basic General Rules		
▲ From previous column				
5	<b>WOODWORK</b> (continued)			
5 5	<b>PROFILED</b> or <b>SELF MITERED</b> when trim ends are exposed.	E	C	P
5 6	<b>SELF MITERED</b> when trim ends are exposed.	E	C	P
5 7	<b>MITERED</b> at outside corners.			
5 8	<b>MITERED</b> at inside corners.	E	C	P
5 9	<b>COPEd</b> at inside corners for shaped surfaces.	E	C	P
5 10	<b>INSTALLED</b> plumb, level, square, and flat within 1/8" (3.2 mm) in 96" (2438 mm), and when required:			
5 10 1	<b>GROUND</b> s and <b>HANGING SYSTEMS</b> set plumb and true.	E	C	P
5 11	Installed <b>FREE OF</b> :			
5 11 1	Warp, twisting, cupping, and/or bowing that cannot be held true.			
5 11 2	Open joints, visible machine marks, cross sanding, tear outs, nicks, chips, and/or scratches.			
5 11 3	Natural defects exceeding the quantity or size limits defined in Sections 3 & 4.			
5 12	<b>SMOOTH</b> and <b>SANDED</b> without <b>CROSS SCRATCHES</b> in conformance to the <b>PRODUCT</b> portion of this section.			
5 13	<b>SCRIBED</b> at:			
5 13 1	Flat surfaces.	E	C	P
5 13 2	Shaped surfaces.	E	C	P
5 14	Sealed when in contact with walls and floors and/or wall and floor anchorage.			
6	<b>THESE STANDARDS</b> do not establish grade rules for joint flushness and or gap tolerances for woodwork products installed in a non climate controlled environment.			
Continues next column ▼				

# SECTION 8


## Wall/Ceiling Surfacing and Partitions

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally

**E C P**

## compliance requirements

8.6.1		Basic General Rules						
▲ From previous column								
7 <b>GAPS</b> at field installation (see Test I illustrations in TESTS) such as,								
7								
and:								
7	1	If caused by excessive deviations in the building's walls and ceilings being in excess of 1/4" (6.4 mm) in 144" (3658 mm) of being plumb, level, flat, straight, square, or of the correct size, or 1/2" (12.7 mm) for floors, shall not be considered a defect or the responsibility of the installer.						
7	2	Not exceed 30% of a joint's <b>LENGTH</b> and:						
7	2	1	Be allowed if filled or caulked, and:		E	C	P	
7	2	1	1	If color compatible.		E	C	P
7	3	At <b>WOOD</b> to <b>WOOD</b> shall not exceed:						
7	3	1	At <b>FLAT</b> surfaces:					
7	3	1	1	0.030" (0.76 mm) in width.		E	C	P
7	3	1	2	0.020" (0.51 mm) in width.		E	C	P
7	3	1	3	0.015" (0.38 mm) in width.		E	C	P
7	3	2	At <b>SHAPED</b> surfaces:					
7	3	2	1	0.040" (1.02 mm) in width.		E	C	P
7	3	2	2	0.025" (0.64 mm) in width.		E	C	P
7	3	2	3	0.015" (0.38 mm) in width.		E	C	P
7	4	Of <b>WOOD</b> to <b>NON WOOD</b> shall not exceed:						
7	4	1	At <b>FLAT</b> and <b>SHAPED</b> surfaces:					
7	4	1	1	0.075" (1.91 mm) in width.		E	C	P
7	4	1	2	0.050" (1.27 mm) in width.		E	C	P
7	4	1	3	0.035" (0.89 mm) in width.		E	C	P
7	5	Of <b>NON WOOD</b> to <b>NON WOOD</b> and/or <b>ALL ELEMENTS</b> shall not exceed:						
7	5	1	At <b>FLAT</b> surfaces:					
7	5	1	1	0.075" (1.91 mm) in width.		E	C	P
7	5	1	2	0.050" (1.27 mm) in width.		E	C	P
7	5	1	3	0.035" (0.89 mm) in width.		E	C	P
Continues next column ▼								

8.6.1		Basic General Rules						
▲ From previous column								
7	<b>GAPS</b> (see Test I illustrations in Tests) (continued)							
7	5	2	At <b>SHAPED</b> surfaces:					
7	5	2	1	0.120" (3.05 mm) in width.		E	C	P
7	5	2	2	0.075" (1.91 mm) in width.		E	C	P
7	5	2	3	0.050" (1.27 mm) in width.		E	C	P
8 <b>FLUSHNESS</b> of joinery (see Test J illustrations in TESTS), such as,								
8								
and:								
8	1	Of <b>WOOD</b> to <b>WOOD</b> shall not exceed:						
8	1	1	At <b>FLAT</b> surfaces:					
8	1	1	1	0.025" (0.64 mm).		E	C	P
8	1	1	2	0.015" (0.38 mm).		E	C	P
8	1	1	3	0.010" (0.25 mm).		E	C	P
8	1	2	At <b>SHAPED</b> surfaces:					
8	1	2	1	0.040" (0.97 mm).		E	C	P
8	1	2	2	0.025" (0.65 mm).		E	C	P
8	1	2	3	0.020" (0.51 mm).		E	C	P
8	2	Of <b>WOOD</b> to <b>NON WOOD</b> shall not exceed:						
8	2	1	At <b>FLAT</b> and <b>SHAPED</b> surfaces:					
8	2	1	1	0.075" (1.91 mm).		E	C	P
8	2	1	2	0.050" (1.27 mm).		E	C	P
8	2	1	3	0.035" (0.89 mm).		E	C	P
8	3	Of <b>NON WOOD</b> to <b>NON WOOD</b> and/or <b>ALL ELEMENTS</b> shall not exceed:						
8	3	1	At <b>FLAT</b> surfaces:					
8	3	1	1	0.075" (1.91 mm).		E	C	P
8	3	1	2	0.050" (1.27 mm).		E	C	P
8	3	1	3	0.035" (0.89 mm).		E	C	P
8	3	2	At <b>SHAPED</b> surfaces:					
8	3	2	1	0.120" (3.05 mm).		E	C	P
8	3	2	2	0.075" (1.91 mm).		E	C	P
8	3	2	3	0.050" (1.27 mm).		E	C	P
Continues next column ▼								

# SECTION 8



## Wall/Ceiling Surfacing and Partitions

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally

**E C P**

# compliance requirements

8.6.1		Basic General Rules			
▲ From previous column					
9	<b>REVEALS at ADJOINING PANELS</b> (see Test K illustrations in TESTS), such as, <div style="text-align: center;">  </div>				
	shall not exceed a maximum variance of:				
	1	0.040" (1.02 mm).	E	C	P
	2	0.025" (0.64 mm).	E	C	P
3	0.015" (0.38 mm).	E	C	P	
▲ From previous column					
10	<b>FLUSHNESS at ADJOINING PANELS</b> (see Test L illustrations in TESTS) such as, <div style="text-align: center;">  </div>				
	shall not exceed a maximum variance of:				
	1	0.040" (1.02 mm).	E	C	P
	2	0.025" (0.64 mm).	E	C	P
3	0.015" (0.38 mm).	E	C	P	
11 <b>FASTENING</b> shall:					
11 1	Use mechanical fasteners at wall panels installed at 108" (2743 mm) or more above finished floor, and ceiling panels regardless of height.				
Continues next column ▼					

8.6.1		Basic General Rules			
▲ From previous column					
11 <b>FASTENING</b> shall:					
11 2	Use <b>CONCEALED</b> fastening wherever possible.				
11 2 1	If exposed fastening is required to complete the installation:				
11 2 1 1	Fasteners shall be set in quirks or reliefs (where possible), countersunk, and kept to a minimum.				
11 2 1 2	<b>PERMIT</b> use of construction adhesive, finish nails, trim screws, and/or pins.				
11 2 1 2 1	Trim screws.	E	C	P	
11 2 1 2 2	Finish nails.	E	C	P	
11 2 1 2 3	Pins and/or construction adhesive.	E	C	P	
11 2 1 3	<b>DO NOT PERMIT</b> the use of drywall, bugle head, or case hardened screws.				
11 2 1 4	Require exposed fasteners to be inconspicuous, as defined in the glossary.				
11 2 1 5	<b>DO NOT PERMIT</b> exposed fastening through decorative laminate.				
11 2 2	Use of metal Z-clips or hanging cleats are acceptable for blind installation.				
11 3	A maximum of 3/4" (19 mm) reveal is permitted at the top of panels to allow lift on clearance of the panel.				
11 4	<b>REQUIRE</b> allowable fastener holes, when:				
11 4 1	Pre-finished materials to be filled by the installer with matching filler furnished by the woodwork supplier.				
11 4 2	Unfinished or primed materials to be filled and caulked by the paint contractor or others.				
12 <b>REVEAL STRIPS</b> that are grooved into paneling are to be left floating and allowed to expand and contract in reaction to changing relative humidity.					
13 <b>EXPANSION JOINTS</b> shall be provided equivalent to 3/16" (4.8 mm) per 47" (1194 mm) of linear elevation.					
13 1	The minimum reveal gap between panels shall be calculated as the length of the panel times:				
13 1 1	0.004 for particleboard core.				
13 1 2	0.0033 for medium density fiberboard (MDF) core.				
Continues next column ▼					

# SECTION 8

## Wall/Ceiling Surfacing and Partitions

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally

**E C P**

## compliance requirements

8.6.1		Basic General Rules			
▲ From previous column					
14	<b>PANELING</b> shall be:				
14 1	Furred and installed in such a way as to avoid deflection when normal pressure is applied.				
14 2	Free of warp exceeding:				
14 2 1	1/16" (1.6 mm) per linear foot (305 mm).	E	C	P	
14 2 2	3/64" (1.2 mm) per linear foot (305 mm).	E	C		P
14 2 3	1/32" (0.8 mm) per linear foot (305 mm).	E	C	P	
15 <b>JOINTS</b> shall be:					
15 1	Smooth and flush to create a homogenous look.				
15 2	Plumb within 1/16" (1.6 mm) in 96" (2438 mm).				
16	<b>BACKS</b> of wood wall and ceiling surfacing shall be sealed at 2 mil dry.				
		E	C	P	
Requires <b>FLATNESS</b> or <b>WARP</b> of installed and removable sheet products (see Test E illustrations in <b>TESTS</b> ) such as,					
17					
	not to exceed grade tolerance listed for 12" (303 mm) diagonal, width and/or length or as lineal ratio (not geometric ratio) thereof. Example, twice the grade tolerance listed for 24" (610 mm), three times the tolerance for 36" (914 mm):				
17 1	0.050" (1.3 mm) per 12" (305 mm) or portion thereof.	E	C	P	
17 2	0.036" (0.9 mm) per 12" (305 mm) or portion thereof.	E	C		P
17 3	0.027" (0.7 mm) per 12" (305 mm) or portion thereof.	E	C	P	
Continues next column ▼					

8.6.1		Basic General Rules			
▲ From previous column					
18	<b>GLUE</b> and filler residue is not permitted on exposed faces.				
<b>EQUIPMENT CUTOUTS</b> , including electrical and plumbing, shall be cut out by the installer, provided needed templates are furnished prior to installation, and:					
19 1	Shall be neatly cut and properly sized.				
19 2	In <b>HPDL</b> or <b>SOLID SURFACE</b> shall have a minimum 1/4" (6.4 mm) radius at inside corners.				
20 <b>HARDWARE</b> shall be:					
20 1	Installed neatly without tear out of surrounding stock.				
20 2	Installed per the manufacturer's instructions.				
20 3	Installed using furnished fasteners and fastener's provisions and when fastener provisions are countersunk, fasteners shall be countersunk.				
20 4	Adjusted for smooth operation.				
21 <b>AREAS</b> of installation shall be left broom clean.					
21 1	Debris shall be removed and dumped in containers provided by the contractor.				
21 2	Items installed shall be cleaned of pencil or ink marks.				
22	<b>FIRST CLASS WORKMANSHIP</b> is required in compliance with these standards.				

# SECTION 8

## Wall/Ceiling Surfacing and Partitions

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



## compliance requirements

8.6.2		Product Specific Rules			
1	<b>VENEER SURFACING</b> requires:				
1	1	For <b>TRANSPARENT FINISH</b> , the installer shall pay special attention to the <b>COLOR</b> and the <b>GRAIN</b> of the various panels and trim pieces to ensure they are installed in compliance with the <b>GRADE</b> specified.			
1	2	<b>PANELS</b> shall be installed as specified.			
1	3	<b>GLUING</b> with construction adhesive is permitted.			
1	4	<b>CONCEALED FASTENING</b> shall be used wherever possible, and:			
1	4	1	A maximum of 3/4" (19 mm) reveal is permitted at the top of panels either under casework or at ceiling to facilitate such.		
1	5	<b>EDGES</b> of core that are not self edged shall have one coat sealer applied before installation.			
1	6	Veneer joints shall be plumb, within:			
1	6	1	1/4" (6.4 mm).	E C P	
1	6	2	3/16" (4.8 mm).	E C P	
1	6	3	1/8" (3.2 mm).	E C P	
1	7	<b>VENEER LOSS</b> (side) between sequenced adjacent panels shall not exceed:			
1	7	1	1-1/2" (38.1 mm).	E C P	
1	7	2	1" (25.4 mm).	E C P	
1	8	<b>VENEER LOSS</b> (end) between sequenced adjacent panels at end match shall not exceed:			
1	8	1	2" (50.8 mm).	E C P	
1	8	2	1-1/2" (38.1 mm).	E C P	
1	9	End matched veneer alignment between sequenced adjacent panels shall not exceed:			
1	9	1	3/8" (9.5 mm).	E C P	
1	9	2	3/16" (4.8 mm).	E C P	
1	10	Figure and/or heart progression shall be uniform and natural between adjacent sequenced panels and not exceed:			
1	10	1	1" (25.4 mm).	E C P	
1	10	2	1/2" (12.7 mm).	E C P	
1	10	3	Except at doors and other components that adjoin at blueprint panels shall not exceed:		
1	10	3	1	2" (50.8 mm).	E C P
1	10	3	2	1-1/2" (38.1 mm).	E C P
Continues next column ▼					

8.6.2		Product Specific Rules		
▲ From previous column				
2	<b>SOLID WOOD SURFACING</b> requires:			
2	1	<b>FIELD JOINTS</b> require:		
2	1	1	No preparation.	E C P
2	1	2	Shall be factory prepared to the greatest extent possible with feature strips and joint trim furnished oversize, where possible.	E C P
3	<b>DECORATIVE LAMINATE SURFACING</b> requires:			
3	1	<b>EXPOSED FASTENING</b> is not permitted, except:		
3	1	1	At removable panels.	
3	2	<b>PANELS</b> shall be installed as specified.		
3	3	<b>EDGES</b> of core that are not self edged shall have one coat sealer applied before installation.		
3	4	<b>SCRATCHES</b> and <b>CHIP OUT</b> shall be inconspicuous beyond:		
3	4	1	72" (1830 mm).	E C P
3	4	2	48" (1220 mm).	E C P
3	4	3	24" (610 mm).	E C P
3	5	<b>PATTERN LINES</b> shall be plumb, within:		
3	5	1	1/4" (6.4 mm).	E C P
3	5	2	3/16" (4.8 mm).	E C P
3	5	3	1/8" (3.2 mm).	E C P
4	<b>SOLID SURFACE</b> (only available in Custom and Premium Grade) requires:			
4	1	<b>SEALANTS</b> and <b>ADHESIVES</b> shall be compatible with the individual manufacturer's recommendations or specially developed sealants to achieve the best color match.		
4	2	<b>VERTICAL SURFACING</b> shall be installed over suitable cores based on the manufacturer's recommendations.		
4	3	<b>EXPANSION</b> joints shall be furnished where required by building design or manufacturer recommendations.		
4	4	<b>FIELD SEAMS</b> :		
4	4	1	Shall be <b>CAULKED</b> with compatible color matched sealant.	C P
4	4	2	Shall be <b>SEAMED</b> with compatible hard seam adhesive.	C P
Continues next column ▼				

# SECTION 8

## Wall/Ceiling Surfacing and Partitions

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



**compliance requirements**

8.6.2		Product Specific Rules	
▲ From previous column			
4	<b>SOLID SURFACE</b> (continued)		
4	<b>5 EXPOSED FASTENING</b> is not permitted, except:		
4	5	1	At removable panels.
4	5	2	Where decorative fasteners are specified.
4	<b>6 SCRATCHES</b> and <b>CHIP OUTS</b> shall be inconspicuous beyond:		
4	6	1	48" (1220 mm). <b>C</b> <b>P</b>
4	6	2	24" (610 mm). <b>C</b> <b>P</b>
5	<b>SOLID PHENOLIC</b> (only available in Premium Grade) requires:		
5	1	<b>SEALANTS</b> and <b>ADHESIVES</b> shall be compatible with the individual manufacturer's recommendations or specially developed sealants to achieve the best color match.	
5	2	<b>VERTICAL SURFACING</b> shall be installed over suitable cores based on the manufacturer's recommendations.	
5	3	<b>EXPANSION CLEARANCE</b> of at least 3/32" (2.4 mm) for every 120" (3048 mm) in length is required.	
5	4	<b>CAULKED JOINTS</b> shall be approximately 1/8" (3.2 mm) wide to allow satisfactory caulking penetration and expansion.	
5	<b>5 EXPOSED FASTENING</b> is not permitted, except:		
5	5	1	At removable panels.
5	5	2	Where decorative fasteners are specified.
5	<b>6 CONCEALED FASTENING</b> shall be used wherever possible, and:		
5	6	1	A maximum of 3/4" (19 mm) reveal is permitted at the top of panels either under casework or at ceiling to facilitate such.
5	6	2	Be approved by product manufacturer or design authority.
5	<b>7 SCRATCHES</b> and <b>CHIP OUTS</b> shall be inconspicuous beyond:		
5	7	1	24" (610 mm).



# SECTION 8

## Wall/Ceiling Surfacing and Partitions

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally




## compliance requirements

### 8.7 BASIC CONSIDERATIONS

- 1 **TOLERANCES** typically found within NAAWS:
- 1.1 Fall into two **CATEGORIES**:
- 1.1.1 Factory fabricated joinery, assembly and construction - found in the **PRODUCT** portion.
- 1.1.2 Field installation joinery and assembly - found in the **INSTALLATION** portion.
- 1.2 **INCLUDE:**
- 1.2.1 Flatness of wood based panel products.
- 1.2.2 Solid wood to solid wood joints and assemblies.
- 1.2.3 Solid wood to wood veneer joints and assemblies.
- 1.2.4 Wood veneer to wood veneer joints and assemblies.
- 1.2.5 Solid wood to wood based product joints and assemblies (decorative laminate Solid Phenolic and panel products).
- 1.2.6 Solid surface to solid surface joints and assemblies.
- 1.3 **EXCLUDE:**
- 1.3.1 **BECAUSE of EXPANSION and CONTRACTION DIFFERENCES of non-wood products compared to solid wood and wood based products, these Standards do not apply tolerances regarding flatness or joinery to:** 
- 1.3.1.1 Solid wood to non-wood based products (which can be drywall, glass, metal, stone, acrylics, and other surfaces).
- 1.3.1.2 Non-wood to non-wood joints.
- 2 **FABRICATED and INSTALLED** woodwork shall be tested for compliance to these standards as follows.
- 2.1 **SEQUENCED AND BLUEPRINT-MATCHED PANELS, COMPONENTS, AND RELATED DOORS:**
- 2.1.1 These tests do not apply to flush doors specified under Section 9 or specified using other standards.
- 2.1.2 **END-MATCHED JOINTS** by separating end-matched panels and visually testing grain void for continuity.

### 8.7 BASIC CONSIDERATIONS (continued)

- 2.1.3 **SIDE-MATCHED JOINTS** by separating side-matched panels and visually testing grain void for continuity.
- 2.1.4 **HEART FIGURE PROGRESSION**, the full heart figure of plain-sliced veneer shall develop in uniform and natural progression.
- 2.1.4.1 Split or cut hearts are permitted, provided they are used to maintain sequence or to achieve special effects.
- 2.2 **SMOOTHNESS** of exposed surfaces:
- 2.2.1 **KCPI** (Knife Cuts Per Inch) is determined by holding the surfaced board at an angle to a strong light source and counting the visible ridges per inch, usually perpendicular to the profile.
- 
- Figure: 8-049
- 2.2.2 **SANDING** is checked for compliance by sanding a sample piece of the same species with the required grit of abrasive, and:
- 2.2.2.1 Observation with a hand lens of the prepared sample and the material in question will offer a comparison of the scratch marks of the abrasive grit.
- 2.2.2.2 Reasonable assessment of the performance of the finished product will be weighed against absolute compliance with the standard.
- 2.2.2.3 A product is sanded sufficiently smooth when knife cuts are removed and remaining sanding marks are or will be concealed by applied finishing coats.
- 2.2.2.4 Grain raise at unfinished wood, due to moisture or humidity in excess of the ranges set forth in this standard, shall not be considered a defect and must be sanded prior to finishing.
- 2.3 **GAPS, FLUSHNESS, FLATNESS and ALIGNMENT:**
- 2.3.1 Maximum gaps between exposed components shall be tested with a feeler gauge at points designed to join, where members contact or touch.
- 2.3.2 Joint length shall be measured with a ruler with minimum 1/16" (1 mm) divisions and calculations made accordingly.

# SECTION 8

## Wall/Ceiling Surfacing and Partitions

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



## compliance requirements

### 8.7 BASIC CONSIDERATIONS (continued)

#### 2.3 GAPS, FLUSHNESS, FLATNESS and (continued)

2.3.3 Reasonable assessment of the performance of the finished product will be weighed against absolute compliance with the standards.

2.3.4 The following is intended to provide examples of how and where compliance testing is measured:




Figure: 8-049

- A - Fabrication Gaps When Surfaces Are Mitered Or Butted
- B - Fabrication Gaps When Parallel Pieces Are Joined
- C - Fabrication Gaps When Edges Are Mitered Or Butted
- D - Fabrication Flushness Between Two Surfaces
- E - Flatness Of Panel Product
- F - Overlap (Flushness Of Laminate)
- G - Chip Out

- H - Over Machining
- I - Installation Gaps
- J - Installation Flushness
- K - Installation Reveal At Adjacent Panels
- L - Installation Flushness At Adjacent Panels
- M - Fabrication Gap At Laminate Butt Jointed On The Same Piece Of Core
- N - Fabrication Flushness At Butt Jointed Laminate

# North American Architectural Woodwork Standards - 3.1

## **S E C T I O N - 09**

# DOORS

<b>Resources . . . . .</b>	<b><a href="#">260</a></b>
<b>Introduction . . . . .</b>	<b><a href="#">262</a></b>
<b>Advisories . . . . .</b>	<b><a href="#">262</a></b>
<b>Recommendations . . . . .</b>	<b><a href="#">263</a></b>
<b>Specification Considerations . . . . .</b>	<b><a href="#">263</a></b>
<b>Design Resources . . . . .</b>	<b><a href="#">274</a></b>
<b>Compliance Requirements . . . . .</b>	<b><a href="#">275</a></b>
<b>Scope &amp; Default Stipulation . . . . .</b>	<b><a href="#">278</a></b>
<b>Basic Requirements . . . . .</b>	<b><a href="#">278</a></b>
<b>Installation Requirements . . . . .</b>	<b><a href="#">296</a></b>
<b>Tests . . . . .</b>	<b><a href="#">300</a></b>

### Within CANADA

#### SUPPORT

- **GUIDE SPECIFICATIONS** – Available for download in interactive digital format, including specification wording for Quality Assurance Program (GIS) at: <http://awmac.com/guide-specifications>
- **CONSULTATION** – Contact any of the local chapters for more information on the NAAWS or any other Architectural Woodwork Questions you may have. See below for contact information.
- **SPECIFICATION REVIEW** – Contact any of the local chapters if you would like your specifications reviewed for compliance to the NAAWS.
- **MANUFACTURER STANDARDS QUESTIONNAIRE (MSQ)** – AWMAC Manufacturer members have the opportunity to have at least one member of their staff study and write the MSQ. The MSQ is a questionnaire on the NAAWS and policy and procedures of the GIS program. A list of Manufacturer members that have passed the MSQ is available at: <http://awmac.com/members>
- **SEMINARS AND PRESENTATIONS** – Contact your local chapter to arrange an informative presentation on any Architectural Woodwork topic. Some topic options – GIS, NAAWS, How to Specify Quality Architectural Woodwork...
- **TRADE SHOWS** – Contact your local chapter to arrange for AWMAC to have a booth or do a presentation on Architectural Woodwork.
- **CONFERENCE** – AWMAC has an annual conference held at unique venues across Canada. The conferences provide an opportunity to learn more about Architectural Woodwork and network with Suppliers and Manufacturers from across Canada. More information is available at: <http://awmac.com/>
- **EDUCATION PARTNERS** – Contact the local chapters to find out more information about support for local Colleges and Universities offering woodworking related courses and programs.

#### QUALITY ASSURANCE

- **GUARANTEE AND INSPECTION SERVICE (GIS)** – The GIS is a national program designed to ensure that project owners get value and quality for their investment by:
  - Supporting architects and design professionals to achieve project plans and specifications; and
  - Helping contractors avoid problems such as cost overruns, delays and loss of reputation.More information is available at: <http://awmac.com/gis>

- **INSPECTION SERVICE** – A GIS Certified Inspector will inspect specific areas of concern on a project for compliance to the NAAWS and provide a written report. Contact your local chapter for more information.
- **EXPERT OPINION** – An expert will be appointed to inspect specific areas of concern on a project and provide a written report. Contact your local chapter for more information.

#### AWMAC CHAPTERS

- AWMAC British Columbia Chapter, Vancouver BC  
<http://bc.awmac.com>
- AWMAC Northern Alberta Chapter, Edmonton Alberta  
<http://nab.awmac.com>
- AWMAC Southern Alberta Chapter, Calgary Alberta  
<http://sab.awmac.com>
- AWMAC Saskatchewan Chapter, Saskatoon Saskatchewan  
<http://sk.awmac.com>
- AWMAC Manitoba Chapter, Winnipeg Manitoba  
<http://mb.awmac.com>
- AWMAC Ontario Chapter, Toronto Ontario  
<http://on.awmac.com>
- AWMAC Quebec Chapter, Montreal Quebec  
<http://qc.awmac.com>
- AWMAC Atlantic Chapter, Halifax Nova Scotia  
<http://atl.awmac.com>

# SECTION 9

## Doors

## resources

### Within UNITED STATES

#### SUPPORT

- **GUIDE SPECIFICATIONS** - Available in interactive digital format including quality control options at: <http://woodworkinstitute.com/publications/architectural-woodwork-standards/>
- **AIA SEMINARS** - The Woodwork Institute is a Registered Provider of the American Institute of Architects (AIA), and its Continuing Education System (CES) program, check out our offerings at: <http://woodworkinstitute.com/architectural-resources/aia-seminars/> 
- **CONSULTATION** - Contact one of our Directors of Architectural Services (DAS) at: <http://woodworkinstitute.com/about-us-2/about-us/>
- **ACCREDITED FABRICATORS AND INSTALLERS** - Our AMC's (Accredited Millwork Company) represents the best fabricators and installers in our industry, check them out at: <http://woodworkinstitute.com/membership-listing-2/> 
- **CERTIFIED INDUSTRY PROFESSIONALS** - Our CMP's (Certified Millwork Professionals) represent the knowledge base of our industry, check them out at: <http://woodworkinstitute.com/membership-listing-2/> 
- **MILLWORK INDUSTRY PARTNERS** - Our MIP's (Millwork Industry Partners) represent the best of our industries material suppliers, check them out at: <http://woodworkinstitute.com/membership-listing-2/> 
- **ACKNOWLEDGED PRODUCTS LISTING** - If it's listed here, you are assured it meets NAAWS minimum requirements, find the listing at: <http://woodworkinstitute.com/acknowledged-product-listing/> 
- **CABINET DESIGN SERIES (CDS)** - Eliminate the need to include casework elevations in your architectural drawings, check out the CDS system in NAAWS "Design Resources" and access the cad files at: <http://woodworkinstitute.com/architectural-resources/cabinet-design-series/>

#### QUALITY ASSURANCE

- **BIDDER QUALIFICATION** - A discipline of bidder pre-qualification wherein your specifications protect you and your customer from the unknown: To be eligible to bid or negotiate this job, the subcontractor must be a Woodwork Institute Accredited Millwork Company (AMC) in good standing. <http://woodworkinstitute.com/architectural-resources/quality-assurance> 
- **CERTIFIED COMPLIANCE PROGRAM (CCP)** - A discipline of quality control used in conjunction with NAAWS providing an unbiased means of ensuring conformance to a project's plans and specifications. CCP, together with the use of the desired Grade(s) in the specifications, informs all parties of the design professional's expectations, without bidder discrimination. <http://woodworkinstitute.com/services/certified-compliance-program> 
- **MONITORED COMPLIANCE PROGRAM (MCP)** - A discipline of quality affirmation used in conjunction with the NAAWS which provides ongoing reviews/inspections of a project from its beginning through completion, ensuring strict conformance to the design intent throughout the millwork fabrication and installation process. <http://woodworkinstitute.com/services/monitored-compliance-program/> 
- **CERTIFIED SEISMIC INSTALLATION PROGRAM (CSIP)** - A standalone seismic assurance option which can be specified in conjunction with or without CCP or MCP, offering design professionals and project owners specific use of WI's seismic casework pre-approvals from California's Office of Statewide Health Planning and Development (OSHPD) without additional engineering costs and/or requirements, assuring proper backing has been installed in the walls when and where required. <http://woodworkinstitute.com/services/certified-seismic-installation-program/> 

# SECTION 9

## Doors

## introductory information

### INTRODUCTION

Section 9 includes information on doors using flush and stile & rail construction with wood or HPDL faces and their related parts.

In the past manufacturers have relied on the natural strength of hardwood lumber and veneer to assure long term performance. Many new engineered wood products are now replacing traditional hardwoods; allowing cost reductions, improved production efficiency and allowing the manufacturers the ability to provide better doors.

However, there is a risk some nonconforming products will not perform as well. The materials and construction methods used determine how well a door will resist high use and abuse. With the introduction of engineered wood products this becomes more important. Wood products, whether natural or engineered, have a wide range of strength characteristics and it is important that the door material and construction method meets the performance criteria of the project requirements.

Quality assurance can be achieved by adherence to these standards and will provide the owner a quality product at competitive pricing. Working with an AWMAC Member (in Canada) or a WI Certified Millwork Professional (CMP) (in the USA) and the WI Accredited Millwork Company (AMC) they represent to provide your woodwork will help ensure the understanding and performance of the quality level required. Illustrations in this Section are not intended to be all inclusive, other engineered solutions may be acceptable. In the absence of specifications; methods of fabrication are the manufacturer's choice. The design professional, by specifying compliance to these standards increases the probability of receiving the product quality expected.

### ADVISORIES

**EXTERIOR DOORS** - Wood doors are not recommended for exterior use. Most flush doors no longer have extended exterior use warranties and some have no warranty at all. Refer to manufacturers' written warranty for specifics.



Wood doors used in an exterior environment should be water repellent treated at the factory after manufacturing. They should be protected according to manufacturers' requirements, which may include flashing of top, bottom and cut outs.

Additionally, they should be protected from the sun and other weather elements by overhangs, deep recesses, etc.

While wood stile and rail entry doors have performed well for centuries, the selection of a wood door places a burden on the owner to maintain the door by keeping it painted or sealed, protected from moisture, and properly adjusted in the opening. Medium density overlay faced doors are strongly recommended for severe exposure conditions and all surfaces should be primed with an exterior enamel primer, followed by a minimum of two additional coats of exterior enamel.

**CODE and RULE REQUIREMENTS** - The design professional shall be responsible for contract documents which clearly detail products which will comply with local or national applicable codes and rules including, but not limited to: positive pressure requirements and labeling; glass or glazing; prefitting and/or machining for hardware; prehanging and/or machining for weather stripping; priming, sealing and/or transparent finishing; and flashing and/or metal edge guards. The door manufacturer is often a valuable assistant in these matters.

Contract documents shall:

- Specify neutral pressure or positive pressure compliance.
- If positive pressure, specify the category of door: A or B assembly.
- Specify whether the smoke and draft label (S label) is validated or not.

**HIGH PRESSURE DECORATIVE LAMINATES (HPDL) CAUTIONS** - Virtually any high pressure decorative laminate color and texture can be used in the manufacture of architectural doors with the following cautions:

- High gloss and Vertical Grades of decorative laminate will highlight minor core and surface imperfections, often unacceptably.
- Decorative laminate doors are not recommended for use in non climate controlled interior or exterior environment due to the potential differences in lineal expansion between the faces and wood components when exposed to the elements.

**VISION AND LOUVER CUTOUTS** - All cutouts for metal or wood vision panels should be spaced a minimum distance from the edge of the door and/or other cutouts for louvers, locks, closers, or other hardware. Due to various labeling requirements and warranty concerns, consult with your manufacturer to determine minimum requirements.

**LOUVERS** - Generally, fusible link louvers installed in 45, 60, and 90 minute fire rated doors must comply with individual fire door authorities. Wood louvers are not allowed by NFPA 80 in fire rated doors. Due to various labeling requirements and warranty concerns, consult with your manufacturer to determine minimum requirements.

**ACCESSIBILITY** - All doors must comply to accessibility requirements.

# SECTION 9

## Doors

## introductory information

### RECOMMENDATIONS



- **FIELD FINISHED**, include in Division 09 of the specifications:
  - **BEFORE FINISHING**, exposed portions of woodwork shall have handling marks or effects to moisture, removed with a through, final sanding over all surfaces of the exposed portions and shall be cleaned before applying sealer or finish.
- **THOROUGHLY REVIEW** Sections 3 and 4, especially Basic Considerations, Recommendations, Acknowledgements, and Industry Practices within GENERAL for an overview of the characteristics and minimum acceptable requirements of lumber and/or sheet products that might be used herein.
- **STRUCTURAL MEMBERS**, grounds, in wall blocking, backing, furring, brackets, or other anchorage which becomes an integral part of the building's walls, floors, or ceilings, required for the installation of architectural woodwork are not to be furnished or installed by the architectural woodwork manufacturer or installer.
- For an excellent **PAINT GRADE SURFACE** Medium Density Overlay (MDO), Medium Density Fiberboard (MDF) or Hardboard should be specified.
- **WOOD DOORS** should be avoided in exterior applications.
- At **GLASS LIGHTS** - To create the proper seal against weather, wind, and rain, the finish coats on doors should be allowed to flow onto the glass area at least 1/16" (1.6 mm), and:



When cleaning, a razor should not be used to scrape the glass because it will destroy the seal; a broad blade putty knife should be used to protect the seal between the paint and the glass. See illustration below showing the finish lapped on the glass.




Figure: 9-001

### SPECIFICATION CONSIDERATIONS



- **FIRE RATINGS.**
- **CODE or REGULATION** compliance, and
  - If they require certain design accommodations, and it is the responsibility of the design professional to employ such within their door designs and schedule.
- **HARDWARE** such as kick plates, door closers, hinges, panic hardware, locks, etc.
- **PROHIBITION of FINGER JOINTS**, which are otherwise allowed at edges.
- **STILE and RAIL DOORS:**
  - Stile or rail widths and/or construction.
  - Ornamental detail or joinery.
  - Panel layout and grain direction.




Figure: 9-002

### • QUALITY ASSURANCE OPTIONS:

#### Within CANADA

- **AWMAC's GUARANTEE AND INSPECTION SERVICE (GIS)** - See NAAWS's Resources page and/or <http://awmac.com/gis>
- **AWMAC's INSPECTION SERVICE** - See NAAWS's Resources page and/or <http://awmac.com/gis>
- **AWMAC's EXPERT OPINION SERVICE** - See NAAWS's Resources page and/or <http://awmac.com/gis>

#### Within UNITED STATES

- **WI'S AMC BIDDER PRE-QUALIFICATION** - See NAAWS's Resources page and/or <http://woodworkinstitute.com/architectural-resources/quality-assurance>
- **WI'S CERTIFIED COMPLIANCE PROGRAM (CCP)** - See NAAWS's Resources page and/or <http://woodworkinstitute.com/services/certified-compliance-program>
- **WI'S MONITORED COMPLIANCE PROGRAM (MCP)** - See NAAWS's Resources page and/or <http://woodworkinstitute.com/services/monitored-compliance-program/>
- **WI'S CERTIFIED SEISMIC INSTALLATION PROGRAM (CSIP)** - See NAAWS's Resources page and/or <http://woodworkinstitute.com/services/certified-seismic-installation-program/>

# SECTION 9

## Doors

## introductory information

### CONSTRUCTION DEFINITIONS

#### • Wood Face:

- **5-Ply** consists of a center core on which is applied to each side a wood veneer or composite cross band with a face veneer applied over the cross band.
- **7-Ply** consists of a center core on which is applied to each side 3-ply face skins.

#### • HPDL Face:

- **3-Ply** consists of a core with a plastic laminate face applied over both sides of the core.
- **5-Ply** consists of a wood veneer or composite cross band applied over the core before application of the face laminate.

### DOOR CONSTRUCTION CUTAWAY EXAMPLES

Illustrations of grain direction is only applicable to wood veneer.

- **WOOD VENEER FACE** with particleboard, MDF, or agrifiber core (PC-5 / PC-7).




Figure: 9-003

- **HPDL FACE** with particleboard, MDF, or agrifiber core (PC-HPDL-3 / PC-HPDL-5).




Figure: 9-004

- **WOOD VENEER FACE** with staved lumber core (SLC-5 / SLC-7).




Figure: 9-005

- **WOOD VENEER FACE** with structural composite lumber (SCL) core (SCLC-5 / SCLC-7).




Figure: 9-006

- **WOOD VENEER FACE** with fire resistant composite core (FD-5 / FD-7).




Figure: 9-007

- **HPDL** with fire resistant composite core (FD-HPDL).




Figure: 9-008

- **WOOD VENEER/HPDL FACE** with hollow core (HC-7).




Figure: 9-009

# SECTION 9

## Doors

## introductory information

### DOOR SYMBOLS and ABBREVIATIONS

Your door manufacturer is the best source of specific guidance when writing door specifications. The following short list of abbreviations applies to some door companies:

- **ME = Matching edges;** i.e., vertical edges same as decorative faces.
- **CE = Compatible edges;** i.e., vertical edges selected for compatibility with decorative faces.
- **PC = Particleboard, MDF, or agrifiber core,** solid core door with stiles and rails bonded to the core and abrasive planed flat prior to the application of the faces, including:
  - **PC-5** = Core with 2 layers on each side.
  - **PC-7** = Core with 3 layers on each side.
  - **PC-HPDL-3** = Core with laminate to each side.
  - **PC-HPDL-5** = Core with crossband and laminate each side.
- **SCLC = Structural composite lumber core,** solid core door with stiles and rails bonded to the core and abrasive planed flat prior to the application of the faces, including:
  - **SCLC-5** = Core with 2 layers on each side.
  - **SCLC-7** = Core with 3 layers on each side.
  - **SCLC-HPDL-5** = Core with crossband and laminate each side.
- **SLC = Staved lumber core,** solid core door with stiles and rails bonded to the core and abrasive planed flat prior to the application of the faces.
  - **SLC-5** = Core with 2 layers on each side.
  - **SLC-7** = Core with 3 layers on each side.
  - **SLC-HPDL-5** = Core with crossband and laminate each side.
- **FPC = Floating particleboard core,** solid core placed within a stile and rail frame, bonded together by the faces, including:
  - **FPC-5** = Core with 2 layers on each side.
  - **FPC-7** = Core with 3 layers on each side.
- **FSLC = Floating staved lumber core,** solid core placed within a stile and rail frame, bonded together by the faces, including:
  - **FSLC-7** = Core with 3 layers on each side.
- **FD = Fire resistant core,** fire resistant materials assembled to stiles and rails according to methods prescribed by the testing agency based on rigorous smoke, flame, and pressure tests. Labeled fire doors are specified by their resistance ratings:
  - **FD-5** = Core with 2 layers on each side.
  - **FD-7** = Core with 3 layers on each side.
  - **FD-HPDL-3** = Core with laminate to each side.
  - **FD-HPDL-5** = Core with crossband and laminate each side.
- **IHC-7 = Institutional hollow core,** honey comb, ladder, or grid type cores inside stiles and rails, bonded together by the faces.
- **SHC-7 = Standard hollow core,** honey comb, ladder, or grid type cores inside stiles and rails, bonded together by the faces.
- **SR = Sound retardant doors,** specified by their performance characteristics.
- **LL = Lead lined doors,** designed to resist penetration by radiation of various types, and specified by their performance.
- **ES = Electrostatic shielded doors.**
- **BR = Ballistic resistant doors.**

### BASIC CORE TYPES

The design professional or specification writer has the opportunity to select the door core type. In the absence of specification, PC shall be furnished, complying with particleboard standard ANSI A208.1 Particleboard, Grade LD-1 or LD-2 as published by the Composite Panel Association, <http://compositepanel.org>.

The five most common core types are PC, SLC, SCLC, HC, and fire resistant door core, conforming to the minimum requirements of WDMA - I.S. 1-A (latest edition).

Specify one, or a combination of, solid core, hollow core, or fire resistant core, and acoustical, ballistic resistant, or lead lining where and when required. The requirements for each core type are illustrated in Section 9. In the absence of clear specifications, the core shall be of the manufacturer's choice.

SCLC may be specified in any Grade, for:

- **SOLID CORE,** specify one of the following: PC, SLC, or SCLC. When the weight of the door is a design factor, consult the door manufacturer to determine the differences between PC, SLC, and SCLC core types.
- **HOLLOW CORE,** specify the honey comb, with the minimum cell size required, grid core, or ladder construction.
- **FIRE RESISTANT CORE,** required beyond the 20 minute label level, consult your door manufacturer for code compliant core types, blocking options, metal edges, cut outs, and astragals.

# SECTION 9

## Doors

## introductory information

### BASIC CORE TYPES (continued)

The use of SCLC for top and/or bottom rails, and blocking is acceptable. SCLC is proving to have excellent performance characteristics as a replacement for stave core, as it often minimizes or eliminates telegraphing of the lumber blocks through the face veneers or overlays.

When the edge of an SCL core door will be visible after installation, design professionals may wish to specify a fill and paint treatment, or the application of a veneer edgeband to conceal the coarse texture of the edge of the SCL material. It is the responsibility of the design professional to make a selection in the best interests of the client.

### SPECIALITY CORES

Such as fire rated, sound resistant, x-ray, bullet resistant, or electrostatic shielded doors shall be properly specified, including the fire rating, sound class, lead thickness, and/or protection rating.

- At **FIRE RATED** doors, the type of construction, core type, thickness, edgebands, moldings, blocking, and use of intumescent coatings shall be the standard of the door manufacturer, conforming to the labeling authority granted to them by their labeling agency.
- At **SOUND RESISTANT** doors, the type of construction, thickness, edgebanding, applied moldings, special stops, stop adjusters, gaskets, and automatic threshold closing devices shall be the standard of the door manufacturer conforming to the STC (Sound Transmission Class) specified when tested as an opening unit (rather than sealed in place).
- At **X-RAY DOORS**, construction, thickness, edgebands, and moldings shall be of the manufacturer's standard.

- At **BULLET RESISTANT** doors, the type of construction, thickness, edgebands, and moldings shall be of the manufacturer's standard.
- At **ELECTROSTATIC SHIELDED** doors, the type of construction, thickness, edgebands, and moldings shall be of the manufacturer's standard.

Cores other than those enumerated herein are manufactured to individual specifications and are not dealt with in these standards for that reason.

### CORE TO EDGE ASSEMBLY

These standards provide for multiple types of assembly between the core and the vertical and horizontal edges in doors:

- Stiles and rails securely bonded to core, prior to application of faces.
- Stiles and rails **NOT** bonded to core prior to application of faces.
- Stiles and rails placed (not bonded) around hollow core inserts.

### FIRE RATINGS

The Model Codes have established a fire door rating and operating classification system for use in protecting door openings in fire rated wall constructions. Fire doors must meet certain requirements and bear certifying labels of an independent testing agency approved by the building official.

### SPECIAL FUNCTION DOORS

Sound retardant (acoustical), lead lined (X-ray), ballistic resistant, and electrostatic shield doors are manufactured by some companies to meet these special needs. Refer to manufacturer's literature for details.

Transom panels and special function doors are available and should be specified carefully, with particular attention to the meeting edge details, operational functions and accessories, and veneer match options. In the absence of clear and complete specifications, fabrication details will be of the manufacturer's choice.

### VENEER FACES

At stand alone doors with face species of Anigre, Ash, Beech, Birch, Cherry, Hickory, African Mahogany, American Mahogany, Makore, Maple, Red Oak, White Oak, Pecan, Poplar, or Walnut shall conform to the HPVA Door Skin Face tables included within the Materials portion of this section. Doors of a species not listed above shall conform to the HPVA Door Skin Faces as agreed on between buyer and seller.

- Doors adjacent to or that become a component of other architectural woodwork shall conform to the applicable requirements of Section 4.
- Stand alone, Center Balanced Matched doors, shall not have the width of outer leaves after trimming exceed 1" (25.4 mm) less than its adjoining leaf for Custom Grade, or 1/2" (12.7 mm) less than its adjoining leaf for Premium Grade.
- Before specifying, check with the door manufacturer for availability.

Special matching shall be so specified, such as: All doors on the same project are to be manufactured using the same or similar flitches.

Sequence matched face veneers required at pairs or sets of doors and adjacent panels.

# SECTION 9

## Doors

### introductory information

#### veneER FACE GRADE SUMMARY

Refer to Section 4 HPVA Panel Grades and Section 9 HPVA Door Skin Grades for the complete description of veneer face grades.

When veneers are specified as “natural,” they may contain any amount or combination of sapwood and heartwood, with the resultant contrast in color in many species.

The industry recognizes that cost is an important factor, and having lower veneer standards can result in some savings. Specifying Architectural Woodwork Standards Custom Grade meets that need. However, when doors are a part of an overall design scheme and/or are adjacent to other architectural woodwork specified under these standards, the level of quality of those doors must be consistent with other millwork components.

#### SPECIFICATION REQUIREMENTS

The panel face veneer standards of the Hardwood Plywood & Veneer Association HP-1, latest edition, is adopted as the minimum standard for face veneers. Specifiers need to determine and specify the following:

#### veneERS FOR TRANSPARENT FINISHES

- **Species:** There are numerous foreign and domestic species available. Involve your manufacturer early in the design and selection process.
- **Matching:** Many different visual effects can be obtained by face veneer matching.
  - Appearance and layout of individual pieces of veneer.
  - Matching between pieces (leaves) of veneer.

- Orientation of spliced veneer on a door face.
- Appearance of doors in pairs or sets.
- Appearance of doors with transoms.

#### MATERIALS FOR OPAQUE FINISHES

- **Medium Density Overlay, MDF or Hardboard.** These provide the optimum paintable surface for architectural doors.
- **Close Grain Hardwood.** Extra preparation will be required by the finisher as there will be grain show through, open appearing veneer joints, and other wood characteristics when using this product for a painted finish.
- **Manufacturers' option.** Face materials are determined by the manufacturer.

#### DOORS IN PAIRS OR SETS

- **Pair Match** - Two doors hung adjacent may be (and in some Grades, must be) specified as a Pair Match. Note to specifying authority: Specifying Pair Matched only means the two doors are to be considered Pair Matched as per the Grade specified, it does not mean the veneer is sequenced, nor does it designate the veneer cut or layup. The Grade specified will determine the type of Match required. Sequencing, veneer cut and layup if different from the Grade Rules must be specified. The illustration in Figure 9-001 shows flat or plain cut, book matched, center matched faces.




Figure: 9-010

- **Set Match** - Three or more doors or two or more Pair Matched doors hung adjacent may be (and in some Grades, must be) specified as a Set Match. Note to specifying authority: Specifying Set Matched only means the three or more doors are to be considered Set Matched as per the Grade specified, it does not mean the veneer is sequenced, nor does it designate the veneer cut or layup. The Grade specified will determine the type of Match required. Sequencing, veneer cut and layup if different from the Grade Rules must be specified. The illustration in Figure 9-002 shows flat or plain cut, book matched, center matched faces.




Figure: 9-011

- **Doors with Transoms**

The use of the transom increases the apparent height of the door and often enhances the appearance of the opening. The type of match should be specified, and a slight misalignment of veneer grain may occur between the transom and the door. Industry practice allows a variation in grain alignment from side to side. If tighter tolerances are desired, they must be specified.

Grain pattern alignment between the door and transom, even when cut from the same panel, will vary to some extent. This is due to the natural progression of the annual rings which create the figure in the wood. Misalignment will be more apparent in doors veneered with open grain species than with close grain.

# SECTION 9

## Doors

## introductory information

### SPECIFICATION REQUIREMENTS

(continued)

#### DOORS IN PAIRS OR SETS (continued)

- **Continuous Match** - Provides optimum veneer utilization as each single piece of veneer extends from the top of the transom to the bottom of the door. Available veneer length in the species may limit this option.




Figure: 9-012

- **End Match** - A single piece of veneer extends from the bottom to the top of the door with a mirror image at the transom.




Figure: 9-013

- **No Match**




Figure: 9-014

### DOOR EDGE CONSTRUCTION and TYPES

Edge construction is the manufacturer's choice unless specified otherwise.

- **Type - A** - Solid Wood edgeband, face, and cross band edges show.



Figure: 9-015

- **Type - B** - Wood Veneer edgeband, face, and cross band edges covered.



Figure: 9-016

- **Type - C** - HPDL or PVC edgeband, face, and cross band edges covered.



Figure: 9-017

- **Type - D** - Solid Wood edgeband, veneer face edge shows.



Figure: 9-018

- **Type - E** - Solid Wood edgeband, veneer face edge shows.



Figure: 9-019

To **PREVENT TELEGRAPHING**, inset solid wood edging when used must have similar moisture content as panel core, be glued securely and calibrated with panel core thickness prior to being laminated with a wood veneer on both faces.



- **Type - F** - Solid Wood edgeband, face, and cross band edges covered.



Figure: 9-020

# SECTION 9

## Doors

## introductory information

### CONSTRUCTION DETAILS

#### GENERAL MOLDING REQUIREMENTS

- **SPECIES** shall match or be compatible with face veneer or laminate.
- **SPECIFY** transparent or opaque finish.
- **FREE** of open defects, shake, splits, or doze.
- **SMOOTH** and **FREE** of visible knife, saw, or sanding marks.

#### HORIZONTAL or TRANSOM MEETING EDGE OPTIONS




Figure: 9-021




Figure: 9-022

#### MEETING EDGE OPTIONS




Figure: 9-023




Figure: 9-024

#### GLAZING OPTIONS




Figure: 9-025




Figure: 9-026

#### LOUVER OPTIONS




Figure: 9-027

#### FLASHING OPTIONS




Figure: 9-028

If the manufacturer is to flash the top of the door or the bottom edge of cutouts for exterior doors, it must be specified.

#### DUTCH DOOR OPTIONS




Figure: 9-029

# SECTION 9

## Doors

## introductory information

### CONSTRUCTION DETAILS (continued)

#### • BLOCKING OPTIONS

For undercutting flexibility and specialized hardware applications, a number of internal blocking options are available from most manufacturers. When blocking is required it is typically at particle core and fire resistant core doors. There are many options available, consult your manufacturer early in the design process to determine your requirements.




Figure: 9-030

Hardware Blocking, if desired, shall be specified from the following typical options:




Figure: 9-031




Figure: 9-032

Top Blocking may be full or partial width as required by its application.

### HAND and BEVEL OF DOORS

The "hand" of a door is always determined from the outside. The outside of an exterior door is the street or entrance (key) side. The outside of an interior room or auditorium door is the corridor or hall (key or imaginary key) side. The outside of a closet door is the side opposite the closet; the room, corridor or hall side. The outside of a single communicating door is the side from which the butts are invisible when the door is closed. The outside of twin communicating doors is the space between the two doors.

Standard handed doors push away from the person standing on the outside/key side. Reverse handed doors pull toward the person standing on the outside/key side.




Figure: 9-033

### FACTORY FINISHING (when specified)

Firms differ in the variety of factory finishes offered. Some finishes may not be available from all manufacturers. Finishes protect wood from moisture, handling, or harsh chemicals. The sooner moisture is restricted from entering or leaving, the longer wood lasts and the finer it looks. Transparent finishes without stain provide a protective coating for the wood, maintaining its natural look. Transparent finishes with stain provide the architect or designer an opportunity to create a striking visual effect by modifying color, texture, and sheen.

Section 5 defines the finishing systems and performance characteristics.

Carefully studying Section 5 with your manufacturer early in the design phase can result in both high quality and cost savings.

Factory finishing is generally specified when a project requires high quality performance and superior appearance.

Factory finishing offers many benefits, including:

- State of the art equipment in a well lighted, dust free environment (conditions normally not available in the field), which provides uniform color, texture, and sheen.
- Proper sanding prior to the application of stains and finishes. Field conditions often hinder surface preparation resulting in a lack of clarity and uniformity in finish and color.
- Protection from unfavorable relative humidity conditions at the earliest possible time.
- Cost savings (in most cases) over the total cost of field applied finishes by a separate contractor.
- Shorter installation time on the job site, resulting in faster project completion.

# SECTION 9

## Doors

## introductory information

### STILE and RAIL DOOR COMPONENTS

- **STILES** - are the vertical outside members. They may be solid wood or veneered. Stiles usually have solid sticking (solid stuck, solid molded). Sticking is usually of three profiles: "ovolo", "ogee" or "quarter round". Other profiles may be used. The stiles are ploughed or grooved along the edge to receive the panels, rails, and/or glass. If the door is to be assembled by dowelled construction, the stiles are bored to receive the dowels. If the door is to be assembled by lag screw construction, the stiles shall be solid hardwood lumber. The stiles will contain much of the hardware for the door, and must be sized and fabricated to fit the intended hardware, locks, and latches.
- **RAILS** - are the cross or horizontal members of the door. They may be solid wood or veneered. Rails are coped on both ends to fit the sticking of the stile. Tenons or dowels are machined into the rails to fit mortises or dowel boring in the stiles.
  - **Top and bottom rails** are required, with the addition of intermediate cross rails or lock rails as appropriate. The bottom rail is usually the widest of the members, made of edge glued lumber or veneered, depending on the door construction. The top rail is often the same face dimension as the stiles.
  - **Lock rail**, if there is one, is usually a wide member located at lock height. In the case of narrow stiles or large hardware, this rail serves to house the lock and latch mechanisms.

- **MULLIONS** - an upright or vertical member between panels. It is similar to a cross rail in the way it is fit and machined.
- **PANELS** - are either solid lumber or panel products that fill the frame formed by the stiles, rails, and mullions. When the figure of the wood is visible in the finished product, the grain direction of the panels usually runs vertically.
- **MUNTINS and BARS** - Stile and rail door with glass panels often utilize muntins and bars, which are smaller in section than mullions. A bar is a rabbeted molding, which extends the total height or width of the glass opening. A muntin is a short bar, either horizontal or vertical, extending from a full bar to a stile, rail, or another bar. Muntins and bars are traditionally coped and mortised joinery.

### STILE and RAIL DOOR DESIGN

Custom stile and rail door design offer many opportunities for creativity and choice. Some of the variables include:

- Panel layout.
- Grain patterns and relationships.
- Stile and rail construction.
- Molding details.
- Panel construction.
- Joinery techniques.

Selection among these variables requires some knowledge of their relative performance characteristics. The following drawings illustrate some of the options. Many manufacturers feel veneered and laminated constructions offer the lowest risk of warp for most species of wood. Consult your manufacturer early in the design process for assistance in making selections.

The strength of a stile and rail door is primarily dependent on the shoulders and joints between the stiles and rails. A wide bottom rail will increase significantly the strength and stability of a door far beyond that of a narrow rail.

Care should be taken to ensure that the design of a door's stiles and rails is large enough to structurally accommodate the intended hardware, provide a strong and stable door, and accommodate the usage and size of the opening.

Door panels of either flush/flat or raised design are typically of the same species as the stiles and rails.

### STILE and RAIL DOOR JOINERY EXAMPLES

- **Haunched Mortise and Tenon**




Figure: 9-034

- **Slot Mortise and Tenon**




Figure: 9-035

- **Loose Tenon**




Figure: 9-036

- **Dowel**





Figure: 9-037

# SECTION 9

## Doors

### introductory information

#### STICKING PROFILES EXAMPLE



#### THICKNESS

Stile and rail doors are usually 1-3/4" (44 mm) thick. For doors over 3'-6" (1067 mm) in width or 8'-0" (2440 mm) in height, it is recommended they be 2 1/4" (57 mm) minimum thickness.

#### GRAIN DIRECTION and LAYOUT

Traditionally, the grain direction flows with the longest dimension of the stile or rail. Panel grain typically runs vertical; however, it can be altered for design purposes. If raised panels are to be rim-raised veneered construction, the grain of the rims will flow around the panel with the long dimension of the rim material.

There are a variety of methods of stile and rail fabrication. It is possible to fabricate stile and rail doors that will perform within the tests established in this Standard using any of the illustrated techniques and others. The illustrations are intended as guidelines for the design professional and should not limit the potential for creative solutions. Glass cannot always be centered on stiles and rails, depending on the thickness. Moldings and stop are usually applied with small brads or finish nails.

#### STILE and RAIL DOOR PANEL LAYOUT and GRAIN PATTERN EXAMPLES




Figure: 9-039

#### STILE and RAIL DOOR CONSTRUCTION EXAMPLES




Figure: 9-040

# SECTION 9

## Doors

### introductory information

#### STILE and RAIL PANEL CONSTRUCTION EXAMPLES




Figure: 9-041

#### STILE and RAIL PANEL and GLASS RETENTION EXAMPLES




Figure: 9-042

### ANTIMICROBIAL SURFACES

There is increasing availability of antimicrobial products, including solid surface and HPDL. It is important to understand that regardless of the methodology used to create the antimicrobial surface there are two significantly different types of claims regarding such antimicrobial products. Common terminology refers to these:

- **Within the United States as:**
  - **Treated Article Claim** - Which the US Environmental Protection Agency (EPA), <http://epa.gov>, classifies as a “treated article exemption”, typically referring to items that are treated with antimicrobial pesticide to protect the item itself, not the public. Such exemption will be absent any EPA registration number and is granted for non-public health use.
  - **Public Health Claim** - Which the EPA classifies as “EPA registered products which have been shown, using EPA testing protocols, to demonstrate efficacy in the installed format. Such test protocol requires an efficacy of killing 99.9% of all bacteria, fungi and viruses within two hours.
- **Within Canada as:**
  - **Disinfectant Drugs** - Which Health Canada, <http://hc-sc.gc.ca>, classifies as a non market authorized claim, lacking a Drug Identification Number (DIN).
  - **Hard Surface Disinfectants** - Which Health Canada classifies as having received “Market Authorization” when such have been granted a Drug Identification Number (DIN).

### NONTRADITIONAL MATERIALS

Covers materials re-purposed from other industrial and manufacturing areas, but assigned to the woodwork manufacturer and treated similarly to traditional millwork items like wall paneling. From a design perspective considerations of appearance, color, finish, variation and relation are deemed important as they would be with traditional wood products.

Examples of non-traditional materials could be a fiber/cement panel designed for fire resistance, insulation re purposed as a decorative panel, metal products, cloth, acrylics, etc.

Because these materials are unique, contract documents, shall clearly indicate or delineate all of the necessary material, fabrication, installation and building code/regulation direction and requirements as may be applicable for the manufacturer/installer to reasonably accomplish the intended design concept.

### RECLAIMED or RECYCLED WOOD

#### DESIGN PROFESSIONAL RESPONSIBILITY

Use of unique materials like reclaimed or recycled wood requires a more active role of the design professional in sourcing and pre-approving desired material selections. There are no traditional guidelines with these types of materials to assure either the woodwork manufacturer or the design professional of achieving an intended result. There will be situations where the design professional will be required to directly participate in the individual piecemeal selection and layout process of the product.

**CONTRACT DOCUMENTS**, shall clearly indicate or delineate all material, fabrication, installation and applicable building code/regulation requirements with the clear understanding that incomplete design choices, changes in scope or material selection, lack of material selection, or design choices made after initial bid may impact the cost or not be possible.

The contract documents shall specifically list the material source and identifier, and address the allowable:

- Variation in color or tone, grain, distress, character, and patina.
- Defects, such as nail/bolt holes, checking, cracking, discoloration, milling marks, roughness in terms of quantity, locations, repetition, etc.
- Distortion in terms of straightness, cupping, flatness, etc.

See SECTION 3 for additional information.

### DESIGN RESOURCES

Is a perpetually expanding, web based resource of pictures, videos, illustrations, ideas and design concepts for inspiring thought and design creativity - assessable at: <http://naaws-design-resources.com>



Relative to this Section, offerings will include:

- Flush Door Configurations
- Stile & Rail Door Illustrations

# SECTION 9

## Doors

### GENERAL/PRODUCT/INSTALLATION/TEST

Where the **C**, or **P** icon is not indicated,  
the rule applies to all Grades equally



## compliance requirements

### INCLUDING: Passage Doors of Flush and Stile & Rail Construction with Wood and HPDL Faces

#### 9.1 BASIC CONSIDERATIONS

##### 1 GRADES

1.1 These Standards are characterized in three Grades of quality that may be mixed within a single project; however, only Custom and Premium are used in this door Section. Limitless design possibilities and a wide variety of lumber and veneer species, along with overlays, high-pressure decorative laminates, factory finishes, and profiles are available in both Grades.

1.2 **CUSTOM GRADE** is typically specified for and adequately covers most high-quality architectural woodworking, providing a well-defined degree of control over a project's quality of materials, workmanship, or installation.

1.3 **PREMIUM GRADE** is typically specified for use in those areas of a project where the highest level of quality, materials, workmanship, and installation is required.

1.4 **EXCLUSION**, these standards do not cover the re-lamination/re-surfacing of flush doors with decorative laminate or other surfacing.

##### 1.5 GRADE LIMITATIONS:

1.5.1 Flush and Stile & Rail doors are offered only in Custom and Premium grades.

2 **CONTRACT DOCUMENTS** shall govern if in conflict with these standards.

3 **ACCEPTABLE REQUIREMENTS** of lumber and/or sheet products used within this woodworking product section are established by Sections 3 and 4, unless otherwise modified herein.

4 **AESTHETIC COMPLIANCE REQUIREMENTS** apply only to surfaces visible after fabrication and installation.

4.1 Shall be judged from a normal viewing stance and considered compliant if inconspicuous when viewed from:

4.1.1 72" (1830 mm) for Economy Grade

4.1.2 48" (1219 mm) for Custom Grade

4.1.3 24" (610 mm) for Premium Grade

#### 9.1 BASIC CONSIDERATIONS (continued)

4.2 For **RECLAIMED** or **RECYCLED WOOD**, the aesthetic compliance requirements of NAAWS does not apply, such shall be as agreed between owner/design professional and the woodwork manufacturer/installer.

4.3 For **NON-TRADITIONAL MATERIALS**, the aesthetic compliance requirements of NAAWS does not apply, such shall be as agreed between owner/design professional and the woodwork manufacturer/installer.

5 Use of **PHENOLIC-BACKED WOOD VENEER** is permitted, if specified or otherwise approved.

6 **EXPOSED SURFACES** include:

6.1 Both visible faces of doors, including applied moldings, lights, and louvers.

6.2 Both vertical edges of doors.

6.3 Top edge, if visible from above.

7 **SEMI-EXPOSED SURFACES** include:

7.1 Top and bottom edges of doors, unless:

7.1.1 The top edge is visible from above.

8 **NFPA 80** requires design accommodations, and:

8.1 Preparation of **FIRE-RATED DOOR ASSEMBLIES** for locks, latches, hinges, remotely operated or monitored hardware, concealed closers, glass lights, vision panels, louvers, astragals, and laminated overlays shall be performed by the manufacturer or its agent in conformance with the manufacturer's **LICENSING** and **LABEL SERVICE AGREEMENT**.

8.2 Preparation of **SURFACE-APPLIED** hardware, function holes for mortise locks, holes for labeled viewers, allowable undercutting, and application of protection plates may be performed at the jobsite.

8.3 Fire-rated wood doors to be glazed under license.

9 **FIRE-RATED DOORS:**

9.1 Are **AVAILABLE** in 20, 45, 60, and 90 minute labels.

9.2 Shall be of **CONSTRUCTION STANDARD** to the door manufacturer and conform with the requirements of applicable labeling agencies.

# SECTION 9

## Doors

### GENERAL/PRODUCT/INSTALLATION/TEST

Where the **C**, or **P** icon is not indicated, the rule applies to all Grades equally



### compliance requirements

#### 9.1 BASIC CONSIDERATIONS (continued)

- 9 **FIRE-RATED DOORS** (continued)
- 9.3 Shall permit **EDGES** on 20, 45, 60, and 90 minute fire-rated doors, regardless of the species of material on the door face and be the standard of the door manufacturer; and the species, width, and fire-retardant treatment shall conform to the requirements of the labeling agency acceptable to the authority with jurisdiction for the label specified.
- 9.4 **HANGING** shall be compliant with the manufacturer's requirements.
- 10 Specific **METHODS OF CONSTRUCTION** for flush, excluding hollow core, and stile and rail doors illustrated in this section may not represent all types available. Variations of construction and materials are permitted, as long as the appropriate minimum WDMA duty performance levels are met or exceeded.
- 11 **ANSI/WDMA I.S. 1A (latest edition) PERFORMANCE DUTY LEVELS.**
- 11.1 **HEAVY DUTY** performance level has been adopted for these Standards.
- 11.1.1 The heavy duty level typically involves doors for moderate usage and requires intermediate minimum performance standards.
- 11.1.2 Typical usage examples:
- |                                     |                       |
|-------------------------------------|-----------------------|
| Assisted living room entry          | Storage               |
| Office - Interior passage stairwell | Apartment/condo entry |
| Mechanical service                  | X-ray                 |
| Hallway                             | Acoustic              |
| Medical exam room                   | Stairwell             |
- 11.1.3 If a higher or lower Performance Duty Level is desired, it shall be so specified.
- 11.2 **EXTRA HEAVY DUTY** level typically involves doors where use is considered heavy and frequent, and requires the highest minimum performance standards.
- 11.2.1 Typical usage examples:
- |                    |                        |
|--------------------|------------------------|
| Classrooms         | Detention/correctional |
| Patient rooms      | Bullet-resistant       |
| Bathrooms - Public | Gym/locker rooms       |
| Dorm rooms         | Surgical entry         |
| Assembly areas     | Trauma centers         |
| Auditorium entry   | Hotel/motel room entry |

#### 9.1 BASIC CONSIDERATIONS (continued)

- 11.3 **STANDARD DUTY** level typically involves doors where frequency of use is low and requires the lowest minimum performance.
- Typical usage examples:
- |          |                         |
|----------|-------------------------|
| Closet   | Bath - Private          |
| Wardrobe | Small, low-usage office |
- 11.4 **DUTY LEVEL** performance requirements are spelled out within the Product portion of this Section.
- 12 **TYPICAL STILE and RAIL DOOR ILLUSTRATIONS** are provided in **DESIGN RESOURCES**. 
- 13 To **PREVENT TELEGRAPHING**, inset solid wood edging when used must have similar moisture content as panel core, be glued securely and calibrated with panel core thickness prior to being laminated with a wood veneer on both faces.
- 14 **INDUSTRY PRACTICES**
- 14.1 **STRUCTURAL MEMBERS**, grounds, in wall blocking, backing, furring, brackets, or other anchorage that becomes an integral part of the building's walls, floors, or ceilings, that are required for the installation of architectural woodwork are not furnished or installed by the architectural woodwork manufacturer or installer.
- 14.2 **WALL, CEILING, and/or opening** variations in excess of 1/4" (6.4 mm) or **FLOORS** in excess of 1/2" (12.7 mm) in 144" (3658 mm) of being plumb, level, flat, straight, square, or of the correct size are not acceptable for the installation of architectural woodwork, nor is it the responsibility of the installer to scribe or fit to tolerances in excess of such.
- 14.3 **WARRANTY** shall be to the terms, conditions, and duration of the door manufacturer, unless specified otherwise. Check with individual door manufacturers for warranty and fire approval requirements.
- 14.3.1 **Warranties** vary between manufacturers-as to the:
- 14.3.1.1 Coverage.
- 14.3.1.2 Duration.

# SECTION 9

## Doors

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **C**, or **P** icon is not indicated, the rule applies to all Grades equally



## compliance requirements

### 9.1 BASIC CONSIDERATIONS (Continued)

#### 14 INDUSTRY PRACTICES (Continued)


- 14.3.1.3 Items and conditions that void it.
- 14.3.1.4 Extent of replacement and cost coverage.
- 14.3.2 **MANUFACTURERS**, typically do not warranty doors with:
  - 14.3.2.1 Different Species, face materials, finishes, or laminates on opposite sides.
  - 14.3.2.2 Different temperature and/or humidity conditions on opposite sides.
  - 14.3.2.3 **LESS THAN 5"** (127 mm) between cutouts or a cutout and the edge of a door, or:
  - 14.3.2.4 **LESS THAN 6"** (152.4 mm) at fire-rated doors between cutouts or a cutout and the edge of a door, unless approved by authorities with jurisdiction.



#### 14 INDUSTRY PRACTICES (continued)


14.4 **HANDING** of a door is always determined from the outside:

14.4.1 The key side is as symbolized below:




Left-Hand

Figure: 9-043




Right-Hand

Figure: 9-044



Left-Hand Reversed

Figure: 9-045



Right-Hand Reversed

Figure: 9-046

Bottom Of Drawings Represent Outside.

# SECTION 9

## Doors

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **C**, or **P** icon is not indicated, the rule applies to all Grades equally



# compliance requirements

### 9.2 SCOPE

- 1 All flush and stile and rail wood doors with corresponding and adjacent transoms, fixed panels, and/or side lights.
- 2 **TYPICAL INCLUSIONS:**
  - 2.1 Flush doors, solid, hollow, fire rated, sound resistant, x-ray, or bullet resistant.
  - 2.2 Stile and rail doors of veneered, solid, and/or laminated (solid) construction with or without fire, sound, or bullet resistant ratings.
  - 2.3 Accessories required to comply with the door manufacturer's fire rated door approval, including treated or metal edges at pairs of fire rated doors as required.
  - 2.4 Accessories required to comply with the door manufacturer's sound resistant certification, including gaskets and automatic door bottoms.
  - 2.5 Glass stops.
  - 2.6 Wood louvers.
  - 2.7 **IF SPECIFIED:**
    - 2.7.1 Glass or glazing.
    - 2.7.2 Pre fitting and machining for hardware.
    - 2.7.3 Pre hanging and machining for weather stripping.
    - 2.7.4 Priming, sealing, and/or finishing.
    - 2.7.5 Flashing and/or metal edge guards.
- 3 **TYPICAL EXCLUSIONS:**
  - 3.1 Cabinet doors included with casework.
  - 3.2 Wood cores for metal or vinyl clad doors.
  - 3.3 Garage, metal, and fiberglass doors.
  - 3.4 Access doors.
  - 3.5 Metal grills or louvers.
  - 3.6 LPDL or vinyl faced doors.

### 9.3 DEFAULT STIPULATION

- 1 If not otherwise specified or indicated in the contract documents, work shall be **CUSTOM GRADE**, solid core, with paint grade faces and edges. 
- 1.1 Core selection is manufacturer's choice.
- 1.2 If transparent finish is specified, doors shall be factory clear finished.

### 9.4 RULES

- 1 The following rules shall govern unless a project's contract documents require otherwise.
- 2 These rules are intended to provide a well defined degree of control over a project's quality of materials, workmanship, or installation.
- 3 **ERRATA**, published at <http://naaws-errata.com>, shall take precedence over these rules, subject to their date of posting and a project's bid date. 

#### 9.4.4 Basic General Rules

- 1 These standards are primarily performance based rather than prescriptive based, allowing a wide variance of construction methods and/or component configurations, provided the end product meets or exceeds **WDMA's HEAVY DUTY PERFORMANCE VALUES** contained within these standards, and:
  - 1 1 **FLUSH SOLID CORE**, fire rated, sound resistant, bullet resistant, lead lined, and electrostatic shielded doors - ANSI/WDMA I.S. - 1A, (latest edition), **EXCEPT** as **MODIFIED HEREIN**.
  - 1 2 **FLUSH HOLLOW CORE** doors shall comply with WDMA's Standard Duty performance values.
  - 1 3 For **STILE** and **RAIL** doors with or without fire, sound, or bullet resistant ratings - ANSI/WDMA I.S. - 6A, (latest edition), **EXCEPT AS MODIFIED HEREIN**.
  - 1 4 It is the **RESPONSIBILITY** of the door manufacturer to provide evidence of compliance upon request.

Continues next column ▼

# SECTION 9


## Doors

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **C**, or **P** icon is not indicated, the rule applies to all Grades equally

**C P**

# compliance requirements

9.4.4		Basic General Rules
▲ From previous column		
IN LIEU OF TESTING for WDMA TM-7 (Slam Cycle) & 8 (Hinge Loading), compliance to the following prescriptive requirements is acceptable:		
2	1	Composite cross bands shall have minimum 55 lbs (24.9 kgs) density.
2	2	FACES on both sides of the door shall be of the same material and construction detail.
2	3	FLUSH VENEERED, solid core door shall include:
2	3	1 Bonded (stiles and rails securely glued to core) construction.
2	3	2 Core shall be SCLC, SLC, particleboard, MDF, or agrifiber core conforming to ANSI A208.1 Grade LD-1 or LD-2.
2	3	3 Stiles and rails with minimum of 1" (25.4 mm) hardwood or material that has been qualified in accordance with WDMA TM 15 (latest edition).
2	3	4 Blocking for screw attached hardware, and:
2	3	4 1 Blocking is not required at SCLC or SLC.
2	3	5 Calibration (sanding) of core to uniform thickness.
2	3	6 For OPAQUE FINISH:
2	3	6 1 Composite face requires minimum 3 ply construction.
2	3	6 2 Veneer face requires minimum 5 ply construction.
2	3	7 For TRANSPARENT FINISH:
2	3	7 1 Minimum 5 ply construction.
2	3	7 2 When veneer is applied to solid wood edge, cross band shall not be set back greater than 1/4" (6.4 mm) from door edge.
		
2	3	8 For HPDL, minimum 5 ply construction including HPDL Faces.
2	4	STILE and RAIL doors with or without fire, sound, or bullet resistant ratings shall:
2	4	1 Be of solid lumber, SCL, LVL, or staved block core construction, with:
2	4	1 1 A minimum of 5/8" (15.9 mm) hardwood edgebands and lock and hinge edges, if not solid lumber.
Continues next column ▼		

9.4.4		Basic General Rules
▲ From previous column		
2	IN LIEU OF TESTING (continued)	
2	4	STILE and RAIL doors (continued)
2	4	2 Be a minimum of 5" (127 mm) wide stiles, top and intermediate rails.
2	4	3 Be a minimum of 10" (255 mm) wide bottom rail.
2	4	4 Be of dowel, mortise, and tenon joinery, and:
2	4	4 1 Dowels shall be a minimum of 1/2" (12.7 mm) in diameter by 5" (127 mm) long, spaced a maximum of 2-1/2" (63.5 mm) on center.
2	4	4 2 Top and intermediate rails shall have a minimum of two dowels per joint; and the bottom rail, a minimum of three per joint.
2	4	5 Have flat or raised panels a minimum of 5/8" (15.9 mm) in thickness at the tongue of solid lumber or M2 Grade particleboard.
3	AESTHETIC GRADE RULES apply only to the faces visible after installation.	
4	LUMBER shall conform to the requirements established in Section 3, and:	
4	1	HEARTWOOD or SAPWOOD is permitted in Ash, Birch, Maple, Cherry, Elm, and Red Oak; however:
4	1	1 If only HEARTWOOD or SAPWOOD is desired, it shall be so specified.
5	SHEET PRODUCTS shall conform to the requirements established in Section 4, and:	
5	1	Use of HPDL BACKED WOOD VENEERS is permitted if specified or otherwise approved.
6	EXPOSED SURFACES INCLUDE:	
6	1	Both visible faces of doors, including applied moldings, lights, and louvers.
6	2	Both vertical edges of doors.
6	3	Top edge, if visible from above.
7	SEMI-EXPOSED SURFACES INCLUDE:	
7	1	Top and bottom edges of doors, unless:
7	1	1 Top edge is visible from above.
Continues next column ▼		

# SECTION 9

## Doors

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **C**, or **P** icon is not indicated, the rule applies to all Grades equally

**C P**

# compliance requirements

9.4.4 Basic General Rules	
▲ From previous column	
8	GLUING or LAMINATION shall be in accordance with the ADHESIVE GUIDELINES within the APPENDIX, and: <span style="float: right; border: 1px solid green; padding: 2px;">a</span>
8 1	DELAMINATION or SEPARATION shall not occur.
8 2	LUMBER shall conform to the requirements established in Section 3.
8 3	SHEET PRODUCTS shall conform to the requirements established in Section 4.
9 For the purpose of this standard, a BALANCED PANEL is one that is free from warp that affects serviceability for its intended purpose.	
10 CATHEDRAL type figure shall be achieved by:	
10 1	A single component in "AA" Face Grade.
10 2	The split heart method in Face Grades "A - D", and:
10 2 1	Each half of a split heart shall be subject to the minimum component width requirements for Face Grade "B".
11 FIRE RATED doors shall be:	
11 1	Of the fire rating specified.
11 2	Constructed to the manufacturer's standard, conforming with the requirements of their applicable labeling service, with:
11 3 1	EDGES, regardless of face species, must conform to the manufacturer's approved labeling service.
11 4	PREPARED, in accordance with NFPA 80, for locks, latches, hinges, remotely operated or monitored hardware, concealed closures, glass lights, vision panels, louvers, astragals, and laminated overlays to be performed in conformance with the manufacturer's licensing and label service agreement; however:
11 4 1	Preparation for surface applied hardware, function holes for mortise locks, holes for labeled viewers, a maximum of 3/4" (19 mm) wood and composite door undercutting, and protection plates may be performed at the jobsite.
11 5	Furnished with the MANUFACTURER'S basic hanging and finishing instructions.
Continues next column ▼	

9.4.4 Basic General Rules	
▲ From previous column	
12 SOUND RESISTANT doors shall:	
12 1	Be constructed to the manufacturer's standard, conforming to the requirements for a minimum STC 50 (Sound Transmission Class) or as specified when tested as an opening unit (versus sealed in place), and:
12 2 1	Include required special stops, stop adjusters, gaskets, and automatic threshold closing devices of the manufacturer's standard.
13 X-RAY doors shall be:	
13 1	Constructed to the manufacturer's standard for the type of construction, thickness, edgebands, and moldings, and:
13 1 1	LEAD thickness shall be a minimum of 1/16" (1.6 mm) or as specified.
14 BULLET RESISTANT doors shall be:	
14 1	Constructed to the manufacturer's standard, conforming to the requirements of UL 752 "Bullet Resisting Equipment" or NIJ (National Institute of Justice) 0108.01 Performance Standards, and:
14 1 1	Have a minimum NIJ Level 2 protection rating.
15 ELECTROSTATIC SHIELDED doors shall be:	
15 1	Constructed to the manufacturer's standard for type of construction, thickness, edgebands, and moldings, and:
15 1 1	Have the number and location of electrical leads as specified.
16 PAIR and SET MATCHING is required for flush wood veneer, and shall be:	
16 1	COMPATIBLE for COLOR and GRAIN. <span style="float: right;">C P</span>
16 2	SEQUENCED and WELL MATCHED for COLOR and GRAIN. <span style="float: right;">C P</span>
17 PAIR and SET MATCHING cannot be achieved at STILE and RAIL and is not required.	
18 EXPOSED FACES and EDGES shall be thoroughly sanded using a minimum of 120 grit sandpaper, and:	
18 1	All EDGES shall be slightly eased.
Continues next column ▼	

# SECTION 9

## Doors

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **C**, or **P** icon is not indicated, the rule applies to all Grades equally



## compliance requirements

9.4.4		Basic General Rules	
▲ From previous column			
19		Overall <b>DOOR SIZE</b> for:	
19 1		<b>NON PREFIT DOORS</b> (blank) shall be furnished within plus or minus of 1/16" (1.6 mm) for <b>HEIGHT, WIDTH, and THICKNESS</b> .	
19 2		<b>PREFIT DOORS</b> shall be furnished, sized in:	
19 2 1		<b>WIDTH</b> within 1/32" (0.8 mm) plus or minus of the specified <b>FRAME</b> size, less 1/4" (6.4 mm) in width with a 3 degree bevel on both edges.	
19 2 2		<b>HEIGHT</b> , within 1/16" (1.6 mm), plus or minus the specified size less the undercut.	
20		<b>BLEED THROUGH</b> of glue at a veneer joint that visually affects an applied finish is not permitted.	
21		<b>CUTOUTS</b> at <b>HPDL</b> shall have a minimum 1/4" (6.4 mm) radius at inside corners.	
22		<b>GLASS</b> and <b>GLAZING</b> requires:	
22 1		Wood glass stops to be manufacturer prepared and bundled in appropriately labeled sets or prefit and tacked in the appropriate light opening, and:	
22 1 1		In the absence of specifications or detail, profile shall be manufacturer's choice.	
23		<b>FACTORY FINISHED, DOORS</b> require both faces and vertical edges to be finished, and:	
23 1		The top/bottom edges and hardware preparation to the top/bottom shall be sealed.	
24		If <b>ANTIMICROBIAL SURFACE</b> is required, it shall be:	
24 1		Within the United States, EPA, <a href="http://epa.gov">http://epa.gov</a> , registered for public health use.	
24 2		Within Canada, Health Canada, <a href="http://hc-sc.gc.ca">http://hc-sc.gc.ca</a> , recognized as having market authorization because of its granted Drug Identification Number (DIN).	
25		<b>FIRST CLASS WORKMANSHIP</b> is required in compliance with these standards. 	

9.4.5		Basic Material Rules	
1		Shall be free of <b>DEFECTS</b> , both natural and from manufacturing, in excess of those permitted herein.	
2		<b>FIGURE</b> (including no figure) is not a function of a species grade, and special requirements must be specified.	
3		<b>HARDBOARD</b> faces shall be standard grade, a minimum of 1/8" (3.2 mm) in thickness.	
4		<b>EXPOSED</b> surfaces shall be:	
4 1		Compatible for color and grain.	<b>C</b> <b>P</b>
4 2		Well matched for color and grain.	<b>C</b> <b>P</b>
5		<b>CONCEALED</b> surfaces shall allow non structural defects and voids; blocking may be of a compatible species or material other than that of the exposed or semi-exposed surface.	
6		<b>At FLUSH</b> doors:	
6 1		<b>VENEER FACES</b> shall be of the species and Grade specified and of sufficient thickness so as not to permit show through of cross banding after sanding and/or final finishing.	
6 1 1		<b>OPAQUE</b> finish shall be:	
6 1 1 1		Sound close grain hardwood veneer, MDO, MDF or hardboard at manufacturer's choice, and:	<b>C</b> <b>P</b>
6 1 1 1 1		If veneer, it shall be:	
6 1 1 1 1 1		HPVA "C" Grade.	<b>C</b> <b>P</b>
6 1 1 1 1 2		HPVA "B" Grade.	<b>C</b> <b>P</b>
6 1 1 2		MDO, MDF or hardboard, at manufacturer's choice.	<b>C</b> <b>P</b>
6 1 2		<b>TRANSPARENT</b> finish requires:	
6 1 2 1		Pairs or sets be compatible for color and grain.	<b>C</b> <b>P</b>
6 1 2 2		Transoms be end matched for color and grain.	<b>C</b> <b>P</b>
6 1 2 3		Pairs or sets be sequenced and well matched for color and grain.	<b>C</b> <b>P</b>
6 1 2 4		Transoms be continuous match for color and grain.	<b>C</b> <b>P</b>
6 1 2 5		<b>COMPATIBILITY</b> in color and grain to the other door faces in the same room or area, and:	
6 1 2 5 1		Coordination of compatibility is the responsibility of the door furnisher.	<b>C</b> <b>P</b>
Continues next column ▼			

# SECTION 9

## Doors

GENERAL/**PRODUCT**/INSTALLATION/TEST

Where the **C**, or **P** icon is not indicated, the rule applies to all Grades equally

**C P**

## compliance requirements

9.4.5 Basic Material Rules					
▲ From previous column					
6					At FLUSH doors (continued)
6	1				VENEER FACES shall (continued)
6	1	2			TRANSPARENT (continued)
6	1	2	6		Doors that are specified as adjacent to or are specified as a component of other architectural woodwork shall conform to the applicable requirements of Section 4 and 8 for the Grade specified.
6	1	2	7		Shall be HPVA "A" Grade, with: <b>C P</b>
6	1	2	7	1	Running match and end component less than the HPVA requirement. <b>C P</b>
6	1	2	8		Shall be HPVA "AA" Grade, with: <b>C P</b>
6	1	2	8	1	Balanced center matched. <b>C P</b>
6	1	2	9		Have visible edges and reveals, when appropriate, that are:
6	1	2	9	1	Matched to species of face, except:
6	1	2	9	1	1 Maple may be used as an alternate when a Birch face is specified.
6	1	2	9	2	Compatible for color and grain. <b>C P</b>
6	1	2	9	3	Well matched for color and grain. <b>C P</b>
6	1	2	9	4	A minimum of 0.020" (0.5 mm) nominal <b>THICKNESS</b> that precludes show through of core.
6	1	2	10		<b>STAND ALONE</b> doors, face species of Anigre, Ash, Beech, Birch, Cherry, Hickory, African Mahogany, American Mahogany, Makore, Maple, Red Oak, White Oak, Pecan, Poplar, or Walnut shall conform to the following <b>HPVA DOOR SKIN FACE TABLES</b> for the allowable veneer characteristics for the Grade required, and:
6	1	2	10	1	If not of a species listed above shall conform to HPVA Door Skin Face Table as agreed on between the design professional and the manufacturer.
6	1	2	10	2	Including those in pairs and sets.
6	1	2	10	3	<b>MATCHING WITHIN A DOOR FACE</b> shall be:
6	1	2	10	3	1 Running match <b>C P</b>
6	1	2	10	2	2 Center balanced match with the width of outer leaves after trimming not exceeding 1" (25.4 mm) less than its adjoining leaf. <b>C P</b>
Continues next column ▼					

9.4.5 Basic Material Rules					
▲ From previous column					
6					At FLUSH doors (continued)
6	1				VENEER FACES shall (continued)
6	1	2			TRANSPARENT (continued)
6	1	2	10		<b>STAND ALONE</b> doors (continued)
6	1	2	10	5	Table: 9-047 - <b>ASH, BEECH</b> (American or European), <b>BIRCH, MAPLE, and POPLAR.</b>
6	1	2	10	6	Table: 9-048 - <b>MAHOGANY</b> (African or American), <b>ANIGRE, MAKORE, and SAPELE.</b>
6	1	2	10	7	Table: 9-049 - <b>RED OAK</b> and <b>WHITE OAK.</b>
6	1	2	10	8	Table: 9-050 - <b>PECAN</b> and <b>HICKORY.</b>
6	1	2	10	9	Table: 9-051 - <b>WALNUT</b> and <b>CHERRY.</b>
Continues next column ▼					

# SECTION 9

## Doors

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **C**, or **P** icon is not indicated, the rule applies to all Grades equally



## compliance requirements

Table: 9-047 - **ASH, BEECH** <sup>(b)</sup>, **BIRCH, MAPLE, and POPLAR** (ANSI/HPVA - HP1 - latest edition), <http://hpva.org/>

Cut	Plain Sliced (Flat Cut), Quarter Cut, Rotary Cut					
	AA			A		
Grade Description	Sap (White)	Heart (Red/Brown)	Natural	Sap (White)	Heart (Red/Brown)	Natural
Color and Matching						
Sapwood	Yes	No	Yes	Yes	No	Yes
Heartwood	No	Yes	Yes	No	Yes	Yes
Color Streaks or Spots	Slight			Slight	Yes	
Color Variation	Slight	Yes		Slight	Yes	
Sharp Color Contrast at Joints	Yes, if Slip, Plank, or Random Matched			Yes, if Slip, Plank, or Random Matched		
Type of Matching Book Matched Slip Matched Pleasant Matched	Yes Specify Not applicable			Yes Specify Not applicable		
Nominal Minimum Width of Face Components <sup>a</sup> Plain Sliced Quarter Rotary	5" (127 mm) 3" (76 mm) 5" (127 mm)			4" (102 mm) 3" (76 mm) 4" (102 mm)		
<b>Natural Characteristics</b>						
Small Conspicuous Burls & Pin Knots, Combined Average Number	1 per 5 sq ft (2 per 1 m <sup>2</sup> )			1 per 3 sq ft (4 per 1 m <sup>2</sup> )		
Conspicuous Burls, Maximum Size	1/4" (6.4 mm)			3/8" (9.5 mm)		
Conspicuous Pin Knots Average Number Maximum Size: Dark Part Total	No			1 per 8 sq ft (4 per 3 m <sup>2</sup> ) 1/8" (3.2 mm) 1/4" (6.4 mm)		
Scattered Sound and Repaired Knots	No			No		
Mineral Streaks	No at Maple, Slight			Slight		
Bark Pockets	No			No		
Worm Tracks	Slight			Slight		
Vine Marks	Slight			Slight		
Cross Bars	Slight			Slight		
<b>Manufacturing Characteristics</b>						
Rough Cut/Ruptured Grain	No			No		
Blended Repaired Tapering Hairline Splits	Two 1/32" x 3" (0.8 mm x 76 mm) on ends only			Two 1/16" x 6" (1.6 mm x 152 mm)		
Repairs	Very small blending			Small blending		
<b>Special Characteristics</b>						
Quartered	1" in 12" (25.4 mm in 305 mm) maximum grain slope; 2-1/2" in 12" (63.5 mm in 305 mm) maximum grain sweep					
Unfilled worm holes, open splits, open joints, open bark pockets, shake, and doze are not allowed in the above grades.						
<sup>a</sup> Outside components will be a different size to allow for edge trim loss and certain types of matching.						
<sup>b</sup> American or European.						

# SECTION 9

## Doors

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **C**, or **P** icon is not indicated, the rule applies to all Grades equally



## compliance requirements

Table: 9-048 - **MAHOGANY** (African or American), **ANIGRE, MAKORE, and SAPELE** (ANSI/HPVA - HP1 - latest edition), <http://hpva.org/>

Cut	Plain Sliced (Flat Cut), Quarter Cut, Rotary Cut	
Grade Description	AA	A
<b>Color and Matching</b>		
Sapwood	No	No
Heartwood	Yes	Yes
Color Streaks or Spots	Slight	Slight
Color Variation	Slight	Slight
Sharp Color Contrast at Joints	Yes, if Slip, Plank, or Random Matched	Yes, if Slip, Plank, or Random Matched
Type of Matching Book Matched Slip Matched Pleasing Matched	Yes Specify Not Applicable	Yes Specify Not Applicable
Nominal Minimum Width of Face Components <sup>a</sup> Plain Sliced Quarter Rotary	5" (127 mm) 3" (76 mm) 5" (127 mm)	4" (102 mm) 3" (76 mm) 4" (102 mm)
<b>Natural Characteristics</b>		
Small Conspicuous Burls & Pin Knots, Combined Average Number	1 per 5 sq ft (2 per 1 m <sup>2</sup> )	1 per 3 sq ft (4 per 1 m <sup>2</sup> )
Conspicuous Burls, Maximum Size	1/4" (6.4 mm)	3/8" (9.5 mm)
Conspicuous Pin Knots Average Number Maximum Size: Dark Part Total	No	1 per 8 sq ft (4 per 3 m <sup>2</sup> ) 1/8" (3.2 mm) 1/4" (6.4 mm)
Scattered Sound and Repaired Knots	No	No
Mineral Streaks	No	Slight
Bark Pockets	No	No
Worm Tracks	No	No
Vine Marks	Slight	Slight
Cross Bars	Occasional	Occasional
<b>Manufacturing Characteristics</b>		
Rough Cut/Ruptured Grain	No	No
Blended Repaired Tapering Hairline Splits	Two 1/32" x 3" (0.8 mm x 76 mm) on ends only	Two 1/16" x 6" (1.6 mm x 152 mm)
Repairs	Very Small Blending	Small Blending
<b>Special Characteristics</b>		
Quartered	1" in 12" (25.4 mm in 305 mm) maximum grain slope; 2-1/2" in 12" (63.5 mm in 305 mm) maximum grain sweep	
Unfilled worm holes, open splits, open joints, open bark pockets, shake, and doze are not allowed in the above grades.		
<sup>a</sup> Outside components will be a different size to allow for edge trim loss and certain types of matching.		

# SECTION 9

## Doors

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **C**, or **P** icon is not indicated, the rule applies to all Grades equally



## compliance requirements

Table: 9-049 - RED OAK and WHITE OAK (ANSI/HPVA - HP1 - latest edition), <http://hpva.org/>

Cut	Plain Sliced (Flat Cut), Quarter Cut, Rift and Comb Grade, Rotary Cut			
	AA		A	
	Red Oak	White Oak	Red Oak	White Oak
<b>Color and Matching</b>				
Sapwood	No		5% <sup>a</sup>	Yes <sup>a</sup>
Heartwood	Yes		Yes	
Color Streaks or Spots	Yes		Yes	
Color Variation	Slight		Slight	
Sharp Color Contrast at Joints	Yes, if Slip, Plank, or Random Matched		Yes, if Slip, Plank, or Random Matched	
Type of Matching				
Book Matched	Yes		Yes	
Slip Matched	Specify		Specify	
Plousing Matched	Not Applicable		Not Applicable	
Nominal Minimum Width of Face Components <sup>a, b, c</sup>				
Plain Sliced	5" (127 mm)		4" (102 mm)	
Quarter	3" (76 mm)		3" (76 mm)	
Rotary	5" (127 mm)		4" (102 mm)	
<b>Natural Characteristics</b>				
Small Conspicuous Burls & Pin Knots, Combined Average Number	1 per 4 sq ft (3 per 1 m <sup>2</sup> )		1 per 2-2/3 sq ft (4 per 1 m <sup>2</sup> )	
Conspicuous Burls - Maximum Size	1/4" (6.4 mm)		3/8" (9.5 mm)	
Conspicuous Pin Knots				
Average Number	No		1 per 3 sq ft (4 per 1 m <sup>2</sup> )	
Maximum Size: Dark Part			1/8" (3.2 mm)	
Total			1/4" (6.4 mm)	
Scattered Sound and Repaired Knots	No		No	
Mineral Streaks	No		Slight, Blending	
Bark Pockets	No		No	
Worm Tracks	No		No	
Vine Marks	No		Slight	
Cross Bars	Slight		Slight	
<b>Manufacturing Characteristics</b>				
Rough Cut/Ruptured Grain	No		No	
Blended Repaired	Two 1/32" x 3" on (0.8 mm x 76 mm) at ends only		Two 1/16" x 6" (1.6 mm x 152 mm)	
Tapering Hairline Splits				
Repairs	Very Small Blending		Small Blending	
<b>Special Characteristics</b>				
Ray Fleck (Flake)	Slight, Blending Quarter Cut Unlimited		Slight, Blending Quarter Cut Unlimited	
Slope and Sweep - Quarter & Rift	1 inch in 12 inches (25.4 mm in 305mm) max. grain slope, 2-1/2 inch in 12 inches (63.5 mm in 305mm) max. grain sweep			
Comb Grain	1/2 inch in 12 inches (12.7 mm in 305mm) max. grain slope, 1/2 inch in 12 inches (12.7 mm in 305mm) max. grain sweep			
Unfilled worm holes, open splits, open joints, open bark pockets, shake, and doze are not allowed in the above grades.				
<sup>a</sup> Sap is allowed in rotary only, unless otherwise specified.				
<sup>b</sup> 10% sap is allowed in rift, comb, and plain sliced; 20% sap is allowed in rotary.				
<sup>c</sup> Outside components will be a different size to allow for the edge trim loss and certain types of matching.				

# SECTION 9

## Doors

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **C**, or **P** icon is not indicated, the rule applies to all Grades equally



## compliance requirements

Table: 9-050 - **PECAN** and **HICKORY** (ANSI/HPVA - HP1 - latest edition), <http://hpva.org/>

Cut	Plain Sliced (Flat Cut), Quarter Cut, Rotary Cut	
	AA	A
<b>Grade Description</b>		
<b>Color and Matching</b>		
Sapwood	Yes	Yes
Heartwood	Yes	Yes
Color Streaks or Spots	Yes	Yes
Color Variation	Yes	Yes
Sharp Color Contrast at Joints	Yes, if Slip, Plank, or Random Matched	Yes, if Slip, Plank, or Random Matched
Type of Matching Book Matched Slip Matched Pleasing Matched	Yes Specify Not Applicable	Yes Specify Not Applicable
Nominal Minimum Width of Face Components <sup>a</sup> Plain Sliced Quarter Rotary	5" (127 mm) 3" (76 mm) 5" (127 mm)	4" (102 mm) 3" (76 mm) 4" (102 mm)
<b>Natural Characteristics</b>		
Small Conspicuous Burls & Pin Knots, Combined Average Number	1 per 1 sq ft (11 per 1 m <sup>2</sup> )	2 per 1 sq ft (22 per 1 m <sup>2</sup> )
Conspicuous Burls - Maximum Size	1/4"	3/8"
Conspicuous Pin Knots <sup>b</sup> Average Number Maximum Size: Dark Part Total	1 per 2 sq ft (6 per 1 m <sup>2</sup> ) 1/8" (3.2 mm) 1/4" (6.4 mm)	2 per 1 sq ft (22 per 1 m <sup>2</sup> ) 1/8" (3.2 mm) 1/4" (6.4 mm)"
Scattered Sound and Repaired Knots	No	No
Mineral Streaks	Slight	Slight
Bark Pockets	No	Small, Occasional
Worm Tracks	No	Slight
Vine Marks	Slight	Occasional
Cross Bars	Slight	Occasional
<b>Manufacturing Characteristics</b>		
Rough Cut/Ruptured Grain	No	No
Blended Repaired Tapering Hairline Splits	Two 1/32" x 3" (0.8 mm x 76 mm) at ends only	Two 1/16" x 6" (1.6 mm x 152 mm)
Repairs	Very Small Blending	Small Blending
<b>Special Characteristics</b>		
Bird Peck <sup>c</sup>	No	Slight
Knife Marks	Knife marks might occur in these dense species.	
Quartered	1" in 12" (25.4 mm in 305 mm) maximum grain slope; 2-1/2" in 12" (63.5 mm in 305 mm) maximum grain sweep	
Unfilled worm holes, open splits, open joints, open bark pockets, and doze are not allowed in the above grades.		
<sup>a</sup> Outside components will be a different size to allow for edge trim loss and certain types of matching.		
<sup>b</sup> For Pecan and Hickory, conspicuous pin knots mean sound knots 1/4" (6.4 mm) or less in diameter with dark centers larger than 1/16" (1.6 mm). Blending pin knots are sound knots 1/4" (6.4 mm) or less in diameter with dark centers 1/16" (1.6 mm) or less and are allowed in all grades.		
<sup>c</sup> To achieve a more rustic appearance, bird peck shall be specified.		

# SECTION 9

## Doors

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **C**, or **P** icon is not indicated, the rule applies to all Grades equally



## compliance requirements

Table: 9-051 - WALNUT and CHERRY (ANSI/HPVA - HP1 - latest edition), <http://hpva.org/>

Cut	Plain Sliced (Flat Cut), Quarter Cut, Rotary Cut	
	AA	A
<b>Grade Description</b>		
<b>Color and Matching</b>		
Sapwood <sup>a</sup>	No	No <sup>a</sup>
Heartwood	Yes	Yes
Color Streaks or Spots	Slight	Slight
Color Variation	Slight	Slight
Sharp Color Contrast at Joints	Yes if Slip, Plank, or Random Matched	Yes if Slip, Plank, or Random Matched
Type of Matching		
Book Matched	Yes	Yes
Slip Matched	Specify	Specify
Pleasant Matched	n/a	n/a
Nominal Minimum Width of Face Components <sup>b</sup>		
Plain Sliced	5" (127 mm)	4" (102 mm)
Quarter	3" (76 mm)	3" (76 mm)
Rotary	5" (127 mm)	4" (102 mm)
<b>Natural Characteristics (except as listed below, natural characteristics are not restricted)</b>		
Small Conspicuous Burls & Pin Knots - Combined Average Number	1 per 4 sq ft (3 per 1 m <sup>2</sup> )	1 per 1-1/3 sq ft (8 per 1 m <sup>2</sup> )
Conspicuous Burls - Maximum Size	1/4" (6.4 mm)	3/8" (9.5 mm)
Conspicuous Pin Knots <sup>c</sup>		
Average Number	1 per 5 sq ft (3 per 1 m <sup>2</sup> )	1 per 2 sq ft (6 per 1 m <sup>2</sup> )
Maximum Size: Dark Part	1/8" (3.2 mm)	1/8" (3.2 mm)
Total	1/4" (6.4 mm)	1/4" (6.4 mm)
Scattered Sound and Repaired Knots	No	No
Mineral Streaks	Slight	Slight
Bark Pockets	No	No
Worm Tracks	No	No
Vine Marks	Slight	Occasional
Cross Bars	Slight	Occasional
<b>Manufacturing Characteristics</b>		
Rough Cut/Ruptured Grain	No	No
Blended Repaired Tapering Hairline Splits	Two 1/32" x 3" (0.8 mm x 76 mm) on panel ends only	Two 1/16" x 6" (1.6 mm x 152 mm)
Repairs	Very Small Blending	Small Blending
<b>Special Characteristics (except as listed below, natural characteristics are not restricted)</b>		
Gum Spots	Occasional Gum Spots permitted in Cherry	Occasional Gum Spots permitted in Cherry
Quartered	1" in 12" (25.4 mm in 305 mm) maximum grain slope; 2-1/2" in 12" (63.4 mm in 305 mm) maximum grain sweep	
Unfilled worm holes, open splits, open joints, open bark pockets, and doze are not allowed in the above grades.		
<sup>a</sup> Sapwood is allowed in Grades A and B; however, the percentage shall be agreed upon between the buyer and the seller.		
<sup>b</sup> Outside components will be a different size to allow for edge trim loss and certain types of matching.		
<sup>c</sup> For Walnut and Cherry, conspicuous pin knots mean sound knots 1/4" (6.4 mm) or less in diameter with dark centers larger than 1/16" (1.6 mm). Blending pin knots are sound knots 1/4" (6.4 mm) or less in diameter with dark centers 1/16" (1.6 mm) or less and are allowed in all grades.		

# SECTION 9

## Doors

GENERAL/**PRODUCT**/INSTALLATION/TEST

Where the **C**, or **P** icon is not indicated,  
the rule applies to all Grades equally

<b>C</b>	<b>P</b>
----------	----------

## compliance requirements

<b>9.4.5</b>		<b>Basic Material Rules</b>	
<b>▲ From previous column</b>			
<b>6</b>	At <b>FLUSH</b> doors (continued)		
<b>6 2</b>	<b>CROSS BAND VENEERS</b> shall be of wood veneer or composite, and:		
<b>6 2 1</b>	Particleboard cross band veneers are not permitted.		
<b>6 3</b>	<b>HORIZONTAL EDGES</b> shall run the full width between stiles without a gap.		
<b>7 At STILE and RAIL doors:</b>			
<b>7 1</b>	For <b>OPAQUE</b> finish, face and edges shall be solid stock of close grain hardwood, veneer of sound close grain hardwood or MDO, at the manufacturer's choice.		
<b>7 2</b>	For <b>TRANSPARENT</b> finish, face and edges shall be:		
<b>7 2 1</b>	Solid stock of species specified.		
<b>7 2 2</b>	Veneer of HPVA "A" Grade.	<b>C</b>	<b>P</b>
<b>7 2 3</b>	Veneer of HPVA "AA" Grade.	<b>C</b>	<b>P</b>



# SECTION 9

## Doors

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **C**, or **P** icon is not indicated, the rule applies to all Grades equally



## compliance requirements

### 9.4.6 Basic Machine/Assembly Rules

- 1 **ANSI/WDMA HEAVY DUTY PERFORMANCE DUTY LEVEL** is required for both Flush and Stile and Rail doors, and:
  - 1 1 If a higher Extra Heavy Duty or lower Standard Duty Performance Duty Level is required, it shall be specified.
  - 1 2 A minimum 1" (25.4 mm) hardwood or material that has been qualified in accordance with WDMA TM 15 (latest edition) is required at flush doors stiles and rails.

Table: 9-052 - **FLUSH WOOD DOOR MINIMUM PERFORMANCE STANDARDS** - (Reprinted with permission from ANSI/WDMA I.S. 1A latest edition), <http://wdma.com>

Performance Attribute	Performance Duty Level		
	EXTRA HEAVY DUTY	HEAVY DUTY	STANDARD DUTY
Adhesive Bond Durability, WDMA TM-6	Type I or Type II		
Cycle Slam, WDMA TM-7	1,000,000 cycles	500,000 cycles	250,000 cycles
Hinge Loading, WDMA TM-8	550 lbs (2440 N)	475 lbs (2110 N)	400 lbs (1780 N)
Door Finish, Various ASTM test methods	TR-6 & OP-6 or equal * (Catalyzed Polyurethane NAAWS System -11)	TR-4 & OP-4 or equal * (Conversion Varnish NAAWS System -5)	TR-2 & OP-2 or equal * (Catalyzed Lacquer NAAWS System -2 or 3)
Screw holding, WDMA TM-10	Door Face (blocked or unblocked)	550 lbs (2440 N)	475 lbs (2110 N)
	Vertical Door Edge	550 lbs (2440 N)	475 lbs (2110 N)
	Horizontal Door Edge **	300 lbs (1330 N)	240 lbs (1060 N)
Telegraph, Section T-1	<b>See NAAWS Test N in TEST</b>	Maximum 0.010" in any 3" span (0.25 mm in any 76 mm span)	
Warp Tolerance, Section T-2	<b>See NAAWS Test E in TEST</b>	Maximum 0.25" per 3'6" x 7'0" (6.4 mm in any 1050 mm x 2100 mm) door section	
Squareness, Section T-3	<b>See NAAWS Test M in TEST</b>	Diagonal variance 1/8" (3.2 mm)	
* Other formulations may exhibit similar performance characteristics, but must meet or exceed the performance levels for the systems specified to be considered equal.			
** Horizontal door edge screwholding applies when hardware is to be attached.			

- 3 **TYPE I or II ADHESIVE** use at the manufacturer's choice.
- Continues next column ▼**



# SECTION 9

## Doors



GENERAL/PRODUCT/INSTALLATION/TEST

Where the **C**, or **P** icon is not indicated, the rule applies to all Grades equally

**C P**

# compliance requirements

9.4.6 Basic Machine/Assembly Rules			
▲ From previous column			
4	APPLIED MOLDINGS require:		
4 1	Solid stock, free of finger joints.		
4 2	Securely and soundly attached, in contact with the adjacent surface.		
4 2 1	For <b>OPAQUE</b> finish:		
4 2 1 1	To be <b>CLOSE GRAIN HARDWOOD</b> of a species of the manufacturer's choice.		
4 2 1 2	Require moldings to be <b>PRIMED</b> when the doors are factory primed.		
4 2 2	For <b>TRANSPARENT</b> finish:		
4 2 2 1	To be of the <b>SAME SPECIES</b> and <b>LUMBER</b> or <b>VENEER GRADE</b> as the face veneer, except:		
4 2 2 1 1	Maple may be used as an alternate when a Birch face is specified.		
4 2 2 2	Require molding to be pre-finished if doors are factory finished.		
4 2 3	At <b>HPDL</b> faced doors:		
4 2 3 1	To be <b>CLOSE GRAIN HARDWOOD</b> of the manufacturer's choice.		
4 2 3 2	Require molding to be <b>STAINED</b> or <b>PAINTED</b> to match the face, if so specified.		
5	<b>GLAZING MATERIAL</b> required be secured in place with mitered wood glazing beads or clips with glass bedded in sealant that squeezes out on both sides, and/or:		
5 1	Sealant shall be a quality, elastic type compound, which is designed for bedding glazing materials or is recommended for such use by the sealant manufacturer.		
5 2	Use of glazing gaskets, tape or high density foam is acceptable.		
6	<b>EXPOSED SURFACES</b> shall comply with the following smoothness requirements (see Item 9.87.1 in TESTS):		
6 1	<b>SHARP EDGES</b> shall be eased with a fine abrasive.		
6 2	<b>TOP FLAT WOOD</b> surfaces; those that can be sanded with a drum or wide belt sander:		
6 2 1	120 grit sanding.	C	P
6 2 2	150 grit sanding.	C	P
6 3	<b>PROFILED</b> and <b>SHAPED WOOD</b> surfaces:		
6 3 1	120 grit sanding.		
6 4	<b>TURNED WOOD</b> surfaces:		
6 4 1	120 grit sanding.	C	P
6 4 2	180 grit sanding.	C	P
Continues next column ▼			

9.4.6 Basic Machine/Assembly Rules			
▲ From previous column			
6	<b>EXPOSED SURFACES</b> (continued)		
6 5	<b>CROSS SANDING</b> , excluding turned surfaces, is not allowed.		
6 6	<b>TEAR OUTS, KNIFE NICKS,</b> or <b>HIT OR MISS</b> machining is not permitted.		
6 7	<b>KNIFE MARKS</b> are not permitted where sanding is required.		
6 8	<b>GLUE</b> or <b>FILLER</b> , if used, shall be inconspicuous and match the adjacent surface for smoothness.		
6 9	<b>HPDL, PVC,</b> and <b>PRE-FINISHED WOOD</b> edges shall be machined flush and filed, sanded, or buffed to remove machine marks and sharp edges, and:		
6 9 1	<b>OVERLAP</b> (See Test F illustrations in TESTS) such as,		
			
	shall not exceed:		
6 9 1 1	0.005" (0.13 mm) for a maximum length of 1" (25.4 mm) in any 24" (610 mm) run.	C	P
6 9 1 2	0.003" (0.08 mm) for a maximum length of 1" (25.4 mm) in any 48" (1220 mm) run.	C	P
6 9 2	<b>CHIP OUT</b> (See Test G illustrations in TESTS) such as		
			
	shall be inconspicuous when viewed at:		
6 9 2 1	48" (1220 mm).	C	P
6 9 2 2	24" (610 mm).	C	P
Continues next column ▼			

# SECTION 9


## Doors



GENERAL/PRODUCT/INSTALLATION/TEST

Where the **C**, or **P** icon is not indicated, the rule applies to all Grades equally

**C P**

# compliance requirements

9.4.6 Basic Machine/Assembly Rules			
▲ From previous column			
6 EXPOSED SURFACES (continued)			
6 9 HPDL, PVC, and PRE-FINISHED WOOD edges (continued)			
<p>6 9 3 OVER MACHINED (See Test H illustrations in TESTS) removal of color or pattern of face material such as,</p>  <p>shall be limited to:</p>			
6 9 3 1	1/32" x 4" (0.8 mm x 102 mm) and may not occur within 60" (1524 mm) of a similar occurrence.	C	P
6 9 3 2	1/32" x 1-1/2" (0.8 mm x 38.1 mm) and may not occur within 72" (1829 mm) of a similar occurrence.	C	P
7 THESE STANDARDS do not establish grade rules for joint flushness and or gap tolerances for woodwork products installed in a non-climate controlled environment: however:			
7 1	Prior to installation, the flushness and/or gap tolerances of woodwork products intended for non-climate controlled environments shall meet the test requirements herein.		
8 JOINTS at ASSEMBLED WOODWORK shall:			
8 1 Be neatly and accurately made.			
8 2 Be SECURELY GLUED, with:			
8 2 1 Adhesive residue removed from exposed and semi-exposed surfaces.			
8 3 Be REINFORCED with glue blocks where essential.			
8 4	Utilize clamp nail, biscuit spline, butterfly, scarf, or dowel joinery.	C	P
8 5	Utilize biscuit spline, butterfly, scarf, or dowel joinery.	C	P
Continues next column ▼			

9.4.6 Basic Machine/Assembly Rules			
▲ From previous column			
8 JOINTS at ASSEMBLED WOODWORK (continued)			
8 6 Be MECHANICALLY FASTENED with nails or screws where practical, with:			
8 6 1 Fasteners at solid wood countersunk.			
8 6 2 Fasteners at solid wood in molding quirks or reliefs where possible.			
8 7 NOT PERMIT fasteners at exposed surfaces of decorative laminate or overlay sheet products.			
8 8 Require FLUSHNESS VARIATIONS at exposed surfaces (See Test D illustrations in TESTS), when mitered or butted, such as,			
 <p>not to exceed at:</p>			
8 8 1 Wood to wood:			
8 8 1 1	0.007" (0.18 mm).	C	P
8 8 1 2	0.005" (0.13 mm).	C	P
8 8 2 Non wood to non wood:			
8 8 2 1	0.015" (0.38 mm).	C	P
8 8 2 2	0.010" (0.25 mm).	C	P
8 9 Allow GAPS at exposed surface (see Test A illustrations in TESTS), when mitered or butted, such as,			
 <p>not to exceed:</p>			
8 9 1	0.015" (0.38 mm) wide by 20% of the joint length.	C	P
8 9 2	0.010" (0.25 mm) wide by 20% of the joint length.	C	P
Continues next column ▼			

# SECTION 9



## Doors

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **C**, or **P** icon is not indicated, the rule applies to all Grades equally



# compliance requirements

9.4.6		Basic Machine/Assembly Rules	
▲ From previous column			
8 JOINTS at ASSEMBLED WOODWORK (continued)			
<p>Allow <b>GAPS</b> at exposed surface joints of parallel members (See Test B illustrations in TESTS), such as,</p>  <p>not to exceed:</p>			
8 10 1	0.015" x 6" (0.38 mm x 152 mm) shall not occur within 60" (1524 mm) of a similar gap in the same joint.	C	P
8 10 2	0.010" x 4" (0.25 mm x 102 mm) shall not occur within 72" (1829 mm) of a similar gap in the same joint.	C	P
<p>Allow <b>GAPS</b> at exposed surface joints (See Test C illustrations in TESTS) when mitered or butted, such as,</p>  <p>not to exceed:</p>			
8 11 1	0.015" (0.38 mm).	C	P
8 11 2	0.010" (0.25 mm).	C	P
8 12 Allows use of filler:			
8 12 1	If inconspicuous when viewed at 24" (610 mm).	C	P
8 12 2	Not allowed.	C	P
9 At FLUSH doors:			
9 1	Shall be 3, 5, OR 7 PLY of the manufacturer's choice, unless specified otherwise.		
9 2	<b>CORES</b> , conforming to the minimum requirements of WDMA - I.S. 1-A (latest edition), at:		
9 2 1	Solid core, shall be particleboard, MDF, agrifiber, staved lumber, SCL, or fire resistant composite.		
Continues next column ▼			

9.4.6		Basic Machine/Assembly Rules	
▲ From previous column			
9 At FLUSH doors (continued)			
9 2 <b>CORES</b> (continued)			
9 2 2	Hollow core, shall be honey comb or expandable paper core, and the:		
9 2 2 1	Stile and/or rail widths remaining after sizing or pre-fitting to be no less than:		
9 2 2 1 1	1" (25.4 mm) at lock and hinge stiles.		
9 2 2 1 2	Top and bottom, horizontal edges shall be as specified or as needed to meet WDMA Performance Duty Level specified and:		
9 2 2 1 2 1	Blocking size and location to be as specified.		
9 3 Require <b>CUTOUTS</b> :			
9 3 1	At <b>NON RATED</b> doors to (unless allowed by individual manufacturer's warranty):		
9 3 1 1	Not exceed 40% of the door area, for the combined area of all cutouts for lights or louvers.		
9 3 1 2	Not exceed one half the door height.		
9 3 1 3	Be at least 5" (127 mm) from door edges, adjacent cutouts, or hardware mortises.		
9 3 Require <b>CUTOUTS</b> (continued)			
9 3 2 At <b>RATED</b> doors:			
9 3 2 1	Be governed by the individual manufacturer's fire rated approval and/or NFPA 80 for the combined area and location of cutouts for lights or louvers.		
9 3 3	At <b>HPDL</b> exposed surfaces have a minimum 1/4" (6.4 mm) radius at all inside corners.		
9 4 Require <b>TRANSOM PANEL</b> :			
9 4 1 <b>BOTTOM RAILS</b> to be:			
9 4 1 1	<b>TYPE 2</b> , which allows side rails to run through.	C	P
9 4 1 2	Compatible for color to the vertical edgeband of the door.	C	P
9 4 1 3	<b>TYPE 1</b> , full width.	C	P
9 4 1 4	Well matched for color to the vertical edgeband of the door.	C	P
9 4 2 <b>TOP RAILS</b> of doors with rabbeted transoms to be:			
9 4 2 1	Compatible in color to the vertical edgeband of the door.	C	P
9 4 2 2	Of the same species as the vertical edgeband of the door.	C	P
Continues next column ▼			

# SECTION 9

## Doors

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **C**, or **P** icon is not indicated, the rule applies to all Grades equally

**C P**

## compliance requirements

9.4.6		Basic Machine/Assembly Rules	
▲ From previous column			
9	At FLUSH doors (continued)		
9 4	Require <b>TRANSOM PANEL</b> (continued)		
9 4 3	<b>FACES</b> , for transparent finish be:		
9 4 3 1	End matched to the door.	C	P
9 4 3 2	Continuous matched to the door.	C	P
9 4 4	<b>END MATCHED VENEER MISALIGNMENT</b> between sequenced adjacent panels shall not exceed:		
4 4 4 1	3/8" (9.5 mm).	C	P
4 4 4 2	3/16" (4.8 mm).	C	P
9 5	Requires <b>DUTCH DOORS</b> without an applied shelf to have the top edge of the bottom leaf and the bottom edge of the top leaf, if rabbeted:		
9 5 1	For <b>OPAQUE</b> finish to be close grain hardwood of a species of the manufacturer's choice.		
9 5 2	For <b>TRANSPARENT</b> finish to be:		
9 5 2 1	Of a species compatible in color with the face veneer.	C	P
9 5 2 2	The same species as the face veneer.	C	P
9 5 3	For <b>HPDL</b> , to be close grain hardwood of a species of the manufacturer's choice, and:		
9 5 3 1	Painted or stained to match the face laminate, if edges are so required.		
9 6	Require <b>VERTICAL EDGES</b> :		
9 6 1	For <b>OPAQUE</b> finished doors:		
9 6 1 1	Be primed, if doors are factory primed.		
9 6 1 2	Be close grain hardwood lumber, veneer, or MDO over backer of the manufacturer's choice.		
9 6 1 3	Permit one finger joint at either veneer edge that is tight, not raised, or not visible from a distance of 48" (1219 mm).	C	P
9 6 1 4	Finger joints are not permitted.	C	P
Continues next column ▼			

9.4.6		Basic Machine/Assembly Rules	
▲ From previous column			
9	At FLUSH doors (continued)		
9 6	Require <b>VERTICAL EDGES</b> (continued)		
9 6 2	For <b>TRANSPARENT</b> finished doors:		
9 6 2 1	Permit one finger joint at each edge that is tight, not raised, uniform in color and grain, without discoloration, or not visible from a distance of 48" (1219 mm).	C	P
9 6 2 2	Finger joint are not permitted.	C	P
9 6 2 3	Be hardwood lumber or veneer over backer, compatible in color with the face veneer.	C	P
9 6 2 4	Allow flat grain Douglas Fir at VG Douglas Fir faced doors.	C	P
9 6 2 5	Be the same species as the face veneer.	C	P
9 6 2 6	Be pre-finished, if the doors are pre-finished.		
9 6 2 7	If the manufacturer's fire rated door approval prevents the use of matching vertical edges, then the species permitted under their approval shall be allowed.	C	P
9 6 2 8	Require VG Grain Douglas Fir at VG Douglas Fir faced doors.	C	P
9 6 3	For <b>HPDL FACED</b> doors:		
9 6 3 1	Be unfinished close grain hardwood of manufacturer's choice, and:	C	P
9 6 3 1 1	At opaque finish, permit finger joints at either edge that are tight, not raised, or not visible from a distance of 48" (1219 mm).	C	P
9 6 3 1 2	At transparent finish, permit one finger joint at either edge that is tight, not raised, uniform in color and grain, without discoloration, and not visible from a distance of 24" (610 mm).	C	P
9 6 3 2	Be HPDL or PVC to match the face laminate or hardwood stained/painted and finished to match the face laminate at the manufacturer's choice.	C	P
Continues next column ▼			

# SECTION 9

## Doors

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **C**, or **P** icon is not indicated, the rule applies to all Grades equally

**C** **P**

## compliance requirements

9.4.6		Basic Machine/Assembly Rules	
▲ From previous column			
10	At STILE and RAIL doors:		
10	1	Shall be glued up with Type I or II Adhesive at the manufacturer's choice.	
10	2	Special stile or rail requirements to accommodate specified hardware shall prevail.	
10	3	Of softwood shall be solid stock or veneer construction.	
10	4	Of hardwood shall be:	
10	4	1	Solid stock or veneer construction. <b>C</b> <b>P</b>
10	4	2	Veneer construction. <b>C</b> <b>P</b>
10	5	The construction of the STILES and RAILS:	
10	5	1	If SOLID STOCK requires:
10	5	1	1 One piece solid stock. <b>C</b> <b>P</b>
10	5	1	2 Two piece balanced lamination for thickness, with opposing grain.
10	5	1	3 Three piece lamination for thickness, balanced outer pieces, with opposing grain, and:
10	5	1	3 1 Face laminations shall be uniform in thickness.
10	5	1	4 No finger joints.
10	5	1	5 Edge gluing in accordance with Section 3.
10	5	2	If VENEERED requires:
10	5	2	1 CORES of either MDF (medium density fiberboard), SCL (structural composite lumber), edge glued wood blocks/strips (staved core), particleboard, agrifiber, laminated veneer lumber core, fire resistant composite core, and specialty door core types, and:
10	5	2	1 1 If STAVED CORE (edge glued wood block/strips), it shall be of one species in any one door, and the staves (block/strips):
10	5	2	1 1 Shall not exceed 2" (50.8 mm) in width.
10	5	2	1 2 May be of any length.
10	5	2	1 3 Shall have staggered end joints in adjacent rows.
10	5	2	1 4 Shall not permit voids between end joints.
10	5	2	1 5 Shall not permit open surface defects.
10	5	2	1 6 Shall be bonded together under pressure.
Continues next column ▼			

9.4.6		Basic Machine/Assembly Rules	
▲ From previous column			
10	At STILE and RAIL (continued)		
10	6	With PANELS require:	
10	6	1	They be finished to a uniform thickness and fit snugly into the stile and rail retention groves, and that:
10	6	1	1 They float in their method of retention, and that:
10	6	1	1 1 Mechanical fastening is not permitted.
10	6	2	MDF (medium density fiberboard) may be used for opaque finish, and:
10	6	3	Grain shall run vertically, and:
10	6	3	1 At single panel, shall be selected for compatibility of color and grain.
10	6	3	2 At Multiple panels:
10	6	3	2 1 Shall be compatibility for color and grain. <b>C</b> <b>P</b>
10	6	3	2 2 Shall be well matched for color and grain. <b>C</b> <b>P</b>
10	6	4	At flat type, they be at least:
10	6	4	1 1/4" (6.4 mm) in thickness at 1-3/8" (35 mm) thick doors.
10	6	4	2 1/2" (12.7 mm) in thickness at 1-3/4" (44 mm) thick doors.
10	6	4	3 5/8" (16 mm) in thickness at 2-1/4" (57 mm) thick doors.
10	6	5	At RAISED type, they shall be:
10	6	5	1 At least 3/4" (19 mm) in thickness at 1-3/8" (35 mm) thick doors.
10	6	5	2 At least 1-1/8" (28.6 mm) in thickness at 1-3/4" (44 mm) thick doors.
10	6	5	3 At least 1-1/2" (38.1 mm) in thickness at 2-1/4" (57 mm) thick doors.
10	6	5	4 Constructed of either:
10	6	5	4 1 Solid stock in opening widths not to exceeding 14" (356 mm).
10	6	5	4 2 Rim banded or membrane- pressed panel construction, and:
10	6	5	4 2 1 Mitered when rim banded.
Continues next column ▼			

# SECTION 9

## Doors

GENERAL/**PRODUCT**/INSTALLATION/TEST

Where the **C**, or **P** icon is not indicated,  
the rule applies to all Grades equally

<b>C</b>	<b>P</b>
----------	----------

**compliance requirements**

<b>9.4.6</b>		<b>Basic Machine/Assembly Rules</b>
<b>▲ From previous column</b>		
<b>10</b>	<b>At STILE and RAIL</b> (continued)	
<b>10 7</b>	Require <b>JOINERY</b> :	
<b>10 7 1</b>	To be either mortise and tenon or doweled and glued under pressure so that the stiles, rails, mullions, and muntins are bonded together.	
<b>10 7 2</b>	At faces to finish true, with stile and rail intersections and other copes well fitted.	
<b>10 7 3</b>	Stickings to be clean cut and smooth.	



# SECTION 9

## Doors

### GENERAL/PRODUCT/INSTALLATION/TEST

Where the **C**, or **P** icon is not indicated,  
the rule applies to all Grades equally



### compliance requirements

#### 9.5 PREPARATION and QUALIFICATION REQUIREMENTS

- 1 **CARE, STORAGE, and BUILDING CONDITIONS** shall be in compliance with the requirements set forth in Section 2 of these standards, and doors shall be:
- 1.1 Sealed at earliest possible moment. Edge sealing is particularly important.
  - 1.2 Lift or carry door. Do not drag one door against another.
  - 1.3 Handle doors with clean hands or clean gloves.
  - 1.4 Severe damage to the woodwork can result from noncompliance. The manufacturer and/or installer of the woodwork shall not be held responsible for damage that might develop by not adhering to the requirements.
- 2 **CONTRACTOR IS RESPONSIBLE FOR** 
- 2.1 Furnishing and installing structural members, grounds, in wall blocking, backing, furring, brackets, or other anchorage required for architectural woodwork installation that becomes an integral part of walls, floors, or ceilings to which architectural woodwork shall be installed.
    - 2.1.1 In the absence of contract documents calling for the contractor to supply the necessary in wall blocking/backing in the wall or ceilings, either through inadvertence or otherwise, the architectural woodwork installer shall not proceed with the installation until such time as the in wall blocking/backing is installed by others.
    - 2.1.2 Preparatory work done by others shall be subject to inspection by the architectural woodwork installer, and may be accepted or rejected for cause prior to installation.
      - 2.1.2.1 **WALL, CEILING, and/or OPENING VARIATIONS** in excess of 1/4" (6.4 mm) or **FLOORS** in excess of 1/2" (12.7 mm) in 144" (3658 mm) of being plumb, level, flat, straight, square, or of the correct size are not acceptable for the installation of architectural woodwork, nor is it the responsibility of the installer to scribe or fit to tolerances in excess of such.

#### 9.5 PREPARATION and QUALIFICATION REQUIREMENTS (continued)

- 2.1.3 Installation site being properly ventilated, protected from direct sunlight, excessive heat and/or moisture, and that the HVAC system is functioning and maintaining the appropriate relative humidity and temperature.
- 2.2 Priming the architectural woodwork in accordance with the contract documents prior to its installation.
- 3 **INSTALLER IS RESPONSIBLE FOR** 
- 3.1 Having adequate equipment and experienced craftsmen to complete the installation in a first class manner.
- 3.2 Checking architectural woodwork specified and studying the appropriate portions of the contract documents, including these standards and the reviewed shop drawings to familiarize themselves with the requirements of the Grade specified, understanding that:
  - 3.2.1 Appearance requirements of Grades apply only to surfaces visible after installation.
  - 3.2.2 For transparent finish, special attention needs to be given to the color and the grain of the various woodwork pieces to ensure they are installed in compliance with the Grade specified.
- 3.3 Verification that installation site is properly ventilated, protected from direct sunlight, excessive heat and/or moisture, and that the HVAC system is functioning and maintaining the appropriate relative humidity and temperature.
- 3.4 Verification that required priming of woodwork has been completed by others before woodwork is installed.
- 3.5 Verification that woodwork has been acclimated to the field conditions for a minimum of 72 hours before installation is commenced.
- 3.6 Woodwork specifically built or assembled in sequence for match of color and grain is installed to maintain that same sequence.

# SECTION 9

## Doors

### GENERAL/PRODUCT/INSTALLATION/TEST

Where the **C**, or **P** icon is not indicated, the rule applies to all Grades equally



## compliance requirements

### 9.6 RULES

- 1 The following rules shall govern unless a project's contract documents require otherwise.
- 2 These rules are intended to provide a well defined degree of control over a project's quality of materials, workmanship, or installation.
- 3 **ERRATA**, published at [naaws-errata.com](http://naaws-errata.com), shall take precedence over these rules, subject to their date of posting and a project's bid date.



9.6.4		Basic General Rules	
1	AESTHETIC	Grade rules apply only to exposed and semi-exposed surfaces visible after installation.	
2 INSTALLERS shall be furnished with an approved:			
2	1	Hardware schedule and required templates.	
2	2	Set of metal frame shop drawings, including the locations of the hardware preparations.	
3 PRE-FIT and PRE-MACHINED doors are to be installed in accordance with the manufacturer's data.			
4 TRANSPARENT FINISH doors in sets or with transoms shall be installed:			
4	1	Compatible in color and grain.	C P
4	2	Well matched for color and grain.	C P
5 BLUEPRINT matched doors and panels shall be single sourced.			
6 UTILITY or STRUCTURAL STRENGTH of doors shall not be impaired in fitting them to the opening, applying hardware, preparing for lights, louvers, plant-ons, or other detailing.			
7 FIRE DOOR ASSEMBLIES, including 20, 30, 45, 60, and 90 minute rated, shall be prepared for locks, latches, hinges, remotely operated or monitored hardware, concealed closers, glass lights, vision panels, louvers, astragals, and laminated overlays in conformance to the manufacturer's Label Service requirements, and:			
7	1	LABELS are prohibited from being removed.	
8 DOORS and their ACCESSORIES shall be hung plumb and level within 1/16" (1.6 mm) of the height and width of the door assembly.			
Continues next column ▼			

9.6.4		Basic General Rules	
▲ From previous column			
9 WHEN INSTALLED, doors shall operate smoothly and easily without binding, and:			
9 1 PAIRS of doors, when closed, shall be within 1/16" (1.6 mm) of flush at the meeting edge.			
10 INSTALLER FABRICATION or MODIFICATIONS shall comply to the general, material, machining, and assembly rules within the PRODUCT portion of this section and the applicable finishing rules in Section 5.			
11 Door FACES shall not extend more than:			
11 1 1/16" (1.6 mm) beyond the face of the jamb.			
11 2 1/8" (3.2 mm) behind the face of the jamb.			
12 FITTING for:			
12 1 WIDTH requires the door to be trimmed equally from both sides; however, on:			
12 1 1 FIRE RATED DOORS, in order to preserve the label, they shall be trimmed per the manufacturer's requirements.			
12 2 HEIGHT prohibits trimming top or bottom rails more than 3/4" (19 mm), and:			
12 2 1 FIRE RATED DOORS shall only be trimmed on the bottom rail only.			
12 2 2 When cutting to length, extreme care shall be used to prevent chipping of veneer.			
12 3 Doors shall be trimmed so as to maintain bevel: or beveled in field 3 degrees unless contra indicated by hardware requirements.			
13 CLEARANCE between the door and frame members shall be a maximum of 1/8" (3.2 mm) on the hinge and lock sides, the top of the door, and between the meeting edges of doors in pairs, and:			
13 1 Installer shall not be responsible for clearances in excess of these dimensions if the door manufacturer made an error on pre-fit widths or locations for mortise hardware.			
13 2 Clearance at the bottom of fire rated doors shall conform to NFPA 80 and at non rated doors shall be a minimum of 1/4" and a maximum of 5/8" measured from the bottom of the door to the highest point of the finish floor that the door swings over.			
Continues next column ▼			

# SECTION 9

## Doors

### GENERAL/PRODUCT/INSTALLATION/TEST

Where the **C**, or **P** icon is not indicated, the rule applies to all Grades equally



## compliance requirements

9.6.4 Basic General Rules	
▲ From previous column	
14	<b>HARDWARE</b> shall be installed:
14 1	In locations and by methods of attachment appropriate for the specific door construction.
14 1 1	Templates for specific hardware preparation and installation are typically available from the manufacturer or the Door Hardware Institute (DHI).
14 2	With appropriate fasteners, and:
14 2 1	Operate as intended.
14 2 2	Preferably use threaded to the head wood screws on nonrated doors.
14 2 3	Use threaded to the head wood screws on fire rated doors.
14 2 4	Require pilot holes to be drilled for screws.
14 2 5	Installed using furnished fasteners or fastener provisions and when fastener provisions are countersunk, fasteners shall be countersunk.
15	<b>LEAF HINGES</b> on:
15 1	<b>SOLID CORE</b> doors shall require:
15 1 1	A minimum of two hinges for doors up to 60" (1524 mm) in height.
15 1 2	A minimum of three hinges for doors over 60" (1524 mm) in height, and:
15 1 2 1	An additional hinge for each additional 30" (762 mm) or portion thereof in door height.
15 1 3	Space between hinges be equal.
15 2	<b>HOLLOW CORE</b> doors weighing less than 50 lbs (22.7 kg) and not exceeding 90" (2286 mm) in height shall require only two hinges.
16	<b>EQUIPMENT CUTOUTS</b> , shall be cut out by the installer, provided templates are furnished prior to installation, and:
16 1	Shall be neatly cut and properly sized to be covered by standard cover plates or rosettes.
16 2	In <b>HPDL</b> shall have a minimum 1/4" (6.4 mm) radius at inside corners.
16 3	<b>CUTOUTS</b> for lights or louvers, if applicable, shall be protected from water entering the door core by a satisfactory method such as metal flashing at the bottom of the cutout.
Continues next column ▼	

9.6.4 Basic General Rules	
▲ From previous column	
17	<b>TEMPORARY DISTORTIONS</b> (warp) will usually disappear when humidity is equalized, and doors seldom need to be replaced.
18	<b>REPAIRS</b> are allowed, provided they are made neatly and are inconspicuous when viewed at:
18 1	48" (1219 mm). <b>C</b> <b>P</b>
18 2	24" (610 mm). <b>C</b> <b>P</b>
19	<b>WOODWORK</b> such as <b>APPLIED TRIM</b> shall be:
19 1	<b>SECURELY</b> fastened and tightly fitted with flush joints.
19 1 1	Joinery shall be consistent throughout the project.
19 2	Of <b>MAXIMUM</b> available and/or practical lengths.
19 3	<b>PROFILED</b> or <b>SELF MITERED</b> when trim ends are exposed. <b>C</b> <b>P</b>
19 4	<b>SELF MITERED</b> when trim ends are exposed. <b>C</b> <b>P</b>
19 5	<b>MITERED</b> at outside corners.
19 6	<b>MITERED</b> at inside corners. <b>C</b> <b>P</b>
19 7	<b>COPEd</b> at inside corners. <b>C</b> <b>P</b>
19 8	<b>INSTALLED</b> plumb, level, square, and flat within 1/8" (3.2 mm) in 96" (2438 mm).
19 8 1	Grounds and hanging systems set plumb and true.
19 9	<b>INSTALLED FREE OF:</b>
19 9 1	Warp, twisting, cupping, and/or bowing that cannot be held true.
19 9 2	Open joints, visible machine marks, cross sanding, tear outs, nicks, chips, and/or scratches.
19 9 3	Natural defects exceeding the quantity and/or size limits defined in Sections 3 and 4.
19 10	<b>SMOOTH</b> and <b>SANDED</b> without cross scratches in conformance to the Product portion of this section.
20	These standards do not establish Grade rules for joint flushness and or gap tolerances for woodwork products installed in a non climate controlled environment.
Continues next column ▼	

# SECTION 9



## Doors

### GENERAL/PRODUCT/INSTALLATION/TEST

Where the **C**, or **P** icon is not indicated, the rule applies to all Grades equally



## compliance requirements

9.6.4		Basic General Rules		
▲ From previous column				
21	GAPS (see Test I illustrations in TESTS) such as,			
				
	and:			
	1	Shall <b>NOT EXCEED</b> 30% of a joint's length, and:		
	1 1	<b>FILLER</b> or <b>CAULKING</b> is allowed, if color compatible.		
	2	Of <b>WOOD</b> to <b>WOOD</b> shall not exceed:		
	2 1	At <b>FLAT</b> surfaces:		
	2 1 1	0.020" (0.51 mm) in width.	<b>C</b>	<b>P</b>
	2 1 2	0.015" (0.38 mm) in width.	<b>C</b>	<b>P</b>
	2 2	At <b>SHAPED</b> surfaces:		
2 2 1	0.025" (0.64 mm) in width.	<b>C</b>	<b>P</b>	
2 2 2	0.015" (0.38 mm) in width.	<b>C</b>	<b>P</b>	
22	FLUSHNESS of joinery (see Test J illustrations in TESTS), such as,			
				
	and:			
	1	Of <b>WOOD</b> to <b>WOOD</b> shall not exceed:		
	1 1	At <b>FLAT</b> surfaces:		
	1 1 1	0.015" (0.38 mm) in width.	<b>C</b>	<b>P</b>
	1 1 2	0.010" (0.25 mm) in width.	<b>C</b>	<b>P</b>
	1 2	At <b>SHAPED</b> surfaces:		
	1 2 1	0.025" (0.65 mm) in width.	<b>C</b>	<b>P</b>
	1 2 2	0.030" (0.51 mm) in width.	<b>C</b>	<b>P</b>
23	AREAS of installation shall be left broom clean.			
23 1	Debris shall be removed and dumped in containers provided by the general contractor.			
23 2	Items installed shall be cleaned of pencil or ink marks.			
24	<b>FIRST CLASS WORKMANSHIP</b> is required in compliance with these standards.			



# SECTION 9

## Doors

### GENERAL/PRODUCT/INSTALLATION/TEST

Where the **C**, or **P** icon is not indicated,  
the rule applies to all Grades equally




### compliance requirements

#### 9.7 BASIC CONSIDERATIONS

- 1 **TOLERANCES** typically found within NAAWS:
- 1.1 Fall into two **CATEGORIES**:
- 1.1.1 Factory fabricated joinery, assembly and construction - found in the **PRODUCT** portion.
- 1.1.2 Field installation joinery and assembly - found in the **INSTALLATION** portion.
- 1.2 **INCLUDE:**
- 1.2.1 Flatness of wood based panel products.
- 1.2.2 Solid wood to solid wood joints and assemblies.
- 1.2.3 Solid wood to wood veneer joints and assemblies.
- 1.2.4 Wood veneer to wood veneer joints and assemblies.
- 1.2.5 Solid wood to wood based product joints and assemblies (decorative laminate Solid Phenolic and panel products).
- 1.2.6 Solid surface to solid surface joints and assemblies.
- 1.3 **EXCLUDE:**
- 1.3.1 **BECAUSE of EXPANSION and CONTRACTION DIFFERENCES of non-wood products compared to solid wood and wood based products, these Standards do not apply tolerances regarding flatness or joinery to:** 
- 1.3.1.1 Solid wood to non-wood based products (which can be drywall, glass, metal, stone, acrylics, and other surfaces).
- 1.3.1.2 Non-wood to non-wood joints.

#### 9.7 BASIC CONSIDERATIONS (continued)

- 2 **FABRICATED and INSTALLED** woodwork shall be tested for compliance to these standards as follows.
- 2.1 **SMOOTHNESS** of exposed surfaces:
- 2.1.1 **KCPI** (Knife Cuts Per Inch) is determined by holding the surfaced board at an angle to a strong light source and counting the visible ridges per inch, usually perpendicular to the profile.
- 
- Figure: 9-053
- 2.1.2 **SANDING** is checked for compliance by sanding a sample piece of the same species with the required grit of abrasive, and:
- 2.1.2.1 Observation with a hand lens of the prepared sample and the material in question will offer a comparison of the scratch marks of the abrasive grit.
- 2.1.2.2 Reasonable assessment of the performance of the finished product will be weighed against absolute compliance with the standard.
- 2.1.2.3 A product is sanded sufficiently smooth when knife cuts are removed and remaining sanding marks are or will be concealed by applied finishing coats.
- 2.1.2.4 Grain raise at unfinished wood, due to moisture or humidity in excess of the ranges set forth in this standard, shall not be considered a defect and must be sanded prior to finishing.
- 2.2 **GAPS, FLUSHNESS, FLATNESS and ALIGNMENT:**
- 2.2.1 Maximum gaps between exposed components shall be tested with a feeler gauge at points designed to join, where members contact or touch.
- 2.2.2 Joint length shall be measured with a ruler with minimum 1/16" (1 mm) divisions and calculations made accordingly.
- 2.3.3 Reasonable assessment of the performance of the finished product will be weighed against absolute compliance with the standards.

# SECTION 9

## Doors

### GENERAL/PRODUCT/INSTALLATION/TEST

Where the **C**, or **P** icon is not indicated, the rule applies to all Grades equally




### compliance requirements

#### 9.7 BASIC CONSIDERATIONS (continued)

#### 2.2 GAPS, FLUSHNESS, FLATNESS and (continued)

2.2.4 The following is intended to provide examples of how and where testing is measured:



- A - Fabrication Gaps When Surfaces Are Mitered Or Butted
- B - Fabrication Gaps When Parallel Pieces Are Joined
- C - Fabrication Gaps When Edges Are Mitered Or Butted
- D - Fabrication Flushness Between Two Surfaces
- E - Flatness Of Panel Product
- F - Overlap (Flushness Of Laminate)

- G - Chip Out
- H - Over Machining
- I - Installation Gaps
- J - Installation Flushness
- M - Squareness
- N - Show-Through Or Telegraphing

Figure: 9-054

# North American Architectural Woodwork Standards - 3.1

## **S E C T I O N - 1 0**

# CASEWORK

<b>Resources . . . . .</b>	<b><a href="#">303</a></b>
<b>Introduction . . . . .</b>	<b><a href="#">305</a></b>
<b>Advisories . . . . .</b>	<b><a href="#">305</a></b>
<b>Recommendations . . . . .</b>	<b><a href="#">306</a></b>
<b>Specification Considerations . . . . .</b>	<b><a href="#">307</a></b>
<b>Design Resources . . . . .</b>	<b><a href="#">318</a></b>
<b>Compliance Requirements . . . . .</b>	<b><a href="#">319</a></b>
<b>Scope &amp; Default Stipulation . . . . .</b>	<b><a href="#">321</a></b>
<b>Basic Rules . . . . .</b>	<b><a href="#">322</a></b>
<b>Annexes 10A - 10C (Material Specific) . . . . .</b>	<b><a href="#">352</a></b>
<b>Annex 10D (Lab Casework) . . . . .</b>	<b><a href="#">359</a></b>
<b>Installation . . . . .</b>	<b><a href="#">361</a></b>
<b>Annex 10E (Seismic Installation) . . . . .</b>	<b><a href="#">368</a></b>
<b>Test . . . . .</b>	<b><a href="#">376</a></b>

### Within CANADA

#### SUPPORT

- **GUIDE SPECIFICATIONS** – Available for download in interactive digital format, including specification wording for Quality Assurance Program (GIS) at: <http://awmac.com/guide-specifications>
- **CONSULTATION** – Contact any of the local chapters for more information on the NAAWS or any other Architectural Woodwork Questions you may have. See below for contact information.
- **SPECIFICATION REVIEW** – Contact any of the local chapters if you would like your specifications reviewed for compliance to the NAAWS.
- **MANUFACTURER STANDARDS QUESTIONNAIRE (MSQ)** – AWMAC Manufacturer members have the opportunity to have at least one member of their staff study and write the MSQ. The MSQ is a questionnaire on the NAAWS and policy and procedures of the GIS program. A list of Manufacturer members that have passed the MSQ is available at: <http://awmac.com/members>
- **SEMINARS AND PRESENTATIONS** – Contact your local chapter to arrange an informative presentation on any Architectural Woodwork topic. Some topic options – GIS, NAAWS, How to Specify Quality Architectural Woodwork...
- **TRADE SHOWS** – Contact your local chapter to arrange for AWMAC to have a booth or do a presentation on Architectural Woodwork.
- **CONFERENCE** – AWMAC has an annual conference held at unique venues across Canada. The conferences provide an opportunity to learn more about Architectural Woodwork and network with Suppliers and Manufacturers from across Canada. More information is available at: <http://awmac.com/>
- **EDUCATION PARTNERS** – Contact the local chapters to find out more information about support for local Colleges and Universities offering woodworking related courses and programs.

#### QUALITY ASSURANCE

- **GUARANTEE AND INSPECTION SERVICE (GIS)** – The GIS is a national program designed to ensure that project owners get value and quality for their investment by:
  - Supporting architects and design professionals to achieve project plans and specifications; and
  - Helping contractors avoid problems such as cost overruns, delays and loss of reputation.

More information is available at: <http://awmac.com/gis>

- **INSPECTION SERVICE** – A GIS Certified Inspector will inspect specific areas of concern on a project for compliance to the NAAWS and provide a written report. Contact your local chapter for more information.
- **EXPERT OPINION** – An expert will be appointed to inspect specific areas of concern on a project and provide a written report. Contact your local chapter for more information.

#### AWMAC CHAPTERS

- AWMAC British Columbia Chapter, Vancouver BC  
<http://bc.awmac.com>
- AWMAC Northern Alberta Chapter, Edmonton Alberta  
<http://nab.awmac.com>
- AWMAC Southern Alberta Chapter, Calgary Alberta  
<http://sab.awmac.com>
- AWMAC Saskatchewan Chapter, Saskatoon Saskatchewan  
<http://sk.awmac.com>
- AWMAC Manitoba Chapter, Winnipeg Manitoba  
<http://mb.awmac.com>
- AWMAC Ontario Chapter, Toronto Ontario  
<http://on.awmac.com>
- AWMAC Quebec Chapter, Montreal Quebec  
<http://qc.awmac.com>
- AWMAC Atlantic Chapter, Halifax Nova Scotia  
<http://atl.awmac.com>

### Within UNITED STATES

#### SUPPORT

- **GUIDE SPECIFICATIONS** - Available in interactive digital format including quality control options at: <http://woodworkinstitute.com/publications/architectural-woodwork-standards/>
- **AIA SEMINARS** - The Woodwork Institute is a Registered Provider of the American Institute of Architects (AIA), and its Continuing Education System (CES) program, check out our offerings at: <http://woodworkinstitute.com/architectural-resources/aia-seminars/> 
- **CONSULTATION** - Contact one of our Directors of Architectural Services (DAS) at: <http://woodworkinstitute.com/about-us-2/about-us/>
- **ACCREDITED FABRICATORS AND INSTALLERS** - Our AMC's (Accredited Millwork Company) represents the best fabricators and installers in our industry, check them out at: <http://woodworkinstitute.com/membership-listing-2/> 
- **CERTIFIED INDUSTRY PROFESSIONALS** - Our CMP's (Certified Millwork Professionals) represent the knowledge base of our industry, check them out at: <http://woodworkinstitute.com/membership-listing-2/> 
- **MILLWORK INDUSTRY PARTNERS** - Our MIP's (Millwork Industry Partners) represent the best of our industries material suppliers, check them out at: <http://woodworkinstitute.com/membership-listing-2/> 
- **ACKNOWLEDGED PRODUCTS LISTING** - If it's listed here, you are assured it meets NAAWS minimum requirements, find the listing at: <http://woodworkinstitute.com/acknowledged-product-listing/> 
- **CABINET DESIGN SERIES (CDS)** - Eliminate the need to include casework elevations in your architectural drawings, check out the CDS system in NAAWS "Design Resources" and access the cad files at: <http://woodworkinstitute.com/architectural-resources/cabinet-design-series/>

#### QUALITY ASSURANCE

- **BIDDER QUALIFICATION** - A discipline of bidder pre-qualification wherein your specifications protect you and your customer from the unknown: To be eligible to bid or negotiate this job, the subcontractor must be a Woodwork Institute Accredited Millwork Company (AMC) in good standing.   
<http://woodworkinstitute.com/architectural-resources/quality-assurance>
- **CERTIFIED COMPLIANCE PROGRAM (CCP)** - A discipline of quality control used in conjunction with NAAWS providing an unbiased means of ensuring conformance to a project's plans and specifications. CCP, together with the use of the desired Grade(s) in the specifications, informs all parties of the design professional's expectations, without bidder discrimination.   
<http://woodworkinstitute.com/services/certified-compliance-program>
- **MONITORED COMPLIANCE PROGRAM (MCP)** - A discipline of quality affirmation used in conjunction with the NAAWS which provides ongoing reviews/inspections of a project from its beginning through completion, ensuring strict conformance to the design intent throughout the millwork fabrication and installation process.   
<http://woodworkinstitute.com/services/monitored-compliance-program/>
- **CERTIFIED SEISMIC INSTALLATION PROGRAM (CSIP)** - A standalone seismic assurance option which can be specified in conjunction with or without CCP or MCP, offering design professionals and project owners specific use of WI's seismic casework pre-approvals from California's Office of Statewide Health Planning and Development (OSHPD) without additional engineering costs and/or requirements, assuring proper backing has been installed in the walls when and where required.   
<http://woodworkinstitute.com/services/certified-seismic-installation-program/>

### INTRODUCTION

Section 10 includes information on Wood, Decorative Laminate, and Solid Phenolic Faced Casework and their related parts.

Quality assurance can be achieved by adherence to these standards and will provide the owner a quality product at competitive pricing. Working with an AWMAC Member (in Canada) or a WI Certified Millwork Professional (CMP) (in the USA) and the WI Accredited Millwork Company (AMC) they represent to provide your woodwork will help ensure the understanding and performance of the quality level required. Illustrations in this Section are not intended to be all inclusive, other engineered solutions may be acceptable. In the absence of specifications; methods of fabrication are the manufacturer's choice. The design professional, by specifying compliance to these standards increases the probability of receiving the product quality expected.

### CASEWORK CATEGORIES

This section addresses three distinct categories of casework based on the exterior exposed face:

- **WOOD CASEWORK** with wood faces for transparent or opaque finish.
- **DECORATIVE LAMINATE CASEWORK** with HPDL or LPDL faces.
- **SOLID PHENOLIC CASEWORK** with solid phenolic faces.

### ADVISORIES

**CONTRACT DOCUMENTS** - Shall clearly indicate or delineate all material, fabrication, installation, and applicable building code/regulation requirements, and:

- It is the design professional's responsibility to evaluate the fastening methods required and modify as appropriate to ensure adequate in wall blocking and fasteners are used for the project conditions.

**SEISMIC CASEWORK INSTALLATION** - Requires explicit specification requirement for such within contract documents.

- Within the United States, the International Building Code (IBC), as published by the International Code Council, <http://iccsafe.org>, establishes these minimum requirements; however, some states have expanded on the U.S. requirements.
- Within Canada, the National Building Code (NBC), as published by the National Research Council Canada, <http://nrc-cnrc.gc.ca/eng/index.html>, establishes these minimum requirements; however, some provinces and cities have expanded on the Canadian requirements.

Optional standards are provided for seismic casework installation; however, must be specifically required in a projects specifications. Compliance requirement are based on 2010 and 2013 California Building Code (CBC) engineering for use in California, which also complies with the minimum requirements of the International Building Code (IBC).

Engineering is applicable at any height within buildings where  $z/h \leq 1.0$ , and the SDS is not greater than 1.93 for base, peninsula and mechanical chase cabinets or 2.0 for wall and tall storage cabinets, for:

- Concrete or concrete masonry unit (CMU) wall construction when grouted solid
- Wood or metal stud wall construction with either continuous 3 x 6 (76 x 152 mm) or 16 gauge in wall blocking respectively, with:
  - One or two layers of 5/8" (16 mm) sheetrock.



- Where Casework construction is of plywood, particleboard, MDF or Solid Phenolic Core (SPC) and in compliance with the minimum requirements of the North American Architectural Woodwork Standards (NAAWS), including:
  - Base cabinets, up to 36" (914 mm) tall x 24" (610 mm) body depth x 48" (1220 mm) wide, including peninsula and those with mechanical chase.
  - Wall cabinets up to 48" (1220 mm) tall x 18" (457 mm) body depth x 48" (1220 mm) wide.
  - Tall storage cabinets up to 96" (2413 mm) tall x 24" (610 mm) body depth x 48" (1220 mm) wide.
  - Peninsula base cabinets up to 36" (914 mm) tall x 36" (914 mm) body depth x 48" (1220 mm) wide.
  - Mechanical chase base cabinets up to 42" (1067 mm) tall x 36" (914 mm) body depth and 48" (1220 mm) wide.

**CAUTION** - It is the user's responsibility to confirm compatibility, acceptability and scope of these seismic engineered installation standards. The Sponsor Associations shall not be responsible to anyone for the use of or reliance upon these standards, nor shall they incur any obligation nor liability for damages, including consequential damages, arising out of or in connection with the use, interpretation of, or reliance upon these standards.



**CHEMICAL or STAIN RESISTANT** - Any special surface requirements must be specified.

- Consider the chemical and staining agents that might be used on or near the surfaces. Chemical resistance and stain resistance are affected by concentration, time, temperature, humidity, housekeeping, and other factors. It is recommended that actual samples are tested in a similar environment with those agents.

# SECTION 10

## Casework

## introductory information

### ADVISORIES (continued)

**ABRASION RESISTANT** - Any special surface requirements must be specified.



Consider the abrasive elements that might be used on or near the surfaces. Common guidelines can be found at:

- ASTM C501 (latest edition) as published by ASTM International, <http://astm.org>.
- NEMA LD3 (latest edition) as published by the National Electrical Manufacturers Association, <http://nema.org>.

### UNLESS SPECIFIED OTHERWISE

- **CORNERS** created by tall, wall, or base casework will create non usable space.
- **FINISHED ENDS** shall be integral, not applied secondarily, except:
  - **APPLIED END PANELS** are allowed at Solid Phenolic casework and at teaching wall assemblies.
- **BASE/TOE** shall be integral (constructed as an integral part of the cabinet body) or separate (constructed as a separate member) at manufacturer's choice.
- **STORAGE, JANITOR CLOSET, and/or UTILITY ROOM CABINETS** shall be built in conformance to Economy Grade, regardless of the overall project's Grade requirement, unless specified otherwise.
- Surfaces behind **PRESENTATION PANELS** (such as white board or tack board) are treated as:
  - **Semi Exposed** at Economy Grade and Custom Grade.
  - **Exposed** at Premium Grade.

- **TOE BASE HEIGHT VARIANCE** due to floor variations is not considered a defect. Casework is required to be installed level; shimming of the toe base, not to exceed 1/2" (12.7 mm), is acceptable. Floor variations exceeding 1/2" (12.7 mm) shall be corrected before cabinets are installed; however, correction of such is not the responsibility of the cabinet installer.

**LABORATORY CASEWORK** - (Requires explicit specification requirement for such within contract documents.

These standards provide minimum requirements for Laboratory Casework in Annex D which is intended to assist design professionals in specifying custom designed wood, HPDL or solid phenolic faced laboratory casework and matching furniture/fixture accessories with the same confidence that is provided by NAAWS for their other casework needs.

Requiring compliance to NAAWS and its optional laboratory casework requirements shall be in concert with that of the Scientific Equipment and Furniture Association (SEFA), <http://sefalabs.com> Recommended Practices.

NAAWS does not address, nor make any recommendations as to, metal casework or fabrications, cylinder restraint assemblies, pipe drop enclosures, drying racks, hoods or containment units, slotted channel framing, etc.

**CAUTION** - It is the users responsibility to confirm compatibility, acceptability and scope of these Laboratory Casework standards. The Sponsor Associations shall not be responsible to anyone for the use of or reliance upon these standards, nor shall they incur any obligation nor liability for damages, including consequential damages, arising out of or in connection with the use, interpretation of, or reliance upon these standards.



### RECOMMENDATIONS



- If **FIELD FINISHED**, include in Division 09 of the specifications:
  - **BEFORE FINISHING**, exposed portions of woodwork shall have handling marks or effects of exposure to moisture, removed with a thorough, final sanding over all surfaces of the exposed portions and shall be cleaned before applying sealer or finish.
- At **CONCEALED SURFACES** - Architectural woodwork that may be exposed to moisture, such as those adjacent to exterior concrete walls, etc., shall be primed.
- **REVIEW the GENERAL** portion of Sections 3 and 4 for an overview of the characteristics and the minimum acceptable requirements of lumber and/or sheet products that might be used herein.
- **STRUCTURAL MEMBERS**, grounds, in wall blocking, backing, furring, brackets, or other anchorage which becomes an integral part of the building's walls, floors, or ceilings, required for the installation of architectural woodwork are not to be furnished or installed by the architectural woodwork manufacturer or installer.

# SECTION 10

## Casework

## introductory information

### SPECIFICATION CONSIDERATIONS



- **CONSTRUCTION TYPE.**
- **DOOR AND DRAWER FRONT INTERFACE STYLE.**
- **DOOR AND DRAWER FRONT EDGE PROFILE.**
- **TOE BASE FINISH.**
- **GRAIN DIRECTION**, if other than vertical.
- **INSIDE CLEARANCE**, if critical.
- **AT WOOD CASEWORK:**
  - Species of veneer.
  - Method of slicing (plain, quarter, rift, or rotary).
  - Matching of veneer leaves (book, slip, or random).
  - Matching of veneer leaves within the face of a cabinet unit.
  - Matching between doors, drawers, and adjacent panels (non sequenced, sequenced, or blueprint).
  - End matching.
  - Grain direction, if other than vertical.
- **HARDWARE.**
- **SEISMIC INSTALLATION.** (Requires explicit specification requirement for such with contract documents.)
- **ANTIMICROBIAL SURFACES**
- **LABORATORY CASEWORK:** (Requires explicit specification requirement for such with contract documents.)
  - Pipe chase allowance and/or removable backs behind base cabinets.
  - Removable top at countertop splash.
  - Moisture resistant base.
  - Chemical resistant finish or surfaces.

- **MOISTURE RESISTANCE.**
- **FLAME SPREAD RATING.**
- **SHIELDING FROM ADJACENT HEATING or COOLING SOURCES.**
- **QUALITY ASSURANCE OPTIONS:**

#### Within CANADA

- **AWMAC's GUARANTEE AND INSPECTION SERVICE (GIS)** - See NAAWS's Resources page and/or <http://awmac.com/gis>
- **AWMAC's INSPECTION SERVICE** - See NAAWS's Resources page and/or <http://awmac.com/gis>
- **AWMAC's EXPERT OPINION SERVICE** - See NAAWS's Resources page and/or <http://awmac.com/gis>

#### Within UNITED STATES

- **WI'S AMC BIDDER PRE-QUALIFICATION** - See NAAWS's Resources page and/or <http://woodworkinstitute.com/architectural-resources/quality-assurance>
- **WI'S CERTIFIED COMPLIANCE PROGRAM (CCP)** - See NAAWS's Resources page and/or <http://woodworkinstitute.com/services/certified-compliance-program>
- **WI'S MONITORED COMPLIANCE PROGRAM (MCP)** - See NAAWS's Resources page and/or <http://woodworkinstitute.com/services/monitored-compliance-program/>
- **WI'S CERTIFIED SEISMIC INSTALLATION PROGRAM (CSIP)** - See NAAWS's Resources page and/or <http://woodworkinstitute.com/services/certified-seismic-installation-program/>

# SECTION 10

## Casework

### introductory information

#### SURFACE TERMINOLOGIES

**Cabinet surfaces** are defined in four distinct categories, three for exposed surfaces with very specific minimum surface requirements and one for concealed surfaces subject to manufacturer's choice, as follows:

- **EXPOSED EXTERIOR SURFACES**, defined as all exterior surfaces exposed to view, including:
  - All surfaces visible when doors and drawers are closed, including knee spaces.
  - Underside of cabinet bottoms over 42" (1067 mm) above the finished floor, including cabinet bottoms behind light valances and the bottom edge of light valances.
  - Cabinet tops under 80" (2032 mm) above the finished floor, or if 80" (2032 mm) and over and visible from an upper building level or floor.
  - Front edgeband of stretchers, ends, divisions, partitions, fixed shelves, tops, and bottoms.
  - Front edgeband of adjustable shelves exposed to view in open casework or behind transparent doors.
  - Sloping tops of cabinets that are visible.
- **EXPOSED INTERIOR SURFACES**, defined as all interior surfaces exposed to view in open casework or behind transparent doors, include:
  - Interior faces of shelves (both fixed and adjustable), divisions and partitions (edgeband is an Exposed Exterior Surface).
  - Interior face of ends (sides), backs, and bottoms (including pull outs).
  - (914 mm) or more above the finished floor.
  - Interior face of doors and applied drawer fronts.

#### SURFACE TERMINOLOGY BY ILLUSTRATION



Figure: 10-001

### SURFACE TERMINOLOGIES

(continued)

- **SEMI-EXPOSED SURFACES**, defined as those interior surfaces only exposed to view when doors or drawers are opened, include:
  - Interior faces and edgeband of adjustable shelves, except at Premium Grade where edgeband shall match Exposed Exterior surface.
  - Divisions and partitions (edgeband is an Exposed Exterior Surface).
  - Interior face of ends (sides), backs, and bottoms (including a bank of drawers).
  - Interior face of cabinet top members 36" (914 mm) or more above the finished floor.
  - Drawer box sides, sub fronts, backs, edgebanding, and bottoms.
  - The underside of cabinet bottoms between 24" (610 mm) and 42" (1067 mm) above the finished floor.
  - Security and dust panels or drawer stretchers.
- **CONCEALED SURFACES**, defined as those exterior or interior surfaces that are covered or not normally exposed to view including:
  - Toe space unless otherwise specified.
  - Sleepers, stretchers, and solid sub tops.
  - The underside of cabinet bottoms less than 24" (610 mm) above the finished floor.
  - The underside of countertops, knee spaces, and drawer aprons.
  - The flat tops of cabinets 80" (2032 mm) or more above the finished floor, except if visible from an upper floor or building level.

- The three non visible edges of adjustable shelves.
- The underside of countertops, knee spaces, aprons and drawer boxes that are less than 36" (914 mm) above the finished floor.
- The faces of cabinet ends of adjoining units that butt together.

### SURFACE FINISH REQUIREMENTS

- **EXPOSED EXTERIOR SURFACES** for:
  - **WOOD** casework requires:
    - For **TRANSPARENT** finish, wood of specified species, cut, and match.
    - For **OPAQUE** finish at:
      - **ECONOMY GRADE**, Particleboard, MDF, MDO, softwood plywood, hardwood plywood, or solid stock.
      - **CUSTOM GRADE**, MDF, MDO, close grain hardwood plywood, or solid stock.
      - **PREMIUM GRADE**, MDF and MDO.
  - **DECORATIVE LAMINATE** casework requires at:
    - **ECONOMY GRADE**, LPDL of specified color or pattern.
    - **CUSTOM** and **PREMIUM GRADE**, HPDL of specified color or pattern.
  - **SOLID PHENOLIC** casework requires for **PREMIUM GRADE**, solid phenolic of specified color or pattern.
- **EXPOSED INTERIOR SURFACES** for:
  - **ECONOMY GRADE** at:
    - **WOOD** casework requires:
      - For **TRANSPARENT** finish, LPDL or wood of the manufacturer's choice.
      - For **OPAQUE** finish at, Particleboard, MDF, MDO, softwood plywood, hardwood plywood, or solid stock of manufacturer's choice.
    - **DECORATIVE LAMINATE** casework requires, LPDL of the manufacturer's choice.
  - **CUSTOM GRADE** at:
    - **WOOD** casework requires:
      - For **TRANSPARENT** finish, wood of the same species as the exposed exterior surface.
      - For **OPAQUE** finish at, MDF, MDO, close grain hardwood plywood, or solid stock of manufacturer's choice.
    - **DECORATIVE LAMINATE** casework requires HPDL or LPDL compatible to exposed exterior surface in color, grain, or pattern of manufacturer's choice.

#### SURFACE FINISH REQUIREMENTS

(continued)

- **PREMIUM GRADE** at:
  - **WOOD** casework requires:
    - For **TRANSPARENT** finish, wood of same the species and cut as the exposed exterior surface.
    - For **OPAQUE** finish, use of MDF and MDO of manufacturer's choice.
  - **DECORATIVE LAMINATE** casework requires, HPDL, the same as the exposed exterior surface.
  - **SOLID PHENOLIC** casework requires, solid phenolic, the same as the exposed exterior surface.
- **SEMI-EXPOSED SURFACES** for:
  - **WOOD** casework require for both **TRANSPARENT** and **OPAQUE** finish at:
    - **ECONOMY GRADE**, wood of the manufacturer's choice of species, MDO, MDF, particleboard, or LPDL of the manufacturer's choice of color.
    - **CUSTOM GRADE**, wood of the manufacturer's choice of species, or LPDL of the manufacturer's choice of color.
    - **PREMIUM GRADE**, wood of a compatible species to the exposed.
  - **DECORATIVE LAMINATE** casework at all grades requires, LPDL of the manufacturer's choice of color.
  - **SOLID PHENOLIC** casework requires, solid phenolic of the mill's choice of color.

- **CONCEALED SURFACES** for all grades at, decorative laminate, wood, and solid phenolic casework require the manufacturer's choice.

#### CABINET CONSTRUCTION TERMINOLOGY / OPTIONS

**FRAMELESS** construction where the front edge of the cabinet body components are edgebanded.




Figure: 10-002

**FACE FRAME** construction where the front edge of the cabinet body components are overlaid with a frame.




Figure: 10-003

**SELECTION** shall be manufacturer's choice, unless specified otherwise.



#### CABINET and DOOR INTERFACE TERMINOLOGY / OPTIONS

**FRAMELESS** construction options include:




Figure: 10-004

**Flush Overlay**




Figure: 10-005

**Reveal Overlay**




Figure: 10-006

**Lipped**




Figure: 10-007

**Flush Inset**

#### CABINET and DOOR INTERFACE TERMINOLOGY / OPTIONS (continued)

FACE FRAME construction options include:




Figure: 10-008

**Reveal Overlay**




Figure: 10-009

**Lipped**




Figure: 10-010

**Flush Inset**

#### LAYOUT REQUIREMENTS OF GRAINED OR PATTERNED FACES BY GRADE

- **STILE** and **RAIL** doors and drawer fronts for all Grades, drawer fronts shall run either vertically or horizontally at the manufacturer's choice for the entire project. Doors shall be vertical.



Figure: 10-011



Figure: 10-012

- **FLUSH PANEL** doors and drawer fronts:
- **ECONOMY GRADE** - drawer fronts shall run either vertically or horizontally at the manufacturer's choice for the entire project. Doors shall be vertical. Mismatch is allowed:



Figure: 10-013




Figure: 10-014

- **CUSTOM GRADE** - doors, drawer fronts, and false fronts shall run and match vertically within each cabinet unit:




Figure: 10-015

# SECTION 10

## Casework

## introductory information

### LAYOUT REQUIREMENTS OF GRAINED OR PATTERNED FACES BY GRADE (continued)

- **PREMIUM GRADE** - doors, drawer fronts, and false fronts shall run and match vertically and be sequenced horizontally within each cabinet unit; and at cathedral grain, the crown shall be pointing up and run in the same direction for the entire project. Doors, drawer fronts, and false fronts shall be well matched for color and grain across multiple cabinet faces in one elevation. Requirement for blueprint or sequencing between cabinet units must be so specified.




Figure: 10-016

### CASEWORK DIMENSION RANGES

These ranges have developed over time with consideration of materials, ergonomics, construction techniques, and general intended usage. The following are guidelines from historical experience. It is the responsibility of the design professional to coordinate accessibility requirements, appliance and equipment sizes, and/or storage requirements with the casework manufacturer and adjust their required dimensions accordingly. Please note that illustrations are not to scale and are provided only to show dimension reference point:

- **BASE:**
  - **HEIGHT** - from the finished floor to the top of the countertop deck ranges from:
    - **34" (864 mm) to 36" (914 mm)** at stand up counters.
    - **31" (787 mm) to 38" (965 mm)** at vanities.
    - **28" (711 mm) to 32" (812 mm)** at sit down counters, providing a clear knee space height of 24-1/2" (622 mm).
    - **25-1/4" (641 mm) to 28" (711 mm)** at keyboard recesses, providing a clear knee space height of 24-1/2" (622 mm).
  - **DEPTH** - from the front of the cabinet door/drawer to the face of the wall ranges from 22" (559 mm) to 30" (762 mm).




Figure: 10-017

- **WALL HUNG:**
  - **HEIGHT** - including the light apron ranges from 12" (305 mm) to 48" (1220 mm).
  - **DEPTH** - from the front of the cabinet door to the face of the wall ranges from 12-1/2" (318 mm) to 14" (356 mm).




Figure: 10-018

- **TALL STORAGE:**
  - **HEIGHT** - from the finished floor to the cabinet top ranges from 72" (1829 mm) to 96" (2438 mm).
  - **DEPTH** - from the front of the cabinet door to the face of the wall ranges from 12-1/2" (318 mm) to 30" (762 mm).




Figure: 10-019

# SECTION 10

## Casework

## introductory information

### CASEWORK DIMENSION RANGES


(continued)

#### RECEPTION COUNTER:

- **HEIGHT** - from the finished floor to the top of the countertop deck ranges from:
  - **34" (864 mm) to 42" (1067 mm)** at the standing side.
  - **28" (711 mm) to 32" (812 mm)** at the sit down side, providing a clear knee space height of 24-1/2" (622 mm).
  - **25-1/4" (641 mm) to 28" (711 mm)** at the sit down keyboard recesses, providing a clear knee space height of 24-1/2" (622 mm).


#### DEPTH:

- **24" (610 mm) to 30" (762 mm)** overall countertop on the sit down side, plus an additional 8" (203 mm) of countertop at the stand up side.



#### TELLER COUNTER:

- **HEIGHT** - from the finished floor ranges from:
  - **50" (1270 mm) to 54" (1372 mm)** on the customer side at the security hood.
  - **40" (1016 mm) to 42" (1067 mm)** on the teller's side transaction countertop.
- **DEPTH:**
  - **24" (610 mm) to 32" (813 mm)** at the countertop on the teller side, plus:
    - An additional 8" (203 mm) of countertop at the customer side.




### DOOR AND APPLIED DRAWER FRONT PROFILES


For illustration purposes only and are not intended to be duplicated exactly:

#### Common EDGE PROFILES:


- Square edge with thin applied edgeband.




- Radius edge with thick applied edgeband.



- Square edge with thick applied edgeband:



- Square edge with inset edgeband.



- Lipped edge with inset edgeband:




To **PREVENT TELEGRAPHING**, inset solid wood edging when used must have similar moisture content as panel core, be glued securely and calibrated with panel core thickness prior to being laminated with a wood veneer on both faces.




#### Common RETENTION PROFILES:


- Fixed panel.



- Removable stop.



- Removable stop at HPDL face.



# SECTION 10

## Casework

## introductory information

### DOOR AND APPLIED DRAWER FRONT PROFILES (continued)

- Common **RETENTION PROFILES:** (continued)

- Removable stop, synthetic.




Figure: 10-030

- Removable retainer, synthetic.




Figure: 10-031

- Removable clips.




Figure: 10-032

### CABINET DESIGN SERIES (CDS)

Details were developed by the industry and represent a series of numbered cabinet designs that are available for ease of specification and drawing. A numerical/elevation key to the CDS may be found in the **APPENDIX**.

CAD details are available in both Autodesk Revit Families and AutoCAD “.dwg / .dxf” files and may be found in **DESIGN RESOURCES** at <http://naaws-cds.com>

These cabinets may be specified by number to a specific size requirement on the plan view drawings without having to draw elevations. They are drawn as Frameless Construction, flush overlay Interface’, with integral finished ends and scribes at wall to wall installations not exceeding 1-1/2” (38.1 mm) in width.

### CASEWORK INTEGRITY

These standards have adopted BIFMA’s (Business + Institutional Furniture Manufacturers Association, <https://www.bifma.org>) ANSI/BIFMA X5.9 (latest edition) requirements with additional enhancements, or a portion of SEFA’s (Scientific Equipment and Fixture Association) <http://sefalabs.com> methods of testing and acceptable results as the minimum acceptable level of integrity for casework, as found in the **APPENDIX**.

### CABINET HARDWARE

These standards have adopted ANSI/BHMA Standards (latest editions) <http://www.buildershardware.com>, Grade 2, as the basic minimum requirement. For more specific details, see the **PRODUCT** portion of this Section. Choice of product should be made on the basis of utility, aesthetics, security objectives, and the end use desired. As a general guide:

- GRADE 1** is the highest and is suitable for most institutional applications.
- GRADE 2** is used in most other applications.

### DRAWER SLIDE SELECTION GUIDE

The following serves as both a checklist and a starting point for the discussion of a wide variety of drawer slide systems. While by no means exhaustive, the characteristics described below are often considered the most important by the client, the design professional, and the woodwork manufacturer. The selection of the slide characteristics will affect the usefulness of the cabinets. Careful consideration should be given to avoid “over specifying” for the purpose intended:

- DEGREE OF EXTENSION:**

- Standard Extension**, all but 4” - 6” (101.6 - 152.4 mm) of drawer body extends out of the cabinet.
- Full Extension**, entire drawer body extends out to the face of cabinet.
- Full Extension with over travel**, entire drawer body extends beyond the face of cabinet.

- STATIC LOAD CAPACITY:**

- 50 pounds** - Residential and light commercial.
- 75 pounds** - Commercial.
- 100 pounds** - Heavy duty.
- Over 100 pounds** - Special conditions, extra heavy duty.

- DYNAMIC LOAD CAPACITY:**

- 30 pounds/35,000 cycles** - Residential and light commercial.
- 50 pounds/50,000 cycles** - Commercial.
- 75 pounds/100,000 cycles** - Heavy duty.

### DRAWER SLIDE SELECTION GUIDE

(continued)

#### REMOVAL:

- **Passive disconnect** - A means of drawer removal that does not require active disconnecting.
- **Positive disconnect** - A means of removing a drawer that requires active disconnection or removal of hardware.

#### CLOSING:

- **Self closing/stay closed** - Drawer slides will self close with the related dynamic load when the drawer is 2" (50.8 mm) from the fully closed position and not bounce open when properly adjusted.

- **METAL SIDED DRAWER SYSTEMS** must be specified and should require:

- **Positive stop** - Drawer must stop within itself and not rely on the drawer front to stop it.
- **Pullout strength** - System must demonstrate sufficient strength of attachment of front to sides, design professional should evaluate and approve individually.

### HINGE SELECTION GUIDE

Architectural cabinet hinges will usually be furnished from the manufacturer's stock unless otherwise specified. The three most common hinge types are illustrated below.

European hinges with the screws set in synthetic inserts are an established industry standard. These hinges have been found to be cost effective alternatives to the more traditional hinges shown below. Follow hinge manufacturers' recommendations on number and spacing of hinges. There are conditions, however, in which the use of butt or wraparound hinges will continue to be the best solution. Pivot hinges often require a cut in center hinge. Consult manufacturer's recommendations:

- **European style hinge**, typically used in conventional flush without face frame and reveal or flush overlay application offering moderate strength, full concealment, moderate cost, ease of installation and adjustment.




Figure: 10-033

- **Wraparound hinge (3 & 5 knuckle)**, typically used in flush and reveal overlay applications offering very high strength, moderate cost, ease of installation and moderate ease of adjustment; however, can require mortising and shows an exposed knuckle and hinge body.




Figure: 10-034

- **Butt hinge**, typically used in conventional flush with face frame application, offering high strength, low cost, moderate ease of installation and adjustment; however, can require mortising and shows an exposed knuckle.




Figure: 10-035

### ADJUSTABLE SHELF LOADING and DEFLECTION

Proper specification can balance aesthetic needs with load requirements.

Load is the total applied weight, uniformly dispersed on an individual shelf, not to exceed 200 lbs (90.7 Kg) on any one shelf. These standards have adopted the following load capacities:

- **50 lbs per sq ft (244.1 kg/m<sup>2</sup>)** - School, hospital, library or book shelving.
- **40 lbs per sq ft (195.3 kg/m<sup>2</sup>)** - All other shelving.

Shelving specification requires consideration of deflection, the measured distance from a straight line that a shelf will deflect under load. L/144 (the length of the shelf divided by 144) is the industry standard for the maximum acceptable deflection of a shelf, which permits 1/4" (6.4 mm) deflection in a 36" (914 mm) shelf.

Creep is the increase in deflection over time, which fluctuates with temperature, humidity, and load stress. Creep is not considered a defect; if it is a concern, it can be reduced by:

- Reduced loading of shelves.
- Use of material with a higher (stiffer) modulus of elasticity (MOE).
- Use of alternate construction (support) techniques.
- Use of a decreased factor of acceptable deflection.

# SECTION 10

## Casework

## introductory information

### CONSTRUCTION DETAIL NOMENCLATURE

Familiarity with the labeled details on this and following pages will facilitate communication between architects, designers, specifiers, and woodwork manufacturers by establishing common technical language:

- **STUB TENON** - Joinery method for assembling stile and rail type frames that are additionally supported, such as web or skeleton case frames.




Figure: 10-036

- **HAUNCH MORTISE AND TENON JOINT** - Joinery method for assembling paneled doors or stile and rail type paneling.




Figure: 10-037

- **CONVENTIONAL MORTISE AND TENON JOINT** - Joinery method for assembling square edged surfaces such as case face frames.




Figure: 10-038

- **DOWEL JOINT** - Alternative joinery method serving same function as Conventional Mortise and Tenon.




Figure: 10-039

- **FRENCH DOVETAIL JOINT** - Method for joining drawer sides to fronts when fronts conceal metal extension slides or overlay the case faces.




Figure: 10-040

- **CONVENTIONAL DOVETAIL JOINT** - Traditional method for joining drawer sides to fronts or backs. Usually limited to flush or lipped type drawers.




Figure: 10-041

- **DRAWER LOCK JOINT** - Another joinery method for joining drawer sides to fronts. Usually used for flush type installation, but can be adapted to lip or overlay type drawers.




Figure: 10-042

- **EXPOSED END DETAILS** - Illustrates attachment of finished end of case body to front frame using:

- **BUTT JOINT**




Figure: 10-043

- **SHOULDER MITERED JOINT.**




Figure: 10-044

- **POCKET SCREW JOINT.**




Figure: 10-045

# SECTION 10

## Casework

### introductory information

#### CONSTRUCTION DETAIL NOMENCLATURE (continued)

- **THROUGH DADO** - Conventional joint used for assembly of case body members. Dado not concealed by application of case face frame.




Figure: 10-046

- **BLIND DADO** - Variation of Through Dado with applied edge "stopping" or concealing dado groove.




Figure: 10-047

- **STOP DADO** - Another method of concealing dado exposure. Applicable when veneer edging or solid lumber is used. Exposed end detail illustrates attachment of finished end of case body to front frame using butt joint.




Figure: 10-048

- **DOWEL JOINT** - An established industry standard assembly method, this versatile joinery technique is often based on 1-1/4" (32 mm) spacing of dowels.




Figure: 10-049

- **DOWEL SCREW JOINT** - An alternative to the dowel joint above.




Figure: 10-050

- **EDGE BANDING** - Method of concealing plies or inner cores of plywood or particleboard when edges are exposed. Thickness or configuration will vary with manufacturers' practices.




Figure: 10-051

- **MITER / MITER FOLD JOINT.**




Figure: 10-052

- **SPLINE JOINT:** Used to strengthen and align faces when gluing panels in width or length, including items requiring site assembly.




Figure: 10-053

- **PANELED DOOR DETAILS** - Joinery techniques when paneled effect is desired. Profiles are optional as is the use of flat or raised panels. Solid lumber raised panels may be used when width does not exceed Custom Grade standard. Rim raised panels are required for Premium Grade or when widths exceed Custom Grade or when transparent finish is used.




Figure: 10-054




Figure: 10-055




Figure: 10-056

### ANTIMICROBIAL SURFACES

There is increasing availability of antimicrobial products, including solid surface and HPDL. It is important to understand that regardless of the methodology used to create the antimicrobial surface there are two significantly different types of claims regarding such antimicrobial products. Common terminology refers to these:

- **Within the United States as:**
  - **Treated Article Claim** - Which the US Environmental Protection Agency (EPA), <http://epa.gov>, classifies as a “treated article exemption”, typically referring to items that are treated with antimicrobial pesticide to protect the item itself, not the public. Such exemption will be absent any EPA registration number and is granted for non-public health use.
  - **Public Health Claim** - Which the EPA classifies as “EPA registered products which have been shown, using EPA testing protocols, to demonstrate efficacy in the installed format. Such test protocol requires an efficacy of killing 99.9% of all bacteria, fungi and viruses within two hours.
- **Within Canada as:**
  - **Disinfectant Drugs** - Which Health Canada, <http://hc-sc.gc.ca>, classifies as a non market authorized claim, lacking a Drug Identification Number (DIN).
  - **Hard Surface Disinfectants** - Which Health Canada classifies as having received “Market Authorization” when such have been granted a Drug Identification Number (DIN).

### NONTRADITIONAL MATERIALS

Covers materials re-purposed from other industrial and manufacturing areas, but assigned to the woodwork manufacturer and treated similarly to traditional millwork items like wall paneling. From a design perspective considerations of appearance, color, finish, variation and relation are deemed important as they would be with traditional wood products.

Examples of non-traditional materials could be a fiber/cement panel designed for fire resistance, insulation re purposed as a decorative panel, metal products, cloth, acrylics, etc.

Because these materials are unique, contract documents, shall clearly indicate or delineate all of the necessary material, fabrication, installation and building code/regulation direction and requirements as may be applicable for the manufacturer/installer to reasonably accomplish the intended design concept.

### RECLAIMED or RECYCLED WOOD

#### DESIGN PROFESSIONAL RESPONSIBILITY

Use of unique materials like reclaimed or recycled wood requires a more active role of the design professional in sourcing and pre-approving desired material selections. There are no traditional guidelines with these types of materials to assure either the woodwork manufacturer or the design professional of achieving an intended result. There will be situations where the design professional will be required to directly participate in the individual piecemeal selection and layout process of the product.

**CONTRACT DOCUMENTS**, shall clearly indicate or delineate all material, fabrication, installation and applicable building code/regulation requirements with the clear understanding that incomplete design choices, changes in scope or material selection, lack of material selection, or design choices made after initial bid may impact the cost or not be possible.

The contract documents shall specifically list the material source and identifier, and address the allowable:

- Variation in color or tone, grain, distress, character, and patina.
- Defects, such as nail/bolt holes, checking, cracking, discoloration, milling marks, roughness in terms of quantity, locations, repetition, etc.
- Distortion in terms of straightness, cupping, flatness, etc.

See **SECTION 3** for additional information.

### DESIGN RESOURCES



Is a perpetually expanding, web based resource of pictures, videos, illustrations, ideas and design concepts for inspiring thought and design creativity - assessable at: <http://naaws-design-resources.com>

Relative to this Section, offerings will include:

- Commercial (case, wall, island, peninsula and tall storage)
  - Wood veneer
    - Flush overlay
    - Reveal overlay
    - Flush inset
  - Decorative Laminate
    - Flush overlay
    - Reveal overlay
    - Flush inset
  - Solid Phenolic
    - Flush overlay
    - Reveal overlay
  - Specialty casework
    - Reception
    - Nurses stations
- Residential (base, wall, island and tall storage)
  - Face frame
    - Reveal overlay
    - Flush inset
    - Lipped
  - Frameless
    - Flush overlay
    - Reveal overlay
    - Flush inset

# SECTION 10

## Casework

### GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



## compliance requirements

### INCLUDING: Wood, Decorative Laminate, and Solid Phenolic Faced Casework

#### 10.1 BASIC CONSIDERATIONS

##### 1 GRADE

- 1.1 These standards are characterized in three Grades of quality that may be mixed within a single project. Limitless design possibilities and a wide variety of lumber and veneer species, along with decorative laminates, factory finishes, and profiles are available in all three Grades.
- 1.2 **ECONOMY GRADE** defines the minimum quality requirements for a project's workmanship, materials, or installation and is typically reserved for woodwork that is not in public view, such as in mechanical rooms and utility areas.
- 1.3 **CUSTOM GRADE** is typically specified for and adequately covers most high quality architectural woodwork, providing a well defined degree of control over a project's quality of materials, workmanship, or installation.
- 1.4 **PREMIUM GRADE** is typically specified for use in those areas of a project where the highest level of quality, materials, workmanship, and installation is required.
- 1.5 **GRADE LIMITATIONS:**
  - 1.5.1 **SOLID PHENOLIC** faced Casework is only offered in **PREMIUM GRADE**.
- 2 **CONTRACT DOCUMENTS** shall govern if in conflict with these standards.
- 3 **ACCEPTABLE REQUIREMENTS** of lumber and/or sheet products used within this woodwork product section are established by Sections 3 and 4, unless otherwise modified herein.
- 4 **AESTHETIC COMPLIANCE REQUIREMENTS** apply only to surfaces visible after fabrication and installation.
  - 4.1 Shall be judged from a normal viewing stance and considered compliant if inconspicuous when viewed from:
    - 4.1.1 72" (1830 mm) for Economy Grade
    - 4.1.2 48" (1219 mm) for Custom Grade
    - 4.1.3 24" (610 mm) for Premium Grade

#### 10.1 BASIC CONSIDERATIONS (continued)

- 4.2 For **RECLAIMED** or **RECYCLED WOOD**, the aesthetic compliance requirements of NAAWS does not apply, such shall be as agreed between owner/design professional and the woodwork manufacturer/installer.
- 4.3 For **NON-TRADITIONAL MATERIALS**, the aesthetic compliance requirements of NAAWS does not apply, such shall be as agreed between owner/design professional and the woodwork manufacturer/installer.
- 5 When **SOLID PHENOLIC** (compact laminate) is referenced in these standards, it refers to panels of melamine impregnated decorative overlay sheets over a kraft phenolic core sheets per Section 4.
- 6 **CASEWORK INTEGRITY** - These standards have adopted a portion of SEFA's (Scientific Equipment and Fixture Association) methods of testing and acceptable results as the minimum acceptable level of integrity for casework, as found in the **APPENDIX**. 
- 7 **HARDWARE** - These standards have adopted ANSI/BHMA Standards (latest edition), Grade 2, as the basic minimum requirement for casework hardware.
- 8 **CABINET DESIGN SERIES (CDS):**
  - 8.1 The Sponsor Associations have developed a series of numbered cabinet designs that are available for ease of specification and drawing.
    - 8.1.1 A numerical/elevation key to the drawings may be found in the **APPENDIX**. 
    - 8.1.2 Autodesk Revit Families and AutoCad ".DWG/.DXE/.DXF" files of the elevations may be found at: <http://naaws-design-resources.com>. 
  - 9 **CASEWORK CONCEPT DRAWINGS** may be found in **DESIGN RESOURCES**. <http://naaws-design-resources.com>. 
  - 10 To **PREVENT TELEGRAPHING**, inset solid wood edging when used must have similar moisture content as panel core, be glued securely and calibrated with panel core thickness prior to being laminated with a wood veneer on both faces. 

# SECTION 10

## Casework

### GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



## compliance requirements

### 10.1 BASIC CONSIDERATIONS (continued)

#### 11 INDUSTRY PRACTICES

11.1 **STRUCTURAL MEMBERS**, grounds, in wall blocking, backing, furring, brackets, or other anchorage that becomes an integral part of the building's walls, floors, or ceilings, that are required for the installation of architectural woodwork are not furnished or installed by the architectural woodwork manufacturer or installer.

11.2 **WALL, CEILING**, and/or opening variations in excess of 1/4" (6.4 mm) or **FLOORS** in excess of 1/2" (12.7 mm) in 144" (3658 mm) of being plumb, level, flat, straight, square, or of the correct size are not acceptable for the installation of architectural woodwork, nor is it the responsibility of the installer to scribe or fit to tolerances in excess of such.

11.3 **PRIMING** of architectural casework is not the responsibility of the manufacturer and/or installer, unless the material is being furnished pre-finished.

11.4 **SURFACING** with a defined grain and/or pattern is installed vertically, unless otherwise specified.

#### 11.5 BASE CABINET, STRETCHER, LAYOUT, and CONSTRUCTION:

11.5.1 **CASEWORK MANUFACTURER** is responsible for coordinating the following with the countertop manufacturer, and:

11.5.2 **COUNTERTOP MANUFACTURER** is responsible for furnishing wall cleating necessary for proper setting of their countertops where there is no casework for support.

11.5.3 At **FRAMELESS CONSTRUCTION** doors, drawer fronts, and false fronts creating a 1/8" (3.2 mm) to 1/4" (6.4 mm) horizontal reveal with the countertop's bottom edge, shall be consistent across elevations, except:




Figure: 10-057

11.5.4 At **FACE FRAME CONSTRUCTION**, reveal shall be 1/4" (6.4 mm) to 1" (25.4 mm) and shall be consistent across elevations.




Figure: 10-058

### 10.1 BASIC CONSIDERATIONS (continued)

11.5.5 At **LABORATORY APPLICATION**, reveal shall be 1/4" (6.4 mm) to 1" (25.4 mm) and shall be consistent across elevations.




Figure: 10-059

11.6 **CORNERS** created by adjoining casework will create non usable space.

11.7 **FINISHED ENDS** shall be **INTEGRAL**, not applied secondarily, except:

11.7.1 Applied end panels are allowed at Solid Phenolic casework.

11.8 **BASE/TOE** shall be **INTEGRAL** (constructed as an integral part of the cabinet body) or **SEPARATE** (constructed as a separate member) at the option of the manufacturer.

11.9 **STORAGE, JANITOR CLOSET, and/or UTILITY ROOM CABINETS** shall be built in conformance to **ECONOMY GRADE**, regardless of the overall project's Grade requirement, unless specified otherwise, except:

11.9.1 If specified material is **SOLID PHENOLIC, PREMIUM GRADE** shall be provided.

11.10 Surfaces behind **PRESENTATION PANELS** (such as white board or tack board) are treated as:

11.10.1 **SEMI-EXPOSED** at Economy Grade and Custom Grade.

11.10.2 **EXPOSED** at Premium Grade.

11.11 **TOE BASE HEIGHT VARIANCE** due to floor variations is not considered a defect. Casework is required to be installed level; shimming of the toe base, not to exceed 1/2" (12.7 mm), is acceptable. Floor variations exceeding 1/2" (12.7 mm) shall be corrected before cabinets are installed; however, correction of such is not the responsibility of the cabinet installer.

# SECTION 10

## Casework

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated,  
the rule applies to all Grades equally



## compliance requirements

### 10.2 SCOPE

- 1 All wood, high pressure decorative laminate (HPDL), and/or solid phenolic casework, cabinets, and components of face frame or frameless construction, fabricated complete in the manufacturer's facilities to field dimensions, as qualified below.
- 2 **TYPICAL INCLUSIONS:**
  - 2.1 Altars.
  - 2.2 Bars and back bars.
  - 2.3 Bulletin boards, built up.
  - 2.4 Bookcases, cabinets, carrels, counters, display cases, lecterns, and pulpits.
  - 2.5 Shelving, built up or machined and knocked down.
  - 2.6 Wardrobes.
  - 2.7 Modular cabinets.
  - 2.8 Cabinet doors.
  - 2.9 Clothes poles and supports.
  - 2.10 Shelf standards and rests.
  - 2.11 Track and hardware for sliding doors.
  - 2.12 Casters.
  - 2.13 File drawer rods and followers.
  - 2.14 Hinges.
  - 2.15 Drawer guides and slides.
  - 2.16 Pulls or knobs.
  - 2.17 Glass, mirrors, and glass doors (including hardware) that is integral to millwork.
  - 2.18 Filler panels, scribe strips, trim and moldings necessary for cabinet installation.
  - 2.19 Rough and finish hardware, which is part of the cabinet.
  - 2.20 Metal brackets and fittings, which are an integral part of the cabinet, unless specified elsewhere.
  - 2.21 Cut outs for sinks or similar units.
  - 2.22 Linoleum, vinyl, cork, or resilient covering integral to cabinet.
  - 2.23 Prefinishing, priming, painting, or sealing if so specified.
  - 2.24 Die walls that become integral to millwork.
  - 2.25 Soffit or fascia panels constructed from cabinet material.

### 10.2 SCOPE (continued)

- 3 **TYPICAL EXCLUSIONS:**
  - 3.1 Field installation, unless specified to be included in this scope of work.
  - 3.2 Cutting of holes for field applied vents, weeps, or grills, unless part of the cabinet.
  - 3.3 Fillers, build up, or sub tops for countertops, including tile and natural stone.
  - 3.4 Cutting for field applied hardware, unless part of the cabinet.
  - 3.5 Vinyl, rubber, or carpet base.
  - 3.6 Metal support brackets and fittings that are part of the building structure.
  - 3.7 Security panels, unless so specified.
  - 3.8 Tote trays (except at Cabinet Design Series) and base leveling adjusters, unless so specified.
  - 3.9 Furring, stripping, in wall blocking, grounds, or stub walls.
  - 3.10 Mirrors, glass, or glazing, unless part of the cabinet.
  - 3.11 Plumbing, electrical fixtures, and telephone equipment.
  - 3.12 Metal or ceramic tile for countertops.
  - 3.13 Sink rims.
  - 3.14 Special equipment housed in cabinets.
  - 3.15 Work not directly associated with the casework.
  - 3.16 Sliding presentation boards.
  - 3.17 Metal grills.
  - 3.18 Chalkboards and tack boards that are a part of the cabinet, with the necessary trim and trays.
  - 3.19 Easel trays of plastic or metal.
  - 3.20 Caulking of casework to work of others.

# SECTION 10

## Casework

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



## compliance requirements

### 10.3 DEFAULT STIPULATION

- 1 If not otherwise specified or indicated, all work shall be Custom Grade, frameless construction with adjustable shelves and Flush Overlay doors of unfinished close grain hardwood intended for an opaque finish, non premium priced standard pattern, color, and finish decorative laminate or solid phenolic, as covered by Sections 3 and 4, except: 
- 1.1 At **EXPOSED KNUCKLE HINGES**, defaulting to **REVEAL OVERLAY** is manufacturer's choice, and:
- 1.1.1 If reveal overlay the reveal shall be determined by the hinge overlay.

### 10.4 RULES

- 1 The following rules shall govern unless a project's contract documents require otherwise.
- 2 These rules are intended to provide a well defined degree of control over a project's quality of materials, workmanship, or installation.
- 3 **ERRATA**, published at <http://naaws-errata.com>, shall take precedence over these rules, subject to their date of posting and a project's bid date. 

10.4.4 Basic General Rules	
1	<b>AESTHETIC</b> grade rules apply only to exposed and semi-exposed surfaces visible after installation.
2	<b>WOODWORK</b> not addressed herein shall be manufactured from solid stock, laminated stock, veneered stock, or a combination thereof.
3	<b>LUMBER</b> shall conform to the requirements established in Section 3.
4	<b>SHEET PRODUCTS</b> shall conform to the requirements established in Section 4.
5	<b>BACKING SHEET</b> shall conform to the requirements established in Section 4.
6	<b>ALL MATERIALS</b> shall be securely attached/fastened/bonded.
Continues next column ▼	

10.4.4 Basic General Rules	
▲ From previous column	
7	<b>SURFACE CATEGORIES</b> Include:
7 1	<b>EXPOSED EXTERIOR</b> surfaces, defined as all exterior surfaces exposed to view, including:
7 1 1	All surfaces visible when doors and drawers are closed, including knee spaces.
7 1 2	Underside of cabinet bottoms over 42" (1067 mm) above the finished floor, including cabinet bottoms behind light valances and the bottom edge of light valances.
7 1 3	Cabinet tops under 80" (2032 mm) above the finished floor, or if 80" (2032 mm) and over and visible from an upper building level or floor.
7 1 4	Front edgeband of stretchers, ends, divisions, partitions, fixed shelves, tops, and bottoms.
7 1 5	Front edgeband of adjustable shelves exposed to view in open casework or behind transparent doors.
7 1 6	Sloping tops of cabinets that are visible.
7 2	<b>EXPOSED INTERIOR</b> surfaces, defined as all interior surfaces exposed to view in open casework or behind transparent doors, include:
7 2 1	Interior faces of shelves (both fixed and adjustable), divisions and partitions (edgeband is an Exposed Exterior Surface).
7 2 2	Interior face of ends (sides), backs, and bottoms (including pull outs).
7 2 3	Interior face of cabinet top members 36" (914 mm) or more above the finished floor.
7 2 4	Interior face doors and applied drawer fronts.
7 3	<b>SEMI-EXPOSED</b> surfaces, defined as those interior surfaces only exposed to view when doors or drawers are opened, include:
7 3 1	Interior faces and edgeband of adjustable shelves.
7 3 2	Divisions and partitions edgeband is an Exposed Exterior Surface).
7 3 3	Interior face of ends (sides), backs, and bottoms (including a bank of drawers).
7 3 4	Interior face of cabinet top members 36" (914 mm) or more above the finished floor.
7 3 5	Drawer box sides, sub fronts, backs, edgebanding, and bottoms.
Continues next column ▼	

# SECTION 10

## Casework

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



## compliance requirements

10.4.4		Basic General Rules
▲ From previous column		
7	<b>SURFACE CATEGORIES</b> (continued)	
7 3	<b>SEMI-EXPOSED</b> surfaces (continued)	
7 3 6	The underside of cabinet bottoms between 24" (610 mm) and 42" (1067 mm) above the finished floor.	
7 3 7	Security and dust panels or drawer stretchers.	
7 4	<b>CONCEALED</b> surfaces, defined as those exterior or interior surfaces that are covered or not normally exposed to view, include:	
7 4 1	Toe space unless otherwise specified.	
7 4 2	Sleepers, stretchers, and solid sub tops.	
7 4 3	The underside of cabinet bottoms less than 24" (610 mm) above the finished floor.	
7 4 4	The flat tops of cabinets 80" (2032 mm) or more above the finished floor, except if visible from an upper floor or building level.	
7 4 5	The three non visible edges of adjustable shelves.	
7 4 6	The underside of countertops, knee spaces, aprons and drawer boxes that are less than 36" (914 mm) above the finished floor.	
7 4 7	The faces of cabinet ends of adjoining units that butt together.	
<b>8 HARDWARE</b> shall:		
8 1	<b>CONFORM TO</b> ANSI/BHMA Standards (latest edition), <a href="http://buildershardware.com">http://buildershardware.com</a> , Grade 2 requirements with the exception of requiring "dynamic" load testing for a minimum of 50,000 cycles, and:	
8 1 1	<b>SCHOOLS</b> and <b>HOSPITAL</b> hinges shall be of all metal construction, meeting or exceeding the ANSI/BHMA (latest edition), <a href="http://buildershardware.com">http://buildershardware.com</a> , Grade 1 "performance" and "permanent set" test requirements..	
8 1 2	<b>DRAWER SLIDE TESTING</b> shall be based on a drawer slide nominal length of 22" or 550 mm mounted on a drawer box 22" (550 mm) in depth with a minimum width of 18" (457 mm) for load ratings up to 125 lbs (56.7 kg) and 24" (610 mm) for load ratings of 125 lbs (56.7 kg) and above, and:	
8 1 2 1	Slides not manufactured in lengths up to 22" (559 mm) shall be tested in their longest production length.	
8 1 3	<b>KEYBOARD TRAYS</b> shall conform to section 4.13 (Test 12, Drawers and Trays) of ANSI/BHMA A156.9 (latest edition), <a href="http://buildershardware.com">http://buildershardware.com</a> .	
Continues next column ▼		

10.4.4		Basic General Rules
▲ From previous column		
8	<b>HARDWARE</b> shall (continued)	
8 1	<b>CONFORM TO</b> (continued)	
8 1 4	<b>HINGES</b> shall have a minimum 110 degree of opening capacity.	
8 2	Be <b>FURNISHED</b> and <b>INSTALLED</b> per manufacturer's recommendations and as required to provide a complete casework assembly without impairment of the cabinet's structural integrity and/or functionality, and:	
8 2 1	Hardware shall not be mounted on, cut into or otherwise impair the usability of the top surface of fixed or adjustable shelves, and:	
8 2 1 1	Cabinet bottoms unless there is no other alternative.	
8 2 2	When fastener provisions are countersunk, fasteners shall be countersunk.	
8 3	Be of a <b>UNIFORM PLATED</b> BHMA 626 or similar <b>POWDER COATED</b> finish on exposed surfaces and:	
8 3 1	Conform to applicable ANSI/BHMA standards (latest edition), <a href="http://buildershardware.com">http://buildershardware.com</a> .	
8 3 2	Powder coat finish shall be of a chemical family with sufficient chemical/solvent resistance to not be affected by a rubdown of the solvents or cleaning materials used for final cleanup of the fabricated product, including removal of over spray, glue.	
8 3 3	Finishes will vary between manufacturers, and it can be expected to see variations from the same manufacturer between different production runs. These variations are not considered a defect, as long as they are compatible with the overall finish of the installed hardware.	
8 4	Have the <b>MANUFACTURER'S NAME</b> or unique brand marking stamped on hinges, slides, and locks for identification purposes.	
8 5	Be of <b>FIRST CLASS WORKMANSHIP</b> , free of manufacturing imperfections (such as tool or machine marks), and consistent in exposed finish appearance.	
Continues next column ▼		

# SECTION 10

## Casework

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



## compliance requirements

10.4.4		Basic General Rules
▲ From previous column		
8	HARDWARE shall (continued)	
8 6	At <b>LOCKS</b> , be furnished when indicated on the contract documents, and:	
8 6 1	Be designed to withstand a minimum of 50 lb (22.7 kg) pull force in the locked position.	
8 6 2	When specified ADA Accessible, shall comply with ADA Standards Section 4.13.9 requiring lever style operation.	
8 6 3	If non digital/electronic:	
8 6 3 1	Be keyed differently, only if so specified.	
8 6 3 2	Be master keyed, only if so specified.	
8 6 4	If digital/electronic, as applicable shall:	
8 6 4 1	Have non volatile memory (not lost with low battery or when battery is changed).	
8 6 4 2	Require standards AA or AAA battery operation (no battery packs) with minimum 10,000 lock cycle life, and:	
8 6 4 2 1	Have external battery replacement and/or external power override provisions.	
8 6 4 3	Be of cast or extruded metal construction with minimum 30,000 life cycle life expectancy.	
8 6 4 4	Have minimum 4 digit user access pin code and 5 digit master pin code.	
8 6 4 5	Single or multiple use access, if not specified shall be at manufacturers option.	
8 7	At <b>DRAWER SLIDES</b> shall conform to the following minimum type roller or ball bearing) and load capacity requirements:	
8 7 1	At drawer boxes 24" (610 mm) or less in width, either roller or ball bearing of:	
8 7 1 1	50 lbs (22.7 kg), at pencil drawers.	
8 7 1 2	75 lbs (34 kg), at general purpose drawers.	
8 7 1 3	100 lbs (45.4 kg) at file drawers.	
8 7 2	At drawer boxes over 24" (610 mm) in width, ball bearing of:	
8 7 2 1	50 lbs (22.7 kg), at pencil drawers.	
8 7 2 2	75 lbs (34 kg), at general purpose drawers.	
8 7 2 3	150 lbs (68 kg) at lateral file drawers 30" (762 mm) or less in width.	
8 7 2 4	200 lbs (91 kg), at lateral file drawers wider than 30" (762 mm), in width.	
8 7 3	Side/slide Systems must be specified.	
Continues next column ▼		

10.4.4		Basic General Rules
▲ From previous column		
8	HARDWARE shall (continued)	
8 8	At <b>SHELF RESTS</b> for bored holes, either include a minimum of 0.1969" (5 mm) metal pin or double 0.1969" (5 mm) plastic pins (meeting ANSI/BHMA, (latest edition), <a href="http://buildershardware.com">http://buildershardware.com</a> Grade 1 requirements) and:	
8 8 1	Meet or exceed these standards' maximum shelf load requirement of 200 lbs (91 kg).	
8 9	At <b>POCKET DOOR HARDWARE</b> , cabinet doors shall be a maximum of 23-5/8" (600 mm) in width and the maximum door height and weight shall be within the manufacturer's listed capacity.	
8 10	At <b>BASE ADJUSTERS</b> shall be of the adjustable screw type, having a floor bearing surface of at least 1-1/8" (28.6 mm) in diameter at each foot, and:	
8 10 1	Shall provide for leveling the cabinet from inside of the case through holes in the cabinet bottom with cover caps.	
8 11	<b>MULTIPLE HARDWARE OPTIONS</b> , when specified, shall be the manufacturer's choice.	
9 At <b>CABINET LIGHTING</b> , shall:		
9 1	Be low voltage LED (light emitting diode), and:	
9 1 1	Be compliant to UL 2108 as sponsored by Underwriters Laboratories, <a href="http://ulstandards.ul.com/standard/?id=8750">http://ulstandards.ul.com/standard/?id=8750</a> , with UL Class 2 double insulated appliance wire and Level IV power supply efficiency rating.	
9 1 2	Be UL (Underwriters Laboratories) listed with "e" number provided which can be verified at: <a href="http://database.ul.com/cgi-bin/XYV/template/LISEXT/1FRAME/gfilebr.html">http://database.ul.com/cgi-bin/XYV/template/LISEXT/1FRAME/gfilebr.html</a>	
9 1 3	Be Title 24 Compliant, California Energy Commission, <a href="http://www.title24energy.com/">http://www.title24energy.com/</a> , with a minimum 90 CRI (color rendering index) value.	
9 1 4	Have a minimum 30,000 hour life rating at L70 (70% of remaining original intensity) in accordance with the LM80 standard as sponsored by the US Department of Energy, <a href="http://www.energy.gov">http://www.energy.gov</a>	
Continues next column ▼		

# SECTION 10

## Casework

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



## compliance requirements

10.4.4		Basic General Rules	
▲ From previous column			
9		At <b>CABINET LIGHTING</b> , shall (continued)	
9	1	Be low voltage <b>LED</b> (light emitting diode) (continued)	
9	1	5	Be compliant with NFPA 70 (National Fire Protection Association, <a href="http://www.nfpa.org/">http://www.nfpa.org/</a> ), Article 410.16, A, B and C
9	1	6	With the exception of ribbon and puck configuration, be of aluminum heat sink construction.
9	1	7	Have a maximum operating voltage of 24 volts with UL Class 2 rated and listed power supplies, <a href="http://www.ul.com/">http://www.ul.com/</a>
9	1	8	For spot lighting, have a minimum 25 degree light spread.
9	1	9	For flood lighting have a minimum 90 degree light spread.
			Color range if not specified shall be at manufacturers option, including:
			Cool White at 5,000 k
			Neutral White at 4,000 k
			Warm White at 3,000 k
			Extra Warm White at 2,700 K
10	<b>CASEWORK</b> shall be:		
10	1	Assembled complete by the manufacturer, with doors, drawers, and hardware installed.	
10	2	Assembled with mechanical fasteners and adhesive.	
10	3	Free of adhesive over spray, fabrication marks, and debris.	
11	<b>PANEL COMPONENTS</b> shall be:		
11	1	Constructed of particleboard, MDF, or a non telegraphing core.	
11	2	Of balanced construction, constructed in such a way as not to warp in its intended use.	
12	<b>FRAMELESS CONSTRUCTION</b> requires self edging of adjoining units be beveled a maximum of 15° for the thickness of the edgebanding, and if adjoined, the total beveled "V" shall not exceed 30°.		
13	<b>SEPARATELY APPLIED COUNTERTOPS</b> are required at base cabinets 48" (1220 mm) or less in height.		
Continues next column ▼			

10.4.4		Basic General Rules	
▲ From previous column			
14	<b>STORAGE, JANITOR, CLOSET, and UTILITY ROOM CABINETS</b> shall be of hardboard, particleboard, MDF, or decorative laminate, at the manufacturer's choice.		E C P
15	<b>CABINETS OVER 72"</b> (1829 mm) high (excluding wardrobe cabinets) not abutting a structural wall or another cabinet on either side shall have a fixed shelf approximately mid height, and:		
15	1	At seismic compliant construction, have a fixed shelf and anchor strip approximately mid height, and:	
15	1	1	Anchor strip and back shall be securely fastened to the fixed shelf with #10 x 2-1/2" (50.8 mm) screws a maximum of 7" (178 mm) on center.
16	<b>SLIDING PRESENTATION BOARDS</b> require an integral stop be provided within the top and bottom track to prevent their stopping against the casework.		
17	<b>GLUING or LAMINATION</b> shall be in accordance with the <b>ADHESIVE GUIDELINES</b> within the <b>APPENDIX</b> , and:		
17	1	<b>DELAMINATION or SEPARATION</b> shall not occur.	
17	2	<b>LUMBER</b> shall conform to the requirements established in Section 3.	
17	3	<b>SHEET PRODUCTS</b> shall conform to the requirements established in Section 4.	
18	<b>PRE-FINISHING</b> of wood faced casework requires wall abutting surfaces shall be factory sealed with two coats at 2 mil dry.		E C P
19	<b>CUT OUTS</b> in <b>HPDL</b> shall have a minimum 1/4" (6.4 mm) radius at inside corners.		
20	<b>CATHEDRAL</b> type figure shall be achieved by:		
20	1	A single component in "AA" Face Grade.	
20	2	The split heart method in Face Grades "A - D", and:	
20	2	1	Each half of a split heart shall be subject to the minimum component width requirements for Face Grade "B".
Continues next column ▼			

# SECTION 10

## Casework

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



## compliance requirements

10.4.4		Basic General Rules	
<b>▲ From previous column</b>			
21	At cabinet doors with <b>GLASS LIGHTS</b> , the exposed groove the glass sits in is considered an Exposed Interior Surface.		
22	If <b>ANTIMICROBIAL SURFACE</b> is required, it shall be:		
22 1	Within the United States, EPA, <a href="http://epa.gov">http://epa.gov</a> , registered for public health use.		
22 2	Within Canada, Health Canada, <a href="http://hc-sc.gc.ca">http://hc-sc.gc.ca</a> , recognized as having market authorization because of its granted Drug Identification Number (DIN).		
23	<b>FIRST CLASS WORKMANSHIP</b> is required in compliance with these standards.		

10.4.5		Basic Material Rules	
1	<b>GRAIN</b> or <b>DIRECTIONAL PATTERNED</b> sheet products:		
1 1	Shall run either vertically or horizontally at the manufacturer's choice, and:	<b>E</b>	<b>C</b> <b>P</b>
1 1 1	Drawer fronts shall run either vertically or horizontally for the entire project.	<b>E</b>	<b>C</b> <b>P</b>
1 2	Shall run and match vertically within each cabinet unit, including doors, drawers, false fronts, and finished ends.	<b>E</b>	<b>C</b> <b>P</b>
1 3	Shall run and match vertically and horizontally within each cabinet unit, including doors, drawers, false fronts, and:	<b>E</b>	<b>C</b> <b>P</b>
1 3 1	Cathedral grain shall have the crown pointing up and run the same direction for the entire project.	<b>E</b>	<b>C</b> <b>P</b>
1 3 2	Shall be well matched for color and grain across multiple cabinet faces in each room.	<b>E</b>	<b>C</b> <b>P</b>
1 3 3	Wood veneer blueprint or sequencing requirement for cabinet elevation must be so specified.		
2	<b>LIGHT VALANCE</b> bottom edge shall be considered an exposed surface.		
3	<b>VINYL</b> covered material is acceptable for cabinet construction.	<b>E</b>	<b>C</b> <b>P</b>
4	<b>GLASS SHELVES</b> shall be tempered or laminated safety glass, with all four edges polished.		
5	<b>SEMI-EXPOSED</b> surfaces, require:		
5 1	Consistent color or species to be used throughout entire project.		
5 2	Matching to exposed surface is only required if so specified.		
5 3	Vinyl overlay is acceptable at cabinet backs if matched in color to other semi-exposed materials.		
5 4	Hardboard used as vertical or horizontal shelves and/or dividers shall be tempered and smooth on both sides, and:	<b>E</b>	<b>C</b> <b>P</b>
5 4 1	Painted to match other semi-exposed portions is only required if so specified.	<b>E</b>	<b>C</b> <b>P</b>
5 5	Vertical or horizontal shelves and/or dividers shall match other semi-exposed surfaces.	<b>E</b>	<b>C</b> <b>P</b>
<b>Continues next column ▼</b>			

# SECTION 10

## Casework

GENERAL/**PRODUCT**/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally

<b>E</b>	<b>C</b>	<b>P</b>
----------	----------	----------

## compliance requirements

10.4.5 Basic Material Rules	
▲ From previous column	
6	<b>CONCEALED</b> surfaces shall be the manufacturer's choice:
6 1	If specifications require a moisture resistant base, base components shall be material complying with the base cabinet submersion test, as explained in the <b>APPENDIX</b> .
<p><b>Specific PRODUCT Requirements for Wood Faced, HPDL faced, Solid Phenolic and Laboratory Casework may be found in Annex A, B, C and/or D which may be found at the end of this PRODUCT portion of Section 10.</b></p> 	

10.4.6 Basic Machining Rules	
1	Of <b>EXPOSED</b> and <b>SEMI-EXPOSED</b> surfaces shall comply with:
1 1	<b>SMOOTHNESS</b> requirements (see Item 5.1 in Tests) for:
1 1 1	<b>SHARP EDGES</b> to be eased with fine abrasive. <b>E C P</b>
1 1 2	<b>TOP FLAT</b> wood surfaces; those that can be sanded with a drum or wide belt sander:
1 1 2 1	Minimum 15 KCPI or 100 grit sanding. <b>E C P</b>
1 1 2 2	120 grit sanding. <b>E C P</b>
1 1 2 3	150 grit sanding. <b>E C P</b>
1 1 3	<b>PROFILED</b> and shaped wood surfaces:
1 1 3 1	Minimum 15 KCPI or 100 grit sanding. <b>E C P</b>
1 1 3 2	Minimum 20 KCPI or 120 grit sanding. <b>E C P</b>
1 1 3 3	120 grit sanding. <b>E C P</b>
1 1 4	<b>TURNED</b> wood surfaces:
1 1 4 1	Minimum 15 KCPI or 100 grit sanding. <b>E C P</b>
1 1 4 2	120 grit sanding. <b>E C P</b>
1 1 4 3	180 grit sanding. <b>E C P</b>
1 1 5	<b>CROSS SANDING</b> , excluding turned surfaces:
1 1 5 1	Is not a defect. <b>E C P</b>
1 1 5 2	Is not permitted. <b>E C P</b>
1 1 6	<b>TEAR OUTS, KNIFE NICKS, or HIT OR MISS</b> machining is not permitted.
1 1 7	<b>KNIFE MARKS</b> are not to be permitted where sanding is required.
1 1 8	<b>GLUE or FILLER</b> , if used, to be inconspicuous and match the adjacent surface for smoothness.
Continues next column ▼	


# SECTION 10



## Casework


GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally

**E C P**

## compliance requirements

10.4.6				Basic Machining Rules			
▲ From previous column							
1 Of EXPOSED and SEMI-EXPOSED surfaces (continued)							
1 2 HPDL, PVC, and PRE-FINISHED WOOD edges shall be machined flush and filed, sanded, or buffed to remove machine marks and sharp edges, and:							
1 2 1 OVERLAP (See Test F illustrations in TESTS) such as							
 <p>shall not exceed:</p>							
1	2	1	1	0.005" (0.13 mm) for a maximum length of 2" (50.8 mm) in any 12" (305 mm) run.	E	C	P
1	2	1	2	0.005" (0.13 mm) for a maximum length of 1" (25.4 mm) in any 24" (610 mm) run.	E	C	P
1	2	1	3	0.003" (0.08 mm) for a maximum length of 1" (25.4 mm) in any 48" (1220 mm) run.	E	C	P
1 2 2 CHIP OUT, (See Test G illustrations in TESTS) at areas such as,							
 <p>shall be inconspicuous when viewed at:</p>							
1	2	2	1	72" (1829 mm).	E	C	P
1	2	2	2	48" (1220 mm).	E	C	P
1	2	2	3	24" (610 mm).	E	C	P
Continues next column ▼							

10.4.6				Basic Machining Rules			
▲ From previous column							
1 Of EXPOSED and SEMI-EXPOSED surfaces (continued)							
1 2 HPDL, PVC, and PRE-FINISHED WOOD edges (continued)							
1 2 3 OVER MACHINED (See Test H illustrations in TESTS) removal of color or pattern of face material such as,							
 <p>shall be limited to:</p>							
1	2	3	1	3/32" x 6" (2.4 mm x 152 mm) and may not occur within 48" (1220 mm) of a similar occurrence.	E	C	P
1	2	3	2	1/32" x 4" (0.8 mm x 102 mm) and may not occur within 60" (1524 mm) of a similar occurrence.	E	C	P
1	2	3	3	1/32" x 1-1/2" (0.8 mm x 38.1 mm) and may not occur within 72" (1829 mm) of a similar occurrence.	E	C	P



# SECTION 10




## Casework



GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally

**E C P**

# compliance requirements

10.4.7		Basic Assembly Rules				
1		<b>THESE STANDARDS</b> do not establish Grade rules for joint flushness and or gap tolerances for woodwork products installed in a non climate controlled environment: however:				
1	1	Prior to installation, the flushness and/or gap tolerances of woodwork products intended for non climate controlled environments shall meet the test requirements herein.				
2		<b>JOINTS</b> at assembled woodwork shall:				
2	1	Be neatly and accurately made.				
2	2	Be securely glued, with:				
2	2	1	Adhesive residue removed from exposed and semi-exposed surfaces.			
2	3	Require <b>FLUSHNESS VARIATIONS</b> at exposed and semi-exposed surfaces (see Test D illustrations in Tests) when mitered or butted such as,				
						
		not to exceed:				
2	3	1	0.025" (0.64 mm).	E	C	P
2	3	2	0.015" (0.38 mm).	E	C	P
2	3	3	0.010" (0.25 mm).	E	C	P
2	4	<b>FIXED HORIZONTAL</b> cabinet members, including tops and bottoms, shall be either flush or set back a maximum of 5/64" (2.0 mm) at their intersection with vertical members and shall be uniform throughout the room,				
						
		and:				
2	4	1	Radius, beveled or square edges and ends are allowed at horizontal and vertical members;			
						
		provided:				
<b>Continues next column ▼</b>						

10.4.7		Basic Assembly Rules							
<b>▲ From previous column</b>									
2		<b>JOINTS</b> (continued)							
2	4	<b>FIXED HORIZONTAL</b> (continued)							
2	4	1	Radius or square edges and ends (continued)						
			The "V" or gap that is formed where a member with a square end meets a member with a radius						
									
		does not exceed:							
2	4	1	1	0.031" (0.78 mm).	E	C	P		
2	4	1	2	0.015" (0.38 mm).	E	C	P		
2	4	1	3	0.007" (0.17 mm).	E	C	P		
2	4	1	2	The core of the square edge member is not visible.					
2	4	1	3	The "V" or gap is uniform throughout the room.					
2	5	Require <b>GAPS</b> at exposed and semi-exposed surfaces (see Test A illustrations in Tests) when mitered or butted such as:							
									
		at:							
2	5	1	0.025" (0.64 mm) wide by 20% of the joint length.				E	C	P
2	5	2	0.015" (0.38 mm) wide by 20% of the joint length.				E	C	P
2	5	3	0.010" (0.25 mm) wide by 20% of the joint length.				E	C	P
<b>Continues next column ▼</b>									

# SECTION 10



## Casework


GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



# compliance requirements

10.4.7		Basic Assembly Rules				
▲ From previous column						
2	JOINT (continued)					
2	6	Require <b>GAPS</b> at exposed and semi-exposed surfaces (see Test B illustrations in Tests) at parallel members such as:				
						
		not to exceed:				
2	6	1	0.025" x 9" (0.64 mm x 229 mm) and shall not occur within 48" (1220 mm) of a similar gap in the same joint.	E	C	P
2	6	2	0.015" x 6" (0.38 mm x 152 mm) and shall not occur within 60" (1524 mm) of a similar gap in the same joint.	E	C	P
2	6	3	0.010" x 4" (0.25 mm x 102 mm) and shall not occur within 72" (1829 mm) of a similar gap in the same joint.	E	C	P
2	7	Require <b>GAPS</b> at exposed and semi-exposed surfaces (see Test C illustrations in Tests) when mitered or butted such as,				
						
		not to exceed:				
2	7	1	0.025" (0.64 mm).	E	C	P
2	7	2	0.015" (0.38 mm).	E	C	P
2	7	3	0.010" (0.25 mm).	E	C	P
2	8	Allows use of <b>FILLER</b> :				
2	8	1	If inconspicuous when viewed at 36" (914 mm).	E	C	P
2	8	2	If inconspicuous when viewed at 24" (610 mm).	E	C	P
2	8	3	<b>NOT ALLOWED.</b>	E	C	P
Continues next column ▼						

10.4.7		Basic Assembly Rules							
▲ From previous column									
2	JOINT (continued)								
2	9	<b>SHEET</b> and <b>LAMINATED LUMBER PANELS</b> shall be allowed to move, float, expand or contract in reaction to ambient humidity changes.							
3	Require <b>FLATNESS</b> of installed and removable sheet products (see Test E illustrations in Tests)								
									
		not to exceed:							
3	1	0.045" (1.1 mm) per 12" (305 mm) or portion thereof.	E	C	P				
3	2	0.030" (0.8 mm) per 12" (305 mm) or portion thereof.	E	C	P				
3	3	0.020" (0.5 mm) per 12" (305 mm) or portion thereof.	E	C	P				
4	<b>JOINERY</b> , other than that provided for within Section 10, is permitted, provided it is fully documented in a text/illustration explanation, and each material application has been independently tested to show compliance to the minimum requirements of the Cabinet Structural Integrity Tests within the <b>APPENDIX</b> . 								
5	<b>BOTTOM EDGES</b> of drawer fronts and aprons at knee spaces shall be edgebanded. <table border="1" style="float: right;"><tr><td>E</td><td>C</td><td>P</td></tr></table>						E	C	P
E	C	P							
6	<b>VISIBLE EDGES</b> requires (see Doors and Drawer Fronts, within this Product portion, for additional requirements), and:								
6	1	At adjustable shelves, only the front edge to be edgebanded.							
6	2	The bottom edge of the end of upper cabinets to be edgebanded.							
6	3	The <b>TOP EDGE</b> of the cabinet ends, when visible from above, shall be edgebanded to match the exposed exterior surface.	E	C	P				
6	4	<b>EDGEBANDING</b> to run parallel to the long direction of the edge regardless of grain and/or pattern.							
6	5	<b>DADOES</b> or <b>LOCK JOINTS</b> shall not run through the edgeband.	E	C	P				
6	6	<b>TEE BANDING</b> must be so specified.							
Continues next column ▼									

# SECTION 10


## Casework

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



## compliance requirements

10.4.7		Basic Assembly Rules				
▲ From previous column						
7	1	DRAWERS (including trays and sliding bins) requires:				
7	1	Components to be of the same material and color for the entire project, and:				
7	1	1	Bottoms may be vinyl if matching in color.			
7	2	SIDES to be manufacturer's choice, and shall be:				
7	2	1	Nailed to sub fronts and backs. <span style="float: right;">E C P</span>			
7	2	2	Rabbeted to the fronts or sub fronts and backs. <span style="float: right;">E C P</span>			
7	2	3	Miter folded sides, back, front, and bottom, with:			
						
7	2	3	1	Core of particleboard or medium density fiberboard.		
7	2	3	2	Side directional grain or pattern running horizontal.		
7	2	4	Multiple dovetailed, which is limited to solid wood or minimum 7-ply hardwood veneer core plywood with exposed core, without additional mechanical fasteners. <span style="float: right;">E C P</span>			
7	2	5	Doweled or Dowel screwed. <span style="float: right;">E C P</span>			
7	2	6	Biscuit splined. <span style="float: right;">E C P</span>			
7	2	7	Lock jointed and nailed. <span style="float: right;">E C P</span>			
7	3	At <b>FLUSH OVERLAY</b> construction without sub front, sides to be blind dovetail dadoed to the front.				
7	4	Minimum of two mechanical fasteners (dowels, biscuit splines, nails, screws) per joint, and:				
7	4	1	A maximum of 3" (76 mm) on center for biscuit splines, nails, or screws.			
7	4	2	A maximum of 1-1/4" (32 mm) on center for joints up to 4" (102 mm) in length and 2-1/2" (64 mm) on center for joints over 4" (102 mm) in length for dowels.			
7	5	JOINTS to be securely glued.				
Continues next column ▼						

10.4.7		Basic Assembly Rules				
▲ From previous column						
7	DRAWERS (continued)					
7	6	To be <b>PROPERLY FITTED</b> to the cabinet without excessive play, and:				
7	6	1	Fit front to back, less a maximum of 2" (50.8 mm) of interior cabinet depth.			
7	6	2	Fill opening top to bottom to the greatest extent possible, while remaining fully functional.			
7	7	SLIDES to operate smoothly.				
7	8	CLOSING STOPS are to be provided at the rear of both drawer sides, unless such is built into the slides to prevent the drawer front from impacting the cabinet body, and:				
7	8	1	STOP SILENCERS are not permitted.			
7	9	SPRING LOADED TIP DOWN STOPS to be provided (design permitting) to prevent the drawer from pulling out of the cabinet, unless such is built into the drawer slides.				
7	10	FILE DRAWERS require:				
7	10	1	Full extension slides.			
7	10	2	CLEAR INSIDE HEIGHT sufficient for hanging file folder tabs.			
7	10	3	File direction of manufacturer's choice.			
7	10	4	System stand or rails shall be at option of the manufacturer, and:			
7	10	4	1	At legal sized drawers they shall accommodate both legal and letter sized files.		
7	11	LOCKS to be furnished only where shown on contract documents, unless specifications denote specific location requirements, and:				
7	11	1	They shall withstand a minimum of 50 lb (22.7 kg) pull force in the locked position, and:			
7	11	1	1 Strikes are required.			
7	11	2	Security or dust panels are required at locked banks of drawers when each drawer is keyed differently.			
7	12	TRAYS, BINS and similar items shall be similarly constructed.				
Continues next column ▼						



# SECTION 10

## Casework



GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



## compliance requirements

10.4.7		Basic Assembly Rules				
▲ From previous column						
7	13	DRAWERS (continued)				
7	13	FRONTS and FALSE FRONTS shall:				
7	13	1	Match the cabinet doors, except:			
7	13	1	1 Where the drawer and false fronts are too small to allow a match.			
7	13	2	Be securely attached to drawer sub front with pan/binder head, countersunk flathead, or ovalhead screws with a minimum of two screws at each end a maximum of 1-1/2" (38.1 mm) from the inside corners of the drawer box and a maximum of 12" (305 mm) on center, and:			
7	13	2	1 Fasteners used to attach drawer pulls or knobs through both the sub front and drawer front shall be considered a fastener.			
7	13	3	At false fronts, be securely attached to the cabinet body.			
7	14	BOTTOMS, excluding integral miter folded, shall:				
7	14	1	Be plowed into sides, fronts, or sub fronts, and:			
7	14	1	1 Be securely glued or glue blocked to form a rigid unit.			
7	14	1	2 Plow to be a minimum of 3/8" (9.5 mm) from the bottom of the drawer sides, front, or sub front.			
7	14	2	Be securely attached to the drawer box back, either by plow or if run through, by mechanical fastening (maximum of 4" [102 mm] on center) .	E	C	P
7	14	3	If 1/2" (12.7 mm) or greater in thickness, they are not required to be plowed into drawer fronts or sub fronts with the use of integral metal drawer side/slide systems; however:			
7	14	3	1 If surface applied, be mechanically fastened (maximum of 4" [102 mm] on center) to the entire box.	E	C	P
Continues next column ▼						

10.4.7		Basic Assembly Rules				
▲ From previous column						
8	DOORS requires:					
8	1	FLUSH OVERLAY is the default for either FRAMELESS or FACE FRAME casework, except:				
8	1	1	At EXPOSED KNUCKLE HINGES, defaulting to REVEAL OVERLAY is at the option of the manufacturer, and:			
8	1	1	1 If reveal overlay, the reveal shall be determined by the hinge overlay.			
8	2	At BACK BEVELED DOORS, edgebanding:				
8	2	1	Is not required.	E	C	P
8	2	2	Is required.	E	C	P
8	3	CORE THICKNESS to be a minimum of 11/16" (17.5 mm).				
8	4	MAXIMUM SINGLE CABINET DOOR SIZE at:				
8	4	1	VERTICAL hinge axis openings shall be 24" (610 mm) in width and 84" (2134 mm) in height, and:			
8	4	1	1 Larger doors are more susceptible to warp, which shall not be the responsibility of the manufacturer/installer.			
8	4	2	HORIZONTAL hinge axis openings shall be 48" (1219 mm) in width and 24" (610 mm) in height.			
8	5	DOOR THICKNESS of 1-3/8" (34.9 mm) or greater be governed by Section 9.				
8	6	STOP SILENCERS to be installed at the top and bottom of hinged cabinet doors (on the closing edge) to properly align the door and silence its closing.		E	C	P
8	7	CORE to be of an approved particleboard or medium density fiberboard, and:				
8	7	1	Veneer, OSB, or lumber cores are not guaranteed against warping, telegraphing, or delamination.			
Continues next column ▼						

# SECTION 10


## Casework

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



## compliance requirements

10.4.7		Basic Assembly Rules	
▲ From previous column			
8 DOORS requires (continued)			
8	8	LOCKS to be furnished <b>ONLY</b> where shown on cabinet elevations of contract documents, unless specifications denote specific location requirements, and:	
8	8	1 Shall withstand a minimum of 50 lb (22.7 kg) pull force in the locked position, and:	
8	8	1 1 Strikes are required.	
8	8	2 Strikes are required at spring loaded latches, except:	
8	8	2 1 When automatic latches are used.	
8	9	GLASS shall be clear laminated or tempered.	
8	9	1 Stops shall:	
8	9	1 1 Be continuous, removable, on inside only, and:	
		Glass clips are permitted, with a minimum of 6 per door.	
8	9	1 1 	
8	9	1 2 For opaque finish, be synthetic or solid stock of the manufacturer's choice.	
8	9	1 3 For transparent finish, be synthetic or solid stock of compatible species to adjacent surface and compatible color to the Exposed Interior surface.	
8	9	1 4 For decorative laminate, be synthetic or solid stock and compatible color to Interior Exposed surface.	
8	9	1 5 Exposed rabbet shall be compatible color painted or finished to the Interior Exposed surface.	
8	10	When <b>HINGED</b> :	
8	10	1 Doors shall stop, as applicable, against the cabinet body at the bottom (except at handicapped units), sides, and top stretcher; however:	
8	10	1 1 Flush inset doors, a positive stop or hardware member acting as such is permitted, and:	
8	10	1 1 1 Stops shall be provided at both sides of the door opening.	E C P
8	10	1 2 Paired doors below a drawer require a rail, stretcher, or partition (full or partial) be provided.	E C P
Continues next column ▼			

10.4.7		Basic Assembly Rules	
▲ From previous column			
8 DOORS (continued)			
8	10	When <b>HINGED</b> (continued)	
8	10	2 Hinges shall be installed by the manufacturer, and shall:	
8	10	2 1 Operate properly without binding.	
8	10	2 2 Align horizontally, when adjacent and exposed.	
8	10	2 3 Be self closing or provided with a catch.	E C P
8	10	2 4 At <b>Grade I</b> hinges, doors:	
8	10	2 4 1 Under 48" (1220 mm) in height shall have a minimum of two hinges.	
8	10	2 4 2 48" (1220 mm) to 84" (2134 mm) height shall have a minimum of three hinges.	
8	10	2 4 3 Over 84" (2134 mm) in height shall have a minimum of four hinges.	
8	10	2 5 At <b>Grade II</b> hinges, doors:	
8	10	2 5 1 Under 40" (1016 mm) in height shall have a minimum of two hinges.	
8	10	2 5 2 40" (1016 mm) to 60" (1524 mm) in height shall have a minimum of three hinges.	
8	10	2 5 3 60" (1524 mm) to 80" (2032 mm) in height shall have a minimum of four hinges.	
8	10	2 5 4 Over 80" (2031 mm) in height shall have a minimum of five hinges and an additional hinge for every 18" (457 mm) of additional height.	
Continues next column ▼			



# SECTION 10




## Casework

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally

**E C P**

## compliance requirements

10.4.7 Basic Assembly Rules			
▲ From previous column			
8	DOORS	requires	(continued)
8	10	When HINGED	(continued)
8	10	2	Hinges shall be installed (continued)
			At <b>FLUSH OVERLAY</b> construction, wrap around hinges shall be let into the edge of the door to maintain proper gap
			
8	10	2	6
			tolerance, and:
8	10	2	6
1			Exposed door edges resulting from the notching for hinges are not required to be finished. <span style="float: right;">E C P</span>
8	10	2	6
2			Exposed door edges resulting from the notching for hinges are required to be painted or stained to match. <span style="float: right;">E C P</span>
			<b>REVEAL OVERLAY</b> construction, wrap around hinges are not required to be let into the edge of the door,
			
8	10	2	7
			and:
			The reveal shall be determined by the hinge overlay.
			
8	10	2	7
1			
Continues next column ▼			

10.4.7 Basic Assembly Rules			
▲ From previous column			
8	DOORS	requires	(continued)
8	10	When HINGED	(continued)
8	10	2	Hinges shall be installed (continued)
8	10	2	8
			<b>CONCEALED CUP HINGE</b> assembly installation, when required to be installed with screws, requires dowel/euro screws or screws recommended by the manufacturer.
8	10	3	<b>LOCKING PAIRS SHALL:</b>
8	10	3	1
			Be equipped with an automatic releasing latch or use of an elbow catch/latch and a stop block on the inactive leaf, and:
8	10	3	2
			At tall storage cabinets with full height doors and fixed mid height shelf shall be equipped with elbow catch/latch and stop block on the inactive leaf at the fixed shelf.
8	10	3	3
			At tall storage cabinets full height doors; however, without fixed mid height shelf shall be equipped with spring actuated chain bolt with shelf depth adjusted accordingly.
8	10	3	4
			Require stop block shall be adequate to prevent the latch of the elbow catch/latch from being defeated by applying vertical pressure on the door.
8	11	When <b>STILE</b> and <b>RAIL CONSTRUCTION</b> (see the Hinged and Sliding sub headings for additional requirements as applicable):	
8	11	1	<b>STILES and RAILS:</b>
8	11	1	1
			Molded profile (sticking) shall be the manufacturer's choice, unless specified otherwise.
8	11	1	2
			Solid lumber shall be a minimum of 2-1/2" (63.5 mm) in width.
8	11	1	3
			Shall be a minimum of 3/4" (19 mm) in thickness, and:
8	11	1	3
1			To a tolerance of +/- 1/32" (0.8 mm) of specified thickness.
8	11	1	4
			Veneered or overlaid construction shall be MDF or particleboard core a minimum of 3-1/2" (88.9 mm) in width, and:
8	11	1	4
1			With approval, framed glass doors may be manufactured from flush panels without stile and rail considerations, provided all other door requirements are met, and:
8	11	1	4
1			1
			All exposed edges shall be edgebanded or finished to match adjacent surfaces.
8	11	1	5
			Doors over 60" (1524 mm) in height shall have an intermediate rail.
Continues next column ▼			

# SECTION 10

## Casework

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally

**E C P**

## compliance requirements

10.4.7		Basic Assembly Rules			
▲ From previous column					
8	DOORS requires (continued)				
8	11	When <b>STILE</b> and <b>RAIL CONSTRUCTION</b> (continued)			
8	11	1	<b>STILES</b> and <b>RAILS</b> (continued)		
8	11	1	6	Stiles shall run the full height of the door, and:	
8	11	1	6	1	Rails, including top, cross, and bottom shall run between stiles. E C P
8	11	1	6	2	Mullions shall run between rails. E C P
8	11	1	7	Grain or directional pattern shall run vertically on stiles and horizontally on rails.	
8	11	1	8	Clearance shall be a minimum of 3/8" (9.5 mm) between hardware machining and glass cutout.	
8	11	1	9	Joinery shall be:	
8	11	1	9	1	The manufacturer's choice. E C P
8	11	1	9	2	Mating male/female sticking glued under pressure. E C P
8	11	1	9	3	Mortise and tenon, dowels or loose tenon glued under pressure. E C P
8	11	2	<b>PANEL:</b>		
8	11	2	1	Direction of grain or pattern shall be the manufacturer's choice. E C P	
8	11	2	2	Direction of grain or pattern shall run vertically, and: E C P	
8	11	2	2	1	Adjacent door panels for transparent finish shall have a pleasing match for color and grain. E C P
8	11	2	3	Core shall be covered by veneer, overlay, or rim banding.	
8	11	2	4	When flat shall be a minimum of 1/4" (6.4 mm) in thickness, and:	
8	11	2	4	1	Edge glued solid lumber is permitted if at least 1/2" (12.7 mm) in thickness and width across grain is 13-3/4" (350 mm) or less. E C P
8	11	2	4	2	Solid lumber is not permitted. E C P
Continues next column ▼					

10.4.7		Basic Assembly Rules			
▲ From previous column					
8	DOORS requires (continued)				
8	11	When <b>STILE</b> and <b>RAIL CONSTRUCTION</b> (continued)			
8	11	2	<b>PANEL</b> (continued)		
8	11	2	5	When raised shall be a minimum of 1/2" (12.7 mm) in thickness, and:	
8	11	2	5	1	Edge glued solid lumber is permitted for panels less than 13-3/4" (350 mm) in width across grain. E C P
8	11	2	5	2	Solid lumber is not permitted for panels. E C P
8	11	2	5	3	Solid lumber is permitted for rimming panels if mitered and glued under pressure.
8	11	2	6	Regardless of retention method, shall have the freedom and room to expand and contract in reaction to ambient humidity changes.	
8	11	2	7	Applied moldings shall be spot glued and finish nailed.	
8	12	When <b>SLIDING:</b>			
8	12	1	Thickness to be a minimum of:		
8	12	1	1	1/4" (6.4 mm) for doors 24" (610 mm) and under in height.	
8	12	1	2	3/4" (19 mm) for doors over 24" (610 mm) in height.	
8	12	2	Vertical edges are considered exposed.		
8	12	3	Top and bottom edges are concealed and not required to be edgebanded or filled.		
8	12	4	Doors more than 1.5 times as tall as they are wide shall be mounted with overhead metal track and roller hanger to prevent tipping and binding.		
8	12	5	At hanging track systems, exposed track is acceptable and door heights of:		
8	12	5	1	36" (914 mm) or less shall be equipped with adequate top and/or bottom guides or runs. Sliding doors in excess of 36" (914 mm) in height shall be installed on hardware of a type optional with the manufacturer. E C P	
8	12	5	2	34" (864 mm) or less shall be installed on the appropriate fiber or metal track, with top guide. E C P	
8	12	5	3	Over 34" (864 mm) shall be installed on either the overhead metal track with nylon roller hangers, or the metal bottom track with sheaves and top guide. E C P	
Continues next column ▼					

# SECTION 10

## Casework

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally

<b>E</b>	<b>C</b>	<b>P</b>
----------	----------	----------

## compliance requirements

10.4.7		Basic Assembly Rules						
▲ From previous column								
8	DOORS requires (continued)							
8	12	When <b>SLIDING</b> (continued)						
8	12	6	At <b>FACE FRAME CONSTRUCTION</b> , a continuous vertical filler strip shall be provided in the opening behind the face frame and in front of the rear sliding door.					
8	13	When <b>FLIPPER</b> or <b>POCKET</b> :						
8	13	1	Doors and installation shall be in conformance with and not exceed manufacturers recommendations.					
8	14	When <b>FRAMELESS GLASS</b> :						
8	14	1	Be a minimum of 1/4" (6.4 mm) thick.					
8	14	2	Be clear tempered glass, with:					
8	14	2	1	Exposed edges ground.	E	C	P	
8	14	2	2	Exposed edges flat polished.	E	C	P	
8	14	3	Laminated glass must be specified.					
8	14	4	Carriers with metal track and top guide, and:					
8	14	4	1	If needed to prevent sagging, bottoms of upper cabinets shall be increased in thickness, provided with a hardwood track member of sufficient thickness, or provided with a strong back support screwed and glued to the underside.				
9	<b>APRONS</b> require:							
9	1	Minimum thickness of 3/4" (19 mm), and:						
9	1	1	Edgebanding of bottom edge.				E C P	
10	<b>ENDS</b> and <b>DIVISIONS</b> require:							
10	1	Cabinet ends are required, including:						
10	1	1	Against walls.					
10	2	Minimum thickness of 3/4" (19 mm), except:						
10	2	1	1/2" (12.7 mm) at face frame construction.				E C P	
10	3	Exposed ends be of integral construction, rabbeted or plowed to receive backs, and horizontal members (excluding countertops) shall not extend beyond the exposed end.						
10	4	Concealed ends allow tops and bottoms to extend past, if applicable.						
10	5	Top edges of the end of cabinets:						
10	5	1	If exposed or visible from above be edgebanded with material of matching color and pattern to exposed exterior surface.					
Continues next column ▼								

10.4.7		Basic Assembly Rules					
▲ From previous column							
10	<b>ENDS</b> and <b>DIVISIONS</b> (continued)						
10	6	Bottom edges of wall cabinet ends shall be edgebanded with:					
10	6	1	Material compatible to the exposed faces.			E C P	
10	6	2	Material of matching color and pattern to the exposed exterior surface.			E C P	
10	7	Solid divisions behind vertical face frame members or hanging stiles.					E C P
10	8	<b>DRAWER COMPARTMENTS</b> to be separated from shelf or open compartments by a solid vertical division unless prevented by design or usage.					
10	9	<b>PANELED CONSTRUCTION</b> , stiles and rails be a minimum of 3/4" (19 mm) thickness, with:					
10	9	1	Minimum of 1/4" (6.4 mm) panel thickness.				
10	9	2	Hardboard is not permitted for transparent finish.				
10	10	<b>FREE STANDING</b> end panels shall be installed with concealed fasteners.			E	C	P
11	<b>TOPS</b> and <b>BOTTOMS</b> requires: (Note: Base cabinets with separate countertops are not covered within this heading; see "Stretchers").						
11	1	Minimum thickness of 3/4" (19 mm), design permitting.					
11	2	<b>BOTTOMS</b> of wall hung cabinets, and:					
11	2	1	When unsupported, not to exceed 46-1/2" (1181 mm) in width.				
11	2	2	Joints are permitted where ends are flush with bottoms in each unit.				
11	2	3	Cores be subject to a 40 lb per sq ft (195.3 kg/m2) load capacity of the manufacturer's choice, with:			E C P	
11	2	3	1	A 50 lb per sq ft (244.1 kg/m2) load capacity at schools, hospitals, and library bookshelves.			E C P
11	2	4	Be secured to ends, divisions, and back.				E C P
11	2	5	Thickness of at least 1" (25.4 mm) when made of particleboard or MDF core and 42" (1067 mm) or more in length.				E C P
11	2	6	If cabinet ends extend below the bottom, the interior exposed surface of the end shall be:				
11	2	6	1	Material compatible to the exposed surface.			E C P
11	2	6	2	The same material as the exposed surface.			E C P
Continues next column ▼							

# SECTION 10

## Casework


GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally

<b>E</b>	<b>C</b>	<b>P</b>
----------	----------	----------

## compliance requirements

10.4.7		Basic Assembly Rules		
▲ From previous column				
11	2	TOPS and BOTTOMS requires (continued)		
11	2	BOTTOMS of wall hung cabinets (continued)		
11	2	7	If thicker core is desired due to heavy loads, it shall be specified.	
11	2	8	E	C P
		At exposed interior shall be uniform in thickness for the entire elevation or connected elevations, except:		
11	2	8	E	C P
		When concealed behind a minimum 1-1/2" (38.1 mm) face frame member.		
11	3	TOPS of wall hung and tall cabinets:		
11	3	1	Are not considered load bearing.	
11	3	2	FRAMELESS CONSTRUCTION, permit joints where exposed ends are flush with tops, and:	
11	3	2	1 Cabinet end shall be edgebanded to match other exposed surfaces.	
12 SECURITY and DUST PANELS shall:				
12	1	Be furnished above locked doors and drawers, only if each drawer or door is keyed differently.		
12	2	Be a solid piece of plywood, particleboard, MDF, or solid phenolic, a minimum of 1/2" (12.7 mm) in thickness, and:		
12	2	1	If front and rear stretchers are used, a 1/4" (6.4 mm) panel may be let into the stretchers.	
13 STRETCHERS shall be: (Note: This is only applicable to base cabinets with separate countertops):				
13	1	Provided at both the front and the back of the cabinet body, except:		
13	1	1	At sink compartments, they may run front to back.	
13	2	Solid stock or veneer core plywood a minimum of 3/4" (19 mm) in thickness and 2" (50.8 mm) in width.		
13	3	Particleboard or MDF a minimum of 3/4" (19 mm) in thickness and 5" (127 mm) in width and reinforced as necessary to support the countertop.		
13	4	In lieu of stretchers, a panel member a minimum of 3/4" (19 mm) in thickness, the full length and depth of the cabinet opening may be used.		
13	5	E	C	P
		At drawer banks, when the total drawer opening height exceeds 30" (762 mm), an intermediate front stretcher is required.		
Continues next column ▼				

10.4.7		Basic Assembly Rules			
▲ From previous column					
14 BACKS:					
14	1	Are required only where the cabinet will be set in an unfinished recess or where the back would be exposed to view, and:		E C P	
14	1	1	Be hardboard or plywood a minimum of 1/8" (3.2 mm) in thickness.	E C P	
14	2	Are required and:		E C P	
14	2	1	Shall be a minimum of 1/4" (6.4 mm) in thickness.	E C P	
14	2	2	Shall be of an approved semi-exposed material.	E C P	
14	2	3	Vinyl is permitted, provided it is of the same color as the other semi-exposed surfaces.		
14	3	At exposed exterior shall be a minimum of 1/2" (12.7 mm) in thickness.			
14	4	Where non plowed/dadoed in shall be screwed to the case body and nailed or stapled to divisions and/or fixed shelves at a maximum of 4" (101.6 mm) on center.			
14	5	Where plowed/dadoed in, with a minimum shoulder of 1/2" (12.7 mm), shall be securely nailed or stapled to the case body and divisions and/or fixed shelves at a maximum of 4" (101.6 mm) on center.			
14	6	Attachment of base, tall, and wall hung cabinet backs by other than the above requirements for non plowed/dadoed or plowed/dadoed in is permitted, provided it has been independently tested to show compliance to the Structural Integrity (Test-Wall Cabinet) as shown in the APPENDIX.			
14	7	Are not required to be glued.			
14	8	E	C	P	
14	9	Shall be removable, if so specified.			
14	10	VISIBLE JOINTS are not permitted at exposed interior or semi exposed interior cabinet backs.			
Continues next column ▼					

# SECTION 10

## Casework

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



## compliance requirements

10.4.7		Basic Assembly Rules		
▲ From previous column				
15 ANCHOR STRIPS (nailers) are required and:				
15	1	Shall be of solid stock, plywood, particleboard, or medium density fiberboard, a minimum of 1/2" (12.7 mm) in thickness, 2-1/2" (63.5 mm) in width, and:		
15	1	1 Be securely glued.		
15	1	2 Top anchor strip must be mechanically fastened at a maximum of 4" (101.6 mm) on center at top long edge.		
15	2	Where backs, 1/2" (12.7 mm) or thicker are used, anchor strips are not required.		
15	3	Cabinet heights over 60" (1524 mm) require an intermediate anchor strip.		
15	4	Shall be provided at the top and bottom of the wall side of the cabinet back, or:		
15	4	1 At the inside if semi-exposed material is used, provided they are attached to the cabinet body as well as the back and they are flush with the top, bottom, and ends of the cabinet body.	E	C
16 TOE BASES, KICKS, and SLEEPERS:				
16	1	Shall be either separate from or integral to the cabinet body at the manufacturer's choice.		
16	2	Shall be a minimum of 4" (101.6 mm) high.		
16	3	Shall be a minimum of 3/4" (19 mm) in thickness.		
16	4	Sleepers shall be provided at separate toe bases a maximum of 48" (1220 mm) on center.		
16	5	Moisture resistant base, if specified, requires base components be material complying with the Base Cabinet Submersion Test, as explained in the APPENDIX. 		
16 6 LEVELERS:				
16	6	1 May be used at the manufacturer's choice.		
16	6	2 At cabinets over 15-1/2" (394 mm) in depth, shall require four levelers per unit up to 37-1/2" (953 mm) in width and six per unit up to 48" (1220 mm) in width.		
16	6	3 At cabinets less than 15-1/2" (394 mm) in depth, levelers are only required at the front and shall require two levelers per unit up to 37-1/2" (953 mm) in width and three per unit up to 48" (1220 mm) in width.		
16	6	4 When levelers are used, removable toe kicks are required.		
Continues next column ▼				

10.4.7		Basic Assembly Rules		
▲ From previous column				
16 TOE BASES, KICKS, and SLEEPERS (continued)				
16	7	MOVEABLE TOES at ADA base cabinets shall be designed to minimize the vertical gap required by their offset installation whether used in paired or single door application, and :		
16	7	1 Metal toe assemblies are allowed provided they are of minimum 18 gauge fabrication with a uniform plated BHMA 626, <a href="http://buildershardware.com">http://buildershardware.com</a> , or similar powder coated finish.		
16	7	2 Plastic toe assemblies are allowed provided they are of minimum 0.10" (2.5 mm) in thickness and formed of high impact polystyrene or equal.		
17 SHELVES require:				
17 1 THICKNESS be a minimum of 3/4" (19 mm), and:				
17	1	1 If thicker shelf is desired due to heavy loads, it shall be specified.		
17	2	GRAIN or DIRECTIONAL PATTERN of the face to run the length of the shelf.		
17	3	DIVIDERS, vertical or horizontal, to match the exposed or the semi-exposed surface, as applicable.	E	C
17	4	UNIFORM THICKNESS at each elevation or connected elevations at open casework.	E	C
17	5	Adjustable shelves in adjacent open cabinets are able to be aligned horizontally, provided the adjacent cabinets are of the same base, wall or tall storage type.		
17	6	HARDBOARD used for shelves or vertical/horizontal dividers be tempered and smooth on both sides.	E	C
17	7	CABINETS OVER 72" (1829) high, not immediately abutting a structural wall or another cabinet at both ends, shall have a fixed shelf at approximate mid height.		
17	8	GLASS shelving shall be supplied as specified, and:	E	C
17	8	1 Have all four edges polished.	E	C
Continues next column ▼				

# SECTION 10

## Casework

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



# compliance requirements

10.4.7		Basic Assembly Rules		
▲ From previous column				
17 SHELVES require (continued)				
17 9 At FIXED SHELVES:				
17 9 1	Thickness of 1" (25.4 mm) minimum when made with particleboard or MDF core and are unsupported for 42" (1069 mm) or more.	E	C	P
17 9 2	Cores to be subject to a 40 lb per sq ft (195.3 kg/m <sup>2</sup> ) load capacity of the manufacturer's choice, except requires:	E	C	P
17 9 2 1	50 lb per sq ft (244.1 kg/m <sup>2</sup> ) load capacity at schools, hospitals, and library bookshelves.	E	C	P
17 9 3 Be secured to ends and divisions, and:				
17 9 3 1	When over 48" (1220 mm) in length, be secured to back.	E	C	P
17 9 3 2	Be secured to back.	E	C	P
17 9 3 3	When over 48" (1220 mm) have a center support.	E	C	P
Continues next column ▼				

10.4.7		Basic Assembly Rules		
▲ From previous column				
17 SHELVES require (continued)				
17 10 At ADJUSTABLE SHELVES:				
17 10 1	<b>CONFORMANCE IN THICKNESS</b> to the following maximum adjustable shelf length listings, based on:			
17 10 1 1	Length and grain direction running left to right.			
17 10 1 2	Creep not taken into consideration or considered a defect.			
17 10 1 3	Information and ratings represented in calculations are believed to be reliable; however, due to variations in use not known or out of our control, no warranties or guarantees are made as to the end results.			
17 10 1 4	Laminations of a rigid glue line; contact adhesive is not permitted unless otherwise indicated.			
17 10 1 5	Total applied weight uniformly dispersed on an individual shelf not exceeding 200 lbs (90.7 kg) on any one shelf while being subject to load capacities of:			
17 10 1 5 1	40 lbs per sq ft (195.3 kg/m <sup>2</sup> ) for commercial shelving.			
17 10 1 5 2	50 lbs per sq ft (244.1 kg/m <sup>2</sup> ) for schools, hospitals, and library book shelves.			
17 10 1 6	The formula below was used in determining shelf spans, subject to a maximum 1/4" (6.4 mm) deflection, in the table on the following pages:			
$L = \frac{(DEWt^3)/(0.1563s^4)}{W/144}$ <p>L = lbs/SF of uniformly distributed load            D = deflection (inches)            E = MOE (psi)            t = thickness (inches)            W = width (front to back) of shelf (inches)            s = span of shelf (inches)</p>				
And may also be used to find other acceptable core materials that may meet the minimum requirements of these standards and the desired shelf width.				
17 10 1 7	MOE (Modulus of Elasticity) estimates are referenced in the following table.			
Continues next column ▼				

# SECTION 10

## Casework

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



## compliance requirements

### 10.4.7 Basic Assembly Rules

▲ From previous column

16 SHELVES require (continued)


16 9 At ADJUSTABLE SHELVES (continued)

16 9 1 CONFORMANCE IN THICKNESS (continued)

MAXIMUM ALLOWABLE ADJUSTABLE SHELF LENGTH based on material compositions.

Capacity Legend:  40 lbs/sf (195.3 kg/m<sup>2</sup>)  50 lbs/sf (244.1 kg/m<sup>2</sup>)

16 9 1 8



Continues next column ▼

# SECTION 10

## Casework

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



## compliance requirements

### 10.4.7

▲ From previous column


16 SHELVES require (continued)

16 9 At ADJUSTABLE SHELVES (continued)

16 9 1 CONFORMANCE IN THICKNESS (continued)

MAXIMUM ALLOWABLE ADJUSTABLE SHELF LENGTH based on material compositions.

Capacity Legend:   
 40 lbs/sf (195.3 kg/m<sup>2</sup>)   
 50 lbs/sf (244.1 kg/m<sup>2</sup>)



Continues next column ▼

# SECTION 10

## Casework

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally

**E C P**

**compliance requirements**

### 10.4.7 Basic Assembly Rules

▲ From previous column


16 SHELVES require (continued)

16 9 At ADJUSTABLE SHELVES (continued)

16 9 1 CONFORMANCE IN THICKNESS (continued)

MAXIMUM ALLOWABLE ADJUSTABLE SHELF LENGTH based on material compositions (continued)

Capacity Legend:  40 lbs/sf (195.3 kg/m<sup>2</sup>)  50 lbs/sf (244.1 kg/m<sup>2</sup>)



Continues next column ▼

# SECTION 10

## Casework

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



## compliance requirements

<b>10.4.7</b>																																	
▲ From previous column																																	
16 SHELVES require (continued)																																	
16 9 At ADJUSTABLE SHELVES (continued)																																	
16 9 1 CONFORMANCE IN THICKNESS (continued)																																	
MAXIMUM ALLOWABLE ADJUSTABLE SHELF LENGTH based on material compositions (continued)																																	
<p>Capacity Legend: <span style="display: inline-block; width: 15px; height: 15px; background-color: #2e7d32; margin-right: 5px;"></span> 40 lbs/sf (195.3 kg/m<sup>2</sup>) <span style="display: inline-block; width: 15px; height: 15px; background-color: #a5d6a7; margin-left: 20px; margin-right: 5px;"></span> 50 lbs/sf (244.1 kg/m<sup>2</sup>)</p>																																	
16 9 1 8	<table border="1"> <thead> <tr> <th>Material Composition</th> <th>Thickness</th> <th>Capacity</th> <th>3/4" (19 mm)</th> <th>1" (25.4 mm)</th> </tr> </thead> <tbody> <tr> <td rowspan="2">Veneer Core with hardwood veneer two sides (MOE: 750,000 +/-)</td> <td>40 lbs/sf</td> <td>35" (889 mm)</td> <td>37" (940 mm)</td> <td>45" (1143 mm)</td> </tr> <tr> <td>50 lbs/sf</td> <td>36" (914 mm)</td> <td>38" (965 mm)</td> <td>43" (1092 mm)</td> </tr> <tr> <td rowspan="2">Veneer Core with vertical grade HPDL two sides (MOE: 775,000 +/-)</td> <td>40 lbs/sf</td> <td>44" (1118 mm)</td> <td>46" (1168 mm)</td> <td>48" (1219 mm)</td> </tr> <tr> <td>50 lbs/sf</td> <td>39" (991 mm)</td> <td>41" (1041 mm)</td> <td>49" (1245 mm)</td> </tr> <tr> <td rowspan="2">Veneer Core with minimum 11 ply at 3/4" (19 mm) or 13 ply at 1" (25.4 mm) void free, hardwood with hardwood veneer two sides (MOE: 1,000,000 +/-)</td> <td>40 lbs/sf</td> <td>38" (965 mm)</td> <td>40" (1016 mm)</td> <td>48" (1219 mm)</td> </tr> <tr> <td>50 lbs/sf</td> <td>39" (991 mm)</td> <td>41" (1041 mm)</td> <td>49" (1245 mm)</td> </tr> </tbody> </table>	Material Composition	Thickness	Capacity	3/4" (19 mm)	1" (25.4 mm)	Veneer Core with hardwood veneer two sides (MOE: 750,000 +/-)	40 lbs/sf	35" (889 mm)	37" (940 mm)	45" (1143 mm)	50 lbs/sf	36" (914 mm)	38" (965 mm)	43" (1092 mm)	Veneer Core with vertical grade HPDL two sides (MOE: 775,000 +/-)	40 lbs/sf	44" (1118 mm)	46" (1168 mm)	48" (1219 mm)	50 lbs/sf	39" (991 mm)	41" (1041 mm)	49" (1245 mm)	Veneer Core with minimum 11 ply at 3/4" (19 mm) or 13 ply at 1" (25.4 mm) void free, hardwood with hardwood veneer two sides (MOE: 1,000,000 +/-)	40 lbs/sf	38" (965 mm)	40" (1016 mm)	48" (1219 mm)	50 lbs/sf	39" (991 mm)	41" (1041 mm)	49" (1245 mm)
Material Composition	Thickness	Capacity	3/4" (19 mm)	1" (25.4 mm)																													
Veneer Core with hardwood veneer two sides (MOE: 750,000 +/-)	40 lbs/sf	35" (889 mm)	37" (940 mm)	45" (1143 mm)																													
	50 lbs/sf	36" (914 mm)	38" (965 mm)	43" (1092 mm)																													
Veneer Core with vertical grade HPDL two sides (MOE: 775,000 +/-)	40 lbs/sf	44" (1118 mm)	46" (1168 mm)	48" (1219 mm)																													
	50 lbs/sf	39" (991 mm)	41" (1041 mm)	49" (1245 mm)																													
Veneer Core with minimum 11 ply at 3/4" (19 mm) or 13 ply at 1" (25.4 mm) void free, hardwood with hardwood veneer two sides (MOE: 1,000,000 +/-)	40 lbs/sf	38" (965 mm)	40" (1016 mm)	48" (1219 mm)																													
	50 lbs/sf	39" (991 mm)	41" (1041 mm)	49" (1245 mm)																													
Continues next column ▼																																	

# SECTION 10

## Casework

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



**compliance requirements**

### 10.4.7 Basic Assembly Rules

▲ From previous column

16 SHELVES require (continued)

16 9 At ADJUSTABLE SHELVES (continued)


16 9 1 CONFORMANCE IN THICKNESS (continued)

MAXIMUM ALLOWABLE ADJUSTABLE SHELF LENGTH based on material compositions.

Capacity 40 lbs/sf  
Legend: (195.3 kg/m<sup>2</sup>)

50 lbs/sf  
(244.1 kg/m<sup>2</sup>)

16 9 1 8



Solid Phenolic

Recommendations only, based on data research from Solid Phenolic Manufacturers. (MOE: 1,300,000 +/-)



Continues next column ▼

# SECTION 10

## Casework

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



**compliance requirements**

### 10.4.7

▲ From previous column

16 SHELVES require (continued)


16 9 At ADJUSTABLE SHELVES (continued)

16 9 1 CONFORMANCE IN THICKNESS (continued)

MAXIMUM ALLOWABLE ADJUSTABLE SHELF LENGTH based on material compositions.

Capacity Legend:  40 lbs/sf (195.3 kg/m<sup>2</sup>)  50 lbs/sf (244.1 kg/m<sup>2</sup>)

16 9 1 8



Tempered Safety Glass

Recommendations only, based on data researched from LOF and ASTM C1036, <http://astm.org>.



Continues next column ▼

# SECTION 10


## Casework

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



## compliance requirements

10.4.7		Basic Assembly Rules	
▲ From previous column			
17 SHELVES require (continued)			
17 9 At ADJUSTABLE SHELVES (continued):			
17 9 2	<p>Length be a maximum of 1/8" (3.2 mm) less than the inside cabinet width plus any additional offset created by the shelf rests used,</p>  <p>and:</p>	E C P	
17 9 2 1	If the gap between the end of a shelf and the inside cabinet body exceeds 1/4" (6.4 mm) both ends of the shelf must be edgebanded.	E	C P
17 9 3	Depth be a maximum of 1/4" (6.4 mm) less than the inside cabinet depth.	E	C P
17 9 4	Be supported on evenly spaced, cleanly bored holes a maximum of 2" (50.8 mm) on center with shelf rests or on metal shelf standards with metal shelf rests, and:		
17 9 4 1	Center line of rests shall not exceed a minimum of 1" (25.4 mm) to a maximum of 4" (102 mm) from the front and back of the interior cabinet body.		
17 9 4 2	Support placement shall not conflict with hinge placement.		
17 9 4 3	The dimension between the center line of the rests shall not be less than 60% of the shelf's depth.		
17 9 4 4	Require three rests at each end of shelves over 29-3/4" (756 mm) deep.		
17 9 5	<b>METAL SHELF STANDARDS</b> shall extend vertically the entire interior length of the cabinet body side member, and:		
17 9 5 1	Be recessed in a plow, slightly proud of the face with the core not visible.		
17 9 5 2	Are not required in the vertical area of drawers.		
17 9 6	<b>BORED HOLE SHELF REST SYSTEMS</b> shall extend vertically to within 6" (152.4 mm) of the interior top or bottom of the cabinet shelf space.		
Continues next column ▼			

10.4.7		Basic Assembly Rules	
▲ From previous column			
18 PULLOUT SHELVES require:			
18 1	<b>BREAD/CUTTING BOARDS</b> to be solid stock a minimum of 3/4" (19 mm) in thickness, with:		
18 1 1	Tongue and groove edgebands front and back, securely glued with type I adhesive.		
18 1 2	Use of exterior plywood is permitted.	E	C P
18 2	<b>WRITING or UTILITY SHELVES</b> be a minimum of 3/4" (19 mm) in thickness, and:		
18 2 1	Be edgebanded three edges.		
18 2 2	Extend a minimum of 15" (381 mm) in cabinets 22" (559 mm) or greater, or 2/3 of the cabinet depth in shallower cabinets.		
18 2 3	Be a smooth compatible material to the exposed interior surface.		
18 2 4	Operate smoothly in channels or other rigid guides.		
19 CLOTHES POLES or RODS require:			
19 1	Wood, a minimum of 1-1/4" (31.8 mm) in diameter, or metal, a minimum of 1-1/16" (27 mm) diameter, at the manufacturer's choice, and supported at:		
19 1 1	Each end by rosettes or hook strips with bored holes.		
19 1 2	A maximum of 48" (1220 mm) on center.		
20 WARDROBES:			
20 1	60" (1524 mm) or wider require a horizontal member at the top rail of sliding doors rigidly supported with a vertical 1-3/8" (28.6 mm) round pole or two strips a minimum of 3/4" x 1-1/4" (19 mm x 31.8 mm) forming a "T" member securely positioned behind the door lap.		
Continues next column ▼			



# SECTION 10

## Casework




GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



# compliance requirements

10.4.7		Basic Assembly Rules	
▲ From previous column			
21	1	<b>MOVEABLE CABINETS</b> require:	
21	1	<b>GLIDES</b> to be metal and adjustable.	
21	2	<b>CASTERS</b> to have a minimum weight capacity of 90 lbs (40.8 kg) per caster.	
21	3	<b>METAL FRAME</b> or <b>DIAPHRAGM TYPE DOUBLE BOTTOM</b> (see <b>DESIGN RESOURCES</b> , <b>CDS</b> drawings) at cabinets over 42" (1067 mm) in height, with doors and without fixed vertical or horizontal stabilizing partitions. 	
21	4	<b>LOCK JOINT CORNERS</b> at bottoms or tops be reinforced with a continuous metal angle or wood cleat securely screwed and set with adhesive into the inside of both corner sides.	
22 JOINERY requires:			
22	1	Cabinet members to be <b>SECURELY FASTENED</b> together, using one or more of the approved methods, at the manufacturer's choice, including:	
22	1	1 Dadoes, lock joints, plows, rabbets, dowels, dowel screws, or biscuit splines.	
22	2	Casework be <b>ASSEMBLED SQUARE</b> and <b>TRUE</b> , within a tolerance not to exceed 1/32" (0.8 mm) difference in measurement at top versus bottom, and 1/16" (1.6 mm) diagonally.	
22	3	All joints be <b>SECURELY GLUED</b> , unless specifically stated otherwise, with:	
22	3	1 Mechanical fasteners for cabinet body, back, and/or drawer construction, a maximum of 4" (101.6 mm) on center with a minimum of two fasteners per joint, except:	
22	3	1 1 At face frames, a maximum of 8" (203 mm) on center is permitted.	
22	3	1 2 Exposed fasteners are not permitted at exposed exterior surfaces.	
22	3	1 3 Exposed fasteners, where permitted, shall be plated, and:	
22	3	1 3 1 Bugle drywall screws are not permitted.	
22	3	1 3 2 Are permitted for access panels. <span style="float: right;">E C P</span>	
22	3	1 4 Mechanical fasteners are not required at dovetail, miter fold, mortise and tenon, and lock miter joints.	
Continues next column ▼			

10.4.7		Basic Assembly Rules	
▲ From previous column			
22	3	JOINERY requires (continued)	
22	3	All joints be securely glued, unless (continued)	
22	3	1 Mechanical fasteners (continued):	
22	3	1 5 At glued in <b>DOWEL</b> joints (see end view diagram below):	
22	3	1 5 1 Dowel to be a minimum of 5/16" x 1-3/16" (8 mm x 30 mm), and: 	
22	3	1 5 1 1 Be glued and clamped.	
22	3	1 5 2 Minimum of two dowels per joint.	
22	3	1 5 3 Spaced with first dowel a maximum of 2" (51 mm) from the front.	
22	3	1 5 4 Subsequent dowels shall be spaced a maximum of 3-25/32" (96 mm) on center, unless joint is less than 9-1/2" (241.3 mm) wide than maximum spacing shall not exceed 2-1/2" (63.5 mm).	
22	3	1 5 5 	
22	3	1 6 At thread in <b>DOWEL SCREW</b> joints (see end view diagram below):	
22	3	1 6 1 Dowel screw to be a minimum of 9/32" x 2" (7 mm x 50 mm). 	
22	3	1 6 2 First dowel screw shall be spaced a maximum of 2" (51 mm) from the front.	
22	3	1 6 3 Subsequent dowel screws shall be spaced a maximum of 5" (127 mm) on center, unless joint is less than 12" (305 mm) maximum spacing shall not exceed 4" (101.6 mm).	
22	3	1 6 4 	
22	3	1 6 5 Glue is not required.	
Continues next column ▼			

# SECTION 10



## Casework



GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



# compliance requirements

10.4.7		Basic Assembly Rules	
▲ From previous column			
22	3	1	JOINERY requires (continued)
22	3	1	All joints be securely glued, unless (continued)
22	3	1	Mechanical fasteners (continued):
22	3	1	7 At laterally engaged <b>DOWEL LINK</b> joints (see end view diagram below), fasteners:
		7	1 Shall be of metal or synthetic construction, and:
22	3	1	7 1 1 Be a minimum of 5/16" x 1-3/16" (8 mm x 30 mm). 
22	3	1	7 1 2 Be glued at panel edge hole only.
22	3	1	7 2 Shall be installed with a minimum of two dowel links per joint.
22	3	1	7 3 Shall be spaced with first dowel link a maximum of 2" (51 mm) from the front, and:
			1 Subsequent dowel links shall be spaced a maximum of 5" (127 mm) on center as shown below, unless joint is less than 9-1/2" (241.3 mm) wide than maximum spacing shall not exceed 2-1/2" (63.5 mm):
22	3	1	7 3 2 
Continues next column ▼			

10.4.7		Basic Assembly Rules	
▲ From previous column			
22	3	1	JOINERY requires (continued)
22	3	1	All joints be securely glued, unless (continued)
22	3	1	Mechanical fasteners (continued):
22	3	1	8 At press-in <b>TWIN DOWEL INSERTION CLIP/SRING PIN</b> or laterally engaged <b>TWIN DOWEL RETENTION CARRIAGE</b> joints (see end/side view diagram below):
22	3	1	8 1 <b>INSERTION CLIP</b> with accompanying metal spring pin shall be of metal or synthetic construction, and
22	3	1	8 1 1 Be a minimum of 1-9/16" (40 mm) in width with minimum 5/16" (8 mm) x 25/32" (20 mm) dowels. 
22	3	1	8 1 2 Spring Pin shall be all metal and a minimum of 5/16" (8 mm) x 1 3/16" (30 mm). 
22	3	1	8 1 3 Shall be installed with a minimum of two clip/pin sets per joint over 6-5/8" (168 mm) in length, otherwise one clip/pin set is acceptable.
22	3	1	8 1 4 Shall be spaced with first set a maximum of 2" (51 mm) from front, and subsequent sets shall be spaced a maximum of 12" (305 mm) on center with last set a maximum of 3" (72 mm) from rear of joint length.
22	3	1	8 2 <b>RETENTION CARRIAGE</b> shall be of metal or synthetic construction, and
22	3	1	8 2 1 Be a minimum of 1-9/16" (40 mm) in width with minimum 5/16" (8 mm) x 25/32" (20 mm) dowels. 
22	3	1	8 2 2 Shall be installed with a minimum of two carriages per joint over 6-5/8" (168 mm) in length, otherwise one carriage is acceptable.
22	3	1	8 2 3 Shall be spaced with first set a maximum of 2" (51 mm) from front or back, and subsequent carriages spaced a maximum of 12" (305 mm) on center.
22	3	1	8 3 Glue is not required.
Continues next column ▼			

# SECTION 10


## Casework




GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally

<b>E</b>	<b>C</b>	<b>P</b>
----------	----------	----------

## compliance requirements

10.4.7				Basic Assembly Rules					
▲ From previous column									
22	3	1	9	Joinery requires (continued)					
22	3	1	9	Joints be securely glued, unless (continued)					
22	3	1	9	Mechanical fasteners (continued):					
22	3	1	9	<b>BISCUIT SPLINE</b> 					
22	3	1	9	joints:					
22	3	1	9	1	Biscuits shall be a minimum #20 or equal, located a maximum of 2" (51 mm) from each edge or end to the center of the plate, and:				
22	3	1	9	1	Be glued and clamped.				
22	3	1	8	2	Subsequent plates shall be spaced a maximum of 6" (152 mm) on center.				
22	4	<p>Joinery other than that provided for within Section 10 is permitted provided it is fully documented in a text/ illustration explanation, and each material application has been independently tested to show compliance to either:</p> <ul style="list-style-type: none"> <li>SEFA's (Scientific Equipment and Fixture Association, <a href="http://sefalabs.com">http://sefalabs.com</a>) Cabinet Structural Integrity Tests.</li> <li>BIFMA's (Business + Institutional Furniture Manufacturers Association, <a href="https://www.bifma.org">https://www.bifma.org</a>) ANSI/BIFMA X5.9 (latest edition), with enhancements.</li> </ul> <p>As qualified within Casework Integrity Testing of the <b>APPENDIX</b>.</p>  							
<b>23 SCRIBING:</b>									
23	1	Is <b>NOT</b> required.			E	C	P		
23	2	Shall be <b>FURNISHED</b> by the manufacturer, and:			E	C	P		
23	2	1	Scribe <b>FILLERS</b> shall not exceed 1-1/2" (38.1 mm) in width.			E	C	P	
23	2	2	Scribe <b>MOLDS</b> shall not exceed 1-1/2" (38.1 mm) in width, and:			E	C	P	
23	2	2	1	Are <b>NOT ALLOWED</b> .			E	C	P
23	3	Match exposed surfaces.							
23	4	Be furnished in maximum available lengths, joints not allowed in material less than 96" (2438 mm).							
Continues next column ▼									

10.4.7				Basic Assembly Rules					
▲ From previous column									
<b>23 SCRIBING</b> (continued)									
23	5	Permits <b>COLOR COMPATIBLE CAULKING</b> not to exceed 1/8" (3.2 mm).			E	C	P		
23	6	Requires <b>TRIM MEMBERS</b> used at the inside corner of the adjoining angled cabinets (which is not a scribe or subject to the 1-1/2" [38.1 mm] maximum scribe allowance) be equal and not exceed 2" (50.8 mm) beyond the cabinet front and/or drawer pull.							
23	7	Requires <b>SOFFIT</b> or <b>FASCIA PANELS</b> , joints not allowed in material less than 96" (2438 mm) at horizontal grain or directional pattern and 48" (1220 mm) at vertical grain or directional pattern, and:			E	C	P		
23	7	1	Be a minimum of 3/4" (19 mm) in thickness.						
23	7	2	Grain direction (if any) shall run vertical, or be manufacturer's choice if less than:						
23	7	2	1	12" (305 mm) tall.			E	C	P
23	7	2	2	1-1/2" (38.1 mm) tall.			E	C	P
<b>23 8 OPTIONS:</b>									
23	8	1	 <p>Scribe Filler.</p>						
23	8	2	 <p>Scribe Mold.</p>						
23	8	3	 <p>Scribe Allowance.</p>						
Continues next column ▼									

# SECTION 10




## Casework





GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally

**E C P**

# compliance requirements

10.4.7		Basic Assembly Rules	
▲ From previous column			
<b>CLOSURE</b> provision is required at voids or open spaces between cabinets and walls, such as at the top of tall and upper cabinets and the bottom of upper cabinets caused by scribing or angle turns, and:			
24	1	At non visible voids, 1-1/2" (38 mm) or less in width, a piece of standard grade laminate may be used as a closure cap.	
			
24	2	At non visible voids, exceeding 1-1/2" (38 mm) in width, a minimum 3/4" (19 mm) closure filler shall be provided of manufacturer's choice.	
			
24	3	At visible voids, a minimum 3/4" (19 mm) closure filler shall be provided matching the adjacent surface.	
<b>25 CLEARANCES and TOLERANCES</b> requires:			
<b>EDGE ALIGNMENT</b> of doors and drawers (see Test I illustrations in Tests) in both the vertical and horizontal plane, such as,			
25	1		
shall not exceed:			
25	1	1	1/16" (1.6 mm). <span style="float: right;">E C P</span>
25	1	2	1/32" (0.8 mm). <span style="float: right;">E C P</span>
25	2	Doors and drawers shall be on the same plane as one another, and shall not exceed:	
25	2	1	1/8" (3.18 mm). <span style="float: right;">E C P</span>
25	2	2	1/16" (1.59 mm). <span style="float: right;">E C P</span>
25	2	3	1/32" (0.79 mm). <span style="float: right;">E C P</span>
Continues next column ▼			

10.4.7		Basic Assembly Rules	
▲ From previous column			
<b>25 CLEARANCES and TOLERANCES</b> (continued)			
25	3	The <b>MAXIMUM GAP</b> variance (see Test N illustrations in Tests) within a cabinet elevation, between any edge of a door and/or drawer and another door and/or drawer or finished end, cabinet member and doors hung in pairs, shall be based on the following elevations and shall be:	
25	3	1	At <b>FLUSH OVERLAY FRAMELESS</b> construction: 
25	3	2	At <b>REVEAL OVERLAY FRAMELESS</b> construction: 
25	3	3	At <b>REVEAL OVERLAY FACE FRAME</b> construction: 
25	3	4	At <b>INSET FACE FRAME</b> construction: 
Continues next column ▼			

# SECTION 10

## Casework

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



## compliance requirements

10.4.7		Basic Assembly Rules			
<b>▲ From previous column</b>					
<b>25 CLEARANCES and TOLERANCES (continued)</b>					
<b>25 3</b> The <b>MAXIMUM GAP</b> variance (continued)					
25	3	5	"A" - a minimum of 1/16" (1.6 mm) and maximum of 1/8" (3.2 mm) and variance shall not exceed 1/32" (0.8 mm).		
25	3	6	"B" - a minimum of 0.0" (0.0 mm) and maximum of 1/16" (1.6 mm) and variance shall not exceed 1/32" (0.8 mm)..		
25	3	7	"C" - a minimum of 1/8" (3.2 mm) to a maximum of 1/4" (6.4 mm), consistent across each elevation and variance shall not exceed 1/32" (0.8 mm), except:		
25	3	7	1	At laboratory countertops, reveal may be as much as 1" (25.4 mm) to allow attachment of laboratory equipment.	
25	3	8	"D" shall be determined by hinge overlay and variance shall not exceed 1/32" (0.8 mm).		
25	3	9	"E" shall be as specified, indicated or agreed and variance shall not exceed 1/32" (0.8 mm).		
25	3	10	"F" - a minimum of 1/4" (6.2 mm) to a maximum of 1" (25.4 mm), consistent across each elevation and variance shall not exceed 1/32" (0.8 mm)..		
<b>26 WARP and TWIST</b> of cabinet doors shall not exceed that indicated below or a maximum of 1/4" (6.4 mm) in any single door:					
<b>26 1</b> Tolerance shall not exceed the following per lineal foot:					
26	1	1	0.0625" or 1/16" (1.6 mm).	<b>E</b>	<b>C</b> <b>P</b>
26	1	2	0.0469" or 3/64" (1.2 mm).	<b>E</b>	<b>C</b> <b>P</b>
26	1	3	0.0313" or 1/32" (0.8 mm).	<b>E</b>	<b>C</b> <b>P</b>
<p><b>Specific PRODUCT Requirements for Wood Faced, HPDL faced, Solid Phenolic and Laboratory Casework may be found in Annex A, B, C and/or D which follow herein.</b></p> 					



# SECTION 10 - ANNEX 10A

## Wood Faced Casework

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally

<b>E</b>	<b>C</b>	<b>P</b>
----------	----------	----------

compliance requirements

# Additional Requirements for Wood Faced Casework

10.4.5.A		Additional Material Rules for Wood Faced Casework				
1		EXPOSED EXTERIOR surfaces:				
1	1	TRANSPARENT FINISH requires:				
1	1	1	Specified species, cut, and match, and:			
1	1	1	1	Use of one species for the entire project.		
1	1	1	2	COMPATIBLE in color and grain.	E	C P
1	1	1	3	WELL MATCHED for color and grain; plywood shall be COMPATIBLE in color with solid stock; and adjacent plywood panels shall be WELL MATCHED for color and grain.	E	C P
1	1	2	VENEER to be:			
1	1	2	1	Hardwood conforming to HPVA definitions and characteristics for:		
1	1	2	1	Grade B.	E	C P
1	1	2	2	Grade A.	E	C P
1	1	2	3	Grade AA.	E	C P
1	1	2	2	SLICED subject to:		
1	1	2	2	1	Manufacturer's choice.	E C P
1	1	2	2	2	Plain sliced, except rotary cut at Birch.	E C P
1	1	2	3	MATCHED between ADJACENT LEAVES subject to:		
1	1	2	3	1	Manufacturer's choice.	E C P
1	1	2	3	2	Book Matching	E C P
1	1	2	4	RUNNING MATCHED within PANEL FACE.		
1	1	2	5	MATCHED between ADJACENT PANELS subject to:		
1	1	2	5	1	Manufacturer's choice.	E C P
1	1	2	5	2	Compatible for color and grain.	E C P
1	1	2	5	3	Well matched for color and grain.	E C P
1	1	2	6	END MATCHED, BLUEPRINT and SEQUENCED only if so specified.		
Continues next column ▼						

10.4.5.A		Additional Material Rules for Wood Faced Casework				
▲ From previous column						
1		EXPOSED EXTERIOR surfaces (continued)				
1	1	TRANSPARENT FINISH requires (continued)				
1	1	3	At STILE and RAIL construction:			
1	1	3	1	DRAWER and FALSE FRONTS shall:		
1	1	3	1	1	Match door profile or be of solid wood or veneered panel run horizontally.	E C P
1	1	3	1	2	Match door profile with panel running vertically.	E C P
1	2	OPAQUE FINISH permits				
1	2	1	Use of particleboard, MDF, MDO, softwood plywood, hardwood plywood, and solid stock.		E	C P
1	2	2	Use of MDF, MDO, close grain hardwood plywood, and solid stock.		E	C P
1	2	3	Use of MDF and MDO.		E	C P
1	2	4	Use of veneer; however:			
1	2	4	1	SPECIES of manufacturer's choice, closed grain hardwood conforming to HPVA definitions and characteristics for:		
1	2	4	1	1	Grade D.	E C P
1	2	4	1	2	Grade C.	E C P
1	2	4	1	3	Grade B.	E C P
2	EXPOSED INTERIOR surfaces, except at doors and drawer fronts, requires:					
2	1	TRANSPARENT FINISH requires:				
2	1	1	LPDL or wood of the manufacturer's choice.		E	C P
2	1	2	Wood, the same species as the exposed exterior surface.		E	C P
2	1	3	Wood, the same species and cut as the exposed exterior surface, and be:		E	C P
2	1	3	1	HPVA Grade C.	E	C P
2	1	3	2	HPVA Grade B.	E	C P
2	1	3	3	HPVA Grade A.	E	C P
Continues next column ▼						

# SECTION 10 - ANNEX 10A

## Wood Faced Casework

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally

<b>E</b>	<b>C</b>	<b>P</b>
----------	----------	----------

## compliance requirements

# Additional Requirements for Wood Faced Casework

10.4.5.A		Additional Material Rules for Wood Faced Casework				
▲ From previous column						
2	EXPOSED INTERIOR surfaces (continued)					
2	2 OPAQUE FINISH permits:					
2	2	1	Use of particleboard, MDF, MDO, softwood plywood, hardwood plywood, and solid stock.	E	C P	
2	2	2	Use of MDF, MDO, close grain hardwood plywood, and solid stock.	E	C P	
2	2	3	Use of MDF and MDO.	E	C P	
2	3 At INSIDE FACE of door and drawer fronts permits:					
2	3	1	Manufacturers' choice of species.	E	C P	
2	3	2	HPVA Grade B face of the same species and cut as the exposed exterior surface.	E	C P	
2	3	3	HPVA Grade A face of the same species and cut as the exposed exterior surface.	E	C P	
3 SEMI-EXPOSED surfaces for both transparent and opaque finishes require:						
3	1	Solid wood, veneer of manufacturers' choice of species, MDO, MDF, particleboard, or LPDL of the manufacturer's choice of color.			E	C P
3	2	Solid wood, veneer of minimum HPVA Grade C of manufacturer's choice of species or LPDL of the manufacturer's choice of color.			E	C P
3	3	Solid wood, veneer of minimum HPVA Grade C of compatible species to the exposed surface.			E	C P
Continues next column ▼						

10.4.5.A		Additional Material Rules for Wood Faced Casework						
▲ From previous column								
3	SEMI-EXPOSED (continued)							
3	4 DRAWER BOX							
3	4 1 SURFACES to be:							
3	4	1	1 Consistent color or species to be used throughout entire project.					
3	4	1	1	1	Solid hardwood, veneer of manufacturers' choice of species, MDO, MDF, or LPDL of the manufacturer's choice of color.	E	C	P
3	4	1	1	2	Solid hardwood, veneer of minimum HPVA Grade C of manufacturer's species choice or LPDL of the manufacturer's color choice.	E	C	P
3	4	1	1	3	For OPAQUE FINISH shall be pre-finished and of solid wood or veneer of manufacturer's choice of species or MDO.	E	C	P
3	4	1	1	4	For TRANSPARENT FINISH shall be pre-finished and of solid wood or veneer of minimum HPVA Grade C of manufacturer's choice of species compatible to exposed face.	E	C	P
3	4 2 DIVIDERS:							
3	4	2	1 If hardboard, to be tempered, smooth on both sides, and:			E	C	P
3	4	2	1	1	Matching other drawer box surfaces is only required if so specified.	E	C	P
3	4	2	2 To match other drawer box surfaces.			E	C	P
3	4 3 SIDES, BACK and SUB FRONTS with:							
3	4 3 1 CORES of:							
3	4	3	1	1	Solid wood, minimum 7-ply hardwood plywood with no inner core voids of manufacturer's choice of species, MDO, MDF, particleboard.	E	C	P
3	4	3	1	2	Solid wood, minimum 7-ply hardwood plywood with no inner core voids of manufacturer's choice of species, MDF, particleboard.	E	C	P
Continues next column ▼								

# SECTION 10 - ANNEX 10A

## Wood Faced Casework

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally

<b>E</b>	<b>C</b>	<b>P</b>
----------	----------	----------

**compliance requirements**

# Additional Requirements for Wood Faced Casework

10.4.5.A		Additional Material Rules for Wood Faced Casework			
▲ From previous column					
3	SEMI-EXPOSED	(continued)			
3	4	DRAWER BOX (continued)			
3	4	3	SIDES, BACK and SUB FRONTS (continued)		
3	4	3	2	MINIMUM THICKNESS of:	
3	4	3	2	1	7/16" (11.1 mm). E C P
3	4	3	2	2	15/32" (12 mm), except: E C P
3	4	3	2	2	1 5/8" (16 mm) at drawer boxes wider than 30" (762 mm). E C P
3	4	4	BOTTOMS with:		
3	4	4	1	CORES of:	
3	4	4	1	1	Veneer core plywood, tempered hardboard, or MDF. E C P
3	4	4	1	2	Veneer core plywood. E C P
3	4	4	2	MINIMUM THICKNESS of:	
3	4	4	2	1	13/64" (5.2 mm), except:
3	4	4	2	1	1/4" (6.4 mm) at MDF.
3	4	4	2	2	3/8" (9.5 mm) at drawers boxes wider than 30" (762 mm). E C P

10.4.7.A		Additional Assembly Rules for Wood Faced Casework			
1	VISIBLE EDGES require:				
1	1	Voids to be filled and sanded. E C P			
1	2	Edge filling not required at medium density fiberboard. E C P			
1	3	Sheet products be edgebanded. E C P			
1	4	Unless specified otherwise, the sequence of edge/face lamination shall be the manufacturer's choice.			
1	5	Door and drawer front edges showing more than 1/4" (6.4 mm) on face shall be mitered, except: E C P			
1	5	1	At the ends of wall hung cabinets, the sequence of edges shall be the bottom edge first.		
1	6	Finger joints to be:			
1	6	1	Unlimited. E C P		
1	6	2	Permitted if adjoining pieces are compatible for color and grain. E C P		
1	6	3	Permitted if well matched for color and grain with a maximum of one in 96" (2438 mm) of length. E C P		
2	DRAWERS require (including trays and sliding bins):				
2	1	Wood shall be finished with a finishing system (see Section 5), at the manufacturer's choice.			
2	2	At solid stock, top edges of sides shall be stop shaped. E C P			
2	3	Permits horizontal grain at stile and rail door cabinets.			
2	4	Permits horizontal grain at solid wood drawer fronts.			
2	5	FRONT and FALSE FRONT:			
2	5	1	Be EDGEBANDED at all four edges, except:		
2	5	1	1	When back beveled.	
2	5	1	2	When of solid wood.	
Continues next column ▼					

# SECTION 10 - ANNEX 10A

## Wood Faced Casework

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally

<b>E</b>	<b>C</b>	<b>P</b>
----------	----------	----------

compliance requirements

# Additional Requirements for Wood Faced Casework

10.4.7.A		Additional Assembly Rules for Wood Faced Casework		
▲ From previous column				
2	DRAWERS require (continued)			
2	5	FRONT and FALSE FRONT (continued)		
2	5	2	For OPAQUE finish, have:	
2	5	2	1	Filled and sanded edges at minimum 7-ply hardwood plywood and particleboard. <b>E C P</b>
2	5	2	2	No edgebanding at medium density fiberboard. <b>E C P</b>
2	4	2	3	Edgebanding at medium density fiberboard shall be at the option of the manufacturer. <b>E C P</b>
2	5	3	At TRANSPARENT finish, have:	
2	5	3	1	Filled and sanded edges at minimum 7-ply hardwood plywood and particleboard. <b>E C P</b>
2	5	3	2	Edgebanding matched to exposed surfaces. <b>E C P</b>
3 DOORS require:				
3	1	Solid lumber not be permitted, except at stile and rail doors.		
3	2	At transparent finish, edgebanding on all four edges matching exposed surfaces.		
3	3	Glass stops for transparent finish be of the same species and grade as the exposed surfaces. <b>E C P</b>		
3	4	When sliding interior faces shall be of balancing species.		
4 FACE FRAMES require (not applicable to decorative laminate casework):				
4	1	Thickness, a minimum of 3/4" (19 mm).		
4	2	Solid stock.		
4	3	Grain to run vertically on stiles and horizontally on rails.		
Continues next column ▼				

10.4.7.A		Additional Assembly Rules for Wood Faced Casework		
▲ From previous column				
4	FACE FRAMES require (continued)			
4	4	Joints to be mortised and tenoned, doweled, metal dowel screwed, pocket screwed or biscuit splined, and:		
4	4	1	To be securely glued.	
Frames to be securely glued to cabinet bodies, and:				
4	5	1	May be face nailed. <b>E C P</b>	
4	5	2	Exposed nailing is not permitted. <b>E C P</b>	
4	5	3	Exposed corners shall be shoulder mitered, lock mitered, spline mitered, or mitered with a biscuit spline. <b>E C P</b>	
5 TOPS and BOTTOMS:				
5	1	Minimum of 1/2" (12.7 mm). <b>E C P</b>		
5	2	Minimum of 3/4" (19 mm). <b>E C P</b>		
6 At FLUSH INSET DOORS:				
6	1	Use of the bottom member of the face frame is the manufacturers choice. <b>E C P</b>		
6	2	Use of the bottom member of the face frame is required <b>E C P</b>		



# SECTION 10 - ANNEX 10B

## HPDL Faced Casework

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally

<b>E</b>	<b>C</b>	<b>P</b>
----------	----------	----------

**compliance requirements**

# Additional Requirements for HPDL Faced Casework

10.4.5.B		Additional Material Rules for HPDL Faced Casework		
<b>1 EXPOSED EXTERIOR</b> surfaces require:				
1	1	LPDL of specified color or pattern.	<b>E</b>	<b>C</b> <b>P</b>
1	2	HPDL of specified color or pattern.	<b>E</b>	<b>C</b> <b>P</b>
1	3	Material, pattern, and color to be as specified, and:		
1	3	1	If not specified, to be a non premium priced, standard pattern or color of manufacturer's choice.	
1	3	2	Decorative laminate, to be a minimum VGS or VGP HPDL type, and:	
1	3	2	1	To be of one color or pattern per room, with a maximum of five different colors or patterns per project.
<b>2 EXPOSED INTERIOR</b> surfaces, except at doors and drawer fronts, require:				
2	1	LPDL of the manufacturer's choice.	<b>E</b>	<b>C</b> <b>P</b>
2	2	HPDL or LPDL compatible to exposed exterior surface in color, grain, or pattern.	<b>E</b>	<b>C</b> <b>P</b>
2	3	HPDL, the same as the exposed exterior surface.	<b>E</b>	<b>C</b> <b>P</b>
2	4	Inside face of solid door and drawer fronts to be:		
2	4	1	The same material and thickness as the face.	
2	4	2	The same material, pattern, color, and thickness as the door face.	
2	5	Inside face of framed glass doors to be:		
2	5	1	The same material and thickness as the face.	
2	5	2	The same material, pattern, color, and thickness as the door face.	
<b>Continues next column ▼</b>				

10.4.5.B		Additional Material Rules for HPDL Faced Casework		
<b>▲ From previous column</b>				
<b>3 SEMI-EXPOSED</b> surfaces require:				
3	1	LPDL or HPDL of the manufacturer's choice of color.		
<b>3 2 DRAWER BOX:</b>				
3	2	1	<b>SURFACES</b> to be:	
3	2	1	1	Consistent color to be used throughout entire project.
3	2	1	2	MDO, HPDL or LPDL of the manufacturer's color choice. <b>E</b> <b>C</b> <b>P</b>
3	2	1	3	HPDL or LPDL of the manufacturer's color choice. <b>E</b> <b>C</b> <b>P</b>
3	2	1	4	HPDL or LPDL matching the color of other semi-exposed surfaces. <b>E</b> <b>C</b> <b>P</b>
3	2	1	5	Allows vinyl overlay at drawer bottoms if matched in color to other drawer surfaces.
3	2	2	<b>DIVIDERS:</b>	
3	2	2	1	If hardboard, be tempered, smooth on both sides, and: <b>E</b> <b>C</b> <b>P</b>
3	2	2	1	1 Matching other drawer box surfaces is only required if so specified. <b>E</b> <b>C</b> <b>P</b>
3	2	2	2	Match other drawer box surfaces. <b>E</b> <b>C</b> <b>P</b>
<b>Continues next column ▼</b>				


# SECTION 10 - ANNEX 10B

## HPDL Faced Casework

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally

<b>E</b>	<b>C</b>	<b>P</b>
----------	----------	----------

compliance requirements

# Additional Requirements for HPDL Faced Casework

10.4.5.B		Additional Material Rules for HPDL Faced Casework							
▲ From previous column									
3	2	SEMI-EXPOSED surfaces require (continued)							
3	2	DRAWER BOX (continued)							
3	2	3	SIDES, BACK and SUB FRONTS with:						
3	2	3	1	CORES of:					
3	2	3	1	1	Minimum 7-ply hardwood plywood with no inner core voids of manufacturer's choice of species, MDO, MDF, particleboard.	E	C	P	
3	2	3	1	2	Minimum 7-ply hardwood plywood with no inner core voids of manufacturer's choice of species, MDF, particleboard.	E	C	P	
3	2	3	2	MINIMUM THICKNESS of:					
3	2	3	2	1	7/16" (11.1 mm).	E	C	P	
3	2	3	2	2	15/32" (12 mm), except:	E	C	P	
3	2	3	2	1	1	5/8" (16 mm) at drawer boxes wider than 30" (762 mm).	E	C	P
3	2	4	BOTTOMS with:						
3	2	4	1	CORES of:					
3	2	4	1	1	Veneer core plywood, tempered hardboard, or MDF.	E	C	P	
3	2	4	1	2	Veneer core plywood.	E	C	P	
3	2	4	2	MINIMUM THICKNESS of:					
3	2	4	2	1	13/64" (5.2 mm), except:				
3	2	4	2	1	1	1/4" (6.4 mm) at MDF.			
3	2	4	2	2	3/8" (9.5 mm) at drawers boxes wider than 30" (762 mm).	E	C	P	

10.4.7.B		Additional Assembly Rules for HPDL Faced Casework	
1	EXPOSED EDGES require:		
1	1	Unless specified otherwise, the sequence of the edge/face lamination shall be the manufacturer's choice.	
1	2	HPDL or PVC a minimum of 0.018" (0.5 mm) and maximum of 0.12" (3 mm) at the manufacturer's choice, well matched to the exposed face.	
1	3	PVC and ABS edgebanding thicker than 0.04" (1 mm) be radiused on edges and corners.	
2	DRAWERS require:		
2	1	Front and false front:	
2	1	1	To be edgebanded at all four edges, except when back beveled.
3	DOORS require:		
3	1	Edgebanding on all four edges matching exposed surfaces.	
3	2	Glass stops to be hardwood solid stock painted to match plastic or a synthetic (vinyl, neoprene, plastic) gasket/retainer; however:	
3	2	1	Synthetic stops are acceptable on the inside only.
3	3	When SLIDING:	
3	3	1	1/4" (6.4 mm) hardboard painted to match adjacent laminate is permitted.
3	3	2	INTERIOR FACES shall be of the same thickness and material as the exterior faces..



# SECTION 10 - ANNEX 10C

## Solid Phenolic Casework

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



compliance requirements

# Additional Requirements for Solid Phenolic Casework

<b>10.4.5.C</b>	<p style="color: green;"><b>Additional Material Rules for Solid Phenolic Casework</b></p> <p style="color: red;">Applicable to Custom or Premium Grade Only</p>
1	<b>EXPOSED EXTERIOR</b> surfaces require:
1 1	Material, pattern, and color to be as specified, and:
1 1 1	If not specified, to be a non premium priced, standard pattern, minimum 3/8" (9.5 mm) thick at the manufacturer's choice.
1 1 2	To be of one color per room, with a maximum of five different colors per project.
2	<b>EXPOSED INTERIOR</b> surfaces shall be the same as the exposed exterior surface.
3	<b>SEMI-EXPOSED</b> surfaces, including drawer boxes, require manufacturers' choice color, and:
3 1	<b>DRAWER</b> sides, back, and sub fronts, a minimum thickness of 1/2" (12.7 mm).
3 2	Drawer bottoms shall be a minimum of 1/4" (6.3 mm).

<b>10.4.7.C</b>	<p style="color: green;"><b>Additional Assembly Rules for Solid Phenolic Casework</b></p> <p style="color: red;">Applicable to Custom or Premium Grade Only</p>
1	<b>EDGEBANDING</b> is not required.
2	<b>DRAWER</b> front and false front thickness to be a minimum of 1/2" (12.7 mm).
3	<b>DOOR</b> thickness to be a minimum of 1/2" (12.7 mm), and:
3 1	Glass clips are permitted.
4	<b>APRONS</b> require a minimum thickness of 1/2" (12.7 mm).
5	<b>SHELVES</b> require a minimum thickness of 3/8" (9.5 mm).
6	<b>TOPS</b> and <b>FIXED BOTTOMS</b> require a minimum thickness of 1/2" (12.7 mm).
7	<b>END</b> and <b>DIVISIONS</b> require a minimum of 1/2" (12.7 mm) in thickness, and:
7 1	Applied ends are permitted.
8	<b>SECURITY</b> and <b>DUST PANELS</b> require a minimum thickness of 1/4" (6.4 mm).
9	<b>STRETCHERS</b> require a minimum of 1/2" (12.7 mm) in thickness and 2" (50.8 mm) in width.
10	<b>BREAD/CUTTING BOARDS</b> require a minimum of 1/2" (12.7 mm) in thickness.
11	For <b>JOINERY</b> , use of a 9/32" x 1-1/4" (7 mm x 32 mm) sheet metal screw is permitted with the first screw 1-15/16" (37 mm) from each edge or end and subsequent screws 5" (128 mm) on center, and:
11 1	Glue is not required.



## Additional Requirements for Laboratory Casework

Requires explicit specification requirement for such within contract documents.

### 10.1.D BASIC CONSIDERATIONS

1 The following **CONSIDERATIONS** and **REQUIREMENTS** for laboratory casework are in addition to those otherwise set forth within these standards, **AND**:

1.1 Shall be in concert with that of the Scientific Equipment and Furniture Association (SEFA), <http://sefalabs.com> Recommended Practices.

#### 2 TYPICAL INCLUSIONS

2.1 Wood, HPDL or solid phenolic faced laboratory casework

2.2 Matching furniture/fixture accessories

#### 3 TYPICAL EXCLUSIONS:

3.1 Metal casework or fabrications

3.2 Cylinder restraint assemblies

3.3 Pipe drop enclosures

3.4 Drying racks

3.5 Hoods or containment units

3.6 Slotted channel framing

3.7 Service fittings and fixtures

3.8 HAVC

3.9 Electrical or Communications

3.10 Stainless steel or other metal accessories

# SECTION 10 - ANNEX 10D

## Laboratory Casework

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



**compliance requirements**

# Additional Requirements for Laboratory Casework

**Requires explicit specification requirement for such within contract documents.**

10.4.4.D		Additional Basic Rules for Laboratory Casework Applicable to all Grades		
1	<b>CASEWORK</b> requires:			
1	1	ADJUSTABLE SHELF load capacities of 50 lbs per sq ft (244.1 kg/m <sup>2</sup> ).		
1	2	DRAWERS SLIDES be full extension suspension, ball bearing with minimum load capacity of 100 lb (45.4 kg).		
1	3	"WET" LAB toe bases be constructed of:		
1	3	1	Particleboard	E C P
1	3	2	Veneer core plywood with Type II adhesive.	E C P
1	3	3	Moisture resistant MDF with a 24-hour thickness swell factor of 4.5% or less.	E C P
1	4	<b>MECHANICAL CHASE ACCESS</b> at all base and peninsula cabinets, including drawer banks, and shall be:		
1	4	1	Neatly cut.	
1	4	2	As large as practical without interfering with installation requirements.	
1	5	<b>TALL CABINETS</b> , 72" (1829 mm) or taller, to have a fixed shelf approximately mid height.		
1	6	<b>REAGENT SHELVES</b> , to have a seismic rail or lip at front edge, including those behind doors, solid or glass.		
1	7	<b>SLIDE BOLTS</b> on inactive door at locking pairs, elbow catches are not acceptable, and:		
1	7	1	At tall storage cabinets over 72" (1829 mm), slide bolts shall have minimum 18" (457 mm) reach.	
Continues next column ▼				

10.4.4.D		Additional Basic Rules for Laboratory Casework Applicable to all Grades		
▲ From previous column				
2	<b>TABLES</b> require:			
2	1	Compliance to SEFA's (Scientific Equipment and Furniture Association, <a href="http://sefalab.com">http://sefalab.com</a> ) Table Structural Integrity Test as explained in the <b>APPENDIX</b> .		
2	2	Minimum 2" x 2" (51 x 51 mm) solid wood legs, with:		
2	2	1	Cross or "I" bracing.	
2	2	2	Minimum 1-1/2" (38.1 mm) diameter, non marring, 150 lb (68 kg) capacity, level adjustable glides.	
2	2	3	Minimum 4" (102 mm) tall vinyl or rubber leg shoes.	



# SECTION 10

## Casework

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



## compliance requirements

### 10.5 PREPARATION and QUALIFICATION REQUIREMENTS

- 1 **CARE, STORAGE, and BUILDING CONDITIONS** shall be in compliance with the requirements set forth in Section 2 of these standards.
- 1.1 Severe damage to the woodwork can result from noncompliance. The manufacturer and/or installer of the woodwork shall not be held responsible for damage that might develop by not adhering to the requirements.
- 2 **CONTRACTOR IS RESPONSIBLE FOR** 
- 2.1 Furnishing and installing structural members, grounds, in wall blocking, backing, furring, brackets, or other anchorage required for architectural woodwork installation that becomes an integral part of walls, floors, or ceilings to which architectural woodwork shall be installed.
- 2.1.1 In the absence of contract documents calling for the contractor to supply the necessary in wall blocking/backing in the wall or ceilings, either through inadvertence or otherwise, the architectural woodwork installer shall not proceed with the installation until such time as the in wall blocking/backing is installed by others.
- 2.1.2 Preparatory work done by others shall be subject to inspection by the architectural woodwork installer and may be accepted or rejected for cause prior to installation.
- 2.1.2.1 **WALL, CEILING, and/or opening variations** in excess of 1/4" (6.4 mm) or **FLOORS** in excess of 1/2" (12.7 mm) in 144" (3658 mm) of being plumb, level, flat, straight, square, or of the correct size are not acceptable for the installation of architectural woodwork, nor is it the responsibility of the installer to scribe or fit to tolerances in excess of such.
- 2.2 Installation site being properly ventilated, protected from direct sunlight, excessive heat and/or moisture, and that the HVAC system is functioning and maintaining the appropriate relative humidity and temperature.
- 2.3 Priming architectural woodwork in accordance with the contract documents prior to its installation:
- 2.3.1 If the architectural woodwork is factory finished, priming by the factory finisher is required.

### 10.5 PREPARATION and QUALIFICATION (continued)

- 3 **INSTALLER IS RESPONSIBLE FOR** 
- 3.1 Having adequate equipment and experienced craftsmen to complete the installation.
- 3.2 Checking architectural woodwork specified and studying the appropriate portions of the contract documents, including these standards and the reviewed shop drawings to familiarize themselves with the requirements of the Grade specified, understanding that:
- 3.2.1 Appearance requirements of Grades apply only to surfaces visible after installation.
- 3.2.2 For transparent finish, special attention needs to be given to the color and the grain of the various woodwork pieces to ensure they are installed in compliance with the Grade specified.
- 3.3 Verification that installation site is properly ventilated, protected from direct sunlight, excessive heat and/or moisture, and that the HVAC system is functioning and maintaining the appropriate relative humidity and temperature.
- 3.4 Verification that required priming of woodwork has been completed by others before woodwork is installed.
- 3.5 Verification that woodwork has been acclimated to the field conditions for a minimum of 72 hours before installation is commenced.
- 3.6 Woodwork specifically built or assembled in sequence for match of color and grain is installed to maintain that same sequence.

# SECTION 10

## Casework

### GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally

<b>E</b>	<b>C</b>	<b>P</b>
----------	----------	----------

## compliance requirements

### 10.6 RULES

- 1 The following rules shall govern unless a project's contract documents require otherwise.
- 2 These rules are intended to provide a well defined degree of control over a project's quality of installation.
- 3 **ERRATA**, published at <http://naaws-errata.com>, shall take precedence over these rules, subject to their date of posting and a project's bid date.



<b>10.6.4 Basic General Rules</b>	
<b>1</b>	<b>AESTHETIC</b> grade rules apply only to exposed and semi-exposed surfaces visible after installation.
<b>2</b>	For <b>TRANSPARENT</b> finish, woodwork shall be installed:
<b>2 1</b>	With consideration of color and grain. <span style="float: right;">E C P</span>
<b>2 2</b>	<b>COMPATIBLE</b> in color and grain. <span style="float: right;">E C P</span>
<b>2 3</b>	<b>WELL MATCHED</b> for color and grain. <span style="float: right;">E C P</span>
<b>3</b>	<b>REPAIRS</b> are allowed, provided they are neatly made and inconspicuous when viewed at:
<b>3 1</b>	72" (1830 mm). <span style="float: right;">E C P</span>
<b>3 2</b>	48" (1220 mm). <span style="float: right;">E C P</span>
<b>3 3</b>	24" (610 mm). <span style="float: right;">E C P</span>
<b>4</b>	<b>INSTALLER FABRICATION</b> or <b>MODIFICATIONS</b> shall comply to the general, material, machining, and assembly rules within the <b>PRODUCT</b> portion of this section and the applicable finishing rules in Section 5.
<b>5</b>	<b>CASEWORK</b> or related items:
<b>5 1</b>	Shall be securely fastened and tightly fitted with flush joint tolerances as set forth in these standards.
<b>5 1 1</b>	Joinery shall be consistent throughout the project.
<b>5 2</b>	Such as scribe molds shall be of maximum available and/or practical lengths and:
<b>5 2 1</b>	Mitered at outside corners.
<b>5 3</b>	Shall be Installed plumb, level, square, flat and in plane within 1/8" (3.2 mm) in 96" (2438 mm), and when required:
<b>5 3 1</b>	Grounds and hanging systems set plumb and true.
Continues next column ▼	

<b>10.6.4 Basic General Rules</b>	
▲ From previous column	
<b>5</b>	<b>CASEWORK</b> or related items (continued)
<b>5 4</b>	Shall be Installed free of:
<b>5 4 1</b>	Warp, twisting, cupping, and/or bowing that cannot be held true.
<b>5 4 2</b>	Open joints, visible machine marks, cross sanding, tear outs, nicks, chips, and/or scratches.
<b>5 4 3</b>	Natural defects exceeding the quantity or size limits defined in Sections 3 and 4.
<b>5 4 4</b>	Exposed fasteners at exposed exterior surfaces.
<b>5 5</b>	Shall be smooth and sanded without cross scratches in conformance to the <b>PRODUCT</b> portion of this section.
<b>5 6</b>	Shall be <b>SCRIBED</b> at:
<b>5 6 1</b>	Flat surfaces. <span style="float: right;">E C P</span>
<b>5 6 2</b>	Shaped surfaces. <span style="float: right;">E C P</span>
<b>THESE STANDARDS</b> do not establish grade rules for joint flushness and or gap tolerances for woodwork products installed in a non climate controlled environment.	
<b>GAPS</b> (see Test I illustrations in <b>TESTS</b> ) such as,	
<b>7</b>	
and:	
<b>7 1</b>	If caused by excessive deviations in the building's walls and ceilings being in excess of 1/4" (6.4 mm) in 144" (3658 mm) of being plumb, level, flat, straight, square, or of the correct size, or 1/2" (12.7 mm) for floors, shall not be considered a defect or the responsibility of the installer.
<b>7 2</b>	Shall not exceed 30% of a joint's length, with:
<b>7 2 1</b>	Be allowed if filled or caulked, and: <span style="float: right;">E C P</span>
<b>7 2 1 1</b>	If color compatible. <span style="float: right;">E C P</span>
Continues next column ▼	

# SECTION 10


## Casework

### GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally

<b>E</b>	<b>C</b>	<b>P</b>
----------	----------	----------

## compliance requirements

10.6.4		Basic General Rules			
▲ From previous column					
7	<b>GAPS</b> (continued)				
7	<b>3</b> Of <b>WOOD</b> to <b>WOOD</b> shall not exceed:				
7	<b>3 1</b> At <b>FLAT</b> surfaces:				
7	3	1	1	0.030" (0.76 mm) in width.	E C P
7	3	1	2	0.020" (0.51 mm) in width.	E C P
7	3	1	3	0.015" (0.38 mm) in width.	E C P
7	<b>3 2</b> At <b>SHAPED</b> surfaces:				
7	3	2	1	0.040" (1.02 mm) in width.	E C P
7	3	2	2	0.025" (0.64 mm) in width.	E C P
7	3	2	3	0.015" (0.38 mm) in width.	E C P
7	<b>4</b> Of <b>WOOD</b> to <b>NON WOOD</b> shall not exceed:				
7	<b>4 1</b> At <b>FLAT</b> and <b>SHAPED</b> surfaces:				
7	4	1	1	0.075" (1.91 mm) in width.	E C P
7	4	1	2	0.050" (1.27 mm) in width.	E C P
7	4	1	3	0.035" (0.89 mm) in width.	E C P
7	<b>5</b> Of <b>NON WOOD</b> to <b>NON WOOD</b> and/or <b>ALL ELEMENTS</b> shall not exceed:				
7	<b>5 1</b> At <b>FLAT</b> surfaces:				
7	5	1	1	0.075" (1.91 mm) in width.	E C P
7	5	1	2	0.050" (1.27 mm) in width.	E C P
7	5	1	3	0.035" (0.89 mm) in width.	E C P
7	<b>5 2</b> At <b>SHAPED</b> surfaces:				
7	5	2	1	0.120" (3.05 mm) in width.	E C P
7	5	2	2	0.075" (1.91 mm) in width.	E C P
7	5	2	3	0.050" (1.27 mm) in width.	E C P
<p><b>FLUSHNESS</b> of joinery (see Test J illustrations in TESTS), such as,</p>  <p>and:</p>					
Continues next column ▼					

10.6.4		Basic General Rules			
▲ From previous column					
8	<b>FLUSHNESS</b> (continued):				
8	<b>1</b> Of <b>WOOD</b> to <b>WOOD</b> shall not exceed:				
8	<b>1 1</b> At <b>FLAT</b> surfaces:				
8	1	1	1	0.025" (0.64 mm).	E C P
8	1	1	2	0.015" (0.38 mm).	E C P
8	1	1	3	0.010" (0.25 mm).	E C P
8	<b>1 2</b> At <b>SHAPED</b> surfaces:				
8	1	2	1	0.040" (0.97 mm).	E C P
8	1	2	2	0.025" (0.65 mm).	E C P
8	1	2	3	0.020" (0.51 mm).	E C P
8	<b>2</b> Of <b>WOOD</b> to <b>NON WOOD</b> shall not exceed:				
8	<b>2 1</b> At <b>FLAT</b> and <b>SHAPED</b> surfaces:				
8	2	1	1	0.075" (1.91 mm).	E C P
8	2	1	2	0.050" (1.27 mm).	E C P
8	2	1	3	0.035" (0.89 mm).	E C P
8	<b>3</b> Of <b>NON WOOD</b> to <b>NON WOOD</b> and/or <b>ALL ELEMENTS</b> shall not exceed:				
8	<b>3 1</b> At <b>FLAT</b> surfaces:				
8	3	1	1	0.075" (1.91 mm).	E C P
8	3	1	2	0.050" (1.27 mm).	E C P
8	3	1	3	0.035" (0.89 mm).	E C P
8	<b>3 2</b> At <b>SHAPED</b> surfaces:				
8	3	2	1	0.120" (3.05 mm).	E C P
8	3	2	2	0.075" (1.91 mm).	E C P
8	3	2	3	0.050" (1.27 mm).	E C P
<p><b>GAPS, EDGE ALIGNMENT</b> and <b>FLUSHNESS</b> of doors and drawers</p> <p><b>9</b> shall be uniform and within the tolerances set forth in the Product portion of this section, and:</p> <p><b>9 1</b> Door and drawer fronts shall align vertically and horizontally, and:</p> <p><b>9 1 1</b> Be flush (on the same plane) to one another.</p> <p><b>9 1 2</b> Minor adjustments are the responsibility of the installer.</p>					
Continues next column ▼					

# SECTION 10

## Casework

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally

<b>E</b>	<b>C</b>	<b>P</b>
----------	----------	----------

## compliance requirements

10.6.4		Basic General Rules		
▲ From previous column				
10	SCRIBING shall be provided where cabinets contact finished walls or ceiling as elaborated below and in the Product portion of this section, and:			
10 1	Is not required.	E	C	P
10 2	Shall be <b>FURNISHED</b> by the manufacturer, and:	E	C	P
10 2 1	Scribe <b>FILLERS</b> shall not exceed 1-1/2" (38.1 mm) in width.	E	C	P
10 2 2	Scribe <b>MOLDS</b> shall not exceed 1-1/2" (38.1 mm) in width, and;	E	C	P
10 2 2 1	End joints may be butt jointed.	E	C	P
10 2 2 2	End joints shall be beveled, and:	E	C	P
10 2 2 2 1	Corners shall be mitered or coped.	E	C	P
10 2 2 3	Are not <b>NOT ALLOWED</b> .	E	C	P
10 3	Match exposed surfaces.			
10 4	Be furnished in maximum available lengths, joints not allowed in material less than 96" (2438 mm).			
10 5	Permits <b>COLOR COMPATIBLE CAULKING</b> not to exceed 1/8" (3.2 mm).	E	C	P
10 6	Fillers at inside corners where two elevations of casework meet must be equal in width, and:			
10 6 1	Not to exceed a maximum of 3" in width unless required for hardware clearance during operation.			
10 7	Requires <b>SOFFIT</b> or <b>FASCIA PANELS</b> to be furnished in maximum available lengths, joints not allowed in material less than 96" (2438 mm) at horizontal grain or directional pattern and 48" (1220 mm) at vertical grain or directional pattern, and:	E	C	P
10 7 1	Be a minimum of 3/4" (19 mm) in thickness.			
10 7 2	Grain direction (if any) shall run vertical, or be manufacturer's choice if less than:			
10 7 2 1	12" (305 mm) tall.	E	C	P
10 7 2 2	1-1/2" (38.1 mm) tall.	E	C	P
Continues next column ▼				

10.6.4		Basic General Rules		
▲ From previous column				
10	SCRIBING (continued)			
10 8	TYPICAL SCRIBING OPTIONS:			
10 8 1	<p>Scribe Filler.</p>			
10 8 2	<p>Scribe Mold.</p>			
10 8 3	<p>Scribe Allowance.</p>			
10 9	At tall and wall hung cabinets, closure panels shall be provided at top and bottom voids.	E	C	P
10 10	Allowable gap at the back bottom edge of wall hung cabinets shall not exceed that listed below and, when scribing is necessary, the use of a separate scribe mold is permitted:	E	C	P
10 10 1	1/2" (12.7 mm).	E	C	P
10 10 2	1/4" (6.4 mm).	E	C	P
11	<b>CLOSURE</b> provision is required at voids or open spaces between cabinets and walls, such as at the top of tall and upper cabinets and the bottom of upper cabinets caused by scribing or angle turns, and:			
11 1	At non visible voids, 1-1/2" (38 mm) or less in width, a piece of standard grade laminate may be used as a closure cap. 			
Continues next column ▼				

# SECTION 10



## Casework


GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally

**E C P**

# compliance requirements

10.6.4 Basic General Rules	
▲ From previous column	
11	<b>CLOSURE</b> provision is required (continued)
11 2	At non visible voids, exceeding 1-1/2" (38 mm) in width, a minimum 3/4" (19 mm) closure filler shall be provided of manufacturer's choice. 
11 3	At visible voids, a minimum 3/4" (19 mm) closure filler shall be provided matching the adjacent surface.
12	<b>EXPOSED FASTENERS</b> are not permitted at exposed exterior surfaces, except: <span style="float: right;">E C P</span>
12 1	At access panels.
13	<b>CASEWORK WALL ANCHORAGE</b> , except for peninsula/island or base casework with mechanical spacing allowances (because of the need to be engineered on an individual basis), requires:
13 1	<b>CONTINUOUS IN WALL BLOCKING</b> or <b>BACKING</b> of at least 2" x 6" (51 mm x 152 mm) nominal wood or 6" x 16 ga (152 mm x 1.4 mm) sheet metal, installed by others, shall be appropriately located in all wood or metal stud walls as shown below: 
Continues next column ▼	

10.6.4 Basic General Rules	
▲ From previous column	
13	<b>CASEWORK WALL ANCHORAGE</b> (continued)
13 2	<b>MANUFACTURER</b> to provide appropriate location layouts on their shop drawings for in wall blocking or backing for all tall, base, and wall hung casework for both top and bottom runs of fasteners, as shown below: 
13 3	<b>ADJACENT</b> cabinet units to be fastened together at the front with a minimum of two #8 x 1-1/4" (31.7 mm) flat, oval, or pan head screws, a maximum of 30" (762 mm) on center, and:
13 3 1	Binder head sex bolts are permitted.
13 3 2	At exposed interior surfaces, cover caps of compatible color to interior are required. <span style="float: right;">E C P</span>
13 4	<b>ANCHORAGE FASTENERS</b> to be neatly installed through the back and anchor strip, at the top and bottom at each cabinet body, and:
13 4 1	At the intermediate height of cabinets over 60" (1524 mm) tall.
13 4 2	Within <b>UNITED STATES</b> , minimum of 3" (76.2 mm) x #14 (6.3 mm) diameter screw with a surface bearing head.
13 4 3	Within <b>CANADA</b> , minimum of 3" (76.2 mm) x #10 (4.6 mm) diameter screw with a surface bearing head.
13 4 4	Achieve a minimum penetration of 1-3/8" (34.9 mm) into the wall studs, in wall blocking, or masonry walls.
Continues next column ▼	

# SECTION 10

## Casework

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



## compliance requirements

10.6.4		Basic General Rules	
▲ From previous column			
13	CASEWORK WALL ANCHORAGE (continued)		
13	4	ANCHORAGE FASTENERS (continued)	
13	4	5	Use of drywall or bugle head screws is prohibited.
13	4	6	At Exposed Interior surfaces, exposed screw heads shall be painted or covered with caps of compatible color to interior surface. <span style="float: right;">E C P</span>
13	5	Each cabinet unit or undivided span shall have a minimum of four anchorage fasteners; two at the top and two at the bottom, subject to:	
13	5	1	Horizontally, within 3" (76.2 mm) of the outside end and equally spaced, at:
13	5	1	1 A maximum spacing of 16" (406 mm) on center, except:
13	5	1	1 Wall cabinet units over 48" (1,219 mm) in height shall be 12" (305 mm).
13	5	2	Vertically, within 3" (76.2 mm) of the outside top or bottom of the cabinet unit and must penetrate the anchor strip.
13	5	3	A locking hanging cleat, or other concealed method of installation may be used, provided it has been independently tested to show compliance to the Wall Cabinet Structural Integrity Test shown in the <b>APPENDIX</b> . <span style="float: right;"></span>
13	5	3	1
Continues next column ▼			

10.6.4		Basic General Rules	
▲ From previous column			
13	CASEWORK WALL ANCHORAGE (continued)		
13	6	Bases or toes are not required to be anchored to the floor; however:	
13	6	1	Separate bases or toes are required to be mechanically fastened in the field to the cabinet bottom with flat head screws set flush or slightly recessed, to prevent their movement, and:
13	6	1	1 Screw heads in cabinet bottoms, where exposed, shall be covered with color compatible adhesive caps.
14	NAIL HOLES through semi-exposed surfaces shall be countersunk and filled with color matched to the adjacent surface.		
15	GLUE and filler residue is not permitted on exposed faces.		
16	CAULKING, when used to fill gaps and/or voids, shall be color compatible and installed neatly.		
17	REQUIRE allowable fastener holes, when:		
17	1	Pre-finished materials to be filled by the installer with matching filler furnished by the manufacturer.	
17	2	Unfinished materials to be filled by the paint contractor or others.	
18	EQUIPMENT CUTOUTS, including electrical and plumbing, shall be cut out by the installer, provided templates are furnished prior to installation, and:		
18	1	Shall be neatly cut and properly sized to be covered by standard cover plates or rosettes.	
18	2	In HPDL shall have a minimum 1/4" (6.4 mm) radius at inside corners.	
19	HARDWARE shall be installed:		
19	1	Neatly without tear out of surrounding stock.	
19	2	Per the manufacturer's instructions.	
19	3	Using all furnished fasteners or fastener provisions and when fastener provisions are countersunk, fasteners shall be countersunk.	
19	4	Properly, fitted and adjusted to ensure correct and smooth operation.	
Continues next column ▼			

# SECTION 10

## Casework

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



**compliance requirements**

10.6.4		Basic General Rules	
▲ From previous column			
20	AREAS of INSTALLATION shall be left broom clean of:		
20	1	Debris shall be removed and dumped in containers provided by the contractor.	
20	2	Items installed shall be cleaned of pencil or ink marks.	
21	FIRST CLASS WORKMANSHIP is required in compliance with these standards.		
<b>Specific INSTALLATION Requirements for Seismic Casework Installation may be found in Annex E which follow herein.</b> 			



## Additional Requirements for Seismic Casework Installation

**Requires explicit specification requirement for such within contract documents.**

**10.5.E ADDITIONAL PREPARATION REQUIREMENTS**  
**Applicable for all Grades**

**CAUTION** - It is the users responsibility to confirm compatibility, acceptability and scope of these seismic engineered installation standards. The Sponsor Associations shall not be responsible to anyone for the use of or reliance upon these standards, nor shall they incur any obligation nor liability for damages, including consequential damages, arising out of or in connection with the use, interpretation of, or reliance upon these standards. 

- 1 These engineered seismic casework installation standards are based on 2010 and 2013 California Building Code (CBC) requirements for use in California (approved by the California Office of Statewide Health Planning and Development (OSHPD) and accepted by California Division of State Architecture (DSA)); however, may also be adequate for use in other areas that base their requirements on the International Building Code (IBC). This engineering is applicable for the installation of casework in building structures:
  - 1.1 At any height within the building where  $z/h \leq 1.0$
  - 1.2 Where the SDS is not greater than:
    - 1.2.1 1.93 for base, peninsula and mechanical chase cabinets
    - 1.2.2 2.0 for wall and tall storage cabinets, and includes:
  - 1.3 At concrete or concrete masonry unit (CMU) wall construction when grouted solid.
  - 1.4 At wood or metal stud wall construction with either continuous 3 x 6 (76 x 152 mm) or 16 gauge in wall blocking respectively, with:
    - 1.4.1 One or two layers of 5/8" (16 mm) sheetrock.

**10.5.E ADDITIONAL PREPARATION** (continued)  
**Applicable for all Grades**

- 1.5 Where Casework construction is of plywood, particleboard, MDF or Solid Phenolic Core (SPC) and in compliance with the minimum requirements of the North American Architectural Woodwork Standards (NAAWS), including:
  - 1.5.1 Base cabinets, up to 36" (914 mm) tall x 24" (610 mm) body depth x 48" (1220 mm) wide, including peninsula and those with mechanical chase
  - 1.5.2 Wall cabinets up to 48" (1220 mm) tall x 18" (457 mm) body depth x 48" (1220 mm) wide
  - 1.5.3 Tall storage cabinets up to 96" (2413 mm) tall x 24" (610 mm) body depth x 48" (1220 mm) wide
  - 1.5.4 Peninsula base cabinets up to 36" (914 mm) tall x 36" (914 mm) body depth x 48" (1220 mm) wide
  - 1.5.5 Mechanical chase base cabinets up to 42" (1067 mm) tall x 36" (914 mm) body depth and 48" (1220 mm) wide

- 2 **CONTRACTOR IS RESPONSIBLE FOR:** 
  - 2.1 **FURNISHING and INSTALLING** in wall blocking and backing anchorage required for seismic casework installation, in accordance with these standards, that becomes an integral part of the walls to which architectural woodwork shall be installed.
    - 2.1.1 In the absence of contract documents calling for the contractor to supply the necessary in wall blocking/backing in the wall, either through inadvertence or otherwise, the architectural woodwork installer shall not proceed with the installation until such time as the in wall blocking/backing is installed by others.
    - 2.1.2 In wall blocking/backing is installed by others shall be subject to inspection by the architectural woodwork installer and may be accepted or rejected for cause prior to installation.

## Additional Requirements for Seismic Casework Installation

Requires explicit specification requirement for such within contract documents.

### 10.5.E ADDITIONAL PREPARATION (continued) Applicable for all Grades

#### 3 INSTALLER IS RESPONSIBLE FOR



- 3.1 Ensuring that the casework shop drawings:
  - 3.1.1 Are in compliance with the NAAWS's minimum requirements as established in Section 1, Including:
    - 3.1.1.1 Casework elevations showing the center-line height and horizontal locations of all required, continuous, internal wall blocking furnished by others.
    - 3.1.1.2 A casework fastener schedule, clearly showing the type, size, location and maximum spacing of the installation fasteners.
  - 3.2 At wood or metal stud walls, prior to application of wall surfacing, examine, approve and acknowledge blocking compliance.

# SECTION 10 - ANNEX 10E

## Seismic Casework Installation

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



**compliance requirements**

# Additional Requirements for Seismic Casework Installation

Requires explicit specification requirement for such within contract documents.

10.6.4.E		Additional General Rules for Seismic Casework Installation Applicable for all Grades	
1		<b>CABINET FABRICATION</b> shall meet the following additional requirements:	
1	1	Nailers shall be minimum 3/4" (19 mm) in thickness, of veneer core plywood (Struct. 1), MDF Grade 150 or Douglas Fir with a specific gravity of 0.5 or higher.	
1	2	Tall storage cabinets shall have a fixed shelf approximately mid height securely attached to the cabinet back and nailer.	
2		<b>WALL BLOCKING/BACKING</b> shall be:	
2	1	For wood stud walls, minimum:	
2	1	1 3 x 6 Douglas Fir (#2 or better).	
2	1	2 16 ga, x 6", 50 KSI sheet metal.	
2	2	For metal stud walls, minimum:	
2	2	1 16 ga, x 6", 50 KSI sheet metal.	
3		<b>INSTALLATION FASTENERS</b> shall:	
3	1	For <b>WOOD STUD WALLS</b> with wood or metal blocking/backing, be minimum:	
3	1	1 #14 washer head wood screw (WS) with minimum 2-1/2" wood blocking penetration.	
3	1	2 #14 washer head Sheet Metal Screws (SMS) with minimum 2-1/2" wood blocking penetration.	
3	1	3 #14 washer head Sheet Metal Screws (SMS) with minimum of three threads extending beyond sheet metal backing.	
3	2	For <b>METAL STUD WALLS</b> with metal backing, be minimum:	
3	2	1 #14 washer head Sheet Metal Screws (SMS) with minimum of three threads extending beyond sheet metal backing.	
<b>Continues next column</b> ▼			

10.6.4.E		Additional General Rules for Seismic Casework Installation Applicable for all Grades	
<b>▲ From previous column</b>			
3		<b>INSTALLATION FASTENERS</b> shall (continued)	
3	3	For <b>CONCRETE WALLS</b> of minimum 4" in thickness:	
3	3	1 3/8" Hilti KWIK BOLT TZ, ICC ESR-1917 (or equal) with minimum 2" embedment and minimum 6" clearance from any wall edge.	
3	4	For <b>CONCRETE MASONRY BLOCK WALL (CMU)</b> , grouted solid:	
3	4	1 3/8" HILTI KWIK Bolt – 3 (or equal) with minimum 2-1/2" embedment and minimum 4" clearance from any wall edge.	
4		<b>INSTALLATION FASTENER PLACEMENT</b> requires:	
4	1	<b>ALL CABINET</b> to have a minimum of 4 fasteners, one each in the four corners of each cabinet box,	
		and:	
4	1	1 Tall storage cabinets require a minimum of 6 fasteners with the additional requirement of one or two rows of fasteners at the mid-height fixed shelf.	
4	1	2 Each fastener shall be centered a maximum of 3" (76 mm) and minimum of 2" (51 mm) from the outside edge, top and/or bottom of the cabinet box.	
4	1	3 All additional fastener requirements outlined for specific cabinet types below:	
<b>Continues next column</b> ▼			

# SECTION 10 - ANNEX 10E

## Seismic Casework Installation

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



**compliance requirements**

# Additional Requirements for Seismic Casework Installation

Requires explicit specification requirement for such within contract documents.

10.6.4.E		Additional General Rules for Seismic Casework Installation Applicable for all Grades	
▲ From previous column			
4	INSTALLATION FASTENER PLACEMENT (continued)		
4	2	For <b>TALL STORAGE CABINETS</b> not to exceed 48" (1220 mm) in width or 96" (2438 mm) in height, and either 12" (305 mm) or 24" (610 mm) Maximum	
and:			
4	2	1	12" (305 mm) or less in depth, excluding doors or drawer fronts:
4	2	1	1 At <b>WOOD</b> or <b>METAL STUD</b> walls: Requires two additional horizontal rows of fasteners, approximately 2" (51 mm) apart split vertical above and below the fixed mid-height shelf.
4	2	1	1 <b>WITH UP TO</b> 1 layer of 5/8" (16 mm) drywall
4	2	1	1 The maximum horizontal spacing between fasteners in the top, bottom or middle rows shall not exceed 12" (305 mm) on center.
4	2	1	2 <b>WITH UP TO</b> 2 layers of 5/8" (16 mm) drywall:
4	2	1	2 1 The maximum horizontal spacing between fasteners in the top, bottom or middle rows shall not exceed 10-1/2" (267 mm) on center.
Continues next column ▼			

10.6.4.E		Additional General Rules for Seismic Casework Installation Applicable for all Grades	
▲ From previous column			
4	INSTALLATION FASTENER PLACEMENT (continued)		
4	2	For <b>TALL STORAGE CABINETS</b> (continued)	
4	2	1	12" (305 mm) or less in depth (continued)
4	2	1	2 At <b>CONCRETE</b> or <b>CONCRETE BLOCK</b> walls:
4	2	1	2 1 Requires one additional horizontal row of fasteners below the fixed mid-height shelf.
4	2	1	2 2 The maximum horizontal spacing between fasteners in the top, bottom or middle rows shall not exceed 14" (357 mm) on center.
4	2	2	24" (610 mm) or less in depth, excluding doors or drawer fronts:
4	2	2	2 At <b>WOOD</b> or <b>METAL STUD</b> walls:
4	2	2	2 1 Requires two additional horizontal rows of fasteners, approximately 2" (51 mm) apart split vertical above and below the fixed mid-height shelf.
4	2	2	2 1 1 <b>WITH UP TO</b> 1 layer of 5/8" (16 mm) drywall
4	2	2	2 1 1 The maximum horizontal spacing between fasteners in the top, bottom or middle rows shall not exceed 6" (152 mm) on center.
4	2	2	2 1 2 <b>WITH UP TO</b> 2 layers of 5/8" (16 mm) drywall:
4	2	2	2 1 2 1 The maximum horizontal spacing between fasteners in the top, bottom or middle rows shall not exceed 5-1/4" (133 mm) on center.
Continues next column ▼			

# SECTION 10 - ANNEX 10E

## Seismic Casework Installation

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



**compliance requirements**

# Additional Requirements for Seismic Casework Installation

Requires explicit specification requirement for such within contract documents.

10.6.4.E		Additional General Rules for Seismic Casework Installation Applicable for all Grades	
▲ From previous column			
4	INSTALLATION FASTENER PLACEMENT (continued)		
4 2	For <b>TALL STORAGE CABINETS</b> (continued)		
4 2 1	12" (305 mm) or less in depth (continued)		
4 2 2 3	At <b>CONCRETE</b> or <b>CONCRETE BLOCK</b> walls:		
4 2 2 3 1	Requires one additional horizontal row of fasteners below the fixed mid-height shelf.		
4 2 2 3 2	At <b>CONCRETE</b> walls:		
4 2 2 3 2 1	The maximum horizontal spacing between fasteners in the top, bottom or middle rows shall not exceed 14" (357 mm) on center.		
4 2 2 3 3	At <b>CONCRETE BLOCK</b> walls:		
4 2 2 3 3 1	The maximum horizontal spacing between fasteners in the top, bottom or middle rows shall not exceed 21" (533 mm) on center.		
4 3	For <b>WALL HUNG CABINETS</b> not to exceed 48" (1220 mm) in width or height, and either 14" (356 mm) or 18" (472 mm) Maximum		
	and:		
4 3 1	14" (357 mm) or less in depth, excluding doors or drawer fronts:		
4 3 1 1	At <b>WOOD</b> or <b>METAL STUD</b> walls:		
4 3 1 1 1	<b>WITH UP TO 1</b> layer of 5/8" (16 mm) drywall		
4 3 1 1 1 1	The maximum horizontal spacing between fasteners in the top or bottom shall not exceed 8" (203 mm) on center.		
Continues next column ▼			

10.6.4.E		Additional General Rules for Seismic Casework Installation Applicable for all Grades	
▲ From previous column			
4	INSTALLATION FASTENER PLACEMENT (continued)		
4 3	For <b>WALL HUNG CABINETS</b> (continued)		
4 3 1	14" (357 mm) or less in depth (continued)		
4 3 1 1	At <b>WOOD</b> or <b>METAL STUD</b> walls (continued)		
4 3 1 1 2	<b>WITH UP TO 2</b> layers of 5/8" (16 mm) drywall:		
4 3 1 1 2 1	The maximum horizontal spacing between fasteners in the top or bottom rows shall not exceed 6" (152 mm) on center.		
4 3 1 2	At <b>CONCRETE</b> or <b>CONCRETE BLOCK</b> walls:		
4 3 1 2 1	The maximum horizontal spacing between fasteners in the top or bottom rows shall not exceed 14" (357 mm) on center.		
4 3 2	18" (610 mm) or less in depth, excluding doors or drawer fronts:		
4 3 2 1	At <b>WOOD</b> or <b>METAL STUD</b> walls:		
4 3 2 1 1	Requires two horizontal rows of fasteners at the top and bottom, approximately 2" (51 mm) apart vertically.		
4 3 2 1 1 1	<b>WITH UP TO 1</b> layer of 5/8" (16 mm) drywall		
4 3 2 1 1 1 1	The maximum horizontal spacing between fasteners in the top or bottom rows shall not exceed 12" (305 mm) on center.		
4 3 2 1 1 2	<b>WITH UP TO 2</b> layers of 5/8" (16 mm) drywall:		
4 3 2 1 1 2 1	The maximum horizontal spacing between fasteners in the top or bottom rows shall not exceed 10" (254 mm) on center.		
Continues next column ▼			

# SECTION 10 - ANNEX 10E

## Seismic Casework Installation

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



compliance requirements

# Additional Requirements for Seismic Casework Installation

Requires explicit specification requirement for such within contract documents.

10.6.4.E		Additional General Rules for Seismic Casework Installation Applicable for all Grades	
▲ From previous column			
4	INSTALLATION FASTENER PLACEMENT (continued)		
4	3	For <b>WALL HUNG CABINETS</b> (continued)	
4	3	2	18" (610 mm) or less in depth (continued)
4	3	2	2 At <b>CONCRETE</b> or <b>CONCRETE BLOCK</b> walls:
4	3	2	1 The maximum horizontal spacing between fasteners in the top or bottom rows shall not exceed 10-1/2" (267 mm) on center.
4	4	For <b>BASE CABINETS</b> not to exceed 36" (914 mm) in height (including countertop) and 24" (610 mm) in depth (excluding doors or drawer fronts),	
		and:	
4	4	1	<b>INCLUDING</b> the two fasteners in each corner of the top and bottom rows of fasteners, the total number of fasteners per row shall be:
4	4	1	1 At <b>WOOD</b> or <b>METAL STUD</b> walls with up to 2 layer of 5/8" (16 mm) drywall:
4	4	1	1 2 for cabinets 12" (305 mm) or less in width
4	4	1	2 3 for cabinets 24" (610 mm) or less in width
4	4	1	3 4 for cabinets 36" (914 mm) or less in width
4	4	1	4 5 for cabinets 48" (1220 mm) or less in width
Continues next column ▼			

10.6.4.E		Additional General Rules for Seismic Casework Installation Applicable for all Grades	
▲ From previous column			
4	INSTALLATION FASTENER PLACEMENT (continued)		
4	4	For <b>BASE CABINETS</b> not to exceed (continued)	
4	4	1	<b>INCLUDING</b> the two fasteners in each corner (continued)
4	4	1	2 At <b>CONCRETE</b> walls:
4	4	1	2 2 for cabinets 24" (610 mm) or less in width
4	4	1	2 3 for cabinets 48" (1220 mm) or less in width
4	4	1	3 At <b>CONCRETE BLOCK</b> walls:
4	4	1	3 1 2 for cabinets 24" (610 mm) or less in width
4	4	1	3 2 3 for cabinets 36" (914 mm) or less in width
4	4	1	3 3 4 for cabinets 48" (1220 mm) or less in width
4	5	For <b>BASE CABINETS</b> with utility chase not to exceed 42" (1067 mm) in height (including countertop), 36" (914 mm) in depth (excluding doors, drawer fronts and utility chase) and 48" (1220 mm) in width requires:	
4	5	1	Integral toe base construction.
Continues next column ▼			

# SECTION 10 - ANNEX 10E

## Seismic Casework Installation

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



**compliance requirements**

# Additional Requirements for Seismic Casework Installation

Requires explicit specification requirement for such within contract documents.

10.6.4.E		Additional General Rules for Seismic Casework Installation Applicable for all Grades	
▲ From previous column			
4	INSTALLATION FASTENER PLACEMENT (continued)		
4	5	For <b>BASE CABINETS</b> with utility chase (continued)	
4	5	2	Anchorage of the toe base to the floor at front only with:
4	5	2	1 A continuous, for each cabinet unit, bent 16 gauge sheet metal 2.5" x 2.5" (64 mm x 64 mm) angle (FY+50KSI) shall be:
4	5	2	1 1 Mounted to the floor with 3/8" diameter Simpson Strong Bolt 2 (or equal) with minimum 2" (51 mm) embedment within 2" (51 mm) of each end and a maximum of 11" (279 mm) on center.
4	5	2	1 2 Fastened to the front left/right toe base member with # 12 sheet metal screws, driven through the toe base member into the metal angle within 4" (102 mm) of each end and a maximum of 12" (305 mm) on center.
4	5	3	Anchorage of the cabinet to the wall as follows:
4	5	3	1 A continuous bent 16 gauge sheet metal channel (FY=50KSI) with 2" (51 mm) legs shall be mounted just below the countertop to bridge between the cabinet back and wall, and:
4	5	3	1 1 Shall be fastened to the wall with a uniformly spaced, continuous horizontal row of fasteners at a maximum of 11" (279 mm) on center with the end fasteners within 2" (51 mm) of each end of the channel.
4	5	3	1 2 Cabinet backs shall be fastened to the continuous metal channel, including the two fasteners in each corner of the top row of fasteners, the total number of fasteners shall be:
4	5	3	1 2 1 2 for cabinets 12" (305 mm) or less in width
4	5	3	1 2 2 3 for cabinets 24" (610 mm) or less in width
4	5	3	1 2 3 4 for cabinets 36" (914 mm) or less in width
4	5	3	1 2 4 5 for cabinets 48" (1220 mm) or less in width
Continues next column ▼			

10.6.4.E		Additional General Rules for Seismic Casework Installation Applicable for all Grades	
▲ From previous column			
4	INSTALLATION FASTENER PLACEMENT (continued)		
4	6	For <b>PENINSULA CABINETS</b> of single row double faced casework not to exceed 36" (914 mm) in height (including countertop), a minimum of 24" (610 mm) or a maximum of 36" (914 mm) in depth (excluding doors and drawer fronts) and 48" (1220 mm) in width requires:	
4	6	1	Integral toe base construction.
4	6	2	Anchorage of the toe base to the floor at front with:
4	6	2	1 A continuous, for each cabinet unit, bent 16 gauge sheet metal 2.5" x 2.5" (64 mm x 64 mm) angle (FY+50KSI) shall be:
4	6	2	1 1 Mounted to the floor with 3/8" diameter Simpson Strong Bolt 2 (or equal) with minimum 2" (51 mm) embedment within 2" (51 mm) of each end and a maximum of 11" (279 mm) on center, with a minimum of:
4	6	2	1 1 1 13.5" (343 mm) on center between front and back anchors at cabinets 24" (610 mm) in depth.
4	6	2	1 1 2 25.5" (648 mm) on center between front and back anchors at cabinets 36" (914 mm) in depth.
4	6	2	1 2 Fastened to the left/right toe base member with # 12 sheet metal screws, driven through the front of the toe base member into the metal angle within 4" (102 mm) of each end and a maximum of 12" (305 mm) on center.
Continues next column ▼			

# SECTION 10 - ANNEX 10E

## Seismic Casework Installation

GENERAL/PRODUCT/INSTALLATION/TEST


Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



**compliance requirements**

# Additional Requirements for Seismic Casework Installation

**Requires explicit specification requirement for such within contract documents.**

<b>10.6.4.E</b>	<b>Additional General Rules for Seismic Casework Installation</b> Applicable for all Grades	
▲ From previous column		
4	<b>INSTALLATION FASTENER PLACEMENT</b> (continued)	
4	7	<p>For <b>PENINSULA CABINETS</b> of double row casework with utility chase, each row of casework shall not exceed 36" (914 mm) in height (including countertop), 36" (914 mm) in depth (excluding doors and drawer fronts) and 48" (1220 mm) in width requires:</p>  <p>The diagram shows two cabinet units side-by-side. A horizontal dimension line above the units indicates a maximum width of 36" (914 mm). A vertical dimension line to the right of the units indicates a maximum height of 36" (914 mm). Small symbols at the base of the units represent fasteners.</p>
4	7	1 Same at <b>PENINSULA CABINETS</b> of single row double faced casework



# SECTION 10

## Casework

### GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally




## compliance requirements

### 10.7 BASIC CONSIDERATIONS

- 1 **TOLERANCES** typically found within NAAWS:
- 1.1 Fall into two **CATEGORIES**:
- 1.1.1 Factory fabricated joinery, assembly and construction - found in the **PRODUCT** portion.
- 1.2.1 Field installation joinery and assembly - found in the **INSTALLATION** portion.
- 1.2 **INCLUDE:**
- 1.2.1 Flatness of wood based panel products.
- 1.2.2 Solid wood to solid wood joints and assemblies.
- 1.2.3 Solid wood to wood veneer joints and assemblies.
- 1.2.4 Wood veneer to wood veneer joints and assemblies.
- 1.2.5 Solid wood to wood based product joints and assemblies (decorative laminate Solid Phenolic and panel products).
- 1.2.6 Solid surface to solid surface joints and assemblies.
- 1.3 **EXCLUDE:**
- 1.3.1 **BECAUSE of EXPANSION and CONTRACTION DIFFERENCES of non-wood products compared to solid wood and wood based products, these Standards do not apply tolerances regarding flatness or joinery to:**
- 1.3.1.1 Solid wood to non-wood based products (which can be drywall, glass, metal, stone, acrylics, and other surfaces).
- 1.3.1.1 Non-wood to non-wood joints.



### 10.7 BASIC CONSIDERATIONS (continued)

- 2 **FABRICATED and INSTALLED** woodwork shall be tested for compliance to these standards as follows.
- 2.1 **SMOOTHNESS** of exposed surfaces:
- 2.1.1 **KCPI** (Knife Cuts Per Inch) is determined by holding the surfaced board at an angle to a strong light source and counting the visible ridges per inch, usually perpendicular to the profile.
- 
- Figure: 10-060
- 2.1.2 **SANDING** is checked for compliance by sanding a sample piece of the same species with the required grit of abrasive, and:
- 2.1.2.1 Observation with a hand lens of the prepared sample and the material in question will offer a comparison of the scratch marks of the abrasive grit.
- 2.1.2.2 Reasonable assessment of the performance of the finished product will be weighed against absolute compliance with the standard.
- 2.1.2.3 A product is sanded sufficiently smooth when knife cuts are removed and remaining sanding marks are or will be concealed by applied finishing coats.
- 2.1.2.4 Grain raise at unfinished wood, due to moisture or humidity in excess of the ranges set forth in this standard, shall not be considered a defect and must be sanded prior to finishing.
- 2.2 **GAPS, FLUSHNESS, FLATNESS and ALIGNMENT:**
- 2.2.1 Maximum gaps between exposed components shall be tested with a feeler gauge at points designed to join, where members contact or touch.
- 2.2.2 Joint length shall be measured with a ruler with minimum 1/16" (1 mm) divisions and calculations made accordingly.
- 2.2.3 Reasonable assessment of the performance of the finished product will be weighed against absolute compliance with the standards.

# SECTION 10

## Casework

### GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally





## compliance requirements




### 10.7 BASIC CONSIDERATIONS (continued)

#### 2.2 GAPS, FLUSHNESS, FLATNESS and (continued)

2.2.4 The following is intended to provide examples of how and where testing is measured:



Measured on the concave face



- A - Gaps when surfaces are mitered or butted
- B - Gaps when parallel pieces are joined
- C - Gaps when edges are mitered or butted
- D - Flushness between two surfaces
- E - Flatness of panel product
- F - Overlap (flushness of laminate)

- G - Chip Out
- H - Over Machining
- I - Installation Gaps
- J - Installation Flushness
- N - Alignment of doors and drawer fronts

Figure: 10-061

# North American Architectural Woodwork Standards - 3.1

## **S E C T I O N - 1 1**

# COUNTERTOPS

<b>Resources . . . . .</b>	<b><a href="#">379</a></b>
<b>Introduction . . . . .</b>	<b><a href="#">381</a></b>
<b>Recommendations . . . . .</b>	<b><a href="#">381</a></b>
<b>Specification Considerations . . . . .</b>	<b><a href="#">381</a></b>
<b>Design Resources . . . . .</b>	<b><a href="#">390</a></b>
<b>Compliance Requirements . . . . .</b>	<b><a href="#">391</a></b>
<b>Scope &amp; Default Stipulation . . . . .</b>	<b><a href="#">393</a></b>
<b>Basic Rules . . . . .</b>	<b><a href="#">394</a></b>
<b>Annexes 11A - 11F (Material Specific) . . . . .</b>	<b><a href="#">400</a></b>
<b>Installation . . . . .</b>	<b><a href="#">412</a></b>
<b>Tests . . . . .</b>	<b><a href="#">420</a></b>

### Within CANADA

#### SUPPORT

- **GUIDE SPECIFICATIONS** – Available for download in interactive digital format, including specification wording for Quality Assurance Program (GIS) at: <http://awmac.com/guide-specifications>
- **CONSULTATION** – Contact any of the local chapters for more information on the NAAWS or any other Architectural Woodwork Questions you may have. See below for contact information.
- **SPECIFICATION REVIEW** – Contact any of the local chapters if you would like your specifications reviewed for compliance to the NAAWS.
- **MANUFACTURER STANDARDS QUESTIONNAIRE (MSQ)** – AWMAC Manufacturer members have the opportunity to have at least one member of their staff study and write the MSQ. The MSQ is a questionnaire on the NAAWS and policy and procedures of the GIS program. A list of Manufacturer members that have passed the MSQ is available at: <http://awmac.com/members>
- **SEMINARS AND PRESENTATIONS** – Contact your local chapter to arrange an informative presentation on any Architectural Woodwork topic. Some topic options – GIS, NAAWS, How to Specify Quality Architectural Woodwork...
- **TRADE SHOWS** – Contact your local chapter to arrange for AWMAC to have a booth or do a presentation on Architectural Woodwork.
- **CONFERENCE** – AWMAC has an annual conference held at unique venues across Canada. The conferences provide an opportunity to learn more about Architectural Woodwork and network with Suppliers and Manufacturers from across Canada. More information is available at: <http://awmac.com/>
- **EDUCATION PARTNERS** – Contact the local chapters to find out more information about support for local Colleges and Universities offering woodworking related courses and programs.

#### QUALITY ASSURANCE

- **GUARANTEE AND INSPECTION SERVICE (GIS)** – The GIS is a national program designed to ensure that project owners get value and quality for their investment by:
  - Supporting architects and design professionals to achieve project plans and specifications; and
  - Helping contractors avoid problems such as cost overruns, delays and loss of reputation.

More information is available at: <http://awmac.com/gis>

- **INSPECTION SERVICE** – A GIS Certified Inspector will inspect specific areas of concern on a project for compliance to the NAAWS and provide a written report. Contact your local chapter for more information.
- **EXPERT OPINION** – An expert will be appointed to inspect specific areas of concern on a project and provide a written report. Contact your local chapter for more information.

#### AWMAC CHAPTERS

- AWMAC British Columbia Chapter, Vancouver BC  
<http://bc.awmac.com>
- AWMAC Northern Alberta Chapter, Edmonton Alberta  
<http://nab.awmac.com>
- AWMAC Southern Alberta Chapter, Calgary Alberta  
<http://sab.awmac.com>
- AWMAC Saskatchewan Chapter, Saskatoon Saskatchewan  
<http://sk.awmac.com>
- AWMAC Manitoba Chapter, Winnipeg Manitoba  
<http://mb.awmac.com>
- AWMAC Ontario Chapter, Toronto Ontario  
<http://on.awmac.com>
- AWMAC Quebec Chapter, Montreal Quebec  
<http://qc.awmac.com>
- AWMAC Atlantic Chapter, Halifax Nova Scotia  
<http://atl.awmac.com>

### Within UNITED STATES

#### SUPPORT

- **GUIDE SPECIFICATIONS** - Available in interactive digital format including quality control options at: <http://woodworkinstitute.com/publications/architectural-woodwork-standards/>
- **AIA SEMINARS** - The Woodwork Institute is a Registered Provider of the American Institute of Architects (AIA), and its Continuing Education System (CES) program, check out our offerings at: <http://woodworkinstitute.com/architectural-resources/aia-seminars/> 
- **CONSULTATION** - Contact one of our Directors of Architectural Services (DAS) at: <http://woodworkinstitute.com/about-us-2/about-us/>
- **ACCREDITED FABRICATORS AND INSTALLERS** - Our AMC's (Accredited Millwork Company) represents the best fabricators and installers in our industry, check them out at: <http://woodworkinstitute.com/membership-listing-2/> 
- **CERTIFIED INDUSTRY PROFESSIONALS** - Our CMP's (Certified Millwork Professionals) represent the knowledge base of our industry, check them out at: <http://woodworkinstitute.com/membership-listing-2/> 
- **MILLWORK INDUSTRY PARTNERS** - Our MIP's (Millwork Industry Partners) represent the best of our industries material suppliers, check them out at: <http://woodworkinstitute.com/membership-listing-2/> 
- **ACKNOWLEDGED PRODUCTS LISTING** - If it's listed here, you are assured it meets NAAWS minimum requirements, find the listing at: <http://woodworkinstitute.com/acknowledged-product-listing/> 
- **CABINET DESIGN SERIES (CDS)** - Eliminate the need to include casework elevations in your architectural drawings, check out the CDS system in NAAWS "Design Resources" and access the cad files at: <http://woodworkinstitute.com/architectural-resources/cabinet-design-series/>

#### QUALITY ASSURANCE

- **BIDDER QUALIFICATION** - A discipline of bidder pre-qualification wherein your specifications protect you and your customer from the unknown: To be eligible to bid or negotiate this job, the subcontractor must be a Woodwork Institute Accredited Millwork Company (AMC) in good standing.   
<http://woodworkinstitute.com/architectural-resources/quality-assurance>
- **CERTIFIED COMPLIANCE PROGRAM (CCP)** - A discipline of quality control used in conjunction with NAAWS providing an unbiased means of ensuring conformance to a project's plans and specifications. CCP, together with the use of the desired Grade(s) in the specifications, informs all parties of the design professional's expectations, without bidder discrimination.   
<http://woodworkinstitute.com/services/certified-compliance-program>
- **MONITORED COMPLIANCE PROGRAM (MCP)** - A discipline of quality affirmation used in conjunction with the NAAWS which provides ongoing reviews/inspections of a project from its beginning through completion, ensuring strict conformance to the design intent throughout the millwork fabrication and installation process.   
<http://woodworkinstitute.com/services/monitored-compliance-program/>
- **CERTIFIED SEISMIC INSTALLATION PROGRAM (CSIP)** - A standalone seismic assurance option which can be specified in conjunction with or without CCP or MCP, offering design professionals and project owners specific use of WI's seismic casework pre-approvals from California's Office of Statewide Health Planning and Development (OSHPD) without additional engineering costs and/or requirements, assuring proper backing has been installed in the walls when and where required.   
<http://woodworkinstitute.com/services/certified-seismic-installation-program/>

# SECTION 11

## Countertops

## introductory information

### INTRODUCTION

Section 11 includes information on Countertops and Window Sills manufactured of Wood, High Pressure Decorative Laminate (HPDL), Solid Surface, Engineered Stone, Epoxy Resin, Solid Phenolic and Natural Stone Products and their related parts.

Quality assurance can be achieved by adherence to these standards and will provide the owner a quality product at competitive pricing. Working with a WI Certified Millwork Professional (CMP) and the WI Accredited Millwork Company (AMC) they represent to provide your woodwork will help ensure the understanding and performance of the quality level required. Illustrations in this Section are not intended to be all inclusive, other engineered solutions may be acceptable. In the absence of specifications; methods of fabrication are the manufacturer's choice. The design professional, by specifying compliance to these standards increases the probability of receiving the product quality expected.

### RECOMMENDATIONS

- If **FIELD FINISHED, INCLUDE IN THE DIVISION 09 OF THE SPECIFICATIONS:**



- **BEFORE FINISHING**, exposed portions of woodwork shall have handling marks or effects of exposure to moisture removed with a thorough, final sanding over surfaces of the exposed portions and shall be cleaned before applying sealer or finish.
- **CONCEALED SURFACES** - Architectural woodwork that may be exposed to moisture, such as those adjacent to exterior concrete walls, etc., shall be primed.
- The underside of wood countertops shall be sealed with at least one coat of primer or sealer.

- **REVIEW** the GENERAL portion of Sections 3 and 4 for an overview of the characteristics and the minimum acceptable requirements of lumber and/or sheet products that might be used herein.
- **STRUCTURAL MEMBERS**, grounds, in wall blocking, backing, furring, brackets, or other anchorage which becomes an integral part of the building's walls, floors, or ceilings, required for the installation of architectural woodwork are not to be furnished or installed by the architectural woodwork manufacturer or installer.
- At **HPDL SINK TOPS**, use of under-mount sinks is not recommended because of the potential for moisture problems, even with proper preparation and installation, and:
  - Use of veneer core plywood with Type II adhesive, or moisture resistant MDF with a 24 hour thickness swell factor of 4.5% or less.
  - Either self-rimming sinks or sinks with surface-mounted metal retention rings are recommended.

### SPECIFICATION CONSIDERATIONS



- **FLAME SPREAD REQUIREMENTS.**
- **ANTIMICROBIAL SURFACES.**
- **LABORATORY USE**, such as:
  - Chemical-resistant work-surface material requirements or finish.
  - Abrasion-resistant work-surface material requirement.
  - Removable splash ledger.
- **SPECIAL SPLASH/DECK OR TOP OR EDGE PROFILES.**

- **QUALITY ASSURANCE OPTIONS:**

#### Within CANADA

- **AWMAC's GUARANTEE AND INSPECTION SERVICE (GIS)** - See NAAWS's Resources page and/or <http://awmac.com/gis>
- **AWMAC's INSPECTION SERVICE** - See NAAWS's Resources page and/or <http://awmac.com/gis>
- **AWMAC's EXPERT OPINION SERVICE** - See NAAWS's Resources page and/or <http://awmac.com/gis>

#### Within UNITED STATES

- **WI'S AMC BIDDER PRE-QUALIFICATION** - See NAAWS's Resources page and/or <http://woodworkinstitute.com/architectural-resources/quality-assurance>
- **WI'S CERTIFIED COMPLIANCE PROGRAM (CCP)** - See NAAWS's Resources page and/or <http://woodworkinstitute.com/services/certified-compliance-program>
- **WI'S MONITORED COMPLIANCE PROGRAM (MCP)** - See NAAWS's Resources page and/or <http://woodworkinstitute.com/services/monitored-compliance-program/>
- **WI'S CERTIFIED SEISMIC INSTALLATION PROGRAM (CSIP)** - See NAAWS's Resources page and/or <http://woodworkinstitute.com/services/certified-seismic-installation-program/>

# SECTION 11

## Countertops

### introductory information

#### TYPICAL COUNTERTOP CONFIGURATIONS

- **Self-edged high pressure decorative laminated** - This type of top consists of plastic laminate over a stable core, self edged or with an applied decorative edge of another material as specified.




Figure: 11-001




Figure: 11-002

- **Post formed high pressure decorative laminated** - This type of top consists of plastic laminate formed with heat and pressure over a stable core typically with a coved integral backsplash and must be specified.




Figure: 11-003

- **Mixed Material** - This type of top may consist of a mixture of materials, such as wood, high pressure decorative laminate, inlays, etc.




Figure: 11-004

- **Solid Surface** - This type of top requires special fabrication techniques, depending upon the composition of the product. Many manufacturers fabricate and install the products. Must be specified by brand name and manufacturer. Typically only available in 1/2" nominal (11-13 mm) thickness.




Figure: 11-005

- **Solid Laminated Wood** - This type of top consists of narrow strips of wood, face glued together, similar to "butcher block," but custom manufactured to contract documents.




Figure: 11-006

# SECTION 11

## Countertops

### introductory information

#### TYPICAL COUNTERTOP CONFIGURATIONS (continued)

- **Solid Wood** - This type of top consists of boards edge glued to a desired width. In this kind of top there is no assurance of matching grain or color at the edges or individual ends of the boards.




Figure: 11-007


- **Wood Veneer** - This type of top consists of wood veneer laid up over a stable core, veneer edged, solid wood edged or with an applied decorative edge of another material as specified.
- **Epoxy Resin** - Specially formulated resin tops designed to resist harsh chemicals. Must be specified by brand name and manufacturer.

#### GUIDELINES FOR FABRICATION / INSTALLATION OF HPDL COUNTERTOPS

The following was taken in part from the National Electrical Manufacturers Association (NEMA), <http://nema.org>.

- When making a cutout (as for electrical receptacles, ranges, sinks, grills, windows, chopping blocks, L shaped counter tops, and so forth), inside corners should be smoothly rounded using a minimum corner radius of 1/8" (3 mm). A router is an ideal tool for making cutouts.
- When removing large areas from a sheet of laminate (e.g., a sink cutout), the connecting strips between the remaining areas should be left as wide as possible.
- Factory-trimmed sheet edges and saw-cut edges should be routed and filed. Original edges on factory cut laminates are not finished edges since oversized laminates are supplied to allow for proper fabrication.

- All chips, saw marks, and hairline cracks should be removed from cuts by filing, sanding, or routing.
- Backsplash seam areas on countertops which are exposed to spilled water or other fluids should be sealed with caulking to ensure a tight seal.
- When laminate is bonded to a core, precaution should be taken to prevent warping of the assembly. Laminates used on shelves or in long unsupported spans should make use of a backer. A thick backer (approximately the same thickness as the face sheet), can provide more stability than a thin backer. Thicker laminates can offer better dimensional stability and resistance to stress (corner) cracking. Paint, varnish, vinyl film, and fiber backers will not balance HPDL.
- Before using nails or screws, oversized holes should be drilled through the laminate with a sharp drill bit.



- 1 Radius these corners
- 2 Make this area as wide as possible and avoid seams
- 3 Seam this area as broken line indicates or radius if one-piece laminate top. Avoid edgeband across countertop joints.
- 4 Support long spans well
- 5 At L-shaped non-wood grain or non-directional pattern countertops, butt joints are permitted.

Figure: 11-008

# SECTION 11

## Countertops

## introductory information

### TYPICAL PROBLEMS AT HPDL COUNTERTOPS - CAUSES AND PREVENTION

Some of the problems that may arise after laminates have been fabricated and installed are the following:

- **Cracking of the laminate at corners and around cutouts** may be caused by improper climate control, improper bonding and, sometimes, poor planning, or combination of these reasons. Cracking may be caused by shrinkage; proper climate control helps to prevent it. Rough edges, inside corners that have not been rounded, binding and/or forced fits can contribute to cracking. If the seams are properly placed in the layout of the laminate, stresses can be minimized.




Figure: 11-009

- **Separation of the laminate** from the core may generally be caused by a poor adhesive bond. The bonding procedure should be reviewed with close attention to uniform glue line, uniform pressure and cleanliness of mating surfaces. If the edges fail to bond, extra adhesive may be applied and the product re-clamped.

Some cleaning agents, excess heat, and moisture can contribute to bond failure at joints and edges.



Figure: 11-010

- **Blistering or Bubbling** of the laminate surface away from the core can be caused by excessive heat, starved glue line, improper conditioning, and inadequate pressure or drying. Use of a PVA glue line and pressure over clean, conditioned laminates and core might have prevented the problem.




Figure: 11-011

The forming of a blister or bubble over a small area, often accompanied by a darkening of the laminate can be caused by continual exposure to a source of heat. Electrical appliances which produce heat and light bulbs should not be placed in contact with or close proximity to laminate surfaces.

- **Repeated Heating** may cause the laminate and adhesive to react and finally deteriorate after continual exposure to temperatures above 150° F (66° C).




Figure: 11-012

- **Cracking of the laminate in the center of the sheet** may be caused by flexing of the core when it covers a wide span or by spot gluing. Wide spans call for sturdy framework, and special attention should be given to the uniformity of glue lines and gluing pressures. Also, care should be taken to avoid trapping foreign objects between the laminate and the core.

Cantilevered overhangs should be designed with appropriate supports.




Figure: 11-013

Long, unsupported spans should be avoided. A wide variety of engineering solutions are available.

- **Warping of the assembly** may be generally caused by unbalanced construction or unbalanced glue lines. Proper HPDL backer sheets should be chosen and aligned so that their grain direction is parallel to that of the face laminate. Proper gluing is also important. If the core is secured to a framework, the framework should be designed to hold the assembly to a flat plane. Conditioning is also helpful.




Figure: 11-014

# SECTION 11

## Countertops

## introductory information

### HIGH PRESSURE DECORATIVE LAMINATE (HPDL) COUNTERTOPS

- **HPDL BACK AND END SPLASH ASSEMBLY TYPES** - if not otherwise specified, shall be manufacturer's choice: **OPTIONAL** within **CANADA**; however, **NOT ALLOWED** within the **UNITED STATES**.

- **ASSEMBLY - 1**, Wall mount, Jobsite Assembled




Figure: 11-015

- **ASSEMBLY - 2**, Deck Mount, Manufacturer Assembled. - **OPTIONAL** within **CANADA**; however, **REQUIRED** within the **UNITED STATES**.




Figure: 11-016

- **WHITE BACKGROUND PAPER** is utilized in some HPDLs to achieve the high fidelity, contrast, and depth of color of their printed pattern, leaving a white line at exposed edges that is extremely noticeable with darker colors.

- **FLAME SPREAD RATED** - Class A Flame Spread Architectural HPDL countertops are available. Countertops desired to be certified as a flame spread rated assembly (versus simply having been built with a flame spread rated laminate surface) shall be specified as a "Class A Flame spread Rated HPDL Countertop."

The term "Class A Flame spread Rated HPDL Countertop" shall mean that the entire countertop assembly, including surface HPDL, backer, core, and adhesive, has been tested and certified as to its Class A Flame spread Rating by an authorized organization, such as Underwriters Laboratories, and must be manufactured by an approved company of the certifying agency.

Manufacturers of "Class A Flame Spread Rated Countertop Assemblies" require specific methods of installation and trimming in order to label and certify their product. Design professionals desiring to use a "Class A Flame Spread Countertop Assembly" should coordinate with an approved manufacturer during the design stage.

- **COUNTERTOP CONFIGURATION OPTIONS**

- **Self Edged w/ No Splash**



Figure: 11-017

- **Self Edged w/ Butt Splash**




Figure: 11-018

- **Self Edged w/ Covered Splash**




Figure: 11-019

- **Post Formed Edge w/ No Splash**



Figure: 11-020

- **Post Formed Edge w/ Butt Splash**




Figure: 11-021

- **Post Formed Edge w/ Covered Splash**




Figure: 11-022

- **Fully Formed w/ Covered Splash**




Figure: 11-023

- **No Drip Edge w/ Covered Splash**




Figure: 11-024

- **Wood Edge w/ No Splash**



Figure: 11-025

# SECTION 11

## Countertops

## introductory information

### HIGH PRESSURE DECORATIVE LAMINATE (HPDL) COUNTERTOPS (continued)

#### • OPTIONS AT TOP OF SPLASH:

- Waterfall w/ Scribe




Figure: 11-026

- Square w/ Scribe




Figure: 11-027

- Square




Figure: 11-028

#### • DECK OPTIONS AT SPLASH:

- Horizontal Butt




Figure: 11-029

- Vertical Butt




Figure: 11-030

- Coved




Figure: 11-031

#### • FRONT EDGE OPTIONS:

- Self Edgeband w/ Wide Build Up



Figure: 11-032

- Self Edgeband Narrow Build Up




Figure: 11-033

- Self Edgeband w/ Drip Groove



Figure: 11-034

- Waterfall




Figure: 11-035

- No Drip




Figure: 11-036

- Full Round




Figure: 11-037

- Solid Wood Edgeband w/ V Groove




Figure: 11-038

- Solid Wood Edgeband w/o V Groove




Figure: 11-039

- Solid Wood Edgeband w/ Overlaid Laminate




Figure: 11-040

- Miter Fold




Figure: 11-041

- Thick PVC Edgeband




Figure: 11-042

- T Mold Edgeband




Figure: 11-043

#### HIGH PRESSURE DECORATIVE LAMINATE (HPDL) COUNTERTOPS (continued)

- **TYPICAL MECHANICAL TIGHT JOINT FASTENER**




Figure: 11-044

#### SOLID SURFACE COUNTERTOPS

- **COLOR and PATTERN MATCH:** Some slight color variation may exist from sheet to sheet, sheet to bowl, or sink products. In sheet stock, use of the same batch material will reduce these variations.
- **REPAIRS:** When allowed, reparability varies from material to material and may be visible.
- **PRECAUTIONS:** Product dimensions are nominal. If tolerances are critical, review them with your manufacturer and/or installer.
- **MACHINABILITY** is an issue with some materials and shall be taken into consideration on selection.

- **CONFIGURATION OPTIONS:**

- **Built Up Edge**



Figure: 11-045

- **Built Up Edge w/ Butt Splash**




Figure: 11-046

- **Built Up Edge w/ Coved Splash**




Figure: 11-047

- **TOP OPTIONS AT SPLASH:**

- **Waterfall**




Figure: 11-048

- **Square**




Figure: 11-049

- **DECK OPTIONS AT SPLASH:**

- **Butt**




Figure: 11-050

- **Coved**




Figure: 11-051

- **EDGE OPTIONS:**

- **Waterfall**



Figure: 11-052

- **No Drip**




Figure: 11-053

- **Build Up w/ Drip Groove**




Figure: 11-054

# SECTION 11


## Countertops

## introductory information

### SOLID PHENOLIC, EPOXY RESIN, AND NATURAL/ENGINEERED STONE COUNTERTOPS

- CONFIGURATION OPTIONS:


- Butt Splash



- Build Up




- Build Up w/ Butt Splash




- TOP AND DECK OPTIONS AT SPLASH:


- Waterfall




- Square



- Butt




- Removable Ledge




- EDGE OPTIONS:


- Drip Groove




- Marine Edge




- Waterfall




- Chamfer Edge



- Bull Nose Edge




- Build Up w/ Drip Groove




### WOOD COUNTERTOPS

- CONFIGURATION OPTIONS:


- Solid Butcher Block




- Solid Wide Width




- Solid, Splined Wide Width



- Veneer Edgebanded



- Solid Edgebanded



### WOOD COUNTERTOPS (continued)

- **Solid Edgebanded w/ Overlaid Veneer**




Figure: 11-071

To **PREVENT TELEGRAPHING**, inset solid wood edging when used must have similar moisture content as panel core, be glued securely and calibrated with panel core thickness prior to being laminated with a wood veneer on both faces.



### CHEMICAL or STAIN RESISTANCE

Requirements must be specified. Consider the chemical and staining agents that might be used on or near the surfaces. Chemical and stain resistance is affected by concentration, time, temperature, humidity, housekeeping, and other factors; it is recommended that actual samples are tested in a similar environment with those agents. Common guidelines can be found by referring to:

- NEMA LD3 (latest edition) for chemical resistance.
- ASTM D3023 and C1378 (latest editions) for stain resistance.
- SEFA #3 - Recommendations for work surfaces.
- SEFA #8 - PH, PL and W - Recommendations for phenolic, plastic laminate and wood casework.

### ABRASION RESISTANCE

Requirements must be specified. When abrasion resistance requirements are a concern, users should consider the abrasive elements that might be used on or near the countertop surfaces. Common guidelines can be found in:

- ASTM C501 (latest edition)
- NEMA LD3-3.13 (latest edition)
- NEMA LD3.7 (latest edition)

### ANTIMICROBIAL SURFACES

There is increasing availability of antimicrobial products, including solid surface and HPDL. It is important to understand that regardless of the methodology used to create the antimicrobial surface there are two significantly different types of claims regarding such antimicrobial products. Common terminology refers to these:

- **Within the United States as:**
  - **Treated Article Claim** - Which the US Environmental Protection Agency (EPA), <http://epa.gov>, classifies as a “treated article exemption”, typically referring to items that are treated with antimicrobial pesticide to protect the item itself, not the public. Such exemption will be absent any EPA registration number and is granted for non-public health use.
  - **Public Health Claim** - Which the EPA classifies as “EPA registered products which have been shown, using EPA testing protocols, to demonstrate efficacy in the installed format. Such test protocol requires an efficacy of killing 99.9% of all bacteria, fungi and viruses within two hours.
- **Within Canada as:**
  - **Disinfectant Drugs** - Which Health Canada, <http://hc-sc.gc.ca>, classifies as a non market authorized claim, lacking a Drug Identification Number (DIN).
  - **Hard Surface Disinfectants** - Which Health Canada classifies as having received “Market Authorization” when such have been granted a Drug Identification Number (DIN).

### RECLAIMED or RECYCLED WOOD

#### DESIGN PROFESSIONAL RESPONSIBILITY

Use of unique materials like reclaimed or recycled wood requires a more active role of the design professional in sourcing and pre-approving desired material selections. There are no traditional guidelines with these types of materials to assure either the woodwork manufacturer or the design professional of achieving an intended result. There will be situations where the design professional will be required to directly participate in the individual piecemeal selection and layout process of the product.

**CONTRACT DOCUMENTS**, shall clearly indicate or delineate all material, fabrication, installation and applicable building code/regulation requirements with the clear understanding that incomplete design choices, changes in scope or material selection, lack of material selection, or design choices made after initial bid may impact the cost or not be possible.

The contract documents shall specifically list the material source and identifier, and address the allowable:

- Variation in color or tone, grain, distress, character, and patina.
- Defects, such as nail/bolt holes, checking, cracking, discoloration, milling marks, roughness in terms of quantity, locations, repetition, etc.
- Distortion in terms of straightness, cupping, flatness, etc.

See SECTION 3 for additional information.

# SECTION 11

## Countertops

## introductory information

### NONTRADITIONAL MATERIALS

Covers materials re-purposed from other industrial and manufacturing areas, but assigned to the woodwork manufacturer and treated similarly to traditional millwork items like wall paneling. From a design perspective considerations of appearance, color, finish, variation and relation are deemed important as they would be with traditional wood products.

Examples of non-traditional materials could be a fiber/cement panel designed for fire resistance, insulation re purposed as a decorative panel, metal products, cloth, acrylics, etc.

Because these materials are unique, contract documents, shall clearly indicate or delineate all of the necessary material, fabrication, installation and building code/regulation direction and requirements as may be applicable for the manufacturer/installer to reasonably accomplish the intended design concept.

### DESIGN RESOURCES



Is a perpetually expanding, web based resource of pictures, videos, illustrations, ideas and design concepts for inspiring thought and design creativity - assessable at:

<http://naaws-design-resources.com>

Relative to this Section, offerings will include:

- HPDL
  - Flat
  - Formed
- Solid Surface
- Solid Phenolic
- Epoxy Resin
- Stone
  - Natural
  - Manufactured

# SECTION 11

## Countertops

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated,  
the rule applies to all Grades equally



## compliance requirements

**INCLUDING: Tops, Wall Caps, Splashes, and Sills of High-Pressure Decorative Laminate, Wood, Solid Surface, Solid Phenolic, Epoxy Resin, and Natural/Engineered Stone**

### 11.1 BASIC CONSIDERATIONS

#### 1 GRADE

- 1.1 These standards are characterized in three Grades of quality that may be mixed within a single project. Limitless design possibilities and a wide variety of lumber and veneer species, along with overlays, high-pressure decorative laminates, factory finishes, and profiles are available in all three Grades.
- 1.2 **ECONOMY GRADE** defines the minimum quality requirements for a project's workmanship, materials, or installation and is typically reserved for woodwork that is not in public view, such as in mechanical rooms and utility areas.
- 1.3 **CUSTOM GRADE** is typically specified for and adequately covers most high-quality architectural woodwork, providing a well-defined degree of control over a project's quality of materials, workmanship, or installation.
- 1.4 **PREMIUM GRADE** is typically specified for use in those areas of a project where the highest level of quality, materials, workmanship, and installation is required.
- 1.5 **GRADE LIMITATIONS**
- 1.5.1 **SOLID SURFACE** countertops are offered only in custom grade and premium grade.
- 1.5.2 **SOLID PHENOLIC, EPOXY RESIN, and NATURAL/ENGINEERED STONE** countertops are offered only in premium grade.
- 2 **CONTRACT DOCUMENTS** shall govern if in conflict with these standards.
- 3 **ACCEPTABLE REQUIREMENTS** of lumber and/or sheet products used within this woodwork product section are established by Sections 3 and 4, unless otherwise modified herein.

### 11.1 BASIC CONSIDERATIONS (continued)

- 4 **AESTHETIC COMPLIANCE REQUIREMENTS** apply only to surfaces visible after manufacturer and installation.
- 4.1 Shall be judged from a normal viewing stance and considered compliant if inconspicuous when viewed from:
- 4.1.1 72" (1830 mm) for Economy Grade
- 4.1.2 48" (1219 mm) for Custom Grade
- 4.1.3 24" (610 mm) for Premium Grade
- 4.2 For **RECLAIMED** or **RECYCLED WOOD**, the aesthetic compliance requirements of NAAWS does not apply, such shall be as agreed between owner/design professional and the woodwork manufacturer/installer.
- 4.3 For **NON-TRADITIONAL MATERIALS**, the aesthetic compliance requirements of NAAWS does not apply, such shall be as agreed between owner/design professional and the woodwork manufacturer/installer.
- 5 **EXPOSED SURFACES**
- 5.1 All visible surfaces of an installed countertop.
- 5.2 The exposed underside surface over 42" (1067 mm) off the finish floor.
- 6 **CONCEALED SURFACES**
- 6.1 The underside surface 42" (1067 mm) or less off the finished floor.
- 6.2 All non-visible surfaces attached to and/or covered by another.
- 6.3 All non-visible blocking, spacers, etc., used for attachment.
- 7 **SOLID SURFACE** is referenced in these standards, it refers to filled cast polymeric resin panels per Section 4.
- 8 **SOLID PHENOLIC** (compact laminate) is referenced in these standards, it refers to panels of melamine impregnated decorative overlay sheets over kraft phenolic core sheets per Section 4.
- 9 **EPOXY RESIN** is referenced in these standards, it refers to homogenous, nonabsorbent, heat cured composite of panels per Section 4.

# SECTION 11

## Countertops

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated,  
the rule applies to all Grades equally



## compliance requirements

### 11.1 BASIC CONSIDERATIONS (continued)

- 10 **NATURAL STONE** is referenced in these standards, it typically refers to granite, marble, slate, soapstone, and limestone. Natural stone countertops are cut directly from the earth and have little processing besides smoothing and shape formation, and will often need to be sealed because natural materials are porous (soapstone is a notable exception to this generalization).
- 11 **ENGINEERED STONE** is referenced in these standards, it typically refers to quartz (a man made substance derived from mineral dust) or quartz based and is entirely a man-made surface designed to mimic the beautiful appearance of natural stone. Engineered stone does not have natural defects and is a more uniform design.
- 12 To **PREVENT TELEGRAPHING**, inset solid wood edging when used must have similar moisture content as panel core, be glued securely and calibrated with panel core thickness prior to being laminated with a wood veneer on both faces.
- 13 **INDUSTRY PRACTICES**
- 13.1 **STRUCTURAL MEMBERS**, grounds, in wall blocking, backing, furring, brackets, or other anchorage that becomes an integral part of the building's walls, floors, or ceilings, required for the installation of architectural woodwork is not furnished or installed by the architectural woodwork manufacturer or installer.
- 13.2 **WALL, CEILING**, and/or opening variations in excess of 1/4" (6.4 mm) or **FLOORS** in excess of 1/2" (12.7 mm) in 144" (3658 mm) of being plumb, level, flat, straight, square, or of the correct size are not acceptable for the installation of architectural woodwork, nor is it the responsibility of the installer to scribe or fit to tolerances in excess of such.
- 13.3 **PRIMING** of architectural woodwork is not the responsibility of the manufacturer and/or installer, unless the material is being furnished pre-finished.
- 13.4 **BUILD-UP** or spacing materials required for installation of a countertop are the responsibility of the countertop manufacturer.

### 11.1 BASIC CONSIDERATIONS (continued)

- 13.5 Defined **GRAIN** and/or **PATTERN** are installed running with the length of the countertop.
- 13.6 **HORIZONTAL REVEAL** between the lower edge of the countertop and the upper edge of the adjacent door or drawer front shall be consistent. Coordination of such is the responsibility of the cabinet manufacturer.

# SECTION 11

## Countertops

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



## compliance requirements

### 11.2 SCOPE

1 All decorative laminate, including Class A Flame Spread-Rated and Chemical-Resistant, Solid Surface, Natural/Engineered Stone, Epoxy Resin, Solid Phenolic, and wood facings, tops, splashes, sills, and ledges.

#### 2 TYPICAL INCLUSIONS

- 2.1 HPDL, Class A Flame Spread-Rated HPDL, Chemical-Resistant HPDL, Solid Surface, Natural/Engineered Stone, Epoxy Resin, Solid Phenolic, and Wood Countertops with approved backing sheet, as applicable.
- 2.2 Splashes, sills, and ledges.
- 2.3 Solid lumber, metal, or self-edge trim; cutouts for sinks; electrical boxes; and fixtures indicated on drawings.
- 2.4 Installation, if specified.
- 2.5 Solid surface and/or epoxy sinks.
- 2.6 Window sills.
- 2.7 Support members that are surface-mounted.

#### 3 TYPICAL EXCLUSIONS

- 3.1 Stripping, furring, in wall blocking, or grounds.
- 3.2 Furnishing or installation of sink rims or sinks not listed above.
- 3.3 In-wall support members.
- 3.4 All grounds, backing members, or other items unrelated to the furnishing and installation of countertops and sinks.
- 3.5 Fixtures, plumbing, and data equipment.
- 3.6 Sink outlets and fittings, except at epoxy sinks.
- 3.7 Welded metal support material or structure.

### 11.3 DEFAULT STIPULATION

1 If not otherwise specified or indicated in the contract documents:



- 1.1 **HPDL COUNTERTOPS** - shall be **CUSTOM GRADE** (unless the related casework is premium grade, then the countertops shall be **PREMIUM GRADE**); of desired HPDL colors selected from the manufacturer's non-premium-priced standard patterns and readily available sheet sizes; with standard self-edge, square butt splash a minimum of 4" (102 mm) above deck, and of **ASSEMBLY 1** or **2 construction** within **CANADA** and **ASSEMBLY 1** construction only within **UNITED STATES**, with square self-edge.
- 1.2 **WOOD COUNTERTOPS** - shall be **CUSTOM GRADE** (unless the related casework is Premium Grade, then the countertops shall be **PREMIUM GRADE**) hardwood plywood intended for an opaque finish.
- 1.3 **SOLID SURFACE COUNTERTOPS** - shall be **CUSTOM GRADE** of the manufacturer's choice of brand name and edge treatment. Desired colors to be selected from the manufacturer's standard, non-premium-priced line with standard matte finish; a minimum of 1/2" nominal (11-13 mm) thick; with a minimum of a 3" (76 mm) high splash above the deck surface.
- 1.4 **SOLID PHENOLIC, EPOXY RESIN, and NATURAL/ENGINEERED STONE COUNTERTOPS** - shall be **PREMIUM GRADE** of manufacturer's choice of brand name and edge treatment; colors to be selected from the manufacturer's standard, non-premium-priced line with standard satin finish, and with compatible sink and accessories.

# SECTION 11

## Countertops

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



## compliance requirements

### 11.4 RULES

- 1 The following rules shall govern unless a project's contract documents require otherwise.
- 2 These rules are intended to provide a well-defined degree of control over a project's quality of materials, workmanship, or installation.
- 3 **ERRATA**, published at <http://naaws-errata.com>, shall take precedence over these rules, subject to their date of posting and a project's bid date. 

11.4.4 Basic General Rules	
1	<b>AESTHETIC</b> grade rules apply only to exposed surfaces visible after installation.
2	<b>LUMBER</b> shall conform to the requirements established in Section 3.
3	<b>SHEET PRODUCTS</b> shall conform to the requirements established in Section 4.
4	<b>BACKER MATERIAL</b> shall conform to the requirements established in Section 4.
5	<b>EXPOSED SURFACES</b> include:
5 1	All visible surfaces on an exposed countertop.
5 2	The exposed underside surface over 42" (1067 mm) off the finish floor.
6	<b>CONCEALED SURFACES</b> include:
6 1	The underside surface 42" (1067 mm) or less off the finished floor.
6 2	All non-visible surfaces attached to and/or covered by another.
6 3	All non-visible blocking, spacers, etc., used for attachment.
7	A <b>BALANCED PANEL</b> , for the purpose of this standard, is one that is free from warp that affects serviceability for its intended purpose.
8	<b>GRAIN</b> and/or <b>PATTERN SURFACING</b> shall be installed with the grain or pattern direction running length-wise.
9	<b>EXPOSED FASTENING</b> is prohibited, except for access panels.
10	Where <b>FIRE-RETARDANT</b> or <b>MOISTURE-RESISTANT</b> core is required, documentation shall be furnished, if requested.
Continues next column ▼	

### 11.4.4 Basic General Rules

#### ▲ From previous column

11	<b>GLUING</b> or <b>LAMINATION</b> shall be in accordance with the <b>ADHESIVE GUIDELINES</b> within the <b>APPENDIX</b> , and: 
11 1	<b>DELAMINATION</b> or <b>SEPARATION</b> shall not occur.
11 2	<b>LUMBER</b> shall conform to the requirements established in Section 3.
11 3	<b>SHEET PRODUCTS</b> shall conform to the requirements established in Section 4.
12	If <b>ANTIMICROBIAL SURFACE</b> is required, it shall be:
12 1	Within the United States, EPA, <a href="http://epa.gov">http://epa.gov</a> , registered for public health use.
12 2	Within Canada, Health Canada, <a href="http://hc-sc.gc.ca">http://hc-sc.gc.ca</a> , recognized as having market authorization because of its granted Drug Identification Number (DIN).
13	<b>FIRST-CLASS WORKMANSHIP</b> is required in compliance with these standards. 

# SECTION 11

## Countertops

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



## compliance requirements

11.4.5		Basic Material Rules			
1	When <b>FACTORY FINISHING</b> is specified, concealed surfaces shall be factory sealed with one coat at 2 mil dry.	E	C	P	
2	For <b>OPAQUE FINISH</b> :				
2 1	Medium-density fiberboard (MDF) is permitted				
2 2	Veneer is permitted; however:				
2 2 1	<b>SPECIES</b> of manufacturer's choice, closed grain hardwood conforming to HPVA definitions and characteristics for:				
2 2 1 1	Grade <b>D</b>	E	C	P	
2 2 1 2	Grade <b>C</b>	E	C	P	
2 2 1 3	Grade <b>B</b>	E	C	P	
3	For <b>TRANSPARENT FINISH, VENEER</b> :				
3 1	<b>SPECIES</b> of manufacturer's choice, hardwood conforming to HPVA definitions and characteristics for:				
3 1 1	Grade <b>B</b>	E	C	P	
3 1 2	Grade <b>A</b>	E	C	P	
3 1 3	Grade <b>AA</b>	E	C	P	
3 2	<b>SLICING</b> of:				
3 2 1	Manufacturer's choice.	E	C	P	
3 2 2	Plain-sliced.	E	C	P	
3 3	<b>MATCHING ADJACENT LEAVES</b> be:				
3 3 1	Manufacturer's choice.	E	C	P	
3 3 2	Book matching.	E	C	P	
3 4	<b>MATCHING WITHIN PANEL FACE</b> be:				
3 4 1	Running	E	C	P	
3 4 2	Balance	E	C	P	
3 5	<b>MATCHING BETWEEN ADJACENT PANELS</b> be:				
3 5 1	Manufacturer's choice.	E	C	P	
3 5 2	Compatible for color and grain	E	C	P	
3 5 3	Well matched for color and grain	E	C	P	
3 5 4	<b>END, SEQUENCE</b> , and <b>BLUEPRINT MATCHING</b> shall be specified				
Continues next column ▼					

11.4.5		Basic Material Rules			
▲ From previous column					
4	At <b>EXPOSED SURFACES</b> :				
4 1	Shall be free of manufacturing defects.				
4 1	<b>TRANSPARENT FINISHED WOOD</b> :				
4 1 1	Permits hardwood or softwood.				
4 1 2	Permits only one species for the entire project.	E	C	P	
4 1 3	Adjacent veneer and lumber shall be:				
4 1 3 1	Manufacturers' choice of species.	E	C	P	
4 1 3 2	Compatible for color and grain.	E	C	P	
4 1 3 3	Well-matched for color and grain.	E	C	P	
4 1 4	Have visible edges, reveals, and/or splines that:				
4 1 4 1	Are full length.				
4 1 4 2	Are manufacturers' choice.	E	C	P	
4 1 4 3	Match the species of the panel face.	E	C	P	
4 1 4 4	Are <b>COMPATIBLE</b> for color and grain.	E	C	P	
4 1 4 5	Are <b>WELL-MATCHED</b> for color and grain.	E	C	P	
4 1 4 6	Are a minimum of 0.020" (0.5 mm) nominal <b>THICKNESS</b> that precludes show-through of core.	E	C	P	
5	At <b>CONCEALED SURFACES</b> shall allow defects, and:				
5 1	Blocking, fillers, and shim stock may be of any sound material.				

**Specific PRODUCT Requirements for Wood, Decorative Laminate, Solid Surface, Solid Phenolic, Epoxy Resin, and Natural/Engineered Stone are in Annex A, B, C, D, E and/or F which may be found at the end of this PRODUCT portion of Section 11.**



# SECTION 11



## Countertops


GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



## compliance requirements

11.4.6 Basic Machining Rules						
1 EXPOSED SURFACES shall comply with:						
1	1	HPDL, PVC, and PRE-FINISHED WOOD edges shall be machined flush and filed, sanded, or buffed to remove machine marks and sharp edges, and:				
1	1	1	OVERLAP (See Test F illustrations in TESTS) such as,			
						
			shall not exceed:			
1	1	1	1	0.005" (0.13 mm) for a maximum length of 2" (50.8 mm) in any 12" (305 mm) run.	E	C P
1	1	1	2	0.005" (0.13 mm) for a maximum length of 1" (25.4 mm) in any 24" (610 mm) run.	E	C P
1	1	1	3	0.003" (0.08 mm) for a maximum length of 1" (25.4 mm) in any 48" (1220 mm) run.	E	C P
1	1	2	CHIP-OUT (See Test G illustrations in TESTS) such as,			
						
			shall be inconspicuous when viewed at:			
1	1	2	1	72" (1829 mm).	E	C P
1	1	2	2	48" (1220 mm).	E	C P
1	1	2	3	24" (610 mm).	E	C P
Continues next column ▼						

11.4.6 Basic Machining Rules						
▲ From previous column						
1 EXPOSED SURFACES shall comply with (continued)						
1	1	3	OVER MACHINED (See Test H illustrations in TESTS) removal of color or pattern of face material such as,			
						
			shall be limited to:			
1	1	3	1	3/32" x 6" (2.4 mm x 152 mm) and may not occur within 48" (1220 mm) of a similar occurrence.	E	C P
1	1	3	2	1/32" x 4" (0.8 mm x 102 mm) and may not occur within 60" (1524 mm) of a similar occurrence.	E	C P
1	1	3	3	1/32" x 1-1/2" (0.8 mm x 38.1 mm) and may not occur within 72" (1829 mm) of a similar occurrence.	E	C P
2 Of CUTOUTS within a top, shall be made by either manufacturer or installer, and:						
2 1 Sink cutouts shall not fall within 18" (457 mm) of a joint.						
3 TEAR-OUTS, KNIFE NICKS, or HIT-OR-MISS machining is not permitted.						
4 KNIFE MARKS not to be permitted where sanding is required.						
5 Requires SHARP EDGES be eased.						

**Specific PRODUCT Requirements for Wood, Decorative Laminate, Solid Surface, Solid Phenolic, Epoxy Resin, and Natural/Engineered Stone are in Annex A, B, C, D, E and/or F which may be found at the end of this PRODUCT portion of Section 11.**



# SECTION 11

## Countertops


GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally

**E C P**

## compliance requirements

11.4.7 Basic Assembly Rules	
1	<b>THESE STANDARDS</b> do not establish grade rules for joint flushness and or gap tolerances for woodwork products installed in a non-climate controlled environment: however:
1 1	Prior to installation, the flushness and/or gap tolerances of woodwork products intended for non-climate controlled environments shall meet the test requirements herein.
2	<b>ADHESIVE</b> or <b>JOINT FILLER</b> material, if used, shall be inconspicuous and match the adjacent surface for smoothness.
3	<b>SQUARENESS</b> shall be within $\pm 1/64"$ (0.4 mm) for each 12" (305 mm).
4	<b>CUTOUTS</b> shall be within $\pm 1/8"$ for locations and $+1/8"$ to 0" (3.2 to 0 mm) for size.
5	For <b>SCRIBING</b> , countertop shall be provided with extra length.
6	Tops requiring more than one sheet of surface material shall be pre-matched to minimize color variation within the scope of the manufacturer's guarantee and: <span style="float: right;">E C P</span>
6 1	Shall be fabricated from the longest lengths available. <span style="float: right;">E C P</span>
6 2	Top widths exceeding product availability shall have manufacturer-assembled joints.
7	<b>FILLERS</b> shall be furnished by the countertop manufacturer.
8	<b>EDGE APPLICATION SEQUENCE</b> shall be the manufacturer's choice, except at HPDL.
9	<b>BACK SPLASHES</b> require end splashes at wall ends.
10	<b>REMOVABLE LEDGES</b> and/or <b>ACCESS PANELS</b> shall be attached with flat-head screws, set flush, and:
10 1	If chemical resistance is required, screws shall be stainless steel.
<b>Continues next column ▼</b>	

11.4.7 Basic Assembly Rules	
<b>▲ From previous column</b>	
11	Of <b>JOINTS</b> at assembled work (continued)
11 1	Be neatly and accurately made.
11 2	Be securely glued, with:
11 2 1	Adhesive residue removed from exposed surfaces.
11 3	Be reinforced with glue blocks where essential.
11 4	Not permit fasteners at exposed surfaces of decorative laminate.
11 5	Require <b>FLUSHNESS VARIATIONS</b> at exposed surfaces (See Test D illustrations in TESTS), when mitered or butted, such as, <div style="text-align: center;">  </div> not to exceed at:
11 5 1	Wood to wood:
11 5 1 1	0.010" (0.25 mm). <span style="float: right;">E C P</span>
11 5 1 2	0.007" (0.18 mm). <span style="float: right;">E C P</span>
11 5 1 3	0.005" (0.13 mm). <span style="float: right;">E C P</span>
11 5 2	Non-wood to non-wood:
11 5 2 1	0.025" (0.64 mm). <span style="float: right;">E C P</span>
11 5 2 2	0.015" (0.38 mm). <span style="float: right;">E C P</span>
11 5 2 3	0.010" (0.25 mm). <span style="float: right;">E C P</span>
<b>Continues next column ▼</b>	



# SECTION 11



## Countertops



GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally

**E C P**

## compliance requirements

11.4.7		Basic Assembly Rules				
▲ From previous column						
11 Of <b>JOINTS</b> at assembled work (continued)						
11 6	Allow <b>GAPS</b> at exposed surface (see Test A illustrations in TESTS), when mitered or butted, such as,					
						
	not to exceed:					
	1	0.025" (0.64 mm) wide by 20% of the joint length.	E	C	P	
2	0.015" (0.38 mm) wide by 20% of the joint length.	E	C	P		
3	0.010" (0.25 mm) wide by 20% of the joint length.	E	C	P		
11 7	Allow <b>GAPS</b> at exposed surface joints of parallel members (See Test B illustrations in TESTS), such as,					
						
	not to exceed:					
	1	0.025" x 9" (0.64 mm x 229 mm) shall not occur within 48" (1219 mm) of a similar gap in the same joint.	E	C	P	
2	0.015" x 6" (0.38 mm x 152 mm) shall not occur within 60" (1524 mm) of a similar gap in the same joint.	E	C	P		
3	0.010" x 4" (0.25 mm x 102 mm) shall not occur within 72" (1829 mm) of a similar gap in the same joint.	E	C	P		
Continues next column ▼						

11.4.7		Basic Assembly Rules				
▲ From previous column						
11 Of <b>JOINTS</b> at assembled work (continued)						
11 8	Allow <b>GAPS</b> at exposed surface joints (See Test C illustrations in TESTS) when mitered or butted, such as,					
						
	not to exceed:					
	1	0.025" (0.64 mm).	E	C	P	
2	0.015" (0.38 mm).	E	C	P		
3	0.010" (0.25 mm).	E	C	P		
11 9 Allows use of <b>FILLER</b> :						
1	If inconspicuous when viewed at 36" (914 mm).	E	C	P		
2	If inconspicuous when viewed at 24" (610 mm).	E	C	P		
3	<b>NOT ALLOWED.</b>	E	C	P		
11 10 <b>SHEET</b> and <b>LAMINATED LUMBER PANELS</b> shall be allowed to move, float, expand or contract in reaction to ambient humidity changes.						
Requires <b>FLATNESS</b> of installed and removable sheet products (see						
12						
	Test E illustrations in <b>TESTS</b> ) such as, not to exceed					
	1	0.045" (1.1 mm) per 12" (305 mm) or portion thereof.	E	C	P	
	2	0.030" (0.8 mm) per 12" (305 mm) or portion thereof.	E	C	P	
3	0.020" (0.5 mm) per 12" (305 mm) or portion thereof.	E	C	P		
Continues next column ▼						

# SECTION 11



## Countertops

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



## compliance requirements

11.4.7 Basic Assembly Rules	
▲ From previous column	
13	<b>EDGE OVERHANGS</b> shall be consistent, and:
13 1	Within a minimum of 1/2" (12.7 mm) and a maximum of 1-1/4" (31.8 mm) over the outer most cabinet face and finished end, and:
13 1 1	Be parallel with the cabinet face or end within +/- 1/8" (3.2 mm) in any 96" (2438 mm) run of countertop.
13 2	At appliance ends, be flush to a maximum of 1/4" (6.4 mm) over the cabinet end.
13 3	If specified, a continuous drip groove 1/8" x 1/8" (3.2 x 3.2 mm), approximately 3/8" (9.5 mm) back from the front edge, shall be provided.
13 4	If specified flush, shall not exceed 1/8" (3.2 mm) over the outer most cabinet face and finished end, and:
13 4 1	Be parallel with the cabinet face or end within +/- 1/16" (1.6 mm) in any 96" (2438 mm) run of countertop.
14	<b>UNSUPPORTED SPANS</b> and <b>CANTILEVERED COUNTERTOPS</b> or <b>OVERHANGS</b> of countertops shall be reinforced to prevent deflection in excess of 1/4" (6.4 mm) under a 50 lbs (22.7 kg) per square foot (kgs per 305 mm square) load in any 48" (1219 mm) span or portion thereof, and:
14 1	<p><b>UNSUPPORTED SPANS</b> such as,</p>  <p>shall not exceed 48" (1219 mm) in width.</p>
14 2	<p><b>CANTILEVERED OVERHANGS</b>, with or without a sub-top, such as</p>  <p>shall not exceed 12" (305 mm) from a support, whether in the front, back, or end.</p>

11.4.7 Basic Assembly Rules	
▲ From previous column	
15	<b>EXPOSED EDGES</b> shall be:
15 1	Neatly and entirely covered.
15 2	Eased.
15 3	Built up at front to a minimum of 1-1/4" (31.8 mm) in thickness, except at epoxy.
15 4	Of one piece of the longest length possible restricted by material availability up to 144" (3658 mm).
16	<b>METAL TRIM RIMS</b> (furnished by others) at sinks or self-rimming sinks must overlap the countertop and/or sink by a minimum of 3/16" (4.8 mm).

**Specific PRODUCT Requirements for Wood, Decorative Laminate, Solid Surface, Solid Phenolic, Epoxy Resin, and Natural/Engineered Stone are in Annex A, B, C, D, E and/or F which may be found at the end of this PRODUCT portion of Section 11.**



# SECTION 11 - ANNEX 11A

## Wood Countertops

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally

<b>E</b>	<b>C</b>	<b>P</b>
----------	----------	----------

## compliance requirements

# Additional Requirements for Wood Countertops

11.4.5.A		Additional Requirements for Wood Material Rules		
1		3/4" (19 mm) minimum thickness hardwood (plywood or solid stock) of one species for the entire project, and:		
1	1	CORE at veneer faced, shall be a minimum of 3/4" (19 mm) particleboard, medium-density fiberboard, veneer core, or otherwise approved engineered core; however, <b>SINK TOPS</b> and their splashes requires use of:		
1	1	1	Particleboard.	E C P
1	1	2	Veneer core plywood with Type II adhesive.	E C P
1	1	3	Moisture resistant MDF with a 24-hour thickness swell factor of 4.5% or less.	E C P

11.4.6.A		Additional Requirements for Wood Machining Rules		
1	OCCASIONAL PATCHES are allowed.			E C P
2	FINGER JOINTS are permitted in solid lumber for opaque or transparent finish.			E C P
3	SMOOTHNESS REQUIREMENTS (see Item 7.1 in TESTS) require:			
3	1	TOP FLAT WOOD surfaces; those that can be sanded with a drum or wide belt sander:		
3	1	1	Minimum of 15 KCPI or 100-grit sanding.	E C P
3	1	2	120-grit sanding.	E C P
3	1	3	150-grit sanding.	E C P
3	2	PROFILED and SHAPED WOOD surfaces:		
3	2	1	Minimum of 15 KCPI or 100-grit sanding.	E C P
3	2	2	Minimum of 20 KCPI.	E C P
3	2	3	120-grit sanding.	E C P
3	3	CROSS-SANDING:		
3	3	1	Is not a defect.	E C P
3	3	2	Is not allowed.	E C P
4	CURVED front edges shall be solid machined, steam bent, bent solid lumber or laminated plies at the option of the manufacturer, and;			
4	1	In full compliance with all other applicable requirements of these Standards including Section 6.		



# SECTION 11 - ANNEX 11A

## Wood Countertops

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally

<b>E</b>	<b>C</b>	<b>P</b>
----------	----------	----------

GENERAL/PRODUCT/INSTALLATION/TEST

compliance requirements

## Additional Requirements for Wood Countertops

<b>11.4.7.A</b>		<b>Additional Requirements for Wood Assembly Rules</b>		
<b>1</b>	<b>JOINTS</b>			
1	1	At L-shaped tops shall have an approximate 45° diagonal joint; butt joints are not permitted.		
1	2	Installation joints shall be fit tight and flush with the use of splines, dowels, or biscuit splines for alignment, and:		
1	2	1	Be securely fastened with draw-bolt-type mechanical fasteners, if practical.	
1	3	Utilize clamp nail, biscuit spline, butterfly, scarf, or dowel joinery.	<b>E</b>	<b>C</b> <b>P</b>
1	4	Utilize biscuit spline, butterfly, scarf, or dowel joinery.	<b>E</b>	<b>C</b> <b>P</b>
<b>2</b>	<b>WIDE WIDTH GLUE-UP</b> requires, boards exceeding 3" (76 mm) in width be alternately set with crown up and crown down.			
<b>3</b>	<b>SOLID WOOD EDGES</b> and applied moldings shall be:			
3	1	Nailed.	<b>E</b>	<b>C</b> <b>P</b>
3	2	Glued and finish nailed.	<b>E</b>	<b>C</b> <b>P</b>
3	3	Pressure glued and splined, biscuit splined, or doweled without the use of fasteners through the exposed face.	<b>E</b>	<b>C</b> <b>P</b>
<b>4</b>	<b>BUILT-UP MEMBERS</b> shall be of acceptable core material with backing sheet applied, or:			
4	1	The use of moisture-resistant core or a color-coded, water-resistant sealer may be substituted for backing sheet.	<b>E</b>	<b>C</b> <b>P</b>
<b>5</b>	<b>FINISHED ENDS</b> at solid lumber countertops shall have a return finish to cover end grain.			



# SECTION 11 - ANNEX 11B

## HPDL Countertops

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



## compliance requirements

# Additional Requirements for HPDL Countertops

11.4.5.B		Additional Requirements for HPDL Material Rules				
1		Shall be <b>HPDL</b> , a minimum of .039" (0.99 mm) in thickness, or:				
1	1	Use of <b>CONTINUOUS-PRESSURE LAMINATES</b> (melamine and polyester-based) as an alternative to HPDL is permitted, provided that they conform to the same physical properties and thickness as required for HPDL.				
2		<b>CORE</b> shall be a minimum of 3/4" (19 mm) particleboard, medium-density fiberboard, veneer core, or otherwise approved engineered core; however:				
2	1	<b>SINK TOPS</b> and their splashes requires use of:				
2	1	1	Particleboard.	E	C	P
2	1	2	Veneer core plywood with Type II adhesive.	E	C	P
2	1	3	Moisture resistant MDF with a 24-hour thickness swell factor of 4.5% or less.	E	C	P
3		<b>FLAME SPREAD RATED</b> countertops require Class A Flame Spread Rated HPDL and:				
3	1	<b>CORE</b> , a minimum of 11/16" (17.5 mm) thick, Class A Flame Spread.				
3	2	<b>BACKING SHEET</b> , a minimum of 0.028" (0.7 mm) high-pressure phenolic Class A Flame Spread Rated.				

11.4.6.B		Additional Requirements for HPDL Machining Rules			
1		<b>CUTOUTS</b> shall have a minimum of 1/4" (6.4 mm) radius at inside corners, and:			
1	1	Edges subject to excessive moisture shall be sealed with a color-toned (for verification), water-resistant sealer before trim or sink rims are installed.			
2		<b>COVES</b> at splashes of:			
2	1	1/4" (6.4 mm) radius permits a square cove stick the same thickness as the core material with voids filled with glue between the HPDL and the cove stick.			
2	2	3/4" (19 mm) radius requires a molded cove stick glued and mechanically fastened a maximum of 12" (305 mm) on center, with no voids permitted between the HPDL or core and the cove stick.			
3		<b>DRIP GROOVE</b> , when specified, shall be continuous and 1/8" x 1/8" (3.2 mm x 3.2 mm) approximately 3/8" (9.5 mm) from the front edge and sealed with a color-toned (for verification), water-resistant sealer:			
3	1	Groove edges shall be smoothly sanded.			
4		<b>MITER-FOLD</b> self edge is acceptable.			



# SECTION 11 - ANNEX 11B

## HPDL Countertops

GENERAL/PRODUCT/INSTALLATION/TEST


Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally

<b>E</b>	<b>C</b>	<b>P</b>
----------	----------	----------


## compliance requirements

# Additional Requirements for HPDL Countertops

11.4.7.B		Additional Requirements for HPDL Assembly Rules			
1	<b>BACKING SHEET</b> shall cover the underside of countertops, the backside of splashes and be the same for the entire project.				
2	<b>LAMINATIONS</b> shall be made securely to the core with Type II adhesive applied as recommended by the adhesive manufacturer, and:				
2	1	Adhesive for solid color core laminate application shall conform to the manufacturer's recommendation.			
3	<b>FLAME SPREAD-RATED</b> countertops require:				
3	1	Non-formed self-edged.			
3	2	Screwed-on back splash.			
3	3	Minimum custom grade conformance.			
3	4	Adhesive be rigid set with Class A Flame Spread.			
4	<b>SELF-EDGE:</b>				
4	1	Applied after top laminate.	<b>E</b>	<b>C</b>	<b>P</b>
4	2	Applied before top laminate.	<b>E</b>	<b>C</b>	<b>P</b>
5	<b>JOINTS:</b>				
5	1	At L-shaped wood grain or directional pattern countertops shall have an approximate 45° diagonal joint, butt joints are not permitted, except:			
5	1	1	At L-shaped non-wood grain or non-directional pattern countertops, butt joints are permitted.		
5	2	Installation joints shall be fit tight and flush with the use of splines, dowels, or biscuit splines for alignment, and:			
5	2	1	Be securely fastened with draw-bolt-type mechanical fasteners, if practical.		
6	<b>BOTTOM OF EDGING</b> and its build-up shall be free of dents, torn grain, glue, and sanded smooth with sharp edges removed.				
Continues next column ▼					

11.4.7.B		Additional Requirements for HPDL Assembly Rules					
▲ From previous column							
7	<b>BUILT-UP MEMBERS</b> shall be of acceptable core material with backing sheet applied, or:			<b>E</b>	<b>C</b>	<b>P</b>	
7	1	The use of moisture-resistant core or a color-coded, water-resistant sealer may be substituted for backing sheet.			<b>E</b>	<b>C</b>	<b>P</b>
8	At <b>ASSEMBLY 1</b> (wall mount) back and end-splash construction. <b>OPTIONAL</b> within <b>CANADA</b> ; however, <b>NOT ALLOWED</b> within the <b>UNITED STATES</b> ,						
							
requires::							
8	1	Top edge to be edgebanded.					
8	2	Front of end splash to be edgebanded.					
8	3	Splash members to be bundled and shipped loose to project.					
8	4	Mechanical fasteners are required between splash members and deck.	<b>E</b>	<b>C</b>	<b>P</b>		
Continues next column ▼							


## Additional Requirements for HPDL Countertops

<b>11.4.7.B</b>	<b>Additional Requirements for HPDL Assembly Rules</b>	
<b>▲ From previous column</b>		
9	<p>At <b>ASSEMBLY 2</b> (deck mount) back and end-splash construction. <b>OPTIONAL</b> within <b>CANADA</b>; however, <b>REQUIRED</b> within the <b>UNITED STATES</b>,</p> <div style="text-align: center;">  </div> <p>requires::</p>	
9	1	Raw core at joint between the countertop deck and end splash or butt joint-applied back splash shall be sealed before assembly.
9	2	End splashes at cove or butt back splashes shall be butt-jointed and securely attached with mechanical fasteners, and:
9	2	1 Mechanical fasteners are not required at wall or cabinet abutments that are not as deep as the countertop return.
9	2	2 Shall be caulked with clear or compatible color waterproof caulking so as to leave a visual bead not exceeding 1/8" (3.2 mm).
9	3	Scribe allowance shall be provided, as appropriate, and:
9	3	1 Un-backed scribe span shall not exceed 1/2" (12.7 mm) at ends and back walls.
<b>10 FINISHED END CAPS</b> may be applied after top laminate.		
11	<b>REMOVABLE COMPONENTS</b> shall be attached with flat-head screws, set flush, and:	
11	1	If chemical resistance is required, the screws shall be stainless steel.



# SECTION 11 - ANNEX 11C

## Solid Surface Countertops

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally





compliance requirements

# Additional Requirements for Solid Surface Countertops

<b>11.4.5.C</b>	<b>Additional Requirements for Solid Surface Material Rules</b> (only available in Custom and Premium Grade):
1	Nominal 1/4" (6.4 mm) minimum thickness for use as wall panels, tub enclosures, or other vertical surfaces.
2	Nominal 1/2" (12.7 mm) minimum thickness for countertops and back splashes..

<b>11.4.6.C</b>	<b>Additional Requirements for Solid Surface Machining Rules</b> (only available in Custom and Premium Grade):
1	Shall conform to the manufacturer's recommendations.
2	<b>MANUFACTURED JOINTS</b> shall be precision-machined and glued with the manufacturer's hard seaming material or equal:
2 1	Silicone is not permitted at joints, except:
2 1 1	Where hot areas meet cold areas.
3	<b>EDGE</b> detail requires a:
3 1	Single drop or build-up with manufacturers' choice of profile, a minimum of 1" (25.4 mm) thick. <span style="float: right;">C P</span>
3 2	Build-up with manufacturers' choice of profile, a minimum of 1-1/2" (38.1 mm) thick. <span style="float: right;">C P</span>
3 3	Miter-fold with manufacturers' choice of profile, a minimum of 1-1/2" (38.1 mm) thick.
4	<b>COVERED</b> splash is only required when so specified, with:
4 1	Ends sent loose without cove.
5	<b>CUT OUTS</b> shall have a minimum 1/4" (6.4 mm) radius at inside corners.

<b>11.4.7.C</b>	<b>Additional Requirements for Solid Surface Assembly Rules</b> (only available in Custom and Premium Grade):
1	<b>FLUSHNESS VARIATIONS</b> at exposed surfaces when mitered or butted (see Test D illustrations in TESTS) such as,  shall be flush.
2	<b>GAPS</b> at exposed surfaces when mitered or butted (see Test A, B, and C illustrations in TESTS) such as,  shall be gap-free.
<b>Continues next column</b> ▼	



# SECTION 11 - ANNEX 11C

## Solid Surface Countertops


GENERAL/PRODUCT/INSTALLATION/TEST


Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



## compliance requirements

# Additional Requirements for Solid Surface Countertops

<b>11.4.7.C</b>	<b>Additional Requirements for Solid Surface Assembly Rules</b> <i>(only available in Custom and Premium Grade):</i>	
▲ From previous column		
<b>3</b>	<p><b>FLATNESS</b> of installed and removable sheet products (See Test E illustrations in TESTS) such as,</p> 	
	not to exceed:	
	<b>1</b>	0.036" (0.9 mm) per 12" (305 mm) or portion thereof.
<b>2</b>	0.027" (0.7 mm) per 12" (305 mm) or portion thereof.	<b>C</b> <b>P</b>
<b>4 JOINTS</b>		
<b>4</b>	<b>1</b> L-shaped tops with a grain or pattern appearance shall have an approximate 45° diagonal joint; butt joints are not permitted.	
<b>5 EXPOSED FINISH</b> shall be the manufacturer's standard matte finish.		
<b>6 SEAM JOINTS</b> shall be joined with a compatible color-matched adhesive and/or sealant.		
<b>7 EXPANSION CLEARANCES</b> of at least 1/8" (3.2 mm) shall be provided.		
<b>8 SEALANTS</b> and/or <b>ADHESIVES</b> , as recommended by individual manufacturers, shall be used to achieve the best performance and color match.		
Continues next column ▼		

<b>11.4.7.C</b>	<b>Additional Requirements for Solid Surface Assembly Rules</b> <i>(only available in Custom and Premium Grade):</i>	
▲ From previous column		
<b>9</b>	<p><b>CANTILEVERED OVERHANGS</b> with or without a sub-top, such as</p> 	
	<p>shall not exceed 12" (305 mm) for 3/4" (19 mm) thick or 6" (152 mm) for 1/2" (12.7 mm) thick material, whether in the front, back, or end.</p>	



# SECTION 11 - ANNEX 11D

## Solid Phenolic Countertops

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



## compliance requirements


# Additional Requirements for Solid Phenolic Countertops

<b>11.4.5.D</b>	<b>Additional Requirements for Solid Phenolic Material Rules</b> <i>(only available in Premium Grade)</i>
<b>1</b>	Minimum 3/4" (19 mm) in thickness.

<b>11.4.6.D</b>	<b>Additional Requirements for Solid Phenolic Machining Rules</b> <i>(only available in Premium Grade)</i>
<b>1</b>	<b>JOINTS</b> shall be precision-machined with tight joint fasteners and sealed with a biocide silicon prior to tightening (producing an almost invisible joint).
<b>2</b>	<b>FRONT EDGES</b> shall be a minimum of 3/4" (19 mm) in thickness.


<b>11.4.7.D</b>	<b>Additional Requirements for Solid Phenolic Assembly Rules</b> <i>(only available in Premium Grade)</i>
-----------------	--

**FLUSHNESS VARIATIONS** at exposed surfaces when mitered or butted (see Test D illustrations in TESTS) such as,



shall not exceed 0.001" (0.03 mm).

**GAPS** at exposed surfaces when edge is mitered or butted (see Test A illustrations in TESTS) such as,







shall not exceed 0.015" (0.4 mm) wide by 20% of the joint length.

Continues next column ▼



# Additional Requirements for Solid Phenolic Countertops

<b>11.4.7.D</b>	<b>Additional Requirements for Solid Phenolic Assembly Rules</b> <i>(only available in Premium Grade)</i>
▲ From previous column	
3	<p><b>GAPS</b> at exposed surfaces at parallel members (see Test B illustrations in TESTS) such as,</p>  <p>shall not exceed 0.015" x 3" (0.4 mm x 76 mm) and shall not occur within 12" (1829 mm) of a similar gap.</p>
4	<p><b>GAPS</b> at exposed surfaces when mitered or butted (see Test C illustrations in TESTS), such as,</p>  <p>shall not exceed 0.015" (0.4 mm).</p>
Continues next column ▼	

<b>11.4.7.D</b>	<b>Additional Requirements for Solid Phenolic Assembly Rules</b> <i>(only available in Premium Grade)</i>
▲ From previous column	
5	<p><b>FLATNESS</b> (see Test E illustrations in TESTS) such as</p>  <p>shall be held within <math>\pm 1/32"</math> (0.8 mm) per 120" (3048 mm) span.</p>
6	<p><b>EDGE FINISH</b> shall be the standard black core with a machined satin sheen; polished edges shall be so specified.</p>
7	<p><b>LIPPED TOPS</b> shall be raised a minimum of 1/4" (6.4 mm) above the work surface; the width of the raised area shall be determined by the manufacturer.</p>
8	<p><b>BACK SPLASHES</b> shall be separate, flat-buttet.</p>
9	<p><b>CANTILEVERED OVERHANGS</b> with or without a sub-top, such as,</p>  <p>shall not exceed 12" (305 mm) for 3/4" (19 mm) thick or 6" (152 mm) for 1/2" (12.7 mm) thick material, whether in the front, back, or end.</p>



# SECTION 11 - ANNEX 11E

## Epoxy Resin Countertops

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally





## compliance requirements


# Additional Requirements for Epoxy Resin Countertops


<b>11.4.5.E</b>	<b>Additional Requirements for Epoxy Resin Material Rules</b> <i>(only available in Premium Grade)</i>
1	Minimum 1" (25.4 mm) in thickness.

<b>11.4.6.E</b>	<b>Additional Requirements for Epoxy Resin Machining Rules</b> <i>(only available in Premium Grade)</i>
1	<b>EXPOSED EDGES</b> shall be smoothly machined and finished to be compatible with the top face.
2	<b>LIPPED TOPS</b> shall be raised a minimum of 3/16" (4.8 mm) above the work surface, and:
2 1	Drip groove is not required.

<b>11.4.7.E</b>	<b>Additional Requirements for Epoxy Resin Assembly Rules</b> <i>(only available in Premium Grade)</i>
1	<b>FLUSHNESS VARIATIONS</b> at exposed surfaces when mitered or butted (see Test D illustrations in TESTS) such as, 
	shall not exceed 0.050" (0.8 mm).
<b>Continues next column</b> ▼	

<b>11.4.7.E</b>	<b>Additional Requirements for Epoxy Resin Assembly Rules</b> <i>(only available in Premium Grade)</i>
<b>▲ From previous column</b>	
2	<b>GAPS</b> at exposed surfaces when edge is mitered or butted shall be per the manufacturer's recommendation and shall be neatly filled with recommended filler material (see Test A, B, and C illustrations in TESTS) such as, 
	shall be gap-free.

3	<b>FLATNESS</b> (see Test E illustrations in TESTS) such as, 
	shall be held within ±1/16" (1.6 mm) for each 36" (914 mm) span.

4	<b>BACK SPLASHES</b> shall be separate, flat-buttet.
5	<b>CANTILEVERED OVERHANGS</b> with or without a sub-top, such as, 
	shall not exceed 12" (305 mm) for 1" (25.4 mm) thick or 6" (152 mm) for 3/4" (19 mm) thick material, whether in the front, back, or end.



# SECTION 11 - ANNEX 11F

## Natural/Engineered Stone Countertops

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



## compliance requirements


# Additional Requirements for Natural/Engineered Stone Countertops

<b>11.4.5.F</b>	<b>Additional Requirements for Natural/Engineered Stone Material Rules</b> <small>(only available in Premium Grade):</small>
1	Minimum 2 cm (13/16" (20 mm)) thick material.

<b>11.4.6.F</b>	<b>Additional Requirements for Natural/Engineered Stone Machining Rules</b> <small>(only available in Premium Grade):</small>
1	<b>EXPOSED EDGES</b> shall be finished the same as the top surface.

<b>11.4.7.F</b>	<b>Additional Requirements for Natural/Engineered Stone Assembly Rules</b> <small>(only available in Premium Grade):</small>
-----------------	--


**FLUSHNESS** or **LIPPAGE VARIATIONS** at exposed surfaces when mitered or butted (see Test D illustrations in TESTS) such as,



1

shall not exceed 1/32" (0.8 mm) at the center of the joint.

**GAPS** at exposed surfaces when mitered or butted (see Test A illustrations in TESTS) such as,



2

shall not exceed 0.015" (0.4 mm) wide by 20% of the joint length.

Continues next column ▼



# SECTION 11 - ANNEX 11F

## Natural/Engineered Stone Countertops



GENERAL/PRODUCT/INSTALLATION/TEST



Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



## compliance requirements

# Additional Requirements for Natural/Engineered Stone Countertops

<b>11.4.7.F</b>	<p><b>Additional Requirements for Natural/Engineered Stone Assembly Rules</b> (only available in Premium Grade):</p>
▲ From previous column	
3	<p><b>GAPS</b> at exposed surfaces at parallel members (see Test B illustrations in TESTS) such as,</p>  <p>shall not exceed 0.015" x 3" (0.4 mm x 76 mm) and shall not occur within 12" (1829 mm) of a similar gap.</p>
4	<p><b>GAPS</b> at exposed surfaces when mitered or butted (see Test C illustrations in TESTS) such as,</p>  <p>shall not exceed 0.015" (0.4 mm).</p>
Continues next column ▼	

<b>11.4.7.F</b>	<p><b>Additional Requirements for Natural/Engineered Stone Assembly Rules</b> (only available in Premium Grade):</p>
▲ From previous column	
5	<p><b>THICKNESS</b> of the material used throughout a project shall not vary in excess of 1/8" (3.2 mm).</p>
6	<p><b>FLATNESS</b> (see Test E illustrations in TESTS) such as,</p>  <p>shall be held within ±1/16" (1.6 mm) for each 48" (1219 mm) span.</p>
7	<p><b>BACK SPLASHES</b> shall be separate, flat-buttet.</p>
8	<p><b>CANTILEVERED OVERHANGS</b> with or without a sub-top, such as,</p>  <p>shall not exceed 6" (152 mm) for 2 cm (13/16" (20 mm)) thick material or 10" (254 mm) for 3 cm (1-3/16" (30 mm)) thick material, whether in the front, back, or end.</p>



# SECTION 11

## Countertops

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



## compliance requirements

### 11.5 PREPARATION AND QUALIFICATION REQUIREMENTS

1. **CARE, STORAGE, and BUILDING CONDITIONS** shall be in compliance with the requirements set forth in Section 2 of these standards.
  - 1.1 Severe damage to the woodwork can result from noncompliance. **THE MANUFACTURER AND/OR INSTALLER OF THE WOODWORK SHALL NOT BE HELD RESPONSIBLE FOR DAMAGE THAT MIGHT DEVELOP BY NOT ADHERING TO THE REQUIREMENTS.**
  - 2 **CONTRACTOR IS RESPONSIBLE FOR** 
    - 2.1 Furnishing and installing structural members, grounds, in wall blocking, backing, furring, brackets, or other anchorage required for architectural woodwork installation that becomes an integral part of walls, floors, or ceilings to which architectural woodwork shall be installed.
      - 2.1.1 In the absence of contract documents calling for the contractor to supply the necessary in wall blocking/backing in the wall or ceilings, either through inadvertence or otherwise, the architectural woodwork installer shall not proceed with the installation until such time as the in wall blocking/backing is installed by others.
      - 2.1.2 Preparatory work done by others shall be subject to inspection by the architectural woodwork installer and may be accepted or rejected for cause prior to installation.
        - 2.1.2.1 **WALL, CEILING,** and/or opening variations in excess of 1/4" (6.4 mm) or **FLOORS** in excess of 1/2" (12.7 mm) in 144" (3658 mm) of being plumb, level, flat, straight, square, or of the correct size are not acceptable for the installation of architectural woodwork, nor is it the responsibility of the installer to scribe or fit to tolerances in excess of such.
    - 2.2 Installation site being properly ventilated, protected from direct sunlight, excessive heat and/or moisture, and that the HVAC system is functioning and maintaining the appropriate relative humidity and temperature.

### 11.5 PREPARATION AND QUALIFICATION REQUIREMENTS (continued)

- 2.3 Priming the architectural woodwork in accordance with the contract documents prior to its installation.
  - 2.3.1 If the architectural woodwork is factory finished, priming by the factory finisher is required.
- 3 **INSTALLER IS RESPONSIBLE FOR** 
  - 3.1 Having adequate equipment and experienced craftsmen to complete the installation in a first class manner.
  - 3.2 Checking architectural woodwork specified and studying the appropriate portions of the contract documents, including these standards and the reviewed shop drawings to familiarize themselves with the requirements of the Grade specified, understanding that:
    - 3.2.1 Appearance requirements of Grades apply only to surfaces visible after installation.
    - 3.2.2 For transparent finish, special attention needs to be given to the color and the grain of the various woodwork pieces to ensure they are installed in compliance with the Grade specified.
  - 3.3 Verification that installation site is properly ventilated, protected from direct sunlight, excessive heat and/or moisture, and that the HVAC system is functioning and maintaining the appropriate relative humidity and temperature.
  - 3.4 Verification that required priming of woodwork has been completed by others before woodwork is install.
  - 3.5 Verification that woodwork has been acclimated to the field conditions for a minimum of 72 hours before installation is commenced.
  - 3.6 Woodwork specifically built or assembled in sequence for match of color and grain is installed to maintain that same

# SECTION 11

## Countertops

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



## compliance requirements

sequence.

### 11.6 RULES

- 1 The following rules shall govern unless a project's contract documents require otherwise.
- 2 These rules are intended to provide a well defined degree of control over a project's quality of installation.
- 3 **ERRATA**, published at <http://naaws-errata.com>, shall take precedence over these rules, subject to their date of posting and a project's bid date.



### 11.6.4 Basic General Rules

1	<b>AESTHETIC GRADE RULES</b> apply only to exposed surfaces visible after installation.					
2	<b>INSTALLED</b> plumb, level, square, and flat within 1/8" (3.2 mm) in 96" (2438 mm), and when required:					
2	1	<b>FOUNDATIONS</b> and hanging systems set plumb and true.				
3	<b>TRANSPARENT</b> finished woodwork shall be installed:					
3	1	With consideration of color and grain.	E	C	P	
3	2	<b>COMPATIBLE</b> in color and grain.	E	C	P	
3	3	<b>WELL MATCHED</b> for color and grain.	E	C	P	
3	3	1	Sheet products shall be compatible in color with solid stock.	E	C	P
3	3	2	Adjacent sheet products shall be well matched for color and grain.	E	C	P
4	<b>REPAIRS</b> are allowed, provided they are neatly made and inconspicuous when viewed at:					
4	1	72" (1829 mm).	E	C	P	
4	2	48" (1220 mm).	E	C	P	
4	3	24" (610 mm).	E	C	P	
5	<b>INSTALLER FABRICATION</b> or <b>MODIFICATIONS</b> shall comply to the general, material, machining, and assembly rules within the PRODUCT portion of this section and the applicable finishing rules in Section 5.					
6	<b>BUILD UP</b> or spacing materials required for installation of a countertop are the responsibility of the countertop manufacturer.					
<b>Continues next column ▼</b>						

### 11.6.4 Basic General Rules

<b>▲ From previous column</b>						
7	<b>HORIZONTAL REVEAL</b> between the lower edge of the countertop and the upper edge of the adjacent door or drawer front at base cabinets with countertops shall be a consistent 1/4" (6.4 mm) +/- 1/8" (3.2 mm), except:					
7	1	At laboratory casework, it shall be 1/4" (6.4 mm) to 1" (25.4 mm) and shall be consistent across elevations, except:				
7	1	1	At sink locations.			
7	2	Coordination of such is the responsibility of the cabinet manufacturer.				
8	<b>CURVED</b> front edges shall be solid machined, steam bent, bent solid lumber or laminated plies at the option of the manufacturer, and;					
8	1	In full compliance with all other applicable requirements of these Standards including Section 6.				
9	<b>COUNTERTOPS</b> shall be:					
9	1	Installed within 1/4" (6.4 mm) plus or minus the industry standard for height specified (see Section 10), except where ADA compliance is required.				
9	2	<b>SECURELY FASTENED</b> and tightly fitted with flush joints.				
9	2	1	The manufacturer's recommended CAULK and SEALANTS shall be used to achieve the best performance and color match.			
9	2	2	Joinery shall be consistent throughout the project.			
9	3	Of <b>MAXIMUM</b> available and/or practical lengths.	E	C	P	
9	4	<b>INSTALLED</b> free of:				
9	4	1	Warp, twisting, cupping, and/or bowing that cannot be held true.			
9	4	2	Open joints, visible machine marks, cross sanding, tear outs, nicks, chips, and/or scratches.			
9	4	3	Natural defects exceeding the quantity and/or size limits defined in Sections 3 and 4.			
9	5	<b>SMOOTH</b> and sanded without cross scratches in conformance to the product portion of this section.				
9	6	<b>SCRIBED</b> at:				
9	6	1	Flat surfaces.	E	C	P
9	6	2	Shaped surfaces.	E	C	P
<b>Continues next column ▼</b>						

# SECTION 11

## Countertops

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



## compliance requirements

### 11.6.4 Basic General Rules

▲ From previous column

10		GLUE and filler residue is not permitted on exposed faces.
11		<b>EQUIPMENT CUTOUTS</b> , including electrical and plumbing, shall be cut out by the installer, provided templates are furnished prior to installation, and:
11	1	Shall be neatly cut and properly sized to be covered by standard cover plates or rosettes.
11	2	In <b>HPDL</b> or <b>SOLID SURFACE</b> shall have a minimum 1/4" (6.4 mm) radius at inside corners.
12		<b>MIRRORS</b> , that are wall mounted, shall not be supported by the countertop or back splash.
13		<b>EDGE OVERHANGS</b> shall be consistent, and:
13	1	Within a minimum of 1/2" (12.7 mm) and a maximum of 1-1/4" (31.8 mm) over the outer most cabinet face and finished end, and:
13	1 1	Be parallel with the cabinet face or end within +/- 1/8" (3.2 mm) in any 96" (2438 mm) run of countertop.
13	2	At appliance ends, be flush to a maximum of 1/4" (6.4 mm) over the cabinet end.
13	3	If specified, a continuous drip groove 1/8" x 1/8" (3.2 x 3.2 mm), approximately 3/8" (9.5 mm) back from the front edge, shall be provided.
13	4	If specified flush, shall not exceed 1/8" (3.2 mm) over the outer most cabinet face and finished end, and:
13	1 1	Be parallel with the cabinet face or end within +/- 1/16" (1.6 mm) in any 96" (2438 mm) run of countertop.

Continues next column ▼

### 11.6.4 Basic General Rules


▲ From previous column

**UNSUPPORTED SPANS** and **CANTILEVERED COUNTERTOPS** or **OVERHANGS** of countertops shall be reinforced to prevent deflection in excess of 1/4" (6.4 mm) under a 50 lbs (22.7 kg) per square foot (kgs per 305 mm square) load in any 48" (1219 mm) span or portion thereof, and:

**UNSUPPORTED SPANS**

such as,


14 1



shall not exceed 48" (1219 mm) in width.

**CANTILEVERED OVERHANGS**, with or without a sub-top, such as

14 2




shall not exceed 12" (305 mm) from a support, whether in the front, back, or end.

**THESE STANDARDS** do not establish grade rules for joint flushness and or gap tolerances for woodwork products installed in a non climate controlled environment.



**GAPS** (see Test A illustrations in TESTS) such as,

16



and:

16 1 If caused by excessive deviations in the building's walls and ceilings being in excess of 1/4" [6.4 mm] in 144" (3658 mm) of being plumb, level, flat, straight, square, or of the correct size, or 1/2" (12.7 mm) for floors, shall not be considered a defect or the responsibility of the installer.

16 2 Shall not exceed 30% of a joint's LENGTH and:

16 2 1	Be allowed if filled or caulked, and:	<b>E</b>	<b>C</b>	<b>P</b>
16 2 2	if color compatible.	<b>E</b>	<b>C</b>	<b>P</b>

Continues next column ▼

# SECTION 11

## Countertops

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally


<b>E</b>	<b>C</b>	<b>P</b>
----------	----------	----------

## compliance requirements

### 11.6.4 Basic General Rules

▲ From previous column					
16	<b>GAPS</b> (see Test A illustrations in TESTS) (continued)				
16	<b>3</b> Of <b>WOOD</b> to <b>WOOD</b> shall not exceed:				
16	<b>3 1</b> At <b>FLAT</b> surfaces:				
16	3	1	1	0.030" (0.76 mm) in width.	E C P
16	3	1	2	0.020" (0.51 mm) in width.	E C P
16	3	1	3	0.015" (0.38 mm) in width.	E C P
16	<b>3 2</b> At <b>SHAPED</b> surfaces:				
16	3	2	1	0.040" (1.02 mm) in width.	E C P
16	3	2	2	0.025" (0.64 mm) in width.	E C P
16	3	2	3	0.015" (0.38 mm) in width.	E C P
16	<b>4</b> Of <b>WOOD</b> to <b>NON WOOD</b> shall not exceed:				
16	<b>4 1</b> At <b>FLAT</b> and <b>SHAPED</b> surfaces:				
16	4	1	1	0.075" (1.91 mm) in width.	E C P
16	4	1	2	0.050" (1.27 mm) in width.	E C P
16	4	1	3	0.035" (0.89 mm) in width.	E C P
16	<b>5</b> Of <b>NON WOOD</b> to <b>NON WOOD</b> and/or all elements shall not exceed:				
16	<b>5 1</b> At <b>FLAT</b> surfaces:				
16	5	1	1	0.075" (1.91 mm) in width.	E C P
16	5	1	2	0.050" (1.27 mm) in width.	E C P
16	5	1	3	0.035" (0.89 mm) in width.	E C P
16	<b>5 2</b> At <b>SHAPED</b> surfaces:				
16	5	2	1	0.120" (3.05 mm) in width.	E C P
16	5	2	2	0.075" (1.91 mm) in width.	E C P
16	5	2	3	0.050" (1.27 mm) in width.	E C P
Continues next column ▼					

### 11.6.4 Basic General Rules

▲ From previous column					
<b>FLUSHNESS</b> of joinery (see Test D illustrations in TESTS), such as					
17					
	and:				
17	<b>1</b> Of <b>WOOD</b> to <b>WOOD</b> and HPDL to HPDL shall not exceed:				
17	<b>1 1</b> At <b>FLAT</b> surfaces:				
17	1	1	1	0.025" (0.64 mm).	E C P
17	1	1	2	0.015" (0.38 mm).	E C P
17	1	1	3	0.010" (0.25 mm).	E C P
17	<b>1 2</b> At <b>SHAPED</b> surfaces:				
17	1	2	1	0.040" (0.97 mm).	E C P
17	1	2	2	0.025" (0.65 mm).	E C P
17	1	2	3	0.020" (0.51 mm).	E C P
17	<b>2</b> Of <b>WOOD</b> to <b>NON WOOD</b> shall not exceed:				
17	<b>2 1</b> At <b>FLAT</b> and <b>SHAPED</b> surfaces:				
17	2	1	1	0.075" (1.91 mm).	E C P
17	2	1	2	0.050" (1.27 mm).	E C P
17	2	1	3	0.035" (0.89 mm).	E C P
17	<b>3</b> Of <b>NON WOOD</b> to <b>NON WOOD</b> and/or all elements excluding HPDL to HPDL shall not exceed:				
17	<b>3 1</b> At <b>FLAT</b> surfaces:				
17	3	1	1	0.075" (1.9 mm).	E C P
17	3	1	2	0.050" (1.27 mm).	E C P
17	3	1	3	0.035" (0.89 mm).	E C P
17	<b>3 2</b> At <b>SHAPED</b> surfaces:				
17	3	2	1	0.120" (3.05 mm).	E C P
17	3	2	2	0.075" (1.9 mm).	E C P
17	3	2	3	0.050" (1.27 mm).	E C P
Continues next column ▼					

# SECTION 11

## Countertops

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



## compliance requirements

### 11.6.4 Basic General Rules

#### ▲ From previous column

#### 18 FASTENING shall:

- |    |   |   |
|----|---|---|
| 18 | 1 | Include the use of construction adhesive, finish nails, trim screws, and/or pins. |
| 18 | 2 | Not permit the use of drywall or bugle head screws.                               |
| 18 | 3 | Not permit exposed fastening through HPDL, except at removable panels.            |

#### 19 EQUIPMENT CUTOUTS shall be neatly cut out by the installer, provided templates are furnished in a timely manner.

- |    |   |   |
|----|---|---|
| 19 | 1 | Cutouts in HPDL shall have radiused inside corners. |
|----|---|---|

#### 20 HARDWARE shall be:

- |    |   |   |
|----|---|---|
| 20 | 1 | Installed neatly without tear out of surrounding stock.   |
| 20 | 2 | Installed per the manufacturer's instructions.  |
| 20 | 3 | Installed using all furnished fasteners and fasteners' provisions and when fastener provisions are countersunk, fasteners shall be countersunk. |
| 20 | 4 | Adjusted for smooth operation.  |

#### 21 AREAS OF INSTALLATION shall be left broom clean.

- |    |   |  |
|----|---|--|
| 21 | 1 | Debris shall be removed and dumped in containers provided by the contractor. |
| 21 | 2 | Items installed shall be cleaned of pencil or ink marks.                     |

22 **FIRST CLASS WORKMANSHIP** is required in compliance with these standards.



#### 23 At **SOLID** or **VENEERED WOOD**:

- |    |     |  |
|----|-----|--|
| 23 | 1   | <b>EDGES</b> , both Front and leading of countertop to withstand a 75 lb (34 kg) pull up pressure.   |
| 23 | 2   | <b>WATERPROOF CAULK</b> shall be used at miter and butt joints including splashes and return ends, and:  |
| 23 | 2 1 | Shall not exceed 1/16" (6.4 mm).   |
| 23 | 2 2 | Shall be furnished by installation contractor, unless otherwise specified.   |
| 23 | 3   | <b>INSTALLER ASSEMBLED JOINTS</b> shall be fastened together with a mechanical tightening system either routed into or mounted on the bottom side of the countertop. |

Continues next column ▼

### 11.6.4 Basic General Rules

#### ▲ From previous column

#### 23 At **SOLID** or **VENEERED WOOD** (continued)

- |    |   |   |
|----|---|---|
| 23 | 4 | <b>SINK CUTOUTS</b> shall not fall within 18" (457 mm) of discretionary installer joints.   |
| 23 | 5 | <b>CUTOUTS</b> , subject to excessive moisture, shall have edges sealed with a color toned (for verification), water resistant sealer before trim or sink rims are installed. |

#### 24 At **HPDL**:

#### 24 1 COUNTERTOPS shall be scribed to walls, and:

- |    |   |   |  |  |
|----|---|---|--|--|
| 24 | 1 | 1 | Securely anchored to base cabinets with proper length screws, and: |  |
| 24 | 1 | 1 | 1  | Properly aligned with uniform front edge overhang.   |
| 24 | 1 | 1 | 2  | <b>INSTALLER ASSEMBLED JOINTS</b> shall be glued and fastened together with a mechanical tightening system either routed into or surface mounted on the bottom side of the countertop. |

#### 24 1 2 EDGES, both Front and leading of countertop to withstand a 75 lb (34 kg) pull up pressure.

#### 24 2 WATERPROOF CAULK shall be used at square butt joints including splashes and return ends, and:

- |    |   |   |  |          |          |          |
|----|---|---|--|----------|----------|----------|
| 24 | 2 | 1 | Shall not exceed 1/4" (6.4 mm).  | <b>E</b> | <b>C</b> | <b>P</b> |
| 24 | 2 | 2 | Shall not exceed 1/8" (3.2 mm).  | <b>E</b> | <b>C</b> | <b>P</b> |
| 24 | 2 | 3 | Shall be furnished by installation contractor, unless otherwise specified. |          |          |          |

Continues next column ▼

# SECTION 11



## Countertops

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



## compliance requirements

11.6.4 Basic General Rules	
▲ From previous column	
24	At HPDL (continued)
24 3	At <b>ASSEMBLY 1</b> (wall mount) back and end splash construction, exposed top and ends shall be scribed to the wall configuration. <b>OPTIONAL</b> within <b>CANADA</b> ; however, <b>NOT ALLOWED</b> within the <b>UNITED STATES</b> , 
and:	
24 3 1	Shall be caulked with clear or compatible color waterproof caulking (furnished by installer), so as to leave a visual bead not exceeding 1/8" (3.2 mm) between the bottom of the splash and the countertop.
24 3 2	Variation in building walls in excess of 1/2" (12.7 mm) in 144" (3658 mm) may result in gaps between splash and walls and shall not be considered a defect or the responsibility of the installer.
24 3 3	Mechanical fasteners are required between splash members and deck. <span style="float: right;">E C P</span>
24 4	At <b>ASSEMBLY 2</b> (deck mount) back and end splash construction, exposed top and ends shall be scribed to the wall configuration. <b>OPTIONAL</b> within <b>CANADA</b> ; however, <b>REQUIRED</b> within the <b>UNITED STATES</b> . 
24 4 1	Unbacked scribe spans shall not exceed 1/2" (12.7 mm) at ends and back walls, and gaps shall:
24 4 1 1	Not exceed 1/16" (1.6 mm) and be caulked. <span style="float: right;">E C P</span>
24 4 1 2	Not exceed 1/32" (0.8 mm) and be caulked. <span style="float: right;">E C P</span>
Continues next column ▼	

11.6.4 Basic General Rules	
▲ From previous column	
24	At HPDL (continued)
24 5	<b>CUTOUTS</b> shall have a minimum of 1/4" (6.4 mm) radius at inside corners, and:
24 4 1	Sink cutouts shall not fall within 18" (457 mm) of discretionary installer joints.
24 4 2	Cutouts, subject to excessive moisture, shall have edges sealed with a color toned (for verification), water resistant sealer before trim or sink rims are installed.
25 At <b>SOLID SURFACE</b> (only available in Custom and Premium Grade):	
25 1	<b>SEALANTS</b> and <b>ADHESIVES</b> shall be compatible with the individual manufacturer's recommendations or specially developed sealants to achieve the best color match.
25 2	<b>EXPANSION</b> joints shall be furnished where required by building design or manufacturer recommendations.
25 3	<b>SUPPORT</b> shall be adequately furnished to minimize stresses, and:
25 3 1	Minimum full perimeter and joint support is required on horizontal applications, with:
25 3 1 1	Maximum on center separation between supports of 30" (750 mm) for acrylic and 24" (610 mm) for non acrylic materials.
25 3 1 2	A maximum unsupported and unloaded overhang of 12" (305 mm) for 3/4" (19 mm) and 6" (152 mm) for 1/2" (12.7 mm) sheet thickness.
25 4	<b>JOINTS</b> shall be:
25 4 1	Square (butt) rather than mitered near corners to minimize material and facilitate installation.
25 4 2	Be fully supported.
25 4 3	Edges to be joined shall be straight, smooth, and clean.
25 4 3 1	All joints shall be made using the manufacturer's recommended adhesive.
25 4 4	L and U shaped corners shall have smooth, rounded inside corners, and:
25 4 4 1	Seams shall be offset a minimum of 3 times the inside corner radius.
Continues next column ▼	



# SECTION 11

## Countertops

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



## compliance requirements

<b>11.6.4 Basic General Rules</b>	
▲ From previous column	
25	At <b>SOLID SURFACE</b> (continued):
25 5	<b>CUTOUT CORNERS</b> shall be rounded, 1/4" (6.4 mm) minimum radius, with edges smoothed, and:
25 5 1	At heat producing areas, corners shall be reinforced per the manufacturer's requirements and protected with approved heat reflective tape.
25 6	<b>BACK</b> and <b>END SPLASHES</b> shall be securely adhered to the wall, butt joined to the countertop, and shall be:
25 6 1	<b>CAULKED</b> with clear or compatible color waterproof caulking (furnished by the installer) so as to leave a visual bead not exceeding 1/8" (3.2 mm) between the bottom of the splash and the countertop.
25 6 2	Variation in building walls in excess of 1/2" (12.7 mm) in 144" (3658 mm) may result in gaps between splash and walls and shall not be considered a defect or the responsibility of the installer.
25 6 3	<b>COVED SPLASHES</b> , if specified, shall be hard seamed and integral to the countertop.
25 7	<b>COUNTERTOP ADHESION</b> shall be made using a clear silicone sealant placed a maximum of 12" (12.7 mm) on center.
25 8	<b>HARD SEAMS</b> shall be water tight and gap free.
Continues next column ▼	

<b>11.6.4 Basic General Rules</b>	
▲ From previous column	
26	At <b>SOLID PHENOLIC</b> (only available in Premium Grade):
26 1	<b>COUNTERTOP</b> shall be secured to supports with silicone cement or appropriately sized machine screws applied to each corner and along the perimeter edge at not more than 48" (1219 mm) on center.
26 2	<b>JOINTS</b> shall be precision machined with tight joint fasteners and sealed with a biocide silicone prior to tightening.
26 3	<b>SINKS</b> shall be stainless steel, polypropylene, or epoxy resin; either lipped or under mount, and:
26 3 1	<b>LIPPED</b> shall be set in a rabbeted cutout in the countertop.
26 3 2	<b>UNDER MOUNT</b> shall be installed using adjustable metal sink supports for underside installation or fastened directly to the underside of the countertop using machine screws and silicone adhesive.
26 3 3	A biocide silicone adhesive shall be used at the juncture of the sink and countertop to produce a leak proof joint.
26 4	<b>BACK</b> and <b>END SPLASHES</b> shall be securely adhered to the wall, butt joined to the countertop, and shall be:
26 4 1	<b>CAULKED</b> with clear or compatible color waterproof caulking (furnished by the installer) so as to leave a visual bead not exceeding 1/8" (3.2 mm) between the bottom of the splash and the countertop.
26 4 2	Variation in building walls in excess of 1/2" (12.7 mm) in 144" (3658 mm) may result in gaps between splash and walls and shall not be considered a defect or the responsibility of the installer.
Continues next column ▼	



# SECTION 11

## Countertops

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally



## compliance requirements

11.6.4 Basic General Rules	
▲ From previous column	
25	At <b>EPOXY RESIN, NATURAL/ENGINEERED STONE</b> (only available in Premium Grade):
25 1	<b>COUNTERTOP</b> shall be secured to supports with epoxy cement applied to each corner and along the perimeter edge at not more than 48" (1219 mm) on center, and:
25 1 1	<b>JOINTS</b> shall be butted and filled with a color matched epoxy cement.
25 2	<b>EDGE OVERHANG</b> shall be provided on the front and ends of 1" (25.4 mm) nominal.
25 3	<b>CANTILEVERED OVERHANGS</b> shall not exceed 12" (305 mm) for 3/4" (19 mm) and 6" (152 mm) for 1/2" (12.7 mm) sheet thickness.
25 4	<b>BACK</b> and <b>END SPLASHES</b> shall be securely adhered to the wall, butt joined to the countertop, and:
25 4 1	Shall be caulked with clear or compatible color waterproof caulking (furnished by the installer) so as to leave a visual bead not exceeding 1/8" (3.2 mm) between the bottom of the splash and the countertop.
25 4 2	Variation in building walls in excess of 1/2" (12.7 mm) in 144" (3658 mm) may result in gaps between the splash and the walls and shall not be considered a defect or the responsibility of the installer.
25 5	<b>HARD SEAMS</b> shall be water tight and gap free.
25 6	<b>SCRIBING</b> is not required.
25 7	<b>SINKS</b> shall be either lipped or under mounted, and:
25 7 1	<b>LIPPED</b> shall be set in a rabbeted cutout in the countertop.
25 7 2	<b>UNDER MOUNT</b> shall be installed using adjustable metal sink supports, and:
25 7 2 1	An epoxy cement is required at the juncture of the sink and countertop to produce a leak proof joint.
25 7 2 2	The maximum gap between the countertop edge of the sink and underside of the countertop shall not exceed 3/16" (4.8 mm).



# SECTION 11

## Countertops

### GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally




## compliance requirements

### 11.7 BASIC CONSIDERATIONS

- 1 **TOLERANCES** typically found within NAAWS:
- 1.1 Fall into two **CATEGORIES**:
- 1.1.1 Factory fabricated joinery, assembly and construction - found in the **PRODUCT** portion.
- 1.1.1 Field installation joinery and assembly - found in the **INSTALLATION** portion.
- 1.2 **INCLUDE:**
- 1.2.1 Flatness of wood based panel products.
- 1.2.2 Solid wood to solid wood joints and assemblies.
- 1.2.3 Solid wood to wood veneer joints and assemblies.
- 1.2.4 Wood veneer to wood veneer joints and assemblies.
- 1.2.5 Solid wood to wood based product joints and assemblies (decorative laminate Solid Phenolic and panel products).
- 1.2.6 Solid surface to solid surface joints and assemblies.
- 1.3 **EXCLUDE:**
- 1.3.1 **BECAUSE of EXPANSION and CONTRACTION DIFFERENCES of non-wood products compared to solid wood and wood based products, these Standards do not apply tolerances regarding flatness or joinery to:** 
- 1.3.1.1 Solid wood to non-wood based products (which can be drywall, glass, metal, stone, acrylics, and other surfaces).
- 1.3.1.2 Non-wood to non-wood joints.

### 11.7 BASIC CONSIDERATIONS (continued)

- 2 **FABRICATED and INSTALLED** woodwork shall be tested for compliance to these standards as follows.
- 2.1 **SMOOTHNESS** of exposed surfaces:
- 2.1.1 **KCPI** (Knife Cuts Per Inch) is determined by holding the surfaced board at an angle to a strong light source and counting the visible ridges per inch, usually perpendicular to the profile.
- 
- Figure: 11-072
- 2.1.2 **SANDING** is checked for compliance by sanding a sample piece of the same species with the required grit of abrasive, and:
- 2.1.2.1 Observation with a hand lens of the prepared sample and the material in question will offer a comparison of the scratch marks of the abrasive grit.
- 2.1.2.2 Reasonable assessment of the performance of the finished product will be weighed against absolute compliance with the standard.
- 2.1.2.3 A product is sanded sufficiently smooth when knife cuts are removed and remaining sanding marks are or will be concealed by applied finishing coats.
- 2.1.2.4 Grain raise at unfinished wood, due to moisture or humidity in excess of the ranges set forth in this standard, shall not be considered a defect and must be sanded prior to finishing.
- 2.2 **GAPS, FLUSHNESS, FLATNESS and ALIGNMENT:**
- 2.2.1 Maximum gaps between exposed components shall be tested with a feeler gauge at points designed to join, where members contact or touch.
- 2.2.2 Joint length shall be measured with a ruler with minimum 1/16" (1 mm) divisions and calculations made accordingly.
- 2.2.3 Reasonable assessment of the performance of the finished product will be weighed against absolute compliance with the standards.

# SECTION 11

## Countertops

GENERAL/PRODUCT/INSTALLATION/TEST

Where the **E**, **C**, or **P** icon is not indicated, the rule applies to all Grades equally




## compliance requirements

### 11.7 BASIC CONSIDERATIONS (continued)

#### 2.2 GAPS, FLUSHNESS, FLATNESS and (continued)

2.2.4 The following is intended to provide examples of how and where compliance testing is measured:



Measured on the concave face

- A - Gaps when surfaces are mitered or butted
- B - Gaps when parallel pieces are joined
- C - Gaps when edges are mitered or butted
- D - Flushness between two surfaces
- E - Flatness of panel product
- F - Overlap (flushness of laminate)

- G - Chip Out
- H - Over Machining
- I - Installation Gaps
- J - Installation Flushness
- M - Show through or telegraphing

Figure: 11-073

# North American Architectural Woodwork Standards - 3.1

## **S E C T I O N - 1 2**

# HISTORIC RESTORATION WORK

<b>Resources . . . . .</b>	<b><a href="#">423</a></b>
<b>Introductory . . . . .</b>	<b><a href="#">425</a></b>
<b>Recommendations . . . . .</b>	<b><a href="#">425</a></b>
<b>Specification Considerations . . . . .</b>	<b><a href="#">426</a></b>
<b>Design Resources . . . . .</b>	<b><a href="#">426</a></b>
<b>Compliance Requirements . . . . .</b>	<b><a href="#">427</a></b>
<b>Scope &amp; Default Stipulation . . . . .</b>	<b><a href="#">428</a></b>
<b>Basic Rules . . . . .</b>	<b><a href="#">428</a></b>
<b>Installation . . . . .</b>	<b><a href="#">430</a></b>

### Within CANADA

#### SUPPORT

- **GUIDE SPECIFICATIONS** – Available for download in interactive digital format, including specification wording for Quality Assurance Program (GIS) at: <http://awmac.com/guide-specifications>
- **CONSULTATION** – Contact any of the local chapters for more information on the NAAWS or any other Architectural Woodwork Questions you may have. See below for contact information.
- **SPECIFICATION REVIEW** – Contact any of the local chapters if you would like your specifications reviewed for compliance to the NAAWS.
- **MANUFACTURER STANDARDS QUESTIONNAIRE (MSQ)** – AWMAC Manufacturer members have the opportunity to have at least one member of their staff study and write the MSQ. The MSQ is a questionnaire on the NAAWS and policy and procedures of the GIS program. A list of Manufacturer members that have passed the MSQ is available at: <http://awmac.com/members>
- **SEMINARS AND PRESENTATIONS** – Contact your local chapter to arrange an informative presentation on any Architectural Woodwork topic. Some topic options – GIS, NAAWS, How to Specify Quality Architectural Woodwork...
- **TRADE SHOWS** – Contact your local chapter to arrange for AWMAC to have a booth or do a presentation on Architectural Woodwork.
- **CONFERENCE** – AWMAC has an annual conference held at unique venues across Canada. The conferences provide an opportunity to learn more about Architectural Woodwork and network with Suppliers and Manufacturers from across Canada. More information is available at: <http://awmac.com/>
- **EDUCATION PARTNERS** – Contact the local chapters to find out more information about support for local Colleges and Universities offering woodworking related courses and programs.

#### QUALITY ASSURANCE

- **GUARANTEE AND INSPECTION SERVICE (GIS)** – The GIS is a national program designed to ensure that project owners get value and quality for their investment by:
  - Supporting architects and design professionals to achieve project plans and specifications; and
  - Helping contractors avoid problems such as cost overruns, delays and loss of reputation.More information is available at: <http://awmac.com/gis>

- **INSPECTION SERVICE** – A GIS Certified Inspector will inspect specific areas of concern on a project for compliance to the NAAWS and provide a written report. Contact your local chapter for more information.
- **EXPERT OPINION** – An expert will be appointed to inspect specific areas of concern on a project and provide a written report. Contact your local chapter for more information.

#### AWMAC CHAPTERS

- AWMAC British Columbia Chapter, Vancouver BC  
<http://bc.awmac.com>
- AWMAC Northern Alberta Chapter, Edmonton Alberta  
<http://nab.awmac.com>
- AWMAC Southern Alberta Chapter, Calgary Alberta  
<http://sab.awmac.com>
- AWMAC Saskatchewan Chapter, Saskatoon Saskatchewan  
<http://sk.awmac.com>
- AWMAC Manitoba Chapter, Winnipeg Manitoba  
<http://mb.awmac.com>
- AWMAC Ontario Chapter, Toronto Ontario  
<http://on.awmac.com>
- AWMAC Quebec Chapter, Montreal Quebec  
<http://qc.awmac.com>
- AWMAC Atlantic Chapter, Halifax Nova Scotia  
<http://atl.awmac.com>

### Within UNITED STATES

#### SUPPORT

- **GUIDE SPECIFICATIONS** - Available in interactive digital format including quality control options at: <http://woodworkinstitute.com/publications/architectural-woodwork-standards/>
- **AIA SEMINARS** - The Woodwork Institute is a Registered Provider of the American Institute of Architects (AIA), and its Continuing Education System (CES) program, check out our offerings at: <http://woodworkinstitute.com/architectural-resources/aia-seminars/> 
- **CONSULTATION** - Contact one of our Directors of Architectural Services (DAS) at: <http://woodworkinstitute.com/about-us-2/about-us/>
- **ACCREDITED FABRICATORS AND INSTALLERS** - Our AMC's (Accredited Millwork Company) represents the best fabricators and installers in our industry, check them out at: <http://woodworkinstitute.com/membership-listing-2/> 
- **CERTIFIED INDUSTRY PROFESSIONALS** - Our CMP's (Certified Millwork Professionals) represent the knowledge base of our industry, check them out at: <http://woodworkinstitute.com/membership-listing-2/> 
- **MILLWORK INDUSTRY PARTNERS** - Our MIP's (Millwork Industry Partners) represent the best of our industries material suppliers, check them out at: <http://woodworkinstitute.com/membership-listing-2/> 
- **ACKNOWLEDGED PRODUCTS LISTING** - If it's listed here, you are assured it meets NAAWS minimum requirements, find the listing at: <http://woodworkinstitute.com/acknowledged-product-listing/> 
- **CABINET DESIGN SERIES (CDS)** - Eliminate the need to include casework elevations in your architectural drawings, check out the CDS system in NAAWS "Design Resources" and access the cad files at: <http://woodworkinstitute.com/architectural-resources/cabinet-design-series/>

#### QUALITY ASSURANCE

- **BIDDER QUALIFICATION** - A discipline of bidder pre-qualification wherein your specifications protect you and your customer from the unknown: To be eligible to bid or negotiate this job, the subcontractor must be a Woodwork Institute Accredited Millwork Company (AMC) in good standing.   
<http://woodworkinstitute.com/architectural-resources/quality-assurance>
- **CERTIFIED COMPLIANCE PROGRAM (CCP)** - A discipline of quality control used in conjunction with NAAWS providing an unbiased means of ensuring conformance to a project's plans and specifications. CCP, together with the use of the desired Grade(s) in the specifications, informs all parties of the design professional's expectations, without bidder discrimination.   
<http://woodworkinstitute.com/services/certified-compliance-program>
- **MONITORED COMPLIANCE PROGRAM (MCP)** - A discipline of quality affirmation used in conjunction with the NAAWS which provides ongoing reviews/inspections of a project from its beginning through completion, ensuring strict conformance to the design intent throughout the millwork fabrication and installation process.   
<http://woodworkinstitute.com/services/monitored-compliance-program/>
- **CERTIFIED SEISMIC INSTALLATION PROGRAM (CSIP)** - A standalone seismic assurance option which can be specified in conjunction with or without CCP or MCP, offering design professionals and project owners specific use of WI's seismic casework pre-approvals from California's Office of Statewide Health Planning and Development (OSHPD) without additional engineering costs and/or requirements, assuring proper backing has been installed in the walls when and where required.   
<http://woodworkinstitute.com/services/certified-seismic-installation-program/>

# SECTION 12

## Historic Restoration Work

## introductory information

### INTRODUCTION

The United States Department of the Interior (<http://doi.gov/>), the National Park Service (<http://nps.gov/>), and the Historic Sites and Monuments Board of Canada (<http://parkscanada.gc.ca/>) publish documents related to work under their jurisdiction. The most recent publications from these entities will provide valuable information for the design professional and the woodwork fabrication, finishing, and installation.

The rationale and intent of this section is to assist in compliance with the U.S. Secretary of the Interior's "STANDARDS FOR THE TREATMENT OF HISTORIC PROPERTIES (The Standards) with Guidelines for Preserving, Rehabilitation, Restoring, and Reconstructing Historic Buildings (The Guidelines)" or the *STANDARDS AND GUIDELINES FOR THE CONSERVATION OF HISTORIC PLACES IN CANADA* which spell out requirements such as:

- The historic character of a property will be retained and preserved. The removal of distinctive materials or alterations of features, spaces, and spatial relationships that characterize a property will be avoided.
- Each property will be recognized as a physical record of its time, place, and use. Changes that create a false sense of historical development, such as adding conjectural features or elements from other historic properties, will not be undertaken.
- Changes to property that have acquired historic significance in their own right will be retained and preserved. Distinctive materials, features, finishes, and construction techniques or examples of craftsmanship that characterize a historic property will be preserved.
- Deteriorated historic features will be repaired rather than replaced. Where the severity of deterioration requires replacement of a distinctive feature, the new feature will match the old in design, color, texture, and, where possible, materials. Replacement of missing features will be substantiated by documentary and physical evidence.

- Chemical or physical treatments, if appropriate, will be undertaken using the gentlest means possible. Treatments that cause damage to historic properties will not be used.
- New additions, exterior alterations, or related new construction will not destroy historic materials and spatial relationships that characterize the property. The new work shall be differentiated from the old and will be compatible with the historic materials, features, size, scale, proportion, and massing to protect the historic integrity of the property and its environment.
- New additions and adjacent or related new construction will be undertaken in such a manner that if they are removed in the future, the essential form and integrity of the historic property and its environment will be unimpaired.
- Acceptable requirements of lumber and/or sheet products used within this woodwork product section are established by Sections 3 and 4, unless otherwise modified herein.
- Contract documents, furnished by the design professional, shall clearly indicate or delineate all material, fabrication, installation, and applicable building code/regulation requirements.

Quality assurance can be achieved by adherence to these standards and will provide the owner a quality product at competitive pricing. Working with a WI Certified Millwork Professional (CMP) and the WI Accredited Millwork Company (AMC) they represent to provide your woodwork will help ensure the understanding and performance of the quality level required. Illustrations in this Section are not intended to be all inclusive, other engineered solutions may be acceptable. In the absence of specifications; methods of fabrication are the manufacturer's choice. The design professional, by specifying compliance to these standards increases the probability of receiving the product quality expected.

### RECOMMENDATIONS



- **IF FIELD FINISHED, INCLUDE IN THE DIVISION 09 OF THE SPECIFICATIONS:**
  - **BEFORE FINISHING**, all exposed portions of woodwork shall have handling marks or effects of exposure to moisture removed with a thorough, final sanding over all surfaces of the exposed portions using an appropriate grit sandpaper, and shall be cleaned before applying sealer or finish.
  - At **CONCEALED SURFACES** - Architectural woodwork that may be exposed to moisture, such as those adjacent to exterior concrete walls, etc., shall be primed.
- **REVIEW** the GENERAL portion of Sections 3 and 4 for an overview of the characteristics and the minimum acceptable requirements of lumber and/or sheet products that might be used herein.
- **STRUCTURAL MEMBERS**, grounds, in wall blocking, backing, furring, brackets, or other anchorage which becomes an integral part of the building's walls, floors, or ceilings, required for the installation of architectural woodwork are not to be furnished or installed by the architectural woodwork manufacturer or installer.
- **EXPOSED SURFACES** shall include those defined within Sections 6 - 11, as applicable.
- **SEMI-EXPOSED SURFACES** shall include those delineated within Sections 6 - 11, as applicable.
- **CONCEALED SURFACES** shall include those define within Sections 6 - 11, as applicable.

### SPECIFICATION CONSIDERATIONS



#### • SPECIFIC REQUIREMENTS FOR:

- Flame spread ratings.
- Special code compliance.

#### • QUALITY ASSURANCE OPTIONS:

##### Within CANADA

- **AWMAC's GUARANTEE AND INSPECTION SERVICE (GIS)** - See NAAWS's Resources page and/or <http://awmac.com/gis>
- **AWMAC's INSPECTION SERVICE** - See NAAWS's Resources page and/or <http://awmac.com/gis>
- **AWMAC's EXPERT OPINION SERVICE** - See NAAWS's Resources page and/or <http://awmac.com/gis>

##### Within UNITED STATES

- **WI'S AMC BIDDER PRE-QUALIFICATION** - See NAAWS's Resources page and/or <http://woodworkinstitute.com/architectural-resources/quality-assurance>
- **WI'S CERTIFIED COMPLIANCE PROGRAM (CCP)** - See NAAWS's Resources page and/or <http://woodworkinstitute.com/services/certified-compliance-program>
- **WI'S MONITORED COMPLIANCE PROGRAM (MCP)** - See NAAWS's Resources page and/or <http://woodworkinstitute.com/services/monitored-compliance-program/>
- **WI'S CERTIFIED SEISMIC INSTALLATION PROGRAM (CSIP)** - See NAAWS's Resources page and/or <http://woodworkinstitute.com/services/certified-seismic-installation-program/>

### RESOURCES AND REFERENCES

**Museums with period rooms** - There are many historic houses around the country which are open to the public. Eighteenth Century homes such as Gunston Hall in VA, and Drayton Hall, near Charleston, SC, along the Eastern Seaboard and Neoclassical houses as one moves West. There are museums with period rooms as well. The Metropolitan Museum in New York, the Philadelphia Museum of Art, and Colonial Williamsburg are only a few.

**Publications** - Dover Publications, Inc., 31 East Second Street, Mineola, NY 11501.

Dover Publications has an incomparable listing of books which, for the most part, are reprintings of older publications; from Andrea Palladio's Four Books of Architecture to Augustus Charles Pugin's Gothic Ornament as well as handbooks and specialized subjects.

One invaluable Dover handbook is Illustrated Dictionary of Historic Architecture by Cyril M. Harris. It is from Harris that the definitions and many of the illustrations in the Glossary have been used with permission.

Three others which offer good illustrations are:

- Colling, James K. *Medieval Decorative Ornament*, New York, (Reprint of 1874 edition); Dover Publications, Inc. 1995
- Griesbach, C.B. *Historic Ornament: A Pictorial Archive*, New York, Dover Publications, Inc., 1975.
- Speltz, Alesander. *The Styles of Ornament*, (Reprint of German Edition of 1906), New York, Dover Publications, Inc., 1959.

Several books explaining in detail the orders of architecture are:

- Adam, Robert. *Classical Architecture: A Comprehensive Handbook to the Tradition of Classical Style*, New York: Harry N. Abrams, Inc., Publishers, 1990.
- Chitham, Robert. *The Classical Orders of Architecture*, New York: Rizzoli International Publications, Inc., 1985 (may be out of print).
- Ware, William R. *The American Vignola: A Guide to the Making of Classical Architecture*, New York: Dover Publications, Inc., 1994.

A definitive history of architecture is:

- Fletcher, Sir Banister. *A History of Architecture on the Comparative Method*, 20th edition ed., Dan Cruickshank and Andrew Saint, Oxford: Architectural Press, 1996.

For carving classical architectural elements: Wilbur, Frederick. *Carving Architectural Detail in Wood: the Classical Tradition*, Lewes, UK: Guild of Master Craftsmen Publications, Ltd. 2000.

### DESIGN RESOURCES



Is a perpetually expanding, web based resource of pictures, videos, illustrations, ideas and design concepts for inspiring thought and design creativity - assessable at: <http://naaws-design-resources.com>

Relative to this Section, offerings will include::

- Restorations

# SECTION 12

## Historic Restoration Work

GENERAL/PRODUCT/INSTALLATION

compliance requirements

### INCLUDING: Stripping, Repairs, and Finishing

#### 12.1 BASIC CONSIDERATIONS

- 1 **GRADE**
- 1.1 Because of the nature of historic woodwork, a specific grade classification is not applicable to this section.
- 2 **ACCEPTABLE REQUIREMENTS** of lumber and/or sheet products used within this woodwork product section are established by Sections 3 and 4, unless otherwise modified herein.
- 3 **CONTRACT DOCUMENTS** shall govern if in conflict with these standards.
- 4 **AESTHETIC COMPLIANCE** requirements apply only to surfaces visible after manufacture and installation.

#### 12.1 BASIC CONSIDERATIONS (continued)

- 5 Historic woodwork restoration, including stripping, repairs, reconstruction, materials, new fabrication, installation, and finishing, shall be of a **SINGLE SOURCE RESPONSIBILITY**.
- 6 **INDUSTRY PRACTICES**
- 6.1 **STRUCTURAL MEMBERS**, grounds, in wall blocking, backing, furring, brackets, or other anchorage that becomes an integral part of the building's walls, floors, or ceilings, that are required for the installation of architectural woodwork are not furnished or installed by the architectural woodwork manufacturer or installer.
- 6.2 **WALL, CEILING**, and/or opening variations in excess of 1/4" (6.4 mm) or **FLOORS** in excess of 1/2" (12.7 mm) in 144" (3658 mm) of being plumb, level, flat, straight, square, or of the correct size are not acceptable for the installation of architectural woodwork, nor is it the responsibility of the installer to scribe or fit to tolerances in excess of such.
- 6.3 **PRIMING** of architectural woodwork is not the responsibility of the manufacturer and/or installer, unless the material is being furnished pre-finished.

# SECTION 12

## Historic Restoration Work

GENERAL/**PRODUCT**/INSTALLATION

**compliance requirements**

### 12.2 SCOPE

1 All restoration, fabrication, installation, and finishing of all existing and/or new historic architectural woodwork.

### 2 TYPICAL INCLUSIONS

2.1 Shall include those delineated within Sections 6 - 11, as applicable.

### 3 TYPICAL EXCLUSIONS

3.1 Shall include those delineated within Sections 6 - 11, as applicable.

### 12.3 DEFAULT STIPULATION

1 If not otherwise specified or indicated in the contract documents, all specified or detailed, all work shall match existing. 

1.1 It is the responsibility of the manufacturer to observe the project before bid and match all materials for species, grain, and overall appearance.

### 12.4 RULES

1 The following rules shall govern unless a project's contract documents require otherwise.

2 These rules are intended to provide a well defined degree of control over a project's quality of materials, workmanship, or installation.

3 **ERRATA**, published at <http://-errata.com>, shall take precedence over these rules, subject to their date of posting and a project's bid date. 

### 12.4.4 Basic General Rules

1 **AESTHETIC** grade rules apply only to exposed and semi-exposed surfaces visible after installation.

2 **FIRST CLASS WORKMANSHIP** is required in compliance with these standards. 

### 12.4.5 Basic Material Rules

1 **WOOD** shall match the species, grain, general pattern, and cut of existing, similar, and/or adjacent woodwork, and shall so be identified by the designer.

2 Shall **COMPLY** with **SECTIONS 3 - 11**, as applicable.

3 **MEMBERS** shall be of the same profile and dimension as existing; however, they may be glued up to achieve this.

4 **DEFECTS**, either natural or manufactured, shall not exceed those permitted by the contract documents.

### 12.4.6 Basic Machining Rules

1 Shall **COMPLY** with **SECTIONS 6 - 11**, as applicable.

2 **MACHINE** new and replacement woodwork to dimensions, profiles, and details to match existing.

3 **EXISTING MOLDINGS**, when hand made and not necessarily uniform in profile, replacement moldings shall be profiled to an agreed representative sample.

# SECTION 12

## Historic Restoration Work

GENERAL/PRODUCT/INSTALLATION

## compliance requirements

12.4.7 Basic Assembly Rules	
1	Shall <b>COMPLY</b> with <b>SECTIONS 6 - 11</b> , as applicable.
2	<b>PLYWOOD BACKING</b> , if approved, may be used in the fabrication of built up panel assemblies, door and/or window frames, and stacked base trim, provided the exposed profile and configuration matches existing.

12.4.8 Repair Rules	
1	<b>MATCH EXISTING</b> for recommended methods of repair by governing authorities.
2	At <b>TRANSPARENT FINISH</b> , be made with wood of the same species, grade, cut, color tone, and grain pattern.
3	<b>CARPENTRY METHODS</b> shall be the same as exhibited in the existing work.
4	<b>FASTENERS</b> shall be nonferrous, and: 1 Dissimilar metals shall be isolated from one another.
5	<b>WOOD PATCHES</b> of boat and/or diamond shape shall be used so as to minimize those joint surfaces at 90 degrees to the member's grain direction.

12.4.9 Stripping Rules	
1	<b>COATING STRIPPERS</b> shall be environmentally approved, and: 2 <b>BEFORE STRIPPING</b> procedures begin, all surfaces shall be tested (with the process and results recorded) to provide the least intrusive and damaging methods, and: 2 1 Approval by the design professional or conservator is required for the selected method. 2 2 Heat based methods of coating removal are permitted, provided the recommendations found in the National Park Service - Preservation Brief 10 Exterior Paint Problems On Historic Woodwork are followed or as allowed by the Historic Sites and Monuments Board of Canada.
3	<b>COMPLETELY REMOVE existing finish</b> using multiple applications of stripper and hand scrapers without gouging, splintering, or otherwise damaging sound wood.
4	<b>STRIPPING RESIDUALS</b> shall be thoroughly removed, including wax. 1 <b>STRIPPED SURFACES</b> shall be tested for evidence of acid and alkali, and: 1 1 All stripped surfaces found not to be pH neutral shall be neutralized and retested. 1 2 A written summary report, including before and after pH levels, shall be submitted to the design professional.
5	<b>SAND</b> all surfaces by hand with steel wool and the appropriate grit sandpaper to remove all signs of raised grain.
6	<b>SEAL</b> all exposed surfaces with an approved sanding sealer.

12.4.10 Finishing Rules	
1	Shall <b>COMPLY</b> with <b>SECTIONS 5</b> as modified by the plans and specifications.
2	<b>REQUIRE</b> use of applications and techniques best suited to match the existing and/or desired finish.

# SECTION 12

## Historic Restoration Work

### GENERAL/PRODUCT/INSTALLATION

### compliance requirements

#### 12.5 PREPARATION AND QUALIFICATION REQUIREMENTS

1 **CARE, STORAGE, and BUILDING CONDITIONS** shall be in compliance with the requirements set forth in Section 2 of these standards.

1.1 Severe damage to the woodwork can result from noncompliance. The manufacturer and/or installer of the woodwork shall not be held responsible for damage that might develop by not adhering to the requirements.

#### 2 **CONTRACTOR IS RESPONSIBLE FOR**



2.1 Furnishing and installing structural members, grounds, in wall or ceiling blocking, backing, furring, brackets, or other anchorage required for architectural woodwork installation that becomes an integral part of walls, floors, or ceilings to which architectural woodwork shall be installed.

2.1.1 In the absence of contract documents calling for the contractor to supply the necessary blocking/backing in the wall or ceilings, either through inadvertence or otherwise, the architectural woodwork installer shall not proceed with the installation until such time as the in wall or ceiling blocking/backing is installed by others.

2.1.2 Preparatory work done by others shall be subject to inspection by the architectural woodwork installer and may be accepted or rejected for cause prior to installation.

2.1.2.1 **WALL, CEILING,** and/or opening variations in excess of 1/4" (6.4 mm) or **FLOORS** in excess of 1/2" (12.7 mm) in 144" (3658 mm) of being plumb, level, flat, straight, square, or of the correct size are not acceptable for the installation of architectural woodwork, nor is it the responsibility of the installer to scribe or fit to tolerances in excess of such.

#### 12.5 PREPARATION AND QUALIFICATION REQUIREMENTS (continued)

2.2 Installation site being properly ventilated, protected from direct sunlight, excessive heat and/or moisture, and that the HVAC system is functioning and maintaining the appropriate relative humidity and temperature.

2.3 Priming the architectural woodwork in accordance with the contract documents prior to its installation.

2.3.1 If the architectural woodwork is factory finished, priming by the factory finisher is required.

#### 3 **INSTALLER IS RESPONSIBLE FOR**



3.1 Having adequate equipment and experienced craftsmen to complete the installation in a first class manner.

3.2 Checking all architectural woodwork specified and studying the appropriate portions of the contract documents, including these standards and the reviewed shop drawings, to familiarize themselves with the requirements of the Grade specified, understanding that:

3.2.1 For transparent finish, special attention needs to be given to the color and grain of the various woodwork pieces to ensure they are installed in compliance to match existing.

3.2.2 Installation site is properly ventilated, protected from direct sunlight, excessive heat and/or moisture, and that the HVAC system is functioning and maintaining the appropriate relative humidity and temperature.

3.3 Verification that installation site is properly ventilated, protected from direct sunlight, excessive heat and/or moisture, and that the HVAC system is functioning and maintaining the appropriate relative humidity and temperature.

3.4 Verification that required priming of woodwork has been completed by others before woodwork is installed.

3.5 Verification that woodwork has been acclimated to the field conditions for a minimum of 72 hours before installation is commenced.

3.6 Woodwork specifically built or assembled in sequence for match of color and grain is installed to maintain that same sequence.

# SECTION 12

## Historic Restoration Work

### GENERAL/PRODUCT/INSTALLATION

### compliance requirements

#### 12.6 RULES

- 1 The following rules shall govern unless a project's contract documents require otherwise.
- 2 These rules are intended to provide a well defined degree of control over a project's quality of materials, workmanship, or installation.
- 3 **ERRATA**, published at <http://-errata.com>, shall take precedence over these rules, subject to their date of posting and a project's bid date.



12.6.4 Basic General Rules	
1	<b>AESTHETIC</b> grade rules apply only to exposed and semi-exposed surfaces visible after installation.
2	<b>MATCH</b> of <b>EXISTING</b> installation methods is required, in:
2 1	Compliance with Sections 3 - 11, as applicable.
3	Where new materials are required to be distressed to blend seamlessly with original, mock-ups shall be approved by the design professional or conservator before proceeding.
4	<b>GROUND, BUCKS, or HANGING SYSTEMS</b> shall be installed plumb and true.
5	<b>TRANSPARENT</b> finished woodwork shall be installed:
5 1	Well matched for color and grain.
5 1 1	Sheet products shall be compatible in color with solid stock.
5 1 2	Adjacent sheet products shall be well matched for color and grain.
5 2	Installer shall pay special attention to the color and the grain of the various trim pieces to ensure they are installed in compliance with Premium Grade.
6	<b>REPAIRS</b> are allowed, provided they are neatly made and inconspicuous when viewed at 24" (610 mm).
Continues next column ▼	

#### 12.6.4 Basic General Rules

##### ▲ From previous column

7 **INSTALLER FABRICATION** or **MODIFICATIONS** shall comply to the general, material, machining, and assembly rules within the Product portion of this section and the applicable finishing rules in Section 5.

8 **EQUIPMENT CUTOUTS**, including electrical and plumbing, shall be cut out by the installer, provided templates are furnished prior to installation, and:

8 1 Shall be neatly cut and properly sized to be covered by standard cover plates or rosettes.

8 2 In **HPDL** or **SOLID SURFACE** shall have a minimum 1/4" (6.4 mm) radius at inside corners.

9 **FIRST CLASS WORKMANSHIP** is required in compliance with these standards.



**Applicable TESTS, may be found in Sections 6 - 11; however, these tests are only applicable to the exposed and semi-exposed portions of installed millwork products.**



# North American Architectural Woodwork Standards - 3.1

## APPENDIX

<b>Introduction . . . . .</b>	<b><a href="#">433</a></b>
<b>Reference Directory &amp; Listing . . . . .</b>	<b><a href="#">434</a></b>
<b>Code Sources . . . . .</b>	<b><a href="#">437</a></b>
<b>Adhesive Guidelines . . . . .</b>	<b><a href="#">438</a></b>
<b>Specific Gravity/Weight of Hardwoods . . . . .</b>	<b><a href="#">439</a></b>
<b>Joinery Details . . . . .</b>	<b><a href="#">441</a></b>
<b>Chemical &amp; Stain Resistance (SEFA) . . . . .</b>	<b><a href="#">443</a></b>
<b>Casework Integrity (SEFA) . . . . .</b>	<b><a href="#">445</a></b>
<b>Refinishing / Refacing / Refurbishing . . . . .</b>	<b><a href="#">450</a></b>
<b>Cabinet Design Series (CDS) . . . . .</b>	<b><a href="#">451</a></b>
<b>Conversion Tables . . . . .</b>	<b><a href="#">471</a></b>

### INTRODUCTION

This **APPENDIX** is provided as additional resources to the manufacturer, design professional, educator, user, or certifying organization and is only part of the standards (compliance requirements) when referenced. For your convenience where referenced it is flagged by the following icon:



### CONTINUING EDUCATION

---

**AIA** - American Institute of Architects  
**AIBD** - American Institute of Building Design  
**BHMA** - Builders Hardware Manufacturers Association  
**CRA** - California Redwood Association  
**IDC** - Interior Design of Canada  
**IIDA** - International Interior Design Association  
**RAIC** - Royal Architectural Institute of Canada

### STANDARDS & REGULATION

---

**ANSI** - American National Standards Institute  
**ARE** - Association for Retail Environments  
**ASID** - American Society of Interior Designers  
**AWI** - Architectural Woodwork Institute  
**AWIQCC** - Quality Certification Corporation  
**AWMAC** - Architectural Woodwork Manufacturers Association of Canada  
**BIFMA** - Business + Institutional Furniture Manufacturers Association  
**CPA** - Composite Panel Association  
**CSC** - Construction Specifications Canada  
**CSI** - Construction Specifications Institute  
**DHI** - The Door and Hardware Institute  
**HPVA** - Hardwood Plywood & Veneer Association  
**ICC** - International Code Council  
**IWPA** - International Wood Products Association  
**NFPA** - National Fire Protection Association  
**NHLA** - National Hardwood Lumber Association  
**NIST** - National Institute of Standards & Technology  
**SEFA** - Scientific Equipment & Furniture Association  
**SFI** - Sustainable Forest Initiative  
**UL** - Underwriters' Laboratories  
**WI** - Woodwork Institute  
**WWPA** - Western Wood Products Association

### MANUFACTURING

---

**AF&PA** - American Forest & Paper Association  
**AHFA** - American Home Furnishings Alliance  
**NAM** - National Association of Manufacturers  
**NEMA** - National Electrical Manufacturers Association  
**WDMA** - Window & Door Manufacturers Association

### TESTING AND GRADING

---

**APA** - The Engineered Wood Association  
**ASTM** - American Society for Testing and Materials  
**ITS** - Intertek Testing Services/Warnock Hersey

### SUSTAINABLE BUILDING

---

**CaGBC** - Canada Green Building Council  
**FSC** - Forest Stewardship Council - U.S.  
**Green Globes:**  
USA - The Green Building Initiative  
Canada - ECD Energy and Environment  
**Rainforest Alliance**  
**SAW** - Sustainable Architectural Woodwork  
**SFI** - Sustainable Forestry Initiative Inc.  
**TFF** - Tropical Forest Foundation  
**USGBC** - U.S. Green Building Council

### SPECIALIZED PRODUCT

---

**KCMA** - Kitchen Cabinet Manufacturers Association  
**LMA** - Laminating Materials Association, Inc.  
**MMPA** - Moulding and Millwork Producers Association  
**NHLA** - National Hardwood Lumber Association  
**WDMA** - Window & Door Manufacturers Association  
**WRCLA** - Western Red Cedar Lumber Association

**AF&PA** - American Forest & Paper Association  
1111 19th Street NW, Suite 800  
Washington, DC 20036  
Ph: 800-878-8878 - Fax: 202-463-2700  
<http://afandpa.org>

**AHFA** - American Home Furnishings Alliance  
Box HP-7  
High Point, NC 27261  
Ph: 336-884-5000 - Fax: 336-884-5303  
<http://ahfa.us>

**AIA** - American Institute of Architects  
1735 New York Avenue NW  
Washington, DC 20006  
Ph: 800-242-3837 - Fax: 202-626-7547  
<http://aia.org>

**AIBD** - American Institute of Building Design  
529 14th Street, NW, Suite 750  
Washington, DC 20045  
Ph: 800-366-2423 - Fax: 855-204-0293  
<http://aibd.org>

**ANSI** - American National Standards Institute  
25 West 23<sup>rd</sup> Street, 4<sup>th</sup> Floor  
New York, NY 10036  
Ph: 212-642-4900 - Fax: 212-398-0023  
<http://ansi.org>

**APA** - The Engineered Wood Association  
7011 South 19th Street  
Tacoma, WA 98466  
Ph: 253-565-6600 - Fax: 253-565-7265  
<http://apawood.org>

**ARE** - Association for Retail Environments  
4651 Sheridan Street, Suite 407  
Hollywood, FL 33021-3657  
Ph: 954-893-7300 - Fax: 954-893-7500  
<http://nasfm.org>

**ASID** - American Society of Interior Designers  
608 Massachusetts Avenue NE  
Washington, DC 20002-6006  
Ph: 202-546-3480 - Fax: 202-546-3240  
<http://asid.org>

**ASTM** - American Society for Testing and Materials  
100 Barr Harbor Drive  
West Conshohocken, PA 19428-2959  
Ph: 610-832-9585 - Fax: 610-832-9555  
<http://astm.org>

**AWI** - Architectural Woodwork Institute  
46179 Westlake Drive, Suite 120  
Potomac Falls, VA 20165  
Ph: 571-323-3636 - Fax: 571-323-3630  
<http://awinet.org>

**AWIQCC** - Quality Certification Corporation  
46179 Westlake Drive, Ste. 120  
Potomac Falls, VA 20165  
Ph: 571-222-6559 - Fax: 703-229-1211  
<http://http://awiqcc.org>

**AWMAC** - Architectural Woodwork Manufacturers Association of Canada  
Unit 02A 4803 Centre Street NW  
Calgary, AB T2E 2Z6  
Ph: 403-652-7685  
<http://awmac.com>

**BHMA** - Builders Hardware Manufacturers Association  
355 Lexington Avenue, 15th Floor  
New York, NY 10017  
Ph: 212-297-2122 - Fax: 212-370-9047  
<http://buildershardware.com>

**BIFMA** - Business + Institutional Furniture Manufacturers Association  
678 Front Avenue, NW Suite 150  
Grand Rapids, MI 49504-5368  
Ph: 616-285-3968 - Fax: 616-265-3765  
<http://bifma.org>

**CPA** - Composite Panel Association  
19465 Deerfield Avenue, Suite 306  
Leesburg, VA 20176  
Ph: 703-724-1128 - Fax: 703-724-1588  
<http://compositepanel.org>

**CRA** - California Redwood Association  
818 Grayson Road, Suite 201  
Pleasant Hill, CA 94523  
Ph: 925-935-1499 - Fax: 925-935-1496  
<http://calredwood.org>

**CSC** - Construction Specifications Canada  
120 Carlton Street, Suite 312  
Toronto, ON, M5A 4K2, Canada  
Ph: 416-777-2198 - Fax: 416-777-2197  
<http://csc-dcc.ca>

**CSI** - Construction Specifications Institute  
99 Canal Center Plaza, Suite 300  
Alexandria, VA 22314  
Ph: 800-689-2900 - Fax: 703-684-8436  
<http://csinet.org>

**DHI** - The Door and Hardware Institute  
14150 Newbrook Drive, Suite 200  
Chantilly, VA 20151-2223  
Ph: 703-222-2010 - Fax: 703-222-2410  
<http://dhi.org>

**FSC** - Forest Stewardship Council  
**USA:**  
212 Third Avenue North, Suite 445  
Minneapolis, MN 55401  
Ph: 612-353-4511 - Fax: 612-208-1565  
<http://fscus.org>  
**Canada:**  
70 The Esplanade, Suite 400  
Toronto, ON M5E 1R2  
Ph: 514-394-1137  
<http://fscCanada.org>

**GREEN GLOBES:**  
**USA:**  
The Green Building Initiative  
2104 SE Morrison,  
Portland, Oregon 97214  
Ph: 877-424-4241 - Fax: 503-961-8991  
<http://thegbi.org>  
**Canada:**  
ECD Energy and Environment  
165 Kenilworth Avenue  
Toronto, ON M4L 3S7  
Ph: 416-699-6671  
<http://greenglobes.com>

**HPVA** - Hardwood Plywood & Veneer Association  
1825 Michael Faraday Drive  
Reston, VA 20190  
Ph: 703-435-2900 - Fax: 703-435-2537  
<http://hpva.org>

**ICC** - International Code Council  
500 New Jersey Avenue NW, 6th Floor  
Washington, DC 20001-2070  
Ph: 888-422-7233 - Fax: 202-783-2348  
<http://iccsafe.org>

**IDC** - Interior Design of Canada  
C 536-43 Hanna Avenue  
Toronto, Ontario, M6K 1X1, Canada  
Ph: 416-649-4425 - Fax: 416-921-3660  
<http://idcanada.org>

**IIDA** - International Interior Design Association  
13-122 Merchandise Mart  
Chicago, IL 60654-1104  
Ph: 312-467-1950 - Fax: 312-467-0779  
<http://iida.org>

**ITS** - Intertek Testing Services

Ph: 800-967-5352

<http://intertek.com>

**IWPA** - International Wood Products Association

4214 King Street West

Alexandria, VA 22302

Ph: 703-820-6696 - Fax: 703-820-8550

<http://iwpaewood.org>

**KCMA** - Kitchen Cabinet Manufacturers Assoc.

1899 Preston White Drive

Reston VA 20191-5435

Ph: 703-264-1690 - Fax: 703-620-6530

<http://kcma.org>

**LEED®** - Leadership in Energy and Environmental Design

**USGBC** - U.S. Green Building Council

2101 L Street, NW, Suite 500

Washington, DC 20037

Ph: 800-795-1747 - Fax: 202-828-5110

<http://usgbc.org>

**CaGBC** - Canada Green Building Council

47 Clarence Street, Suite 202

Ottawa, ON K1N 9K1

Ph: 866-941-1184 - Fax: 613-241-4782

<http://cagbc.org>

**MMPA** - Moulding and Millwork Producers Association

507 First Street

Woodland, CA 95695

Ph: 530-661-9591 - Fax: 530-661-9586

<http://wrmmpa.com>

**NAM** - National Association of Manufacturers

733 10th Street, NW, Suite 700

Washington, DC 20001

Ph: 800-814-8468 - Fax: 202-637-3182

<http://nam.org>

**NEMA** - National Electrical Manufacturers Association

1300 North 17th Street, Suite 1752

Rosslyn, Virginia 22209

Ph: 703-841-3200 - Fax: 703-841-5900

<http://nema.org>

**FPA** - National Fire Protection Association

1 Batterymarch Park

Quincy, MA 02169-7471

Ph: 617-770-3000 - Fax: 617-770-0700

<http://nfpa.org>

**NHLA** - National Hardwood Lumber Association

6830 Raleigh-Lagrange Road

Memphis, TN 38184-0518

Ph: 901-377-1818 - Fax: 901-382-6419

<http://nhla.com>

**NIST** - National Institute of Standards & Technology

100 Bureau Drive, Stop 3460

Gaithersburg, MD 20899-3460

Ph: 301-975-6478 - Fax: 301-926-1630

<http://nist.gov>

**RAIC** - Royal Architectural Institute of Canada

330-55 Murray Street

Ottawa, Ontario, K1N 5M3, Canada

Ph: 613-241-3600 - Fax: 613-241-5750

<http://raic.org>

**SEFA** - Scientific Equipment & Furniture Association

65 Hilton Avenue

Garden City, NJ 11530

Ph: 877-294-5424 - Fax: 516-294-4765

<http://sefalabs.com>

**SFI** - Sustainable Forest Initiative, Inc.

**USA:**

2121 K Street, NW, Suite 750

Washington, DC 20037

Ph: 202-596-3450 - Fax: 202-596-3451

**Canada:**

1306 Wellington Street, Suite 400

Ottawa, ON K1Y 3B2

Ph: 613-747-2454 - Fax: 613-747-2453

<http://sfiprogram.org>

**RAINFOREST ALLIANCE**

233 Broadway, 28th Floor

New York, NY 10279

Ph: 212-677-1900 - Fax: 212-677-2187

<http://rainforest-alliance.org>

**SAW** - Sustainable Architectural Woodwork

PO Box 980248

West Sacramento, CA 95798-0248

Ph: 916-372-8242 - Fax: 916-372-9950

<http://sawcertified.org>

**TFF** - Tropical Forest Foundation

2121 Eisenhower Avenue, Suite 200

Alexandria, VA 22314

Ph: 703-518-8834 - Fax: 703-518-8974

<http://tropicalforestfoundation.org>

**UL** - Underwriters' Laboratories

333 Pfingsten Road

Northbrook, IL 60062-2096

Ph: 847-272-8800 - Fax: 847-272-8129

<http://ul.com>

**WDMA** - Window & Door Manufacturers Association

2025 M Street, NW, Suite 800

Washington DC, 20036-3309

Ph: 800-223-2301 - Fax: 847-299-1286

<http://wdma.com>

**WI** - Woodwork Institute

P.O. Box 980247

West Sacramento, CA 95798

Ph: 916-372-9943 - Fax: 916-372-9950

<http://woodworkinstitute.com>

**WRCLA** - Western Red Cedar Lumber Association

1501-700 West Pender Place 1, Business Building

Vancouver, BC, Canada V6C 1G8

Ph: 866-778-9096

<http://realcedar.org>

**WWPA** - Western Wood Products Association

Yeon Building, 522 SW Fifth Avenue

Portland, OR 97204-2122

Ph: 503-224-3930 - Fax: 503-224-3934

[www2.wwpa.org](http://www2.wwpa.org)

### PRESERVATIVE & WATER REPELLENT TREATMENTS

---

- **Within U.S.** - Governed under I.S. - 4, latest edition, as published by the Window and Door Manufacturers Association (WDMA), <http://wdma.com>, subject to any applicable EPA or local Air Quality Management District's restrictions on what may be used for the project location.
- **Within Canada** - Governed by the National Building Code of Canada, Section 3.8, Appendix A. Contact the National Research Council Canada at <http://nrc.ca>.

### FIRE RETARDANT COATINGS

---

Fire retardant coatings are typically subject to listing by an accredited testing laboratory and require a registration number for approval recognized by fire inspectors.

### FIRE CODES

---

- **Within the U.S.** - Governed by the International Code Council, Inc. (ICC), <http://iccsafe.org>, and the National Fire Protection Association (NFPA), <http://nfpa.org>
- **Within Canada** - Governed by the National Building Code of Canada, Section 3.8, Appendix A. Contact the National Research Council Canada at <http://nrc.ca>.

### ADA REQUIREMENTS

---

- **Within the U.S.** - Governed by the Federal Americans with Disabilities Act (ADA) subject to any applicable state or local requirements that might be more stringent for the project location. Contact the Access Board at <http://access-board.gov>
- **Within Canada** - Contact the National Building Code of Canada, Section 3.8, Appendix A. Contact the National Research Council Canada at <http://nrc.ca>.

### RATED FIRE DOOR ASSEMBLIES

---

- **Within U.S.** - Rated fire door assemblies are governed in accordance with the National Fire Protection Association's Publication NFPA 80, <http://nfpa.org>, "Standard for Fire Doors and Fire Windows," subject to any applicable state or local requirements that might be more stringent for the project location.
- **Within Canada** - Governance is by the National Building Code of Canada, Section 3.8, Appendix A, which can be reviewed at <http://nrc.ca>.

### BUILDING CODE REQUIREMENTS

---

- **Within the U.S.** - Governed by the International Building Code (IBC), <http://iccsafe.org>, subject to any applicable state or local requirements that might be more stringent for the project location.
- **Within Canada** - Governed by the National Building Code of Canada, Section 3.8, Appendix A. Contact the National Research Council Canada at <http://nrc.ca>.

### SEISMIC FABRICATION & INSTALLATION REQUIREMENTS

---

- **Within the U.S.** - Governed by the International Building Code (IBC), <http://iccsafe.org>, subject to any applicable state or local requirements that might be more stringent for the project location.
- **Within Canada** - Governed by the National Building Code of Canada, Section 3.8, Appendix A. Contact the National Research Council Canada at <http://nrc.ca>.

# APPENDIX

## adhesive usage guidelines

### BASIC REQUIREMENTS:

**ADHESIVE** used shall be for the intended purpose, applied in accordance with the manufacturer's instructions, and **DELAMINATION** or **SEPARATION** shall not occur, and:

- **LUMBER** shall conform to the requirements established in Section 3.
- **SHEET PRODUCTS** shall conform to the requirements established in Section 4.
- When intended for:
  - **NON-CLIMATE CONTROLLED INTERIOR** or **EXTERIOR USE**, it shall be **Type I Fully Waterproof (Exterior)** - Two Cycle Boil/Shear Test.
  - **CLIMATE CONTROLLED USE**, it shall be **Type II Water Resistant (Interior)** - Three Cycle Soak Test.

TYPE I FULLY WATER PROOF (Exterior)													
GENERIC NAME	MANUFACTURING					INSTALLATION					RIGID GLUE LINE	CHARACTERISTICS	
	Wood to Wood	HPDL to Wood		Glass to Wood & HPDL	Metal to Wood	Wood to Wood	HPDL to Wood		Glass to Wood & HPDL	Metal to Wood			
	All Work	Flat Work	Curved Work	All Work	All Work	All Work	Flat Work	Curved Work	All Work	All Work			
<b>EPOXY</b>	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Two part system; fully waterproof.
<b>PVA (Polyvinyl Acetate - Catalyzed)</b>	Yes	Yes	Yes	No	No	Yes	Yes	Yes	No	No	Yes	Yes	Fully waterproof.
<b>RESORCINOL RESIN</b>	Yes	Yes	Yes	No	No	Yes	Yes	Yes	No	No	Yes	Yes	Fully waterproof; purple glue line; two part system; limited pot life (3 hours).
TYPE II WATER RESISTANT (Interior)													
<b>CONTACT ADHESIVE</b>	No	Yes	Yes	No	No	No	Yes	Yes	No	No	No	No	Water resistant.
<p><b>NOTE:</b> curved reception walls or panel work shall incorporate a minimum 1-1/2" (38 mm) wide rigid glue line at spring line and all perimeter borders.</p>													
<b>HOT MELT * , **</b>	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Liquefies when heated; bonds in a liquid state; solidifies as it cools.
<p><b>NOTE:</b> HPDL edgebanding shall be primed before application.</p>													
<b>POLYURETHANE Reactive (PUR) * , **</b>	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Minimizes the visible glue line.
<p><b>NOTE:</b> HPDL edgebanding shall be primed before application.</p>													
<b>PVC (Polyvinyl Chloride) *</b>	Yes	Yes	Yes	No	No	Yes	Yes	Yes	No	No	Yes	Yes	Crystal clear; fast drying.
<b>UREA RESIN</b>	Yes	Yes	Yes	No	No	Yes	Yes	Yes	No	No	Yes	Yes	Mixes with water; must be clamped; 3 to 7 hours of drying time at 70° F (21.1° C).
<b>PANEL/ CONSTRUCTION ADHESIVE</b>	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Plastic epoxy base; liquid state; quick grab; difficult to remove; can be used to set adjustment screws in European type hinges.
<b>SILICONE</b>	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	No	No	Typical 5 hour cold cure.

\* Check adhesive manufacturer's rating for possible Type I rating.

\*\* Check with adhesive manufacturer for specific compatibility when bonding dissimilar materials.

# APPENDIX

## specific gravity and weight of hardwoods

SPECIES	SPECIFIC GRAVITY <sup>1</sup>	WEIGHT <sup>2</sup>
<b>ALDER, RED</b> Alnus rubra	.37	28
<b>ASH, WHITE</b> Average of 4 species	.54	41
<b>ASPEN</b> Populus tremuloides	.35	27
<b>AVODIRE</b> Turraeanthus africanus	n/a	36
<b>BASSWOOD</b> Tilia americana	.32	26
<b>BEECH</b> Fagus grandifolia	.56	45
<b>BIRCH, SWEET</b> Betula lenta	.60	46
<b>BIRCH, YELLOW</b> Betula alleghaniensis	.55	43
<b>BUBINGA</b> Guibourtia demeusil	n/a	55
<b>BUTTERNUT</b> Juglans cinerea	.36	27
<b>CATALPA, NORTHERN</b> Catalpa speciosa	.38	29
<b>CATIVO</b> Pioria copaifera	.40	29
<b>CHERRY, BLACK</b> Prunus serotina	.47	35
<b>CHESTNUT</b> Castanea dentata	.40	30
<b>COTTONWOOD, EASTERN</b> Populus deltoides	.37	28
<b>CUCUMBER TREE, YELLOW</b> Magnolia acuminata	.44	34
<b>CYPRESS (BALD CYPRESS)</b> Taxodium distichum	.42	32

SPECIES	SPECIFIC GRAVITY <sup>1</sup>	WEIGHT <sup>2</sup>
<b>DOGWOOD, FLOWERING</b> Cornus florida	.64	51
<b>EBONY (NIGERIAN)</b> Diospyros crassiflora	n/a	63
<b>ELM, AMERICAN</b> Ulmus Americana	.46	36
<b>SWEETGUM (RED AND SAP)</b> Liquidambar styraciflua	.44	34
<b>TUPELO, WATER</b> Nyssa aquatica	.46	35
<b>HACKBERRY</b> Celtis occidentalis	.49	37
<b>HICKORIES, TRUE</b> Average of 4 species	.65	51
<b>HOLLY</b> Ilex opaca	.50	40
<b>LIMBA</b> Terminalia superba	.45	34
<b>LOCUST, BLACK</b> Robinia pseudoacacia	.66	48
<b>MAHOGANY, AFRICAN</b> Khaya ivorensis	.43	31
<b>MAHOGANY, CUBAN</b> Swietenia mahogany	.57	41
<b>MAHOGANY, CENTRAL AMERICAN</b> Swietenia species	.45	32
<b>MAKORE</b> Tieghemella heckelii		40
<b>MAPLE, RED</b> Acer rubrum	.49	38
<b>MAPLE, SILVER</b> Acer saccharinum	.44	33
<b>MAPLE, SUGAR</b> Acer saccharum	.57	44

# APPENDIX

## specific gravity and weight of hardwoods


SPECIES	SPECIFIC GRAVITY <sup>1</sup>	WEIGHT <sup>2</sup>
<b>MYRTLE</b> Umbellularia Californica	.51	39
<b>NARRA</b> Pterocarpus indicus	.52	42
<b>OAK, COMMERCIAL RED</b> Average of 9 species	.56	44
<b>OAK, COMMERCIAL WHITE</b> Average of 6 species	.59	47
<b>ORIENTAL WOOD</b> Endiandro palmerstoni	n/a	44
<b>OSAGE ORANGE</b> Maclura pomifera	.76	n/a
<b>PADUAK (AFRICAN)</b> Pterocarpus soyauxii	n/a	43
<b>PADUAK (ANDAMAN)</b> Pterocarpus dalbergioides	.62	45
<b>PADUAK (BURMA)</b> Pterocarpus macrocarpus	.75	54
<b>PALDAO</b> Dracontomelum dao	.59	44
<b>PECAN</b> Carya illinoensis	.60	47
<b>PEARWOOD (EUROPEAN)</b> Purus communis	n/a	43
<b>PHILIPPINE HARDWOODS</b>		
<b>RED LAUAN</b> Shorea negrosensis	.40	36
<b>WHITE LAUAN</b> Pentacme contorta	n/a	36
<b>TANGUILE</b> Shorea polysperma	.53	39
<b>POPLAR, YELLOW (TULIPTREE)</b> Liriodendron tulipifera	.38	28
<b>PRIMAVERA</b> Cybistax donnell-smithii	.40	30

SPECIES	SPECIFIC GRAVITY <sup>1</sup>	WEIGHT <sup>2</sup>
<b>ROSEWOOD (BRAZIL)</b> Dalbergia nigra	n/a	50
<b>SAPELE</b> Entandrophragma cylindricum	.54	40
<b>SATINWOOD (EAST INDIAN)</b> Chloroxylon swietenio	.83	67
<b>SONORA (MANGGASINORO)</b> Shorea philippinensis	.42	31
<b>SYCAMORE</b> Platanus occidentalis	.46	35
<b>TEAK</b> Tectona grandis	.60	43
<b>TIGERWOOD</b> Lavoa klaineana	.45	34
<b>WALNUT, AMERICAN (BLACK)</b> Juglans nigra	.51	39
<b>WILLOW, BLACK</b> Salix nigra	.34	26
<b>ZEBRAWOOD</b> Microberlinia brazzavillensis	.62	48


The data for native species as furnished on this chart are from the U.S. Forest Products Laboratory's Technical Bulletin 158. <http://fpl.fs.fed.us>.

<sup>1</sup> Based on green volume and oven dry weight.


<sup>2</sup> Based on pounds per cubic foot at 12% moisture content.




**Butt**




**Tongue & Groove**




**Spline**




**Half Lap**




**Half Lap**




**Scarf**




**Finger**




**Doweled**




**Slotted Mortise & Tenon**




**Stub Mortise & Tenon**




**Blind Mortise & Tenon**




**Through Mortise & Tenon**




**Biscuit Spline**




**Pocket Screw**




**Plowed In**




**Rabbet**




**Lock Shoulder**




**Dovetail**




**Dovetail (French) Dado**




**Blind Dovetail**




**Dado**




**Dado, Blind Or Stopped**




**Dado, Blind Or Stopped**




**Miter**



**Splined Miter**



**Shoulder Miter**



**Lock Miter**

If chemical and/or stain resistance is a concern, users should consider the chemical and staining agents that might be used on or near casework or countertop surfaces. Common guidelines can be found in NEMA LD3 (latest edition), <http://nema.org> for chemical resistance and ASTM D3023 and C1378 (latest editions), <http://astm.org>, for stain resistance. Because chemical and stain resistance is affected by concentration, time, temperature, humidity, housekeeping, and other factors, it is recommended that actual samples are tested in a similar environment with those agents that are of concern.

In lieu of actual sample testing to evaluate the resistance a finish has to chemical spills, the SEFA 8-1999 (Scientific Equipment and Fixture Association <http://sefalabs.com>), standard list of 49 chemicals/concentrations, their required methods of testing, and their minimum acceptable results have been adapted for use in these standards as the means of establishing a minimum acceptable chemical resistance for exposed and semi-exposed surfaces where required by contract documents.

**REQUIREMENT:** Exposed horizontal surfaces, such as countertops, are required to pass a 24 hour exposure test, whereas exposed vertical surfaces and semi-exposed surfaces are required to pass a 1 hour exposure test.

**TEST PROCEDURE:** Obtain one sample panel measuring 14" x 24" (356 mm x 610 mm) and test for chemical resistance as described herein:

Place the panel on a flat surface, clean with soap and water, and blot dry. Condition the panel for 48 hours at 73° ±3° F (20° ±2° C) and 50% ±5% relative humidity. Test the panel for chemical resistance using the following 49 different chemical reagents by one of the following methods:

- **METHOD A** - Test volatile chemicals by placing a cotton ball saturated with reagent in the mouth of a 1 oz. (29.574 cc) bottle and inverting the bottle on the surface of the panel.
- **METHOD B** - Test non volatile chemicals by placing five drops of the reagent on the surface of the panel and covering with a 24 mm watch glass, convex side down.

For both of the above methods, leave the reagents on the panel for a period of:

- **One (1) hour** for exposed vertical surfaces and semi-exposed surfaces.
- **Twenty four (24) hours** for exposed horizontal surfaces such as countertops.

Wash off the panel with water, clean with detergent and naphtha, and rinse with deionized water. Dry with a towel and evaluate after 24 hours at 73° ±3° F (20° ±2° C) and 50% ±5% relative humidity using the following rating system:

**RESULT CLASSIFICATIONS:**

- **LEVEL 0** - No detectable change.
- **LEVEL 1** - Slight change in color or gloss.
- **LEVEL 2** - Slight surface etching or severe staining.
- **LEVEL 3** - Pitting, cratering, swelling, or erosion of coating; obvious and significant deterioration.

**ACCEPTANCE LEVEL:** Results will vary from product to product, and suitability for a given application is dependent upon the chemicals used in a given laboratory setting. Without contract documents requiring otherwise, an acceptable level of chemical and stain resistance for products requiring such in accordance with these standards and a project's contract documents shall be finishes with test results **SHOWING NO MORE THAN** four of the Level 3 Result Classifications.

	CHEMICAL REAGENT	TEST METHOD
1	Acetate, Amyl	A
2	Acetate, Ethyl	A
3	Acetic Acid, 98%	B
4	Acetone	A
5	Acid Dichromate, 5%	B
6	Alcohol, Butyl	A
7	Alcohol, Ethyl	A
8	Alcohol, Methyl	A
9	Ammonium Hydroxide, 28%	B
10	Benzene	A
11	Carbon Tetrachloride	A
12	Chloroform	A
13	Chromic Acid, 60%	B
14	Cresol	A
15	Dichlor Acetic Acid	A
16	Dimethylformamide	A
17	Dioxane	A
18	Ethyl Ether	A
19	Formaldehyde, 37%	A
20	Formic Acid, 90%	B
21	Furfural	A
22	Gasoline	A
22	Hydrochloric Acid, 37%	B
24	Hydrofluoric Acid, 48%	B
25	Hydrogen Peroxide, 3%	B

# APPENDIX

## chemical and stain resistance

	CHEMICAL REAGENT	TEST METHOD
26	Iodine, Tincture of	B
27	Methyl Ethyl Ketone	A
28	Methylene Chloride	A
29	Mono Chlorobenzene	A
30	Naphthalene	A
31	Nitric Acid, 20%	B
32	Nitric Acid, 30%	B
33	Nitric Acid, 70%	B
34	Phenol, 90%	A
35	Phosphoric Acid, 85%	B
36	Silver Nitrate, Saturated	B
37	Sodium Hydroxide, 10%	B
38	Sodium Hydroxide, 20%	B
39	Sodium Hydroxide, 40%	B
40	Sodium Hydroxide, Flake	B
41	Sodium Sulfide, Saturated	B
42	Sulfuric Acid, 33%	B
43	Sulfuric Acid, 77%	B
44	Sulfuric Acid, 96%	B
45	Sulfuric Acid, 77% and Nitric Acid, 70% - equal parts	B
46	Toluene	A
47	Trichloroethylene	A
48	Xylene	A
49	Zinc Chloride, Saturated	B

### CASEWORK INTEGRITY TESTING

BIFMA's (Business + Institutional Furniture Manufacturers Association, <https://www.bifma.org>) ANSI/BIFMA X5.9 (latest edition) requirements with the following additional enhancements:

- **Static Pull Test:**
  - A minimum horizontal, outward force of 300 lbs. applied to the end panel without noticeable joint separation.
- **Static Load Test:**
  - A minimum vertical, downward force of 300 lbs applied to the cabinet bottom.

OR

**SEFA's** (Scientific Equipment and Fixture Association, <http://sefalabs.com>) SEFA 8-1999 methods of testing and acceptable results have been adapted for use in these standards as the minimum acceptable level of integrity for casework conforming to all grades as follows:

- **TEST LISTING**
  - **Structural Integrity - Base Cabinet**
  - **Concentrated Load - Base Cabinet**
  - **Torsion - Base Cabinet**
  - **Base Submersion**
  - **Structural Integrity - Wall Cabinet**
  - **Door and Door Hinge Durability**
  - **Door Impact**
  - **Drawer Bottom Impact**
  - **Drawer Support**
  - **Drawer and Door Pull**
  - **Drawer Rolling Load**
  - **Shelf Load**
  - **Structural Integrity - Table**

#### SHELF TEST UNIT

Shelves, both fixed and/or adjustable, regardless of material or application, shall be tested using the following procedure. This is inclusive of shelves in wall cabinets, base cabinets, full height cabinets, wall mounted shelves, and free standing shelves.


#### TABLE TEST UNIT

Shall be 48" (1219 mm) long, 24" (610 mm) deep, and 36" (914 mm) high. A top of 1" (25.4 mm) thick medium density fiberboard shall be positioned on the table so that it will overhang the frame perimeter by 1" (25.4 mm), and its weight shall be included in the test as live load. Tables are represented by a large range of styles and designs, including free standing tables, desks, aprons mounted between two fixed areas (such as a wall or casework), mobile tables (free standing tables on wheels or casters), and mobile under counter units.

#### BASE CABINET TEST UNIT


Shall be 48" (1219 mm) wide, 36" (914 mm) high, and 22" (559 mm) deep with one full width drawer (approximately one fourth the height of the cabinet's face opening) and two doors. Cabinet shall be designed to provide unobstructed entry into the cabinet interior with the doors open and shall contain one adjustable shelf. For LABORATORY USE, the cabinet back shall be removable and tested with the cabinet back removed.

The cabinet shall be free standing, squared, and set level. A piece of 1" (25.4 mm) thick medium density fiberboard shall be positioned on the cabinet without glue or fasteners of any kind, of such dimensions that it will overhang the cabinet perimeter by 1" (25.4 mm), and its weight shall be included in the test as live load. Doors and the drawer should be free moving, and the door shall latch properly.




#### WALL CABINET TEST UNIT

Shall be 48" (1219 mm) wide, 36" (914 mm) high, and 12" (305 mm) deep with two swinging doors and one shelf, and shall be designed in such a way that when the doors are open, access to the cabinet is unobstructed.



### STRUCTURAL INTEGRITY TEST - BASE CABINET


- **CHALLENGES** the load bearing capability of a cabinet's construction.
- **PROCEDURE** - Load the cabinet top by using 2000 lbs. (907 kg) of solid steel bars stacked eight high and evenly spaced for a time period of 10 minutes, then unload the cabinet.



- **ACCEPTANCE LEVEL** - Cabinet shall have no signs of permanent failure. If used, inspect the levelers; any deformation shall not interfere with the function of the leveling system.

### CONCENTRATED LOAD TEST - BASE CABINET


- **CHALLENGES** the functional characteristics of the cabinet when subjected to a concentrated load on the center of the cabinet top.
- **PROCEDURE** - Using solid weights or 10 lb (4.53kg) sand bags, apply a total of 200 lbs (90.7 kg) to the top of the cabinet along the cabinet center-line. Operate the doors and the drawer.



- **ACCEPTANCE LEVEL** - Door and drawer operation shall be normal under condition of test load and there shall be no signs of permanent distortion to the front rail, cabinet joinery, doors, or the drawer after load is removed.

### TORSION TEST - BASE CABINET

- **CHALLENGES** the structural integrity of the cabinet construction when subjected to a torsional load.
- **PROCEDURE** - The cabinet shall be tested in its normal upright position, raised not less than 4" (101.6 mm) off the floor, and supported on both rear corners and one front corner. The area of support under the cabinet shall be located not more than 6" (152.4 mm) in from each supported corner. Secure the cabinet diagonally from the unsupported corner with seven solid steel bars (350 lbs [159 kg]) on the top of the cabinet to prevent overturning. Apply four solid steel bars (200 lbs [90.7 kg]) to the unsupported corner for a period of 15 minutes. Remove the weight, and place the cabinet on the floor in its normal upright position. Observe the cabinet joinery. Level the cabinet and measure the face and back of the cabinet across the diagonal corners.



- **ACCEPTANCE LEVEL** - When returned to the normal position, the operation of the cabinet shall be normal without any signs of permanent damage. The difference between the two measurements taken from measuring the diagonal corners shall be no more than 1/8" (3.2 mm).

### SUBMERSION TEST - BASE CABINET


**ONLY APPLICABLE TO casework specified for moisture resistant or laboratory use.**



- **CHALLENGES** the cabinet's resistance to standing water and is only applicable to cabinets whose bases are within 2" (50.8 mm) of the finished floor.
- **PROCEDURE** - The material thickness along the perimeter of the cabinet shall be measured on 6" (152.4 mm) increments. Record the thickness of the material to be submerged in water. Calculate the arithmetic mean of the data taken. Place the entire test cabinet in its upright position so that the cabinet is submerged in a pan filled with 2" (50.8 mm) of water. After 4 hours, remove the unit from the water and immediately measure the thickness of the material at the same points measured initially. Calculate the new arithmetic mean. After the unit has been allowed to dry, inspect for other damage.
- **ACCEPTANCE LEVEL** - The cabinet will show no signs of permanent deformation or deterioration. Any increase in thickness of the base material shall not exceed 4% of the initial mean measurements.

### STRUCTURAL INTEGRITY TEST - WALL CABINET


- **CHALLENGES** the strength of the back of the wall cabinet as well as the joinery of the cabinet and the function of the doors when the wall mounted unit is subjected to load.
- **PROCEDURE** - Using sand or shot bags weighing 10 lbs (4.5 kg) each, load the cabinet bottom, shelf, and top uniformly to a maximum of 200 lbs (90.7 kg) each, with the maximum load not exceeding 600 lbs (272 kg).



- **ACCEPTANCE LEVEL** - With weights in place, operate the doors through full travel to verify the normal operation of the doors. Remove the weights and operate the doors to verify normal operation. Verify that there is no significant permanent deflection of the cabinet top, cabinet back, cabinet bottom, or shelf. After the weights are removed, the cabinet shall show no permanent damage to the cabinet, cabinet bottom, or shelf.

### DOOR and DOOR HINGE DURABILITY TEST


- **CHALLENGES** the durability of the door and its hardware (hinge leaf, screws, etc.) to an applied load of 200 lbs (90.7 kg).
- **PROCEDURE** - Remove the shelf for this test. With the unit and top set, add sufficient weight to the top in order to prevent overturning. With the cabinet door open 90 degrees, hang a sling made up of two 100 lb (45.4 kg) weights (shot bags or solid weights) over the top of the door at a point 12" (305 mm) out from the hinge center line. Slowly move the door through the full cycle of the hinge, up to a 160 degree arc. Remove the weight, swing the door through its full intended range of motion, and close the door.



- **ACCEPTANCE LEVEL** - The open door shall withstand a load of 200 lbs (90.7 kg) when applied at a point 12" (305 mm) from the hinge center-line without significant permanent distortion that will cause binding of the door or hinges or that will adversely affect the operation of the catch.

### DOOR IMPACT TEST

- **CHALLENGES** the resistance of a 240 inch pound impact to the door face and is applicable only to cabinet doors that extend below the work surface, excluding glass doors.
- **PROCEDURE** - With the unit and top set, add sufficient weight to the top in order to prevent overturning. A 20 lb (9 kg) sand bag shall be suspended and dropped to provide an impact of 240 inch pounds at the center of the closed door.



- **ACCEPTANCE LEVEL** - After the test, the door and catch shall operate normally and show no signs of permanent damage.

### DRAWER BOTTOM IMPACT TEST



- **CHALLENGES** the resistance to impact of the drawer bottom and slide mechanism.
- **PROCEDURE** - Open the drawer to 13" (330 mm) of travel. Drop a 10 lb (4.5 kg) sand or shot bag from a height of 24" (610 mm) into the bottom of the drawer at the center of the width of the drawer and 6" (152 mm) back from the inside face of the drawer. Remove the sand or shot bag.
- **ACCEPTANCE LEVEL** - Operate the drawer through the full cycle. The drawer shall operate normally. Any deformation will not cause binding or interfere with the operation of the drawer.

### DRAWER SUPPORT TEST

- **CHALLENGES** the ability to support a point load given to the front of the drawer and will challenge the attachment of the drawer head to the drawer.
- **PROCEDURE** - With the unit and top set, add sufficient weight to the top in order to prevent overturning. Open the drawer to 13" (330 mm) of travel and hang 150 lbs (68 kg) from the drawer head at the center-line of the drawer for 5 minutes. Remove the weight and operate the drawer through the full cycle.
- **ACCEPTANCE LEVEL** - There shall be no interference with the normal operation of the drawer.

### DRAWER AND DOOR PULL TEST


- **CHALLENGES** the strength of the pull hardware.
- **PROCEDURE** - Pulls are to be installed in accordance with the manufacturer's practice, using the specified attaching hardware and method. Block the door and the drawer closed. Using a cable pulley and weight assembly, apply a force of 50 lbs (22.7 kg) perpendicular to each pull. Revise the setup to hang weight from each pull.



- **ACCEPTANCE LEVEL** - The pulls shall resist force and support weight without breakage. After completion of the test and removal of the weight, there shall be no significant permanent distortion. Some pull designs will require variations to set up apparatus. These pulls shall be tested in conformance to the applied pull forces.

### DRAWER ROLLING LOAD TEST

- **CHALLENGES** the strength of the drawer head, bottom, and back as a result of opening and closing the drawer with a rolling load.
- **PROCEDURE** - Position the drawer on a table at a 45 degree angle. Place a 2" (50.8 mm) diameter by 12" (305 mm) long steel rod (approximately 10 lbs [4.5 kg]) 13" (330 mm) from the target impact area (so that the rod will roll freely to impact the back) of the drawer. Subject the back to three impacts, and reverse the drawer to subject the front to three additional impacts.




- **ACCEPTANCE LEVEL** - The drawer shall show no signs (other than minor scratches and dents) of permanent damage. All joinery shall be intact, and the drawer, when replaced in the unit, shall operate normally. Minor scratches and dents are acceptable.

### SHELF LOAD TEST

- **CHALLENGES** the ability of a shelf and its mounting hardware to support normal loads.
- **PROCEDURE** - The shelf shall be mounted as designed. Measure the distance from the underside of the shelf to a reference point perpendicular to the center of the shelf. Using shot or sand bags weighing 10 lbs. (4.5 kg) each, uniformly load the shelf to a maximum of 200 lbs. (90.7 kg). Measure the deflection on the shelf by measuring the distance to the reference point and calculating the difference between the two measurements.
- **ACCEPTANCE LEVEL** - The maximum deflection shall be 1/180 of the span, not to exceed 1/4" (6.4 mm).

### TABLE STRUCTURAL INTEGRITY TEST

- **CHALLENGES** the table components to a normal load.
- **PROCEDURE** - Load the table top with an evenly distributed load of no less than 300 lbs (136 kg) for mobile, 600 lbs (272 kg) for free standing, and 2000 lbs (907 kg) for fixed. Include the weight of the working surface as a live load by using solid steel bars, each weighing 50 lbs (22.7 kg).



- **ACCEPTANCE LEVEL** - No structural breakage shall occur, and the apron rails shall not deflect more than 1/8" (3.2 mm). In the case of a table with a drawer, the deflection of the rail shall not interfere with the function of the drawer.

# APPENDIX

## casework refinishing/refacing/refurbishing - guidelines

### IN GENERAL

This type of work is typically required to be done in the field and without specific contract document requirements to the contrary:



- Will not update any seismic fabrication and/or installation deficiencies.
- Lead and/or toxic material abatement shall not be the responsibility of the woodwork manufacturer/installer.

### SPECIFICATIONS

Shall clearly indicate whether refinishing, refacing, refurbishing, or a combination thereof is required.

### ARCHITECTURAL PLANS

Shall clearly indicate all casework to be refinished, refaced, and/or refurbished. The casework elevations shall also indicate any unusual or special requirements (such as structural repair or component replacement).

It is the design professional's responsibility to specify any and all modifications required for code compliance.

Including the means, methods, and materials required to retrofit casework for IBC Title 24 or other national compliance code(s).

The requirement for reinstallation of existing casework (if needed to be removed), in a manner other than the original, shall be so specified.

If new or additional wall blocking is required, it shall be so specified and be the responsibility of the contractor.

All refinishing, refacing, and/or refurbishing of casework governed by these standards shall generally be in accordance with these standards as applicable, with the following exception:

- Repair or modification of existing casework shall be in compliance with accepted methods of joinery as contained in these standards.

The method of repair used shall be optional with the manufacturer/installer.

### REFINISHING

Can be as simple as the application of a new finish over the existing cabinet surfaces or as extensive as the removal of the existing finish, repair or patch of all physical defects, and the application of a new finish; however: does not include the replacement of hardware, unless so specified.

### REFACING

Is usually more involved and very field labor intensive, and existing surfaces, including doors, drawer fronts, cabinet face, and finished ends:

- **IF HPDL**, shall be removed with any damaged core areas repaired and core surface suitably prepared for proper adhesion of the new surface material. Or resurfaced with a laminate with a peel and stick adhesive especially formulated for resurfacing existing HPDL or LPDL surfaces.
- **IF PAINT**, shall be stripped to the original surface with any damaged areas repaired and resurfaced with the specified material.

Does not include the replacement of hardware, unless so specified.

### REFURBISHING

Includes either the refinishing or refacing of the exterior cabinet body, replacement of the cabinet doors and drawer fronts, and replacement of all exposed cabinet hardware, including hinges, pulls, catches, and locks; however:

- It does not include the repair or replacement of interior components such as shelves, drawer boxes, or drawer slides unless so specified.

New components, such as doors, drawer fronts, drawer boxes, and shelves, shall be compliant to these standards.

Gaps and tolerances shall match that of the existing casework within an elevation and within a room.

Hardware replacement for refurbished casework, or when specified to be included with refinishing or refacing, shall include door hinges, door and drawer pulls, and locks (keying requirement to be as specified).

Drawer slide replacement is not included unless specifically required in the contract documents.

Match of existing hardware is contingent on the availability of such from a manufacturer's current stock.

The method of repair or patching of tear outs used for proper hardware replacement shall be optional with the manufacturer/installer.

All work shall meet the requirements of first class workmanship.

# APPENDIX


## Cabinet Design Series (CDS)

CDS illustrations are provided to assist design professionals and casework users in selecting typical designs. These illustrations are not intended to limit or restrict creativity, or to be all inclusive. CDS files available at: <http://naaws-cds.com>

When utilizing the CDS numbering system, it is not necessary to show casework elevations in your contract documents. However, it is necessary to show a plan view with each CDS number indicated along with the width, height, and depth in inches or millimeters (example: 102-36"x 30"x 18" [102-914 mm x 762 mm x 457 mm]). Cabinet dimensions indicate the nominal outside dimension (floor to top of countertop for height and face of finished wall to face of cabinet door for depth). Manufacturers are permitted a tolerance of plus/minus 1/2" (12.7 mm) in width only.

When designs other than those provided for in the CDS system are desired, they may be indicated by selecting the CDS number most closely representing the desired design, followed by the letter "M" and a description or illustration of the design modification (example: 102M - 2 shelves - 36"x 30"x 18" [102M - 2 shelves - 914 mm x 762 mm x 457 mm] or 102M - no shelves -36"x 30"x 18" [102M - no shelves -914 mm x 762 mm x 457 mm]). It is suggested that a standard number/dimension convention similar to that shown below, is used.

If the CDS numbering system is used in conjunction with cabinet elevations on contract documents, the cabinet elevations shall govern on any conflict between the requirements of the elevation and the CDS number.



CDS cabinets are intended for **FRAMELESS CONSTRUCTION** with integral finished ends and scribes at wall to wall installations not exceeding 1-1/2" (38.1 mm) in width. Hardware and accessories shall be as provided for in these standards.

CDS are subdivided as follows:

- **Base Cabinets w/o Drawers**                      **100 Series**
- **Base Cabinets w/ Drawers**                      **200 Series**
- **Wall Hung Cabinets**                              **300 Series**
- **Tall Storage Cabinets**                              **400 Series**
- **Tall Wardrobe Cabinets**                              **500 Series**
- **Library Cabinets**                                      **600 Series**
- **Moveable Cabinets**                                  **700 Series**

### GENERAL NOTES:

- 100 or 200 Series cabinets may be converted into moveable cabinets by prefixing a "7" to the number. (Example: 7-102-36"x 30"x 18" [7-102-914 mm x 762 mm x 457 mm]).
- Moveable cabinets shall be equipped with adequate approved casters for the intended load capacity.
- CDS #'s 728, 729, 735, 736, 737, 738, and 739 require metal angle reinforced corners.
- Carts and rolling tall storage cabinets with doors, lacking any horizontal and/or vertical stabilizing dividers, require a diaphragm bottom; specifically CDS #'s 702, 712, 716, 722, 743,744, 746, 747, 750, and 751.
- Wardrobe cabinets (500 Series) with doors require a framed mirror on one door, and cabinets # 533 and 534 require a paper roller/cutter and slide out tilting paper shelves.
- Cart storage cabinets are required to have hardwood side guides, specifically CDS #'s 160, 161, and 162.
- Ceramics drying cabinets are required to have galvanized metal frame shelves with wire mesh, specifically CDS #'s 198 199, and 459.
- File drawers require full extension slides and a file hanging system, specifically CDS #'s 223, 224, 230, 231, 240, 242, 253, 255, 531, 532, and 533.
- Wardrobe cabinets are required to have a shelf, pole, and framed mirror (without pin tray) when closed with hinged doors, specifically CDS #'s 501, 511, 512, 522, 530, 531, 532, and 552.
- Wardrobe cabinets are required to have a roll paper dispenser/cutter, specifically CDS #'s 533 and 534.


**SPECIAL BASE CASEWORK HEIGHTS**, the following are recommended for various school grades, subject to ADA requirements:

- **Kindergarten - Grade 1**                      **24" (610 mm)**
- **Grades 2 - 3**                                      **27" (686 mm)**
- **Grades 4 - 6**                                      **30" (762 mm)**
- **Grades 7 - 9**                                      **33" (838 mm)**
- **Grades 10 and above**                              **36" (914 mm)**


# APPENDIX

## Cabinet Design Series (CDS)


### 100 SERIES - BASE CABINETS without DRAWERS




100




101




102




106




107




110




111




112




116




117




120



121




122




130




131




132




136



140  
Removable Back



141  
Removable Back




142  
Removable Back

AVAILABLE in Autodesk®, Revit®, DWG or DXF file format at [naaws-cds.com](http://naaws-cds.com)


# APPENDIX

## Cabinet Design Series (CDS)


### 100 SERIES - BASE CABINETS without DRAWERS (continued)




146  
Removable Back




148  
Removable Back




150




151




152




153  
Removable Base/Toe




154




154 B




154 C




155  
Removable Back




156  
Cart Storage




160  
Cart Storage




161




162  
Cart Storage




170




171




172



176




177




178

AVAILABLE in Autodesk®, Revit®, DWG or DXF file format at [naaws-cds.com](http://naaws-cds.com)


**100 SERIES - BASE CABINETS without DRAWERS** (continued)




**179**  
Retractable Towel Rack




**180**




**182**




**186**



**187**  
Sliding Tray & Lift Shelf




**188**




**189**  
Drawing Board Rack




**190**




**191**




**192**




**193**




**194**




**195**




**196**



**197**




**198**



**199**

**AVAILABLE** in Autodesk®, Revit®, DWG or DXF file format at [naaws-cds.com](http://naaws-cds.com)

### 200 SERIES - BASE CABINETS with DRAWERS



**AVAILABLE** in Autodesk®, Revit®, DWG or DXF file format at [naaws-cds.com](http://naaws-cds.com)


**200 SERIES - BASE CABINETS with DRAWERS** (continued)



270



271



272



290



291




292

**AVAILABLE** in Autodesk®, Revit®, DWG or DXF file format at [naaws-cds.com](http://naaws-cds.com)

# APPENDIX


## Cabinet Design Series (CDS)

### 300 SERIES - WALL HUNG CABINETS




**AVAILABLE** in Autodesk®, Revit®, DWG or DXF file format at [naaws-cds.com](http://naaws-cds.com)


**300 SERIES - WALL HUNG CABINETS** (continued)




336




340




341  
Open Back




342




343  
Open Back




350



351  
Open Back



352




353  
Open Back

**AVAILABLE** in Autodesk®, Revit®, DWG or DXF file format at [naaws-cds.com](http://naaws-cds.com)

# APPENDIX

## Cabinet Design Series (CDS)

### 400 SERIES - TALL STORAGE CABINETS




**AVAILABLE** in Autodesk®, Revit®, DWG or DXF file format at [naaws-cds.com](http://naaws-cds.com)

# APPENDIX

## Cabinet Design Series (CDS)

### 400 SERIES - TALL STORAGE CABINETS (continued)




**AVAILABLE** in Autodesk®, Revit®, DWG or DXF file format at [naaws-cds.com](http://naaws-cds.com)

# APPENDIX


## Cabinet Design Series (CDS)

### 400 SERIES - TALL STORAGE CABINETS (continued)



**AVAILABLE** in Autodesk®, Revit®, DWG or DXF file format at [naaws-cds.com](http://naaws-cds.com)


### 400 SERIES - TALL STORAGE CABINETS (continued)




446  
Hutch




447  
Hutch




448  
Hutch




449  
Hutch




454



459




460



461

**AVAILABLE** in Autodesk®, Revit®, DWG or DXF file format at [naaws-cds.com](http://naaws-cds.com)


**500 SERIES - WARDROBE CABINETS**




See General Notes

**AVAILABLE** in Autodesk®, Revit®, DWG or DXF file format at [naaws-cds.com](http://naaws-cds.com)


**500 SERIES - WARDROBE CABINETS** (continued)



**534**  
See General Notes



**540**




**541**



**552**  
Pole w/ Wall Hooks


**AVAILABLE** in Autodesk®, Revit®, DWG or DXF file format at [naaws-cds.com](http://naaws-cds.com)

**600 SERIES - LIBRARY CABINETS**




**AVAILABLE** in Autodesk®, Revit®, DWG or DXF file format at [naaws-cds.com](http://naaws-cds.com)


**600 SERIES - LIBRARY CABINETS** (continued)




**651**  
Book Cart



**654**




**664**




**671a**  
671b w/ Lateral Bracing




**672**




**673**  
Gate




**674**




**681**




**682 / 692**  
Magazine Rack



**683**




**684**



**693**  
Dictionary Stand


**AVAILABLE** in Autodesk®, Revit®, DWG or DXF file format at [naaws-cds.com](http://naaws-cds.com)

**700 SERIES - MOVEABLE CABINETS**



**AVAILABLE** in Autodesk®, Revit®, DWG or DXF file format at [naaws-cds.com](http://naaws-cds.com)

**700 SERIES - MOVEABLE CABINETS** (continued)




**AVAILABLE** in Autodesk®, Revit®, DWG or DXF file format at [naaws-cds.com](http://naaws-cds.com)

# APPENDIX

## Cabinet Design Series (CDS)

### 700 SERIES - MOVEABLE CABINETS (continued)



AVAILABLE in Autodesk®, Revit®, DWG or DXF file format at [naaws-cds.com](http://naaws-cds.com)


**700 SERIES - MOVEABLE CABINETS** (continued)




754



755



760  
Study Carrel



Typical Diaphragm Bottom Detail

**AVAILABLE** in Autodesk®, Revit®, DWG or DXF file format at [naaws-cds.com](http://naaws-cds.com)

# APPENDIX

## fraction/decimal/millimeter conversions

FRACTION	DECIMAL	MILLIMETER
1/64	0.01563	0.3969
1/32	0.03125	0.7938
3/64	0.04688	1.1906
1/16	0.06250	1.5875
5/64	0.07813	1.9844
3/32	0.09375	2.3813
7/64	0.10937	2.7781
1/8	0.12500	3.1750
9/64	0.14063	3.5719
5/32	0.15625	3.9688
11/64	0.17188	4.3656
3/16	0.18750	4.7625
13/64	0.20312	5.1594
7/32	0.21875	5.5563
15/64	0.23438	5.9531
1/4	0.25000	6.3500
17/64	0.26563	6.7469
9/32	0.28125	7.1438
19/64	0.29688	7.5406
5/16	0.31250	7.9375
21/64	0.32813	8.3344
11/32	0.34375	8.7313
23/64	0.35938	9.1281
3/8	0.37500	9.5250
25/64	0.39063	9.9219
13/32	0.40625	10.3188
27/64	0.42188	10.7156
7/16	0.43750	11.1125
29/64	0.45313	11.5094
15/32	0.46875	11.9063
31/64	0.48438	12.3031
1/2	0.50000	12.7000

FRACTION	DECIMAL	MILLIMETER
33/64	0.51563	13.0969
17/32	0.53125	13.4938
35/64	0.54688	13.8906
9/16	0.56250	14.2875
37/64	0.57813	14.6844
19/32	0.59375	15.0813
39/64	0.60938	15.4781
5/8	0.62500	15.8750
41/64	0.64063	16.2719
21/32	0.65625	16.6688
43/64	0.67188	17.0656
11/16	0.68750	17.4625
45/64	0.70313	17.8594
23/32	0.71875	18.2563
47/64	0.73438	18.6531
3/4	0.75000	19.0500
49/64	0.76563	19.4469
25/32	0.78125	19.8438
51/64	0.79688	20.2406
13/16	0.81250	20.6375
53/64	0.82813	21.0344
27/32	0.84375	21.4313
55/64	0.85938	21.8281
7/8	0.87500	22.2250
57/64	0.89063	22.6219
29/32	0.90625	23.0188
59/64	0.92188	23.4156
15/16	0.93750	23.8125
61/64	0.95313	24.2094
31/32	0.96875	24.6063
63/64	0.98438	25.0031
1	1.00000	25.4000

# APPENDIX

## miscellaneous conversions

▼ WHEN KNOWN ▼	▼ MULTIPLY BY ▼	▼ TO FIND ▼
Inches	2.54	Centimeters
Inches	25.4	Millimeters
Square Inches	6.452	Square Centimeters
Feet	30.48	Centimeters
Square Feet	.0929	Square Meters
Yards	.9144	Meters
Square Yards	.8361	Square Meters
Miles	1.6	Kilometers
Square Miles	2.59	Square Kilometers
Acres	.4047	Hectares
Ounces	28.349527	Grams
Pounds	.4536	Kilograms
Pressure	.0703	Bar
Radius	2	Diameter
Diameter	.5	Radius
Diameter	3.1416	Circumference
Diameter	.8862	Side of an Equal Square
Circumference	.31831	Diameter
Circumference	.15915	Radius
Circumference	.2821	Side of an Equal Square
Square of Diameter	.7854	Area of Circle
Square of Diameter	3.1416	Square of Sphere of Globe
Square of Circumference	.07958	Area of Circle
Square of Radius	3.1416	Area of Circle
▲ TO FIND ▲	▲ DIVIDE BY ▲	▲ WHEN KNOWN ▲

▼ WHEN KNOWN ▼	▼ MULTIPLY BY ▼	▼ TO FIND ▼
Fahrenheit	0.556 after subtracting 32	Celsius
Celsius	1.8 and add 32	Fahrenheit

# North American Architectural Woodwork Standards - 3.1

# GLOSSARY

Introduction . . . . .	<a href="#">474</a>
Terminology Definitions . . . . .	<a href="#">474</a>

# GLOSSARY

## INTRODUCTION

This Glossary provides definitions of words and is intended to clarify terms and usage with regard to specific application within the standards.



**DESIGN RESOURCES** includes an additional Historic Woodwork Glossary, listing terms and definitions relating to ornamental woodwork and architectural moldings.



**(+/-):** see Plus/Minus

**1 MIL:** A mil is 1/1000" or 0.001" (0.00254 mm).

**ABRASION RESISTANCE:** Resistance to friction wear.

**ABS:** Abbreviation for "Acrylonitrile butadiene styrene," a synthetic decorative coating or edgebanding.

**ACRYLIC LACQUER:** In finishing, a high quality clear system for finishing furniture.

**ADHESION:** The degree of attachment between a finish step and the underlying material.

**ADHESIVE:** A substance capable of bonding materials together by surface attachment. It is a general term and includes all cements and glues.

**ADHESIVE, COLD PRESS AND HOT PRESS:** "Cold press" means no heat is applied to the press while in operation. "Hot press" means heat is applied at the time the press is in operation.

## ADHESIVE, TYPE I FULLY

**WATERPROOF:** Forms a bond that will retain practically all of its strength when occasionally subjected to a thorough wetting and drying; bond shall be of such quality that specimens will withstand shear and the two cycle boil test specified in ANSI/HPVA HP (latest edition).

## ADHESIVE, TYPE II WATER

**RESISTANT:** Forms a bond that will retain practically all of its strength when occasionally subjected to a thorough wetting and drying; bond shall be of such quality that specimens will withstand the three cycle cold soak test specified in ANSI/HPVA HP (latest edition).

**ADJACENT:** When one surface is directly next to or touching another surface with no other surfaces in between the two.

**ADJACENT PANEL:** When one panel surface is within 6" (152 mm) of another panel surface on the same plane within a room.

**ADJUSTABLE SHELVES:** Generally accomplished through the use of multiple holes with either plastic or metal pins to hold the shelves. Some metal or plastic shelf standards are still in use. The adjustment method is the manufacturer's option unless otherwise specified.


**AGRIFIBER:** Refers to core products made from the residual material from a grain crop similar in composition to particleboard. Shall meet or exceed the performance properties of ANSI A208.1 or 2 <http://compositepanel.org>

**AIR DRIED:** Seasoned by controlled exposure to the atmosphere, in the open or under cover, without artificial heat.



**ALL HEART:** Of heartwood throughout; free of sapwood.

**ANCHOR STRIPS:** Used to mount woodwork; other names include nailers, mounting cleats, hanging strips, and wall cleats.



**ANCHORAGE FASTENER:** Installation screws used to attach casework to walls. Screw requirements are as described in section 10.



**ANILINE DYE:** A synthetic dye often used to impart enhanced clarity of color to wood.


**ANTIMICROBIAL SURFACE:** A surface containing an antimicrobial agent that inhibits or reduces the ability of microorganisms to grow on the surface of the material. As regulated by:

US - EPA Registered - <http://epa.gov>.

Canada - Health Canada - <http://hc-sc.gc.ca>

# GLOSSARY

**APRON:** For purposes of these standards, means a horizontal trim member below the countertop typically at knee spaces or open sink areas.




## ARCHITECTURAL WOODWORK:

Custom woodworking, so varied in design and complexity that it becomes difficult to define; specified for special applications and functions by design professionals and created by manufacturers. It includes all exterior and interior woodwork exposed to view in a finished building (except specialty items of flooring, shingles, exposed roof decking, siding, structural wood trusses and rafters, and overhead type doors), including all exposed wood, plywood, high and low pressure decorative laminates, and doors. Items made of other materials are included only if called for in the specifications. Finishing may be included if specified. Site installation may also be included if specified.


**ARRIS:** In architecture, a sharp edge formed by the meeting of two flat or curved surfaces.

**ARTICULATED JOINT:** In architectural paneling, joint details that allow for field variations.

**ASSEMBLY-1:** A wall mounted method of decorative laminate back and end splash countertop construction.



**ASSEMBLY-2:** A deck mounted method of back and end splash countertop construction.




**B-STAGE CURING:** Is a process that utilizes heat or UV light to remove the majority of solvent from a substance, thereby allowing application to be "staged." In between application, coating and curing can be held for a period of time, without sacrificing performance.


**BACK:** The side reverse to the face of a panel, or the poorer side of a panel in any Grade of plywood calling for a face and a back.

**BACK PRIMING:** A finish coating typically applied to concealed surfaces of architectural woodwork to minimize moisture penetration.

**BACK VENEER:** The veneer placed on the semi-exposed or concealed face of a veneered panel construction to balance the construction. Also, the side reverse to the face of a panel, or the poorer side of panel in any Grade calling for a face and a back.




**BACKED OUT:** Wide, shallow area machined on the back surface of wide solid moldings and some frames. Allows the item to span irregular surfaces.




**BACKER MATERIAL:** A sheet product with performance properties determined by its material composition. Because material composition types vary then backer sheet types accordingly vary in performance properties. Which backer sheet material is used should be based on overall product demands. When used as a balancing sheet a backer must have performance properties equal to an opposing surface with a similar adhesive and application process as the face sheet. (See BALANCING SHEET) Otherwise a backer sheet need not have performance properties equal to an opposing surface.

# GLOSSARY

**BALANCED CONSTRUCTION:** To achieve balanced construction, panels should be absolutely symmetrical from the center line; i.e., use materials on either side that contract or expand, or are moisture permeable, at the same rate. Balanced finishing coats on the back of veneered panels are also highly recommended. Balancing sheet requirements for decorative laminate fabrication vary with the product. Doors and panels should have a balancing sheet on the back side and be applied in the same machine direction. Countertops or cabinet members, on the other hand, require some form of backer material.



**BALANCED MATCH:** A common term in book matching that uses two or more leaves of uniform width on the face of a panel, wherein the two outermost leaves in a panel or face are of the same width.



**BALANCING SHEET:** A sheet product with performance properties equal to an opposing surface. A balancing sheet is laminated to the secondary surface of a core with the same adhesive and application process as the primary surface material (i.e., face material) to maintain the panel's flatness. Typically a balance sheet is used to balance a panel that will not be captured or restrained (e.g., doors).

**BALANCING SPECIES:** A species of similar density to achieve balance by equalizing the rate of moisture absorption or emission.


**BALUSTER:** One of the repetitive vertical members below a handrail or guardrail to provide support and a functional barrier.




**BALUSTRADE:** The assembly of newels, balusters, and rails that make up the safety barrier along balconies and open sides of stairways and ramps.



**BANDED:** Usually refers to the application of a similar material to the edge of a built up member to cover or hide the otherwise exposed core, such as on plywood.



**BARBER POLE:** An effect in book matching of veneers resulting from tight and loose sides of veneers causing different light reflections when finished.




**BARK POCKET:** Bark around which normal wood has grown.



**BEDDING IN PUTTY:** Glazing whereby a thin layer of putty or bedding compound is placed in the glass rabbet, and the glass is inserted and pressed onto this bed.

**BEVEL:** A machine angle other than a right angle; e.g., a 3 degree bevel, which is equivalent to a 1/8" (3.2 mm) drop in a 2" (50.8 mm) span. Also, in flooring or wall paneling, a V shaped groove between strips, planks, or panels.

**BEVELED EDGE:** An edge of the door that forms an angle of less than 90 degrees with the wide face of the door, such as a 3 degree beveled edge.




# GLOSSARY

**BIRD'S EYE:** Decorative figure due to small conical depressions in the outer annual rings, which appear to follow the same contour in subsequent growth rings, probably for many years. Rotary slicing cuts the depressions crosswise, exposing a series of circlets called bird's eyes.



**BISCUIT SPLINE:** A concealed oblong shaped spline used to join adjacent members.




**BLEACHING:** The chemical process used to remove color or whiten solid wood or wood veneered panels. This process may be used to lighten an extremely dark wood or to whiten a lighter colored wood. Most woods do not turn completely white when bleached.

**BLEEDING:** When the color of one coating material migrates up through the finishing layer to the succeeding coat, imparting some of its characteristics.

**BLENDING:** Color change that is detectable but that does not detract from the overall appearance of the panel.


**BLIND CORNER:** The space created by abutting cabinets at an approximate 90 degree angle.



**BLISTERING:** The formation of bubbles on the surface of a coating, caused by trapping air or vapors beneath the surface; an area where veneer does not adhere; a figure resembling an uneven collection of rounded or blister like bulges caused by the uneven contour of annual growth rings.




**BLOCKING:** Commonly understood as the wooden support material placed within or upon gypsum board and plaster walls to support casework.




**BLUEPRINT SEQUENCED PANELS AND COMPONENTS:** Each panel for walls and components (e.g., desk, doors) is custom manufactured to the specific size required. All panels are balance matched and sequenced to the adjacent panels.

**BLUSHING:** The whitish, cloud like haze that occurs in fast drying finishes, especially lacquer, when they are sprayed in very humid conditions. Blushing is most often due to moisture (water vapor) trapped in the film or to resin precipitating out of solution.

**BOARD:** A piece of lumber before gluing for width or thickness.




**BOARD FOOT:** A unit of measurement of lumber represented by a board 12" (305 mm) long, 12" (305 mm) wide, and 1" (25.4 mm) thick. Abbreviated BF, Bf, bf. When stock is less than 1" (25.4 mm) thick, it is usually calculated as if it were a full 1" (25.4 mm) thick.




# GLOSSARY

**BOOK MATCH:** Matching between adjacent veneer leaves on one panel face. Every other piece of veneer is turned over so that the adjacent leaves are “opened” as two pages in a book. The fibers of the wood, slanting in opposite directions in the adjacent leaves, create a characteristic light and dark effect when the surface is seen from an angle.



**BOW:** A deviation, flatwise, from a straight line drawn from end to end of a piece. It is measured at the point of greatest distance from the straight line.



**BOX STRINGER:** See closed stringer.


**BUCKS:** In wall blocking used for the installation of door/window jambs and other woodwork in conjunction with metal framing and/or block walls.



**BUGLE HEAD SCREW:** Is similar to countersunk; however, there is a smooth progression from the shaft to the angle of the head, similar to the bell of a bugle. This term is generally used in referencing drywall screws.



**BULLNOSE:** A convex, rounded shape such as the front edge of a stair step.




**BURL:** A figure created by abnormal growth or response to injury that forms an interwoven, contorted, or gnarly mass of dense woody tissue on the trunk or branch of the tree. Burls are usually small and characterized by eye like markings surrounded by swirls and clusters of distorted tissues. The measurement of the burl is the average of the maximum and minimum dimensions of the burl.




**BURL, BLENDING:** A swirl, twist, or distortion in the grain of the wood which usually occurs near a knot or crotch but does not contain a knot and does not contain abrupt color variation. A blending burl is detectable at 72" (1829 mm) as a swirl or roundel.




**BURL, CONSPICUOUS:** A swirl, twist, or distortion in the grain of the wood which usually occurs near a knot or crotch. A conspicuous burl is associated with abrupt color variation and/or a cluster of small dark piths caused by a cluster of adventitious buds.




**BUTCHER BLOCK:** Generally refers to face laminate hardwoods (usually Maple) forming a work surface in which the edge grain is exposed to wear.



**BUTT JOINT:** A joint formed by square edged surfaces (ends, edges, faces) coming together; end butt joint, edge butt joint.




**CABINET, BASE:** A cabinet less than 72" (1829 mm) in height that either rests or is attached to the floor and is either free standing (and finished all sides) or mounted and secured structurally to the wall.




# GLOSSARY

**CABINET FACE:** The outermost surface of a cabinet unit that allows access to the interior of the cabinet unit, including door faces, drawer faces or false front faces. Does not include ends, sides, top, bottom or back. If the cabinet is an open cabinet the cabinet face is the outermost front exposed edges of the cabinet box.




**CABINET LINER:** As used within these standards, shall describe 0.020" (0.5 mm) high pressure decorative laminate (HPDL).

**CABINET, TALL STORAGE:** A cabinet 72" (1829 mm) or more in height that either rests or is attached to the floor and is either free standing (and finished all sides) or mounted and secured structurally to the wall.




**CABINET UNIT:** A single manufactured case typically consisting of two ends, a top, a bottom, and may include back, stretchers, anchor strips, shelves, doors, drawer fronts, drawers, dividers, and hardware.


**CABINET, WALL:** A cabinet that is mounted and secured structurally to a wall without resting on the floor.



**CANTILEVER:** A projecting structure that is attached or supported at only one end, such as an extended countertop.



**CANT STRIP:** A triangular shaped or beveled strip of material used to ease the transition from a horizontal plane to a vertical plane.



**CAPTURED:** A component whose perimeter is mechanically fastened or joined to other components so that it's not allowed to warp independent of those attached components.

**CASEWORK:** Base and wall cabinets, display fixtures, and storage shelves. The generic term for both "boxes" and special desks, reception counters, nurses stations, and the like. Generally includes the countertops and work surfaces. As normalized within NAAWS through:

ANSI/KCMA 161.1 - <http://www.kcma.org>

IANSI/BIFMA X5.9 - <http://www.bifma.org>

SEFA 8 - <http://sefalabs.com>

**CATALYZED:** In finishing, an ingredient added to a basic product to provide additional performance characteristics.


**CATHEDRAL GRAIN:** A grain appearance characterized by a series of stacked and inverted "V" or cathedral type of spring-wood (early wood)/ summer-wood (late wood) patterns common in plain sliced (flat cut) veneer.



**CAULK:** Either the action of making a watertight or airtight seal between two adjacent surfaces by filling the area between the surfaces with a sealant, or the sealant itself.



**CENTER MATCHED:** A form of veneer matching that uses two or more even numbered leaves, matched with a joint occurring in the center of the panel. A small amount of the figure is lost.



# GLOSSARY

**CHAIN OF CUSTODY:** A method of tracking the handling of a wood product from forest to delivery of a finished product. Each step of transportation and manufacturing is documented for verification of the handling process.

**CHAMFER:** To cut away the edge where two surfaces meet in an exterior angle, leaving a bevel at the junction.



**CHARACTER MARK:** As an element of nature, a distinctive feature in a hardwood surface produced by minerals and other elements that are absorbed as a tree grows.

**CHARACTERISTICS:** The natural irregularities found in wood, whether solid or veneered. Their acceptance is a function of each particular Grade.

**CHATTER:** Lines appearing across the panel or board at right angles to the grain, giving the appearance of one or more corrugations resulting from bad setting of sanding equipment or planing knives.



**CHECKING:** Cracks that appear in a finishing

film due to lack of cohesion, often caused by too heavy of a coat being applied or a poor grade of finish being used. Also called cold checking.



**CHECKS:** Small slits running parallel to the grain of wood, caused chiefly by strains produced while drying and/or seasoning.



**CHIP MARKS:** Shallow depressions or indentations on or in the surface of dressed lumber caused by shavings or chips getting embedded in the surface during dressing.



**CLIMATE:** Conditions found inside or outside a building that include temperature, humidity and barometric pressure.


**CLIMATE CONTROLLED:** Referring to the inside areas of a building where heat or air conditioning systems are installed and actively used for environmental controls.

## CLOSED GRAIN AND OPEN GRAIN:

The size and distribution of the cellular structure of the wood influences the appearance and uniformity. Open grain hardwoods, such as Elm, Oak, Ash, and Chestnut, are “ring porous” species. These species have distinct figure and grain patterns. Close grain hardwoods, such as Cherry, Maple, Birch, and Yellow Poplar, are “diffuse porous” species. Most North American diffuse porous woods have small, dense pores resulting in less distinct figure and grain. Some tropical diffuse porous species (e.g., Mahogany) have rather large pores.



**CLOSED STRINGER:** In stairwork, a stringer that boxes in the treads and risers.



# GLOSSARY


**COFFER:** A sunken, decorative panel in a ceiling.



**COMB GRAIN:** A quality of rift cut veneer with exceptionally straight grain and closely spaced growth increments resembling the appearance of long strands of combed hair.



**COMBINATION CORE:** Panels are a hybridization of veneer and composition cores offering the advantages of both. Typically these cores have internal layers which are constructed of three or five plies of veneer or a center layer of wafer board (randomly oriented wafers) or other wood fiber which are sandwiched between thin laminations of a composite product like MDF, particleboard, hardboard, etc. Typically these products result in stronger, lighter weight, dimensionally stable panels with increased screw holding ability and superior surface flatness. Shall meet or exceed the performance characteristics of ANSI A208.1 or 2 <http://compositepanel.org>



## COMPATIBLE FOR COLOR AND GRAIN:

For purposes of these standards, means members shall be selected so that:

- Lighter than average color members will not be adjacent to darker than average color members, and there will be no sharp contrast in color between the adjacent members, and
- The grain of adjacent members shall not vary widely or be dissimilar in grain, character, and figure.

**COMPATIBLE SPECIES:** For purposes of these standards, means different species which are able to exist in a harmonious combination of color and grain.

**CONCEALED SURFACE:** Surface not normally visible after installation.


**CONSPICUOUS:** Detectable; readily visible with the naked eye when observed in normal light at a distance stated within these standards.

**CONTACT ADHESIVE:** Normally used for bonding high pressure decorative laminates to a core.


**CONTRACTOR:** A general contractor, normally holding the legal agreement for construction of an owner's building project.

**CONVERSION VARNISH:** In finishing, a class of coatings that are tough and exhibit excellent resistance to household chemicals.

**COPE/COPEd:** To cut the end of one member to match the profile of another molded member.



**CHORD SEGMENTATION:** The process of cutting short lengths of straight molding and joining them around a curve core which is not permitted under these standards.



**CORE:** The material (typically, veneer, lumber, particleboard, medium density fiberboard, or a combination of these) on which an exposed surface material (typically, veneer or decorative laminate) is applied.




**CRATERING:** The formation of small depressions in a finish, sometimes called fish eye. Often caused by the contamination of the finish material or the core with silicone, oil, or other substances.




# GLOSSARY

**CREEP:** The deflection over time of loaded or unloaded adjustable shelves, which fluctuates with temperature, humidity and load stress.

**CROOK:** A deviation, edgewise, from a straight line drawn from end to end of a piece. It is measured at the point of greatest distance from the straight line.



**CROSSBANDING:** A ply placed between the core and face veneer in 5 ply construction, or a ply placed between the back and face of a 3 ply skin in 7 ply construction. When the crossbanding has directional grain, it is placed at right angles to the grain of the face veneer. When used with laminate face doors, crossbanding may consist of more than one ply.



**CROSS BAR:** Irregularity of grain resembling a dip in the grain running at right angles, or nearly so, to the length of the veneer.




**CROSS GRAIN:** Applied to wood in which the grain is not running lengthwise of the material in one direction. The irregularity is due to interlocked fiber, uneven annual rings, or to the intersection of branch and stem.



**CROTCH:** Comes from the portion of a tree just below the point where it forks into two limbs. The grain is crushed and twisted, creating a variety of plume and flame figures, often resembling a well formed feather. The outside of the block produces a swirl figure that changes to full crotch figure as the cutting approaches the center of the block.



**CUP:** A deviation in the face of a piece from a straight line drawn from edge to edge of that piece. It is measured at the point of greatest distance from the straight line.



**CURB STRINGER:** See closed stringer.

**CURING:** The complete drying of a finish to the ultimate development of its properties.


**CURLY:** Figure that occurs when the fibers are distorted, producing a wavy or curly effect in the lumber or veneer. Primarily found in Maple or Birch.




**CUSTOM GRADE:** The middle or normal Grade in both material and workmanship, and intended for high quality, conventional work.

**CUT HEART:** See split heart.

**DADO, BLIND, OR STOPPED JOINT:** A dado that is not visible when the joint is completed.



**DADO JOINT:** A rectangular groove across the grain of a wood member into which the end of the joining member is inserted; also a housed joint. Variations include "mortise and tenon" and "stopped or blind dado" joints.



# GLOSSARY

**DECAY:** Disintegration of wood due to the action of wood destroying fungi; “doze”, “rot”, and “unsound wood” mean the same as “decay.”




**DECORATIVE COMPOSITE PANELS:**

For the purposes of these standards, a thermally fused panel flat pressed from a thermoset polyester or melamine resin impregnated paper (minimum 30%); see low pressure decorative laminates.

**DEFECT:** Fault that detracts from the quality, appearance, or utility of the piece. Handling marks and/or grain raising due to moisture shall not be considered a defect.

**DEFECT, OPEN:** Open joints, knotholes, cracks, loose knots, wormholes, gaps, voids, or other openings interrupting the smooth continuity of the wood surface.


**DEFLECTION:** When weight is applied to a flat panel supported at two opposing ends in a horizontal position, such as a shelf, and the weight causes the shelf surface to become concave. Deflection is affected by the weight applied as well as the shelf core and finish materials.



**DELAMINATION:** Separation of plies or layers of wood or other materials through failure of the adhesive joint. When one lamination element is solid, veneer or composite wood and has not been subject to adverse environmental conditions (humidity & temperature) beyond its intended use, the absence of grain tear out shall be deemed an adhesive failure.

**DESIGN PROFESSIONAL:** An architect, interior designer, specification writer, or other individual qualified by virtue of education and/or training to provide services for the design of buildings, interiors, and furnishings.

**DIE WALL:** A millwork assembly, typically vertical, that includes sub framing and a finish face on one or more sides. Die walls are commonly used at reception desks, nurse stations and low walls dividing areas within a larger room. They are typically self supported or attached to floors or walls. A die wall typically allows other millwork items to be attached, such as countertops, transaction countertops and casework.



**DIMENSION LUMBER:** Material that is precut in width and thickness to a standard size.



**DIRECTIONAL PATTERN OR VENEER GRAIN MATCH:** (see Veneer Grain or directional pattern Match).

**DISCOLORATIONS:** Stains in wood substances. Common veneer stains are sap stains, blue stains, stains produced by chemical action caused by the iron in the cutting knife coming in contact with the tannic acid of the wood, and those resulting from exposure of natural wood extractives to oxygen and light, to chemical action of vat treatments or the adhesive components, and/or to the surface finish.




**DISTRESSING:** In finishing, either a mechanical or chemical special effect.



# GLOSSARY

**DISTRIBUTOR:** A person or organization that provides products on a wholesale basis to a manufacturer of woodwork.


**DIVISION:** A cabinet component that is not one of the two sides, top or bottom. A division divides a cabinet into sections. Divisions may be horizontal or vertical.




## DOOR CORE, PASSAGE:

As regulated by WDMA's ANSI/WDMA I.S. 1A, ANSI/WDMA I.S. 6A, and ANSI/WDMA TM 15 <https://wdma.site-ym.com>


- **HOLLOW** - A core assembly of strips or other units of wood, wood derivative, or insulation board with intervening hollow cells or spaces that support the outer faces.




- **MINERAL** - A fire resistant core material generally used in doors requiring fire rating of 3/4 hours or more.



- **SOLID:** The innermost layer or section in flush door construction. Typical constructions are as follows:
- **PARTICLEBOARD** - A solid core of wood or other lignocellulose particles bonded together with a suitable binder, cured under heat, and pressed into a rigid panel in a flat platen press.




- **STAVE** - A solid core of wood blocks or strips.




- **WOOD BLOCK, LINED** - A solid core of two parts; a central wood block core bonded to two core liners of wood or other lignocellulose materials.

**DOOR FURNISHER:** As used in PRODUCT of section 09, is defined as the party responsible for the taking off, ordering and supplying of the doors to a project.

**DOVETAIL JOINT:** A joint formed by inserting a projecting wedge shaped member (dovetail tenon) into a correspondingly shaped cut out member (dovetail mortise); variations include the "dovetail dado" and the "blind dovetail dado."




**DOWEL:** Cylindrical peg used to strengthen a wood joint.




# GLOSSARY


**DOWEL LINK:** Synthetic, cylindrical, rimmed cabinet assembly peg that mates to a machined, self-tightening and locking groove.




**DOWEL (Twin) INSERTION CLIP/SPRING PIN:** Synthetic, twin dowel mounted cabinet assembly fastener with elongated, self locking member that mates to a machined pocket. The system is further strengthened with an accompanying metal spring dowel.




**DOWEL (Twin) RETENTION CARRIAGE:** Synthetic or metal, twin dowel mounted cabinet assembly fastener with elongated, self locking carriage mates to a machined, self-tightening groove.



**DOWEL SCREW:** Metal cabinet assembly screw with an extended un-threaded shaft that functions much like a dowel.



**DOWELED JOINT:** A joint using "dowels" (doweled construction); also "doweled edge joint."




**DOUG FIR:** Referring to Douglas Fir. Douglas fir is a common name for softwood evergreen coniferous trees of the genus *Pseudotsuga* in the family Pinaceae. Also known as Douglas Tree, False Hemlock and Oregon Pine. The heartwood of Doug Fir is moderately resistant to decay and is often used in exterior applications that require a smooth finish. The grain is typically straight.



**DOZE:** A form of incipient (early) decay characterized by a dull and lifeless appearance of the wood, accompanied by a loss of strength and softening of the wood substance.

**DRAWER FRONT:** Is the portion of the drawer box that is viewable even when the drawer is closed. Some drawer fronts are applied directly to the drawer box without use of a sub-front.



**DRAWER SLIDES, BALL BEARING:**

A linear motion, load bearing system that incorporates two or more parallel rows of caged ball bearings running in hardened steel raceways. Minimum requirements within NAAWS based on BHMA's (Builders Hardware manufacturers Association, <http://www.buildershardware.com>) ANSI/BHMA A156.9 - Cabinet Hardware.



**DRAWER SLIDES, ROLLER:** A linear motion, load bearing system that incorporates mounted cylindrical rollers on opposing tracks. Minimum requirements within NAAWS based on BHMA's (Builders Hardware manufacturers Association, <http://www.buildershardware.com>) ANSI/BHMA A156.9 - Cabinet Hardware.



# GLOSSARY

**DRAWER SLIDE-SIDE SYSTEM:** A roller or ball bearing slide system combined drawer sides or bars that make up a drawer unit when combined with otherwise provide drawer front, bottom and back. Minimum requirements within NAAWS based on BHMA's (Builders Hardware manufacturers Association, <http://www.buildershardware.com>) ANSI/BHMA A156.9 - Cabinet Hardware.




**DRAWINGS:** Part of a project's design documents which, in combination with written specifications, define the scope, quality assurance, requirements, submittals, dimensions, product handling, and product specifications to the manufacturer. See Shop Drawings.

**EASED EDGES:** For the vast majority of work, a sharp arris or edge is not permitted. Such edges are traditionally "eased" by lightly striking the edge with a fine abrasive. Less often, or as a design element, such edges are machined to a small radius.




**EASEMENTS:** Short curved segments of handrail that provide for changes in pitch, elevation, or direction



**ECONOMY GRADE:** The lowest Grade in both material and workmanship, and intended for work where price outweighs quality considerations.

**EDGEBANDING:** The process of attaching a finished material to the edge of panels. Typically a machine applied with hot melt glue, however hand attachment is allowed. Edgeband application is subject to tolerances found in these Standards.



**EDGE GRAIN (EG) OR VERTICAL GRAIN (VG):** A piece or pieces sawn at approximately right angles to the annual growth rings so that the rings form an angle of 45 degrees or more with the surface of the piece.




**EDGE JOINT:** At the edges of boards when glued together to increase the width.




**EFFECT:** The final result achieved in a finished wood surface, after the application of a clearly specified series of finishing procedures (steps) have been completed. Successfully achieving a specified "effect" requires the active participation of the design professional and the woodwork finisher.

**ELEVATION:** As used within these standards, a view of the front, back or end of an assembly or grouping of architectural woodwork components.



**END BUTT JOINT:**

- One end is glued to an edge or face of another board to form an angle (e.g., stiles and rails of a face frame)
- The end of one board is fastened to the end of another to increase its length (e.g., running trim).




**END GRAIN:** The grain seen in a cut made at a right angle to the direction of the fibers in a board.



# GLOSSARY

**END MATCH:** Butting adjacent veneer leaves on one panel end to end in sequence. Veneer leaves are book matched end to end. Generally used for very long panels or for projects in which only short length veneers are available.



**EQUILIBRIUM MOISTURE CONTENT:** The moisture content at which wood neither gains nor loses moisture when surrounded by air at a given relative humidity and temperature.

**ESCUTCHEON:** A protective fitting around a keyhole; also a shield like ornament.



**EXPOSED EXTERIOR SURFACES:** For purposes of these standards, specifically casework, means all exterior surfaces exposed to view.



**EXPOSED FASTENERS:** Any mechanical fastening device, filled or unfilled, that can be seen on exposed or semi-exposed surfaces of woodwork.


**EXPOSED INTERIOR SURFACES:** For purposes of these standards, specifically casework, means all interior surfaces exposed to view in open casework or behind transparent doors.




**EXPOSED SURFACES:** Surfaces normally visible after installation.

**EXTERIOR (Building):** That portion of the structure that is outside of the weather proofing of the building, including the weather proofing (non climate controlled).


**FACE:** The better side of any panel in which the outer plies are of different veneer grades; also either side of a panel in which there is no difference in veneer grade of the outer plies.



**FACE FRAME CONSTRUCTION:** A type of construction, where the front edge of the cabinet body components is overlaid with a frame.



**FACE VENEER:** The outermost exposed wood veneer surface of a veneered door, panel, or other component exposed to view when the project is completed.



# GLOSSARY


**FALSE FRONT:** Is a non-functional, exposed exterior member that gives the appearance of a drawer front without being attached to a drawer box. There is typically no usable space behind a false front, as it is only used for aesthetic purposes.

**FASTENER, MECHANICAL:** The generic term for securing devices that are used in the fabrication and/or installation of architectural woodwork, such as dowels, dowel screws, splines, nails, screws, bolts, staples, etc.

**FEW:** A small number without regard to their arrangement in the panel.

**FIBER:** One of the long, thick walled cells that give strength and support to hardwoods.

**FIBERBOARD CORE:** (Medium Density Fiberboard MDF) Manufactured from wood reduced to fine fibers mixed with binders and formed by the use of heat and pressure into panels.



**FIDDLEBACK:** A fine, strong, even ripple figure as frequently seen on the backs of violins. The figure is found principally in Mahogany and Maple, but occurs sometimes in other species.




**FIELD:** With reference to work location, meaning in the field or jobsite versus in the manufacturing plant or shop.

**FIGURE:** The natural pattern produced in the wood surface by annual growth rings, rays, knots, and natural deviations from the normal grain, such as interlocked and wavy grain, and irregular coloration.




**FILLER:**

- In finishing, ground inert solids specifically designed to fill pores or small cavities in wood as one step in the overall finishing process.
- In casework, paneling, ornamental work, stairwork, frames, and some other architectural woodwork applications, an additional piece of trim material between woodwork members or between woodwork and some other material used to create a fill or transition between the members.



**FINGER JOINT:** When the ends of two pieces of lumber are cut to an identically matching set. Used most commonly to increase the length of the board. A series of interlocking fingers are precision cut on the ends of two pieces of wood that mesh together and are held rigidly in place with adhesive.



**FIRE RETARDANT TREATMENT:** Only a few species are treated with chemicals to reduce flammability and retard the spread of flame over the surface. This usually involves impregnation of the wood, under pressure, with salts and other chemicals. White Oak is untreatable.

**FIRE RATED DOOR:** A door that has been constructed in such a manner that when installed in an assembly and tested will pass ASTM E-152 "Fire Test of Door Assemblies," and can be rated as resisting fire for 20 minutes (1/3 hour), 30 minutes (1/2 hour), 45 minutes (3/4 hour) (C), 1 hour (B), or 1-1/2 hours (B). The door must be tested and carry an identifying label from a qualified testing and inspection agency.

**FIRST CLASS WORKMANSHIP:** For architectural woodwork, the finest or highest class of workmanship for the Grade specified, and shall be free of manufacturing and natural defects covered under grading rules in these standards.

# GLOSSARY

**FLAKE:** See “Fleck, Ray”.

**FLAKEBOARD:** See “particleboard.”

**FLAME SPREAD:** A material’s propensity to burn and spread flames, that is determined by laboratory standard test methodology such as: NFPA’s (National Fire Protection Association, <http://nfpa.org>) NFPA 255 Standard Method of Test of Surface Burning Characteristics of Building Materials and NFPA 286 Standard Methods of Fire Tests for Evaluating Contribution of Wall and Ceiling Interior Finish to Room Fire Growth

**FLAME SPREAD CLASSIFICATION:**

The generally accepted measurement for flame spread rating of materials such as NFPA’s (National Fire Protection Association, <http://nfpa.org>) NFPA 80 and Life Safety Code NFPA 101.


Class	Flame Spread Index
A	0-25
B	26-75
C	76-200

**FLAT GRAIN (FG) OR SLASH GRAIN (SG):** A piece or pieces sawn approximately parallel to the annual growth rings so that all or some of the rings form an angle of less than 45 degrees with the surface of the piece.



**FLAT SLICING:** See “Plain Slicing”.

**FLATNESS:** A panel face having an even or smooth surface in one plane without depressions or projections.




**FLECK, RAY:** Portion of a ray which usually appears on quarter cut veneers and solids faces. This feature is most common in oaks (mainly white oak) but appears in other species well maple, beech, lacewood and sycamore can have the similar ray figure. See Medullary Ray.




**FLITCH:** Veneers sliced from a log (or part), reassembled into a bundle in its original sequence.



**FLUSH INSET:** Cabinet construction in which the door and drawer faces are set within and flush with the body members or face frames of the cabinet with spaces between face surfaces sufficient for operating clearance.



**FLUSH OVERLAY:** Cabinet construction in which door and drawer faces cover the body members of the cabinet with spaces between face surfaces sufficient for operating clearance.




# GLOSSARY


**FLUTE:** One of a series of parallel, lengthwise channels or grooves in a column, cornice molding, band, or furniture leg.



**FRAMELESS CONSTRUCTION:** A type of construction, where no frame is attached to the front edge of the cabinet body components which are typically edgebanded.



**FRENCH CLEAT:** A method of concealed panel or trim hanging where one component is screwed to the wall and the other component is screwed to the back of a millwork product. Each cleat has an opposing 45 degree edge, causing the two pieces to interlock. French cleats may be used for cabinet hanging provided it has been independently tested to show compliance to the Wall Cabinet Structural Integrity Test shown in **APPENDIX**.



**FURRING:** Material added to a building surface to create a true plane in order to install woodwork plumb and level.

**GABLE:** Aside from the traditional usage referring to the end of a building, in casework the end or side of a cabinet.

**GAP:** An unfilled opening between adjoining surfaces.



**GENERAL CONTRACTOR:** See contractor.

**GLAZING:** In finishing, an added step for achieving color or to heighten grain appearance.

**GLOSS:** See sheen.

**GLUE BLOCK:** A wood block, usually triangular in cross section, securely glued to an angular joint between two members for a greater glue bond area.



**GLUE SPOTS:** The discoloration or barrier to finish penetration caused by the bleed through or unremoved glue on an exposed or semi-exposed wood surface.

**GLUED, SECURELY:** The bonding of two or more members with adhesive, forming an element without delamination or separation.

**GRADE:** Unless otherwise noted, this term means Grade rules for Economy, Custom, and/or Premium Grade.


**GRADING RULES:** Most hardwoods are graded utilizing the rules established by the National Hardwood Lumber Association. Softwoods, on the other hand, are graded by several grading associations. The three primary softwood grading associations are Western Wood Products Association, Southern Pine Inspection Bureau, and Redwood Inspection Service.

- Although lumber must be purchased by the manufacturer according to these grading rules, these rules should not be used to specify lumber for architectural woodwork. Specify the Grade of Work for the fabricated products under these standards.
- Softwood plywood is graded by the American Plywood Association (APA, The Engineered Wood Association). Grade markings are stamped on the back or edge of each sheet.
- Hardwood plywood is made under the standards of the Hardwood Plywood and Veneer Association (HPVA). These Grades are rarely marked on the panels.

# GLOSSARY

**GRAIN:** The fibers in wood and their direction, size, arrangement, appearance, or quality. When severed, the annual growth rings become quite pronounced and the effect is referred to as "grain":

- **FLAT GRAIN (FG) or SLASH GRAIN (SG)** - lumber or veneer is a piece sawn or sliced approximately parallel to the annual growth rings so that some or all of the rings form an angle of less than 45 degrees with the surface of the piece.



- **MIXED GRAIN (MG)** - is any combination of vertical or flat grain in the same member. Vertical grain lumber or veneer is a piece sawn or sliced at approximately right angles to the annual growth rings so that the rings form an angle of 45 degrees or more with the surface of the piece.



- **QUARTERED GRAIN** - is a method of

sawing or slicing to bring out certain figures produced by the medullary or pith rays, which are especially conspicuous in Oak. The log is flitched in several different ways to allow the cutting of the veneer in a radial direction. Rift or comb grain is lumber or veneer that is obtained by cutting at an angle of about 15 degrees off of the quartered position. Twenty-five percent (25%) of the exposed surface area of each piece of veneer may contain medullary ray flake.



- **OPEN GRAIN AND CLOSED GRAIN** - The size and distribution of the cellular structure of the wood influences the appearance and uniformity. Open grain hardwoods, such as Elm, Oak, Ash, and Chestnut are "ring porous" species. These species have distinct figure and grain patterns. Close grain hardwoods, such as Cherry, Maple, Birch, and Yellow Poplar, are "diffuse porous" species. Most North American diffuse porous woods have small, dense pores resulting in less distinct figure and grain. Some tropical diffuse porous species (e.g., Mahogany) have rather large pores.



- **GRAIN RAISE** - When moisture in a finish swells and lifts wood fibers away from the surface of the wood being finished. The wood surface should be further sanded to eliminate grain raise.




- **RAISED GRAIN** - Roughened condition of the surface of dressed lumber on which hard summerwood is raised above the softer springwood, but is not torn loose from it.



**GRAIN CHARACTER:** A varying pattern produced by cutting through growth rings, exposing various layers. It is most pronounced in veneer cut tangentially or rotary.

# GLOSSARY

**GRAIN FIGURE:** The pattern produced in a wood surface by annual growth rings, rays, knots, or deviations from natural grain, such as interlocked and wavy grain and irregular coloration.



**GRAIN RAISE:** See Grain.


**GRAIN SLOPE:** Expression of the angle of the grain to the long edges of the veneer component.



**GRAIN SWEEP:** Expression of the angle of the grain to the long edges of the veneer component over the area extending one-eighth of the length of the piece from the ends.



**GROOVE:** Rectangular slot of three surfaces cut parallel with the grain of the wood.



**GROUND:** A narrow strip of wood that serves as a guide for plaster as well as a base to which trim members are secured. Grounds are applied to rough interior openings especially doors and windows; along interior walls at the finish floor line; and wherever wainscot may be installed. The thickness of a ground is that of the combined lath and plaster, while the width varies from 1" (25.4 mm) to 3" (76.2 mm), which is often called plaster grounds (around interior or exterior openings) and base grounds (when used around base of rooms).

**GROWTH RINGS:** The layer of wood added by a tree in a single growing season, the markings of which contribute to the figure in finished woods. Annual growth rings include both summer and winter growth.



**GUM POCKETS:** Well defined openings between rings of annual growth, containing gum or evidence of prior gum accumulations.




**GUM SPOTS AND STREAKS:** Gum or resinous material or color spots and streaks often dark brown, black or golden, caused by prior resin accumulations sometimes found on veneer or lumber surfaces.




**HAIRLINE:** A thin, perceptible line showing at the joint of two pieces of wood.

# GLOSSARY

**HALF LAP JOINT:** A joint formed by extending (lapping) the joining part of one member over the joining part of another.



**HALF ROUND SLICING:** A method of veneer cutting similar to rotary cutting, except that the piece being cut is secured to a “stay log,” a device that permits the cutting of the log on a wider sweep than when mounted with its center secured in the lathe to produce rotary sliced veneer. A type of half round cutting is used to achieve plain sliced or flat cut veneer.



**HANDLING MARKS:** Scratches, dents, blemishes, mars, or scuffs left or created by physical handling or packaging.

**HANDRAIL:** See “Molding”.

**HAND RUBBED FINISH:** In finishing, a manual step performed to smooth, flatten, or dull the topcoat.

**HARDBOARD:** A generic term for a panel manufactured primarily from inter-felted lignocellulose fibers consolidated under heat and pressure in a hot press and conforming to the requirements of ANSIA 135.4 (latest edition), <http://compositepanel.org>.

- **TEMPERED HARDBOARD** has been coated or impregnated with an oil and then baked to give it more impact resistance, hardness, rigidity, tensile strength, and more resistance to scratches and moisture. Tempered hardboard is typically smooth on both sides and may have a darker smooth finish.



**HARDNESS (in finishing):** The property of a coating that causes it to resist denting or penetration by a hard object.

**HARDWOOD:** General term used to designate lumber or veneer produced from temperate zone deciduous or tropical broad leaved trees in contrast to softwood, which is produced from trees that are usually needle bearing or coniferous. The term does not imply hardness in its physical sense. Minimum requirements within NAAWS based on enhancement of NHLA Grading Rules - <http://nhla.com>

**HEARTWOOD:** The non active or dormant center of a tree, generally distinguishable from the outer portion (sapwood) by its darker color, sometime referred to as heart.




**HIGH DENSITY OVERLAY:** The standard grades of high density overlay shall be as listed in PS 1, latest edition. The surface of the finished product shall be hard, smooth, or uniformly textured, although some evidence of underlying grain may appear. The surface shall be of such a character that further finishing by paint or protective coating is not necessary. Minimum requirements based on Voluntary Product Standard PS 1, <http://nist.gov>.



**HIGH PRESSURE CABINET LINER:** Conforms to NEMA's (National Electric Manufacturers Association, <http://nema.org>) ANSI/NEMA LD-3 (latest edition), has a color or pattern sheet to enhance its appearance, and is intended for use in cabinet interiors.

# GLOSSARY

**HIGH PRESSURE DECORATIVE LAMINATE (HPDL):** Laminated thermosetting decorative sheets intended for decorative purposes. The sheets consist essentially of layers of a fibrous sheet material, such as paper, impregnated with a thermosetting condensation resin and consolidation under heat and pressure. The top layers have a decorative color or a printed design. The resulting product has an attractive exposed surface that is durable and resistant to damage from abrasion and mild alkalis, acids, and solvents, meeting the requirements of the National Electrical Manufacturers Association (NEMA) LD-3 (latest edition). Minimum requirements based on NEMA's (National Electric Manufacturers Association, <http://nema.org>) ANSI/NEMA LD-3.



**HOLE:** Applies to holes from any cause.

**HOLES, WORM:** Holes resulting from infestation by worms greater than 1/16" (1.6 mm) in diameter.



**HONEYCOMB DOOR CORE:** A method of using lightweight paper, wood or other material based products to form a door core. The honeycomb provides some structural integrity and is a base for attachment of back bands or cross bands.



**HONEYCOMB IN RED OAK:** A structural defect found in Red Oak caused by bacterial heartwood infection resulting in abnormal odors in kiln dried lumber and an appearance of voids within the lumber.



**HOUSED CABINET BACK:** When a cabinet back is set in a three sided groove such as a plow or groove.

**HPDL:** See "high pressure decorative laminate."

**HPDL COMPACT:** See "Solid Phenolic".

**HUMIDITY:** The common term for relative humidity; the amount of moisture in an atmosphere in relation to temperature.

**INCONSPICUOUS:** Not readily visible without careful inspection (as a measurement of natural or machining characteristics).

**INDENTATIONS:** Areas in the face that have been compressed as the result of residue on the platens of the hot press or handling damage through the factory.



**INNER PLYS:** Plies other than face or back plies in a panel construction. Crossbands and centers are classed as inner plies (see core).



**INSTALLER:** A person or organization that regularly engages in the practice of installing architectural woodwork.

**INTERIOR (Building):** That portion of a building that is inside the building weather proofing, not including the weather proofing (can be climate controlled).

**INTUMESCENT COATINGS:** Can be applied to the surface of flammable products to reduce flammability.

# GLOSSARY

**JOINT:** The line of juncture between the edges or ends of two adjacent pieces of lumber or sheets of veneer, such as butt, dado (blind, stopped), dovetail, blind dovetail, finger, half lap, lock, miter (shoulder, lock, spline), mortise and tenon (blind slotted, stub, or through), rabbet, scarf, spline, and tongue and groove joint.


**JOINT, OPEN:** Joint in which two adjacent pieces of lumber or veneer do not fit tightly together.




**JOINTS TIGHT, FACTORY:** Any joints or a combination of joints and/or mechanical fasteners, that are used to join two members in the shop. Distance between members shall not exceed those set forth in these standards.

**JOINTS TIGHT, FIELD:** Any joints or a combination of joints and/or mechanical fasteners that are used to join two members in the field. Distance between members shall not exceed those set forth in these standards.

**KCPI:** Stands for “knife cuts per inch”; generally used when describing the result of molded profiles or S4S materials.




**KERF:** The groove or notch made as a saw passes through wood; also the wood removed by the saw in parting the material.



**KILN DRIED:** Lumber dried in a closed chamber in which the removal of moisture is controlled by artificial heat and usually by controlled relative humidity.



**KNIFE MARKS:** The imprints or markings of the machine knives on the surface of dressed lumber.



**KNOCKED DOWN (KD):** Unassembled, as contrasted to assembled.

**KNOT:** Cross section of tree branch or limb with grain usually running at right angles to that of the piece of wood in which it occurs

- **CONSPICUOUS PIN** - Sound knots 6.4 mm (1/4 inch) or less in diameter containing dark centers.



- **HOLES** - Openings produced when knots drop from the wood in which they were embedded.



- **OPEN** - Opening produced when a portion of the wood substance of a knot has dropped out or where cross checks have occurred to produce an opening.



- **SOUND TIGHT** - Knots that are solid across their face and fixed by growth to retain their place.



- **SPIKE** - Knots cut from 0° to 45° to the long axis of limbs.



# GLOSSARY

**LACQUER:** A coating composed of synthetic film forming materials such as nitrocellulose, ethylcellulose, natural and synthetic resins, which are dissolved in organic solvents and are dried by solvent evaporation.

**LEAF, VENEER:** The individual pieces of wood veneer that make up a flitch.



**LEED®:** An environmental building rating system created by United States Green Building Council (USGBC) to encourage and certify the environmental and energy saving attributes of a building and its operations.


**LIFTING:** In finishing, the softening of a dried film by the solvents of a succeeding coat, which causes raising and wrinkling of the first coat.

**LIGHTS (Lites):** In door construction, openings to receive glazing.


**LIPPAGE:** Variation in the height of adjoining stone or epoxy resin counter top joints. The differences in elevation between edges of adjacent tile modules.

**LISTING:** A tabular method of describing materials or methods that do not require drawings.

**LOCK BLOCK:** A concealed block the same thickness as the door stile or core that is adjacent to the stile at a location corresponding to the lock location and into which a lock is fitted.



**LOCK JOINT:** Interlocking machine joint between two members.



**LOOSE SIDE (of leaf):** In knife cut veneer, that side of the leaf that was in contact with the knife as the veneer was being cut, and containing cutting checks (lathe checks) because of the bending of the wood at the knife edge.

**LOUVER:** A slat or slats installed in a panel or door at an angle to the panel allowing various degrees of light, air or sound passage. May be constructed as adjustable.



**LOW PRESSURE DECORATIVE LAMINATE (LPDL):** A general term referring to a variety of melamine or polyester enhanced surface papers and foils laminated to a core, typically referred to as melamine or polyester overlays. Minimum requirements based on NEMA's (National Electric Manufacturers Association, <http://nema.org>) ANSI/NEMA LD-3.

**LPDL:** See "low pressure decorative laminate."

**LUMBER:** Pieces of wood no further manufactured than by sawing, planing, crosscutting to length, and perhaps edge machining.



**LUSTER:** See "Sheen".

**MADE TO ORDER SEQUENCED PANELS:** All panels are manufactured to width and/or height according to each elevation. All panels are balanced matched and sequenced to the adjacent panels.

# GLOSSARY

**MAHOGANY:** The term “Mahogany” should not be specified without further definition. It must be understood that there are different species of Mahogany that should be specified.

African, Central and South American, or Tropical American, including American Mahogany, are genuine and true Mahoganies. American Mahogany varies in color from light pink to light red; reddish brown to golden brown or yellowish tan. Some Mahogany turns darker and some lighter in color after machining.

The figure or grain in American Mahogany runs from plain sliced, plain stripe to broken stripe, mottled, fiddleback, swirl, and crotches. As uniform color is not a natural characteristic of this species, if a uniform color is desired it is recommended that the finishing specification include a statement that toner or tint must be applied so that color variation shall be kept to a minimum.

Lauan White and Red, Tanguile, and other species are native to the Philippine Islands and are sometimes referred to as Philippine Mahogany. Those species are not a true Mahogany.

When only the word “Mahogany” is specified, it usually (but not always) means a true Mahogany as selected by the manufacturer unless a specific species is called for in the specifications. When Philippine Mahogany is specified, it nearly always means Lauan, Tanguile, and other natural Philippine species of wood.




**MANUFACTURER:** A person or organization that regularly engages in the practice of manufacturing, prefinishing, and/or installing architectural woodwork.

**MATCHING EDGEBOARD:** See “self edge.”

**MECHANICAL FASTENER:** The generic term for securing devices that are used in the fabrication and/or installation of architectural woodwork such as dowels, dowel screws, splines, biscuit splines nails, screws, bolts, pins, etc.

**MEDIUM DENSITY FIBERBOARD (MDF):** See particleboard for a basic description. As used in these standards, whether as MDF alone or as core material. Minimum requirements based on CPA's (Composite Panel Association) ANSI A208.2 (latest edition), <http://compositepanel.org>.




**MEDIUM DENSITY OVERLAY (MDO):**

A panel product particularly well suited for opaque (paint) finishes; most versions are highly weather resistant. Minimum requirements based on Voluntary Product Standard PS 1, <http://nist.gov>.



**MEDIUM DENSITY PARTICLEBOARD:**

Generally refers to particleboard manufactured to an approximate density of 45 lbs per cubic foot (20.41 kg per cubic cm); the type of particleboard used for architectural woodworking cores. Minimum requirements based on CPA's (Composite Panel Association) ANSI A208.2 (latest edition), <http://compositepanel.org>.



**MEDULLARY RAY:** Extends radially from the center of a log toward the outer circumference. These rays serve primarily to store food and transport it horizontally. These rays vary in height from a few cells in some species to an excess of 4" (102 mm) in Oaks. In Oak, it produces the flake effect common to quarter sawn lumber.



**MELAMINE:** Resin impregnated paper used in decorative composite panel products (see thermally fused decorative laminate panel).



# GLOSSARY

**MEMBER:** An individual piece of solid stock or plywood that forms an item of woodwork.

**METAMERISM:** An apparent change in color when exposed to differing wavelengths of light; the human perception of color (see Barber Pole and Book Match).

**MILL RUN:** Molding run to pattern only, not graded, machined for assembly, or cut to length. The terms “material only” and “loose and long” mean the same as “mill run.”

**MILLWORK:** See “architectural woodwork.”

**MINERAL STREAK:** An olive to greenish black or brown discoloration of undetermined cause in hardwoods.




**MIRROR POLISH FINISH:** In finishing, several steps of wet sanding, mechanical buffing, and polishing.

## MISMATCH:


**PHYSICAL** - An uneven fit in worked lumber when adjoining pieces do not meet tightly at all points of contact or when the surfaces of adjoining pieces are not in the same plane.

**APPEARANCE** - Color, Grain and/or figure are not the same or similar.


**MITERFOLD:** Made from a single panel in one machining process; includes placement of tape, machining, application of adhesive, folding, glue, clamp, and clean.




**MITER JOINT:** The joining of two members at an angle that bisects the angle of junction.



**MITER, LOCK JOINT:** A miter joint employing a tongue and groove to further strengthen it.



**MITER, SHOULDER JOINT:** Any type of miter joint that presents a shoulder, such as a lock miter or a splined miter.



**MOCK-UP:** A sample made by the manufacturer to demonstrate materials, assembly, finish and/or tolerances proposed for a project. A mock-up does not eliminate the requirements found in section 1 for shop drawings. Mock-ups, if approved, may be allowed to become part of the finished project.

**MODULAR CASEWORK:** Casework produced from a manufacturer's standard details adapted for use rather than custom manufactured for a particular project.

## MODULUS OF ELASTICITY (MOE):

As referenced in this standard, the theoretically recoverable longitudinal deflection value of a material from an applied load.

## MODULUS OF RUPTURE (MOR):

The maximum load carrying capacity of a member under bending load.

**MOISTURE CONTENT:** The weight of the water in the wood expressed in percentage of the weight of the oven dry wood. Within NAAWS, requirements based on US Forest Products Laboratory publications, <http://fpl.fs.fed.us/index.php>

**MOLDED EDGE:** Edge of piece machined to any profile other than a square or eased edge.



# GLOSSARY

**MOLDING (MOULDING):** A decorative strip, usually having a curved or projecting surface. Some common moldings used are listed below. (Additional ornamental and architectural moldings are listed in the **DESIGN RESOURCES** Section under Historic Woodwork Glossary):


- **ASTRAGAL** - A molding attached to one door of a pair of doors covering the gap between the doors.
- **BACK BAND** - Used in conjunction with casing or baseboard to create a wide variety of trim options for windows and doors. Generally backband moldings create thicker or wider moldings than single piece components.
- **BASE BLOCK** - The square block terminating a molded baseboard at a doorway; a plinth block.
- **BASE CAP** - A molding applied to the top edge of a base molding to add aesthetic affect.
- **BASE or BASEBOARD** - Moldings used to trim the intersection of a wall or cabinet and the floor.
- **BASE SHOE** - A small molding combined with a base molding to complete the trimming of the wall and floor intersection.
- **BEAD MOLDING** - A narrow half round molding that is continuous or divided into bead like forms.
- **CASING** - Generally, a molding placed around a door frame or window frame.
- **BED MOLDING** - A molding or group of moldings used immediately beneath a projection.

- **CHAIR RAIL** - Applied along a wall for protection or as a design element between wall treatments, such as paneling, wallpaper, or paint. Traditionally placed at the horizontal location on the wall at a height that would be rubbed by a chair back, to protect the wall.
- **CORNICE** - A wood or composite wood molding detail along the top edge of a piece of a millwork assembly or a building. May be built up of several moldings or components to create one large profile.
- **COVE** - Similar to crown moldings, often smaller in size and less decorative.
- **CROWN** - Used to accent ceiling intersections and traditional pediments and casework tops.
- **FILLET** - A thin molding used to separate or decorate larger moldings and also refers to the infill strip that fits between the balusters on a stair case.
- **HANDRAIL** - A molding used along a hallway or corridor designed to be grasped by the hand to provide stability or support.
- **LATTICE** - A thin, flat molding, rectangular in cross-section, used to build decorative screening or conceal joinery.
- **OGEE** - A molding with reverse curved face that is concave above and convex below.
- **QUARTER ROUND** - A molding with a convex, quarter cylindrical shape.
- **PANEL MOLDING** - A decorative molding used to trim out raised or recessed wall panels.

- **SHOE** - A small molding with a concave channel and a square back.
- **TRANSITION MOLDING** - A molding that conceals the joint between uneven surfaces.


## **MORTISE AND TENON, BLIND JOINT:**

A mortise and tenon joint in which the tenon does not extend through the mortise and does not remain visible once the joint is completed; also "blind tenoned."




## **MORTISE AND TENON, SLOTTED JOINT:**

A mortise and tenon right angle joint in which the tenon is visible on two edges once the joint is completed.




**MORTISE AND TENON, STUB JOINT:** A short tenon inserted in a plow or groove.



# GLOSSARY

## MORTISE AND TENON, THROUGH JOINT:

A mortise and tenon joint in which the inserted tenon extends completely through the mortise and the end of the tenon remains visible once the joint is completed.



**MOTTLE:** Broken wavy patches across the face of the wood that give the impression of an uneven, although smooth, surface caused by a twisted interwoven grain with irregular cross figure, which is the mottle. The effect is due to reflected light on the uneven arrangement of the fibers. Other terms used to describe variations include bee's wing, fiddle, peacock, plum, ram, block, or stop mottle.




**NAILED:** Members secured together with nails, including power driven nails or staples. On exposed surfaces, staples and tee nails shall run parallel to the grain.

**NATURAL:** When referring to color and matching, veneers containing any amount of sapwood and/or heartwood.




**NEWEL POST:** In stairwork, an upright post that supports or receives the handrail at critical points of the stair, such as starting, landing, or top; the central vertical support of a spiral staircase.




**NGR STAINS:** Refers to non grain raising stains.

**NOMINAL:** The average sizes (width and thickness) of lumber just out of the sawmill before being processed into usable board stock. Always larger than "finished" dimensions. Also, a term that designates a stated dimension as being approximate and subject to allowances for variation.



**NON CLIMATE CONTROLLED:** Referring to the inside or outside areas of a building where heat or air condition systems are not used for environmental controls.

**NON HOUSED CABINET BACK:** When a cabinet back is set in a rabbet or is plant on back style.



## NONTRADITIONAL MATERIALS:

Materials re-purposed from other industrial and manufacturing areas, but assigned to the woodwork manufacturer and treated similarly to traditional millwork items like wall paneling.

**NON WOOD:** As used in INSTALLATION sections of this Standard refers to components made of material other than wood and that are subject to this Standard's tolerance threshold values.

**NON WOOD BASED PRODUCTS:** Any material that is not made of wood, veneer or paper based materials. Common non wood based products include: solid surface, stone, metals, fabrics, drywall, and masonry.

**NON WOOD TO NON WOOD:** A two or more component joint or assembly containing products that are not made of wood or wood based products.

**NOSING:** A rounded convex edge, as on a stair step.



**OCCASIONAL:** A small number of characteristics that are arranged somewhat diversely within the panel face.

# GLOSSARY

**OPAQUE FINISH:** A paint or pigmented stain finish that hides the natural characteristics and color of the grain of the wood surface and is not transparent.



**OPEN GRAIN AND CLOSED GRAIN:**  
See Grain.


**ORANGE PEEL:** The description of a coating that does not flow out smoothly, exhibiting the texture of an orange.




**ORIENTED STRAND BOARD (OSB):** is an engineered wood product formed by layering strands (flakes) of wood in specific orientations. In appearance it may have a rough and variegated surface with the individual strips lying unevenly across each other. Minimum requirements based on Voluntary Product Standard PS 2 <http://nist.gov>



**OVER FILING:** In manufacturing, rough edges are required to be filed or sanded smooth. Over filing exposes the core of the decorative laminate or otherwise causes defects in the finished product.



**OVERLAP:** A condition where the veneers comprising plywood are so misplaced that one piece overlaps the other and does not make a smooth joint.




**OVERLAY:** To superimpose or laminate a wood veneer of various species or a decorative item, such as melamine, polyester, or high pressure decorative laminate to one or both sides of a given core, such as plywood, particleboard, or medium density fiberboard.

**OVERSPRAY:** The dry, pebble like surface caused when the sprayed finish begins to dry in the air before it hits the surface.

**OXIDATION:** The effect on the appearance of exposed wood faces caused by exposure to atmosphere. This is analogous to browning reactions in freshly cut fruit; for instance, apples. Hardwoods can develop deep yellow to reddish brown discolorations on the surface of the wood when exposed to air immediately after sawing or peeling. These discolorations are especially noticeable on Cherry, Birch, Red Alder, Sycamore, Oak, Maple, and Sweet Gum. Some species, such as Alder, Oak, Birch, and Maple, develop these discolorations during air seasoning. A related gray stain on several varieties of Southern Oaks also appears to be oxidative in nature. Proper selection, sanding, and finishing can minimize the effects of oxidation. Care should be taken when using filler, as it might not change the same as the wood.



**PAIR MATCH:** Relating to passage doors, means doors are adjacent to each other or are next to each other with only a door frame member separating the two doors.




**PANEL:** Panels are consistent in thickness, with edges that are at right angles to the face and are either homogeneous or made up of three or more layers.


**PANEL MATCH:** Establishes the leaf layout in each individual panel.

# GLOSSARY

**PANEL REVEAL:** A detail used in wall and ceiling surfacing panel design that allows for expansion and contraction between adjacent panels. The reveal is a space between adjacent panels or other architectural features that allows for panel expansion and contraction.



**PARTICLEBOARD:** A generic term for a panel manufactured from lignocellulosic materials (usually wood), primarily in the form of discrete pieces of particles, as distinguished from fibers, combined with a synthetic resin or other suitable binder, and bonded together under heat and pressure in a hot press by a process in which the entire interparticle bond is created by the added binder, and to which other materials may have been added during manufacturing to improve certain properties. Particles are further defined by the method of pressing. When pressure is applied in the direction perpendicular to the faces as in a conventional multi platen hot press, they are defined as flat platen pressed; and when the applied pressure is parallel to the faces, they are defined as extruded. Minimum requirements based on CPA's (Composite Panel Association) ANSI A208.2 (latest edition), <http://compositepanel.org>.



**PARTICLEBOARD, FIRE RETARDANT TREATED:** Particleboard treated to obtain Class A or Class B flame spread. Minimum requirements based on CPA's (Composite Panel Association) ANSI A208.2 (latest edition), <http://compositepanel.org>.

**PARTITION:**

- A fixed panel within a cabinet.
- A panel or a panel assembly that is securely attached to floor, ceiling, walls or a supported frame used to divide room spaces.




**PATCH:** A repair made by inserting and securely gluing a sound piece of wood of the same species in place of a defect that has been removed. The edges shall be cut clean and sharp and fit tight with no voids. "Boat" patches are oval shaped with sides tapering in each direction to a point or to a small rounded end; "router" patches have parallel sides and rounded ends; "sled" patches are rectangular with feathered ends.



**PECKY:** Pockets of disintegrated wood caused by localized decay or wood areas with abrupt color change related to localized injury such as bird peck. Peck is sometimes considered a decorative effect, such as bird peck in Pecan and Hickory or pecky in Cypress.



**PEDIMENT:** A triangular ornament above a cornice.



Fronton : 1. à pans ; 2. à jour ; 3. circulaire ; 4. brisé ; 5. entrecoupé ; 6. doublé ; 7. surbaissé ; 8. surmonté ; 9. sans retour ; 10. triangulaire ; 11. sans base ; 12. par enroulement

**PENETRATING OIL:** In finishing, an oil based material designed to penetrate the wood.

**PERFORMANCE BASED:** With reference to these standards, and in contrast to prescriptive based, refers to the lack of dictated or specifically required technical processes in lieu of a concept that allows innovation as long as the required outcomes are achieved.

# GLOSSARY

## PHENOL FORMALDEHYDE RESIN:

Typically used for exterior type construction. Plywood and doors bonded with this adhesive have a high resistance to moisture. The most common types require high temperatures during pressing to aid in the curing process.

**PHOTODEGRADATION:** The effect on the appearance of exposed wood faces caused by exposure to both sun and artificial light sources. Obviously, if an entire face is exposed to a light source, it will photodegrade somewhat uniformly and hardly be noticeable; whereas partially exposed surfaces or surfaces with shadow lines may show nonuniform photodegradation. Some woods, such as American Cherry and Walnut, are more susceptible than others to photodegradation.



**PILASTER:** A fluted or carved, flat, decorative column vertically attached to a building or furniture.

**PIN HOLES:** All circular or nearly circular holes in the exposed surface.



**PITCH:** An accumulation of resin that occurs in separations in the wood or in the wood cells themselves.

**PITCH POCKET:** A well defined opening between the annual growth rings that contains pitch.



**PITCH STREAK:** A well defined accumulation of pitch in the wood cells in a more or less regular streak.




**PITH:** A small, soft core occurring in the center of the log.



**PLAIN SAWN:** A hardwood figure developed by sawing a log lengthwise at a tangent to the annual growth rings. It appears as U shaped or straight markings in the board's face.




**PLAIN SLICING:** Most commonly used for hardwood plywood. The log is cut in half, and one half is placed onto a carriage and moved up and down past a fixed knife to produce the veneers. Veneer is sliced parallel to the pith of the log and approximately tangent to the growth rings to achieve flat cut veneer. Each piece is generally placed in a stack and kept in order. One half log, sliced this way, is called a "flitch."



**PLANK:** A board, usually between 1-1/2" to 3-1/2" (38.1 to 88.9 mm) thick and 6" (152 mm) or more wide, laid with its wide dimension horizontal and used as a bearing surface.

**PLANT ON BACK:** When a cabinet back is applied and fastened to the back edges of a cabinet box. The back is not set in grooves, plows or rabbets.




**PLASTIC LAMINATE FINISH:** See "high pressure decorative laminate."

# GLOSSARY

**PLEASING MATCHED:** A face containing components that provide a pleasing overall appearance. The grain of the various components need not be matched at the joints, but will not be widely dissimilar in character and/or figure. Sharp color contrasts at the joints of the components are not permitted. Members are selected so that lighter than average color members are not placed adjacent to darker than average members.

**FLOW:** A rectangular groove or slot of three surfaces cut parallel to the grain of a wood member, in contrast to a dado, which is cut across the grain.




**PLUS/MINUS or (+/-):** References the maximum positive or negative variance allowed from one object to another object.


**PLY:** A single sheet of veneer or several strips laid with adjoining edges that may or may not be glued, which forms one veneer laminate in a glued panel (see layer). In some constructions, a ply is used to refer to other wood components such as particleboard or MDF.



**PLYWOOD:** A panel composed of a cross-banded assembly of layers or plies of veneer, or veneers in combination with a lumber core or particleboard core, that are joined with an adhesive. Except for special constructions, the grain of alternate plies is always approximately at right angles, and the thickness and species on either side of the core are identical for balanced effect. An odd number of plies is always used.



**POCKET SCREW:** Pocket screw joints are created by aligning two pieces perpendicular, drilling angled pocket and pilot holes and then driving cabinet assembly screws to connect the pieces. These screws are used in concealed surface locations only.



**POLYESTER:** In finishing, a very high solids content plastic coating, leaving a deep, wet look.

**POLYURETHANE:** A very hard and wear resistant finish, which is very difficult to repair. Most commonly used as a two component system, comprising multifunctional isocyanate or moisture cured urethane, with a higher solids content than lacquers. Single component (excluding moisture cured) products are usually composed of pre-catalyzed urethane.

**PRE-FINISHED:** Product that is delivered with finish as opposed to field finishing.

**PRE-MANUFACTURED SETS:** Each panel, usually 4' x 8' (1219 mm x 2438 mm) or 4' x 10' (1219 mm x 3048 mm), is part of a sequenced set of running or balanced matched, pre-manufactured panels to be installed full width with the sequencing maintained. The panel's balanced match becomes unequal at the start, end, and any other opening or change in plane when trimmed.

**PREMIUM GRADE:** The highest Grade available in both material and workmanship intended for the finest work. This is naturally the most expensive Grade.

**PRESCRIPTIVE BASED:** With reference to these standards, and in contrast to performance based, refers to the manner in which regulations are expressed that dictate the technical processes by which the required outcomes are to be achieved.

**PRESERVATIVE:** (n.) A treating solution that prevents decay in wood; (adj.) having the ability to preserve wood by inhibiting the growth of decay fungi. Minimum requirements based on Window and Door Manufacturers Association (WDMA) WDMA I.S. 4-15A - <http://wdma.com>

# GLOSSARY

**PRESSED:** As in panel layup, hot, cold, vacuum or mechanical requires pressure until glue sets and becomes rigid.

**PROFILE:** A trim that has a shaped detail along one or more edges. Eased edges are included in profiles. Ends or faces may also have profiles.



**PUR:** Is a general adhesive with polyurethane as its primary component used in the woodwork industry. It is also referred to as PU and polyurethane reactive.

**PUTTIED:** See "fill."

**PVA:** Is a wood adhesive with polyvinyl acetate as its primary component and is commonly referred to as wood glue, white glue, carpenter's glue, or PVA glue.

**PVC:** Abbreviation for "polyvinyl chloride," a synthetic decorative coating or edgebanding.


**PVC EDGING:** A polyvinyl chloride edging, usually in seamless rolls, typically applied by edgebanding machines using hot melt adhesives. Available in a variety of solid colors, patterns, and wood grain designs, in both textured and smooth finish.



**QUARTER SAWN (QUARTERED LUMBER):** Refers to solid lumber cutting. Available in limited amounts in certain species. Yields straight grain, narrow boards with "flake" or figure in some species (particularly in Red and White Oak).




**QUARTER SLICING:** Produces a striped grain pattern, straight in some woods, varied in others. Veneer produced by cutting in a radial direction to the pith to the extent that fleck or ray flake is produced, and the amount may be unlimited. In some woods, principally Oak, fleck results from cutting through the radial medullary rays.




**QUARTERS:** The commercial thicknesses usually associated with the purchase or specification of hardwoods, such as "five quarter" (5/4 of 1"), meaning 1-1/4" (31.8 mm) in thickness.

**QUIRK:** For purposes of these standards, means a sharp decorative incision or kerf in moldings or trim that can hide the use of mechanical fastener.


**RABBET:** Rectangular cut on the edge of a member; a "rabbet" has two surfaces, and a "plow" has three.




**RABBET JOINT:** A groove cut across the grain of the face of a member at an edge or end to receive the edge or end thickness of another member.



**RAIL:** The cross or horizontal pieces of a stile and rail assembly or the cross pieces of the core assembly of a wood flush door or panel.




**RAILING:** In stairwork, the member that follows the pitch of the stair for grasping by the hand.




**RAISED GRAIN:** See "Grain".

# GLOSSARY

**RAISED PANEL:** Traditional door or wall panel with a bevel edge captured in a stile and rail frame.



**RANDOM MATCH:** Matching between adjacent veneer leaves on one panel face. Random selection in the arrangement of veneer leaves from one or more flitches producing a deliberate mismatch between the pieces of veneer.



**RAY:** One of the radial structures in a tree that stores nourishment and transports it horizontally through the trunk. In quarter sawn Oak, the rays form a figure called fleck.

**RECONSTITUTED VENEER:** Logs that are first sliced into veneer leaves, the leaves may be dyed, then glued under pressure in a mold to produce a large laminated block. The laminated block is then sliced across the glue line to create a faux grain with a designed appearance that is highly repeatable.



**RECLAIMED OR RECYCLED WOOD:** Processed wood retrieved from its original application for purposes of subsequent use, and the process of turning waste timber into usable products.

**RED/BROWN:** When referring to color and matching, veneers containing all heartwood, ranging in color from light to dark.



**RED BIRCH:** The heartwood of the Yellow Birch tree.



**RELIEF:** Defined as the difference in elevation between the high and the low parts of an area or where a form is raised (or alternatively lowered) from a flattened background without being disconnected from it.



**REPAIRS:** A patch, shim, or filler material inserted and/or glued into veneer or a panel to achieve a sound surface.




**REPAIRS, BLENDING:** Wood or filler insertions similar in color to adjacent wood so as to blend well.



**RESORCINOL FORMALDEHYDE RESIN:** For woodworking, formulated into water resistant glues.

**RESTRAINED:** See "Captured".

**RETENTION MOLDING:** A molding used to capture or hold in place another material such as a panel, glass, metal or other millwork product.




**RETURN:** Continuation in a different direction of a molding or projection, usually right angles.




# GLOSSARY


**REVEAL, CABINET:** The space between door edges and inset frames. The amount of viewable case edge when a door is in the closed position in flush overlay or reveal overlay cabinet construction.



**REVEAL OVERLAY:** Cabinet construction in which the door and drawer faces partially cover the body members or face frames of the cabinet with spaces between face surfaces creating decorative reveals.



**RIFT CUT:** A straight grain appearance achieved through the process of cutting at a slight angle, approximately 15 degrees, to the radial on the half round stay log or through the use of veneer cut in any fashion that produces a straight grain with minimal ray fleck. Twenty-five percent (25%) of the exposed surface may contain medullary ray flake.




**RIGID GLUE LINE:** For purposes of this standard, a rigid glue line is one that does not use a contact or otherwise flexible type adhesive.

**RING, ANNUAL GROWTH:** The growth layer put on in a growth year.




**RISER:** The board at the back of a tread that "rises" to the bottom of the next tread above. In an "open riser" stair, this element is left out, and the gap between the treads is open. Open riser stairs are prohibited by code in many circumstances.



**ROOM MATCH:** Refers to the matching of panel faces within a room.


**ROTARY SLICING:** Most common method for preparing veneers for softwood plywood. The log is placed in a lathe and rotated against a stationary knife. This produces a more or less continuous sheet of veneer, similar to pulling a long sheet off a roll of paper towels.



**ROUGH CUT:** Irregular shaped areas of generally uneven corrugation on the surface of veneer, differing from the surrounding smooth veneer and occurring as the veneer is cut by the lathe or slicer.



**RUNNING MATCH:** Each panel face is assembled from as many veneer leaves as necessary. Any portion left over from one panel may be used to start the next.



# GLOSSARY

**RUNNING TRIM:** Generally combined in the term “standing and running trim” and refers to random, longer length trims delivered to the jobsite (e.g., baseboard, chair rail, crown molding). Running trim is generally installed horizontally. Standing trim installed vertically.

**RUNS:** The result of spraying a heavier coat on a vertical, or nearly vertical, surface than the viscosity of the finish will allow to hold without movement; when in close multiples are also called “sags.”



**RUPTURED GRAIN:** A break or breaks in the grain or between spring-wood and summer-wood caused or aggravated by excessive pressure on the wood by seasoning, manufacturing, or natural processes. Ruptured grain appears as a single or series of distinct separations in the wood such as when spring-wood is crushed leaving the summer-wood to separate in one or more growth increments.



**S4S:** Means “Surfaced Four Sides,” and generally refers to the process of reducing nominal sized rough lumber to finished widths and thicknesses.



**SAGS:** In finishing, partial slipping of finish film creating a “curtain” effect.



**SAND THROUGH:** A defect on the exposed visible surface, such as depressions, bumps, marks, or core usually caused by thin veneers or over sanding.



**SANDED, CROSS:** Sanded across, rather than parallel to, the grain of a wood surface.



**SANDED, MACHINE:** Sanded by a drum or equivalent sander to remove knife or machine marks.

**SANDED, SMOOTHLY:** Sanded sufficiently smooth so that all machining, machine sanding marks, cross sanding, and other sanding imperfections will be concealed by the painter’s applied finish work. The proper sanding grit varies with the species of material; however, it generally runs in the 120 to 150 grit range and grade of workmanship specified.


**SAPWOOD:** The living wood of lighter color occurring in the outer portion of a tree, sometimes referred to as sap.



**SASH:** A single assembly of stiles and rails into a frame for holding glass, with or without dividing bars, to fill a given opening. It may be either open or glazed.



**SCARF JOINT:** When the ends of two boards are cut on an angle and glued together to increase the length of the board.




**SCL:** See “Structural Composite Lumber”.


# GLOSSARY

**SCRIBE:** To mark and cut an item of woodwork so that it will abut an uneven wall, floor, or other adjoining surface.


**SCRIBE FILLER:** A scribe filler is used to fill the space between a base or wall cabinet and an adjacent wall. The face of the scribe filler is typically set flush or a maximum of 1/16" (1.6 mm) set back from the face edge of the cabinet box.



**SCRIBE MOLD:** A scribe mold is used to cover the space between a base of wall cabinet and adjacent wall. The face of the scribe mold is typically set on top of the face edge of the cabinet box and not interfering with the door swing.



**SCRIBE ALLOWANCE:** A scribe allowance is an amount added to the all side of a cabinet face frame allowing the installer material to cut in order to achieve a tight fit to the wall.



**SEALING:** The process of applying a moisture resistant finish to the edges of sink cut outs. The process of applying a finish to concealed areas of factory finished millwork. Sealing is a part of proper factory finished panel balancing.

**SEALERS:** Compounds that provide a sandable coating and a smooth surface for final topcoat application, provide system toughness and moisture resistance, and contribute to build and clarity.

**SEASONING:** The process of allowing new cut wood to release moisture and achieve optimal moisture content without the aid of mechanical drying processes such as kiln drying.




**SECURELY ATTACHED:** The attachment of one member to another by means of approved joinery, adhesive, mechanical fasteners, or by a combination of these means. Members shall not be considered securely attached if they disassemble during standard usage and stress.

**SECURELY FASTENED OR BONDED:** See "securely attached."

**SELECT:** A lumber grading term. Also, in architectural specifications, the term "select" is frequently used to describe, clarify, or qualify specific characteristics of the hardwood lumber being specified; for example, Select White Maple or Select White Birch, by using "select" as a descriptor, Natural, Brown, and Red Maple/Birch are excluded.

**SELF EDGE:** Application of an edge that matches the face.



**SEMI-EXPOSED SURFACES:** Surfaces that are only visible under closer examination.

**SET MATCH:** Relating to passage doors, means three or more doors that are adjacent to each other or are next to each other with only a door frame member separating any of the doors.

**SHADING:** In finishing, transparent color used for highlighting and uniform color.

**SHAKE:** A separation or rupture along the grain of wood in which the greater part occurs between the rings of annual growth (see ruptured grain).

**SHARP CONTRAST:** For the purpose of this standard, this term applies to woodwork such as veneer of lighter than average color joined with the veneer of darker than average color. Two adjacent pieces of woodwork should not be widely dissimilar in grain, figure, and natural character markings.




**SHEEN:** Finish shine or brightness; luster, patina, and radiance. The sheen or gloss level of a cured finish is traditionally measured with a 60 degree gloss meter. The words used to describe various sheens are not standardized between companies.

# GLOSSARY

**SHELF CLEAT:** A piece of wood or other solid material attached directly to a wall blocking just below the bottom edge of a shelf.



**SHELF DEFLECTION:** Shelf deflection is the deviation from true flat of a shelf when placed under load.



**SHELF LOAD:** The amount of weight a shelf is designed to carry based on shelf core material, Modulus of Elasticity and surface materials.

**SHELLAC:** A coating made from purified lac, a secretion from an insect (*laccifera lacca*) that is dissolved in alcohol and often bleached white.

**SHOP DRAWINGS:** Shop drawings are detailed engineering drawings produced by the manufacturer for the fabrication of the architectural woodwork products, and are often submitted to the design professional for review and comment. See Drawings.

**SHOW THROUGH:** Irregular surfaces visible on the face of a veneered panel (such as depressions, bumps, mechanical marks, or core or frame outlines).




**SKIN:** The hardwood plywood (usually 3 ply), hardboard, or composition panel, whether flat or configured, that is used for facings for flush doors, bending laminations, finished end panels, and the like.

**SKIRT BOARD:** A trim member similar to base, run on the rake along the wall adjoining a stairway. The skirt board covers the joint between the treads and risers and the wall. Also, the similar member below the treads at the open side of a stairway. A wall routed to receive the treads and risers may replace a skirt board.




**SLEEPER:** A support member, usually vertical in placement, between the front and rear members of a non integral toe base or kick assembly.



**SLICED (SLICE):** See "Veneer, Sliced".

**SLIGHT:** Visible on observation, but does not interfere with the overall aesthetic appearance with consideration of the applicable grade of the panel.

**SLIP MATCHED:** Each leaf from a flitch is laid out in sequence from their place in the bundle, all faces in one direction. The result is that all the faces are either loose or tight, therefore reflect light the same minimizing the barber pole or metamerism effect.



**SMOOTH, TIGHT CUT:** Veneer cut to minimize lathe checks.

**SMOOTHNESS:** The degree to which a surface has had machining and handling effects removed. Typically accomplished by sanding with progressively finer sanding grits until the required surface texture is achieved.

**SOFT CONVERSION:** An inch measurement is mathematically converted to its exact, or nearly exact metric equivalent. Inches are multiplied by 25.4 to determine millimeters. Example: 48" x 25.4 = 1219.2 mm, commonly rounded to 1219 mm.

**SOFTWOOD:** General term used to describe lumber or veneer produced from needle and/or cone bearing trees (see hardwood). Minimum requirements within NAAWS based on enhancement of Voluntary Product Standard PS 20, <http://nist.gov>.

# GLOSSARY

**SOLID PHENOLIC:** A composite of solid phenolic resins molded with a homogenous core of organic fiber reinforced phenolic and one or more integrally cured surfaces of compatible thermoset nonabsorbent resins.



**SOLID STOCK:** Solid, sound lumber (as opposed to plywood), that may be more than one piece of the same species, securely glued for width or thickness.

**SOLID SURFACE:** Filled cast polymeric resin panel. The fillers enhance both its performance properties and aesthetics. With a homogeneous composition throughout its thickness, solid surface requires no finish coat and is capable of being fabricated with inconspicuous seams and repaired to its original finish. Minimum requirements based on CPA's (Composite Panel Association) ANSI/ICPA SS-1 - <http://icpa-hq.org>

**SOUND:** In reference to lumber or veneer, the absence of decay, pith, shake, doze and wane.

**SP:** See "Solid Phenolic".

**SPANDREL:** The triangular element in a staircase between the stringer and the baseboard.



**SPECIES:** A distinct kind of wood.


**SPECIFIC GRAVITY:** The ratio of the weight of a certain volume of a substance to the weight of an equal volume of water, the temperature of which is 39.2 degrees Fahrenheit (4 degrees Celsius).

**SPECIFICATION:** Directions provided by the design professional and found within a given project's contract documents, or addendum. Specifications may be modified by agreements such as change orders or field directives from the Design Professional.


**SPECIFIED:** See "Specification".

**SPECIFY:** See "Specification".

**SPLINE:** A thin narrow strip forming a key between two members, usually of plywood, inserted into matching grooves that have been machined in abutting edges of panels or lumber to ensure a flush alignment and a secure joint.




**SPLINE JOINT:** A joint formed by the use of a "spline." Splines customarily run the entire length of the joint.



**SPLIT:** Separations of wood fiber running parallel to the grain.



**SPLIT HEART:** A method of achieving an inverted "V" or cathedral type figure by joining two face components of similar color and grain usually required by removal of the veneer leaf's defective heart (center).



**STAIN:** A variation (normally blue or brown) from the natural color of the wood. It should not be confused with natural red heart. In finishing, produces the desired undertone color with proper distribution, depth, and clarity of grain. Selection of the type of stain used is governed by the desired artistic result. In natural wood, a variation in the color tending toward blue or brown, but not to be confused with naturally occurring heartwood.

**STAINING:** An optional operation in wood finishing to achieve the desired undertone color and complement the wood with proper distribution of color, depth of color, and clarity of grain.

# GLOSSARY

**STAIRWORK:** Wood material to form a stair or to clad stair parts constructed of materials other than wood, and that are custom manufactured to a design for a particular project.


**STANDING TRIM:** Generally combined in the term “standing and running trim” and refers to vertically installed moldings of fixed length delivered to the jobsite (e.g., door jambs and casings, premachined window stools).

**STAPLED:** Members secured together with nails, including power driven nails or staples. On exposed surfaces, staples shall run parallel to the grain.

**STAVED CORE:** Typically refers to a core used in flush doors made up of end and edge glued wood blocks.




**STICKING:** A term used to describe shaped or molded solid wood members.




## STILE AND RAIL CONSTRUCTION:

A technique often used in the making of doors, wainscoting, and other decorative features for cabinets and furniture. The basic concept is to capture a panel within a frame, and in its most basic form it consists of five members: the panel and the four members that make up the frame. The vertical members of the frame are called stiles, while the horizontal members are known as rails.




## STILES AND VERTICAL EDGES:

The upright or vertical pieces of stile and rail assemblies; the vertical members of the core assembly of a wood flush door.



**STOPS:** Generally a molding used to “stop” a door or window in its frame.



**STOP SHAPED:** Generally refers to the action of stopping a shaped edge detail prior to the end of the of a run for added detail or joinery fit. As an example the rounding over of the top edge of a drawer side is stopped before it reaches the drawer front or rear members.



**STOP SILENCER:** Generally a felt or rubber pad applied to the back side of cabinet doors to silence their contact with the cabinet body.



**STREAKS, MINERAL:** Sharply contrasting elongated discolorations of the wood substance.




# GLOSSARY

**STRETCHER:** A horizontal support member of base cabinet fabrication, used to attach the countertop, to space the end panels or used below a drawer to provide for a for door backstops.



**STRINGER:** A diagonal element supporting the treads and risers in a flight of stairs.



**STRINGER TURNOUT:** In stairwork, that portion of a stringer that curves or angles away from the basic run, typically used at the beginning tread.



**STRIPE:** Stripe figure is a ribbon grain:

- **BROKEN STRIPE** - A modification of ribbon stripe. The figure markings taper in and out, due to twisted or interlocked grain, so that the ribbon stripe is not continuous as it runs more or less the full length of the flitch.

- **PLAIN STRIPE** - Alternating darker and lighter stripes running continuously along the length of a piece, due to cutting wood with definite growth rings on the quarter.
- **RAINDROP** - When the waves of the fibers occur singly or in groups with considerable intervals between, the figure looks like streaks made by raindrops striking a window pane at a slant.
- **RIBBON STRIPE** - In some wood with interwoven grain, such as Mahogany, wide unbroken stripes can be produced by cutting on the quarter.
- **ROE** - Also called "roey." Short, broken ribbon or stripe figure in quarter sliced or sawn wood, due to the spiral formation of the fibers, or interlocked grain, in the growth rings. The irregular growth produces alternate bands of varying shades of color and degrees of luster.


**STRIPPING:** For purposes of these standards, means the process of removing an old or existing finish from a surface.

## STRUCTURAL COMPOSITE LUMBER

**(SCL):** A man made composite that utilizes stranded wood fibers from a variety of tree species, providing an alternative to dimension lumber. The material is engineered for strength and stability. While not really "lumber", it is marketed as a lumber substitute to be used in place of stave lumber core materials.



**SUB FRONT:** A front drawer box member over which a drawer front is placed.



**SUBTOP:** A separate support member for countertops.

**SURFACE BEARING HEAD:** A screw with a homogeneous head that has a flat bottom surface at least two times the diameter of the screw shaft and when tightened applies distributed pressure on the surfaces being screwed. Screws and washers are not considered surface bearing heads for the purpose of this Standard.




**SURFACE CHECK:** The separation of a wood, normally occurring across the rings of annual growth; usually as a result of seasoning, and occurring only on one surface of the piece.



# GLOSSARY

**SWIRL:** Figure obtained from that part of a tree where the crotch figure fades into the figure of the normal stem.




**TAMBOUR:** A rolling top or front in casework enclosing a storage space. It consists of narrow strips of wood fastened to canvas or a similar material.




**TELEGRAPH OR TELEGRAPHING:**

In veneer or laminated work, the variations in surface refraction as a result of the stile, rail, core, core laps, glue, voids, or extraneous matter show through to the face of a panel or a door. The selection of high gloss laminates and finishes should be avoided because they tend to accentuate natural telegraphing.



**TENON:** The projecting tongue like part of a wood member to be inserted into a slot (mortise) of another member to form a mortise and tenon joint.



**TEXTURE:** A term used to describe relative size and distribution of the wood elements. Coarse texture in veneer is associated with fast growth and harder, more difficult wood to cut. Soft or fine texture in veneer is associated with slower growth and with less summerwood, resulting in wood fibers that are easier to cut.

**THERMALLY FUSED DECORATIVE LAMINATE PANEL:**

A polyester or melamine resin impregnated paper, thermally fused under pressure to a composite core. Minimum requirements based on NEMA's (National Electric Manufacturers Association, <http://nema.org>) ANSI/NEMA LD-3.




**THICK PHENOLIC:** See solid phenolic.


**TIGHT:** Set together so that there is no opening between members.

**TIGHT SIDE (of leaf):** In knife cut veneer, that side of the leaf that was farthest from the knife as the veneer was being cut and containing no cutting checks (lathe checks).

**TONGUE:** Projection on the edge or end of a wood member that is inserted into the groove or plow of a similar size to form a joint.



**TONGUE AND GROOVE JOINT:** A joint formed by the insertion of the "tongue" of one wood member into the "groove" of the other.



**TOPCOAT:** The final protective film of a finish system. There are various topcoats with different properties.


**TOP FLAT SURFACE:** The flat surface that can be sanded with a drum sander.

**TORN GRAIN:** A roughened area caused by machine work in processing.



**TRANSPARENT FINISH:** A stain or a clear finish that allows the natural characteristics and color of the grain of the wood surface to show through the finish.

**TREAD:** The horizontal surface of a staircase step.




# GLOSSARY

**TREAD RETURN:** A narrow piece of tread stock applied to the open end of a tread so that the end grain is not exposed. The leading corner of the return is mitered to the leading edge of the tread with a shoulder miter.



**TWIST:** A distortion caused by the turning or winding of the edges of the surface, so that the four corners of any face are no longer in the same plane.



**UREA FORMALDEHYDE RESIN:**

Commonly used for Type I assemblies; relatively water resistant. Often requires curing by heat, but will cure at room temperature over time.


**V GROOVED:** Narrow and shallow V or U shaped channels machined on a surface to achieve a decorative effect. V grooving is most commonly encountered in mismatched or random matched wall panels as the grooves fall on the edge joints of the pieces of veneer, making the face appear as planking.



**VARNISH:** An oil based finish used to coat a surface with a hard, glossy film.

**VENEER:** A thin layer of wood, rotary cut or sliced from a log or flitch. Thickness may vary from 1/100" (0.3 mm) to 1/4" (6.4 mm).

**VENEER CORE:** Core of plywood constructed using an odd number of veneer plies, with face and back veneers of overlays adhered thereto.



Speciality versions include a veneer core mdf cross bands to limit telegraphing of core grain or defects



and void free hardwood veneer core with an increased number of thin veneer plies for additional strength and rigidity.



**VENEER GRAIN OR DIRECTIONAL**

**PATTERN MATCH:** Produced by cutting one or more components from the same panel and assembled maintaining grain or pattern alignment.

**VENEER LOSS:** The figure and grain misalignment as a result of manufacturer's perimeter trimming of pre-manufactured or made-to-order veneer panels within a panel sequence.

**VENEER, RIFT CUT:** See "Rift Cut".

**VENEER, ROTARY CUT:** See "Rotary Slicing".

**VENEER, SLICED:** Veneer in which a log or sawn flitch is held securely in a slicing machine and is thrust downward into a large knife that shears off the veneer. See Rift Cut, Quarter Cut or Plain Slices".

**VERTICAL GRAIN:** Produced by cutting perpendicular to a log's growth rings, where the member's face is no more than 45 degrees to the rings. This produces a pleasing straight grain line. Vertical grain is defined as having no less than an average of five growth rings per inch on its exposed face.



**VINE MARK:** Bands of irregular grain running across or diagonally to the grain which are caused by the growth of climbing vines around the tree.




**VINYL:** Heavy film, minimum of 4 mils in thickness, opaque or reverse printed.

**VINYL LACQUERS:** In finishing, catalyzed lacquers with a plastic rather than a nitrocellulose base.

**VISCOSITY:** The property of resistance to flow in a fluid or semi fluid.

**VOLUTE:** The spiral decorative element terminating the lower end of a stair rail.



# GLOSSARY

**WAFERBOARD:** See “particleboard.”

**WAINSCOT:** A lower interior wall surface that contrasts with the wall surface above it.




**WANE:** Defect in lumber defined as bark or lack of wood from any cause on the edge or corner, except eased edges.



**WARP:** Any deviation from a true or plane surface, including bow, crook, cup, twist, or any combination thereof. Warp restrictions are based on the average form of warp as it occurs normally, and any variation from this average form, such as short kinks, shall be appraised according to its equivalent effect. Pieces containing two or more forms of warp shall be appraised according to the combined effect in determining the amount permissible.


- **BOW** - A deviation flatwise from a straight line drawn from end to end of a piece. It is measured at the point of greatest distance from the straight line.




- **CROOK** - A deviation edgewise from a straight line drawn from end to end of a piece. It is measured at the point of greatest distance from the straight line.



- **CUP** - A deviation in the face of a piece from a straight line drawn from edge to edge of a piece. It is measured at the point of greatest distance from the straight line.



- **TWIST** - A deviation flatwise, or a combination of flatwise and edgewise, in the form of a curl or spiral, and the amount is the distance an edge of a piece at one end is raised above a flat surface against which both edges at the opposite end are resting snugly. In passage doors, any distortion in the door itself and not its relationship to the frame or jamb in which it is to be hung, measured by placing a straight edge or a taut string on the concave face.



**WASH COATS:** Thin solutions applied as a barrier coat to wood. Used prior to wiping stains for color uniformity.

**WATER REPELLENT:** A wood treating solution that deposits waterproof or water resistant solids on the walls of wood fibers and ray cells, thereby retarding their absorption of water; having the quality of retarding the absorption of water by wood fibers and ray cells.

**WAVY:** Curly grain with large undulations; sometimes referred to as “finger roll” when the waves are about the width of a finger.

**WELL HOLE:** In stairwork, the open space in which the stair is set.

**WELL MATCHED FOR COLOR AND GRAIN:** For the purpose of these standards, means that the members that make up the components of an assembly and components of an adjacent assembly are:

- Similar and nearly uniform in color, and
- Have similar grain, figure, and character. Adjacent members must be of the same grain type whether flat grain (plain sliced), vertical grain (quarter cut), rift grain, or mixed grain.

**WHITE:** When referring to color and matching, veneers containing all sapwood ranging in color from pink to yellow.

**WHITE BIRCH:** Term used to specify the sapwood of the Yellow Birch tree.



# GLOSSARY


**WINDOWS:** In architectural woodwork, all frames and sashes for double hung, casement, awning, sidelights, clerestory, and fixed windows. Stock and name brand units are not included.

**WIPING STAINS:** Refers to pigmented oils or solvents applied to wood.

**WOOD BASED PRODUCTS:** Products made of wood, veneer or paper based materials such as plastic laminate and engineered panels.

**WOOD FILLER:** An aggregate of resin and strands, shreds, or flour of wood, which is used to fill openings in wood and provide a smooth, durable surface.

**WOOD FLUSH DOOR:** An assembly consisting of a core, stiles and rails, and/or edgebands, with two or three plies of overlay on each side of the core assembly. All parts are composed of wood, wood derivatives, or high pressure decorative laminates.



**WOOD TO NON WOOD:** A two or more component joint or assembly containing wood or wood based products being installed next to non wood based components.

**WOOD TO WOOD:** A two or more component joint or assembly containing wood or wood based products.

**WOODWORK:** See "Architectural Woodwork".

**WOODWORKER:** See "Manufacturer".

**WORKMANSHIP:** See "First Class Workmanship".

**WORMHOLES:** Holes resulting from infestation of worms.



**WORM TRACK:** Marks caused by various types of wood attacking larvae. Often appear as sound discolorations running with or across the grain in straight to wavy streaks. Sometimes referred to as "pith flecks" in certain species of Maple, Birch and other hardwoods because of a resemblance to the color of pith.



# North American Architectural Woodwork Standards Committee requests your comments and suggestions.

Please complete and submit the form below:

## NAAWS 3.1 Improvement Suggestion Form

I believe that the following suggestion(s) will improve the North American Architectural Woodwork Standards (NAAWS):

Please look at Division/Section #: \_\_\_\_\_ Page #: \_\_\_\_\_ Item #: \_\_\_\_\_

Suggestions (please fully describe the addition, deletion, and/or revision you feel will improve these standards):

Include any additional descriptive sheets, drawings, or product data that may be needed to fully explain your suggestions with your submission.

Submission date: \_\_\_\_\_

My Name: \_\_\_\_\_ Title: \_\_\_\_\_

Company Name: \_\_\_\_\_

Address: \_\_\_\_\_

City: \_\_\_\_\_ State/Province: \_\_\_\_\_ Zip: \_\_\_\_\_

Phone: \_\_\_\_\_ Fax: \_\_\_\_\_ Email: \_\_\_\_\_

After completing the form, save as PDF and submit it and any additional attachments to the NAAWS Committee through the NAAWS Editor at [rob@woodinst.com](mailto:rob@woodinst.com).



Unit 02A, 4803 Center Street NW, Calgary, Alberta, T2E 2Z6, Canada  
Phone: 403-981-7300 <http://awmac.com>



P. O. Box 980247, West Sacramento, CA 95798-0247  
Phone: 916-372-9943 <http://woodworkinstitute.com>

INTRODUCTION

USER'S GUIDE

PREFACE

**1** SUBMITTALS

**2** CARE & STORAGE

**3** LUMBER

**4** SHEET PRODUCTS

**5** FINISHING

**6** MILLWORK

**7** STAIRWORK & RAILS

**8** WALL/CEILING SURFACING & PARTITIONS

**9** DOORS

**10** CASEWORK

**11** COUNTERTOPS

**12** HISTORIC RESTORATION WORK

APPENDIX



GLOSSARY

**JOINTLY  
SPONSORED BY:**



ARCHITECTURAL WOODWORK  
MANUFACTURERS ASSOCIATION  
OF CANADA

ASSOCIATION DES MANUFACTURIERS  
DE MENUISERIE ARCHITECTURALE  
DU CANADA



## **SECTIONS 8, 10 & 11**

INCLUDES SEPERATE ANNEXES FOR  
THE PRODUCT REQUIREMENTS OF  
EACH MATERIAL TYPE.

## **GLOSSAY**

ENHANCED WITH PICTURES  
AND ILLUSTRATIONS.

## **DESIGN RESOURCES**



NOW A PERPETUALLY  
EXPANDING, WEB-BASED  
RESOURCES OF PICTURES, VIDEOS,  
ILLUSTRATIONS, IDEAS AND DESIGN  
CONCEPTS FOR INSPIRING THOUGHT  
AND DESIGN CREATIVITY.

## **MEETS OR EXCEEDS**

ANSI A161.1  
AND A MULTITUDE OF  
ACCREDITED COMPONENT  
STANDARDS

(SEE INTRODUCTION)

ISBN 978-0-9909876-7-3



9 780990 987673