




Always check the website for the most updated specifications: www.americh.com











Tub pictured with optional waste & overflow

**Builder Series** 

**Luxury Series** 






Platinum Series

## Combination

(pump and blower location only)






# 







### **INSTALLATION TIPS**

- Install according to Owner's Manual and local codes.
- Airbath III units may be 11/2" 21/2" higher than stated.
- Any whirlpool or Airbath unit requires an access panel.
- Hot water supply should be 65-75% of tub capacity or greater.
- Always consult your local plumber for recommendations as installations will vary.

#### **DIMENSIONS**

60" x 30" x 22" ( 1524 x 762 x 559 mm) Whirlpool Operating Gallons = 40 (Liters = 152) Gallon to Overflow = 65 (Liters = 246)

MATERIAL: Acrylic (White and Biscuit Only)

TUB FLOOR: Non-Textured

**UNDERMOUNT: No.** 

#### **ELECTRICAL REQUIREMENTS**

Americh recommends one 20 amp ground fault circuit interrupter (GFCI) for each power supply provided with the bathtub.

#### **STANDARD EQUIPMENT:**

- Apron
- Molded Tile Flange

#### **OPTIONAL ACCESSORIES**

- Chromatherapy\*
- Grab Bars: 9" \* 14" 16"
- High Density Insulation\*
- iBath Sound System
- Inline Heater (whirlpool only)
- Jets: Additional or Rotary\*
- Lo Profile Tub Edge
- Ozone System (whirlpool and/or Airbath only)
- Pillow: 13"\*
- Remote Control Upgrade (select series only)
- Serenity Soak (tub only)
- Syllent Pump with Heated Air\*
- Trim Kit Upgrade\*
- Waste & Overflow
  - Cable Drive Overflow\*
  - Linear Overflow

#### \*Standard on Platinum Series

#### **CODES AND COMPLIANCE**

Americh products meet or exceed the following standards:

- Underwriters Laboratories (UL)
- Underwriters Laboratories Canada (cUL)
- Canadian Standards Association (CSA)
- ANSI Z124.1 ANSI A112-19.7
- ANSI A112.19.8

Contact Americh for additional approvals.