



BARRINGTON® 6036

Always check the website for the most updated specifications: www.americh.com











All bathtub dimensions are ± 1/2".

Builder Series




Luxury Series




Platinum Series


Combination


(pump and blower location only)














INSTALLATION TIPS

- Install according to Owner's Manual and local codes.
- \bullet Airbath III units may be $11/\!\!/2''$ $21/\!\!/2''$ higher than stated.
- Any whirlpool or Airbath® unit requires an access panel.
- Hot water supply should be 65-75% of tub capacity or greater.
- Always consult your local plumber for recommendations as installations will vary.
- Cut-out dimension: 58" x 34"

DIMENSIONS

60" x 36" x 22" (1524 x 914 x 559 mm) Whirlpool Operating Gallons = 45 (Liters = 170) Gallon to Overflow = 70 (Liters = 265)

MATERIAL: Acrylic (All Americh Standard Colors)

TUB FLOOR: Textured **UNDERMOUNT:** Yes

- Advise Americh when ordering to ensure there are no issues with deck mounted controls.
- · Always take dimensions directly from the unit.

ELECTRICAL REQUIREMENTS

Americh recommends one 20 amp ground fault circuit interrupter (GFCI) for each power supply provided with the bathtub.

OPTIONAL ACCESSORIES

- Apron
- Chromatherapy*
- Grab Bars: 9" * 14" 16"
- High Density Insulation*
- iBath Sound System
- Inline Heater (Whirlpool Only)
- Jets: Additional or Rotary*
- Lo Profile Tub Edge
- Ozone System (whirlpool and/or Airbath only)
- Pillow: 13" *
- Remote Control Upgrade (select series only)
- Serenity Soak (tub only)
- Syllent Pump with Heated Air*
- Tile Flange Kit
- Trim Kit Upgrade*
- Waste & Overflow
 - Cable Drive Overflow*
 - Linear Overflow

CODES AND COMPLIANCE

Americh products meet or exceed the following standards:

- Underwriters Laboratories (UL)
- Underwriters Laboratories Canada (cUL)
- Canadian Standards Association (CSA)
- ANSI Z124.1 ANSI A112-19.7
- ANSI A112.19.8 ASTM F462-79

Contact Americh for additional approvals.

^{*}Standard on Platinum Series